

Contractor; My Favorite Pool Builder, Inc. CPC1459058 Steve Cronin
386-965-0066 steve@mfpblc.com

Pump Pentair Inteliflow 3
Filter Pentair CLean and Clear 150.
Pump and filter information located on page 2 of 7

.Safety - Screen Room
Pool lighting is 12 volt LED
Screen Deck Footer
3IN Deck drain across pool deck
Bonding per code page 2 of 7
Pool is 616 SqFt
Pool Deck is 1,020 SQ Ft
Pool depth 3' 0" to 6' 0" top of rim



Pools	
Count:	1
Envelope:	33' 2" x 23' 1"
Perimeter:	106' 10"
Area:	616.92 ft ²
Int Surface Area:	1113.43 ft ²
Depth:	2' 11" to 6' 1"
Height:	0"
Volume:	17,708 gallons
Drains:	0
Lights:	2
Spillover Length(s):	
Spillover Mtrl:	
Interior Finish:	Pool Interiors, B...
Tile Line:	+6" 106' 10"
Tile Material:	Tile, Blue
Exterior Facing:	0 ft ²
Coping Area:	111.01 ft ²
Coping Interior:	106' 10"
Coping Material:	Artistic Pavers,...
Raised Beams:	
Raised Beam Mtr:	
Steps/Benches:	7
Step Linear Ft:	30' 2"
Step Perimeter:	69' 11"
Step Area:	29.76 ft ²
Trim Tile:	
Trim Tile Material:	
Floor Design Interi:	0"
Floor Design Area:	0 ft ²
Floor Design Mater:	
Excavation - Top:	0 ft ³
Excavation - Hole:	3336 ft ³
Concrete:	33.8 yards ³
Rebar:	5966' 1"

. Francis X. Neylon
. 296 SE Nature Dr
. Lake City, Fl. 32055
.Par ID # 30-4s-17-08898-124
(32849)

Contractor; My Favorite Pool Builder, Inc. CPC1459058 Steve Cronin
386-965-0066 steve@mfpblc.com

Distance from Pool water line to property line.

475 FT to North

562 FT to South

332 FT to East

202 FT to West

6'≥ Pool to house

< City Water sewer< power under ground

Power Company FPL El Lt side of house. Power to house is run underground and is more than 45.5' away from pools waters edge

NO Glass with 60IN Of pools water

Pool deck water will Drain away from pool onto ground. 3" deck drain. No change to current water drainage direction

