

Frost scope of work:

- Demo existing office area/prep for new construction
- Bathroom stay as is
- Frame new walls for larger reception and waiting area
- Exterior of walls plywood/interior walls to be painted drywall
- Insulate exterior walls and ceiling
- Electrical per plan
- No plumbing work
- Framed ceiling for drywall
- Existing exit door to stay as is
- New vinyl plank flooring