62

Designer:

Project Information for:	L106588		
-3uilder:	Aaron Simque	Date:	3/8/2005
Lot:	Lot 5	Start Number:	252
Subdivision:	Hunters Ridge		
County or City:	Columbia County		
Truss Page Count:	40		

Truss Design Load Information (UNO) Design Program: MiTek 5.2

FBC2001 **Building Code:** Gravity Wind **ASCE 7-98** 42 Wind Standard: Roof (psf):

110

55 Wind Speed (mph): Floor (psf): Note: See individual truss drawings for special loading conditions

Building Designer, responsible for Structural Engineering: (See attached)

SIMQUE, AARON D. RB29003130

320 SW AINSLEY GLN. Address: LAKE CITY, FL. 32024

Truss Design Engineer: Thomas, E. Miller, P.E., 56877 - Byron K. Anderson, PE FL 60987

Structural Engineering and Inspections, Inc. EB 9196 Company:

16105 N. Florida Ave, Ste B, Lutz, FL 33549 Address

Notes:

1. Truss Design Engineer is responsible for the individual trusses as components only.

2. Determination as to the suitability and use of these truss components for the structure is the responsibility of the Building Designer of Record, as defined in ANSI/TPI 1-1995 Section 2.2

3. The seal date shown on the individual truss component drawings must match the seal date on this index

#	Truss ID	Dwg. #	Seal Date	#	Truss ID	Dwg. #	Seal Date
1	CJ1	030805252	3/8/2005				
2	CJ3	030805253	3/8/2005		1	,	
3	CJ5	030805254	3/8/2005				
4	EJ7	030805255	3/8/2005				
5	HJ7	030805256	3/8/2005		†		
6	PB01	030805257	3/8/2005				
7	PB02	030805258	3/8/2005		1		
8	PB04	030805259	3/8/2005				
9	PB05	030805260	3/8/2005				
10	PB06	030805261	3/8/2005				
11	PB07	030805262	3/8/2005		1		
12	T01G	030805263	3/8/2005				
13	T02	030805264	3/8/2005				
14	T02G	030805265	3/8/2005				1
15	T03	030805266	3/8/2005				
16	T04	030805267	3/8/2005				
17	T04G	030805268	3/8/2005				
18	T05	030805269	3/8/2005				
19	T07	030805270	3/8/2005		1		
20	T08	030805271	3/8/2005			<u>"</u>	
21	T09	030805272	3/8/2005				
22	T10	030805273	3/8/2005				
23	T11	030805274	3/8/2005				
24	T12	030805275	3/8/2005				
25	T13	030805276	3/8/2005				
26	T13A	030805277	3/8/2005				
27	T13B	030805278	3/8/2005				
28	T14	030805279	3/8/2005				
29	T16	030805280	3/8/2005				
30	T17	030805281	3/8/2005				
31	T18	030805282	3/8/2005				
32	T19	030805283	3/8/2005			· · ·	
33	T20	030805284	3/8/2005				
34	T21	030805285	3/8/2005				
35	T22	030805286	3/8/2005				
36	T23	030805287	3/8/2005				
37	T25	030805288	3/8/2005				
38	T26	030805289	3/8/2005				
39	T27	030805290	3/8/2005				
40	T28	030805291	3/8/2005				







DBPR Home | Online Services Home | Help | Site Map

09:24:32 AM

Public Services

Search for a Licensee
Apply for a License
View Application Status
Apply to Retake Exam
Find Exam Information
Find a CE Course
File a Complaint
AB&T Delinquent Invoice
& Activity List Search

User Services

Renew a License
Change License Status
Maintain Account
Change My Address
View Messages
Change My PIN
View Continuing Ed

Term Glossary

Online Help

Licensee Details

Licensee Information

Name: SIMQUE, AARON DAVID (Primary Name)
AARON SIMQUE HOMES INC (DBA Name)

Main Address: 320 SW AINSLEY GLN.

LAKE CITY, Florida 32024

License Information

License Type: Registered Building Contractor

Rank: Reg Building
License Number: RB29003130

Status: Current, Active Licensure Date: 10/23/2002

Expires: **08/31/2005**

Bldg Code Core Course Credit

Special Qualifications

Qualified Business License

Required


02/20/2004


Effective Date


View Related License Information View License Complaint


New Search


| Terms of Use | | Privacy Statement |




















TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D WEBS 2 X 4 SYP No.3

OTHERS 2 X 4 SYP No.3 Sheathed or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=51/0-3-8, 9=243/0-3-8, 10=315/0-3-8, 8=315/0-3-8, 7=51/0-3-8 Max Horz 1=138(load case 4)

Max Uplift1=-29(load case 3), 9=-12(load case 5), 10=-192(load case 5), 8=-183(load case 6), 7=-16(load case 6) Max Grav 1=68(load case 7), 9=243(load case 1), 10=320(load case 7), 8=320(load case 8), 7=68(load case 8)

FORCES (Ib) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-137/137, 2-3=-124/214, 3-4=-28/165, 4-5=-13/165, 5-6=-94/214, 6-7=-34/13
BOT CHORD 2-10=-130/138, 9-10=-130/138, 8-9=-130/138, 6-8=-130/138

WEBS 4-9=-229/35, 3-10=-192/184, 5-8=-192/180


- NOTES


 1) Unbalanced roof live loads have been considered for this design.


 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.


 3) Bearing at joint(s) 1, 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing
- surface.
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 1, 12 lb uplift at joint 9, 192 lb uplift at joint 10, 183 lb uplift at joint 8 and 16 lb uplift at joint 7.


LOAD CASE(S) Standard





































































1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.

- 2) Provide adequate drainage to prevent water ponding.
 3) Bearing at joint(s) 16 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 191 lb uplift at joint 16, 486 lb uplift at joint 2 and 1013 lb uplift at joint 13.

LOAD CASE(S) Standard




REACTIONS (lb/size) 7=1006/0-4-0, 2=1102/0-4-0 Max Horz 2=464(load case 5)


Max Uplift7=-353(load case 4), 2=-354(load case 5)


FORCES (Ib) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/45, 2-3=-1457/384, 3-4=-950/328, 4-5=-515/233, 5-6=-514/234, 6-7=-927/456
BOT CHORD 2-11=-588/1124, 10-11=-588/1124, 9-10=-588/1124, 8-9=-350/715, 7-8=-6/14
WEBS 3-11=0/225, 3-9=-510/325, 4-9=-150/465, 4-8=-369/234, 5-8=-315/301, 6-8=-427/937


1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified. 2) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 353 lb uplift at joint 7 and 354 lb uplift at joint 2.


LOAD CASE(S) Standard

















COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001

ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

- 1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
- 2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
- 3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERA	L REQUIREMI	ENTS; Two (2) complete sets of plans containing the following:
Applicant	Plans Examine	
	B	All drawings must be clear, concise and drawn to scale ("Optional" details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
		footage of different areas shall be shown on plans. Designers name and signature on document (FBC 104.2.1). If licensed William Myer, architect or engineer, official seal shall be affixed. MARK DISOSWAY
D See ATTA	chsac PLAN	Site Plan including: a) Dimensions of lot b) Dimensions of building set backs c) Location of all other buildings on lot, well and septic tank if
	· • •	applicable, and all utility easements. d) Provide a full legal description of property. Property Applications of property. Property Applications with FBC Section 1606 certicalizations.
See Sheet	5-1	b) The following information must be shown as per section 1606.1.7 FBC a. Basic wind speed (MPH) // 0 b. Wind importance factor (I) and building category I c. Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated B d. The applicable internal pressure coefficient e. Components and Cladding. The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component and cladding materials not specifally designed by the registered design professional
0 . 0 0 0 0		Elevations including: a) All sides b) Roof pitch 13/8 c) Overhang dimensions and detail with attic ventilation 24 MAY CONTINUOUS d) Location, size and height above roof of chimneys NoNe Shown on Eluation per e) Location and size of skylights NONe Shown on Eluation plan f) Building height 21 4 Plus Foundation e) Number of stories 1

		Eloor Plan including:		
3	8	Eloor Plan including: a) Rooms labeled and dimensioned b) Shear walls Sheet 5-3 Stephen 138, 5 Long. 61-5 (1A55 Blocks) c) Windows and doors (including garage doors) showing size, mfg., approval		
	E	b) Shear walls Sheet S-3 See ATTACKED PACKAGE		
	B	c) Windows and doors (including garage doors) showing size, mfg., approval		
		listing and attachment specs. (FBC 1707) and safety glazing where needed		
		(egress windows in bedrooms to be shown) ALL Four bedroom Show egress		
	₽	d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth		
0	D-	x e) Stairs with dimensions (width, tread and riser) and details of guardrails and		
0	B	handrails f) Must show and identify accessibility requirements (accessible bathroom) Both		
		Foundation Plan including:		
	B	a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing See Sheet S-2		
	Ð	b) All posts and/or column footing including size and reinforcing See Sheet 5-2		
	8-	c) Any special support required by soil analysis such as piling		
	₽-	d) Location of any vertical steel		
_	_			
	<u></u>	a) Truss package including: Fire Source Builder		
_		1. Truss layout and truss details signed and sealed by Fl. Pro. Eng. Thomas		
		2. Roof assembly (FBC 104.2.1 Roofing system, materials,		
		manufacturer, fastening requirements and product evaluation with		
		wind resistance rating) See Sheets-1 ANCHOT TAble		
	B -	人的 Conventional Framing Layout including:		
		1. Rafter size, species and spacing		
		2. Attachment to wall and uplift		
		3. Ridge beam sized and valley framing and support details		
		4. Roof assembly (FBC 104.2.1 Roofing systems, materials,		
		manufacturer, fastening requirements and product evaluation with wind resistance rating)		
		Wall Sections including:		
	Д-	(a) Masonry wall		
		1. All materials making up wall		
		2. Block size and mortar type with size and spacing of reinforcement		
		3. Lintel, tie-beam sizes and reinforcement		
		 Gable ends with rake beams showing reinforcement or gable truss 		
	N.	and wall bracing details		
		5. All required connectors with uplift rating and required number and		
		size of fasteners for continuous tie from roof to foundation		
		6. Roof assembly shown here or on roof system detail (FBC 104.2.1		
		Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)		
		7. Fire resistant construction (if required)		
		8. Fireproofing requirements		
		9. Shoe type of termite treatment (termiticide or alternative method)		
		10. Slab on grade		
		a. Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)		
		b. Must show control joints, synthetic fiber reinforcement or		
		Welded fire fabric reinforcement and supports		
		11. Indicate where pressure treated wood will be placed		
		12. Provide insulation R value for the following:		
		a. Attic space		
		b. Exterior wall cavity		
		c. Crawl space (if applicable)		

P 1	
□ Ø b) Wood frame wall
	1. All materials making up wall 2. Size and species of studs 2 × 4/6 oN /6 oN 3. Sheathing size, type and nailing schedule Headers sized See Sheet 5-3 Header he gend 5. Gable end showing balloon framing detail or gable truss and wall hince bracing detail Sheet 5-1 Typical Gable Edd x Barcing
	2. Size and species of stude 2 x y/6 7/16 7/16 7/16
121 - 11/5-6	3. Sheathing size, type and nailing schedule
10 x 7 OHd For GARAGE H	MADELS 4. Headers sized See Sheet 5-3 HEADER REGION
/	5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail Sheet S-1 Ty Pical Gable Edd & Barcing
	6. All required fasteners for continuous tie from roof to foundation
	(truss anchors, straps, anchor bolts and washers)
	7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements
	and product avaluation with wind resistance rating) Sheef 5-1 = 4 h L e
	and product evaluation with wind resistance rating) Shell 5-1 Able 8. Fire resistant construction (if applicable)
	9. Fire resistant construction (if applicable) 9. Fireproofing requirements See ONE STORY WALL SECTION STREET 5-1
	10. Show type of termite treatment (termiticide or alternative method) Skeel 5-2
	11. Slab on grade $\frac{5hcc7}{5-2}$
	a. Vapor retarder (6Mil. Polyethylene with joints lapped 6
	inches and sealed
	b. Must show control joints, synthetic fiber reinforcement or
	welded wire fabric reinforcement and supports
	12. Indicate where pressure treated wood will be placed
	13. Provide insulation R value for the following:
	a. Attic space $R^{-3}U$ Sheet AI
	b. Exterior wall cavity R-13
_	c. Crawl space (if applicable)
	c) Metal frame wall and roof (designed, signed and sealed by Florida Prof.
\wedge	Engineer or Architect)
	Floor Framing System:
	a) Floor truss package including layout and details, signed and sealed by Florida
	Registered Professional Engineer
	b) Floor joist size and spacing
	c) Girder size and spacing
	d) Attachment of joist to girder
	e) Wind load requirements where applicable
	Plumbing Fixture layout
	Electrical layout including:
	a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
	b) Ceiling fans
	c) Smoke detectors S d) Service panel and sub-panel size and location(s) IN GATAGE
	a) Service panel and suo-panel size and location(s)
	e) Meter location with type of service entrance (overhead or underground)
	g) Arc Fault Circuits (AFCI) in bedrooms See Electrical Notes Sheet A. U
	HVAC mior mation
	a) Manual J sizing equipment or equivalent computation
	b) Exhaust fans in bathroom Energy Calculations (dimensions shall match plans) Of MATCA
	Energy Calculations (dimensions shall match plans)
	Gas System Type (LP or Natural) Location and BTU demand of equipment
)	Notice Of Commencement NOT AS OF 3-22-05
	Private Potable Water
	Notice Of Commencement NOT AS OF 3-22-03 Private Potable Water a) Size of pump motor b) Size of pressure tank
38	b) Size of pressure tank
,	c) Cycle stop valve if used
	-/ -/

MI HOME PRODUCTS - PRIME ALUMINUM WINDOWS INSTALLATION INSTRUCTIONS FOR "NAIL FIN" PRODUCTS

MI Home Products appreciates your recent purchase of a maintenance free prime window, which will not rust, rot, mildew, or warp. This is a quality product that left our factory in good condition – proper handling and installation are just as important as good design and workmanship. Please follow these recommendations to allow this product to complete its function.

- 1 Handle units one at a time in the closed and locked position and take care not to scratch frame or glass or to bend the nailing fin.
- 2. Set unit plumb and square into opening and make sure that there is 3/16" ± 1/16" clearance around the frame. Fasten unit into opening in the closed and locked position, making sure that fasteners are screwed in straight in order to avoid twisting or bowing of the frame. Make sure that sill is straight and level. Check operation of unit before any and all fasteners are set.
- 3. Use # 8 sheet metal or wood screws with a minimum of 1" penetration into the framing (stud). Place first screws (two at each comer) 3" from end of fin. For positive and negative DPs (design pressures) up to 35, do not exceed 24" spacing of additional screws. For DPs from 35.1 to 50, do not exceed 18". Install load bearing shim adjacent to each anchor. Use shim where space exceeds 1/16".
- 4. Flash over head and caulk outside perimeter in accordance with code requirements and good installation practices.
- 5. Fill voids between frame and construction with loose batten type insulation or <u>non-expanding</u> aerosol foam specifically formulated for windows and doors to eliminate drafts. The use of <u>expanding</u> aerosol type insulating foam, which can bow the frame, waives all stated warranties.
- 6. Remove plaster, mortar, paint and any other debris that may have collected on the unit and make sure that sash/vent tracks and interlocks are also clear. Do not use abrasives, solvents, ammonia, vinegar, alkaline, or acid solutions for clean-up, especially with insulated glass units as their use could cause chemical breakdown of the glass seal. Take care not to scratch glass; scratches severely weaken glass and it could eventually break from thermal expansion and contraction. Clean units with water and mild detergent as you would you automobile.

CAUTION -

MI Home Products or its representatives are unable to control and cannot assume responsibility for the selection and placement of their products in a building or structure in a manner required by laws, statutes, and/or building codes. The purchaser is solely responsible for knowledge of and adherence to the same. MI Home Products window products are not provided with safety glazing unless specifically ordered with such. Many laws and codes require safety glazing near doors, bathtubs, and shower enclosures. Also be aware of emergency egress code requirements.

Corporate Headquarters: 650 West Market St. Gratz, PA 17030-0370 (717) 365-3300



AAMA/NWWDA 101/LS.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess, Technician

MAH:nlb

allea M. Recom



AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC. 650 West Market Street P.O. Box 370 Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01

Test Date: 03/07/02

Report Date: 03/26/02

Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com

aller 91. Recon



Weatherstripping:

Description	Quantity	Location
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock with keeper	1	Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

allen M. Reur



Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.1	Operating Force	11 lbs	30 lbs max.
2.1.2	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft²	$0.3 \text{ cfm/}\Omega^2 \text{ max}.$

Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/LS. 2-97 for air infiltration.

2.1.3	Water Resistance (ASTM E 547-00) (with and without screen)			
	WTP = 2.86 psf	No leakage	No leakage	
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)			
	@ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.	

^{*}Exceeds L/175 for deflection, but passes all other test requirements.

2.1.4.2	Uniform Load Structural (ASTM E 330-97)				
	(Measurements reported were taken on the meeting rail)				
	(Loads were held for 10 seconds)				
	@ 38.9 psf (positive)	0.02"	0.18" max.		
	@ 52.1 psf (negative)	0.02"	0.18" max.		
	70115				

aller M. Recen



Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail Bottom rail	0.12"/25% 0.12"/25%	0.50"/100% 0.50"/100%
	In remaining direction at 50 lbs		
	Left stile Right stile	0.06"/12% 0.06"/12%	0.50"/100% 0.50"/100%
2.1.8	Forced Entry Resistance (ASTM F	588-97)	
	Type: A Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5 Test A7	No entry No entry	No entry No entry
	Lock Manipulation Test	No entry	No entry
Optional Perfor	mance		
4.3	Water Resistance (ASTM F 547-00 (with and without screen)	0)	
	WTP = 6.00 psf	No leakage	No leakage
4.4.1	Uniform Load Deflection (ASTM) (Measurements reported were taker (Loads were held for 33 seconds)	on the meeting rail)	
	@ 45.0 psf (positive) @ 47.2 psf (negative)	0.47"* 0.46"*	0.26" max.
*Exceeds L/175	for deflection, but passes all other		0.26" max.
4.4.2	Uniform Load Structural (ASTM E (Measurements reported were taker (Loads were held for 10 seconds)	330-97)	
	@ 67.5 psf (positive)	0.05"	0.18" max.
	@ 70.8 psf (negative)	0.05"	0.18" max.

alle M. Recogn



Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess Technician

MAH:nlb 01-41134.01 Allen N. Reeves, P.E.

Director - Engineering Services

allen M. Rem

AAMA/NWWDA 101/I.S,2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 450/650/850 Drop In Glazing TYPE: Aluminum Single Hung Window

Title	Summary of Results
AAMA Rating	H-LC30 53 x 90
Operating Force	24 lb max.
Air Infiltration	$0.11 \mathrm{cfm/ft}^2$
Water Resistance Test Pressure	6.75 psf
Uniform Load Deflection Test Pressure	+32.8 psf
Omform Load Deficedon Test Flessing	-47.2 psf
Uniform Load Structural Test Pressure	+49.2 psf
Omform Load Structurar Test Fressure	-70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to ATI Report No. 01-42487.01 for complete test specimen description and data.



AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC. P.O. Box 370 650 West Market Street Gratz, Pennsylvania 17030-0370

Report No: 01-42487.01

Test Date:

08/14/02

And:

08/15/02

Report Date:

10/02/02

Expiration Date:

08/15/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on a Series/Model 450/650/850 Drop In Glazing, aluminum single hung window at their facility in Elizabethville, Pennsylvania. The sample tested successfully met the performance requirements for a H-LC30 53 x 90 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 450/650/850 Drop In Glazing

Type: Aluminum Single Hung Window

Overall Size: 4' 5-1/8" wide by 7' 5-5/8" high

Interior Sash Size: 4'2-3/4" wide by 3'8-7/8" high

Fixed Daylight Opening Size: 4'0" wide by 3'5-3/8" high

Screen Size: 4' 0-3/4" wide by 3' 8-3/4" high

Finish: The unit was white.

Glazing Details: The specimen utilized 5/8" thick, sealed insulating glass constructed from two sheets of 3/32" thick, clear annealed glass and a metal reinforced butyl spacer system. The lites were interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com

Weatherstripping:

Description	Quantity	Location
0.190" high by 0.187" polypile with center fin	1 Row	Fixed meeting rail interlock
0.190" high by 0.187" polypile with center fin	2 Rows	Interior sash stiles
1/4" vinyl foam-filled bulb seal	l Row	Interior sash bottom rail
5/8" wide by 7/8" long polypile plug	4 Pieces	Interior sash, all corners

Frame Construction: The frame was constructed of extruded aluminum. Each corner was coped, butted, sealed, and fastened with two #8 x 1" screws per corner through the head and sill into jamb screw boss. End caps were utilized on the ends of the meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was then secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum. Each corner was coped, butted, and fastened with one #8 x 1-1/4" screw per corner.

Screen Construction: The screen was constructed of roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock	2	Interior sash, 6-1/2" from top rail ends
Spring-loaded coil balance	2	One per jamb
Plastic tilt latch	2	Interior sash top rail ends
Metal tilt latch pin	2	Interior sash bottom rail ends
Screen spring-loaded retainer pin	2	6-3/4" from rails on stiles

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The specimen was installed into a #2 2 x 8 Spruce-Pine-Fir wood buck. #8 x 1-5/8" drywall screws were placed 3" from corners and 15" on center around nailing fin. Polyurethane was used a s a scalant around the exterior perimeter.

Test Results:

The results are tabulated as follows:

Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.1	Operating Force	24 Ibs	35 lbs max.
2.1.2	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.11 cfm/ft ²	$0.3 \text{ cfm/ft}^2 \text{ max}.$

Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/I.S. 2-97 for air infiltration.

2.1.3	Water Resistance (ASTM E (with and without screen)	547-00)	
	WTP = 3.75 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (A (Measurements reported wer (Loads were held for 52 seco	e taken on the meeting ra	nil)
	@ 25.0 psf (positive) @ 25.0 psf (negative)	0.64"* 0.54"*	0.29" max. 0.29" max.

^{*}Exceeds L/175 for deflection, but meets all other test requirements.

2.1.4.2	Uniform Load Structural (ASTM E 330-97)		
	(Measurements reported were taken on the meeting rail)		
	(Loads were held for 10 seconds)		
	@ 37.5 psf (positive)	0.04"	0.20" max.
	@.37.5 psf (negative)	0,03"	0.20" max.

Test Results:

Paragraph	Title of Test - Test Method	Results	4 13 1
	- Tool Monda	ACSUICS	Allowed
2.2.1.6.2	Deglazing Test (ASTM E 987-88) In operating direction at 70 lbs		
	Interior sash meeting rail Interior sash bottom rail	0.12"/25% 0.12"/25%	0.50"/100% 0.50"/100%
	In remaining direction at 50 lbs		
	Interior sash right stile Interior sash left stile	0.06"/12% 0.06"/12%	0,50"/100% 0.50"/[00%
2.1.8	Forced Entry Resistance (ASTM F	588-97)	
	Type: A Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Test A1 through A5 Test A7	No entry No entry	No entry No entry
	Lock Manipulation Test	No entry	No entry
Optional Perfor	mance		
4.3	Water Resistance (ASTM E 547-00))	
	(with and without screen) WTP = 6.75 psf	No leakage	No leakage
4.4.1	Uniform Load Deflection (ASTM E (Measurements reported were taken (Loads were held for 33 seconds)		
	@ 32.8 psf (positive)	0.85"*	0.29" max.
	@ 47.2 psf (negative)	0.87"*	0.29" max.
*Exceeds L/173	5 for deflection, but meets all other te	est requirements.	
4.4.2	Uniform Load Structural (ASTM E (Measurements reported were taken (Loads were held for 10 seconds)		
	@ 49.2 psf (positive)	0.09"	0.20" max.
	@ 70.8 psf (negative)	0.12"	0.20" max.

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator. This report may not be reproduced except in full without the approval of Architectural Testing.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess Technician

MAH:nlb 01-42487.01 Allen, N. Recves, P.E.

Director - Engineering Services

11 OCTOBER 2007



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650
TYPE: Aluminum Triple Single Hung Window

Title of Test	Summary of Results
AAMA Rating	H-R35 112 x 72
Uniform Load Deflection Test Pressure	+35.3 psf -47.2 psf
Operating Force .	25 lb max.
Air Infiltration	0.16 cfm/ft^2
Water Resistance Test Pressure	5.25 psf
Uniform Load Structural Test Pressure	+53.0 psf -52.5 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to ATI Report No. 01-41641.01 for complete estrement description and data.

aller M. Reary 7 NUNE 2002



AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC. P.O. Box 370 650 West Market Street Gratz, Pennsylvania 17030-0370

Report No: 01-41641.01

Test Date: 05/13/02

7 JUNE ZOOZ

And: 05/16/02

Report Date: 06/05/02

Expiration Date: 05/16/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to witness testing on a Series/Model 650, aluminum triple single hung window at their facility located in Elizabethville, Pennsylvania. The sample tested successfully met the performance requirements for a H-R35 112 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 650

Type: Aluminum Triple Single Hung Window

Overall Size: 9' 3-1/2" wide by 5' 11-11/16" high

Active Sash Size (3): 3' 0-1/4" wide by 2' 10-3/4" high

Fixed Daylight Opening Size (3): 2'8-1/4" wide by 2'9-1/8" high

Screen Size (3): 2' 9-1/8" wide by 2' 11" high

Finish: All aluminum was painted white.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com



Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

Weatherstripping:

Description	Quantity	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" by 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. The meeting rail was secured to the frame utilizing two 1-1/4" screws. The mullions were secured utilizing four #8 x 1-1/4" screws through the head and sill into the mullion screw boss.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each stiles' screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

STATE OF STA

TUNE ZOOZ



Hardware:

Description	Quantity	<u>Location</u>
Metal cam lock with keeper	1	Midspan of each active meeting rail with adjacent keepers
Plastic tilt latch	2	Each active sash meeting rail ends
Metal tilt pin	2	Each active sash bottom rail ends
Balance assembly	2	Each active sash contained one in each jamb
Screen plunger	2	Each screen contained two 4" from rail ends on top rail

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.1	Operating Force	25 lbs	30 lbs max.
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.16 cfm/ft ²	0.3 cfm/ft ² max.

Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/I.S. 2-97 for air infiltration.

Water Resistance (ASTM E 547-00) (with and without screen)

WTP = 2.86 psf

No leakage

7 JUNE 2002



Test Results: (Continued)

Paragraph	Title of Test - Test Method	Results	Allowed	
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the mullion)			
	(Loads were held for 52 seconds) @ 15.0 psf (positive)	0.15"	0.41" max.	
	@ 15.0 psf (negative)	0.29"	0.41" max.	
2.1.4.2	Uniform Load Structural (ASTM (Measurements reported were tal (Loads were held for 10 seconds)	cen on the mullion)		
	@ 22.5 psf (positive)	0.01"	0.29" max.	
	@ 22.5 psf (negative)	0.01"	0.29" max.	
2.26.2	Deglazing Test (ASTM E 987-88 In operating direction at 70 lbs	8)		
	Right sash, meeting rail	0.12"/25%	0.50"/100%	
	Right sash, bottom rail	0.12"/25%	0.50"/100%	
	Middle sash, meeting rail	0.12"/25%	0.50"/100%	
	Middle sash, bottom rail	0.12"/25%	0.50"/100%	
	Left sash, meeting rail	0.12"/25%	0.50"/100%	
	Left sash, bottom rail	0.12"/25%	0.50"/100%	
	In remaining direction at 50 lbs			
	Right sash, right stile	0.06"/12%	0.50"/100%	
	Right sash, left stile	0.06"/12%	0.50"/100%	
	Middle sash, right stile	0.06"/12%	0.50"/100%	
	Middle sash, left stile	0.06"/12%	0.50"/100%	
	Left sash, right stile	0.06"/12%	0.50"/100%	
*,	Left sash, left stile	0.06"/12%	0.50"/100%	
2 .8	Forced Entry Resistance (ASTM	I F 588-97)		
	Type: A Grade: 10			
	Lock Manipulation Test	No entry	No entry	
	Test A1 through A5	No entry	No entry	
	Test A7	No entry	No chin	
	Lock Manipulation Test	No entry	No entry !!	



Test Results: (Continued)

<u>Paragraph</u> <u>Title of Test - Test Method</u> <u>Results</u> <u>Allowed</u>

Optional Performance

4.3 Water F

Water Resistance (ASTM E 547-00)

(with and without screen)

WTP = 5.25 psf

No leakage

No leakage

Uniform Load Deflection (ASTM E 330-97)

(Measurements reported were taken on the mullion)

(Loads were held for 52 seconds)

@ 35.3 psf (positive)

0.46"*

0.41" max

@ 47.2 psf (negative)

0.67"*

0.41" max

Uniform Load Structural (ASTM E 330-97)

(Measurements reported were taken on the mullion)

(Loads were held for 10 seconds)

@ 53.0 psf (positive)

0.03"

0.29" max

@ 52.5 psf (negative)

0.02"

0.29" max

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

Ich A. Ofens

Mark A. Hess Technician

MAH:nlb 01-41641.01 Allen N. Reeves, P.E.

Director - Engineering Services

7 JUNE 2002

HD. 19354

STATE OF

^{*}Exceeds L/175 for deflection, but meets all other test requirements.



AAMA/NWWDA 101/LS.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650
TYPE: Aluminum Picture Window

Title of Test	Results	
Rating	F-R45 60 x 80	
Overall Design Pressure	+45.0 psf	
	-47.2 psf	
Air Infiltration	0.04 cfm/ft^2	
Water Resistance	8.25 psf	
Structural Test Pressure	+67.5 psf	
	-70.8 psf	
Forced Entry Resistance	Grade 10	

Reference should be made to Report No. 01-41135.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess, Technician

MAH:nlb

allen Mr Reun



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC. 650 West Market Street P.O. Box 370 Gratz, Pennsylvania 17030-0370

Report No: 01-41135.01

Test Date:

03/07/02

Report Date:

03/26/02

Expiration Date:

03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650, aluminum picture window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a F-R45 60 x 80 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description

Series/Model: 650

Type: Aluminum Picture Window

Overall Size: 5'0" wide by 6'8" high

Daylight Opening Size: 4' 9-1/4" wide by 6' 5-1/4" high

Finish All aluminum was white.

Glazing Details: The test specimen utilized 7/8" thick, sealed insulating glass constructed from two sheets of 3/16" thick, clear annealed glass and a metal reinforced butyl spacer system. The glass was interior glazed against double-sided adhesive foam tape and second with aluminum snap-in glazing beads.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com

allow M. Rem



Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss.

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck. #8 x 2-1/2" installation screws were utilized 18" on center around the interior perimeter. Polyurethane was utilized to seal the exterior.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	Title of Test - Test Method	Results	Allowed
	Air Infiltration (ASTM E 283-91)		
	@ 1.57 psf (25 mph)	$0.04 \mathrm{cfm/fl}^2$	$0.3 \text{cfm/ft}^2 \text{max}$

Note #1: The tested specimen meets the performance levels specified in AAMA/NWWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E	547-00)	
	WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (A.	STM E 330-97)	
	(Measurements reported were		
	(Loads were held for 33 second	nds)	
	@ 25.9 psf (positive)	0.01"	0.41" max.
	@ 34.7 psf (negative)	0.01"	0.41" max.
2.1.4.2	Uniform Load Structural (AS	TM E 330-97)	
	(Measurements reported were		
	(Loads were held for 10 second	nds)	
	@ 38.9 psf (positive)	0.0"	0.29" max.
	@ 52.1 psf (negative)	0.01"	0.29" max.





Test Results: (Continued)

<u>Paragraph</u>	Title of Test - Test Method	Results	Allowed
	Forced Entry Resistance (ASTM F	588-97)	
	Type: D Grade: 10		
	Hand and Tool Manipulation Test	No entry	No entry
Optional Perfo	rmance		
4.3	Water Resistance (ASTM E 547-00	0)	
	WTP = 8.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM)	E 330-97)	
	(Measurements reported were taken		
	(Loads were held for 33 seconds)	3 /	
	@ 45.0 psf (positive)	0.02"	0.41" max.
	@ 47.2 psf (negative)	0.02"	0.41" max.
	Uniform Load Structural (ASTM E		
	(Measurements reported were taken (Loads were held for 10 seconds)	on the jamb)	
	@ 67.5 psf (positive)	0.01"	0.208
	@ 70.8 psf (negative)	0.02"	0.29" max. 0.29" max.

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

In A. Kens

Mark A. Hess Technician

MAH:nib 01-41135.01 Allen N. Reeves, P.E.

Director - Engineering Services (1917)

I APRIL ZOOZ

650 SH & PW SERIES - MILE PER HOUR (MPH) MAXIMUM SIZE CHART

PAGE 2 OF 2

	N/A	- T	(No Mullion)	up то 140 МРН	650 SH OR PW CONTINUOUS HDR & SILL SNG GI 7 OB INS
N/A N/A	37" x 72" w/Transom*		SELF- STACKING SILL #CM-45026	ир то 140 МРН	650 SH OR PW FIN FRAME SNG GLZ OR INS
N/A	48" x 72" w∕Transom*		SELF- STACKING SILL #CM-45026	up то 120 MPH	650 SH OR PW FIN FRAME SNG GLZ OR INS
N/A N/A	53-1/8" x 72" w/Transom*		SELF- STACKING SILL #CM-45026	ир то 110 МРН	650 SH OR PW FIN FRAME SNG GLZ OR INS
45" x 72" w/Transom* 30" x 72" w/Transom*	N/A	e .	HORIZONTAL MULL #5765	up то 140 MPH	650 SH OR PW FLANGE FRAME SNG GLZ OR INS
53-1/8" x 72" w/Transom* 32" x 72" w/Transom*	N/A	# E	HORIZONTAL MULL #5765	ир то 120 МРН	650 SH OR PW FLANGE FRAME SNG GLZ OR INS
MAXIMUM SIZES ALLOWED TWIN UNIT TRIPLE UNIT	SINGLE UNIT	MULLION	REQUIRED MULLION	MPH Zone(s)	SERIES/TYPE

^{*1} All Transoms (1, 2, & 3-Lites) must be continuous frame.
*2 Transom units must be a minimum of 1/0 tall. The maximum transom height is one half the width of the transom.
Both Single Hung & Picture Windows can be used in combination up to the maximum sizes listed above.

650 SH & PW SERIES - MILE PER HOUR (MPH) MAXIMUM SIZE CHART

PAGE 1 OF 2

			I		1						
650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FLANGE FRAME SNG GLZ OR INS	650 SH OR PW FLANGE FRAME SNG GLZ OR INS	650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FLANGE FRAME SNG GLZ OR INS	650 SH OR PW FLANGE FRAME SNG GLZ OR INS	650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FIN FRAME SNG GLZ OR INS	650 SH OR PW FIN OR FLANGE FRAME SNG GLZ OR INS	SERIES/TYPE
ир то 140 МРН	uр то 120 MPH	ир то 140 МРН	ир то 120 МРН	uр то 140 MPH	up то 120 MPH	uр то 140 MPH	uр то 130 MPH	uр то 140 MPH	ир то 130 МРН	up то 140 MPH	MPH Zone(s)
HORIZONTAL MULL #5767	HORIZONTAL MULL #5767	HORIZONTAL MULL #CM-65129	HORIZONTAL MULL #CM-65129	HORIZONTAL MULL #CM-65131	HORIZONTAL MULL #CM-65131	VERTICAL MULL #CM-65129	VERTICAL MULL #CM-65129	VERTICAL MULL #CM-65130	VERTICAL MULL #CM-65130	Z/A	REQUIRE
\$ 	W	i_i HD	i Li	*	*	×	*	¥	3	N/A	REQUIRED MULLION
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	53-1/8" x 72"	MAX SINGLE UNIT
45" x 72" w/Transom*	53-1/8" x 72" w/Transom*	30" x 72" w/TRANSOM*	37" x 72" w/Transom*	45" x 72" w/Transom*	53-1/8" x 72" w/Transom*	53-1/8" x 63" OR 42" x 72"	53-1/8" × 72"	53-1/8" x 63" OR 42" x 72"	53-1/8" x 72"	N/A	MAXIMUM SIZES ALLOWED
30" x 72" w/T RANSOM*	32" x 72" w/Transom*	N/A	N/A	30" x 72" w/Transom*	32" x 72" w/Transom*	53-1/8" x 63" OR 42" x 72"	53-1/8" × 72"	53-1/8" x 63" OR 42" x 72"	53-1/8" x 72"	N/A	WED TRIPLE UNIT

<sup>All Transoms (1, 2, & 3-Lites) must be continuous frame.
Transom units must be a minimum of 1/0 tall. The maximum transom height is one half the width of the transom.
Both Single Hung & Picture Windows can be used in combination up to the maximum sizes listed above.</sup>



AAMA/NWWDA 101/I.S.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf
	-47.2 psf
Operating Force	11 lb max.
Air Infiltration	$0.13 \mathrm{cfm/ft}^2$
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf
	-70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess, Technician

MAH:nlb



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC. 650 West Market Street P.O. Box 370 Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01

Test Date:

03/07/02

Report Date: Expiration Date:

03/26/02 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3'11-3/8" wide by 2'9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and 1/2 secured with PVC snap-in glazing beads.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com

allen M. Reun 1 APRIL 2002



Weatherstripping:

<u>Description</u>	Quantity	Location
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	Quantity	Location
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top fail 110. 1935.
		APRIL ZOOZ MAJONAL ENGLIS



<u>Paragraph</u>	Title of Test - Test Method	Results	Allowed
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM	F 588-97)	
	Type: A Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry
Optional Perfe	ormance		
4.3	Water Resistance (ASTM E 547- (with and without screen)	00)	
	WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM	I E 330-97)	
	(Measurements reported were tak (Loads were held for 33 seconds)	en on the meeting rail)	
	@ 45.0 psf (positive)	0.47"*	0.26" max.

^{*}Exceeds L/175 for deflection, but passes all other test requirements.

@ 47.2 psf (negative)

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 67.5 psf (positive) 0.05" @ 70.8 psf (negative) 0.05"

0.46"*

alla M. Recon

0.26" max.





Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess Technician

MAH:nlb 01-41134.01 Allen N. Reeves, P.E.

Director - Engineering Services

I APRIL ZOOZ





AAMA/NWWDA 101/I.S.2-97 TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 4250, 4550, 8500, 8540 TYPE: PVC Fixed Window

	Results			
Title of Test	Test Specimen #1	Test Specimen #2		
Ratings	F-C35 72 x 96	F-C50 65 x 84*		
Overall Design Pressure	35 psf	50 psf		
Air Infiltration	$0.04 \mathrm{cfm/ft}^2$	N/A		
Water Resistance	12.0 psf	N/A		
Structural Test Pressure	+58.5, -63.0 psf	+75.0 psf		
Deglazing	Passed	Passed		
Forced Entry Resistance	Grade 40	N/A		

Reference should be made to Report No. 01-39039.03 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Adam Fodor, Technician

AF:tjp/nlb



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC. 650 West Market Street Gratz, Pennsylvania 17030-0370

Report No: 01-39039.03

Test Date:
Report Date:

03/09/01 10/19/01

Expiration Date:

03/09/05

Project Summary: Architectural Testing, Inc. (ATI) was contracted to witness tests on two Series/Model 4250, 4550, 8500, 8540, PVC fixed windows at the MI Home Products, Inc. inplant test facility in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for the following ratings: Test Specimen #1 F-C35 72 x 96; Test Specimen #2F-C50 65 x 84*. Test specimen descriptions and results are reported herein.

General Note: An asterisk (*) next to the performance grade indicates that the size tested for optional performance was smaller than the gateway size for the product type and class.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description:

Series/Model: 4250, 4550, 8500, 8540

Type: PVC Fixed Window

Test Specimen #1: F-C35 72 x 96

Overall Size: 5' 11-1/2" wide by 7' 11-1/2" high

Fixed Daylight Opening Size: 5' 7-3/4" wide by 7' 7-3/4" high

Glazing Type: 7/8" thick sealed insulating glass fabricated from two sheets of 3/16" thick tempered transparent glass.

130 Derry Court York, PA 17402-9405 phone: 717.764.7700 fax: 717.764.4129 www.archtest.com