



(01) -Existing canopy structure

(02) -(2) 60 watt Power Supplies Located Inside Enclosure

(03) -Canopy fascia by others

04 -Vacuum Formed Sunoco Yellow Polycarbonate

05 -Tek 3 #12 X 1" Metal Screws into Canopy fascia/fascia supports

(06) -Vacuum Formed White ABS Backer

(07) -Principal Quik Mod 2 (3500K) White LED Modules taped to back of Arrow Backer

-Metal Enclosure with Primary Disconnect Switch Located Behind Canopy Fascia.

-Aluminum Canopy Filler to match 3M 180C-47 Intense Blue Vinyl. Filler to Cap off Recess Section of Canopy On Left, Right & Bottom Of Arrow Sign

(10) -1/4" Dia Drain Holes

O-1 Section B-B Detail

SECTION



THIS ITEM HAS BEEN DIGITALLY SIGNED & SEALED BY ENRIQUE A TORRENS, P.E. ON THE DATE ADJACENT TO THE SEAL PRINTED COPIES OF THIS DOCUMENT ARE NOT SIGNATURE MUST BE

Digitally signed by **ENRIQUE TORRENS** DN: c=US, o=Unaffiliated, dnQualifier=A01410C000 00191C3371375000F384 7, cn=ENRIQUE TORRENS Date: 2024.10.15 13:23:26 -04'00'

UL LISTED

I.THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES.

Columbia

Reviewed

for Code

Compliance.

Pore of Florida

- 2.THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.
- 3.WET RATED EXTERNAL DISCONNECT BOX/SWITCH TO BE PROVIDED AS PER NATIONAL ELECTRICAL CODE (NEC) 600.6
- 4. EXISTING BRANCH CIRCUIT IN COMPLIANCE W/ NEC 600.5 NOT TO EXCEED 20 AMPS

## NOTE:

- DESIGN WIND PRESSURE IN CONFORMANCE W ASCE 7-22, I40 MPH Vult, PER 2023 8TH EDITION
- 2. BOLTS: ASTM A307
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR WATERPROOFING.
- 4. ALUM: 6061-T6
- 5. ELECTRICAL: NEC 2020

## **ENGINEER**

ENRIQUE A. TORRRENS, P.E. # 33379 624 BUCKINGHAM DR. OVIEDO, FLORIDA 32765

WIND DESIGN CRITERIA		PH/FAX (407) 765-6130	
RISK CATEGORY	2	PROJECT: SINOCO	PROJECT:
WIND VELOCITY	140 MPH Vult	PROJECT: SUNOCO 441 Lake City, FL 32024	2024-0837
EXPOSURE CATEGORY (MMRF)	В	CLIENT:	1
COMPONENT & CLADDING PRESSURES	31.4 PSF	PETROGROUP	-
FORCE COEFFICIENT &	1.2	08/15/2024   0F	