


BEARING WOOD INTERIOR WALL SCHEDULE

MARK	STUD SPACING	CONNECTION & FASTENERS		LUMBER SPECIES	UPLIFT CAP (LBS)
		TOP	BOTTOM		
BW1	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW2	16"	SP2 W/ (6)10d NAILS	SP1 W/ (6) 10d NAILS	SPF	402
BW3	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	571
BW4	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW5	16"	SP2 W/ (6) 10d NAILS	SP1 W/ (6) 10d NAILS	SYP	439
BW6	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	665
BW7	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW8	12"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SPF	535
BW9	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	760
BW10	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW11	12"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SYP	585
BW12	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	885

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS
ALL LUMBER TO BE GRADE #2
CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED
SPF'S & SYP'S CAN BE SUB. FOR SP4'S W/ RESPECT TO STUD SIZE



BEARING INTERIOR WALL DETAIL

- GENERAL NOTES
- SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED UNO.
 - ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.
 - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 - CONTACT E.O.R. IF SP4'S, SP1'S OR SP2'S CONNECTORS ARE SUBSTITUTED. TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
 - IF "B" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE WRO6/S3.1 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO 1st FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY.)
 - IF "S" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 7/16" OSB PLYWOOD W/ 8d NAILS AT 4" O.C. IN FIELD AND EDGE TO (1) SIDE OF WALL & 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE AND AS SHEARWALLS. SEE PLAN AND WALLS SECTION FOR STUD SPACING AND GRADE.
 - IF THE BEARING WALL IS INDICATED WITH THE BWL, BW4, BW7, BW10 THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE NAILED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (8d NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

COLUMN SCHEDULE

MARK	COLUMN SIZE	(BASE) CONN. & FASTENER	UPLIFT(LBS)
C1	(3) 2 x 4 #2 SPF	(4) - 16d TOENAILS	0
C2	(3) 2 x 4 #2 SPF	DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145
C3	(3) 2 x 4 SYP #1 OR-	(4) - 16d TOENAILS	0
C4	(4) 2 x 4 SYP #2		2145
C5	4 x 4 P.T. #2 SYP POST	AQUA W/ 5/8" ATR** & (12) - 16d NAILS	G = 6665 U = 2200
C6	6 x 6 P.T. #2 SYP POST	ABUG6 W/ 5/8" ATR** & (12) - 16d NAILS	G = 12000 U = 2300
C7	8 x 8 P.T. #2 SYP POST	ABUG8 W/ (2) - 5/8" ATR** & (18) - 16d NAILS	G = 21335 U = 2320
C8	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C9	3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C10	3.5 x 7 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	6970
C11	5.25 x 5.25 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C12	7 x 7 F.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870
C13	5.25 x 7 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.)	HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR**	7870

GENERAL COLUMN NOTES

- SEE FLOOR PLAN FOR WALL WIDTH. STUD PACKS TO MATCH WALL WIDTH UNO.
- ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.
- NAIL BUILT UP STUDS PER DETAIL WFS7.
- MINIMUM BOLT EMBEDMENT:
5" EMBEDMENT FOR 1/2" ATR
6" EMBEDMENT FOR 5/8" ATR
8" EMBEDMENT FOR 1" ATR
- IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL-OUT ON PLAN FOR ATTACHMENT)
- SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
- SAVE NOMINAL SIZE PARALLAM COLUMNS (1.8E) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS

COMMON NAIL vs. PNEUMATIC GUN NAILS:

COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL DIA./LENGTH	COMMON vs. GUN NAIL DIA./LENGTH	APPLICATION
8d	0.131" X 2 1/4"	0.131" X 2 1/4"	SEE PLAN RING	SHEATHING ROOF & WALLS
10d OR 12d	0.148" X 3"	0.131" X 3"	SEE PLAN	BLOCKING & TOE NAILS & TOP PLATE
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	8" O.C.(COMMON) 8" O.C.(GUN NAIL)	STUD WALL CORNERS
10d	0.148" X 3"	0.131" X 3"	8" O.C.(COMMON) 8" O.C.(GUN NAIL)	STUD PACK COLUMNS
16d	0.162" X 3 1/4"	0.131" X 3 1/4"	(2) 16d(COMMON) (3) 16d (GUN NAILS)	SEE PLAN

BEAM SCHEDULE

MARK	BEAM SIZE	CONNECTIONS
BM1	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA18 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM2	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM3	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM4	(2) - 1 3/4" X 11 1/4" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA14 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM5	(2) - 1 3/4" X 11 7/8" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA14 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM6	(2) - 1 3/4" X 16" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.

- GENERAL BEAM NOTES
- VERIFY W/ PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)
 - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
 - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.

HEADER SCHEDULE

(IF USED, SEE DET. "HDR" ON SHEET S-2 FOR ENERGY STAR INSULATION ON HEADERS)


MARK	HEADER SIZE	REMARKS
H1	(2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 1 3/4" X 11 1/4" LVL 2.0E Rb=2600 PSI	ATTACH TOGETHER W/ (2) ROWS 1/4" X 1 1/2" SDS MD SCREWS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 1 3/4" X 9 1/4" LVL 2.0E Rb=2600 PSI	ATTACH TOGETHER W/ (2) ROWS 1/4" X 1 1/2" SDS MD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS

OPENING SIZE	2x4 WALL	2x6 OR 2x8 WALL
	JACKS EA. END	JACKS EA. END
1'-0" - 3'-11"	(1)	(1)
4'-0" - 9'-11"	(2)	(2)
10'-0" - 16'-0"	(3)	(4)

GENERAL HEADER NOTES


- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1st FLOOR, SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CONNECTIONS UNO ON PLAN
- IF HEADER IS ON THE 2nd FLOOR, SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.
- ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WFS7.
- FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" o.c. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
- IF HEADER IS NOT SPECIFIED CONTACT E.O.R.



- Any accessible space under a stairway shall be protected with 1/2" gypsum board.
- Maximum Stair Riser height not to exceed 7 3/4"
- Minimum Stair Tread depth shall be not less than 10" (exclusive of nosing).

STAIR DETAIL (STRAIGHT)

SCALE: 1/4" = 1'-0"



NOTE:
INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attic by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished garage or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
M1502.3 Duct termination
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
Option 1: Gypsum:
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
The gypsum board shall be attached w/ Type "W" 1x4 drywall screws at 8" O.C. in field and edges.
Option 2: Plyster Base:
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

1st FLOOR	1020 S.F.
2nd FLOOR	1385 S.F.
TOTAL LIVING (AC)	2405 S.F.
GARAGE	416 S.F.
LANAI	118 S.F.
COVERED ENTRY	52 S.F.
TOTAL AREA UNDER ROOF	2991 S.F.

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is for the structural engineering portions of the drawing pages bearing engineer's signature and seal.
CA No. 9161 AA26003115

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333
100% Employee Owned
myTSGhome.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE


INVENTORY
LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan/Issue Date:
Wednesday, March 19, 2025
KA PROJECT NUMBER:
25-02688

Sheet: **2** Of:
FLOOR PLAN

BEARING WOOD INTERIOR WALL SCHEDULE					
MARK	STUD SPACING	CONNECTION & FASTENERS	LUMBER SPECIES	UPLIFT CAP (lb)	
		TOP	BOTTOM		
BW1	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW2	16"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SPF	402
BW3	16"	SP4 W/ (6) 10d x 1 1/2" NAILS	SP4 W/ (6) 10d x 1 1/2" NAILS	SPF	574
BW4	16"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW5	16"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SYP	439
BW6	16"	SP4 W/ (6) 10d x 1 1/2" NAILS	SP4 W/ (6) 10d x 1 1/2" NAILS	SYP	665
BW7	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SPF	0
BW8	12"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SPF	535
BW9	12"	SP4 W/ (6) 10d x 1 1/2" NAILS	SP4 W/ (6) 10d x 1 1/2" NAILS	SPF	760
BW10	12"	(2) 16d TOENAILS	(2) 16d TOENAILS	SYP	0
BW11	12"	SP2 W/ (6)10d NAILS	SP1 W/ (6)10d NAILS	SYP	585
BW12	12"	SP4 W/ (6) 10d x 1 1/2" NAILS	SP4 W/ (6) 10d x 1 1/2" NAILS	SYP	885



- ### GENERAL NOTES
- SEE FLOOR PLAN FOR WALL SIZE, ASSUME 2x4 STUDS USED U.N.O.
 - ALL STRUCTURAL LUMBER TO BE SPF #1 OR SPF #2 U.N.O. ON PLAN.
 - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 - CONTACT E.O.R. IF SP4'S, SP2'S OR SP4'S CONNECTIONS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS
 - IF "BW" IS INDICATED ON SECOND FLOOR, BASE CONNECTION TO IGNORED, SEE W/09.3.1 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2ND FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 3 STORY PROJECTS ONLY)
 - IF "BW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 7" MIN. OSB FLUTCH PLATE AND NAILS AT 4" O.C. IN FIELD AND ONE (1) SIDE OF WALL
 - ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALL SECTIONS FOR STUD SPACING AND GRADE
 - IF THE BEARING WALLS IS INDICATED WITH THE BOLD, BWA, BW7, BWA7 THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT, THE STUDS ARE TOE NAILS TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HAND CAPPED NAILS (GUN NAILS) AND WILL NOT BE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

MARK	COLUMN SIZE	(BASE) CONN. & FASTENER	UPLIFT(LB)
C1	(3) 2 x 4 #2 SPF	(4) - 16d TOENAILS	0
C2	(3) 2 x 4 #2 SPF	DT22 W/ 1/2" WEDGE ANCHOR & (6) 1/4" x 1 1/2" SDS SCREWS	2145
C3	(3) 2 x 4 SYP #1 OR	(4) - 16d TOENAILS	0
C4	(4) 2 x 4 SPF #2	DT22 W/ 1/2" WEDGE ANCHOR & (6) 1/4" x 1 1/2" SDS SCREWS	2145
C5	4 x 4 P.T. #2 SYP POST	ABU4 W/ 5/8" ATR** & (2) - 16d NAILS	G = 6065 U = 2200
C6	6 x 6 P.T. #2 SYP POST	ABU6 W/ 5/8" ATR** & (2) - 16d NAILS	G = 12000 U = 2300
C7	8 x 8 P.T. #2 SYP POST	ABU8 W/ (2) - 5/8" ATR** & (3) - 16d NAILS	G = 24335 U = 2320
C8	3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C9	3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	5645
C10	3.5 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	6970
C11	5.25 x 5.25 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	7870
C12	7 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR**	7870
C13	5.25 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.)	H0US-SDS2.5 W/ (7) 7/8" ATR AND (20) 1/4" x 2" SDS WOOD SCREWS	7870

- ### GENERAL COLUMN NOTES
- SEE FLOOR PLAN FOR WALL WIDTH, STUD PAKS TO MATCH WALL WIDTH U.N.O.
 - ALL STRUCTURAL LUMBER TO BE SPF #1 OR SPF #2 U.N.O. ON PLAN.
 - NAIL BUILT UP STUDS PER DETAIL W/37
 - MINIMUM BOLT EMBEDMENT:
5" EMBEDMENT FOR 1/2" ATR
6" EMBEDMENT FOR 5/8" ATR
8" EMBEDMENT FOR 7/8" ATR
 - IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
 - SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
 - SAME NOMINAL SIZE PARALLAM COLUMNS (L8E) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS**

COMMON NAIL VS. PNEUMATIC GUN NAILS:			
COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL (COMMON VS. GUN NAIL) (LENGTH) IN INCH, SPACING	APPLICATION
8d	0.131" x 2 1/4"	0.131" x 2 1/4"	SEE PLAN RING SHANK ON ROOF
10d OR 12d	0.148" x 3"	0.131" x 3"	SEE PLAN
12d	0.148" x 3 1/4"	0.131" x 3 1/4"	8" O.C. (COMMON) 16" O.C. (GUN NAIL)
10d	0.148" x 3"	0.131" x 3"	8" O.C. (COMMON) 16" O.C. (GUN NAIL)
16d	0.162" x 3 3/4"	0.131" x 3 3/4"	(2) 16d (COMMON) (3) 16d (GUN NAILS)

MARK	BEAM SIZE	CONNECTIONS
BM1	(2) - 2 x 8 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM2	(2) - 2 x 10 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM3	(2) - 2 x 12 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM4	(2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM5	(2) - 1 3/4" x 11 7/8" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.
BM6	(2) - 1 3/4" x 16" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HT520 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN.

- ### GENERAL BEAM NOTES
- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEYOND EACH END)
 - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
 - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.

MARK	HEADER SIZE	REMARKS
H1	(2) - 2x6 #2 SYP W/ 1/2" FLUTCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2x6 #2 SYP W/ 1/2" FLUTCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2x10 #2 SYP W/ 1/2" FLUTCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 #2 SYP W/ 1/2" FLUTCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI	ATTACH TOGETHER W/ (2) ROWS 1/4" x 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 1 3/4" x 9 1/4" LVL 2.0E Fb=2600 PSI	ATTACH TOGETHER W/ (3) ROWS 1/4" x 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE

HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS					
OPENING SIZE	2x4 WALL	JACKS EA. END	KINGS EA. END	JACKS EA. END	KINGS EA. END
1'-0" - 3'-11"	(1)	(2)	(1)	(2)	(2)
4'-0" - 9'-11"	(2)	(3)	(2)	(2)	(2)
10'-0" - 16'-0"	(3)	(4)	(3)	(4)	(4)

- ### GENERAL HEADER NOTES
- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
 - IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN
 - IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.
 - ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL W/37
 - FASTEN ALL MULT-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" O.C. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
 - FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
 - IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

EXTERIOR 2ND FLOOR BEARING WALL SCHEDULE			
HEIGHT	STUD	SPECIES	SPACING
8'-0"	2x4	SYP #2	16" O.C.
9'-0"	2x4	SYP #2	16" O.C.
>9'-0"	2x6	SYP #2	16" O.C.

* WHEN THE TOP OF WALL IS GREATER THAN 9'-0", THEN AT EACH EXTERIOR CORNER WITHIN THE 4'-0" END ZONE, THE STUDS WILL BE DOUBLE STUDS @ 16" O.C. OR SINGLE STUDS @ 12" O.C.



THIS IS ONLY USED WITH PLASTER OR STUCCO EXTERIOR FINISH

** WALL SHEATHING 15/32" EXPOSURE 1 OR EQUIVALENT, REFER TO SHEATHING SCHEDULE FOR ATTACHMENTS. **

Y	N	MASTER BA. OPTIONS
		4030 (1) PG. FIBERGLASS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. DISC LT.

OPT. MASTER BATH

SCALE: 1/4" = 1'-0"



2ND FLOOR PLAN

SCALE: 1/4" = 1'-0"
(ALL ELEVATIONS)

NOTE:
○ INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used 1 L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.1.7.1.1 through R4501.1.7.1.4.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and it's attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its retracted position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
M1502.3 Duct termination
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
Option 1: Gypsum:
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
The gypsum board shall be attached W/ Type "W" 1x4" drywall screws at 8" O.C. in field and edges.
Option 2: Plaster Base:
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

COUNTY
SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY


Model Name / Number:
2405

Plan/Issue Date:
Wednesday, March 19, 2025


KA PROJECT NUMBER:
25-02688

Sheet: **2.1** Of:


2nd FLOOR PLAN




FM01 SINGLE STORY FTG 1/2" = 1'-0"




FM02 SECTION @ GARAGE 1/2" = 1'-0"




FM25 PORCH COLUMN W/ BRICK 1/2" = 1'-0"




FM06 EXT. DOOR SILL SCALE: 3/4" = 1'-0"




FM03 THICKENED EDGE 1/2" = 1'-0"




FM08 2-STORY FTG. 1/2" = 1'-0"




FM01A SINGLE STORY FTG 1/2" = 1'-0"




FM09 SECTION @ GAR. DOOR 1/2" = 1'-0"




FM10 INTERIOR BRG WALL 1/2" = 1'-0"




FM02A SECTION @ GARAGE 1/2" = 1'-0"




FM11 STEP DOWN BRG. 1/2" = 1'-0"




FM12 STEP DOWN NON BRG. 1/2" = 1'-0"




FM14 SECTION @ RECESS SHOWER 1/2" = 1'-0"



FM18 TYP. STEP FTG. DETAIL 1/2" = 1'-0"



FM19 TYP. CORNER BAR DETAIL 1 1/2" = 1'-0"




FM23 TYP. FND PENETRATION 1/2" = 1'-0"

FOOTING SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRVITY CAP. [lbs]
F1.0	1'-0" X CONT.	1'-0"	2 #5 E.W. BOT.	2000
F2.0	2'-0" X 2'-0"	1'-0"	3 #5 E.W. BOT.	7200
F2.5	2'-6" X 2'-6"	1'-0"	3 #5 E.W. BOT.	11000
F3.0	3'-0" X 3'-0"	1'-0"	4 #5 E.W. BOT.	15600
F3.5	3'-6" X 3'-6"	1'-0"	4 #5 E.W. BOT.	19500
F4.0	4'-0" X 4'-0"	1'-0"	5 #5 E.W. BOT.	26000
F4.5	4'-6" X 4'-6"	1'-4"	5 #5 E.W. BOT.	34500
F5.0	5'-0" X 5'-0"	1'-4"	6 #5 E.W. BOT.	42500
F5.0	5'-0" X 5'-0"	1'-4"	7 #5 E.W. BOT.	61500

LEGEND	
	INDICATES SINGLE STORY FOOTING
	INDICATES TWO STORY FOOTING
	INDICATES PAD FOOTING


- GENERAL FOUNDATION NOTES (U.N.O.)
- PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.
 - 4" 2500 PSI CONC. SLAB W/ 6/8 W1.4 X W1.4 OR FIBERMESH /FIBERMIX ADDED TO THE CONCRETE. IN ACCORDANCE W/ MANUF'S INSTRUCTIONS AND PER-284 FOR FIBERMESH OR PER-414 FOR FIBERMIX. OVER 6 MIL. VISCQUEEN VAPOR BARRIER. GC SHALL PROVIDE APPROVED SOIL OR BORATE TREATMENT.
 - INDICATES FILLED CELL W/3000 PSI CONC. FROM FIR. TO BEAM W/ (1) #5 REBAR TYPICAL ABOVE SLAB. HOOKED FTG. DOWELS 17" EMBEDMENT W/ 30" EXT. ABOVE SLAB.
 - CONSULT W/ MANUF. SPECIFICATIONS PRIOR TO POURING OR RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.
 - EXTERIOR SLABS SHALL SLOPE MIN. 2% OR 1/4" PER FOOT AWAY FROM HOUSE U.N.O. ON PLAN.
 - CONTROL JOINTS (IF SHOWN) ARE NOT REQUIRED BY CODE BUT ARE SUGGESTED (ESPECIALLY WHEN USING FIBER REIN. CONCRETE OR IN EXTERIOR CONDITIONS). CONTROL JOINTS TO BE 3/8" SAW CUT A DEPTH OF 1/4 OF THE THICKNESS OF THE SLAB AND SPACED MAX. 10' APART. FILL CUT W/ APPROVED JOINT MATERIAL OR USE ALTERNATE APPROVED METHOD.
 - NO WOOD STAKES PERMITTED IN FOUNDATION.
 - PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED DOWN. G.C. TO DETERMINE STEP LOCATIONS IF REQUIRED.
 - R403.1.4 MINIMUM DEPTH. EXTERIOR FOOTINGS SHALL BE PLACED NOT LESS THAN 12 INCHES BELOW THE FINISHED GRADE OF GROUND SURFACE. WHERE APPLICABLE, THE DEPTH OF FOOTINGS SHALL ALSO CONFORM TO SECTION R403.1.4.1.
 - MASON TO COORDINATE WITH BUILDER ANY ELECTRICAL REQUIREMENT THROUGH SLAB.
 - PROVIDE 4" STEPDOWN TO SIDEWALK FROM ENTRY
 - ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF. SEE SOILS REPORT AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS IF SOIL CONDITIONS IN THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN. SOIL TO BE COMPACTED TO AT LEAST 95% OF MAX. DRY DENSITY AS DETERMINED BY ASTM - 1557 (MODIFIED PROCTOR) THE FOUNDATION SIZES INDICATED ON THE FOUNDATION PLAN HAS BEEN DESIGNED FOR A MINIMUM SOIL BEARING CAPACITY OF 2000 PSF.



PLUMBING RISER

NOTE: ALL PLUMBING RISERS ARE TO BE VERIFIED W/ PLUMBING CONTRACTORS

N.T.S.



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

FMASW ALTERNATE STEM WALL FOOTING SCHEDULE 1/2" = 1'-0"

STEMWALL SCHEDULE					
STEMWALL HEIGHT (ft)	FOOTING DIMENSION				SEE FOUNDATION PLAN FOR F.C. SPACING ABOVE SLAB LEVEL
	d 1 STORY	d 2 STORY	b 1 STORY	b 2 STORY	
0'-0"-2'-0"	8"	10"	16"	20"	W/ (2) #5 BARS
2'-0"-3'-4"	10"	10"	20"	24"	W/ (3) #5 BARS
3'-4"-4'-0"	12"	12"	32"	32"	W/ (4) #5 BARS
4'-0"-5'-4"	16"	16"	48"	48"	W/ (5) #5 BARS CONT. & #5 @ 18" O.C. TRANSV.

NOTES:

- VERTICAL REIN. IN SOLID GROUTED CELLS AT ALL CORNERS, JAMBS, WALL INTERSECTIONS, BELOW GIRDER TRUSS LOCATIONS, AND AT THE MAXIMUM SPACING STATED IN SCHEDULE
- W.W.M. IS REQUIRED TO MAKE ADEQUATE CONNECTION BETWEEN SLAB AND WALL WHEN STEM WALL EXCEEDS 4'-0" FIBERMESH CAN NOT BE USED AND #4 TURN BARS ARE REQUIRED @ EACH FILLED CELL LOCATION. EACH BAR TO TIE INTO VERTICAL BAR AND EXTEND OUT A MIN. 4'-0" INTO SLAB/ STEM
- IF STEM IS REQ'D TO BE HIGHER CONTACT ENGINEER OF RECORD PRIOR TO CONSTRUCTION FOR MORE INFORMATION
- G.C. TO PROVIDE ADEQUATE BRACING OF STEM WALL WHEN UNEVEN BACK FILLING IS TAKING PLACE
- #5 HORIZONTAL CORNER BARS WITH 4'-0" LEGS IN KNOCKOUT BLOCK @ 16" O.C. VERTICAL. GROUTED SOLID WHEN STEM WALL IS GREATER THAN 4'-0" TALL (TYPICAL ALL CORNERS)
- IF STEMWALL IS WITH IN 5'-0" OF POOL OR WATER FEATURE FOUNDATIONS TO BE A MINIMUM 12" BELOW BOTTOM OF POOL OR WATER FEATURE.
- ALL STEM WALLS GREATER THAN (4) COURSES SHALL BE FULLY GROUTED.
- R403.1.4 MINIMUM DEPTH: ALL EXTERIOR FOOTINGS (BOTTOM) SHALL BE PLACED AT LEAST 12" BELOW THE UNDISTURBED GROUND SURFACE.

EXTERIOR SHORING BY CONTRACTOR AS REQ'D WHEN STEM WALL IS OVER 4'-0"

MIN. 8" COVER REQ'D

3" COVER TYP.

SEE CHART ABOVE STEMWALL F.C. SPACING

(1) #5 CONT. TIED TO EACH VERT. REIN. BAR

#4 TURN BAR AT STEM WALLS GREATER THAN 4'-0"

IF USED: W.W.M. TO BE TIED TO #5 CONT. REBAR

COMPACTED CLEAN FILL

SEE SCHEDULE FOR REIN.

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TSG
Making Dreams Come True

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688

Sheet: 3 Or:

FOUNDATION PLAN

Wednesday, March 19, 2025

COUNTY
SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 3333

100% Employee Owned
myTSGhome.com



FLORIDA CONTRACTORS' LICENSE NO. CRC1330146

100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:

GAINESVILLE

Job Information:

INVENTORY

LOT: 117

BLK:

SEC:

SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:

25-02688

Sheet:


5

Of:

ELEVATION - A

VENTILATION CALCULATION

Soffit product provides	4.12 net sq in / sf
Ridge vent provides	18.00 net sq in / lf
Off ridge vent provides	138.00 net sq in / sf
Overhang distance	1.33 ft
S.F. of Area to be vented (SF)	1335 s.f.
Total needed for exhaust for upper 1/3	320 net sq inches
Total needed for intake (soffit area, lower)	320 net sq inches
Number of Off Ridge Vents for upper 1/3 needed	2
L.F. of Ridge Vent needed (can be used in combo with ORV)	18
Lineal Feet of Soffit needed to meet required	58
Lineal S.F. provided by plan	191




LEFT ELEVATION "A"

SCALE: 1/4" = 1'-0"



REAR ELEVATION

SCALE: 1/4" = 1'-0"




RIGHT ELEVATION "A"

SCALE: 1/4" = 1'-0"




FRONT ELEVATION "A"


SCALE: 1/4" = 1'-0"

[illegible]


Wednesday, March 19, 2025




TB15 EXTERIOR NON-BEARING WALL DETAIL N.T.S.




WC04 GARAGE HEADER ANCHOR 3/4" = 1'-0"




WC05 SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.



FB06 SECTION @ CORNER FRAMING 3/4" = 1'-0" STANDARD CORNER A-A




WC03 WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




CD11 COMMON BEAM ATTACHMENT N.T.S.

NOTE: @ ALL EXT. CONDITIONS ATTACH 2x STUDS TO TOP PLATE W/ (4) 16d TONAILS (2) ON EA. SIDE TYP. TOE NAILS MAY BE SUBSTITUTED W/ (1) SIMPSON H2.5A CONNECTOR @ EA. STUD TO TOP PLATE W/ 8d 2 1/2" x 0.131 NAILS




CD25 BEAM TO WALL CONNECTION N.T.S.




CONNECTOR LEGEND		WINDOW & DOOR JACK TABLE	
(A)	SIMPSON SPH4 W/ 12-10d x 1/2	PROVIDE JACKS @ EACH END AS FOLLOWS	
(B)	(1) SIMPSON SDWC15600 @ 16" O.C.	(2) WHEN OPN'GS ARE GREATER THEN 4'-0"	
(C)	(2) SIMPSON SDWC15600 @ EACH SIDE OF HEADER FROM KING STUDS TO TOP PLATE & (2) SDWC15600 FROM JACK STUD TO HEADER.	(3) WHEN OPN'GS ARE GREATER THEN 10'-0" BUT LESS THAN 16'-0"	
(D)	SIMPSON SPH4 W/ 12-10d x 1 1/2"	NOTE: FOR EXTERIOR OR SHEAR WALL SEE SHEET S1 FOR WALL & ROOF SHEATHING INSTALLATION & NAILING SCHEDULES	
(E)	1/2"x10" J-BOLT W/ 2"x2"x1/8" WASHER @ 32" O.C. PLUS (2) WITHIN 6" EACH SIDE OF JACK STUDS @ HEADER		


WF66 TYPICAL BEARING WALL N.T.S.




WC06 EXTERIOR FRAME CORNER 3/4" = 1'-0"



RD01 VALLEY FLASHING DETAIL N.T.S.




CD26 GIRDER BASE CONNECTION 1/2" = 1'-0"



WF68 CORNER CONNECTION N.T.S.

NOTE: @ ALL EXT. CONDITIONS ATTACH 2x STUDS TO TOP PLATE W/ (4) 16d TONAILS (2) ON EA. SIDE TYP. TOE NAILS MAY BE SUBSTITUTED W/ (1) SIMPSON H2.5A CONNECTOR @ EA. STUD TO TOP PLATE W/ 8d 2 1/2" x 0.131 NAILS



CD25 BEAM TO WALL CONNECTION N.T.S.

COUNTY SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELLFLOWER DR
LAKE CITY

Model Name / Number:

2405


Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:


25-02688

Sheet: **S-2** of:


TYPICAL FRAMING DETAILS




WF03 WALL SPLICE DETAIL 3/4" = 1'-0"




SG07 2 STORY COLUMN @ GIRDER N.T.S.




TB18 NON-BRG. EXT CMU WALL (FLOOR TRUSS) 3/4" = 1'-0"



WF39 TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



WF67 WALL FRAMING 3/4" = 1'-0"



WF09 WALL HEADER DETAIL N.T.S.

STAIR NOTES
STAIRWAY CONSTRUCTION SHALL CONFORM TO THE FBC-R (CURRENT EDITION) SECTIONS R311.7, R312 AND R302.7.

RISER HEIGHT:
THE RISER HEIGHT SHALL BE NOT MORE THAN 7 3/4 INCHES. THE RISER HEIGHT SHALL BE MEASURED VERTICALLY BETWEEN LEADING EDGES OF THE ADJACENT TREADS. THE GREATEST RISER HEIGHT WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH. RISERS SHALL BE VERTICAL OR SLOPED FROM THE UNDERSIDE OF THE NOSING OF THE TREAD ABOVE. OPEN RISERS ARE PERMITTED PROVIDED THAT THE OPENINGS LOCATED MORE THAN 30 INCHES, AS MEASURED VERTICALLY, TO THE FLOOR OR GRADE BELOW DO NOT PERMIT THE PASSAGE OF A 4-INCH DIAMETER SPHERE.

TREAD DEPTH:
THE TREAD DEPTH SHALL BE NOT LESS THAN 10 INCHES. THE TREAD DEPTH SHALL BE MEASURED HORIZONTALLY BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AND AT A RIGHT ANGLE TO THE TREAD'S LEADING EDGE. THE GREATEST TREAD DEPTH WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH.

WINDERS:
WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 10 INCHES MEASURED BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AT THE INTERSECTIONS WITH THE WALKLINE. WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 6 INCHES AT ANY POINT WITHIN THE CLEAR WIDTH OF THE STAIR.


NOSINGS:
NOSINGS AT TREADS, LANDINGS AND FLOORS OF STAIRWAYS SHALL HAVE A RADIUS OF CURVATURE AT THE NOSING NOT GREATER THAN 9/16 INCH OR A BEVEL NOT EXCEEDING 1/2 INCH. A NOSING PROJECTION NOT LESS THAN 3/4 INCH AND NOT MORE THAN 1 1/4 INCHES SHALL BE PROVIDED ON STAIRWAYS. THE GREATEST NOSING PROJECTION SHALL NOT EXCEED THE SMALLEST NOSING PROJECTION BY MORE THAN 3/8 INCH WITHIN A STAIRWAY.

HANDRAILS:
HANDRAILS SHALL BE PROVIDED ON NOT LESS THAN ONE SIDE OF EACH FLIGHT WITH FOUR OR MORE RISERS. HANDRAIL HEIGHT MEASURED VERTICALLY FROM THE SLOPED PLANE ADJOINING THE TREAD NOSING, OR FINISH SURFACE OF RAMP SLOPE, SHALL BE NOT LESS THAN 34 INCHES AND NOT MORE THAN 38 INCHES. HANDRAILS FOR STAIRWAYS SHALL BE CONTINUOUS FOR THE FULL LENGTH OF THE FLIGHT, FROM A POINT DIRECTLY ABOVE THE TOP RISER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOWEST RISER OF THE FLIGHT. HANDRAIL ENDS SHALL BE RETURNED OR SHALL TERMINATE IN NEWEL POSTS OR SAFETY TERMINALS. HANDRAILS ADJACENT TO A WALL SHALL HAVE A SPACE OF NOT LESS THAN 1 1/2 INCHES BETWEEN THE WALL AND THE HANDRAILS.

GRIP-SIZE:
HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF NOT LESS THAN 1 1/4 INCHES AND NOT GREATER THAN 2 INCHES OR PROVIDE EQUIVALENT GRASPABILITY IN COMPLIANCE WITH SECTION R311.7.B.3.


GUARDS:
GUARDS SHALL BE PROVIDED FOR THOSE PORTIONS OF OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, RAMPS AND LANDINGS, THAT ARE LOCATED MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW AT ANY POINT WITHIN 24 INCHES HORIZONTALLY TO THE EDGE OF THE OPEN SIDE. REQUIRED GUARDS AT OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, PORCHES, BALCONIES OR LANDINGS, SHALL BE NOT LESS THAN 36 INCHES IN HEIGHT AS MEASURED VERTICALLY ABOVE THE ADJACENT WALKING SURFACE OR THE LINE CONNECTING THE LEADING EDGES OF THE TREADS. REQUIRED GUARDS SHALL NOT HAVE OPENINGS FROM THE WALKING SURFACE TO THE REQUIRED GUARD HEIGHT THAT ALLOW PASSAGE OF A SPHERE 4 INCHES IN DIAMETER.

UNDER-STAIR PROTECTION:
ENCLOSED SPACE UNDER STAIRS THAT IS ACCESSED BY A DOOR OR ACCESS PANEL SHALL HAVE WALLS, UNDER-STAIR SURFACE AND ANY SOFFITS PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH GYPSUM BOARD.



INTERIOR STAIR SECTION

N.T.S.



SD04 GENERAL LANDING FRAMING INFO. N.T.S.

COUNTY
SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELLFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025


KA PROJECT NUMBER:

25-02688


Sheet: S-2.1 of:

TYPICAL FRAMING
DETAILS


Wednesday, March 19, 2025




WS02 TYPICAL WALL SECTION EXTERIOR FRAME 3/4" = 1'-0"




SE TYPICAL SOFFIT AND EAVE DETAIL 3/4" = 1'-0"




WF37 TYPICAL COLUMNS DETAILS N.T.S.




WF17 TOP PLATE SPLICE DETAIL 3/4" = 1'-0"




WF63 SECTION AT DOUBLE BEARING N.T.S.




CD24 POST & BEAM DETAIL 1/2" = 1'-0"




SW01 INTERIOR BEARING SHEARWALL w/UPLIFT N.T.S.




WC07 STEP UP @ CORNER & RAISED BEAM 1/2" = 1'-0"



BD07 BRICK SHELF DETAIL N.T.S.



WC08 STEP UP @ CORNER & RAISED BEAM N.T.S.



SW04 INTERIOR SHEARWALL @ TRUSSES 3/4" = 1'-0"

COUNTY SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



100% Employee Owned
myTSHome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330148
**100 WEST GARDEN STREET
PENSACOLA FL 32502**

**DIVISION LOCATION:
GAINESVILLE**

Job Information:

INVENTORY

LOT: 117
BLK: SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:

2405


Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688


Sheet: **S-3** Of:

TYPICAL WALL DETAILS


SG01 GIRDER/COLUMN @ 2ND FLR w/HIGH BM N.T.S.




FB12 BLOCKING DETAIL 3/4\" = 1'-0"




WF71 KNEEWALL AT DORMER N.T.S.




SH05 HEADER CONNECTION @ 2ND FLOOR w/ HIGH BEAM




WS06 FLOOR ATTACHMENT DETAIL 3/4\" = 1'-0"




SH07 ALTERNATE HEADER CONDITIONS N.T.S.




WF69 WALL @ 2ND FLOOR N.T.S.




WF70 CANTELIVER FLOOR SECTION N.T.S.




WF06 2 STORY INTERIOR BEARING WALL N.T.S.




18 FLOOR CONNECTION N.T.S.



WF65 LOW ROOF TO SECOND FLOOR CONN. N.T.S.



WS04 TYPICAL TWO STORY WALL SECTION 3/4\" = 1'-0"



INVENTORY

LOT: 117
BLK: SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688

Sheet: S-3.1 Of:

TYPICAL WALL DETAILS

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myISGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 117
BLK: SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688

Sheet: S-3.1 Of:

TYPICAL WALL DETAILS

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myISGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 117
BLK: SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY


Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025


KA PROJECT NUMBER:
25-02688

Sheet: S-3.1 Of:

TYPICAL WALL DETAILS




TB01 TYPICAL CROSS BRACING DETAIL N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL N.T.S.

THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




CH01 TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"


RAFTER SIZE	
0'-8" SPAN -	2"x6" W/4-12d EACH END
8'-12" SPAN -	2"x8" W/4-12d EACH END
12'-15" SPAN -	2"x10" W/ SIMPSON A 34 @ EA. END
15'-18" SPAN -	2"x12" W/ SIMPSON A 34 @ EA. END



TB17 CONV. FRAMING & VALLEY FRAMING N.T.S.






TB03 HIP / RIDGE BLOCKING DETAIL N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.

TRUSS NOTES:


- WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUNDLES OF SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS GRAVEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
- ALL BRACING (DB,CB,BB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUF. SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
- ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
- ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
- PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS.




A-A ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING

TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL


TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"



GE04 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"




WF05 DORMER FRAMING DETAIL N.T.S.



GENERAL NOTES
1. SEE SH07/D4 FOR ALT. CONDITION

SH00 HEADER CONNECTION @ 2ND FLOOR 3/4" = 1'-0"



WF05 WALL SPICE DETAIL 3/4" = 1'-0"

COUNTY
SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.
CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
**100 WEST GARDEN STREET
PENSACOLA FL 32502**

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:


25-02688

Sheet:


S-4

Of:


ROOF FRAMING
AND BRACING DETAILS




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.




GE21 SECTION @ DUTCH GABLE 3/4"=1'-0"




LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.



GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4"=1'-0"



GE16 SECTION @ HIP GABLE SCALE: 3/4"=1'-0"

COUNTY SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TS&G

CA No. 9161 AA26003115

Making Dreams Come True

TOTAL SOLUTIONS GROUP

258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned

myTS&Ghome.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:

GAINESVILLE

Job Information:

Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025


KA PROJECT NUMBER:
25-02688

Sheet: **S-4.1** Of:

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

ROOF FRAMING AND BRACING DETAILS




- HEAD FLASHING TIE-IN INSTRUCTIONS:
1. Cut, fold up & temporarily secure weather resistive barrier above header to allow for flashing installation
 2. Self-adhered flashing plus head flashing under weather resistive barrier
 3. Fold weather resistive barrier back over head flashing and seal with tape

SELF-ADHERED FLASHING
FLASHING INSTALLATION AFTER WEATHER RESISTIVE BARRIER


Scale: NTS

WP01




SELF-ADHERED FLASHING
HALF ROUND WINDOW

WP04



SELF-ADHERED FLASHING
W/0.8362x/DECK JOIST


WP07



- NOTES:
1. INSTALL WINDOW PER MANUFACTURER'S RECOMMENDATION AND USE APPROPRIATE SEALANT FOR WINDOW AND WOOD BUCK
 2. WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.


RECESSED WINDOW

WP10




SELF-ADHERED FLASHING
EXTERIOR DOOR WITH DECK - SECTION A

WP02




SELF-ADHERED FLASHING
EXTERIOR DOOR WITH DECK

WP05



SELF-ADHERED FLASHING
OUTSIDE CORNER


WP08



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
 2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.


WALL-TO-WALL OUTSIDE CORNER

WP11




TIE-IN WITH VINYL SIDING
AT WINDOW SILL

WP03



SELF-ADHERED FLASHING
INSIDE CORNER

WP06



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
 2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL INSIDE CORNER

WP12

THESE DETAILS ARE GENERIC AND MEANT TO SHOW
GENERAL FLASHING AND WATERPROOFING METHODS
TO BE USED.

SELF-ADHERED FLASHING PRODUCTS DETAILS

TWO LAYERS OF FELT OR ONE LAYER OF HOUSE WRAP AND
ONE LAYER OF FELT ARE REQUIRED BEHIND STUCCO. FBC R703.2

DETAIL INSTRUCTIONS

REFER TO THE NUMBER MARKED AS (#) IN EACH DETAIL THAT
CORRESPONDS TO THE NUMBERED ITEMS IN THE LIST OF
INSTRUCTIONS BELOW:

1. INSTALL SELF-ADHERED FLASHING IN ORDER AS SHOWN BY NUMBERS.
2. INSTALL FLASHING AND WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.
3. SELF-ADHERED FLASHING CAN BE SUBSTITUTED FOR BUILDING PAPER.
4. SPLIT THE RELEASE PAPER USING THE RIPCORD (SPLIT RELEASE ON DEMAND, EMBEDDED IN THE ADHESIVE LAYER) - FOR EASE OF INSTALLATION AND TO MINIMIZE SCORING CUTS.
5. REMOVE ALL RELEASE PAPER PER STANDARD INSTALLATION INSTRUCTIONS AND ADHERE TO SUBSTRATE USING A SQUARE PIECE OF FLASHING MATERIAL (6" X 6" MINIMUM).
6. FOLD AS SHOWN BY ARROWS.
7. ANGLE OF CORNER MAY VARY, ADJUST FOLDING OF THE FLASHING ACCORDINGLY TO FIT TIGHT TO CORNER.
8. MECHANICALLY FASTEN AS NECESSARY.

FLASHING REQUIREMENTS

R703.1 GENERAL. EXTERIOR WALLS SHALL PROVIDE THE BUILDING WITH A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. THE EXTERIOR WALL ENVELOPE SHALL INCLUDE FLASHING AS DESCRIBED IN SECTION R703.4. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL, BEHIND AN EXTERIOR WALL COVERING THAT IS INTENDED TO RESIST LIQUID WATER THAT HAS PENETRATED BEHIND THE EXTERIOR COVERING FROM FURTHER INTRUDING INTO THE EXTERIOR WALL ASSEMBLY. AN EXTERIOR WALL COVERING IS DESCRIBED AS A MATERIAL OR ASSEMBLY OF MATERIALS APPLIED ON THE EXTERIOR SIDE OF EXTERIOR WALLS FOR THE PURPOSE OF PROVIDING A WEATHER-RESISTIVE BARRIER, INSULATION, OR FOR AESTHETICS, INCLUDING BUT NOT LIMITED TO, VENEERS, SIDING, EXTERIOR INSULATION AND FINISH SYSTEMS, ARCHITECTURAL TRIM AND EMBELLISHMENTS SUCH AS CORNICES, SOFFITS, AND FASCIAS.

R703.2 WATER-RESISTIVE BARRIER. ONE LAYER OF NO. 15 ASPHALT FELT, FREE FROM HOLES AND BREAKS, COMPLYING WITH ASTM D228 FOR TYPE I FELT OR OTHER APPROVED WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51 MM) WHERE JOINTS OCCUR. FELT SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 MM). THE FELT OR OTHER APPROVED MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1.

R703.7.3 WATER-RESISTIVE BARRIERS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.

EXCEPTION: WHERE THE WATER-RESISTIVE BARRIER THAT IS APPLIED OVER WOOD-BASED SHEATHING HAS A WATER RESISTANCE EQUAL TO OR GREATER THAN THAT OF 60-MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING, SUBSTANTIALLY NONWATER-ABSORBING LAYER OR DESIGNED DRAINAGE SPACE.

R703.4 FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SHINGLE-FASHION IN A MANNER TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED MEMBRANES USED AS FLASHING SHALL COMPLY WITH AAMA 711. ALL EXTERIOR PENETRATION PRODUCTS SHALL BE SEALED AT THE JUNCTURE WITH THE BUILDING WALL WITH A SEALANT COMPLYING WITH AAMA 800 OR ASTM C920 CLASS 25 GRADE NS OR GREATER FOR PROPER JOINT EXPANSION AND CONTRACTION. ASTM C1281, AAMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE TYPE OF SEALANT. FLUID-APPLIED MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH AAMA 714. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED CORROSION-RESISTANT FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS:

1. EXTERIOR WINDOW AND DOOR OPENINGS. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER-RESISTIVE BARRIER COMPLYING WITH SECTION 703.2 FOR SUBSEQUENT DRAINAGE. MECHANICALLY ATTACHED FLEXIBLE FLASHINGS SHALL COMPLY WITH AAMA 712. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL BE INSTALLED IN ACCORDANCE WITH ONE OR MORE OF THE FOLLOWING:
 - 1.1 THE PENETRATION MANUFACTURER'S INSTALLATION AND FLASHING INSTRUCTIONS, OR FOR APPLICATIONS NOT ADDRESSED IN THE PENETRATION MANUFACTURER'S INSTRUCTIONS, IN ACCORDANCE WITH THE FLASHING MANUFACTURER'S INSTRUCTIONS, WHERE FLASHING INSTRUCTIONS OR DETAILS ARE NOT PROVIDED. PAN FLASHING SHALL BE INSTALLED AT THE SILL OF EXTERIOR WINDOW AND DOOR OPENINGS. PAN FLASHING SHALL BE SEALED OR SLOPED IN SUCH A MANNER AS TO DIRECT WATER TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE. OPENINGS USING PAN FLASHING SHALL INCORPORATE FLASHING OR PROTECTION AT THE HEAD AND SIDES.
 - 1.2. IN ACCORDANCE WITH THE FLASHING DESIGN OR METHOD OF A REGISTERED DESIGN PROFESSIONAL.
 - 1.3. IN ACCORDANCE WITH OTHER APPROVED METHODS.
 - 1.4. IN ACCORDANCE WITH FMA/AAMA 100, FMA/AAMA 200, FMA/WDMA 250, FMA/AAMA/WDMA 300 OR FMA/AAMA/WDMA 400.
2. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTING LIPS ON BOTH SIDES UNDER STUCCO CORNICES.
3. UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS.
4. CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM.
5. WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION.
6. AT WALL AND ROOF INTERSECTIONS.
7. AT BUILT-IN GUTTERS.

FIGURE 1: FLASHING INSTALLATION

ASPHALT SEALANT:
EXTEND MIN. OF 6"
OUTSIDE OF FLASHING






FIGURE 2: WALL FINISH



FLASHING INSTALLATION
WHERE ROOF MEETS VERTICAL WALL

FIGURE 3: CORNER DETAIL



FLASHING DETAIL AT CRICKET
/ KNEEWALL INTERSECTION

COUNTY
SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code-Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TOTAL SOLUTIONS GROUP

258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688

Sheet: WP Of:
WATER PROOF
DETAILS