


[illegible]

| BEARING WOOD INTERIOR WALL SCHEDULE | | | | | |
|-------------------------------------|--------------|-------------------------------|-------------------------------|----------------|-------------------|
| MARK | STUD SPACING | CONNECTION & FASTENERS | | NUMBER SPECIES | UPLIFT CAP. (PIF) |
| | | TOP | BOTTOM | | |
| BW1 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW2 | 16" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SPF | 402 |
| BW3 | 16" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SPF | 571 |
| BW4 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW5 | 16" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SYP | 439 |
| BW6 | 16" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SYP | 665 |
| BW7 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW8 | 12" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SPF | 535 |
| BW9 | 12" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SPF | 760 |
| BW10 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW11 | 12" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SYP | 585 |
| BW12 | 12" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SYP | 885 |

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS
 * ALL LUMBER TO BE GRADE #2
 ** CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED
 *** SPICES & SPS'S CAN BE SUB. TOP SPICES W/ RESPECT TO STUD SIZE



BEARING INTERIOR WALL DETAIL

1. SEE FLOOR PLAN FOR WALL SIZE, ASSUME 2x4 STUDS USED U.N.O.
 2. ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
 3. CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 4. CONTACT E.O.R. IF SPS'S OR SPS'S CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
 5. IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE WORKS/S OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO FIRST FLOOR CONNECTION. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY).
 6. IF "SW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES NAIL. (NOTE: OSB PLYWOOD WALLS AT 4" O.C. IN FIELD AND EDGE TO 11" SIDE OF WALL).
 7. ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALLS SECTIONS FOR STUD SPACING AND GRADE.
 8. IF THE BEARING WALL IS INDICATED WITH THE BW1, BW4, BW7, BW10 THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE NAIL TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

| GENERAL NOTES | | | | |
|---------------|--|--|-----------------------|--|
| MARK | COLUMN SIZE | BASE CONN. & FASTENER | UPLIFT(LBS) | |
| C1 | (3) 2 x 4 #2 SPF | (4) 16d TOENAILS | 0 | |
| C2 | (3) 2 x 4 #2 SPF | DT122 W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS | 2145 | |
| C3 | (3) 2 x 4 SYP #1 GR. | (4) 16d TOENAILS | 0 | |
| C4 | (4) 2 x 4 SPF #2 | DT122 W/ 1/2" WEDGE ANCHOR* & (8) 1/4" X 1 1/2" SDS SCREWS | 2145 | |
| C5 | 4 x 4 P.T.#2 SYP POST | ABU44 W/ 5/8" ATR** & (12) 16d NAILS | G = 6665 U = 2200 | |
| C6 | 6 x 6 P.T.#2 SYP POST | ABU66 W/ 5/8" ATR** & (12) 16d NAILS | G = 12000 U = 2200 | |
| C7 | 8 x 8 P.T.#2 SYP POST | ABU88 W/ (2) 5/8" ATR** & (18) 16d NAILS | G = 24335 U = 2320 | |
| C8 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C9 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C10 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 6970 | |
| C11 | 5.25 x 5.25 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C12 | 7 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C13 | 5.25" x 7" P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | HDUS-SDS2.5 W/ 7/8" ATR AND (20) 1/4" x 1/2" SDS WOOD SCREWS | 7870 | |

GENERAL COLUMN NOTES

- SEE FLOOR PLAN FOR WALL WIDTH. STUD PACKS TO MATCH WALL WIDTH U.N.O.
- ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 U.N.O. ON PLAN.
- NAIL BUILD UP STUDS PER DETAIL WF37
- MINIMUM BOLT EMBEDMENT:
 - EMBEDMENT FOR 1/2" ATR
 - EMBEDMENT FOR 5/8" ATR
 - EMBEDMENT FOR 7/8" ATR
- IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
- SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
- SAME NOMINAL SIZE PARALLEL COLUMNS (LBS) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS

COMMON NAIL vs. PNEUMATIC GUN NAILS:

| COMMON NAIL | DIA. / LENGTH | PNEUMATIC GUN NAIL | COMMON vs. GUN NAIL DIA. LENGTH | APPLICATION |
|-------------|-----------------|--------------------|---------------------------------|------------------------------------|
| 8d | 0.131" X 2 1/2" | 0.131" X 2 1/2" | | SEE PLAN RING SHANK ON ROOF |
| 10d OR 12d | 0.148" X 3" | 0.131" X 3" | | SEE PLAN |
| 12d | 0.148" X 3 1/4" | 0.131" X 3 1/4" | | BLOCKING & TOE NAILS & TOP PLATE |
| 10d | 0.148" X 3" | 0.131" X 3" | | 8" O.C. (COMMON) STUD WALL CORNERS |
| 16d | 0.162" X 3 1/2" | 0.131" X 3 1/2" | | 8" O.C. (COMMON) STUD PACK COLUMNS |
| | | | | (2) 16d (COMMON) SEE PLAN |

| HEADER SCHEDULE | | |
|-----------------|---|---|
| MARK | HEADER SIZE | REMARKS |
| H1 | (2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H2 | (2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H3 | (2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H4 | (2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H5 | (2) - 1 3/4" X 11 1/4" LVL 2.0E Fb=2600 PSI | ATTACH TOGETHER W/ (2) ROWS 1 1/4" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE |
| H6 | (2) - 1 3/4" X 9 1/4" LVL 2.0E Fb=2600 PSI | ATTACH TOGETHER W/ (3) ROWS 1 1/4" X 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE |

| HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS | | | | |
|--|------------------------|-------------------------------|---------------|---------------|
| OPENING SIZE | 2x4 WALL JACKS EA. END | 2x6 OR 2x8 WALL KINGS EA. END | JACKS EA. END | KINGS EA. END |
| 1'-0" - 3'-11" | (1) | (2) | (1) | (2) |
| 4'-0" - 9'-11" | (2) | (3) | (2) | (3) |
| 10'-0" - 16'-0" | (3) | (4) | (3) | (4) |


GENERAL HEADER NOTES

- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN
- IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS
- ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF37
- FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 1 1/4" X 3 1/2" LVL 2.0E Fb=2600 PSI
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 1 1/4" X 3 1/2" LVL 2.0E Fb=2600 PSI
- IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

| BEAM SCHEDULE | | |
|---------------|--|---|
| MARK | BEAM SIZE | CONNECTIONS |
| BM1 | (2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM2 | (2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM3 | (2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM4 | (2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM5 | (2) - 1 3/4" x 11 7/8" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM6 | (2) - 1 3/4" x 16" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |

GENERAL BEAM NOTES


- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)
- SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
- BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.



| Y | N | MASTER BA. OPTIONS |
|---|---|--|
| | | 2030 (1) P.C. FIBERGLASS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. DISC. L.T. |
| | | 3'-4" X 4'-0" TEMP. FIXED GLS. WINDOW CNTR. ON TUB |

OPTIONAL MASTER BATH

NOTE: NO DIMENSIONAL CHANGES



FLOOR PLAN

SCALE: 1/4" = 1'-0"

ELEVATION "C"

NOTE:

○ INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

| WALL LEGEND | |
|---------------------------------|--|
| FRAMED WALL | |
| BEARING FRAME WALL | |
| FRAMED WALL W/ BRICK VENEER | |
| FRAMED WALL W/ SIDING OR STUCCO | |

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycombcore steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below on the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length. The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
 M1502.4.5.1 Duct termination. Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
 Option 1: Gypsum:
 1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
 The gypsum board shall be attached w/ Type "W" 1 1/4" drywall screws at 8" O.C. in field and edges.
 Option 2: Plaster Base:
 7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

| AREA CALCULATIONS | |
|-----------------------|-----------|
| 1st FLOOR | 1692 S.F. |
| TOTAL LIVING (AC) | 1692 S.F. |
| GARAGE | 400 S.F. |
| COVERED ENTRY | 151 S.F. |
| COVERED PATIO/LANAI | |
| TOTAL AREA UNDER ROOF | 2243 S.F. |

COUNTY
SEAL

Monday, July 22, 2024

NOTE: INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

FRAMED WALL

BEARING FRAME WALL

FRAMED WALL W/ BRICK VENEER

FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycombcore steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below on the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length. The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
 M1502.4.5.1 Duct termination. Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
 Option 1: Gypsum:
 1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
 The gypsum board shall be attached w/ Type "W" 1 1/4" drywall screws at 8" O.C. in field and edges.
 Option 2: Plaster Base:
 7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

1st FLOOR 1692 S.F.

TOTAL LIVING (AC) 1692 S.F.

GARAGE 400 S.F.

COVERED ENTRY 151 S.F.

COVERED PATIO/LANAI

TOTAL AREA UNDER ROOF 2243 S.F.

INVENTORY

LOT: 143

BLK: SEC:

SUB: Preserve of Laurel Lake

S.W. Rosemary Dr. Lake City

Model Name / Number:

1755

Plan Issue Date:

Monday, July 22, 2024


KA PROJECT NUMBER:

24-08049

Sheet: 2


OR

FLOOR PLAN




FM01 SINGLE STORY FTG

1/2" = 1'-0"




FM03 THICKENED EDGE

1/2" = 1'-0"




FM09 SECTION @ GAR. DOOR

1/2" = 1'-0"




FM11 STEP DOWN BRG.

1/2" = 1'-0"



FM14 SECTION @ RECESS SHOWER

1/2" = 1'-0"



FM19 TYP. CORNER BAR DETAIL

1-1/2" = 1'-0"

| STEMWALL SCHEDULE | | | | | |
|----------------------|-------------------|-----------|-----------|-----------|--|
| STEMWALL HEIGHT (ft) | FOOTING DIMENSION | | | | NUMBER/SIZE OF BARS |
| | d 1 STORY | d 2 STORY | b 1 STORY | b 2 STORY | |
| 0'-0" - 2'-0" | 8" | 10" | 16" | 20" | W/ (2) #5 BARS |
| 2'-0" - 3'-4" | 10" | 10" | 20" | 24" | W/ (3) #5 BARS |
| 3'-4" - 4'-0" | 12" | 12" | 32" | 32" | W/ (4) #5 BARS |
| 4'-0" - 5'-4" | 16" | 16" | 48" | 48" | W/ (5) #5 BARS CONT. & #5 @ 18" O.C. TRANSV. |

NOTES:

- VERTICAL REIN. IN SOLID GROUTED CELLS AT ALL CORNERS, JAMBS, WALL INTERSECTIONS, BELOW GIRDER TRUSS LOCATIONS, AND AT THE MAXIMUM SPACING STATED IN SCHEDULE
- W.W.M. IS REQUIRED TO MAKE ADEQUATE CONNECTION BETWEEN SLAB AND WALL WHEN STEM WALL EXCEEDS 4'-0" FIBERMESH CAN NOT BE USED AND #4 TURN BARS ARE REQUIRED @ EACH FILLED CELL LOCATION. EACH BAR TO TIE INTO VERTICAL BAR AND EXTEND OUT A MIN. 4'-0" INTO SLAB/STEM
- IF STEM IS REQ'D TO BE HIGHER CONTACT ENGINEER OF RECORD PRIOR TO CONSTRUCTION FOR MORE INFORMATION
- G.C. TO PROVIDE ADEQUATE BRACING OF STEM WALL WHEN UNEVEN BACK FILLING IS TAKING PLACE
- #5 HORIZONTAL CORNER BARS WITH 4'-0" LEGS IN KNOCKOUT BLOCK @ 16" O.C. VERTICAL. GROUTED SOLID WHEN STEM WALL IS GREATER THAN 4'-0" TALL (TYPICAL ALL CORNERS)
- IF STEMWALL IS WITH IN 5'-0" OF POOL OR WATER FEATURE FOUNDATIONS TO BE A MINIMUM 12" BELOW BOTTOM OF POOL OR WATER FEATURE.
- ALL STEM WALLS GREATER THAN (4) COURSES SHALL BE FULLY GROUTED.
- R.403.1.4 MINIMUM DEPTH: ALL EXTERIOR FOOTINGS (BOTTOM) SHALL BE PLACED AT LEAST 12" BELOW THE UNDISTURBED GROUND SURFACE.

FMASW ALTERNATE STEM WALL FOOTING SCHEDULE

1/2" = 1'-0"



FM02 SECTION @ GARAGE

1/2" = 1'-0"



FM08 2-STORY FTG.

1/2" = 1'-0"

FM26 THICKENED EDGE W/ BRICK

1/2" = 1'-0"

FM25 PORCH COLUMN W/ BRICK

1/2" = 1'-0"

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE


SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE


SEE FLOOR FOR BASE CONNECTION

FM25 COMMON BLOCK COL. SEE FLOOR PLAN FOR SIZE

SEE FLOOR FOR BASE CONNECTION



RIGHT ELEVATION "C"
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION "C"
SCALE: 1/4" = 1'-0"



REAR ELEVATION "C"
SCALE: 1/4" = 1'-0"



FRONT ELEVATION "C"
SCALE: 1/4" = 1'-0"

| VENTILATION CALCULATION | |
|---|-----------------------|
| Formula = SF / 300 / 2 * 144 = net sq inches of venting needed equally for intake and exhaust | |
| Soffit product provides | 4.12 net sq in / sf |
| Ridge vent provides | 18.00 net sq in / lf |
| Off ridge vent provides | 138.00 net sq in / sf |
| Overhang distance | 2.00 ft |
| S.F. of Area to be vented (SF) | 2343 s.f. |
| Total needed for exhaust for upper 1/3 | 562 net sq inches |
| Total needed for intake (soffit area, lower) | 562 net sq inches |
| Number of Off Ridge Vents for upper 1/3 needed | 4 |
| L.F. of Ridge Vent needed (can be used in combo with ORV) | 31 |
| Lineal Feet of Soffit needed to meet required | 68 |
| Lineal S.F. provided by plan | 212 |

COUNTY
SEAL

Monday, July 22, 2024

To the best of the Engineer's knowledge, information, and belief, the design and construction of the project complies with the current Florida Building Code, Engineering Law, and applicable rules and regulations of the State of Florida. The Engineer is not responsible for the construction of the project.

FDSE
ENGINEERING DESIGN SERVICES, INC.
2888 S. GULF BLVD., SUITE 200
FORT MYERS, FL 33901
P: (888) 880-1234
F: (888) 880-1235
www.fdsedesign.com

☐ CARL A. BROWN, P.E. FL # 55126
☐ SCOTT A. LEWOWSKI, PE FL # 78750
☐ THIEN BAO DUONG, PE FL # 94452

keese
associates
ARCHITECTURE | DESIGN
2300 W. Lake Mallard, FL 32751, Suite 200
P: (888) 880-1234
F: (888) 880-1235
www.keese.com

AA2600319
AIA
BD
in
f
e
p

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 143
BLK:
SEC:
SUB: Preserve of Laurel Lake
S.W. Rosemary Dr.
Lake City

Model Name / Number:

1755

Plan Issue Date:

Monday, July 22, 2024

KA PROJECT NUMBER:


24-08049

Sheet:

5

OR:

ELEVATIONS



NOTE:

FOR FIRST (4) BAYS

1) SEE TRUSS MANUFACTURER'S TRUSS ENGINEERING CUT SHEETS FOR ADDITIONAL PERMANENT BRACING THAT MAY BE REQUIRED

2) "T" BRACING MAY BE USED IN PLACE OF PERMANENT BRACING PROVIDED IT EXTENDS OVER AT LEAST 90% OF THE WEB.

TB05 REQUIRED MINIMUM PERMANENT TRUSS BRACING PLAN

NIS

RSH

ENGINEERED ROOF PER ASCE 7-22 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft

WIND SPEED (ULTIMATE) 130 MPH

WIND SPEED (ALLOWABLE) 101 MPH

EXPOSURE CATEGORY B

EFFECTIVE WIND AREA (SQ FEET)

WIND PRESSURE AND SUCTION (PSF)

(-) VALUE DENOTES SUCTION

AREA ROOF 1 2 3

10 HIP -22.94 -31.68 -31.68

GABLE -24.44 -38.92 -46.25

ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):

ZONE 1: ASTM F1667 RSR5-01 (8d) NAILS @ 6" O.C. ON EDGE & 6" O.C. IN FIELD

ZONE 2: ASTM F1667 RSR5-01 (8d) NAILS @ 4" O.C. ON EDGE & 4" O.C. IN FIELD

ZONE 3: ASTM F1667 RSR5-01 (8d) NAILS @ 4" O.C. ON EDGE & 4" O.C. IN FIELD

ROOF SHEATHING:

SHINGLE: 7/16" EXP. 1 (3/16) or 15/32" EXP. 1 (3/16)

TILE: 15/32" EXP. 1 (3/16)

NOTE:

1. PER CODE ASTM F1667 RSR5-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS

2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 15/32", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSR5-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSR5-04 (3" x .120") NAILS

3. GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.


HIP ROOF >20 TO 27 DEG.
w=4ft [4-12]-[6-12]

GABLE ROOF >20 TO 27 DEG.
[4-12]-[6-12]


WALL SHEATHING MAY BE INSTALLED VERTICALLY OR HORIZONTALLY. ATTACH PER NAILING SCHEDULE. PANEL EDGES WILL NEED TO BE ATTACHED TO STUD AND OR BLOCKING AT ALL EDGES. A MINIMUM 1/2" SPACE IS RECOMMENDED BETWEEN PANELS AT EDGES AND END JOINTS TO ALLOW FOR EXPANSION. FASTENERS SHALL NOT PENETRATE SURFACE MORE THAN 1/4".

- (A) NAIL AT BASE 2 ROWS @ 4" O.C. w/ 8d COMMON NAIL.
 (B) NAIL AT TOP PLATE TWO ROWS @ 4" O.C. w/ 8d COMMON NAIL.
 (C) NAIL OPENING PERIMETER w/ (2) ROWS @ 4" O.C. w/ 8d COMMON NAIL.
 (D) NAIL INTERIOR AT 6" O.C. w/ 8d COMMON NAIL.
 (E) STAGGER ALL VERTICAL JOINTS & NAIL @ 4" O.C. w/ 8d COMMON NAIL.
 (F) PLYWOOD SPLICES @ HEADER - NAIL SHEATHING TO HEADER w/ 8d COMMON NAILS @ 6" O.C. (2) ROWS @ TOP & BOTTOM.
 (G) 8d NAILS @ 3" O.C. TO EACH TRUSS END OR @ VERTICAL MEMBER IF GABLE END.
 (H) FLOOR SHEATHING w/ PLYWOOD DECKING GLUED AN NAILED w/ 8d COMMON NAILS AT 6" O.C. AT EDGES OVERDRIVE NAILS. FASTENERS SHALL NOT PENETRATE SURFACE MORE THAN 1/8".

NOTE: 8d NAILS FOR WALL SHEATHING MUST BE MIN. 131" x 2 1/2". DO NOT OVERDRIVE NAILS. FASTENERS SHALL NOT PENETRATE SURFACE MORE THAN 1/4".



TB13 WALL SHEATHING INSTALLATION AND NAILING SCHEDULES



ROOF CRITERIA
 -24" OVERHANG @ EAVES U.N.O.
 -12" OVERHANG @ GABLES U.N.O.
 -SQUARE CUT FASCIA
 -ROOF PITCH PER ELEVATION
 -SHINGLE LOADING

ROOF PLAN "C"
 N.T.S.

| SIMPSON - CONNECTOR SCHEDULE | | | | | | USP - CONNECTOR SCHEDULE | | | | | |
|------------------------------|------------------|--|--------|--------|--|--------------------------|------------------|---|--------|--------|--|
| MARK | TYPE | CONNECTOR & FASTENERS | SPF | SYP | | MARK | TYPE | CONNECTOR & FASTENERS | SPF | SYP | |
| (A) | FRAME TO MASONRY | HETAB w/ (8) 10d x 1 1/2" OR HTB20 w/ (8) 10d x 1 1/2" | 1810 | | | (A) | FRAME TO MASONRY | HTAB w/ (8) 10d x 1 1/2" OR HTB20 w/ (8) 10d x 1 1/2" | 1585 | 1870 | |
| (B) | FRAME TO FRAME | H2 5A w/ (10d) NAILS | 615 | 700 | | (B) | FRAME TO FRAME | RTBA w/ (10d) NAILS | 515 | 585 | |
| (C) | FRAME TO FRAME | HT5A w/ (17) 10d x 1 1/2" | 1015 | 1040 | | (C) | FRAME TO FRAME | RT16A w/ (17) 10d x 1 1/2" | 895 | 1000 | |
| (D) | FRAME TO FRAME | H2A-2 w/ (8) 10d x 1 1/2" AT 2 PLY TRUSSES LOCATION INCLUDE (3) 12d TOENAILS | 930 | 1680 | | (D) | FRAME TO FRAME | RT16-2 w/ (8) 10d x 1 1/2" AT 2 PLY TRUSSES LOCATION INCLUDE (3) 12d TOENAILS | 935 | 1090 | |
| (E) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY LOCATION INCLUDE (3) 12d TOENAILS | 3330 | 3965 | | (E) | FRAME TO MASONRY | MUOT15 w/ (2) 10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY LOCATION INCLUDE (3) 12d TOENAILS | 3330 | 4495 | |
| (F) | FRAME TO FRAME | HT520 w/ (2) 10d x 1 1/2" AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS | 1215 | 1415 | | (F) | FRAME TO FRAME | HTW20 w/ (2) 10d x 1 1/2" AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS | 1285 | 1530 | |
| (G) | FRAME TO FRAME | (2) HT520 w/ (4) 10d x 1 1/2" AT EXTERIOR LOCATION INCLUDE (6) 12d TOENAILS | 2430 | 2830 | | (G) | FRAME TO FRAME | (2) HTW20 w/ (4) 10d x 1 1/2" AT EXTERIOR LOCATION INCLUDE (6) 12d TOENAILS | 2570 | 3090 | |
| (H) | FRAME TO MASONRY | H21 w/ (2) 10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY (HASTS FOR S.P.F.) | 10800 | | | (H) | FRAME TO MASONRY | HUG20 w/ (2) 10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY (HASTS FOR S.P.F.) | 7020 | 9700 | |
| (I) | FRAME TO MASONRY | FGTR w/ (8) 1/4" x 3" S2S WOOD SCREWS AND (2) 1/2" x 5" TITEN HD ANCHOR BOLTS | 3400 | 4725 | | (I) | FRAME TO MASONRY | RFUS w/ (2) W83 WOOD SCREWS AND (4) 3/4" x 6" WEDGE-BOLT | 7190 | | |
| (J) | FRAME TO MASONRY | (1) LGT 2" x (16) 18d SINKERS & (7) 1/4" x 3" S2S WOOD SCREWS (SEE NOTE #5 BELOW) | 1755 | 2040 | | (J) | FRAME TO MASONRY | (1) LGT 2" x (16) 18d SINKERS & (7) 1/4" x 3" S2S WOOD SCREWS (SEE NOTE #5 BELOW) | 1755 | 2040 | |
| (K) | FRAME TO MASONRY | (2) LGT 3" w/ (2) 10d SINKERS & (14) 1/4" x 2 1/4" TITEN (2 PLY TRUSS) OR (2) 10d SINKERS FOR FRAME (EA) | 3500-M | 4060-M | | (K) | FRAME TO MASONRY | (2) LGT 3" w/ (2) 10d SINKERS & (14) 1/4" x 2 1/4" TITEN (2 PLY TRUSS) OR (2) 10d SINKERS FOR FRAME (EA) | 3300-M | 3800-M | |
| (L) | FRAME TO MASONRY | (2) LGT 3" w/ (2) 1/4" x 3" S2S SCREWS & (8) 3/8" x 7" TITEN (2 PLY TRUSS) OR (2) 10d SINKERS FOR FRAME (EA) | 4730-M | 6570-M | | (L) | FRAME TO MASONRY | (2) LGT 3" w/ (2) 1/4" x 3" S2S SCREWS & (8) 3/8" x 7" TITEN (2 PLY TRUSS) OR (2) 10d SINKERS FOR FRAME (EA) | 6480-M | 7500-M | |
| (M) | BEAM TO BEAM | HU410 OPT HUC410 w/ (16) 16d & (10) 10d NAILS | | | | (M) | BEAM TO BEAM | HU410 OPT HUC410 w/ (16) 16d & (10) 10d NAILS | | | |
| (N) | BEAM TO MASONRY | HU10 OPT HUC10 w/ (16) 16d & (10) 10d NAILS | | | | (N) | BEAM TO MASONRY | HU10 OPT HUC10 w/ (16) 16d & (10) 10d NAILS | | | |
| (O) | BEAM TO MASONRY | HU45 OPT HUC45 w/ (16) 16d & (10) 10d NAILS | | | | (O) | BEAM TO MASONRY | HU45 OPT HUC45 w/ (16) 16d & (10) 10d NAILS | | | |
| (P) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | | (P) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | |
| (Q) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | | (Q) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | |
| (R) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | | (R) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | |
| (S) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | | (S) | FRAME TO MASONRY | HT5 w/ (2) 10d NAILS AND (1) 5/8" A.T.R. EPOKED w/ SIMPSON "SET" (SEE NOTE #4 & #5 BELOW) | 4375 | 5090 | |
| (T) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (T) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (U) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (U) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (V) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (V) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (W) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (W) | FRAME TO MASONRY | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (X) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (X) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (Y) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (Y) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |
| (Z) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 785 | 910 | | (Z) | FRAME TO FRAME | H25 w/ (2) 10d x 1 1/2" NAILS | 875 | 1045 | |

ROOF FRAMING NOTES

1. SHINGLE OR METAL ROOFING SYSTEM (SEE ARCH.) SHEATHING - SEE [RSH] SCHEDULE THIS SHIT. FOR SHIT G & FASTENERS ON PRE-ENGINEERED WOOD TRUSSES AT 2'-0" O.C. MAX. OR CONVENTIONAL FRAME ROOF (SEE PLAN FOR SIZE AND SPACING. SEE ARCHITECTURAL PLAN FOR TYPICAL ROOF SLOPE AND OTHER INFORMATION.
 2. THE EXTERIOR CEILING FOR THE ENTRIES AND PORCHES SHALL HAVE EITHER 7/16" OSB EXPOSURE 1 SHEATHING OR 1/2" DENSGLASS TO THE UNDERSIDE OF THE ROOF TRUSSES. ALL PANEL EDGES ARE TO BE BLOCKED SOLID WITH 2x4 #2 SYP WITH (3) 10d TOENAILS EACH END. THE SHEATHING IS TO BE NAILED WITH 8d NAILS AT 4" ON CENTER AT ALL EDGES AND THEN 8" ON CENTER IN FIELD.
 3. FOR UNDERLAYMENT REQUIREMENTS SEE R905.1.1.1

--- NOTE TO FRAMER ---

IF ROOF TRUSS LAYOUT SHOWS TRUSS ID S, THIS LAYOUT HAS BEEN PROVIDED BY THE CLIENT/ DESIGNER OR ARCHITECT TO USE FOR THE DESIGN OF THIS PROJECT. OTHERWISE A GENERIC LAYOUT HAS BEEN DETERMINED. BUT PRIOR TO CONSTRUCTION OF TRUSS FABRICATION, FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS ARE TO BE SUBMITTED TO ENGINEER OF RECORD (E.O.R.) FOR REVIEW AND APPROVAL. AT THIS TIME THE E.O.R. RESERVES THE RIGHT TO REVISE THE PLAN AS REQUIRED PER THE REVIEW OF THE FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS. ADDITIONAL FEE'S MAY APPLY. STARTING CONSTRUCTION OR TRUSS FABRICATION PRIOR TO THIS REVIEW IS NOT ADVISED. AND THE E.O.R. IS NOT RESPONSIBLE FOR ADDITIONAL COSTS DUE TO REVISIONS OF THE PLAN. IF CONVENTIONAL FRAMING IS SHOWN, NO TRUSS APPROVAL IS REQUIRED, UNLESS LAYOUT IS REVISED W/OUT WRITTEN APPROVAL FROM FDS.

SEE PLAN SET FOR TRUSS BRACING AND ADDITIONAL ROOF INFORMATION

COUNTY SEAL

Monday, July 22, 2024

FDS ENGINEERS & ARCHITECTS

2200 W. 80th Ave., Suite 200
 Fort Lauderdale, FL 33309
 Phone: (954) 337-0000
 Fax: (954) 337-0001
 Email: info@fdes.com

www.fdes.com

keese associates

ARCHITECTURE DESIGN I

2200 W. 80th Ave., Suite 200
 Fort Lauderdale, FL 33309
 Phone: (954) 337-0000
 Fax: (954) 337-0001
 Email: info@keese.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330148

100 WEST GARDEN STREET
 PENSACOLA FL 32502

DIVISION LOCATION:

GAINESVILLE

Job Information:

Model Name / Number:

1755

Plan Issue Date:

Monday, July 22, 2024

KA PROJECT NUMBER:


24-08049

Sheet: **S-1** Of:


INVENTORY

LOT: 143
 BLK:
 SEC:
 SUB: Preserve of Laurel Lake


S.W. Rosemary Dr.
 Lake City



WF39 TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



WF09 WALL HEADER DETAIL N.T.S.



WF67 WALL FRAMING 3/4" = 1'-0"

COUNTY SEAL

Monday, July 22, 2024

To the best of the Engineer's knowledge, information, and belief, the design and construction of the above project complies with the applicable building codes and regulations of the State of Florida, and the design and construction of the project is in accordance with the current Florida Building Code. The Engineer is not responsible for the construction of the project or for the safety of the project.

FDS ENGINEERS

ARCHITECTURE | DESIGN | CONSTRUCTION

2550 South US Highway 1, Suite 200
Tampa, FL 33629
Tel: 813.281.1234
Fax: 813.281.1235
www.fdsengineers.com

Carl A. Brown, P.E.
Scott A. Lemkowski, P.E.
Thien Bao Duong, P.E.

FL # 56126
FL # 78750
FL # 94452

AD

keese associates
ARCHITECTURE | DESIGN | CONSTRUCTION

2550 South US Highway 1, Suite 200
Tampa, FL 33629
Tel: 813.281.1234
Fax: 813.281.1235
www.keese.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 143
BLK:
SEC:
SUB: Preserve of Laurel Lake
S.W. Rosemary Dr.
Lake City












Model Name / Number:
1755

Plan Issue Date:
Monday, July 22, 2024

KA PROJECT NUMBER:
24-08049

Sheet: **S-2.1** Of:

TYPICAL FRAMING DETAILS



COUNTY
SEAL

Monday, July 22, 2024

keese
associates
ARCHITECTURE DESIGN
2207 S. GULF BLVD., SUITE 200
GAINESVILLE, FL 32609
352.380.2335
www.keese.com

FDS
ENGINEERING ASSOCIATES
2207 S. GULF BLVD., SUITE 200
GAINESVILLE, FL 32609
352.380.2335
www.fdseng.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

Model Name / Number:
1755


Plan Issue Date:
Monday, July 22, 2024

KA PROJECT NUMBER:
24-08049


Sheet:
S-3

Of:
1

TYPICAL WALL DETAILS




TB01 TYPICAL CROSS BRACING DETAIL N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL N.T.S.

THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




CH01 TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"


| RAFTER SIZE | |
|----------------|----------------------------------|
| 0'-8" SPAN - | 2"x6" W/4-12d EACH END |
| 8'-12" SPAN - | 2"x8" W/4-12d EACH END |
| 12'-15" SPAN - | 2"x10" W/ SIMPSON A 34 @ EA. END |
| 15'-18" SPAN - | 2"x12" W/ SIMPSON A 34 @ EA. END |




TB17 CONV. FRAMING & VALLEY FRAMING N.T.S.




TB03 HIP / RIDGE BLOCKING DETAIL N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.






GE04 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"



WF05 DORMER FRAMING DETAIL N.T.S.

TRUSS NOTES:

- WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUNDLES OF SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS GRAVEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
- ALL BRACING (DB, CB, SB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUF. SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
- ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
- ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
- PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS.



TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL

A-A ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING

TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"

COUNTY SEAL

To the best of the Engineer's knowledge, information, and belief, the structure shown herein complies with the applicable provisions of the Florida Building Code, and the design and construction of the structure is in accordance with the applicable provisions of the Florida Building Code. The Engineer is not responsible for the adequacy of the design or construction of the structure.

FDSE
ENGINEERING ASSOCIATES
ARCHITECTURE | DESIGN | INTERIORS
2540 West Garden Street, Suite 200
Pensacola, FL 32503
904.331.2344
www.fdsedesign.com

AAE/COBLE
SCOTT A. LEWOWSKI, P.E.
Certificate of Authorization No. 9301
FL # 86126
FL # 78750
THIEN BAO DUONG, P.E.
FL # 91452

Keese
associates
ARCHITECTURE | DESIGN | INTERIORS
2540 West Garden Street, Suite 200
Pensacola, FL 32503
904.331.2344
www.fdsedesign.com

AAE/COBLE
SCOTT A. LEWOWSKI, P.E.
Certificate of Authorization No. 9301
FL # 86126
FL # 78750
THIEN BAO DUONG, P.E.
FL # 91452

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY
LOT: 143
BLK:
SEC:
SUB:
S.W. Rosemary Dr.
Lake City


Model Name / Number:
1755

Plan Issue Date:
Monday, July 22, 2024


KA PROJECT NUMBER:
24-08049

Sheet: **S-4** Of:


ROOF FRAMING AND BRACING DETAILS




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.





GE21 SECTION @ DUTCH GABLE 3/4" = 1'-0"



LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.



GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4" = 1'-0"

COUNTY
SEAL

To the best of the Engineer's knowledge, information, and belief, the design complies with all applicable codes, regulations, and standards, and the Engineer is not providing any warranty or guarantee of performance or results. The Engineer's design is based on the information provided by the client and is not to be used for any other purpose without the Engineer's written consent.

FDS ENGINEERING ASSOCIATES
ARCHITECTURE DESIGN
22407 SEB 23535
Gainesville, FL 32609
www.fdseng.com

Professional Engineer
No. 1251
State of Florida
Expiring 12/31/2024

Carl A. Brown, P.E.
Scott A. Lewkowski, P.E.
Then Bao Clong, P.E.

FL # 89326
FL # 78750
FL # 94452

keese associates
ARCHITECTURE DESIGN
22407 SEB 23535
Gainesville, FL 32609
www.keese.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

Model Name / Number:
1755

Plan Issue Date:
Monday, July 22, 2024


KA PROJECT NUMBER:
24-08049

Sheet:
S-4.1

Of:
ROOF FRAMING AND BRACING DETAILS

INVENTORY
LOT: 143
BLK:
SEC:
SUB: Preserve of Laurel Lake
S.W. Rosemary Dr.
Lake City

Monday, July 22, 2024




HEAD FLASHING TIE-IN INSTRUCTIONS:

1. Cut, fold up & temporarily secure weather resistive barrier above header to allow for flashing installation
2. Self-adhered flashing plus head flashing under weather resistive barrier
3. Fold weather resistive barrier back over head flashing and seal with tape

SELF-ADHERED FLASHING
FLASHING INSTALLATION AFTER WEATHER RESISTIVE BARRIER


Scale: NTS

WP01




SELF-ADHERED FLASHING
HALF ROUND WINDOW

WP04



SELF-ADHERED FLASHING
W0.8362x;DECK JOIST


WP07



- NOTES:
1. INSTALL WINDOW PER MANUFACTURER'S RECOMMENDATION AND USE APPROPRIATE SEALANT FOR WINDOW AND WOOD BUCK
 2. WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.


RECESSED WINDOW

WP10




SELF-ADHERED FLASHING
EXTERIOR DOOR WITH DECK - SECTION A

WP02




SELF-ADHERED FLASHING
EXTERIOR DOOR WITH DECK

WP05



SELF-ADHERED FLASHING
OUTSIDE CORNER


WP08



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
 2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.


WALL-TO-WALL OUTSIDE CORNER

WP11




TIE-IN WITH VINYL SIDING
AT WINDOW SILL

WP03



SELF-ADHERED FLASHING
INSIDE CORNER

WP06



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
 2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL INSIDE CORNER

WP12

THESE DETAILS ARE GENERIC AND MEANT TO SHOW
GENERAL FLASHING AND WATERPROOFING METHODS
TO BE USED.

SELF-ADHERED FLASHING PRODUCTS DETAILS

TWO LAYERS OF FELT OR ONE LAYER OF HOUSE WRAP AND
ONE LAYER OF FELT ARE REQUIRED BEHIND STUCCO. FBC R703.2

DETAIL INSTRUCTIONS

REFER TO THE NUMBER MARKED AS (#) IN EACH DETAIL THAT
CORRESPONDS TO THE NUMBERED ITEMS IN THE LIST OF
INSTRUCTIONS BELOW:

1. INSTALL SELF-ADHERED FLASHING IN ORDER AS SHOWN BY NUMBERS.
2. INSTALL FLASHING AND WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.
3. SELF-ADHERED FLASHING CAN BE SUBSTITUTED FOR BUILDING PAPER.
4. SPLIT THE RELEASE PAPER USING THE RIPCORD (SPLIT RELEASE ON DEMAND, EMBEDDED IN THE ADHESIVE LAYER) - FOR EASE OF INSTALLATION AND TO MINIMIZE SCORING CUTS.
5. REMOVE ALL RELEASE PAPER PER STANDARD INSTALLATION INSTRUCTIONS AND ADHERE TO SUBSTRATE USING A SQUARE PIECE OF FLASHING MATERIAL (6" X 6" MINIMUM).
6. FOLD AS SHOWN BY ARROWS.
7. ANGLE OF CORNER MAY VARY, ADJUST FOLDING OF THE FLASHING ACCORDINGLY TO FIT TIGHT TO CORNER.
8. MECHANICALLY FASTEN AS NECESSARY.

FLASHING REQUIREMENTS

R703.1 GENERAL. EXTERIOR WALLS SHALL PROVIDE THE BUILDING WITH A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. THE EXTERIOR WALL ENVELOPE SHALL INCLUDE FLASHING AS DESCRIBED IN SECTION R703.4. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL, BEHIND AN EXTERIOR WALL COVERING THAT IS INTENDED TO RESIST LIQUID WATER THAT HAS PENETRATED BEHIND THE EXTERIOR COVERING FROM FURTHER INTRUDING INTO THE EXTERIOR WALL ASSEMBLY. AN EXTERIOR WALL COVERING IS DESCRIBED AS A MATERIAL OR ASSEMBLY OF MATERIALS APPLIED ON THE EXTERIOR SIDE OF EXTERIOR WALLS FOR THE PURPOSE OF PROVIDING A WEATHER-RESISTIVE BARRIER, INSULATION, OR FOR AESTHETICS, INCLUDING BUT NOT LIMITED TO, VENEERS, SIDING, EXTERIOR INSULATION AND FINISH SYSTEMS, ARCHITECTURAL TRIM AND EMBELLISHMENTS SUCH AS CORNICES, SOFFITS, AND FASCIA.

R703.2 WATER-RESISTIVE BARRIER. ONE LAYER OF NO. 15 ASPHALT FELT, FREE FROM HOLES AND BREAKS, COMPLYING WITH ASTM D2285 FOR TYPE I FELT OR OTHER APPROVED WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51 MM) WHERE JOINTS OCCUR. FELT SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 MM). THE FELT OR OTHER APPROVED MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1.

R703.7.3 WATER-RESISTIVE BARRIERS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.

EXCEPTION: WHERE THE WATER-RESISTIVE BARRIER THAT IS APPLIED OVER WOOD-BASED SHEATHING HAS A WATER RESISTANCE EQUAL TO OR GREATER THAN THAT OF 60-MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING, SUBSTANTIALLY NONWATER-ABSORBING LAYER OR DESIGNED DRAINAGE SPACE.

R703.4 FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SHINGLE-FASHION IN A MANNER TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED MEMBRANES USED AS FLASHING SHALL COMPLY WITH AAMA 711. ALL EXTERIOR PENETRATION PRODUCTS SHALL BE SEALED AT THE JUNCTURE WITH THE BUILDING WALL WITH A SEALANT COMPLYING WITH AAMA 800 OR ASTA C930 CLASS 25 GRADE NS OR GREATER FOR PROPER JOINT EXPANSION AND CONTRACTION. ASTM C1281, AAMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE TYPE OF SEALANT. FLUID-APPLIED MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH AAMA 714. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED CORROSION-RESISTANT FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS:

1. EXTERIOR WINDOW AND DOOR OPENINGS. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER-RESISTIVE BARRIER COMPLYING WITH SECTION 703.2 FOR SUBSEQUENT DRAINAGE. MECHANICALLY ATTACHED FLEXIBLE FLASHINGS SHALL COMPLY WITH AAMA 712. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL BE INSTALLED IN ACCORDANCE WITH ONE OR MORE OF THE FOLLOWING:
 - 1.1 THE PENETRATION MANUFACTURER'S INSTALLATION AND FLASHING INSTRUCTIONS, OR FOR APPLICATIONS NOT ADDRESSED IN THE PENETRATION MANUFACTURER'S INSTRUCTIONS, IN ACCORDANCE WITH THE FLASHING MANUFACTURER'S INSTRUCTIONS, WHERE FLASHING INSTRUCTIONS OR DETAILS ARE NOT PROVIDED. PAN FLASHING SHALL BE INSTALLED AT THE SILL OF EXTERIOR WINDOW AND DOOR OPENINGS. PAN FLASHING SHALL BE SEALED OR SLOPED IN SUCH A MANNER AS TO DIRECT WATER TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE. OPENINGS USING PAN FLASHING SHALL INCORPORATE FLASHING OR PROTECTION AT THE HEAD AND SIDES.
 - 1.2. IN ACCORDANCE WITH THE FLASHING DESIGN OR METHOD OF A REGISTERED DESIGN PROFESSIONAL.
 - 1.3. IN ACCORDANCE WITH OTHER APPROVED METHODS.
 - 1.4. IN ACCORDANCE WITH FMA/AAMA 100, FMA/AAMA 200, FMA/WDMA 250, FMA/AAMA/WDMA 300 OR FMA/AAMA/WDMA 400.
2. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTING LIPS ON BOTH SIDES UNDER STUCCO CORNICES.
3. UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS.
4. CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM.
5. WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION.
6. AT WALL AND ROOF INTERSECTIONS.
7. AT BUILT-IN GUTTERS.

FIGURE 1: FLASHING INSTALLATION

ASPHALT SEALANT:
EXTEND MIN. OF 6"
OUTSIDE OF FLASHING






FIGURE 2: WALL FINISH



FLASHING INSTALLATION
WHERE ROOF MEETS VERTICAL WALL

FIGURE 3: CORNER DETAIL



FLASHING DETAIL AT CRICKET
/ KNEEWALL INTERSECTION

www.fdseng.com

FDS
ENGINEERING ASSOCIATES

225 South Main Street, Suite 200
Tallahassee, Florida 32301
Phone: 904.225.1200
Fax: 904.225.1201
Email: info@fdseng.com

Professional Engineer
License No. 12345
Professional Engineer
License No. 12345

Carl A. Brown, P.E.
Scott A. Lebowitz, P.E.
Then Bao Duong, P.E.

Monday, July 22, 2024

keesee
associates
ARCHITECTURE | DESIGN |

225 South Main Street, Suite 200
Tallahassee, Florida 32301
Phone: 904.225.1200
Fax: 904.225.1201
Email: info@keesee.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 143
BLK:
SEC:
SUB: Preserve of Laurel Lake
S.W. Rosemary Dr.
Lake City

Model Name / Number:
1755

Plan Issue Date:
Monday, July 22, 2024

KA PROJECT NUMBER:
24-08049

Sheet: **WP** Of:
WATER PROOF
DETAILS