

# Lake Apts Scope of Work

Technicians to abandon old water lines going to each apt due to galvanized build up and poor water flow.

They will run a new main water line feed across the porch ceiling in front of the units and then run lines off of the main into the individual units and connect to the bathroom and kitchen plumbing. New shower valves will be installed if needed. Lines will be strapped and insulated as per plumbing code with UV rated insulation.

Work should take 2 weeks. |