


Gill Engineering Services, Inc.

P/O. BOX 1420 ~LIVE OAK, FLORIDA ~ 32066 ~ 386.590.1242



4/3/2023

Columbia County Building Department  
Building and Zoning  
Lake City, FL

**SUBJECT: Mike Morrison Residence  
Roof Plan**

To Whom It May Concern,

The following field changes for the abovementioned project have been approved,

- Stick frame the roof with 2X8 SYP rafters on 24 in. centers.
- The top of the rafters connected to the ridge board with Simpson SDWS screws.
- Simpson LTS12 twist connections - top of rafters to ridge board.

All new construction shall meet the requirements of the 2020 Florida Building Code (7<sup>th</sup> Edition)

Thank you,

Gary Gill, PE 51942

Gary Gill

2023.04.03 12:36:45 -04'00'

2023.001.20093



*Gill*  
Engineering Services, Inc.