

juris luzins  
architect

pllc

AR 0007907

Chief Building Official  
Columbia County, FL

30 May, 2024

Fire Damage and Termite Repairs  
314 SW Old Bellamy Rd.

- A – Install 2 Simpson LSTA 24 or equal at intersection of top plates
- B - Install Simpson SP1 @ header ea. side of opening or LSTA 24
- C – Continuous load path LSTA24 ea. side. Tie studs together across header
- D – Strap top plates and header to king studs w/ Simpson LSTA24 to create continuous Load path from rafters to footing
- E – Install Simpson HD3B or equal ea. side of openings at bottom plate to provide Continuous load path from roof to foundation 4 holdowns required  
1/2" x 6" lags into studs  
1/2" x 6" Titan concrete screws into slab

Ensure that each rafter is anchored to the wall with Simpson H2.5A or equal  
All sheathing to be fastened w/ 8d nails @6" oc @ edges and 12" oc in the field  
2"x4" blocking @ any sheathing joints and @ 8' max spacing  
Ensure all headers have Simpson LSTA at top of wall each side of window openings

Respectfully Submitted,



Juris  
Luzins

Digitally signed  
by Juris Luzins  
Date:  
2024.05.31  
10:57:40 -04'00'

9320 nw 13<sup>th</sup> place • gainesville, fl • 32606  
352-224-8673 • luzinsarchitects@yahoo.com