

DATE 12/05/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023927

APPLICANT HAROLD FRANKEL PHONE 752-9592
ADDRESS 1703 SW SISTERS WELCOME RD LAKE CITY FL 32025
OWNER HAROLD FRANKEL PHONE 752-9592
ADDRESS 1703 SW SISTERS WELCOME LAKE CITY FL 32025
CONTRACTOR OWNER PHONE
LOCATION OF PROPERTY 341 ON THE LEFT CORNER OF BUSINESS POINTE AND 341

TYPE DEVELOPMENT HANGAR ESTIMATED COST OF CONSTRUCTION 44000.00
HEATED FLOOR AREA TOTAL AREA 2880.00 HEIGHT 24.00 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 4/12 FLOOR SLAB
LAND USE & ZONING RMF-1 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 1 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 13-4S-16-02952-201 SUBDIVISION SOUTHERN APPROACHES
LOT 1 BLOCK PHASE UNIT 1 TOTAL ACRES .50

Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING 05-1058-N BK JH N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: 1ST FLOOR TO BE AT 116.5 FT PER GRADING PLAN BY ENGINEER. NEED PROOF
BY ELEVATION LETTER BEFORE SLAB

NOC ON FILE Check # or Cash 1148

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 220.00 CERTIFICATION FEE \$ 14.40 SURCHARGE FEE \$ 14.40
MISC. FEES \$.00 ZONING CERT. FEE \$ FIRE FEE \$.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ CULVERT FEE \$ TOTAL FEE 248.80
INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

New Construction Subterranean Termite Soil Treatment Record

OMB Approval No. 2502-0525
(exp. 10/31/2005)

This form is completed by the licensed Pest Control Company.

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is mandatory and is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when soil treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Operator and builder, unless stated otherwise.

23927

Section 1: General Information (Treating Company Information)

Company Name: Aspen Pest Control, Inc.
Company Address: 301 NW Cole Terrace City Lake City State FL Zip 32055
Company Business License No. JF109476 Company Phone No. 386-755-3611
FHA/VA Case No. (if any) _____

Section 2: Builder Information

Company Name: Harold Frankel Company Phone No. _____

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) 115 SW Bonanza Glen
Airplane Hangar Lake City, FL 32025
Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____
Approximate Depth of Footing: Outside 1' Inside 2' Type of Fill Sand

Section 4: Treatment Information

Date(s) of Treatment(s) 12/30/05
Brand Name of Product(s) Used Pro Build TC
EPA Registration No. 100-1006
Approximate Final Mix Solution % 5%
Approximate Size of Treatment Area: Sq. ft. 2880 Linear ft. _____ Linear ft. of Masonry Voids _____
Approximate Total Gallons of Solution Applied 290 gals.
Was treatment completed on exterior? ☐ Yes ☒ No
Service Agreement Available? ☒ Yes ☐ No

Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____
Comments _____

Name of Applicator(s) S. Gregory Certification No. (if required by State law) JF104376

The applicator has used a product in accordance with the product label and state requirements. All treatment materials and methods used comply with state and federal regulations.

Authorized Signature Shannon Gregory Date 12/30/05

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form NPCA-99-B may still be used

form HUD-NPCA-99-B (04/2003)

Reorder Product #2581 • from CROWNMAX • 1-800-252-4011



Cal-Tech Testing, Inc.

- Engineering
- Geotechnical
- Environmental

LABORATORIES

P.O. Box 1625 • Lake City, FL 32056-1625
6919 Distribution Avenue S., Unit #5 • Jacksonville, FL 32256

Tel. (904) 755-3633 • Fax (904) 752-5456
Tel. (904) 262-4046 • Fax (904) 262-4047

"Excellence in Engineering & Geoscience"

JOB NO: 05-579

DATE TESTED: 12-30-05

REPORT OF IN-PLACE DENSITY TEST

ASTM METHOD: ☒ D-2922 (Nuclear)

☐ D-2937 (Drive Cylinder)

☐ Other

PROJECT: Frankel Residence Plane Hanger

CLIENT: Harold Frankel

GENERAL CONTRACTOR: S.A.C. EARTHWORK CONTRACTOR: S.A.C.

SOIL USE: 1 SPECIFICATION REQUIREMENTS: 95%

TECHNICIAN: Charles Day

MODIFIED (ASTM D-1557): ☒ STANDARD (ASTM D-698):


TEST NO.	TEST LOCATION	TEST <input checked="" type="checkbox"/> DEPTH <input type="checkbox"/> ELEV. <input type="checkbox"/> LIFT#	PROCTOR NO.	WET DENS. LBS.CU.FT.	DRY DENS. LBS.CU.FT.	MOIST. PERCENT	% MAX.DENS.
8	N.W. Corner of Pad 4'S. 5'E.	12"	1	108.4	101.8	6.5	95.0
9	S.E. Corner of Pad 12'N. 10'W.	12"	1	115.2	108.8	5.8	101.6
10	South footer center of pad	12"	1	106.8	102.2	4.5	95.4
11	N.W. Corner of footer	12"	1	106.9	102.0	5.0	95.2

REMARKS:

PROCTOR NO.	SOIL DESCRIPTION	PROCTOR VALUE	OPT.MOIST.
1	Light Tan Sand (Richardson's Pad)	107.1	10.8

NOTE: SOIL USES: 1. Building Pad Fill 2. Trench Backfill 3. Base Course 4. Subbase-Stabilized Subgrade 5. Embankment
6. Subgrade - Natural Soil 7. Other

The test results presented in this report are specific only to the samples tested at the time of testing. The tests were performed in accordance with generally accepted methods and standards. Since material conditions can vary between test location and change with time, sound judgment should be exercised with regard to the use and interpretation of the data.



AMERICAN STEEL BLDGS
2865 PLUMMERS COVE RD. SUITE 3
JACKSONVILLE, FL. 32223

DATE: 9/30/05

HAROLD FRANKEL
Re: JOB NO. 15070R1
BUILDING SIZE:
WIDTH : 47.75 ft.
LENGTH : 60 ft.
EAVE HT : 16 ft.

JOBSITE : LAKE CITY, FL

To Whom It May Concern:

This is to certify that the above referenced building is designed in accordance with the order documentation, the Ninth Edition of the American Institute of Steel Construction (AISC) "Manual of Steel Construction" and the 1986 Edition of American Iron and Steel Institute (AISI) "Cold Formed Steel Design Manual. "The basic loads of the subject building meet or exceed the minimum county climatic data as published in the 1996 edition of the MBMA "Low Rise Building Systems Manual".

The criteria for application of design loads are follows
Governing Code : FBC 04

Roof Dead Load : 2 psf plus wt. of metal bldg structure

Live Load based on the tributary area :

0 - 200 sq. ft.....20 psf
201 - 600 sq. ft.....16 psf
over 600 sq. ft.....12 psf

Collateral Load	: 0 psf	Roof Snow Load	: 0 psf
Wind Load (3 sec gust)	: 100 mph	Snow Exp. Fac	: N/A
Enclosure Type	: Closed	Snow Imp. Fac.	: N/A
Wind Exp. Cat	: B	Seismic Coef SDS	: .08
Wind Imp. Factor	: 1.00	Seismic Coef SDI	: .04
Ground Snow Load	: 0 psf	Seismic Imp. Fac1	: 1.0

This Letter of Certification applies solely to the building and its component parts as furnished by the Metal Building Manufacturer. Doors, windows and louvers are not structural components of the building. It is the responsibility of the owner to determine if wind lock accessories are supplied if required. Certification specifically excludes any foundation, masonry, or general contract work.

Sincerely,

Charles W. Embden
CHARLES W. EMBDEN, P.E.

10/7/05

AMERICAN STEEL BLDGS
2865 PLUMMERS COVE RD. SUITE 3
JACKSONVILLE, FL. 32223

DATE: 9/30/05

HAROLD FRANKEL
Re: JOB NO. 15070R1
BUILDING SIZE:
WIDTH : 47.75 ft.
LENGTH : 60 ft.
EAVE HT : 16 ft.

JOB SITE : LAKE CITY, FL

To Whom It May Concern:

This is to certify that the above referenced building is designed in accordance with the order documentation, the Ninth Edition of the American Institute of Steel Construction (AISC) "Manual of Steel Construction" and the 1986 Edition of American Iron and Steel Institute (AISI) "Cold Formed Steel Design Manual. "The basic loads of the subject building meet or exceed the minimum county climatic data as published in the 1996 edition of the MBMA "Low Rise Building Systems Manual".

The criteria for application of design loads are follows
Governing Code : FBC 04

Roof Dead Load : 2 psf plus wt. of metal bldg structure

Live Load based on the tributary area :

0 - 200 sq. ft.....20 psf
201 - 600 sq. ft.....16 psf
over 600 sq. ft.....12 psf


Collateral Load	: 0 psf	Roof Snow Load	: 0 psf
Wind Load (3 sec gust)	: 100 mph	Snow Exp. Fac	: N/A
Enclosure Type	: Closed	Snow Imp. Fac.	: N/A
Wind Exp. Cat	: B	Seismic Coef SDS	: .08
Wind Imp. Factor	: 1.00	Seismic Coef SDI	: .04
Ground Snow Load	: 0 psf	Seismic Imp. Fac1	: 1.0

This Letter of Certification applies solely to the building and its component parts as furnished by the Metal Building Manufacturer. Doors, windows and louvers are not structural components of the building. It is the responsibility of the owner to determine if wind lock accessories are supplied if required. Certification specifically excludes any foundation, masonry, or general contract work.

Sincerely,

Charles W. Embden
CHARLES W. EMBDEN, P.E.

10/7/05



**AAMA/NWDA 101/I.S.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.

**SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window**


Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.


For ARCHITECTURAL TESTING, INC.


Mark A. Hess, Technician

MAH:nlb


1 APRIL 2002





Architectural Testing

AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high


Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.


Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen H. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max

Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry

Optional Performance


4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"*	0.26" max.
	@ 47.2 psf (negative)	0.46"*	0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"

Allen N. Reeves
1 APRIL 2002





Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess
Technician

MAH:nlb
01-41134.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



HI-FOLD DOORS

...the **ONLY** bi-fold doors with high-clearance advantages

[Advantages](#)[Operation](#)[Applications](#)[Components](#)[Req. for Quote](#)[Specifications](#)

As the Hi-Fold Door rises (right), the smooth-rolling steel wheels on its exclusive auxiliary arms contact the jamb posts to guide and support the door into the full-open position. When the door is closed, the auxiliary arms store themselves against the jamb posts and remain flush with the building until the next operation.



[Automatic
Latching Video](#)



[Hand](#)

HI-FOLD DOORS

...the **ONLY** bi-fold doors with high-clearance advantages

Advantages

Operation

Applications


Components

Req. for Quote


Specifications



High speed, hydraulically-powered operator option (patent pending)



Get the speed and power only a hydraulic operator can offer. A two horsepower electric motor runs a hydraulic pump and supplies pressure to a hydraulic wheel motor. System comes complete with a safety brake to lock door in position in the event of hydraulic pressure loss. System is shipped fully assembled, wired, plumbed and tested. Maintenance free operation in all climates.



Strong, welded-steel frame assures long life.

Hi-Fold Door panels are built with double, rectangular, structural-steel tubes at the center hinge line (2" x 4" on doors to 46' wide; 2" x 6" on wider doors) and 1 1/2" or 2" square structural-steel tubing, depending on door size, for the remainder of the frame. Doors over 46' wide are made in two sections that bolt together through super-strong, 1/2" steel butt-plate joints. Strong mounting hinges (4,5,7 or 9, depending on door width) are welded to the top rail.



Welded-steel trusses withstand strongest wind loads.

All Hi-Fold Doors receive one to three inside trusses. Made of heavy-gauge, steel tubing with angle-iron webbing, they provide extra strength to control wind-load deflection when the door is closed and to help the "doalea" center



Double-strength center hinge design eliminates sagging.

Unique, "dogleg" center hinge design, formed by the rectangular-steel members on both the top and bottom Hi-Fold Door panels, provides a "double-strength" beam that virtually eliminates sagging in the full-open position. This strength, combined with the strength of the welded-steel trusses on the inside of the door, provides even greater resistance to wind-load when the door is closed. A floor cane-bolt on all doors over 40' wide further resists wind-loads.



...the **ONLY** bi-fold doors with high-clearance advantages

[Advantages](#) [Operation](#) [Applications](#) [Components](#) [Req. for Quote](#) [Specifications](#)

Applications Gallery

Hi-Fold Doors fill many needs!

You won't go wrong with quality-built Hi-Fold Doors! They're the only bi-fold doors with high-clearance advantages, requiring less overhead space. Made of heavy-duty steel tubing in sizes up to 70-feet wide and 20-feet high, their rugged, all-welded construction prepares them for many years of day-in and day-out use with minimum maintenance. Cost-saving, standard bi-folds are also available for installations where Hi-Fold advantages are not required. A dependable, three year warranty covers all materials and workmanship.

You may click to open any album by desired subject below, or use the *Search* feature to look for a sample application that fits your needs. The *Slideshow* will provide a random view of the sample application photos.

Search:

4 albums, 12 images


[\[slideshow\]](#) [\[login\]](#)



Aircraft Hangars

Last changed on 12/22/04. This album contains 7 items

This album has been viewed 1007 times since 12/22/04.



Industrial Buildings

Last changed on 12/22/04. This album contains 1 item

This album has been viewed 281 times since 12/22/04.



Farm Buildings

Last changed on 12/22/04. This album contains 3 items

This album has been viewed 464 times since 12/22/04



HI-FOLD DOORS



...the **ONLY** bi-fold doors with high-clearance advantages

Advantages

Operation

Applications

Components

Req. for Quote

Specifications

Aircraft Hangars

7 images in this album

[\[slideshow\]](#) [\[login\]](#)

Gallery: Applications Gallery ↗



Viewed: 275 times.



Viewed: 306 times.



Viewed: 295 times.



Viewed: 277 times.



Forty-two Hi-Fold doors are installed in three T-hangars
Viewed: 278 times.



Viewed: 254 times.



Eight T-hangar buildings, equipped with Hi-Fold doors with walk-in doors.
Viewed: 261 times.

Gallery: Applications Gallery ↗



...the **ONLY** bi-fold doors with high-clearance advantages

Advantages **Operation** **Applications** **Components** **Req. for Quote** **Specifications**

HI-FOLD DOOR SPECIFICATIONS


- **Standard door sizes** - 12' to 70' clear opening width: heights to 20' clear.
- **Main door structure** - Double 2" x 4" Class A500 14-gauge structural center hinge line tubing on doors to 46' wide and double 2" x 6" Class A500 on larger doors.
- **Door frame** - 14-gauge, welded, Class A513 square steel tubing: 1-1/2" x 1-1/2" on doors up to 46' wide: 2" x 2" on doors over 46' wide. Door frame unitized on doors to 46' x 18'. Doors over 18' high and over 46' wide built in right and left halves. Doors over 18' high may have the top and bottom horizontally divided to facilitate freight.
- **Door trusses** - Heavy-gauge, steel tubing with angel iron webbing: 1 to 3 horizontal trusses, 6 1/2" to 12" deep, depending on door width, height and load requirements.
- **Door finish** - All doors primed with black water base oxide and painted with black ester enamel epoxy.
- **Hinges** - Strong factory welded leaf type hinges are installed on the horizontal centerline and top of the door. Top hinge can be ordered with 9-1/4" wide leaf up for wood buildings or 3" wide leaf up for steel buildings. Five top hinges on doors to 34' wide, seven hinges on doors over 34' and nine hinges on doors over 56' wide and 16' tall.
- **Auxiliary arms** - Patented, high-clearance door support arms made of heavy-gauge square-steel tubing with self-concealing chain followers.
- **Wheels** - roller wheels on door bottom and Auxiliary Arms are solid steel with sealed roller bearings inserts.
- **Drive unit** - 1 h.p. to 2 h.p. motor with 45 to 1 speed reducer. Electric brake installed on all doors. Jack shaft with dual chain drives supplied on all doors. Motor mounted to side on doors over 34' wide.
- **Bottom follower system** - Hold bottom of door against building with door closed. Rubber bottom seal - 3" space between door frame and finished floor sealed with standard 12" wide bottom seal.
- **Floor cane-bolt** - Factory installed at center of door over 40' wide. Cane-bolt slides thru sleeve on door into a hole drilled in the floor.
- **Warranty** - 3 years on materials and workmanship.

Optional Features


- **Extra-heavy duty trussing** - Standard wind load can be increased or special demands provided.
- **Rubber top seal** - Standard 9" wide rubber roofing membrane with ultraviolet inhibitor to weather proof top of door.
- **Weather-strip package** - Supplied in bulk on a per foot basis for sealing between door frame and building jamb on vertical and horizontal surfaces and at center hinge area.
- **Jamb reinforcement rail** - 10 gauge galvanized steel 5" wide, suitable for doors to 46' wide, 3/16" oxide primed plate 5-1/2" wide available for doors wider than 46'. Wood or concrete jamb buildings require a reinforcing plate for operation.
- **Automatic "knee action" jamb latch** - Patented drive shaft driven latch reaches out and pulls door securely closed before motor shuts off. Automatic cane bolt supplied on doors over 40' wide. Single location latches deleted. Safety edge recommended.
- **Safety edge** - Full width sensing switch to automatically stop and reverse a closing door if obstacle is encountered. Attaches to bottom of door prior to bottom seal.
- **Dead-man operating control** - NEMA

End Views of Bi-fold Door

Closed View







Open View



When door is open it is held up by
4 independent lift cables

HINGE INSTALLATION FOR STEEL STRUCTURE HEADER



ATTACHMENT TO STUB COLUMN:

EACH OUTBOARD HINGE IS SUPPLIED WITH AN EXTENSION FOR 2-BOLT ATTACHMENT TO THE VERTICAL COLUMN.

THERE ARE TWO OPTIONS:

2 BOLTS REQUIRED AT EACH HINGE

OR

WELDING THE HINGE TO THE STUB IS ACCEPTABLE.

NOTE:
WELD THE FULL PERIMETER OF THE HINGE.
THE DOOR MUST BE PARTIALLY OPEN TO
COMPLETE THE WELD ACROSS THE HINGE BOTTOM.
OUTBOARD HINGES WILL EXTEND BEYOND THE
VERTICAL COLUMN, MAKING IT NECESSARY TO WELD
A VERTICAL LAP JOINT, WELD ON BACK OF HINGE
AT COLUMN.

Post-it [®] Fax Note	7671	Date	12-2	# of pages	6
To	Harold Frankel	From	Bill		
Co./Dept.		Co.			
Phone #		Phone #			
Fax #	386-752-9542	Fax #			

HI-FOLD DOOR CORPORATION		MORRISVILLE, NC	
PREPARED FOR: Harold Frankel			
100 WPK EXPOSURE C. WIND LOAD PER REC			
QUOTATION NO.: FPA150205.F02		DRAWN BY: TOL	
CUTAWAY OPENING: 42'-0" X 12'-0"		DATE: 12-1-2005	
DOOR SIZES: 11'X12'		SCALE: NONE	
DRAWING NO./Revs - FPA150205.F02		SHEET: 1 of 1	

12/2/2005

hinge calc Harold Frankel 1212005.xls

Door Force/Strength Analysis
for Harold Frankel, 42'-0"x12'-0" clear opening
reference FRA1560205.P02 Quote
12/1/2005

page 1/2 This sheet looks at closed door (vertical)

note: hinges at mid-height of door are welded;
hinges at top of door are welded to door and bolted to building
This spreadsheet looks at top hinges, outermost hinges only

clear width, ft	42
height, ft	12
area, ft ²	504.0
design wind P, PSF	22.6
total force on door, lb	11390

Hinge Strength Analysis

total wind load on door, lbs: see small table, above
fraction of windload on all top hinges
average wind load, all hinges
door weight, lbs
number of hinges
avg load per hinge, lb
multiplier for end hinge
vertical load on end hinge, est., lb., parallel to plate
horizontal load on end hinge, est., lb., perp. to plate
combined load on end hinge, lb

Weight load alone	Wind load alone	Weight and Wind load
door vertical, both hinge plates vertical		
	11390	
	0.16	
2777	1822	
7	7	
397	260	
1.75	1.75	
694	0	0
0	456	0
0	0	830

Maximum Force to Yielding, lbs	Lowest Safety Factors		
A. bolts in tension, perpendicular to hinge plate	9547	21.0	
B1. Bolts in shear, parallel to hinge plate	8645	12.5	
B2. Weld in shear, parallel to hinge plate	10541		
C. bearing stress, holes, parallel to hinge plate	11812		
D. tear-out, parallel to hinge plate	11550		
E. tear apart tube, welded, any direction	18230		
F. pin shear, any direction	8247	11.8	18.1
See separate hand calculations, for cases A-F, on three pages, dated Dec 3, 2003			
lowest safety factor is 9.8, acceptable			

This analysis looks at worst case loading
and compares with forces which cause yielding
in various modes, and calculates safety factors.

JAMB:

Horizontal force on door jambs with door closed:	
decimal portion of wind load on trusses A, B, and hinge tubes conversion to force pushing out on door x 7/8:	0.72
decimal portion of force applied to jamb instead of being transferred up or down by Hi-Fold door vert frame.	0.6
force on each building frame door jamb, at midheight, lb	2153

hinge calc Harold Frankel 1212005.xls

12/2/2005

10:40 AM

Door Force/Strength Analysis
for Harold Frankel, 42'-0"x12'-0" clear opening
reference FRA1560205.P02 Quote

page 2/2 This sheet looks at open door in up position

note: hinges at mid-height of door are welded;
hinges at top of door are welded to door and bolted to building
This spreadsheet looks at top hinges, outermost hinges only

Hinge Strength Analysis	
door clear opening is 12'-0" Top of door from finish floor is 13'-2" headroom equals 1'-2"	
door weight, lbs	
multiplier of door weight to get horiz force, lb*	
total horizontal force on all top hinges, lb	
----note this is also force on building frame----	
door weight, lbs	
number of hinges	
avg load per hinge, lb	
multiplier for end hinge	
vertical load on end hinge, est., lb., parallel to plate	
horizontal load on end hinge, est., lb., perp. to plate	
combined load on end hinge, lb	
Maximum Force to Yielding, lbs	
A. bolts in tension, perpendicular to hinge plate	9547
B1. Bolts in shear, parallel to hinge plate	8645
B2. Weld in shear, parallel to hinge plate	10541
C. bearing stress, holes, parallel to hinge plate	11812
D. tear-out, parallel to hinge plate	11550
E. tear apart tube, welded, any direction	19230
F. pin shear, any direction	8247
See separate hand calculations, for cases A-F, on three pages, dated Dec 3, 2003	


Note this column is same as on page 1	Refer to item G In hand calcs,	
Weight load alone (vertical)	horizontal force	combined force on top hinge
door open		
	2777	
	1.35	
	3748.95	
2777		
7	7	
397	536	
1.75	1.75	
694	0	0
0	937	0
0	0	1166
Maximum Force to Yielding, lbs		Lowest Safety Factors
		10.2
	12.5	
	11.9	8.8 7.1
See separate hand calculations, for cases A-F, on three pages, dated Dec 3, 2003		Lowest Safety Factor is 7.1 acceptable

This analysis looks at worst case loading and compares with forces which cause yielding in various modes, and calculates safety factors.

JAMB	Horizontal force on each side of door, at roller/jamb	1674.475	
CABLE	door weight, from above, lb	3617	
	decimal portion of door weight as cable weight, worst case*	0.6	
	total force on all 4 lifting cables, with door in up position, lb	2170.2	
	average load per cable assuming equal distr., lb	543	
	multiplier to end cables	1.75	
	load on end cables, lb	949.5	
	strength of 7/32" cable, lb	5600	
	safety factor on cable, compare to minimum of 5	5.9	

~~HINGE STRENGTH ANALYSIS~~ 1/2" 3-03 Tensile

(A) Bolts in tension Note: three Grade 5, 3/8" bolts



$$F_{\text{bolt}} = \frac{P_{\perp} \times 1.55}{.75} = 2.07 P_{\perp}$$

In tension:

$$6_{T \text{ bolt}} = \frac{F_{\text{bolt}}}{3 A_{\text{bolt}}} = \frac{2.07 (P_{\perp})}{3 (.0775 \text{ in}^2)}$$

Note: Gr 5 bolt has:

 S_y = yield strength of 85ksi \Rightarrow Force to yield = P_y

$$P_y = \frac{S_y \times 3 \times .0775 \text{ in}^2}{2.07} = \boxed{7547 \text{ lb}}$$

(B1) Bolts in shear

due to parallel-to-plate force P_p

$$\tau = \frac{T_p}{3 \times A_{\text{shear}}} = \frac{P_p}{3 \times .0678 \text{ in}^2}$$

$$\text{Shear yield strength} = \frac{85,000}{2} = 42,500 \text{ psi}$$

$$\text{Failure, in shear yield} = P_p = \frac{42,500 \text{ psi} \times 3 \times .0678}{1} = \boxed{8645 \text{ lb}}$$

B2 - see next sheet

(C) Bearing stress in bolt holes, in 3/8" mat'l (see Fig above)

for force P_p parallel to plate:

$$\sigma_c = \frac{P}{3 \times A} = \frac{P_p}{3 \times 3/8 \times 3/8} \quad \text{Note: } 3/8 \text{ bolt is in } 1/2 \text{ hole, but assume } 3/8 \text{ hole (conservative)}$$

$$\text{yield strength } S_y = 28,000 \text{ psi}$$

$$\text{Force to yield} = P_p = 28 \text{ ksi} \times 3 \times 3/8 \times 3/8 = \boxed{11,812 \text{ lb}}$$


See: Hinge Calcs.xls spreadsheet
Michael Brito Hifold Door, 16X60

Page 1/3

HINGE STRENGTH ANALYSIS

12/3/05 - JMS/gcl

- (B2) Weld in shear
for force parallel to plate
Will look @ single center section, which is conservative
compared to wider end hinge section. Holes are ignored.



Assume welded all around perimeter

$$Perim = 2(2\frac{7}{8}) + 2(1.7) \\ = 9.15"$$


Welds in shear:

$$Allowable = P_p = w \times Perim \times 9600 \quad \text{(allowable #/in)}$$

$$= .12(9.15) 9600$$

$$= 10541 \text{ lb}$$

tube welded shut

 P_p

- (E) Tear L-point Hinge Tube, with tube welded shut
.12 thick mat'l x $2\frac{7}{8}$ " / in

$$Area in tension = 2 \times .12 \times 2\frac{7}{8} = .69 \text{ in}^2$$


$$\sigma_T = \frac{P}{A} \Rightarrow P_{allowed, to yield} = S_y \times A$$

$$= 28,000 \text{ psi} \times .69 \text{ in}^2$$

$$= 19230 \text{ lb}$$

- (D) Tear out of Holes - for force // to plate

Using only 2 holes (which align w/ center section)
with $\frac{3}{8}$ thick section



$$\tau = \frac{P}{A} = \frac{P_p}{2 \times 2 \times .55 \times \frac{3}{8}}$$

$$Shear yield = \frac{28,000}{2}$$

$$P_{allowed, to yield} = 14,000 \text{ psi} \times 2 \times 2 \times .55 \times \frac{3}{8}$$


$$= 11550 \text{ lb}$$

Page 2/3

HINGE STRENGTH ANALYSIS

12/1/03 Jorgensen

① Pin Shear, any direction
(2 shear areas)



$$\tau = \frac{P}{2A_{cs}}$$


Shear yield
Strength = $42,000 \text{ psi}$
 $\frac{2}{2}$

$$P \text{ to Shear yield} = S \times 2A$$

$$= 21,000 \text{ psi} \times 2 \times \frac{\pi}{4} (.5)^2$$

$$= \boxed{8247.16}$$

② Horizontal Force on Top Hinge



W , assumed roughly in center of door half (conservative)


$$\sum M_o = 0 = W \times 48 - F_{A,H} \times 24$$

$$\Rightarrow F_{A,H} = \frac{W \times 48}{24} \text{ or } W \times \underline{2}$$

multiplier

END OF HAND CALCULATIONS

Page 3/3



HI-FOLD DOOR CORPORATION

N6170 1070th Street, River Falls, Wisconsin 54022
 Telephone: (800) 443-6536; FAX: (715) 262-3998
www.hi-fold.com

FRA1560205.P02

Frankel, Mr. Harold
 Rt #18, Box 18802

September 6, 2005

Lake City, FL 32025
 Att: Harold Frankel
 Door Number: 01 Product Number: H4212-2

Called Clear Opening Width	42	Feet	0.000	Inches
Called Clear Opening Height	12	Feet	0.000	Inches
Measured Frame Height	12	Feet	11	Inches
Panel Height	6	Feet	5.5	Inches
Top of Door AFF	13	Feet	2	Inches
Base of Stub column AFF	13	Feet	0	Inches
Clearance Height Required	13	Feet	6	Inches
Measured Frame Width	42	Feet	8	Inches
Clearance Width Required	42	Feet	10	Inches
Arm Location Measurement			30	Inches

Hinge location is based on hinge quantity - Hinge Reverse

Hinge Quantity = 7 If Hinge "B" or "C" is blank then go to "D"

	Standard Wood	Reverse Steel
Edge of door to first Hinge	4.630	2.500
Hinge "A" Measurement	45.370	47.500
Hinge "B" Measurement	132.000	
Hinge "C" Measurement	0.000	
Center of Door to first hinge and Hinge "D"	74.000	

Active weights for the Hi-Fold Door are as follows:

Door Closed

Dead Weight.....	2273	1873 LBS.
Estimated Weight for Exterior covering.....		504 LBS.
Total Dead Weight less any options.....	2777	2377 LBS.
Wind Load Transferred to Vertical Column.....		75%
Wind Load Transferred to Header/hinge mount point.....		25%

Door Open - Tends to pull away from building at hinge line.

Horizontal Component - 1.35 times Dead Weight.....	3749	3209 LBS.
Number of hinges.....		7 Hinges
Horizontal Tension in Pounds per Hinge.....	536	458 LBS.
Horizontal compression At Wheel on each vertical Column..		1604 LBS.
	1874	

... the only Bi-Fold Door with high clearance advantages!



HI-FOLD DOOR CORPORATION

N6170 1070th Street, River Falls, Wisconsin 54022
 Telephone: (800) 443-6536; FAX: (715) 262-3998
 www.hi-fold.com

Quotation and Purchase Agreement

September 6, 2005
 Frankel, Mr. Harold
 Rt #10, Box 10002

Quotation Number: FRA1560205.P02

Lake City, FL 32025
 Attention: Harold Frankel
 Phone: 386-752-9592

Ship To:

Lake City, FL
 Attention:

1703 SW SISTERS
 WELCOME RD

This Quotation shall be in effect for 30 days. If this is acceptable, please sign it, the attached transmittal print and the information sheet and return one copy of each to us. Each must be returned for the manufacturing of your door to start. This Agreement includes the terms shown on the reverse hereof.

Hi-Fold Doors: Size is Measured Clear Opening after installed and in open position - FOB River Falls, WI 54022

Product Door

Number Number Product Description and Size

Quantity Unit Price Amount

H4212-2	01	42' 0.000" Wide X 12' 0.000" High	Standard	1	3,975.00	3,975.00
Special Increased loading		100 MPH wind load per FBC 2001 exp C 3 sec gust		1.0	680.000	680.00
Option Stamped Print		Engineer verified wind load		1.0	312.000	312.00
Option Top Seal		12" wide rubber top seal		43.0	1.050	45.15
Option Weather Stripping		3/4" X 5/8" open cell foam with adhesive back		69.0	.150	10.35

Package Total 5,022.50 **4710.50**

Freight Total 775.00

Quote Total 5,797.50 **5485.50**

Down Payment 1,255.63

Balance Due 4,541.88

Anticipated Shipping Date: 4-8 Weeks from receipt of signed agreement.
 Shipping Method: Contract FT

All doors are custom made for your specific application; therefore, our terms are 25% down payment with order. Remaining balance C.O.D. Advance payment by check or bank letter of credit including freight will save C.O.D. charges. Open account terms require management authorization and credit department approval. Any applicable taxes will be added unless exemption certificate is supplied or on file.

Customer Signature

Date:

Sincerely,

Hi-Fold Door Corporation

Bill Bakulich
 Marketing Manager

Hi-Fold Acceptance

Date:

Post-It® Fax Note 7671

Date

of pages

To

From

Co./Dept.

Co.

Phone #

Phone #

Fax #


Fax #

... the only Bi-Fold Door with high clearance advantages!


PREPARED FOR Handel Frankel
QUOTE NUMBER FRA1510 205.102
HINGE LOCATION MEASURED FROM DOOR C/L:
A 47 1/2" B 132" C 74"
HINGE QUANTITY 7

DOOR CLEAR OPENING HEIGHT 12'-0"
MEASURED DOOR FRAME HEIGHT 12'-11"
DOOR PANEL HEIGHT FOR SKIN:
TOP 6'-9 1/2" BOTTOM 6'-5 1/2"
TOP OF DOOR FRAME FROM FLOOR 13'-2"

BUILDING MEASUREMENTS BELOW:
BOTTOM OF STUB COLUMN 13'-0"
CLEARANCE HEIGHT REQUIRED 13'-6"
CLEARANCE HEIGHT IS BOTTOM OF
SHEETING AND TRIM ABOVE DOOR



FOR APPROVAL PLEASE RETURN ONE SET OF DRAWINGS FOR PROMPT SCHEDULING
APPROVED FOR CONSTRUCTION AS SHOWN AS NOTED
DATED 9/9/05 SIGNED Handel Frankel



1. All doors shipped fully assembled. Units over 26' to 46' wide may require a vertical split. All doors over 48' must be vertically split. Units over 18' in height may require each half to be split horizontally. Vertically split doors to require field bolting, horizontally split doors to require field welding.
2. Doors over 46' wide supplied with 1.5 or 2 horsepower motor wired for 220 volt single phase and require separate circuit with circuit interrupt (provided by others) to protect the required 13 amps. Most doors 46' and under supplied with a 1 horsepower motor wired 110 volts and provided with individual circuit protection to protect the required 20 amps. "Up-Stop-Down" control wired 24 volts with cable long enough to place control five feet above floor on the side of door to be specified by customer. Flexible power cable 4' longer than height of door and requires service at that point. Hi-Fold electrical system meets the requirements of the National Electrical Code for typical applications hence it is the customers responsibility to provide instructions to meet special applications and local codes.
3. The electrical system requires a grounded circuit and substantial wiring. Extension cords and generators may not be adequate for door operation, and are not recommended.
4. Optional jamb reinforcement rails are available for wood or concrete jamb building applications.
5. Hi-Fold Door exerts considerable horizontal loads on the building structure in the open position. Loads specific to this application are provided to the purchaser. Purchaser is responsible to insure that the buildings structural design is capable of handling the imposed loads.
6. Operating times vary with door size. Contact Hi-Fold Door for operating speed for a particular size.
7. Purchaser required to inform Hi-Fold Door if any weight in addition to standard 26 gauge roll formed steel exterior covering (provided by others) is to be applied to and lifted by door operating system. Excessive weight will void warranty.
8. Hi-Fold Door is welded steel primed with a water base oxide primer and painted with black epoxy ester enamel and is not intended to be left exposed to the elements. In a highly corrosive atmosphere it may be necessary to field apply finish paint. Operating components must be checked frequently and properly lubricated as necessary.
9. Defective components will be replaced upon receipt of the defective component. Immediate replacement of defective components will be made by UPS or freight shipment on a COD basis with reimbursement upon return of the defective part following analysis and evaluation if deemed necessary by Hi-Fold Door.
10. Field alteration or repair of a door must be authorized in advance in writing. Unauthorized alteration will void warranty.
11. Hi-Fold is not responsible for the installation of the Hi-Fold Door, nor for installation errors or normal installation adjustments as might be required. Compliance with all applicable state and local codes is the sole responsibility of purchaser. Optional walk doors may not meet state or local life safety code requirements for exit doors.
12. Hi-Fold will attempt to answer any installation problem by phone. Factory service will be supplied when all field effort can not rectify the problem. Hi-Fold must be allowed reasonable time within which to travel to the job site. Abnormal cost incurred to answer demand for immediate service must be paid by purchaser. Purchaser must pay for total service cost if Hi-Fold is not found responsible for defect or defective operation.
13. Customer must thoroughly check shipments for damage. Significant damage is reason to refuse shipment of the product. Minor damage must be noted on the bill of lading and claim filed with the carrier. Hi-Fold is not responsible for freight damage. Neither Hi-Fold nor the trucking company can be held responsible for damage caused during unloading. Unloading is the responsibility of the purchaser. Shipment must be checked for road salt during winter months, if shipment comes in contact with salt it must be washed thoroughly prior to unloading truck and noted on the bill of lading.
14. Delivery to be accepted on confirmed delivery date. Any delay caused by purchaser shall require an additional amount paid to cause deposit to equal fifty percent of the order value.
15. Delivery delay exceeding 30 days caused by purchaser will require payment to equal 90 percent of order value and a storage fee may be imposed. Hi-Fold is not responsible for exposure deterioration caused by delivery delays in excess of 30 days.
16. Delivery date to be confirmed when all components of the contract are received. Any change order must be received at least two weeks prior to confirmed delivery date.
17. Issuance of a purchase order alone is not adequate for door to be manufactured. This contract and size print must be signed and returned.
18. Cancellation policy: Once manufacturing has begun there will be no cancellations made. If cancellation is prior to manufacturing deposit will be returned in full, less any engineering that has been done.

Customer Signature



G



STATE OF FLORIDA
DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number 05-1058 N

PART II - SITE PLAN -

Scale: Each block represents 5 feet and 1 inch = 50 feet.

See
Attached

Notes: _____

Site Plan submitted by: [Signature]

Signature

OWNER


Title

Plan Approved [Signature] Not Approved _____

Date 10/13/05

By [Signature] Colin C County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT



Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 0511-77 Date Received 11-21-05 By LH Permit # 23927
Application Approved by - Zoning Official BLK Date 29.11.05 Plans Examiner OK JTH Date 12-02-05
Flood Zone X Development Permit N/A Zoning RMF-1 Land Use Plan Map Category RES. Mod Dev.
Comments 1st Floor to be at 116.5 ft per grading plan by Engineer.

Applicants Name HAROLD J FRANKEL Phone 386-752-9592
Address 1703 SW SISTERS WELCOME RD LAKE CITY FL 32025
Owners Name SAME Phone _____
911 Address 115 SW Bonanza Gl, Lake City, FL 32025
Contractors Name SAME Phone _____
Address _____
Fee Simple Owner Name & Address N/A
Bonding Co. Name & Address N/A
Architect/Engineer Name & Address CHARLES W. EMBDEN JAX, FL - NICHOLAS GEISLER LKCY.
Mortgage Lenders Name & Address _____
Circle the correct power company - FL Power & Light - Clay Elec - Suwannee Valley Elec. - Progressive Energy
Property ID Number 13-45-16-02952-201 Estimated Cost of Construction 44,000
Subdivision Name SOUTHERN APROCES Lot #1 Block _____ Unit #1 Phase _____
Driving Directions SISTERS WELCOME RD TO BUSINESS POINT RD ON CORNER

Type of Construction STEEL Hangar Number of Existing Dwellings on Property 1
Total Acreage .5 AC Lot Size _____ Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
Actual Distance of Structure from Property Lines - Front 72' 11" Side 10' 6" Side 29' 11" Rear 31' 9"
Total Building Height 24 FT Number of Stories 1 Heated Floor Area 2880 Roof Pitch 4/12
STORAGE = 720

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Harold J Frankel
Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA


Sworn to (or affirmed) and subscribed before me
this 21 day of November 2005.

Personally known ✓ or Produced Identification _____



Contractor Signature
Contractors License Number _____
Competency Card Number _____
NOTARY STAMP/SEAL

Laurie Hodson
Notary Signature



THE UNDERSIGNED hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

Tax Parcel ID Number 13-45-16-02952-201


1. Description of property: (legal description of the property and street address or 911 address)
LOT 1 UNIT 1 SOUTHERN APPROACHES COLUMBIA COUNTY
115 SW BONANZA GLEN - COURT
2. General description of Improvement: NEW HOUSE + HANGAR
3. Owner Name & Address HAROLD + CYNTHIA FRANKEL = 1703 SW SISTERS WELCOME
RD. LAKE CITY, FL 32025 Interest in Property _____
4. Name & Address of Fee Simple Owner (if other than owner): _____
5. Contractor Name OWNER CONTRACTOR Phone Number (386) 752-9592
Address _____
6. Surety Holders Name _____
Address _____ Inst: 2005021867 Date: 09/08/2005 Time: 11:16
Amount of Bond _____ YMK DC, P. DeWitt Cason, Columbia County B: 1057 P: 1591
7. Lender Name _____
Address _____ Phone Number _____
8. Persons within the State of Florida designated by the Owner upon whom notices or other documents may be served as provided by section 718.13 (1)(a) 7; Florida Statutes:
Name _____ Phone Number _____
Address _____
9. In addition to himself/herself the owner designates _____ of _____
to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) -
(a) 7. Phone Number of the designee _____
10. Expiration date of the Notice of Commencement (the expiration date is 1 (one) year from the date of recording, (Unless a different date is specified) _____

NOTICE AS PER CHAPTER 713, Florida Statutes:
The owner must sign the notice of commencement and no one else may be permitted to sign in his/her stead.

[Signature]
Signature of Owner

Sworn to (or affirmed) and subscribed before
day of August 29, 2005

NOTARY STAMP/SEAL



[Signature]
Signature of Notary

DISCLOSURE STATEMENT

FOR OWNER/BUILDER WHEN ACTING AS THEIR OWN CONTRACTOR AND CLAIMING EXEMPTION OF CONTRACTOR LICENSING REQUIREMENTS IN ACCORDANCE WITH FLORIDA STATUTES, ss. 489.103(7).

State law requires construction to be done by licensed contractors. You have applied for a permit under an exemption to that law. The exemption allows you, as the owner of your property, to act as your own contractor with certain restrictions even though you do not have a license. You must provide direct, onsite supervision of the construction yourself. You may build or improve a one-family or two-family residence or a farm outbuilding. You may also build or improve a commercial building, provided your costs do not exceed \$25,000. The building or residence must be for your own use or occupancy. It may not be built or substantially improved for sale or lease. If you sell or lease a building you have built or substantially improved yourself within 1 year after the construction is complete, the law will presume that you built or substantially improved it for sale or lease, which is a violation of this exemption. You may not hire an unlicensed person to act as your contractor or to supervise people working on your building. It is your responsibility to make sure that people employed by you have licenses required by state law and by county or municipal licensing ordinances. You may not delegate the responsibility for supervising work to a licensed contractor who is not licensed to perform the work being done. Any person working on your building who is not licensed must work under your direct supervision and must be employed by you, which means that you must deduct F.I.C.A. and withholding tax and provide workers' compensation for that employee, all as prescribed by law. Your construction must comply with all applicable laws, ordinances, building codes, and zoning regulations.

TYPE OF CONSTRUCTION

- ☐ Single Family Dwelling
☐ Farm Outbuilding
☐ New Construction

☐ Two-Family Residence

☒ Other HANGER

☐ Addition, Alteration, Modification or other Improvement

NEW CONSTRUCTION OR IMPROVEMENT


I HAROLD J FRANKEL, have been advised of the above disclosure statement for exemption from contractor licensing as an owner/builder. I agree to comply with all requirements provided for in Florida Statutes ss.489.103(7) allowing this exception for the construction permitted by Columbia County Building Permit Number _____


Signature

11/21/05
Date

FOR BUILDING USE ONLY

I hereby certify that the above listed owner/builder has been notified of the disclosure statement in Florida Statutes ss 489.103(7).

Date 11-21-05 Building Official/Representative 

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

0511-77

Reference to: Build permit application Number:

Harold Frankel Owner/Builder lot 1 Unit 1 Southern Approaches

On the date of November 22, 2005 application 0511-77 and plans for construction of a residential aircraft hanger were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.


Please include application number 0511-77 when making reference to this application.

1. Please have Mr. Nicholas Geisler show on the plans a design detail for the interior 1 hour fire wall which will provide separation between the aircraft hanger area and the storage area.
2. Please submit product approval specification as required by Fla. Statute 553.842 and Fla. Administrative Code 9B-72 for all windows and doors which includes the hanger door that will be placed in the sheer walls of the hanger.
3. Please show compliance with the FBC-2004 section 412.3.1 residential aircraft hangars: An accessory building less than 2,000 square feet (186 m2) and 20 feet (6096 mm) in height, constructed on a one- or two-family residential property where aircraft are stored. Such use will be considered as a residential accessory use incidental to the dwelling. As shown on the floor plan submitted in

application 0511-77 the acceptable square footage of a residential aircraft hangar is exceed by 304 square feet.

4. Show the method of attachment of the hanger door and supports to the structure also include the method of attachment of these supports to the foundation. Provide the wind-load rating for the hanger door and all components of the hanger door.
5. Provide the manufacture specification and fire rating on the door which will be placed within the one hour fire rated wall.
6. If any penetration is made through the 1 hour fire wall, show the method to be used to maintain the firewall integrity.
7. Please provide a copy of the release, of the waste water disposal system from the Columbia County Environmental Department.
8. Please verify the requirement of Mr. Disosway grading plan for your property which stipulates that the first floor elevation of the hanger building to be elevated to 116.5 feet.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department

#23927


The hanger next to Frankel's house @ Cannon Creek Airport is alledged not to meet wind load standards. Apparently, the bolt patterns did not match and therefore were altered. Please check on this.


Dale

at request from Dale I made a spotcheck at Mr. Frankel's Airplane Hanger. I found that there were several places where the Bolts in the Skab did not match the main Steel Beam's holes. I spoke with Mr. Frankel + he said that he would get his Engineer to approve the alteration of the Bolts.



2.23.20










2.23.20



2.23.20













2.23.20







N3
**NICHOLAS
PAUL
GEISLER**
ARCHITECT
N.C.A.R.B. Certified

1758 NW Brown Road
Lake City, FL 32055
386/755-9021

17 JULY 2006

JOHNNY KEARSE, BUILDING OFFICIAL
COLUMBIA COUNTY, BUILDING DEPT.
COLUMBIA COUNTY COURTHOUSE ANNEX
LAKE CITY, FLORIDA 32055

RE: HAROLD FRANKEL, METAL BUILDING
PERMIT Nr.: 23927


DEAR SIR:

PLEASE BE ADVISED THAT I HAVE INSPECTED THE ABOVE REFERENCED METAL BUILDING AND HAVE FOUND THAT IT IS CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERED METAL BUILDING SHOP DRAWINGS AS PREPARED BY THE BUILDING'S MANUFACTURER. WHILE I HAVE NOT INSPECTED THE PROJECT DURING CONSTRUCTION, THE SLAB APPEARS TO BE IN GOOD CONDITION, WITH NO APPEARENT CRACKING OR SETTLEMENT.

SHOULD YOU HAVE ANY FURTHER QUESTIONS WITH THIS, PLEASE CALL FOR ASSISTANCE.

YOURS TRULY,
NICHOLAS PAUL GEISLER, ARCHITECT AR0007005





RADI US=50.95 (S)
 LENGTH=61.34 (S)
 DELTA=68° 59' 05\"/>



I HEREBY CERTIFY THIS SURVEY WAS DONE UNDER MY DIRECT SUPERVISION AND IT MEETS THE MINIMUM TECHNICAL STANDARDS FOR LAND SURVEYING PURSUANT TO CHAPTER 61G17-6, FLORIDA ADMINISTRATION CODE, CHAPTER 472, FLORIDA STATUTES.

WILLIAM N. KITCHEN PSM 5490

William N. Kitchen
 10-18-2005

NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.






CERTIFIED TO:
1. HAROLD FRANKEL

- SURVEYORS NOTES**
1. BEARING BASED ON PLAT.
 2. THIS SURVEY BASED ON LEGAL DESCRIPTION FURNISHED. THE PUBLIC RECORDS, WERE NOT SEARCHED BY THIS SURVEYOR FOR EASEMENTS, TITLE, COVENANTS, RESTRICTIONS, CLOSURES, TAKINGS OR ORDINANCES, ETC., THERE COULD BE OTHER MATTER OF RECORD THAT EFFECT THIS PARCEL.


REV: _____

WILLIAM N. KITCHEN PROFESSIONAL SURVEYOR AND MAPPER 152 N MARION AVENUE LAKE CITY, FLORIDA 32055 PHONE (386) 755-7786		DRAWN BY: RI		FIELD BOOK: 05406	
		SCALE: 1" = 30'			
		SURVEY DATE: OCTOBER 5, 2005			
		JOB NUMBER		SHEET	

CLIENT: HAROLD FRANKEL	05406	1 OF 1	LEGEND (P) = PLAT (S) = SURVEY MEASUREMENT FCM = FOUND CONCRETE MONUMENT SIR = SET IRON ROD LS = LAND SURVEYOR N/D = NO IDENTIFICATION R/W = RIGHT OF WAY



FIELD LOCATE:
(2) 3' X 7' F.O.
(1) 3' X 3' F.O.
(6) 3' X 5' F.O.



ANCHOR BOLT NOTES:
VALUES GIVEN FOR BENDS AND ANCHOR BOLT TOTAL LENGTHS ARE SUGGESTED
LENGTHS ONLY. IT IS THE RESPONSIBILITY OF THE FOUNDATION ENGINEER TO
DETERMINE THESE VALUES SINCE THEY ARE A FUNCTION OF CONCRETE STRENGTH
AS WELL AS OTHER FACTORS.

ANCHOR BOLT SUMMARY						
Qnt		Loc	Dia (in)	Total Len (in)	Bend Len (in)	Profi (in)
○ 4	DJ		5/8"	9.00	3.00	3.00
○ 16	EW		5/8"	12.00	3.00	3.00
⊗ 24	RF		3/4"	18.00	3.00	3.00
⊗ 4	WF		3/4"	18.00	3.00	3.00

ANCHOR BOLT SUMMARY

SEAL

$$* = 1 \frac{3}{4}''$$


ANCHOR BOLT PLAN
NOTE: All Base Plates @ 100'-0" (U.N.)

REVISIONS									
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD			

DRAWING STATUS	AMERICAN STEEL BLDGS		HAROLD FRANKEL
<input checked="" type="checkbox"/> FOR CONSTRUCTION	PROJECT	477 x 600 x 16.0	ANCHOR BOLT PLAN
<input type="checkbox"/> FOR PERMIT ONLY	ID	1507081	DESIGN: _____ DRAFT: SPV _____ CHECK: <i>[Signature]</i>
<input type="checkbox"/> FOR APPROVAL	PROJECT	LAKE CITY, FL	DATE: 9/30/05 SHEET 1
<input type="checkbox"/> OTHER, EXPLAIN -----	ADDRESS		

10/7/05
HAROLD FRANKEL

WIND COLUMN REACTIONS



GENERAL NOTES

- (1.) APPLICATION OF ENGINEERS SEAL IS FOR METAL BUILDING ONLY AND DOES NOT REPRESENT THE PROFESSIONAL OF RECORD.
- (2.) FOUNDATION DESIGN AND CONSTRUCTION ARE NOT THE RESPONSIBILITY OF THE METAL BUILDING MANUFACTURER.
- (3.) ANCHOR BOLTS SHALL BE ACCURATELY SET TO A TOLERANCE OF +/- 1/8" IN BOTH ELEVATION AND LOCATION.
- (4.) THE BUILDING REACTION DATA REPORTS THE LOADS WHICH THIS BUILDING PLACES ON THE FOUNDATION. THE FOUNDATION IS TO BE DESIGNED BY A LICENSED ENGINEER TO SUPPORT THE BUILDING REACTIONS IN ADDITION TO OTHER LOADS IMPOSED BY THE BUILDING USE OR OCCUPANCY WITH RESPECT TO JOB SITE CONDITIONS.
- (5.) ALL ANCHOR BOLTS TO BE ASTM SPECIFICATION A307 UNLESS OTHERWISE NOTED.
- (6.) VALUES GIVEN FOR BOLDS AND ANCHOR BOLT TOTAL LENGTHS ARE SUGGESTED LENGTHS ONLY. IT IS THE RESPONSIBILITY OF THE FOUNDATION ENGINEER TO DETERMINE THESE VALUES SINCE THEY ARE A FUNCTION OF CONCRETE STRENGTH AS WELL AS OTHER FACTORS.


ENDWALL COLUMN: REACTIONS, ANCHOR BOLTS, & BASE PLATES

Column Reactions (k)									
Frm	Col	Dead	Coll	Live	Wind-Left	Wind-Fight	Out-Of-Plane		
Line	Line	Vert	Vert	Horiz	Vert	Horiz	Wd P	Wd S	
							Horiz	Horiz	
1	H	0.0	1.0	0.0	0.0	0.0	-0.1	0.1	
2	B	0.0	1.0	0.0	0.0	0.0	-0.1	0.1	
3	E	0.3	0.0	1.4	0.0	-1.8	0.0	0.0	
4	A	1.0	0.0	3.7	0.0	-3.3	-3.8	4.1	
		0.3	0.0	1.4	0.0	-1.8	0.0	0.0	

SPlice BOLTS				-----Bolt-----			
Splice Mark	Quan	Top/Bot	Int Type	Dia	Len		
SP-1	4	4	0	A325	0.625	1.75	
SP-2	4	4	0	A325	0.625	1.75	

▽FLANGE BRACES:
FBxxxA(1): xx=length(in)
A - L2X2X14G

MEMBER SIZE TABLE (in)				OUTSIDE FLANGE		INSIDE FLANGE	
PIECE	WEB DEPTH START/END	WEB PLATE THICK / LENGTH		W x T x LEN		W x T x LEN	
RF3-1	7.6/15.8	0.120	188.2	5x3/16"x182.9		5x1/4" x167.5	
RF3-2	15.6/ 7.6 7.6/ 7.6	0.120 0.120	121.6 167.5	5x3/16"x240.0		5x1/4" x121.8 5x3/16"x164.9	
RF3-3	15.8/ 8.6	0.120	188.0	5x3/16"x182.6		5x1/4" x167.2	



GENERAL NOTES:


* NOTICE TO ERECTOR *

(A)It is IMPORTANT that for members exceeding 30 ft. in length that a spreader bar be used when lifting.

(B)ALL flange braces and wind bracing must be installed prior to exterior finishes being applied.

REVISIONS						DRAWING STATUS				AMERICAN STEEL BLDGS				HAROLD FRANKEL			
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD	[] FOR CONSTRUCTION	[X] FOR PERMIT ONLY	[] FOR APPROVAL	ID	PROJECT	LAKE CITY, FL	DATE: 9/30/05	DRAFT: SPV	CHECK:	SHEET	5

10/7/05



TRIM TABLE			
ROOF PLAN			
OID	MARK	LENGTH	DETAIL
1	RC-R26	3'-0"	TRIM_19



MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
EB-1	8X4CH16	1'-5 1/2"
EB-2	WBX10	2'-4 5/8"
EB-3	WBX10	2'-4 5/8"
EB-4	8X35C16	2'-4 5/8"
EB-5	8X35C16	2'-4 5/8"
EB-6	WBX10	2'-4 5/8"
P-1	8X25Z16	22'-1 1/2"
P-2	8X25Z16	23'-3 1/2"
P-3	8X25Z16	19'-1 1/2"
E-1	BE16	19'-2 1/2"
E-2	BE16	20'-4 1/2"
E-3	BE16	17'-0 1/2"
E-4	8X25C16	20'-8"
E-5	8X25C16	20'-4 1/2"
E-6	8X25C16	17'-8"
E-7	BE16	10"
CB-2	0.250CBL	23'-9"
CB-3	0.250CBL	23'-0"
CB-4	0.250CBL	19'-11"




SEE SHEET 6A FOR
SECTION "B-B"

REVISIONS				DRAWING STATUS				AMERICAN STEEL BLDGS		HAROLD FRANKEL			
REV.	DESCRIPTION	DATE	DLTR	DATE	CHKR	APPD		PROJECT	47.7 x 600 x 16.0	DESIGN	DRAFT	SPV	CHECK
							<input type="checkbox"/> FOR CONSTRUCTION	ID	150708R1				
							<input checked="" type="checkbox"/> FOR PERMIT ONLY	PROJECT	LAKE CITY, FL	DATE: 9/30/05			
							<input type="checkbox"/> FOR APPROVAL	ADDRESS				SHEET	6
							<input type="checkbox"/> OTHER, EXPLAIN						

SEAL




SECTION B-B




1. SEE FRAMING ELEVATIONS FOR GIRTS
2. SEE DETAILS FOR BOLT AND FRAMING REQUIREMENTS
3. FIELD CUT AND WORK GIRTS, PANELS, AND TRIM AS REQUIRED.

(1) FIELD LOCATED 3' x 3' FRAMED OPENING



1. SEE FRAMING ELEVATIONS FOR GIRTS
2. SEE DETAILS FOR BOLT AND FRAMING REQUIREMENTS
3. FIELD CUT AND WORK GIRTS, PANELS, AND TRIM AS REQUIRED.

(6) FIELD LOCATED 3' x 5' FRAMED OPENING



1. SEE DETAILS FOR BOLT AND FRAMING REQUIREMENTS
2. FIELD CUT AND WORK GIRTS, PANELS, AND TRIM AS REQUIRED.


(2) FIELD LOCATED 3070 SUB-JAMBS

REVISIONS					DRAWING STATUS				
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD	[] FOR CONSTRUCTION	[X] FOR PERMIT ONLY	[] FOR APPROVAL
							[] OTHER, EXPLAIN		

PROJECT	AMERICAN STEEL BLDGS	PROJECT	PIPE STRUT & F.D. DETAILS
DATE	9/13/05	DATE	9/13/05
PROJECT	LAKE CITY, FL	PROJECT	LAKE CITY, FL

SEAL

10/17/05




NOTE:
ATTACH WF-1 TO COLUMN
W/ 5/8" x 1 1/2"
A325 BOLTS

SEE FRAME CROSS
SECTION FOR LOCATIONS


6 BOLTS TOTAL

ADDITIONAL HOLES ARE PRESENT FOR
ALIGNMENT PURPOSES ONLY



SIDEWALL FRAMING: FRAME LINE 1

(Gutters with 2 downspouts)



SIDEWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Ga. R - Desert Sand

BOLT TABLE			
FRAME LINE 1		QUAN	TYPE DIA LENGTH
LOCATION			
WF-1 - RF3-3		4	A325 5/8" 1 1/2"

TRIM TABLE		
FRAME LINE 1	LENGTH	DETAIL
1 CTR	16'-2"	TM29
2 RVCB	6"	TM38
3 VGE	20'-3"	TM50
4 RVEG	9'-2"	TM31
5 JTR	9'-3"	TM33
6 HT	20'-3"	
7 RSRT		

MEMBER TABLE		
FRAME LINE 1	PART	LENGTH
WF-1	W12x41	15'-0"
DJ-1	8x35C16	13'-2"
DH-1	8x35C16	9'-0"
E-1	8E16	19'-2 1/2"
E-2	8E16	20'-4 1/2"
E-3	8E16	17'-0 1/2"
G-14	8X25Z13	19'-1 1/4"
G-15	8X25Z16	19'-1 1/4"
G-16	8X25Z13	20'-3 1/4"
G-17	8X25Z16	20'-3 1/4"
G-18	8X25Z16	2'-8"
G-19	8X35Z16	16'-11 1/2"
G-20	8X25Z16	4'-8"

GENERAL NOTES:

1.) IF CABLE BRACING, WIND BENTS, WIND COLUMNS, OR WEAK AXIS DESIGN OF SIDE WALL COLUMNS WERE NOT PROVIDED IT HAS BEEN DETERMINED THAT DIAPHRAGM PANEL ACTION IS SUFFICIENT TO RESIST LONGITUDINAL FORCES. TEMPORARY BRACING SHOULD BE PROVIDED BY ERECTOR UNTIL ALL WALL AND ROOF PANELS ARE INSTALLED.

REVISIONS						DRAWING STATUS						AMERICAN STEEL BLDGS				HAROLD FRANKEL			
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD	[] FOR CONSTRUCTION	[X] FOR PERMIT ONLY	[] FOR APPROVAL	[] OTHER, EXPLAIN		PROJECT	ID	DESIGN	DRAFT	SPV	CHECK	DATE	SHEET
												477 x 600 x 160	15070R1	9/30/05				8	
												LAKE CITY, FL							


SEAL

10/7/05

BOLT TABLE			
FRAME LINE 1		QUAN	TYPE DIA LENGTH
LOCATION		4	A325 1/2" 1 1/4"
Columns			


TRIM TABLE		
FRAME LINE 1	LENGTH	DETAIL
1 DTR	14'-6"	TM1 1
3 VRT	20'-3"	TM1 1
4 VRT	6'-6"	TM1 1
5 VPB	1'-4"	TM39

MEMBER TABLE		
FRAME LINE 1	PART	LENGTH
MARK		
EC-1	W8x41	15'-11 5/8"
EC-2	W8x10	4'-4 5/16"
EC-3	W8x10	8'-0 5/16"
EC-4	W8x10	10'-0 15/16"
EC-5	W8x41	15'-11 5/8"
G-1	8X25Z16	2'-2"
G-2	8X25C14	14'-9 1/2"
G-3	8X25Z16	3'-6"
G-5	8X25Z16	10'-4 1/2"
G-6	8X25Z16	10'-3 7/16"
G-7	8X25C14	12'-3 1/2"
G-8	8X25Z16	5'-6 1/2"
G-9	8X25Z16	10'-3 7/16"



ENDWALL FRAMING: FRAME LINE 1

SEE SHEET 11 FOR
DOOR FRAMING



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Ga. R - Desert Sand

GENERAL NOTES:

(1) IF CABLE BRACING FOR END WALL IS NOT SHOWN ON ERECTION DRAWINGS IT HAS BEEN DETERMINED THAT DIAPHRAGM PANEL ACTION IS SUFFICIENT TO RESIST LONGITUDINAL FORCES. TEMPORARY BRACING SHOULD BE PROVIDED BY ERECTOR UNTIL ALL WALL AND ROOF PANELS ARE INSTALLED.

REVISIONS						DRAWING STATUS					
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPR	[] FOR CONSTRUCTION	[X] FOR PERMIT ONLY	[] FOR APPROVAL	[] OTHER, EXPLAIN	

AMERICAN STEEL BLDGS		HAROLD FRANKEL	
PROJECT	477 x 600 x 160	PROJECT	ENDWALL FRAMING
ID	15070R1	DESIGN	DRAFT SPW
PROJECT ADDRESS	LAKE CITY, FL	DATE: 9/30/05	SHEET 9


Handwritten signature and date:
10/17/05

SEAL



BOLT TABLE				
FRAME LINE 4				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2	8	A325	5/8"	2"
Cor_Column/Ref	4	A325	1/2"	1 1/4"
Int_Column/Ref	4	A325	5/8"	1 1/4"

TRIM TABLE			
FRAME LINE 4			
ID	MARK	LENGTH	DETAIL
1	VRT	20'-3"	TM11
2	VRT	6'-6"	TM11
3	VPB	1'-4"	TM39


MEMBER TABLE			
FRAME LINE 4			
MARK	PART	LENGTH	
EB-4	8x35C16	2'-4 5/8"	
EB-5	8x35C16	2'-4 5/8"	
EC-6	8x35C16	14'-6 5/8"	
EC-7	WBX13	22'-0 1 1/4"	16"
ER-1	10x25C13	25'-2"	
ER-2	10x25C13	25'-2"	
G-10	8x35Z12	22'-7"	
G-11	8x25Z13	22'-7"	
G-12	8x25Z16	22'-7"	
G-13	8x25Z16	18'-6 1/2"	




EAVE EXTENSION DETAIL AT ENDWALL



ENDWALL FRAMING: FRAME LINE 4



F10 RAFTER SPLICE AT SURFACE CHANGE



ENDWALL SHEETING & TRIM: FRAME LINE 4


PANELS: 26 Ga. R - Desert Sand

GENERAL NOTES:
1.) IF CABLE BRACING FOR END WALL IS NOT SHOWN ON ERECTION DRAWINGS IT HAS BEEN DETERMINED THAT DIAPHRAGM PANEL ACTION IS SUFFICIENT TO RESIST LONGITUDINAL FORCES. TEMPORARY BRACING SHOULD BE PROVIDED BY ERECTOR UNTIL ALL WALL AND ROOF PANELS ARE INSTALLED.


REVISIONS						DRAWING STATUS		AMERICAN STEEL BLDGS		HAROLD FRANKEL	
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD	<input type="checkbox"/> FOR CONSTRUCTION	<input checked="" type="checkbox"/> FOR PERMIT ONLY	PROJECT	47.7 x 600 x 16.0	ENDWALL FRAMING
							<input type="checkbox"/> FOR APPROVAL		ID	1507081	DESIGN:
							<input type="checkbox"/> OTHER, EXPLAIN		PROJECT	LAKE CITY, FL	DRAFT: SPV
							-----		ADDRESS		CHECK:
											DATE: 9/30/05
											SHEET 10

SEAL


10/7/07




U2 BOLTED END PLATE CONNECTION AT BUILDING PEAK



U3 BOLTS FOR RAFTER TO COLUMN CONNECTION



W8 SECTION OF ENDWALL GIRT TO RAFTER



RIDGE VENT INSTALLATION DETAIL

ridgevent

REVISIONS						DRAWING STATUS				AMERICAN STEEL BLDGS		HAROLD FRANKEL					
REV.	DESCRIPTION	DATE	DLR	DATE	CHKR	APPD	() FOR CONSTRUCTION	(X) FOR PERMIT ONLY	() FOR APPROVAL	() OTHER, EXPLAIN	PROJECT	ID	Detail Page	DESIGN	DRAFT	SPV	CHECK
											LAKE CITY, FL	15070R1					

SEAL

10/17/05