



FRONT ELEVATION




REAR ELEVATION WINDOW



RIGHT SIDE ELEVATION

WINDOW



LEFT SIDE ELEVATION

WINDOW

GENERAL NOTES

- APPLICABLE CODES, REGULATIONS, & STANDARDS
 - THE 2020 FLORIDA BUILDING CODE, 7TH EDITION
 - ASCE/SEI 7-16: MINIMUM DESIGN LOADS ON BUILDINGS AND OTHER STRUCTURES
 - ACI 318-14: BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
- THESE PLANS BELONG EXCLUSIVELY TO THE STRUCTURE, INCLUDING MAIN WIND FORCE RESISTING SYSTEM (MWFRS), COMPONENTS AND CLADDING (C&C), AND BASE RAIL ANCHORAGE. OTHER DESIGN ISSUES, INCLUDING BUT NOT LIMITED TO PROPERTY SET-BACKS, ELECTRICAL, PLUMBING, INGRESS/EGRESS, FINISH FLOOR SLOPES AND ELEVATIONS, OR OTHER LOCAL ZONING REQUIREMENTS ARE THE LIABILITY OF OTHERS.
- THESE STRUCTURES ARE ENGINEERED AS (RISK CATEGORY 2) CAPABLE OF SUPPORTING DEAD LOAD OF THE STRUCTURE AND LIVE AND WIND LOADS. UPGRADES NOT SPECIFICALLY ADDRESSED HEREIN, SUCH AS WINDOWS, DOORS, OR ANOTHER COMPONENT NOT LISTED IN THE FLORIDA BUILDING CODE APPROVED PRODUCT LIST, AND NOT PROVIDED AND INSTALLED BY TUBULAR BUILDING SYSTEMS, WHICH CAUSE ADDITIONAL LOADS ON THE STRUCTURE SHALL BE AT THE OWNER'S RISK. FLORIDA ENGINEERING LLC, SHALL NOT BE RESPONSIBLE FOR FAILURE OR STRUCTURAL DAMAGE DUE TO THE EXTRA LOAD.
- LOW ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 5.0 FEET.
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
- ALL STEEL TUBING SHALL BE 50 KSI GALVANIZED STEEL. ALL FASTENERS SHALL BE ZINC COATED HARDWARE.
- SPECIFICATIONS APPLICABLE TO 29 GAUGE METAL PANELS FASTENED DIRECTLY TO 2 1/2" x 2 1/2" - 14 GAUGE TUBE STEEL (TS) FRAMING MEMBERS FOR VERTICAL PANELS, 29 GAUGE METAL PANELS SHALL BE FASTENED TO 18 GAUGE HAT CHANNELS (UNLESS OTHERWISE NOTED).
- FASTENERS CONSIST OF #12-14 x 3/4" SELF DRILLING FASTENER (SDF), USE CONTROL SEAL WASHER WITH EXTERIOR FASTENERS SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14" (3:12 PITCH) OR LESS SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, AND POSTS, INTERIOR = 9" OR END = 6", (MAX.).
- WIND FORCES GOVERN OVER SEISMIC FORCES. SEISMIC PARAMETERS ANALYZED ARE:
SOIL SITE CLASS = D
RISK CATEGORY II/III
R = 3.25 Ie = 1.0
Sds = 0.087 g V = CsW
Sdi = 0.084 g
- GROUND ANCHORS SHALL BE INSTALLED THROUGH BASE RAIL WITHIN 6" OF EACH RAFTER COLUMN ALONG SIDES.
- GROUND ANCHOR (SOIL NAILS) CONSIST OF #5 REBAR W/ WELDED NUT X 30" LONG IN SUITABLE SOIL CONDITIONS MAY BE USED FOR LOW (≤ 108 MPH NOMINAL) WIND SPEEDS ONLY. OPTIONAL ANCHORAGE MAY BE USED IN SUITABLE SOILS AND MUST BE USE IN UNSUITABLE SOILS AS NOTED.
- MIN. LAP REQUIREMENT FOR REBAR IN FOOTER IS 25".
- SOIL TO BE COMPACTED TO 95% OF ITS MAXIMUM DRY DENSITY, AT OPTIMUM MOISTURE CONTENT, IN ACCORDANCE WITH ASTM D1557-93
- PRIOR TO PLACING CONCRETE, TREAT THE ENTIRE SUBSURFACE AREA FOR TERMITES IN COMPLIANCE WITH THE FBC. FOR RISK CATEGORY II, III, & IV STRUCTURES ONLY.
- ALL OPEN AREAS OF CONCRETE OUTSIDE OF THE PROPOSED STRUCTURE SHALL BE DESIGNED TO SLOPE AWAY FROM THE STRUCTURE.
- A LANDING OF MIN. 36" WIDTH IN THE DIRECTION OF TRAVEL SHALL BE PROVIDED AT THE EXTERIOR DOORS. SLOPE OF LANDING NOT TO EXCEED 1/4"-1". LANDING LEVEL NOT TO BE LOWER THAN 1-1/2" (FOR EGRESS DOORS) & 7-3/4" (FOR OTHER EXTERIOR DOORS) BELOW THE TOP OF THRESHOLD.


PRODUCT CATEGORY	SUB CATEGORY	MANUFACTURER	APPROVAL No. & DATE
STRUCTURAL COMPONENTS	ROOF DECK	CAPITAL METAL SUPPLY, INC. 29 GA. CAPITAL RIB ROOF PANEL	FL20147.2-R2 10/13/20
STRUCTURAL COMPONENTS	STRUCTURAL WALL	CAPITAL METAL SUPPLY, INC. 29 GA. CAPITAL RIB WALL PANEL	FL20148.2-R2 10/13/20
EXTERIOR DOORS	SWINGING	PLASTPRO INC. / NANYA PLASTICS CORP. A. SMOOTH/WOOD GRAIN/RUSTIC/ MAHOGANY SERIES N FIBERGLASS DOOR	FL15220.1-R4 10/11/22
EXTERIOR DOORS	SWINGING	PLASTPRO INC. / NANYA PLASTICS CORP. D. SMOOTH/WOOD GRAIN/RUSTIC/ MAHOGANY SERIES N FIBERGLASS DOOR	FL15220.4-R4 10/11/22
WINDOWS	SINGLE HUNG	SIMONTON 41-18	FL5414.1-R33 11/03/22

CTP = CONTRACTOR TO PROVIDE APPROVED PRODUCTS THAT MEET OR EXCEED WIND DESIGN PRESSURES.

PROPOSED METAL BUILDING FOUNDATION & SHELL STRUCTURAL DESIGN ONLY. ALL OTHER REQUIRED PERMITS TO BUILD OUT TO A HABITABLE LIVING SPACE ARE TO BE BY OTHERS/ PER SEPERATE CERTIFICATE. INCLUDING BUT NOT LIMITED TO, ELECTRICAL, PLUMBING, ENERGY CALCS., ETC. FOR MORE INFORMATION VISIT:
<https://flengineeringllc.com/order/> OR SCAN QR CODE.




3-D FINITE ELEMENT ANALYSIS PERFORMED
STRUCTURE COMPLIES W/ FBC 2020 7th EDITION




DESIGN DATA																																																			
DESIGN CRITERIA:	ASCE/SEI 7																																																		
RISK CATEGORY :	II																																																		
BUILDING CLASSIFICATION :	R3																																																		
CONSTRUCTION TYPE:	II-B																																																		
MAXIMUM DISPLACEMENT =	L/240																																																		
ULTIMATE DESIGN WIND SPEED (MPH) V _{ULT} =	120																																																		
NOMINAL DESIGN WIND SPEED (MPH) V _{ASD} =	93																																																		
EXPOSURE CATEGORY:	C																																																		
MEAN BUILDING HEIGHT (FT) =	12.38																																																		
MINIMUM BUILDING PLAN DIMENSION (FT) =	38.00																																																		
END ZONE DIMENSION (FT) a =	3.80																																																		
ROOF STYLE:	GABLE																																																		
ROOF PITCH:	3.00		IN 12																																																
OCCUPANCY CLASSIFICATION:	PARTIALLY OPEN																																																		
DEAD LOAD =	5 PSF																																																		
ROOF LIVE LOAD =	10 PSF																																																		
ADJUSTED C & C WIND PRESSURES (ASD) (PSF)																																																			
<table><tr><th>ROOF</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">481.33</td></tr><tr><td>Zone 1'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 1</td><td>7.7</td><td>-10.9</td></tr><tr><td>Zone 2'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 2</td><td>7.7</td><td>-18.9</td></tr><tr><td>Zone 3'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 3</td><td>7.7</td><td>-31.7</td></tr></table>			ROOF	EWA (FT ²)			481.33		Zone 1'	NA	NA	Zone 1	7.7	-10.9	Zone 2'	NA	NA	Zone 2	7.7	-18.9	Zone 3'	NA	NA	Zone 3	7.7	-31.7	<table><tr><th>ROOF O/H</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">481.33</td></tr><tr><td>Zone 1'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 1</td><td>NA</td><td>-22.2</td></tr><tr><td>Zone 2'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 2</td><td>NA</td><td>-30.2</td></tr><tr><td>Zone 3'</td><td>NA</td><td>NA</td></tr><tr><td>Zone 3</td><td>NA</td><td>-42.9</td></tr></table>	ROOF O/H	EWA (FT ²)			481.33		Zone 1'	NA	NA	Zone 1	NA	-22.2	Zone 2'	NA	NA	Zone 2	NA	-30.2	Zone 3'	NA	NA	Zone 3	NA	-42.9
ROOF	EWA (FT ²)																																																		
	481.33																																																		
Zone 1'	NA	NA																																																	
Zone 1	7.7	-10.9																																																	
Zone 2'	NA	NA																																																	
Zone 2	7.7	-18.9																																																	
Zone 3'	NA	NA																																																	
Zone 3	7.7	-31.7																																																	
ROOF O/H	EWA (FT ²)																																																		
	481.33																																																		
Zone 1'	NA	NA																																																	
Zone 1	NA	-22.2																																																	
Zone 2'	NA	NA																																																	
Zone 2	NA	-30.2																																																	
Zone 3'	NA	NA																																																	
Zone 3	NA	-42.9																																																	
<table><tr><th>WALL</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">33.33</td></tr><tr><td>Zone 4</td><td>17.4</td><td>-19.0</td></tr><tr><td>Zone 5</td><td>17.4</td><td>-22.4</td></tr></table>			WALL	EWA (FT ²)			33.33		Zone 4	17.4	-19.0	Zone 5	17.4	-22.4																																					
WALL	EWA (FT ²)																																																		
	33.33																																																		
Zone 4	17.4	-19.0																																																	
Zone 5	17.4	-22.4																																																	
<table><tr><th>SWING DOOR</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">20.00</td></tr><tr><td>Zone 4</td><td>18.1</td><td>-19.7</td></tr><tr><td>Zone 5</td><td>18.1</td><td>-23.6</td></tr></table>			SWING DOOR	EWA (FT ²)			20.00		Zone 4	18.1	-19.7	Zone 5	18.1	-23.6	<table><tr><th>ROLL-UP DOOR</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">40.00</td></tr><tr><td>Zone 4</td><td>17.2</td><td>-18.8</td></tr><tr><td>Zone 5</td><td>17.2</td><td>-21.9</td></tr></table>	ROLL-UP DOOR	EWA (FT ²)			40.00		Zone 4	17.2	-18.8	Zone 5	17.2	-21.9																								
SWING DOOR	EWA (FT ²)																																																		
	20.00																																																		
Zone 4	18.1	-19.7																																																	
Zone 5	18.1	-23.6																																																	
ROLL-UP DOOR	EWA (FT ²)																																																		
	40.00																																																		
Zone 4	17.2	-18.8																																																	
Zone 5	17.2	-21.9																																																	
<table><tr><th>WINDOW</th><th colspan="2">EWA (FT²)</th></tr><tr><td></td><td colspan="2">15.00</td></tr><tr><td>Zone 4</td><td>18.4</td><td>-20.0</td></tr><tr><td>Zone 5</td><td>18.4</td><td>-24.3</td></tr></table>			WINDOW	EWA (FT ²)			15.00		Zone 4	18.4	-20.0	Zone 5	18.4	-24.3																																					
WINDOW	EWA (FT ²)																																																		
	15.00																																																		
Zone 4	18.4	-20.0																																																	
Zone 5	18.4	-24.3																																																	

This item has been electronically signed and sealed by Craig E. Gunderson, P.E. on date below using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



Digitally signed by
Craig E Gunderson
Date:
2023.10.17
13:29:58-04'00'

FLORIDA ENGINEERING LLC
4161 TAMiami TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com



CA CERT. #30782

PROJECT NO. 2327222

CONTRACTOR:
TUBULAR BUILDING SYSTEMS

PROJECT ADDRESS:
PLUMB LEVEL CABRAL
PID #30-5S-18-10609-000

DESIGN DATE: 10/16/2023

REVISION 1: DATE

REVISION 2: DATE


DRAWN BY: TCP

SCALE: NTS

SHEET:

01


This item has been electronically signed and sealed by Craig E. Gunderson, P.E. on date below using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.




Digitally signed by
Craig E Gunderson

Date:
2023.10.17
13:29:59-04'00'

GALVANIZED METAL WALL PANELS FASTENED TO POSTS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS





1.5" 18 GAUGE FURRING CHANNEL SPACED AT 4'-0" (MAX.) O.C. AND FASTENED TO EACH RAFTER WITH (2) #12-14 x 3/4" SDF'S





GALVANIZED METAL WALL PANELS FASTENED TO POSTS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS

12"X20" MONOLITHIC FOOTER 12" BELOW GRADE W/ 2 - #5 REBARS CONT. SEE SHEET/ 03




GALVANIZED METAL WALL PANELS FASTENED TO POSTS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS


GALVANIZED METAL WALL PANELS FASTENED TO POSTS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS



ROOF PANEL ATTACHMENT
SCALE: NTS




BEAM CROSS SECTION
SCALE: NTS



GALVANIZED METAL ROOF PANELS FASTENED TO PURLINS ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS

FLORIDA ENGINEERING LLC
4161 TAMiami TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com



CA CERT. #30782


PROJECT NO. 2327222

CONTRACTOR:
TUBULAR BUILDING SYSTEMS

PROJECT ADDRESS:
PLUMB LEVEL CABRAL
PID #30-5S-18-10609-000

DESIGN DATE: 10/16/2023
REVISION 1: DATE
REVISION 2: DATE
DRAWN BY: TCP
SCALE: NTS

SHEET:
02



1 12'x12' MONO. FOOTER BASE RAIL ANCHORAGE
SCALE: NTS

GENERAL NOTES

CONCRETE:

CONCRETE SHALL HAVE A MINIMUM SPECIFIED COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS.

COVERAGE OF THE REINFORCED STEEL:

FOR FOUNDATIONS, MINIMUM CONCRETE COVER OVER REINFORCING BARS SHALL BE PER ACI-318: 3 INCHES WHERE THE CONCRETE IS POURED AGAINST AND TEMPORARY IN CONTACT WITH THE EARTH OR UNPROTECTED FROM THE EARTH OR WEATHER, OTHERWISE 1-1/2 INCHES.

CONCRETE NOTE:


ALL OPEN AREAS OF CONCRETE OUTSIDE OF THE PROPOSED STRUCTURE SHALL BE DESIGNED TO SLOPE AWAY FROM THE STRUCTURE

REINFORCING STEEL:


THE TURNDOWN REINFORCING STEEL SHALL BE ASTM A615 GRADE 60. THE SLAB REINFORCEMENT SHALL BE WELDED WIRE FABRIC, MEETING ASTM A185 OR FIBERGLASS FIBER REINFORCEMENT.

REINFORCEMENT MAY BE BENT IN THE FIELD OR SHOP AS LONG AS:


1. IT IS BENT COLD;
2. REINFORCEMENT PARTIALLY EMBEDDED IN CONCRETE SHALL NOT BE FIELD BENT;
3. THE DIAMETER OF THE BEND, MEASURED ON THE INSIDE OF THE BAR, IS NOT LESS THAN SIX-BAR DIAMETERS.




2 END POST/RAFTER CONNECTION DETAIL
SCALE: NTS




3 RAFTER POST/BASE RAIL CONNECTION DETAIL
SCALE: NTS




3A RAFTER POST/BASE RAIL CONNECTION DETAIL
SCALE: NTS




4 END POST/BASE RAIL CONNECTION DETAIL
SCALE: NTS




5 POST TO NON-STRUCTURAL HEADER, BASE, RAIL OR WINDOW RAIL CONNECTION DETAIL
SCALE: NTS




6 POST TO NON-STRUCTURAL HEADER, BASE, RAIL OR WINDOW RAIL CONNECTION DETAIL
SCALE: NTS




7 NON-STRUCTURAL HEADER OR WINDOW RAIL TO POST CONNECTION DETAIL
SCALE: NTS




8 CHORD/RAFTER CONNECTION DETAIL
SCALE: NTS




9 TRUSS POST AND CORD TO RAFTER CONNECTION DETAIL
SCALE: NTS




10 RAFTER/LEG ASSEMBLY CONNECTION DETAIL
SCALE: NTS



11 SPLICE CONNECTION DETAIL
SCALE: NTS




12 COLUMN OR WINDOW RAIL TO POST CONNECTION DETAIL
SCALE: NTS



13 COLUMN/DOUBLE HEADER CONNECTION DETAIL
SCALE: NTS


This item has been electronically signed and sealed by Craig E. Gunderson, P.E. on date below using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



Digitally signed by
Craig E Gunderson

Date:
2023.10.17
13:30:01-04'00'

FLORIDA ENGINEERING LLC
4161 TAMiami TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com



PROJECT NO. 2327222

CA CERT. #30782

CONTRACTOR:
TUBULAR BUILDING SYSTEMS

PROJECT ADDRESS:
PLUMB LEVEL CABRAL
PID #30-5S-18-10609-000

DESIGN DATE: 10/16/2023

REVISION 1: DATE

REVISION 2: DATE

DRAWN BY: TCP

SCALE: NTS

SHEET:

03