

## DESIGN SPECIFICATIONS

**DESIGN CODE:**  
2023 FLORIDA BUILDING CODE - RESIDENTIAL

**DESIGN IS VOID ONE YEAR AFTER THE DATE OF THE ORIGINAL PLANS, UNLESS PLANS HAVE BEEN REVISED FOR CODE COMPLIANCE.**

**DESIGN LOADS:** ACTUAL AND UNIFORM

**FLOOR**

ROOF LOADING	ROOF
TOP CHORD LIVE LOAD	(cd=1.25)
TOP CHORD DEAD LOAD	40 psf
TOP CHORD DEAD LOAD	7 psf (ARCH SHINGLES)
TOP CHORD DEAD LOAD	20 psf (TILE SHINGLES)
BOTTOM CHORD LIVE LOAD	10 psf
BOTTOM CHORD DEAD LOAD	5 psf

**DEFLECTION CRITERIA:**  
ROOF FRAMING: LIVE LOAD L/240 TOTAL LOAD L/180  
FLOOR FRAMING: LIVE LOAD L/360 & TOTAL LOAD L/240  
0.75" MAX ANY CASE

**WIND LOADING:**  
ASCE 7/22 FOR WIND UPLIFT, TRUSSES SHALL BE DESIGNED WITH A MIN. HEAD LOAD CONDITION OF 5 PSF TOP CHORD AND 5 PSF BOTTOM CHORD. REACTIONS CALCULATED FOR THE BEARING POINTS OF ROOF TRUSSES SHALL BE REDUCED, SPECIFICALLY, AT TIC FLOOR LIVE LOADS COMBINED WITH ROOF LIVE LOADS SHALL BE MULTIPLIED BY 0.75 WHEN COMBINED w/ DEAD LOAD.

**BASIC WIND SPEED (ASCE 7-22)** **130 MPH**

**IMPORTANCE FACTOR** 1.00

**MEAN ROOF HEIGHT** 20.0 FT

**ROOF PITCH** 8/12

**BUILDING CATEGORY** C

**EXPOSURE CATEGORY** C

**ENCLOSURE CLASSIFICATION** enclosed

**INTERNAL PRESSURE COEFFICIENT** ± 0.18

## COMPONENTS & CLADDING ALLOWABLE DESIGN PRESSURES

TRIBUTARY AREA (sf)	INTERIOR		EDGE STRIP (PSF)	
	ZONE (PSF)	'a' = 6'-6"	PSF	PSF
10	+25.5	-27.7	+25.5	-34.2
50	+22.9	-25.0	+22.9	-28.8
100	+21.8	-23.2	+21.8	-26.5

**THE VALUES ABOVE ARE ALLOWABLE WIND PRESSURE VALUES (ASD). THE ABOVE WIND PRESSURES HAVE BEEN REDUCED BY 0.60 AS PERMITTED BY THE ALLOWABLE STRESS DESIGN METHODOLOGY. NO FURTHER REDUCTION SHALL BE PERMITTED.**

**COMPONENT & CLADDING WALL ELEMENTS SHALL BE DESIGNED FOR BOTH POSITIVE AND NEGATIVE PRESSURES SHOWN IN TABLE ABOVE.**

**LINEAR INTERPOLATION IS PERMISSIBLE.**

**PLUS = PRESSURE AND MINUS = SUCTION.**

**DESIGN OF WINDOWS/DOORS FASTENING TO THE WALL FRAMING IS THE RESPONSIBILITY OF THE WINDOW/DOOR MANUF./SUPPLIER & SHALL MEET THE ABOVE NOTED POSITIVE AND NEGATIVE PRESSURES.**

## USP CONNECTORS

CONNECTOR	UPLIFT		FASTENERS	FL# CODE
	SYP	SPF		
USP A35	450	450	(9)10dX1 1/2"	
USP R17	585	495	(5)8d EA. END	
USP R18A	775	650	(5)10dX1 1/2" EA. END	
USP MTW12	1195	860	(7)10dX1 1/2" EA. END	
USP MSTA24	1640	1455	(9)10d EA. END	
USP MSTA36	2065	2065	(13)10d EA. END	
USP L1520B	1105	1105	1/2" ROD TO FTG.	
USP AJ528	1305	1305	(6)10d TO HEADER	
USP HT116	4290	4290	3/4" ROD TO FTG.	
USP HT122	5370	5370	3/4" ROD TO FTG.	
USP PAU44	2535		3/4" ROD W/ (12)16d	
USP PAU66	2535		3/4" ROD W/ (12)16d	
USP MSTM24	1545	1455	(5)1/2" X 1/4" TAPCONS	

## SIMPSON CONNECTORS

CONNECTOR	UPLIFT		FASTENERS	FL# CODE
	SYP	SPF		
A35	450	450	12-8dX1 1/2"	10446.4
H2.5T	600	520	5-8d EA. END	11478.3
HTS16	1150	1085	16-10d EA. END	10456.6
MTS12	1000	860	7-10dX1 1/2" EA. END	10456.3
HTS20	1450	1245	24-10dX1 1/2" EA. END	13872.3
MSTA24	1765	1270	9-10d EA. END	13872.4
MSTA36	2050	1870	13-10d EA. END	13872.8
HTT4	3480	3080	18-16d TO TRUSS/BREAM	11496.2
			1-3/4" ROD TO FTG.	
HTT5	5250	4670	32-16d TO TRUSS/BREAM	11496.2
			1-3/4" ROD TO FTG.	
LUS28	930	780	6-10d TO HEADER	10655.113
			4-10d TO JOIST	
HU410	905	785	16-16d TO HEADER	10531.36
			6-16d TO JOIST	
ABU44	2200		3/4" ROD EPOXIED 6" MIN	10849.6
ABU66	2300		3/4" ROD EPOXIED 6" MIN	10849.6
SET	N/A	N/A	SIMPSON EPOXY-TIE	11506.4
LTT20B	1675	1675	10-16d TO STUD/BREAM/POST	11496.3
			1-1/2" ROD TO FTG.	
LSTAT2	805	695	10-10d	13872.5
CS16	1705	1705	13-8d	10852.1

## MATERIAL SPECIFICATIONS

**HARDWARE AND ANCHORS:**  
**ANCHOR BOLTS & THREADED ROD:** SHALL BE IN ACCORDANCE WITH ASTM A 307 OR ASTM F 1554 GRADE 36.  
**WASHERS:** SHALL BE IN ACCORDANCE WITH ASTM A500 (GRADE B).  
**NUTS:** SHALL BE IN ACCORDANCE WITH ASTM A 563 GRADE A HEX.  
**METAL CONNECTORS:** ALL METAL CONNECTORS WHICH ARE EXPOSED TO EXTERIOR SHALL BE GALVANIZED.  
**REINFORCING BAR/ROD INSTALLATION:** EMBEDMENT OF RODS OR REBAR DOWELS SHALL BE 12 BAR DIAMETER MINIMUM. HOLES SHALL BE 1/4" LARGER THAN REBAR SIX AND 1/2" LARGER THAN THREADED ROD SIZE (O.D.).  
**ANCHORING ADHESIVE:** SHALL BE ONE OF THE FOLLOWING PRODUCTS (DUAL CARTRIDGE INSTALLATION ONLY):  
**EPOXY:** ITW RED HEAD A7  
**REINFORCING STEEL:** SHALL BE ASTM A615, GRADE 60.  
**STRUCTURAL STEEL:** SHALL BE ASTM A992, GRADE 50.  
**WELDED WIRE FABRIC (W/F):** SHALL BE ASTM A185.  
**LAMINATED VENEER LUMBER (LVL):** ALL LAMINATED VENEER LUMBER SHALL MEET OR EXCEED THE FOLLOWING DESIGN PROPERTIES - ELASTIC MODULUS (E), 900ksi; BENDING STRESS (Fb) 2600psi

## SCOPE OF SERVICE

**MEANS AND METHODS:**  
THE STRUCTURAL ENGINEER SHALL NOT HAVE CONTROL OR BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, PROCEDURES, OR SEQUENCES FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR OR ANY OTHER PERSONS PERFORMING THE WORK OR FOR THE FAILURE FOR ANY OF THEM TO CONSTRUCT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

**LIMITS OF STRUCTURAL ENGINEERING RESPONSIBILITIES:**  
THE ITEMS SPECIFICALLY DESIGNED BY THE STRUCTURAL ENGINEER ARE LIMITED TO THE FOLLOWING: CONTINUOUS LOAD PLAN FOR WIND UPLIFT, WOOD PANEL SHEARWALLS, WALL FRAMING AND REQUIRED SHEATHING AND HEADERS DIRECTLY SUPPORTING ROOF FRAMING, ITEMS NOT DESIGNED PRE-ENGINEERED WOOD FLOOR AND ROOF TRUSSES, FLOOR FRAMING NOT SPECIFICALLY ADDRESSED, TRUSS-TO-TRUSS CONNECTION, AND ANY ARCHITECTURAL, MECHANICAL OR ELECTRICAL SYSTEM.

## GENERAL NOTES & CONSTRUCTION SPECIFICATIONS

**FLOOR SHEATHING SPECIFICATIONS:**  
23/32" 1&6 OSB OR PLYWOOD SHEATHING, GLUE AND NAIL WITH 10d COMMON @ 6" O.C. EDGE & FIELD

**ROOF SHEATHING SPECIFICATIONS:**  
**SHINGLE** - MIN. 15/32", 32/16, APA RATED OSB OR PLYWOOD SHEATHING, NAILED w/ 0.131x2" RING SHANK NAILS @ 6" O.C. EDGE & 6" O.C. FIELD (AT GABLE ENDS DECREASE EDGE NAIL SPACING TO 4" O.C. WITHIN 4'-0" OF ROOF EDGE).  
**TILE** - MIN. 15/32" 32/16, APA RATED PLYWOOD SHEATHING, NAILED w/ 0.131x2" RING SHANK @ 6" O.C. EDGE & 6" O.C. FIELD (AT GABLE ENDS DECREASE EDGE NAIL SPACING TO 4" O.C. WITHIN 4'-0" OF ROOF EDGE).  
**METAL** - MIN. 1/2", 32/16, APA RATED PLYWOOD SHEATHING, NAILED w/ 0.131x2 1/2" RING SHANK NAILS @ 6" O.C. EDGE & 6" O.C. FIELD (AT GABLE ENDS DECREASE EDGE NAIL SPACING TO 4" WITHIN 4'-0" OF ROOF EDGE).

**WALL SHEATHING SPECIFICATIONS:**  
**FLEXIBLE FINISH** - MIN. 7/8", 24/16, APA RATED OSB OR PLYWOOD SHEATHING, FASTENED w/ 8d @ 6" O.C. EDGE AND 6" O.C. FIELD. SHEATHING SHALL EXTEND FULL HEIGHT FROM BOTTOM PLATE TO UPPER TOP PLATE. FLEXIBLE FINISH INCLUDES: WOOD, CEMENT, OR VINYL SIDING, HARDI PANEL & BRICK. ALL OTHER WALL SHALL BE CONSIDERED BRITTLE FINISH.  
**STUCCO FINISH** - MIN. 7/8", 24/16, APA RATED OSB OR PLYWOOD SHEATHING, FASTENED w/ 8d @ 6" O.C. EDGE AND 6" O.C. FIELD. SHEATHING SHALL ORIENTED WITH THE LONG DIMENSION PERPENDICULAR TO THE STUDS. CONTRACTOR MAY USE 3/8" STRUCTURAL 1 GRADE SHEATHING OR 3/8" OSB SHEATHING AND ORIENT THE PANELS VERTICALLY.

**MASONRY SPECIFICATIONS:**  
MASONRY HAS BEEN DESIGNED IN ACCORDANCE WITH ACI 530-05, AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH ACI 530.1-05. GROUT SHALL BE IN ACCORDANCE WITH ASTM C476 WITH A MINIMUM OF 28 DAY COMPRESSIVE STRENGTH OF 2000 psi PER ASTM C1019. GROUT SHALL HAVE A MAXIMUM COURSE AGGREGATE SIZE OF 3/8" PLACED AT AN 8" TO 11" SLUMP. MORTAR SHALL CONFORM TO ASTM C270 AND TYPE M OR S. TYPE N MORTAR MAY BE USED IN BRICK VENEER. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ALL FLASHING.

**CONCRETE MASONRY UNITS (CMU):**  
CMU SHALL BE IN ACCORDANCE WITH ASTM C90-75, HOLLOW LOAD-BEARING (CMU), TYPE 1, GRADE N-1, NORMAL WEIGHT, WITH A MINIMUM COMPRESSIVE STRENGTH OF 1900 psi (f'm=1500 psi). GROUT ALL CELLS CONTAINING VERTICAL REINFORCEMENT IN 5'-0" MAXIMUM LISTS PROVIDE CLEANOUTS PER ACI 530.1-02 IN THE BOTTOM OF COURSE OF MASONRY WHEN THE WALL HEIGHT EXCEEDS 5'-0".

**MASONRY STEMWALLS:** ALL CONCRETE MASONRY UNITS SHALL BE COMPOSED OF ASTM C90E, E GRADE N-1 HOLLOW CONCRETE MASONRY UNITS WITH TYPE "S" MORTAR. WALL COURSING SHALL BE RUNNING BONDS, STACK BOND SHALL NOT BE USED. GROUT ALL CELLS CONTAINING REINFORCEMENT WITH 3000 PSI PEAK ROOF CONCRETE GROUT. SPLICES IN REINFORCING, WHERE PERMITTED, SHALL BE 48 BAR DIAMETERS. ALL EXTERIOR WALLS SHALL BE REINFORCED FULL HEIGHT WITH #4 @ 4'-0" O.C. MAX. AND AT EACH CORNER WALL END, AND WALL INTERSECTIONS PROVIDE CONTINUITY OF REINFORCING AT INTERSECTIONS OF PERPENDICULAR MASONRY ELEMENTS BY INSTALLING CORNER BARS, MINIMUM OF 40 BAR DIAMETERS INTO EACH ELEMENT, AT STEMWALL CONSTRUCTED OF 5 OR MORE COURSES, PROVIDE HORIZONTAL JOINT REINFORCEMENT AT 16" O.C. VERTICALLY, (EVERY OTHER COURSE), AND VERTICAL REINFORC. SHALL BE INCREASED AS NOTED ON A 1/5.0. UNLESS NOTED OTHERWISE, LAP JOINT REINFORCING SHALL BE A MINIMUM OF 6".

**CONCRETE SPECIFICATIONS:**  
ALL CONCRETE HAS BEEN DESIGNED IN ACCORDANCE WITH ACI 318-08, AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH ACI 301. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS CONCRETE AT GARAGE AND PORCH SLABS SHALL HAVE A COMPRESSIVE STRENGTH OF 3000 PSI.

**GENERAL NOTES:**  
**FOOTINGS AND FOUNDATIONS:**  
FOOTINGS AND FOUNDATIONS SHALL BE IN ACCORDANCE WITH LOCAL BUILDING CODES. FOOTING HAVE BEEN DESIGNED WITH A SOIL BEARING (DESIGN MAXIMUM) OF 2000 PSF. A SOILS INVESTIGATION REPORT IS RECOMMENDED TO VERIFY SUITABLE SUBSURFACE CONDITIONS. IF THE FOOTING ELEVATIONS SHOWN OCCUR IN A DISTURBED OR UNSTABLE SOIL, THE ENGINEER SHALL BE NOTIFIED. SOIL SHALL BE FREE OF ORGANIC MATERIAL AND COHESIVE (CLAY) SOILS. SOIL COMPACTION AND FILL SHALL BE COMPACTED TO A MIN. OF 95% MODIFIED PROCTOR IN ACCORDANCE WITH ASTM D 1557.

FOUNDATION PLAN ONLY CONVEYS STRUCTURAL INFORMATION. FOR GENERAL FEATURES, CONDUITS, ELECTRICAL EMBEDS, STEP HEIGHTS, ETC., SEE ARCHITECTURAL PLANS. DO NOT SCALE FOOTING DIMENSIONS AND LOCATION FROM THE FOUNDATION PLAN SHOWN ON S1.0. DO NOT DETERMINE FOOTING LOCATION BASED ON EITHER THE ARCHITECTURAL PLAN OR FRAMING PLAN, BUT BY DIMENSIONS PROVIDED ON FOUNDATION PLAN. IF FOOTING SIZE OR LOCATION IS NOT DETERMINED ON PLAN THEN CONTACT ENGINEER OF RECORD (EOR)

UNLESS OTHERWISE NOTED ON DRAWINGS, MINIMUM CONCRETE COVER FOR REINFORCING SHALL BE 3" IN FOOTINGS AND MESH SHALL BE CENTERED IN SLAB ON GRADE, IN ALL CONTINUOUS FOOTINGS PROVIDE #3 @ 48" O.C. OR ROD CHAIRS, PROVIDE CONTINUITY OF REINFORCING AT INTERSECTIONS OF PERPENDICULAR CONCRETE ELEMENTS BY INSTALLING CORNER BARS, MINIMUM OF 40 BAR DIAMETERS INTO EACH ELEMENT, SPLICES IN REINFORCING, WHERE PERMITTED, SHALL BE 48 BAR DIAMETERS

**CONCRETE SLABS ON GRADE:**  
SHALL BE INSTALLED OVER MINIMUM 6 MIL POLYETHYLENE VAPOR RETARDER WITH JOINTS LAPPED 6" AND SEALED OVER CLEAN, COMPACTED EARTH OR FILL WITH APPROVED CHEMICAL SOIL TREATMENT FOR PREVENTION OF SUBTERRANEAN TERMITES. SAWCUTS FOR CONTROLLED CRACKING CUT A 1" SAWCUT INTO SLAB IN A 12"x12" GRID WITHIN 12 HOURS OF CONCRETE PLACEMENT, PROVIDE SAWCUTS THROUGHOUT SLAB CALL FOR ALTERNATIVE METHODS.

**WOOD FRAMING SPECIFICATIONS:**  
ALL WOOD FRAMING HAS BEEN DESIGNED IN ACCORDANCE WITH NATIONAL DESIGN SPECIFICATIONS (NDS) FOR WOOD CONSTRUCTION, LATEST EDITION. ALL WOOD MEMBERS EXPOSED TO WEATHER OR IN CONTACT WITH MASONRY, CONCRETE OR SOIL SHALL BE PRESSURE-TREATED TO F-400 OR NON-BOT BOARD PRESERVATIVE TREATMENT IS USED. ALL ATTACHED FASTENERS SHALL BE HOT DIPPED GALVANIZED. IF AZECA PRESERVATIVE IS USED, ALL ATTACHED FASTENERS SHALL BE STAINLESS STEEL.

**PRE-ENGINEERED WOOD TRUSSES:**  
SHALL BEAR THE LOAD OF AN ENGINEER IN THE STATE WHERE PROJECT IS BEING BUILT AND SHALL COMPLY WITH NFPA, TPI, AND AISC 100. CONTRACTOR SHALL VERIFY THAT ADEQUATE TRUSS BEARING IS INSTALLED AT ALL TRUSSES AS INDICATED IN THE TRUSS SHOP DRAWINGS. ALL TRUSS-TO-TRUSS CONNECTIONS AND TRUSS PROFILES ARE THE RESPONSIBILITY OF THE DELEGATED TRUSS MANUFACTURER. ALL TRUSSES SHALL HAVE TEMPORARY BRACING PER "COMMENTARY" AND RECOMMENDATION FOR HANDLING, INSTALLING & BRACING METAL PLATE CONNECTED WOOD TRUSSES, HB-91." AT MULTIPLE STRAP CONNECTIONS, SPREAD STRAPS TO AVOID NAILING CONFLICTS THROUGH TRUSS. WHEN USING (2) STRAPS ON SINGLE PLY TRUSSES, PLACE STRAPS DIAGONALLY ACROSS DBL. TOP PLATE FROM EA. OTHER.

**ROOF COVERING SPECIFICATIONS:**  
THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF THE ROOF COVERING SYSTEM. ASPHALT SHINGLES SHALL COMPLY WITH ASTM D3161 AND BE INSTALLED ACCORDING TO THE MANUFACTURER'S REQUIREMENTS. CLAY AND TILE ROOFS SHALL BE INSTALLED PER THE "CONCRETE AND CLAY ROOF TILE INSTALLATION MANUAL" AND THE MANUFACTURER'S REQUIREMENTS. STAINLESS STEEL METAL ROOFS SHALL COMPLY WITH ASTM E1514 AND BE INSTALLED ACCORDING TO THE MANUFACTURER'S REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ALL METAL FLASHING AND VALLEY MATERIALS.

**WATERPROOFING:**  
THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN/INSTALLATION OF ALL WATER PROOFING.

### WOOD FASTENING SCHEDULE

MEMBERS	CONNECTION TYPE	FASTENER
TOP PLATE TO TOP PLATE	FACE NAIL	2-GUN NAILS @ 12" STAG.
TOP PLATE, LAPS/INTERSECTION	FACE NAIL	(2-16d) 3-GUN NAILS
DBL. TOP PLATE TO STUD	FACE NAIL	(2-16d) 3-GUN NAILS
ROOF JOIST TO TOP PLATE	TOE NAIL	(8d @ 6") GUN NAIL @ 6"
CEILING JOIST TO TOP PLATE	TOE NAIL	(3-8d) 5-GUN NAILS
CEILING JOIST, OVER PARTITIONS	FACE NAIL	(3-16d) 4-GUN NAILS
CEILING JOIST TO ROOF RAFTER	FACE NAIL	(6-16d) 8-GUN NAILS
JOIST/TRUSS TO PLATE	TOE NAIL	(2-16d) 3-GUN NAILS
RAFTER TO PLATE	TOE NAIL	(3-8d) 3-GUN NAILS
JACK RAFTER TO HIP	TOE NAIL	(3-10d) 4-GUN NAILS
ROOF RAFTER TO 2nd RIDGE BM.	TOE NAIL	(2-16d) 3-GUN NAILS
CONT. HEADER, TWO PIECES	FACE NAIL	16d @ 16" O.C. @ EDGE
CONT. HEADER TO STUD	TOE NAIL	(3-16d) 4-GUN NAILS
STUD TO SOLE PLATE	TOE NAIL	(3-16d) 4-GUN NAILS
SOLE PLATE TO JOIST/BLOCKING	FACE NAIL	(16d @ 16") GUN NAIL @ 8"

**NAIL SPECIFICATIONS:**  
3"x0.131" = GUN NAILS  
2"x0.113" = 6d  
3"x0.148" = 10d  
1 1/2"x0.148" = 10dX1 1/2"  
2 1/2"x0.131" = RINK SHANK  
2 1/2"x0.113" = 8d  
3 1/2"x0.162" = 16d  
1 1/2"x0.131" = 8dX1 1/2"

### BRICK NOTES / LINTEL SCHED

LINTEL DIMENSION	MIN. BRG.	MAX. SPAN
L3 1/2"x3 1/2"x 1/4"	4"	6'-0"
L4 x3 1/2"x 1/4"	6"	8'-0"
L5 x3 1/2"x 1/4"	6"	10'-0"
L6 x3 1/2"x 1/4"	6"	12'-0"
L7 x3 1/2"x 1/4"	6"	16'-0"

1. STEEL LINTELS TO BE MINIMAL 36" LINTEL MUST HAVE CORROSION RESISTANT COATING OF EPOXY BASED PAINT.


2. LINTEL MORE THAN 8'-0", SHOULD BE LATERALLY SUPPORTED NOT TO EXCEED 6 FT. O.C. w/ 2-1/4"x3" WD. SCREWS INTO HEADER PROVIDE A 1/2" VERTICAL SLOTTED HOLE FOR SCREW.

3. BRICK VENEER ATTACHMENT: HORIZONTAL TIES @ 24" O.C., VERT. TIES @ 12" O.C. (FOR 110mph WIND-ZONE VERT. TIES @ 16" O.C.) AT ALL OPENINGS SPACE TIES WITHIN 12" OF OPENING. PROVIDE 1/2" WEEP HOLES @ 33" O.C. IMMEDIATELY ABOVE FLASHING.

**SECTION VIEW OF BRICK LINTEL**

### PLAN LEGEND AND ABBREVIATIONS

	INTERIOR LOAD BEARING WALL		BUILT-UP POST IN THE WALL
	CABLE X-BRACE, SEE DETAIL 10250.1		HEADER SIZE, JACK AND KING STUD QUANTITY
	DESIGNATES SHEARWALL, THE HIDDEN LINE DESIGNATES SIZE OF WALL, THE SHEARWALL SHEATHING TO BE APPLIED		
	SW 3/8"		
	ADJ - ADJACENT		LG - Long Manufacture
	BM - BEAM		MONO - Masonolithic
	BOT - BOTTOM		OC - On Center
	BRG - BEARING		OSB - Oriented Strand Board
	CMU - CONCRETE MASONRY UNIT		PERP - Perpendicular
	DBL - DOUBLE		DIA - DIAMETER
	EA - EACH		PSF - Pounds per Square Foot
	EE - EACH END		PT - PRESSURE TREATED
	EOR - ENGINEER OF RECORD		QT - Quick Tie
	EXT - EXTERIOR		REIN - Reinforce
	FBC - FLORIDA BUILDING CODE		SF - Square Foot
	FDN - FOUNDATION		SFP - Spruce Fine Fur
	FT - FOOT		SYF - Southern Yellow Pine
	FTR - FOOTING		THRU - Through
	HDR - HEADER		TYP - Typical
	HORZ - HORIZONTAL		UNOT - Unless Otherwise Noted
	LES - POUNDS		VERT - Vertical
			W/F - Welded Wire Fabric



**CHRISTOPHER J. SABOURIN**  
PROFESSIONAL ENGINEER  
No. 71461  
STATE OF FLORIDA  
FL PE#71461

08.02.24  
Christop Sabourin  
FL PE#71461

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24 AS A AUTHENTICATION CODE.

3 COPIES OF THIS DOCUMENT IT CONSIDERED SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24 AS A AUTHENTICATION CODE. ELECTRONIC COPIES MUST BE FILED ON ANY ELECTRONIC COPIES

**SABO STRUCTURAL ENGINEERING**  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME: BZEC HENDRICK  
55E NO. 24-0402


ISSUE DATE: 08.02.24  
PERMIT DATE: 08.02.24  
REVISIONS DATE:

Structural Engineering for  
Hendrick Residence at  
279 SW Sydney Nicole Ct.  
Lake City, FL, 32024


FIELD ALTERATION  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER J. SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.

SCALING  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWING OR CONTACT THE E.O.R.


DESIGN CRITERIA AND GENERAL NOTES  
SHEET 1 OF 7



**1 GARAGE HEADER FRAMING**  
SCALE: N.T.S.




**2 TYPICAL PORCH FRAMING DETAILS**  
SCALE: N.T.S.




**4 WALL ADJ. TO ROOF CONNECTION**  
SCALE: N.T.S.


**1 GARAGE HEADER FRAMING**  
SCALE: N.T.S.



**5 SHEARWALL ATTACHMENT AT ROOF & FLOOR**  
SCALE: N.T.S.




**6 TYPICAL SHEARWALL ELEVATION**  
SCALE: N.T.S.




**8 LEDGER CONNECTION**  
SCALE: N.T.S.


**9 DECK LEDGER AT OVERFRAME RAFTERS**  
SCALE: N.T.S.




**10 GABLE END BRACING**  
SCALE: N.T.S.




**11 PERMANENT TRUSS BRACING**  
SCALE: 3/4" = 1'-0"




**12 FULL HEIGHT WOOD FRAME WALL ANCHORING SYSTEM**  
SCALE: N.T.S.




**13 3/8\"/>**



**15 HOLD DOWN ATTACHMENT DETAIL**  
SCALE: N.T.S.



**16 DOOR JAMB FASTENING**  
SCALE: N.T.S.



Christopher J. Sabourin  
FL PE #71461

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24. A SHA AUTHENTICATION CODE IS LOCATED AT THE BOTTOM OF THIS DOCUMENT. COPIES OF THIS DOCUMENT IF CONSIDERED SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24. A SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES.

**SABO STRUCTURAL ENGINEERING**  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME: BZEC HENDRICK  
SSE No.: 24-0402


ISSUE DATE: 08.02.24  
PERMIT DATE: 08.02.24  
REVISIONS DATE:

**STRUCTURAL ENGINEERING FOR HENDRICK RESIDENCE AT 279 SW SYDNEY NICOLE CT., LAKE CITY, FL, 32024**

**FIELD ALTERATION**  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER J. SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.

**SCALING**  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

**TYPICAL FRAMING DETAILS**



**FOUNDATION PLAN**  
SCALE: 1/4" = 1'-0"

**FOUNDATION LEGEND**

	DESIGNATES SLAB EDGE LINE
	DESIGNATES FOOTING LINE
	DESIGNATES SAWCUT LINE
	DESIGNATES STEMWALL
	DESIGNATES SLAB STEP RECESS


**FOOTING SCHEDULE**

TYPE	DEPTH	WIDTH	BOTTOM BARS
F2.0	1'-0"	2'-0"x2'-0"	(3) #5 EW
F2.5	1'-0"	2'-6"x2'-6"	(3) #5 EW
F3.0	1'-0"	3'-0"x3'-0"	(3) #5 EW
F3.5	1'-0"	3'-6"x3'-6"	(4) #5 EW
F4.0	1'-4"	4'-0"x4'-0"	(4) #5 EW

**GENERAL FOUNDATION NOTES**

- THIS FOUNDATION PLAN ONLY CONVEYS STRUCTURAL INFORMATION. SEE ARCH FOR DIMENSIONS.
- SEE GENERAL NOTES AND SPECIFICATIONS ON SO.0 FOR FEATURES NOT INCLUDED WITHIN THIS PLAN.
- FOOTINGS AND FOUNDATIONS SHALL BE IN ACCORDANCE WITH LOCAL BUILDING CODES.
- SOIL COMPACTION AND FILL SHALL BE COMPACTED TO A MIN. OF 95% MODIFIED PROCTOR IN ACCORDANCE WITH ASTM D 1557.

CONTRACTOR TO VERIFY DIMENSIONS



Christopher J. Sabourin  
FL PE #71461

CHRISTOPHER J. SABOURIN STATE OF FLORIDA, PROFESSIONAL ENGINEER, LICENSE NO. 71461.

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24. A SHA AUTHENTICATION CODE:  
1. COPIES OF THIS DOCUMENT IF CONSIDERED SIGNED AND SEALED AND THE SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES.

**SABO**  
STRUCTURAL  
ENGINEERING  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME  
BZEC HENDRICK  
SSE No.  
24-0402

ISSUE	DATE
PERMIT	08.02.24
REVISIONS	DATE


STRUCTURAL ENGINEERING FOR  
HENDRICK RESIDENCE AT  
279 SW SYDNEY NICOLE CT.  
LAKE CITY, FL, 32024

**FIELD ALTERATION**  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.


**SCALING**  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

**FOUNDATION PLAN**


SHEET  
**S1.0**  
SHEET 3 OF 7




1 STEMWALL FOOTING  
S1.01 SCALE: 3/4" = 1'-0"



2 FOOTING W/ SHOWER RECESS  
S1.01 SCALE: 3/4" = 1'-0"




3 THICKENED SLAB  
S1.01 SCALE: 3/4" = 1'-0"




4 STEMWALL FOOTING AT SLIDER  
S1.01 SCALE: 3/4" = 1'-0"


STEMWALL SCHEDULE	
CMU COURSES	REINFORCING
1 TO 6	#5 VERT. @ 72" O.C.
7 TO 10	#5 VERT. @ 48" O.C.
STEMWALLS OVER 6 COURSES TO HAVE TRUSS TYPE HORIZ. JOINT REINF. BETWEEN EVERY OTHER COURSE. FILL CELLS SOLID.	




5 SAW CUT DETAIL  
S1.01 SCALE: 3/4" = 1'-0"




6 BEARING AT INTERIOR  
S1.01 SCALE: 3/4" = 1'-0"




7 MONO. FOOTING AT STEP-DOWN  
S1.01 SCALE: 3/4" = 1'-0"




8 STEP AT STEMWALL  
S1.01 SCALE: 3/4" = 1'-0"




9 GARAGE STEM WALL  
S1.01 SCALE: 3/4" = 1'-0"



10 STEMWALL AT GARAGE  
S1.01 SCALE: 3/4" = 1'-0"



11 SPOT FOOTING AT PORCH SLAB  
S1.01



Christopher J. Sabourin  
FL PE #71461

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, PE ON 08/02/24. A SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES.

**SABO**  
STRUCTURAL  
ENGINEERING  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME  
BZEC HENDRICK  
SSE No.  
24-0402


ISSUE	DATE
PERMIT	08.02.24
REVISIONS	DATE

STRUCTURAL ENGINEERING FOR  
HENDRICK RESIDENCE AT  
279 SW SYDNEY NICOLE CT.  
LAKE CITY, FL, 32024

**FIELD ALTERATION**  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER J. SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.

**SCALING**  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

FOUNDATION  
DETAILS



SYMBOLS LEGEND	
	DESIGNATES OSB SHEARWALL. THE HIDDEN LINE DESIGNATES SIDE OF WALL. THE SHEARWALL SHEATHING TO BE APPLIED. 84 @ 2\"/>
	DESIGNATES THE HEADER SIZE, NUMBER OF PLYS & JACK/KING STUDS NEEDED FOR SUPPORT HEADER.
	BEAM OR TRUSS, SEE PLAN

ANCHOR LEGEND	
	SIMPSON HTTS SEE DETAIL 15/SO.1
	SIMPSON DTTZ SEE DETAIL 15/SO.1
	SIMPSON LITZOB SEE DETAIL 15/SO.1


WALL STUD SCHEDULE		
LOCATION	PLATE HEIGHT	STUD SIZE & SPACING
EXTERIOR	9'-1\"/>	
EXTERIOR	10'-1\"/>	
EXTERIOR	10'-1 TO 14'-0\"/>	
INTERIOR	10'-0\"/>	
INTERIOR	12'-0\"/>	

- STUD NOTES:**
- 1.) WALL STUDS SPECIFIED ON PLAN SUPERSEDE THIS TABLE.
  - 2.) MINIMUM STUD SIZE AND SPACING ARE SHOWN. CONTRACTOR MAY INCREASE STUD SIZE TO MEET ARCHITECTURAL REQUIREMENTS.
  - 3.) SPF DENOTES SPRUCE PINE FIR. SYP DENOTES SOUTHERN YELLOW PINE.
  - 4.) USE SYP#2 FOR ALL TOP PLATES AND SOLE PLATES.
  - 5.) FASTEN BOTTOM PLATE OF INTERIOR LOAD BEARING WALLS TO CONCRETE SLAB w/166 MASONRY CUT NAILS @ 16\"/>

- GENERAL NOTES**
1. SEE DETAIL 2/SO.0 FOR WALL FRAMING DETAIL. SEE WALL STUD SCHEDULE THIS SHEET FOR STUD SIZES AND SPACING. AT GIRDERS AND BEAMS, PROVIDE STUDS BELOW TO MATCH BEAM/GIRDER FLIES.
  2. SEE SHEET S0.0 FOR ROOF AND FLOOR SHEATHING SPECIFICATIONS.
  3. WHERE FRAMING MEMBERS CONSIST OF MULTIPLE PLYS (BEAMS, HEADER, AND STUDS) FASTEN PLYS TOGETHER PER DETAIL 6/SO.0.
  4. INSTALL SOLE PLATE ANCHORS PER DETAIL 3/SO.0.
  5. AT SHEARWALLS, PROVIDE DIAPHRAGM ATTACHMENT PER DETAIL 5/SO.1.
  6. FOR ATTACHMENT OF EXTERIOR WALLS THAT TERMINATE BETWEEN TRUSSES, SEE 5A/SO.1.
  7. AT PORCHES, SEE DETAIL 2/SO.1 FOR FRAMING AND HOLD DOWNS.

SOLE PLATE ANCHOR SPACING SCHED	
ALL EXTERIOR WALL UNLESS OTHER NOTED	42\"/>
SHEARWALLS (SW 8003/6\"/>	
	WHEN NOTED ON PLAN SEE NOTE 2

1. INSTALL SOLE PLATE ANCHORS PER DETAIL 4/SO.1
2. ANCHOR SPACING SHALL BE AS NOTED. FOR EXAMPLE = SOLE PLT @ 36\"/>



Christopher J Sabourin  
FL PE#71461

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J SABOURIN, PE ON 08/02/24. A SHA AUTHENTICATION CODE: [XXXXXXXXXX] COPIES OF THIS DOCUMENT IF IT CONSIDERED SIGNED AND SEALED AND THE SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES

**SABO STRUCTURAL ENGINEERING**  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME: BZEC HENDRICK  
SSE No.: 24-0402

ISSUE	DATE
PERMIT	08.02.24
REVISIONS	DATE


**STRUCTURAL ENGINEERING FOR HENDRICK RESIDENCE AT 279 SW SYDNEY NICOLE CT. LAKE CITY, FL, 32024**

**FIELD ALTERATION**  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.

**SCALING**  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

**FIRST LEVEL WALL FRAMING PLAN**

**FIRST LEVEL WALL FRAMING PLAN**  
SCALE: 1/4" = 1'-0"



**TRUSS / ROOF RAFTER NOTES: STRAPPING NOTES:**  
 STRAP ROOF TRUSSES AND RAFTERS TO BEARING WITH  
 (2)12D TOENAILS & (1)SIMPSON SDWC15600 SCREW UNLESS  
 OTHERWISE NOTED.


**ROOF TRUSS PLACEMENT PLAN**  
 SCALE: 1/4" = 1'-0"

**SYMBOLS LEGEND**


HTS16	DESIGNATES UPLIFT CONNECTION.
-------	-------------------------------

**FRAMING PLAN NOTES:**  
 1. FOR TYPICAL ROOF SHEATHING AND FRAMING, SEE SHEET S0.0  
 2. FOR SPECIFIC UPLIFT CONNECTIONS, SEE PLAN MIN. (1)SDWC CONNECTOR.  
 3. FOR GENERAL DESIGN SPECIFICATIONS SEE SHEET S0.0  
 4. WHEN USING (2)H25T CLIPS ON 1 1/2" WIDE LUMBER, PLACE CLIPS DIAGONALLY ACROSS DOUBLE TOP PLATE FROM EACH OTHER.


**TRUSS FASTENING DETAILS**




**TRUSS TIE DOWN WITH SIMPSON SDWC**




**SIMPSON SDWC INSTALLATION RANGE**




**SDWC INSTALLATION**



**SDWC INSTALLATION RANGE**



**SDWC AT TOP PLATE SPLICE**



Christopher J. Sabourin  
 FL PE #71461

THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, P.E. ON 08/02/24. A SHA AUTHENTICATION CODE IS PROVIDED. 3 COPIES OF THIS DOCUMENT ARE REQUIRED. IT IS CONSIDERED SIGNED AND SEALED AND THE SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES.

**SABO STRUCTURAL ENGINEERING**  
 CA#32529  
 235 9TH AVE N  
 JAX BEACH, FL 32250  
 904-712-5750  
 CHRIS@SABOENG.COM

PLAN NAME: BZEC HENDRICK  
 SHEET NO.: 24-0402


ISSUE	DATE
PERMIT	08.02.24
REVISIONS	DATE

**STRUCTURAL ENGINEERING FOR HENDRICK RESIDENCE AT 279 SW SYDNEY NICOLE CT. LAKE CITY, FL, 32024**

**FIELD ALTERATION**  
 CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.

**SCALING**  
 DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

**ROOF TRUSS PLACEMENT PLAN**



08.02.24  
Christopher J. Sabourin  
FL P.E.#71461

CHRISTOPHER J. SABOURIN STATE OF FLORIDA, PROFESSIONAL ENGINEER, LICENSE NO. 71461.  
THIS DOCUMENT HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY CHRISTOPHER J. SABOURIN, P.E. ON 08/16/2024. A SHA AUTHENTICATION CODE.  
COPIES OF THIS DOCUMENT IF CONSIDERED SIGNED AND SEALED AND THE SHA AUTHENTICATION CODE MUST BE FILED ON ANY ELECTRONIC COPIES.

**SABO**  
STRUCTURAL  
ENGINEERING  
CA#32529  
235 9TH AVE N  
JAX BEACH, FL 32250  
904-712-5750  
CHRIS@SABOENG.COM

PLAN NAME  
BZEC HENDRICK  
SSE No.  
24-0402

ISSUE	DATE
PERMIT	08.02.24
REVISIONS	DATE


STRUCTURAL ENGINEERING FOR  
HENDRICK RESIDENCE AT  
279 SW SYDNEY NICOLE CT.  
LAKE CITY, FL, 32024

**FIELD ALTERATION**  
CONTRACTOR SHALL CONTACT SABO STRUCTURAL ENGINEERING PRIOR TO MAKING ANY STRUCTURAL FIELD MODIFICATIONS WHICH MAY VARY FROM THE INTENT OF THE ORIGINAL CONSTRUCTION DOCUMENTS. ANY FIELD ALTERATIONS MADE PRIOR TO BEING APPROVED BY CHRISTOPHER SABOURIN MAY RESULT IN ADDITIONAL ENGINEERING OR INSPECTION FEES.


**SCALING**  
DO NOT SCALE DIMENSIONS FROM THESE DRAWINGS. IF A DIMENSION IS UNCLEAR REFER TO THE ARCHITECTURAL DRAWINGS OR CONTACT THE E.O.R.

MISC DETAILS


SHEET  
**S2.0**  
SHEET 7 OF 7




2 DORMER DETAIL  
S2.0



SECTION AT CORNER




ELEVATION




SECTION A


SECTION B



1 MITERED WINDOW HEAD FRAMING  
S2.0 SCALE: N.T.S.



4 GARAGE HEADER FRAMING  
S2.0



3 DOOR JAMB FASTENING  
S2.0 THIS DETAIL ONLY APPLIES WHEN NOTED ON PLAN