

DATE 02/04/2008

Columbia County Building Permit
This Permit Must Be Prominently Posted on Premises During Construction

PERMIT
000026709

APPLICANT TRENT GIEBEIG PHONE 397-0545
ADDRESS 697 SE HOLLY TERR LAKE CITY FL 32024
OWNER PETE GIEBEIG PHONE 752-7968
ADDRESS 398 SE HOLLY TERR LAKE CITY FL 32025
CONTRACTOR TRENT GIEBEIG PHONE 397-0545
LOCATION OF PROPERTY 441 S, L 252, R HOLLY TERR, THEN 1ST ON RIGHT

TYPE DEVELOPMENT SFD,UTILITY ESTIMATED COST OF CONSTRUCTION 146900.00
HEATED FLOOR AREA 2026.00 TOTAL AREA 2938.00 HEIGHT 19.10 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 7/12 FLOOR SLAB
LAND USE & ZONING AG-3 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE XPP DEVELOPMENT PERMIT NO.

PARCEL ID 21-4S-17-08631-101 SUBDIVISION CREEK RUN PLANTATION
LOT 1 BLOCK PHASE UNIT TOTAL ACRES 5.03

000001545 R282811523
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
PERMIT 07-0982 BK JH N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: MINIMUM FLOOR ELEVATION 100.0', ELEVATION CONFIRMATION LETTER
REQUIRED AT SLAB

Check # or Cash 2400

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 735.00 CERTIFICATION FEE \$ 14.69 SURCHARGE FEE \$ 14.69
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ 25.00 TOTAL FEE 864.38
INSPECTORS OFFICE L. Hedger CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED TO BE IN ACTIVE PROGRESS WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

26709

NOTICE OF COMMENCEMENT

STATE OF: Florida
COUNTY OF: ColumbiaInst: 200812002377 Date: 2/6/2008 Time: 12:10 PM
DC, P. DeWitt Cason, Columbia County Page 1 of 1

The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement:

1. Description of Property: Lot #1 Creek Run Plantation S/D
398 SE Holly Terrace Lake City, Fl. 32025
2. General Description of Improvement: Construction of Single Family Residence
3. Owner Information:
 - a. Name and Address: Peter W. Giebeig
P.O. Box 1384 Lake City, FL. 32056
 - b. Interest in Property: Fee Simple
 - c. Name and Address of Fee Simple titleholder (if other than Owner): _____
4. Contractor (Name and Address): Trent Giebeig Construction, Inc
697 SE Holly Terrace Lake City, Fl. 32025
5. Surety:
 - a. Name and Address: N/A
 - b. Amount of Bond: _____
6. Lender (Name and Address): N/A
7. Persons within the State of Florida designated by Owner upon notices or other documents may be Served as provided by 713.13 (1)(a)(7), Florida Statutes.
N/A
8. In addition to himself, the Owner designates the following person to receive a copy of the Lienor's Notice as provided in 713.13 (1)(b), Florida Statutes (Name and Address):
N/A
9. Expiration date of Notice of Commencement (the expiration date is 1 year from the date of Recording unless a different date is specified): _____

Type Owner Name: _____

Type Owner Name: Peter W. Giebeig


Vanessa Bryant
Witness #1
Vanessa Bryant

Elaine K. Tolar
Witness #2
ELAINE K. TOLAR

Sworn to and subscribed before me by the
Owner (s) on this 5th day of FEB 2007

Elaine K. Tolar
Type Name: ELAINE K. TOLAR
Notary Public, State of Florida
COMMISSION EXPIRY / NUMBER:

Personally Known Peter W. Giebeig
Produced Identification _____
Did Take an Oath / Did Not Take an Oath _____



For Office Use Only Application # 0801-131 Date Received 1/25 By JW Permit # 1545/26709
Zoning Official BLK Date 31.01.08 Flood Zone 2 pph FEMA Map # N/A Zoning A-3
Land Use A-3 Elevation N/A MFE 100 ft River N/A Plans Examiner OKYTH Date 1-29-08
Comments Elevation ~~cert~~ Confirmation Letter Required

☒ NOC ☒ EH ☐ Deed or PA ☐ Site Plan ☐ State Road Info ☐ Parent Parcel #
☐ Dev Permit # ☐ In Floodway ☐ Letter of Authorization from Contractor
☐ Unincorporated area ☐ Incorporated area ☐ Town of Fort White ☐ Town of Fort White Compliance letter

Septic Permit No. 07-0992 Fax 752-1284

Name Authorized Person Signing Permit Trent Gieberg Phone 397-0545

Address 697 SE Holly Terrace, L.C. FL 32024

Owners Name Pete Gieberg Phone 752-7968

911 Address 398 SE Holly Terr, L.C. 32025

Contractors Name Trent Gieberg Construction Phone 397-0545

Address 697 SE Holly Terrace Lake City FL 32025

Fee Simple Owner Name & Address _____

Bonding Co. Name & Address _____

Architect/Engineer Name & Address Freeman Design Group

Mortgage Lenders Name & Address _____

Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progress Energy

Property ID Number 21-45-17-08631-101 Estimated Cost of Construction 120,000

Subdivision Name Creek Run Plantation Lot 1 Block _____ Unit _____ Phase _____

Driving Directions 441 South turn Left on 252

take Right on Holly Terrace inter subdivision

1st on right Number of Existing Dwellings on Property - 0 -

Construction of 70 Total Acreage 5.03 Lot Size _____

Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive Total Building Height 19'1"

Actual Distance of Structure from Property Lines - Front 75' Side 130' Side 30' Rear 490'

Number of Stories 1 Heated Floor Area 2026 Total Floor Area 2938 Roof Pitch 7/12

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment

According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE:


YOU ARE HEREBY NOTIFIED as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

OWNERS CERTIFICATION: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning. I further understand the above written responsibilities in Columbia County for obtaining this Building Permit.



Owners Signature


CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit.



Contractor's Signature (Permitee)


Contractor's License Number BR282811523
Columbia County
Competency Card Number 000141

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 16th day of Jan 2008.
Personally known X or Produced Identification _____



State of Florida Notary Signature (For the Contractor)


SEAL:



011-0982

**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**
Permit Application Number: _____

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT



Site Plan Submitted By Paul Lloyd Date 12/17/07
Plan Approved ✓ Not Approved _____ Date 1/24/08
By M. J. O. H. C. J. H. CPHU

Notes: _____

Water Wells
Pumps & Service

Phone: (386) 752-6677
Fax: (386) 752-1477

Lynch Well Drilling, Inc.

173 SW Young Place
Lake City, FL 32025
www.lynchwelldrilling.com

November 6, 2007

To Whom It May Concern:

As required by building code regulations for Columbia County in order that a building permit can be issued, the following well information is provided with regard to the above-referenced well:

Size of Pump Motor:	1 Horse Power
Size of Pressure Tank:	81-Gallon Bladder Tank
Cycle Stop Valve Used:	No

Should you require any additional information, please contact us.

Sincerely,



Linda Newcomb
Lynch Well Drilling, Inc.

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	St. Johns Model- Creek Run Lot#1	Builder:	T. Geibeig
Address:		Permitting Office:	Lake City
City, State:	,	Permit Number:	26709
Owner:		Jurisdiction Number:	221500
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 32.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 13.00
4. Number of Bedrooms	4	b. N/A	
5. Is this a worst case?	No	c. N/A	
6. Conditioned floor area (ft ²)	2026 ft ²		
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		13. Heating systems	
a. U-factor:	Description Area	a. Electric Heat Pump	Cap: 32.0 kBtu/hr
(or Single or Double DEFAULT) 7a. (Dble Default) 174.0 ft ²			HSPF: 8.50
b. SHGC:		b. N/A	
(or Clear or Tint DEFAULT) 7b. (Clear) 174.0 ft ²		c. N/A	
8. Floor types		14. Hot water systems	
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	a. Electric Resistance	Cap: 50.0 gallons
b. N/A			EF: 0.94
c. N/A		b. N/A	
9. Wall types		c. Conservation credits	
a. Frame, Wood, Exterior	R=13.0, 1779.4 ft ²	(HR-Heat recovery, Solar	
b. N/A		DHP-Dedicated heat pump)	
c. N/A		15. HVAC credits	PT, CF,
d. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
e. N/A		HF-Whole house fan,	
10. Ceiling types		PT-Programmable Thermostat,	
a. Under Attic	R=30.0, 2026.0 ft ²	MZ-C-Multizone cooling,	
b. N/A		MZ-H-Multizone heating)	
c. N/A			
11. Ducts			
a. Sup: Con. Ret: Con. AH: Interior	Sup. R=6.0, 62.0 ft		
b. N/A			

Glass/Floor Area: 0.09

Total as-built points: 23328

Total base points: 30091

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Debbie A. Motes

DATE: 1-4-08

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____

DATE: _____

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BSPM = Points Floor Area				Type/SC							

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT									
Summer Base Points: 26630.3				Summer As-Built Points: 22337.0									
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component (System - Points)	X	Cap Ratio (DM x DSM x AHU)	X	Duct Multiplier	X	System Multiplier	X	Credit Multiplier	= Cooling Points
26630.3		0.3250	8654.8	(sys 1: Central Unit 32000btuh ,SEER/EFF(13.0) Ducts:Con(S),Con(R),Int(AH),R6.0(INS) 22337 1.00 (1.00 x 1.147 x 0.91) 0.260 0.902 5470.8 22337.0 1.00 1.044 0.260 0.902 5470.8									

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BWPM = Points Floor Area				Type/SC Overhang Ornt Len Hgt Area X WPM X WOF = Points							
.18	2026.0	20.17	7356.0	1.Double, Clear	N	1.0	6.0	30.0	24.58	1.00	737.0
				2.Double, Clear	N	1.0	6.0	45.0	24.58	1.00	1106.0
				3.Double, Clear	S	6.0	6.0	30.0	13.30	2.73	1089.0
				4.Double, Clear	S	6.0	6.0	30.0	13.30	2.73	1089.0
				5.Double, Clear	S	1.0	6.0	30.0	13.30	1.02	408.0
				6.Double, Clear	W	1.0	6.0	4.0	20.73	1.01	83.0
				7.Double, Clear	W	1.0	6.0	5.0	20.73	1.01	104.0
				As-Built Total:		174.0			4616.0		
WALL TYPES Area X BWPM = Points				Type R-Value Area X WPM = Points							
Adjacent	0.0	0.00	0.0	1. Frame, Wood, Exterior		13.0		1779.4	3.40	6050.0	
Exterior	1779.4	3.70	6583.8								
Base Total:		1779.4	6583.8	As-Built Total:		1779.4			6050.0		
DOOR TYPES Area X BWPM = Points				Type Area X WPM = Points							
Adjacent	0.0	0.00	0.0	1.Exterior Insulated				33.0	8.40	277.2	
Exterior	72.6	12.30	893.0	2.Exterior Insulated				39.6	8.40	332.6	
Base Total:		72.6	893.0	As-Built Total:		72.6			609.8		
CEILING TYPES Area X BWPM = Points				Type R-Value Area X WPM X WCM = Points							
Under Attic	2026.0	2.05	4153.3	1. Under Attic		30.0		2026.0	2.05 X 1.00	4153.3	
Base Total:		2026.0	4153.3	As-Built Total:		2026.0			4153.3		
FLOOR TYPES Area X BWPM = Points				Type R-Value Area X WPM = Points							
Slab	211.0(p)	8.9	1877.9	1. Slab-On-Grade Edge Insulation		0.0		211.0(p)	18.80	3966.8	
Raised	0.0	0.00	0.0								
Base Total:		1877.9	1877.9	As-Built Total:		211.0			3966.8		
INFILTRATION Area X BWPM = Points				Area X WPM = Points							
		2026.0	-0.59			2026.0			-0.59		-1195.3

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT						
Winter Base Points:		19668.6		Winter As-Built Points:			18200.6			
Total Winter Points	X System Multiplier	=	Heating Points	Total Component (System - Points)	X Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	=	Heating Points
19668.6	0.5540		10896.4	(sys 1: Electric Heat Pump 32000 btuh ,EFF(8.5) Ducts:Con(S),Con(R),Int(AH),R6.0 18200.6 1.000 (1.000 x 1.169 x 0.93) 0.401 0.950 7541.2						
19668.6				18200.6	1.00	1.087	0.401	0.950		7541.2

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

BASE				AS-BUILT					
WATER HEATING				Tank	EF	Number of	X	Tank	X
Number of	X	Multiplier	=	Volume		Bedrooms		Ratio	Multiplier
Bedrooms			Total						Credit = Total
									Multiplier
4		2635.00	10540.0	50.0	0.94	4		1.00	2578.94
									1.00
				As-Built Total:					10315.7

CODE COMPLIANCE STATUS

BASE					AS-BUILT				
Cooling	+	Heating	+	Hot Water	Cooling	+	Heating	+	Hot Water
Points		Points		Points	Points		Points		Points
				=					=
				Total					Total
				Points					Points
8655		10896		30091	5471		7541		10316
									23328

PASS

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , , ,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 88.6

The higher the score, the more efficient the home.

1 1 1 1

1. New construction or existing	New	___	12. Cooling systems	
2. Single family or multi-family	Single family	___	a. Central Unit	Cap: 32.0 kBtu/hr
3. Number of units, if multi-family	1	___		SEER: 13.00
4. Number of Bedrooms	4	___	b. N/A	___
5. Is this a worst case?	No	___	c. N/A	___
6. Conditioned floor area (ft ²)	2026 ft ²	___		___
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		___	13. Heating systems	
a. U-factor:	Description Area		a. Electric Heat Pump	Cap: 32.0 kBtu/hr
(or Single or Double DEFAULT)	7a. (Dble Default) 174.0 ft ²	___		HSPF: 8.50
b. SHGC:		___	b. N/A	___
(or Clear or Tint DEFAULT)	7b. (Clear) 174.0 ft ²	___	c. N/A	___
8. Floor types		___	14. Hot water systems	
a. Slab-On-Grade Edge Insulation	R=0.0, 211.0(p) ft	___	a. Electric Resistance	Cap: 50.0 gallons
b. N/A	___	___		EF: 0.94
c. N/A	___	___	b. N/A	___
9. Wall types		___	c. Conservation credits	___
a. Frame, Wood, Exterior	R=13.0, 1779.4 ft ²	___	(HR-Heat recovery, Solar	___
b. N/A	___	___	DHP-Dedicated heat pump)	___
c. N/A	___	___	15. HVAC credits	PT, CF, ___
d. N/A	___	___	(CF-Ceiling fan, CV-Cross ventilation,	
e. N/A	___	___	HF-Whole house fan,	
10. Ceiling types		___	PT-Programmable Thermostat,	
a. Under Attic	R=30.0, 2026.0 ft ²	___	MZ-C-Multizone cooling,	
b. N/A	___	___	MZ-H-Multizone heating)	
c. N/A	___	___		
11. Ducts		___		
a. Sup: Con. Ret: Con. AH: Interior	Sup. R=6.0, 62.0 ft	___		
b. N/A	___	___		

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____

Date: _____

Address of New Home: _____

City/FL Zip: _____



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStar™ designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.*

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCPB v4.5.2)

BUILDING INPUT SUMMARY REPORT

PROJECT	Title: St. Johns Model- Creek Run L		Family Type: Single		Address Type: Street Address	
	Owner: (blank)		New/Existing: New		Lot #: N/A	
	# of Units: 1		Bedrooms: 4		Subdivision: N/A	
	Builder Name: T. Geibeig		Conditioned Area: 2026		Platbook: N/A	
	Climate: North		Total Stories: 1		Street: (blank)	
	Permit Office: Lake City		Worst Case: No		County: Columbia	
	Jurisdiction #: (blank)		Rotate Angle: (blank)		City, St, Zip: , ,	

FLOORS	#	Floor Type	R-Val	Area/Perimeter	Units
	1	Slab-On-Grade Edge Insulation	0.0	211.0(p) ft	1

DOORS	#	Door Type	Orientation	Area	Units
	1	Insulated	Exterior	33.0 ft²	1
2	Insulated	Exterior	39.6 ft²	1	

CEILINGS	#	Ceiling Type	R-Val	Area	Base Area	Units
	1	Under Attic	30.0	2026.0 ft²	2026.0 ft²	1
Credit Multipliers: None						

COOLING	#	System Type	Efficiency	Capacity
	1	Central Unit	SEER: 13.00	32.0 kBtu/hr
Credit Multipliers: Ceil Fn, PT				

WALLS	#	Wall Type	Location	R-Val	Area	Units
	1	Frame - Wood	Exterior	13.0	1779.4 ft²	1

HEATING	#	System Type	Efficiency	Capacity
	1	Electric Heat Pump	HSPF: 8.50	32.0 kBtu/hr
Credit Multipliers: PT				

WINDOWS	#	Panes	Tint	Ornt	Area	OH Length	OH Hght	Units
	1	Double	Clear	N	30.0 ft²	1.0 ft	6.0 ft	1
	2	Double	Clear	N	15.0 ft²	1.0 ft	6.0 ft	3
	3	Double	Clear	S	15.0 ft²	6.0 ft	6.0 ft	2
	4	Double	Clear	S	30.0 ft²	6.0 ft	6.0 ft	1
	5	Double	Clear	S	15.0 ft²	1.0 ft	6.0 ft	2
	6	Double	Clear	W	4.0 ft²	1.0 ft	6.0 ft	1
	7	Double	Clear	W	5.0 ft²	1.0 ft	6.0 ft	1

DUCTS	#	Supply Location	Return Location	Air Handler Location	Supply R-Val	Supply Length
	1	Cond.	Cond.	Interior	6.0	62.0 ft
Credit Multipliers: None						

WATER	#	System Type	EF	Cap.	Conservation Type	Con. EF
	1	Electric Resistance	0.94	50.0	None	0.00

REFR.	#	Use Default?	Annual Operating Cost	Electric Rate
	1	Yes	N/A	N/A

MISC	Rater Name:	CodeOnlyPro	Class #:	3	Pool Size:	0
	Rater Certification #:	CodeOnlyPro	Duct Leakage Type:	N/A	Pump Size:	0.00 hp
	Area Under Fluorescent:	0.0	Visible Duct Disconnects:	N/A	Dryer Type:	Electric
	Area Under Incandescent:	2026.0	Leak Free Duct System Proposed:	No	Stove Type:	Electric
	NOTE: Not all Rating info shown		HRV/ERV System Present?:	No	Avg Ceil Hgt:	

Residential System Sizing Calculation

Summary

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North


1/4/2008

Location for weather data: Gainesville - Defaults: Latitude(29) Altitude(152 ft.) Temp Range(M)					
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(54gr.)					
Winter design temperature	33	F	Summer design temperature	92	F
Winter setpoint	70	F	Summer setpoint	75	F
Winter temperature difference	37	F	Summer temperature difference	17	F
Total heating load calculation	27486	Btuh	Total cooling load calculation	17003	Btuh
Submitted heating capacity	% of calc	Btuh	Submitted cooling capacity	% of calc	Btuh
Total (Electric Heat Pump)	116.4	32000	Sensible (SHR = 0.75)	159.7	24000
Heat Pump + Auxiliary(0.0kW)	116.4	32000	Latent	404.1	8000
			Total (Electric Heat Pump)	188.2	32000

WINTER CALCULATIONS

Winter Heating Load (for 2026 sqft)


Load component		Load	
Window total	174 sqft	5601	Btuh
Wall total	1779 sqft	5844	Btuh
Door total	73 sqft	940	Btuh
Ceiling total	2026 sqft	2387	Btuh
Floor total	211 sqft	9212	Btuh
Infiltration	86 cfm	3501	Btuh
Duct loss		0	Btuh
Subtotal		27486	Btuh
Ventilation	0 cfm	0	Btuh
TOTAL HEAT LOSS		27486	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 2026 sqft)

Load component		Load	
Window total	174 sqft	3581	Btuh
Wall total	1779 sqft	3712	Btuh
Door total	73 sqft	711	Btuh
Ceiling total	2026 sqft	3355	Btuh
Floor total		0	Btuh
Infiltration	43 cfm	804	Btuh
Internal gain		2860	Btuh
Duct gain		0	Btuh
Sens. Ventilation	0 cfm	0	Btuh
Total sensible gain		15024	Btuh
Latent gain(ducts)		0	Btuh
Latent gain(infiltration)		1580	Btuh
Latent gain(ventilation)		0	Btuh
Latent gain(internal/occupants/other)		400	Btuh
Total latent gain		1980	Btuh
TOTAL HEAT GAIN		17003	Btuh



Version 8
For Florida residences only

EnergyGauge® System Sizing

PREPARED BY: Debra A. Moles

DATE: 1-4-08

Residential Load - Whole House Component Details

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

1/4/2008

Component Loads for Whole House

Window	Panes/SHGC/Frame/U	Orientation	Area(sqft)	X	HTM=	Load
1	2, Clear, Metal, 0.87	N	30.0		32.2	966 Btuh
2	2, Clear, Metal, 0.87	N	45.0		32.2	1449 Btuh
3	2, Clear, Metal, 0.87	S	30.0		32.2	966 Btuh
4	2, Clear, Metal, 0.87	S	30.0		32.2	966 Btuh
5	2, Clear, Metal, 0.87	S	30.0		32.2	966 Btuh
6	2, Clear, Metal, 0.87	W	4.0		32.2	129 Btuh
7	2, Clear, Metal, 0.87	W	5.0		32.2	161 Btuh
	Window Total		174(sqft)			5601 Btuh
Walls	Type	R-Value	Area	X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1779		3.3	5844 Btuh
	Wall Total		1779			5844 Btuh
Doors	Type		Area	X	HTM=	Load
1	Insulated - Exterior		33		12.9	427 Btuh
2	Insulated - Exterior		40		12.9	513 Btuh
	Door Total		73			940Btuh
Ceilings	Type/Color/Surface	R-Value	Area	X	HTM=	Load
1	Vented Attic/D/Shin	30.0	2026		1.2	2387 Btuh
	Ceiling Total		2026			2387Btuh
Floors	Type	R-Value	Size	X	HTM=	Load
1	Slab On Grade	0	211.0 ft(p)		43.7	9212 Btuh
	Floor Total		211			9212 Btuh
	Envelope Subtotal:					23984 Btuh
Infiltration	Type	ACH	X	Volume(cuft)	walls(sqft)	CFM=
	Natural	0.32		16208	1779	86.4
						3501 Btuh
Ductload	(DLM of 0.000)					0 Btuh
All Zones	Sensible Subtotal All Zones					27486 Btuh

WHOLE HOUSE TOTALS

	Subtotal Sensible	27486 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	27486 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

1/4/2008

EQUIPMENT

1. Electric Heat Pump	#	32000 Btuh
-----------------------	---	------------

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



Version 8
For Florida residences only

System Sizing Calculations - Winter

Residential Load - Room by Room Component Details

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 37.0 F

1/4/2008

Component Loads for Zone #1: Main					
Window	Panes/SHGC/Frame/U	Orientation	Area(sqft) X	HTM=	Load
1	2, Clear, Metal, 0.87	N	30.0	32.2	966 Btuh
2	2, Clear, Metal, 0.87	N	45.0	32.2	1449 Btuh
3	2, Clear, Metal, 0.87	S	30.0	32.2	966 Btuh
4	2, Clear, Metal, 0.87	S	30.0	32.2	966 Btuh
5	2, Clear, Metal, 0.87	S	30.0	32.2	966 Btuh
6	2, Clear, Metal, 0.87	W	4.0	32.2	129 Btuh
7	2, Clear, Metal, 0.87	W	5.0	32.2	161 Btuh
	Window Total		174(sqft)		5601 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Frame - Wood - Ext(0.09)	13.0	1779	3.3	5844 Btuh
	Wall Total		1779		5844 Btuh
Doors	Type		Area X	HTM=	Load
1	Insulated - Exterior		33	12.9	427 Btuh
2	Insulated - Exterior		40	12.9	513 Btuh
	Door Total		73		940Btuh
Ceilings	Type/Color/Surface	R-Value	Area X	HTM=	Load
1	Vented Attic/D/Shin	30.0	2026	1.2	2387 Btuh
	Ceiling Total		2026		2387Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab On Grade	0	211.0 ft(p)	43.7	9212 Btuh
	Floor Total		211		9212 Btuh
	Zone Envelope Subtotal:				23984 Btuh
Infiltration	Type	ACH X	Volume(cuft) walls(sqft)	CFM=	
	Natural	0.32	16208 1779	86.4	3501 Btuh
Ductload	Average sealed, Supply(R6.0-Cond.), Return(R6.0-Cond)DLM of 0.000)				0 Btuh
Zone #1	Sensible Zone Subtotal				27486 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

1/4/2008

WHOLE HOUSE TOTALS

	Subtotal Sensible	27486 Btuh
	Ventilation Sensible	0 Btuh
	Total Btuh Loss	27486 Btuh

EQUIPMENT

1. Electric Heat Pump	#	32000 Btuh
-----------------------	---	------------

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)
Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)



Version 8
For Florida residences only

System Sizing Calculations - Summer

Residential Load - Whole House Component Details

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

Reference City: Gainesville (Defaults) Summer Temperature Difference: 17.0 F

1/4/2008

Component Loads for Whole House

Window	Type*	Ornt	Overhang		Window Area(sqft)			HTM		Load	
	Pn/SHGC/U/InSh/ExSh/IS		Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1	2, Clear, 0.87, B-D, N,F	N	1ft.	6ft.	30.0	0.0	30.0	19	19	560	Btuh
2	2, Clear, 0.87, B-D, N,F	N	1ft.	6ft.	45.0	0.0	45.0	19	19	841	Btuh
3	2, Clear, 0.87, B-D, N,F	S	6ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
4	2, Clear, 0.87, B-D, N,F	S	6ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
5	2, Clear, 0.87, B-D, N,F	S	1ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
6	2, Clear, 0.87, B-D, N,F	W	1ft.	6ft.	4.0	0.0	4.0	19	55	222	Btuh
7	2, Clear, 0.87, B-D, N,F	W	1ft.	6ft.	5.0	0.0	5.0	19	55	277	Btuh
	Window Total				174 (sqft)					3581 Btuh	
Walls	Type		R-Value/U-Value		Area(sqft)			HTM		Load	
1	Frame - Wood - Ext		13.0/0.09		1779.4			2.1		3712 Btuh	
	Wall Total				1779 (sqft)					3712 Btuh	
Doors	Type				Area (sqft)			HTM		Load	
1	Insulated - Exterior				33.0			9.8		323 Btuh	
2	Insulated - Exterior				39.6			9.8		388 Btuh	
	Door Total				73 (sqft)					711 Btuh	
Ceilings	Type/Color/Surface		R-Value		Area(sqft)			HTM		Load	
1	Vented Attic/DarkShingle		30.0		2026.0			1.7		3355 Btuh	
	Ceiling Total				2026 (sqft)					3355 Btuh	
Floors	Type		R-Value		Size			HTM		Load	
1	Slab On Grade		0.0		211 (ft(p))			0.0		0 Btuh	
	Floor Total				211.0 (sqft)					0 Btuh	
	Envelope Subtotal:									11360 Btuh	
Infiltration	Type		ACH		Volume(cuft)			wall area(sqft)		CFM=	
	SensibleNatural		0.16		16208			1779		86.4	
Internal gain			Occupants		Btuh/occupant			Appliance		Load	
			2		X 230			+		2400	
	Sensible Envelope Load:									15024 Btuh	
Duct load	(DGM of 0.000)									0 Btuh	
	Sensible Load All Zones									15024 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

1/4/2008

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	15024 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	15024 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	15024 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	1580 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (2 people @ 200 Btuh per person)	400 Btuh
	Latent other gain	0 Btuh
	Latent total gain	1980 Btuh
	TOTAL GAIN	17003 Btuh

EQUIPMENT

1. Central Unit	#	32000 Btuh
-----------------	---	------------

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Ornt - compass orientation)



Version 8
For Florida residences only

System Sizing Calculations - Summer

Residential Load - Room by Room Component Details

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

Reference City: Gainesville (Defaults)

Summer Temperature Difference: 17.0 F

1/4/2008

Component Loads for Zone #1: Main

Window	Type*		Overhang		Window Area(sqft)			HTM		Load	
	Pn/SHGC/U/InSh/ExSh/IS	Ornt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1	2, Clear, 0.87, B-D, N,F	N	1ft.	6ft.	30.0	0.0	30.0	19	19	560	Btuh
2	2, Clear, 0.87, B-D, N,F	N	1ft.	6ft.	45.0	0.0	45.0	19	19	841	Btuh
3	2, Clear, 0.87, B-D, N,F	S	6ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
4	2, Clear, 0.87, B-D, N,F	S	6ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
5	2, Clear, 0.87, B-D, N,F	S	1ft.	6ft.	30.0	30.0	0.0	19	23	560	Btuh
6	2, Clear, 0.87, B-D, N,F	W	1ft.	6ft.	4.0	0.0	4.0	19	55	222	Btuh
7	2, Clear, 0.87, B-D, N,F	W	1ft.	6ft.	5.0	0.0	5.0	19	55	277	Btuh
Window Total					174 (sqft)					3581	Btuh
Walls	Type	R-Value/U-Value			Area(sqft)			HTM		Load	
1	Frame - Wood - Ext	13.0/0.09			1779.4			2.1		3712	Btuh
Wall Total					1779 (sqft)					3712	Btuh
Doors	Type				Area (sqft)			HTM		Load	
1	Insulated - Exterior				33.0			9.8		323	Btuh
2	Insulated - Exterior				39.6			9.8		388	Btuh
Door Total					73 (sqft)					711	Btuh
Ceilings	Type/Color/Surface	R-Value			Area(sqft)			HTM		Load	
1	Vented Attic/DarkShingle	30.0			2026.0			1.7		3355	Btuh
Ceiling Total					2026 (sqft)					3355	Btuh
Floors	Type	R-Value			Size			HTM		Load	
1	Slab On Grade	0.0			211 (ft(p))			0.0		0	Btuh
Floor Total					211.0 (sqft)					0	Btuh
Zone Envelope Subtotal:										11360 Btuh	
Infiltration	Type	ACH			Volume(cuft) wall area(sqft)			CFM=		Load	
	SensibleNatural	0.16			16208 1779			43.2		804	Btuh
Internal gain		Occupants			Btuh/occupant			Appliance		Load	
		2			X 230 +			2400		2860	Btuh
Sensible Envelope Load:										15024 Btuh	
Duct load	Average sealed, Supply(R6.0-Cond.), Return(R6.0-Cond)							(DGM of 0.000)		0 Btuh	
	Sensible Zone Load									15024 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

1/4/2008

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	15024 Btuh
	Sensible Duct Load	0 Btuh
	Total Sensible Zone Loads	15024 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	15024 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	1580 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	0 Btuh
	Latent occupant gain (2 people @ 200 Btuh per person)	400 Btuh
	Latent other gain	0 Btuh
	Latent total gain	1980 Btuh
	TOTAL GAIN	17003 Btuh

EQUIPMENT

1. Central Unit	#	32000 Btuh
-----------------	---	------------

*Key: Window types (Pn - Number of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(U - Window U-Factor or 'DEF' for default)

(InSh - Interior shading device: none(N), Blinds(B), Draperies(D) or Roller Shades(R))

(ExSh - Exterior shading device: none(N) or numerical value)

(BS - Insect screen: none(N), Full(F) or Half(H))

(Ornt - compass orientation)



Version 8
For Florida residences only

Residential Window Diversity

MidSummer

Project Title:
St. Johns Model- Creek Run Lot#1


Code Only
Professional Version
Climate: North

1/4/2008

Weather data for: Gainesville - Defaults

Summer design temperature	92 F	Average window load for July	5120 Btuh
Summer setpoint	75 F	Peak window load for July	6188 Btuh
Summer temperature difference	17 F	Excursion limit(130% of Ave.)	6656 Btuh
Latitude	29 North	Window excursion (July)	None

WINDOW Average and Peak Loads



The midsummer window load for this house does not exceed the window load excursion limit.

This house has adequate midsummer window diversity.

EnergyGauge® System Sizing for Florida residences only

PREPARED BY: Debbie D. Motes

DATE: 1-4-08

EnergyGauge® FLRCPB v4.5.2



Columbia County Building Department Culvert Permit

Culvert Permit No.
000001545

DATE 02/04/2008 PARCEL ID # 21-4S-17-08631-101
APPLICANT TRENT GIEBEIG PHONE 397-0545
ADDRESS 697 SE HOLLY TERR LAKE CITY FL 32024
OWNER PETE GIEBEIG PHONE 752-7968
ADDRESS 398 SE POLLY TERR LAKE CITY FL 32025
CONTRACTOR TRENT GIEBEIG PHONE 397-0545
LOCATION OF PROPERTY 441 S. L 252, R HOLLY TERR, THEN 1ST ON RIGHT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT CREEK RUN PLANTATION 1
SIGNATURE *Pete Giebeig*

INSTALLATION REQUIREMENTS



Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
 - b) the driveway to be served will be paved or formed with concrete.
- Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.



Culvert installation shall conform to the approved site plan standards.



Department of Transportation Permit installation approved standards.



Other _____

ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALATION OF THE CULVERT.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00





BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Clopay Building Products Co.
8585 Duke Blvd.
Mason, OH 45040

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code. This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone.

DESCRIPTION: Sectional Garage Door 16'- 2" Wide.

APPROVAL DOCUMENT: Drawing No. 101300, titled "Double Car Hurricane Pan Door", dated 02/15/95 with last revision on 01/06/04, sheets 1 and 2 of 2, prepared by Clopay Building Products Co, signed and sealed by M. W. Westerfield, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: Large and Small Missile Impact

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

LIMITATION: This approval requires the manufacturer to do testing of all coils used to fabricate door panels under this Notice of Acceptance. A minimum of 2 specimens shall be cut from each coil and tensile tested according to ASTM E-8 by a Dade County approved laboratory selected and paid by the manufacturer. Every 3 months, four times a year, the manufacturer shall mail to this office: a copy of the tested reports with confirmation that the specimen were selected from coils at the manufacturer production facilities. And a notarized statement from the manufacturer that only coils with yield strength of 38000 psi or more shall be used to make door panels for Dade County under this Notice of Acceptance

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews NOA # 03-0829.05 and consists of this page, evidence page as well as the approval document mentioned above.

The submitted documentation was reviewed by **Candido E. Font PE.**

[Signature]
03/23/06



NOA No 05-1212.02
Expiration Date: March 26, 2007
Approval Date: March 23, 2006

Clopay Building Products Co.

NOTICE OF ACCEPTANCE: EVIDENCE PAGE

A. DRAWINGS

1. Drawing prepared by Clopay Building Products Co., titled "Double Car Hurricane Pan Door", Drawing No. 101300, dated 02/15/95, with last revision on 01/06/2004, sheets 1 through 2 of 2, signed and sealed by M.W. Westerfield, PE.

B. TESTS

1. Test report of large missile impact test per PA 201 and cyclic wind pressure test per PA 203 of "Garage Door", prepared by Hurricane Engineering & Testing, Inc., report No. HETI 95-408, dated 01/25/95, signed and sealed by H. M. Medina, PE.
2. Test report of Uniform Static Air Pressure Test Per PA 202 on "Garage Door", prepared by Hurricane Engineering & Testing, Inc., report No. HETI 95-407, dated 01/24/95, signed and sealed by H. M. Medina, PE.
3. Test report of Forced Entry Resistance per section 3603.2(b)5 on "Garage Door" prepared by Hurricane Engineering Testing, Inc. report No. HETI 95-407f, dated 01/25/95, signed and sealed by H. M. Medina, PE.

C. CALCULATIONS

1. Calculations dated 01/20/95; pages 1 and 2, prepared by M. W. Westerfield, PE, signed and sealed by M. W. Westerfield, PE.
2. Calculations dated 02/24/95, page 1, prepared M.W. Westerfield, PE, signed and sealed by M.W. Westerfield, PE.

D. MATERIAL CERTIFICATIONS


1. Test report of Tensile Test per ASTM E 8, report No. HETI 94-T59, prepared by Hurricane Engineering & Testing, Inc., dated 02/06/95, signed and sealed by H.M. Medina, PE.
2. Test report of Salt Spray Test per ASTM D1654 & ASTM B117, report No. 9EM-1144, prepared by Q.C. Metallurgical, Inc., dated 06/03/99, signed and sealed by K. Grate.

E. STATEMENTS.

1. Affidavit of yield strength compliance prepared by R. D. Shifflett employed by Clopay Building Products Co., notarized on 01/11/2001 by B. H. Schuler.

F. QUALITY ASSURANCE.

1. Building Code Compliance Office.


03/23/06
Candido F. Font, PE.
Senior Product Control Division
NOA No 05-1212.02
Expiration Date: March 26, 2007
Approval Date: March 23, 2006

PAIRED, L-LOC SYSTEM (10" & BUI)
E ADHESIVE (ALONG CENTER)

16 GA. PAINTED END STILES ATTACHED TO DOOR SKIN WITH PATENTED TOG-L-LOC SYSTEM (TOP, BOTTOM & CENTER).

VIEW "C"
VIEW "B"

LOCK POSITION (BOTH SIDES) TWO POINT LOCKING HAS BEEN TESTED PER REQUIREMENTS OF SECTION 12.1 OF TAS 202. LOCKS HAVE 5/8" MIN. ENGAGEMENT. DOOR TESTED FOR FORCED ENTRY WITH BOTH OUTSIDE KEYS LOCK AND INSIDE SLIDE BOLT LOCK OPTIONS (SEE LAYOUT OF EACH LOCK ON NEXT PAGE).

OPTIONAL OUTSIDE KEYS LOCK POSITION
MAX. DOOR WIDTH = 16'-2"
INSIDE ELEVATIONS

24 GA. DDS STEEL (MIN. YIELD STRENGTH: 38 KSI) EXTERIOR SKIN WITH G-40 GALVANIZING, BAKED-ON PRIMER AND A BAKED-ON POLYESTER PAINTED TOP COAT APPLIED TO BOTH SIDES OF STEEL SKIN. (ASTM No. A653).

SHIP LAP JOINTS.

TRACK CONFIGURATION
EXTENDED HEIGHT MODELS H93, H94
DOORS UP TO 12'-0" HIGH
CENTER H-ANG REQUIRED FOR DOORS OVER 8' HIGH

GH

PANEL GALV. INTER. STILES
PANEL PAINTED/GALV. INTER. STILES

84A, 93, 94

VITAL TRACK SUPPORT BY DOOR INSTALLER (TO SUIT)
ICE SYSTEM

CONTINUOUS ANGLE

DOORS ONLY

SECTION

DOOR HEIGHT	"L"
6'-6"	70"
7'-0"	76"
7'-6"	82"
8'-0"	88"

ONE 5/16" x 1-5/8" LAG SCREW SPACED AT THE SAME DISTANCES AS THE TRACK BOLTS (I.E. 3'-1/2", 10", 22", 34", 46", ETC.). ADDITIONAL LAG SCREWS LOCATED AT 16", 28", & 40" FROM BOTTOM. ALSO TWO LAG SCREWS LOCATED ABOVE VERTICAL/HORIZONTAL TRACK JUNCTION.

DOOR HEIGHT	VERTICAL TRACK LENGTH
9'-0"	96"
10'-0"	108"
12'-0"	132"

3" GALV. TAPERED STEEL TRACK AND ANGLE. TRACK THICKNESS: .101". ANGLE THICKNESS: .080".
VERTICAL/HORIZONTAL TRACK JUNCTION. TWO 1/4" BOLTS & NUTS FOR EACH TRACK.
14" MAXIMUM SPACING FROM LAST MOUNTING SLOT TO TRACK JUNCTION

ADDITIONAL MOUNTING SLOTS SPACED AT 12" CENTERS.

12" ON CENTER

ONE 1/4" TRACK BOLT AND NUT AT EACH MOUNTING SLOT LOCATION.

HORIZONTAL TRACK SUPPORT BY DOOR INSTALLER (TO SUIT)

2" THICK

12 GA. GALV. STEEL TOP R. EACH BRACKET ATTACHED W/ SHEET METAL SCREWS. ADJ. TO TOP BRACKET WITH (2) NUTS PER BRACKET.

14 GA. GALV. ROLLER HINGE FASTENED TO STILES W/ (4) #14x5/8" S AND (4) 1/4"x3/4" SELF (SEE VIEW "B").

ONE 6" TALL C-CHANNEL P C-CHANNEL ATTACHED AT E (1) 1/4"x3/4" SELF TAPPIN

1-1/4" WIDE x 16 GA. GAL DOOR SECTION, EXCEPT (8) SECTION (SEE INSIDE ELEVATION WITH (3) 1/4"x3/4" SELF SCREWS TO DOOR, ONE SCI

13 GA. GALV. STEEL BOTTOM BRACKET. ATTACHED WITH (2) #14x5/8" SHEET N

ALUMINUM EXTRUSION & VINYL WEATHER

#14x5/8" ST

14 GA. END HINGES
VIEW "B"

1/6/04

DESIGN LOADS: +46.6 P.S.F. & -52.0 P.S.F. (MODELS 83, 84A, 93, 94)
DESIGN LOADS: +46.6 P.S.F. & -51.7 P.S.F. (MODELS H93, H94)

IM DESIGN LOAD OF +372.8 LB & -416 LB. PER LINEAR FOOT OF JAMB. (NOT REQUIRED) COUNTERSUNK TO PROVIDE A FLUSH MOUNTING SURFACE.

BE FRAMED SOLID BY NOT LESS THAN (3) 2x6 PRESSURE TREATED GRADE SS GRADE NOT LESS THAN 1200 PSI NOMINAL EXTREME FIBER STRESS 10" HIGH. STUB WALLS TO BE CONTINUOUS FROM FOOTING TO TIE BEAMS BUILDING CODE. (4) 2x6 PRESSURE TREATED GRADE #2 OR BETTER LESS THAN 1200 PSI NOMINAL EXTREME FIBER STRESS IN BENDING FOR


TO GROUT REINFORCED BLOCK WALL OR CONCRETE COLUMN. WITH CONCRETE AND REINFORCED WITH #5 BAR EXTENDING S. ALL BARS SHALL BE CONTINUOUS FROM THE TIE BEAMS CRETE COLUMN. BLOCK WALLS AND CONCRETE COLUMNS TO BE OF RECORD AND IN ACCORDANCE WITH THE FLORIDA BUILDING CODE.

SUPPORTING STRUCTURE ATTACHMENT


ENT OF TRACK ANGLE TO 2x6 VERTICAL JAMBS OR SUPPORTING STRUCTURE)

TYPE	MAXIMUM ON-CENTER DISTANCE BETWEEN FASTENERS	STEEL WASHERS REQUIRED?
1/4" MIN. EMBED ELCO TAPCON CONCRETE ANCHOR	16"	YES
1/4" MIN. EMBED POWER-STUD EXPANSION ANCHOR (7400 SERIES)	10"	YES
1/4" MIN. EMBED POWER LOK/BOLT ANCHOR BOLT (5000 SERIES)	16"	NO
ANCHOR AND EDGE OF CONCRETE BLOCK: 3" EXCLUDING STUCCO THICKNESS. 3" MORE THAN HALF OF THE MAXIMUM ON-CENTER DISTANCE. HIGHEST ANCHOR INSTALLED AT LEAST AS HIGH AS THE DOOR OPENING.	14"	NO

D HAS BEEN USED IN THE DESIGN OF CONCRETE ANCHORS & WOOD FASTENERS.





5	8/25/03	ADDED EXTENDE
6	1/6/04	JAMB ATTACHEME



INTER. :

OUTSIDE KEYE
HANDL



JAMB PREPARATION NOTE
EACH CONTINUOUS ANGLE TRACK SHALL BE FASTENED TO PINE WOOD JAMBS WITH 5/16"x1-5/8" LAG SCREWS (12" 7"0" HIGH AND (13) LAG SCREWS PER SIDE UP TO 8'0" TO 9'0" HIGH, (15) LAG SCREWS PER SIDE UP TO 10'0" SIDE UP TO 11'0" HIGH, (17) LAG SCREWS PER SIDE U ATTACHMENT TO THE SUPPORTING STRUCTURE OF THE PRI SHALL BE APPROVED BY THE PROFESSIONAL OF RECORD ACCORDANCE WITH CURRENT BUILDING CODES FOR THE L PREPARATION OF JAMBS BY OTHERS.

ALL MOUNTING OF TRACK, ANGLES, HORIZONTAL TRACK SI DOOR HARDWARE TO BE INSTALLED PER CLOPAY INSTALLA SUPPLIED WITH DOOR SYSTEM UNLESS OTHERWISE NOTED.

PRODUCT REVIEWED
as complying with the Florida
Building Code
Acceptance No. 05-12124
Expiration Date 03/2016
Mark W. Westerfield, P.E.
Florida Registration No. 48495

DESIGN ENGINEER
MARK W. WESTERFIELD, P.E.
FLORIDA REGISTRATION No. 48495

DESIGN LOADS: +46.6 P.S.F. & -52.0 P.S.F. (MODELS 83,
DESIGN LOADS: +46.6 P.S.F. & -51.7 P.S.F. (MODEL H93,



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Tamko Roofing Products, Inc.
P.O. Box 1404
Joplin, MO 64802

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: TAMKO Heritage Declaration & Heritage XL Roof Shingles

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This consists of pages 1 through 4.

The submitted documentation was reviewed by Frank Zuloaga, RRC



NOA No.: 03-0620.01
Expiration Date: 09/04/08
Approval Date: 09/04/03
Page 1 of 4

ROOFING ASSEMBLY APPROVAL

Category: Roofing
Sub-Category: 07310 Composition Shingles
Materials: Dimensional
Deck Type: Wood

1. SCOPE:

This approves **Tamko Heritage Declaration and Heritage XL** Asphalt Shingles, manufactured by **Tamko Roofing Products, Inc.** as described in this Notice of Acceptance.

2. PRODUCT DESCRIPTION

<u>Product</u>	<u>Dimensions</u>	<u>Test Specifications</u>	<u>Product Description</u>
Heritage Declaration & Heritage XL	12" x 36"	TAS 110	A heavy weight dimensional asphalt shingle.

3. EVIDENCE SUBMITTED:

<u>Test Agency</u>	<u>Test Identifier</u>	<u>Test Name/Report</u>	<u>Date</u>
PRI Asphalt Technologies, Inc.	TAS 100	TAP-066-02-01	01/09/03
		TAP-073-02-01	05/20/03
Underwriters Laboratories, Inc.	ASTM D 3462	R2919	06/12/03
Underwriters Laboratories, Inc.	TAS 107	03CA08442	06/12/03

4. LIMITATIONS

- 4.1 Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 4.2 Shall not be installed on roof mean heights in excess of 33 ft.
- 4.3 All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 9B-72 of the Florida Administrative Code.

5. INSTALLATION

- 5.1 Shingles shall be installed in accordance with Roofing Application Standard RAS 115.
- 5.2 The manufacturer shall provide clearly written application instructions.
- 5.3 Exposure and course layout shall be in compliance with Detail 'A', attached.
- 5.4 Nailing shall be in compliance with Detail 'B', attached.

6. LABELING

- 5.1 Shingles shall be labeled with the Miami-Dade Logo or the wording "Miami-Dade County-Product Control Approved".

7. BUILDING PERMIT REQUIREMENTS

- 7.1 Application for building permit shall be accompanied by copies of the following:
 - 7.1.1 This Notice of Acceptance.
 - 7.1.2 Any other documents required by the Building Official or the applicable Building Code in order to properly evaluate the installation of this system.




NOA No.: 03-0620.01
Expiration Date: 09/04/08
Approval Date: 09/04/03
Page 2 of 4

DETAIL A

HERITAGE DECLARATION & XL

All dimensions are in inches.




DETAIL B

HERITAGE DECLARATION

12" x 36" LAMINATED SHINGLE


All dimensions are in inches.



HERITAGE XL

12" x 36" LAMINATED SHINGLE

All dimensions are in inches.



END OF THIS ACCEPTANCE





BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Therma-Tru Corporation
108 Mutzfeld Road
Butler, IN 46721

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by the BCCO and accepted by the Building Code and Product Review Committee (BCPRC) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The BCCO (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BCPRC reserves the right to revoke this acceptance, if it is determined by BCCO that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the South Florida Building Code, 1994 Edition for Miami-Dade County or Florida Building Code.

DESCRIPTION: Outswing Glazed Residential Steel Door w/Sidelites

APPROVAL DOCUMENT: Drawing No. S-2003, titled "Therma-Tru Wood edge Outswing", sheets 1 through 6 to 6, prepared by RW Consulting, dated 3/9/01, bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews NOA # 00-0207.06 and, consists of this page 1 as well as approval document mentioned above. The submitted documentation was reviewed by **Raul Rodriguez**.



NOA No 02-0418.01
Expiration Date: April 05, 2007
Approval Date: May 23, 2002
Page 1

THERMA-TRU®

"CONSTRUCTION" AND "PREMIUM" SERIES
INSULATED STEEL DOOR WITH WOOD FRAMES.

GENERAL NOTES

1. THIS PRODUCT IS DESIGNED TO MEET THE SOUTH FLORIDA BUILDING CODE 1994 EDITION FOR MIAMI-DADE COUNTY.
2. WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.
3. PRODUCT ANCHORS SHALL BE AS LISTED AND SPACED AS SHOWN ON DETAILS. ANCHOR EMBLEMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
4. MIAMI-DADE APPROVED IMPACT RESISTANT SHUTTERS ARE REQUIRED.
5. DESIGNED PRESSURE RATING SEE TABLE PAGE 1.
6. SIDELITES ARE AN OPTION AND CAN BE IN A SINGLE OR DOUBLE CONFIGURATION.

RESIDENTIAL INSULATED STEEL DOOR (Common to all frame conditions)


Door Leaf Construction:
Face sheets: 25 GA (0.018") minimum thickness, 4000 Galvanized steel A-525 commercial quality per ASTM 620 with yield strength F_y (min.) = 47,000 psi
Core design: Polyurethane foam core, with 1.9 lbs. density by BASF.
Construction: Flush or embossed type. The vertical edges of the skin, are rolled formed to provide a mechanical interlock with finger jointed pine stiles. Wood composite end rails are butt jointed to stiles at corners. Panels are sandwich glazed using a two piece PVC lite frame with mitered & welded corners.

TABLE OF CONTENTS

SHEET #	DESCRIPTION
1	COMMON (GENERAL NOTES, TYPICAL ELEVATION)
2	VERTICAL CROSS SECTIONS & BILL OF MATERIALS
3	HORIZONTAL CROSS SECTIONS & DOOR MODELS
4	HORIZONTAL CROSS SECTIONS & GLAZING DETAILS
5	ANCHORING LOCATIONS
6	

DESIGN PRESSURE RATING

WHERE WATER INFILTRATION REQUIREMENT IS NEEDED	
POSITIVE	+ 48.0 PSF
NEGATIVE	- 51.0 PSF



ALL DOOR MODELS ARE VIEWED
FROM THE INTERIOR SIDE
(OUTSWING DOORS)

PRODUCT REVIEWED
as compliant with the Florida
Building Code
Acceptance No. 021-2418 C1
Expiration Date 12/31/2007
By: [Signature]
Miami-Dade Product Control
Division


APPROVED AS COMPLIING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE: 4/11/05 JAL
CHK. BY: RW
DRAWING NO.: S-2003
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 020-0207.066

RM BUILDING CONSULTANTS, INC.
813.864.3831

NO.	DATE	REVISIONS
1	4/11/00	GENERAL REVISION
2	3/09/01	GENERAL REVISION
3	4/11/00	GENERAL REVISION

PRODUCT: THERMA TRU WOODGE
OUTSWING UP TO 12-0\"/>

THERMA TRU®
108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811



Item	DESCRIPTION	MATERIAL
1	CONSTRUCT: SERIES DOOR (25GA. .018\" MIN.)	STEEL
2	4 1/2\" LATCH JAMB (THERMA-TRU)	WOOD
3	4 1/2\" HINGE JAMB (THERMA-TRU, PONDEROSA PINE)	WOOD
4	4 1/2\" HINGE JAMB (THERMA-TRU, PONDEROSA PINE)	WOOD
5	4 1/2\" BLANK JAMB (THERMA-TRU, PONDEROSA PINE)	WOOD
6	4\" x 4\" HINGE .097\" THK. (THERMA-TRU)	STEEL
7	#9 x 3/4\" LG. (Hinge to Frame)	STEEL
8	#10 WOOD SCREW X 2 1/2\" LG.	STEEL
9	#8 x 2 1/2\" LG. WOOD SCREW	STEEL
10	3/16\" TAPCON ANCHOR (ELCO, 1.75\" MIN. LG.)	STEEL
11	ONE PIECE BUMP FACE THRESHOLD (THERMA-TRU)	ALUM./WOOD
12	COMPRESSION WEATHERSTRIP (THERMA-TRU)	PVC
13	PLASTIC UP LIE FRAME (PVC, THERMA-TRU)	STEEL
14	#10 x 1 1/4\" LG. TYPE \"A\" FLATHEAD	STEEL
15	TOP & BOTTOM RAIL (1.75\" x 1.625\") (THERMA-TRU, PONDEROSA PINE)	WOOD
16	BLANK SIDE STYLE (THERMA-TRU, PONDEROSA PINE)	WOOD
17	#8 x 1 1/2\" LG. TYPE \"AB\" PANHEAD	STEEL
18	#10 WOOD SCREW X 2\" LG.	STEEL
19	KWIKSET 200 DL PASSAGE	STEEL
20	KWIKSET 660 DEADBOLT	STEEL
21	MASONRY WALL	WOOD
22	2\" WOOD BUCK	WOOD
23	MAX. 1/4\" SHIM MATERIAL	WOOD
24	ASTRAGAL (.052\" WALL THK.)	WOOD/ALUM.
25	GLAZING, 1/2\" INSULATED TREATED GLASS	GLASS
26	3/4\" THK. PRESSURE TREATED SIDELITE PAD	WOOD
27	#12 x 1/2\" LG. PANHEAD SHEET METAL SCREW	STEEL
28	ASTRAGAL WEATHERSTRIP	VINYL
29	#6-18 x 1 3/4\" PHILLIPS FLATHEAD SCREW	STEEL
30	#9 x 1\" LG. PHILLIPS FLATHEAD SCREW	STEEL
31	LATCH SIDE STYLE (THERMA-TRU, PONDEROSA PINE)	WOOD
32	HINGE SIDE STYLE (THERMA-TRU, PONDEROSA PINE)	WOOD
33	CORRUGATED STAPLE FASTENER (1 1/2\" x 3/4\")	STEEL
34	LOCK BLOCK (4\" x 11\" x 1.625\")	WOOD
35	POLYURETHANE FOAM (BASF, 1.9lbs. DENSITY)	FOAM
36	IVES SURFACE BOLT (.25\" STEEL)	STEEL
37	3/16\" TAPCON ANCHOR (ELCO, 3.25\" MIN. LG.)	STEEL
38	1/8\" THK. CELLULAR GLAZING TAPE (STIK-II TAPE)	—

NOTE:
SIDELITE IS DIRECT SET INTO JAMB WITH #10 x 2\" PH.F.H. WOOD SCREWS AT 6\" FROM EACH END AND A MAX. OF 12\" O.C. ON VERTICAL LEG JAMBS ONLY.


THERMA TRU®
108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811

REVISIONS	NO.	DATE
GENERAL REVISION	1	4/11/00
GENERAL REVISION	2	3/09/01
GENERAL REVISION	3	3/09/01
GENERAL REVISION	4	4/11/00
GENERAL REVISION	5	4/11/00
GENERAL REVISION	6	4/11/00
GENERAL REVISION	7	4/11/00
GENERAL REVISION	8	4/11/00
GENERAL REVISION	9	4/11/00
GENERAL REVISION	10	4/11/00
GENERAL REVISION	11	4/11/00
GENERAL REVISION	12	4/11/00
GENERAL REVISION	13	4/11/00
GENERAL REVISION	14	4/11/00
GENERAL REVISION	15	4/11/00
GENERAL REVISION	16	4/11/00
GENERAL REVISION	17	4/11/00
GENERAL REVISION	18	4/11/00
GENERAL REVISION	19	4/11/00
GENERAL REVISION	20	4/11/00
GENERAL REVISION	21	4/11/00
GENERAL REVISION	22	4/11/00
GENERAL REVISION	23	4/11/00
GENERAL REVISION	24	4/11/00
GENERAL REVISION	25	4/11/00
GENERAL REVISION	26	4/11/00
GENERAL REVISION	27	4/11/00
GENERAL REVISION	28	4/11/00
GENERAL REVISION	29	4/11/00
GENERAL REVISION	30	4/11/00
GENERAL REVISION	31	4/11/00
GENERAL REVISION	32	4/11/00
GENERAL REVISION	33	4/11/00
GENERAL REVISION	34	4/11/00
GENERAL REVISION	35	4/11/00
GENERAL REVISION	36	4/11/00
GENERAL REVISION	37	4/11/00
GENERAL REVISION	38	4/11/00
GENERAL REVISION	39	4/11/00
GENERAL REVISION	40	4/11/00
GENERAL REVISION	41	4/11/00
GENERAL REVISION	42	4/11/00
GENERAL REVISION	43	4/11/00
GENERAL REVISION	44	4/11/00
GENERAL REVISION	45	4/11/00
GENERAL REVISION	46	4/11/00
GENERAL REVISION	47	4/11/00
GENERAL REVISION	48	4/11/00
GENERAL REVISION	49	4/11/00
GENERAL REVISION	50	4/11/00


DATE: 3/3/00	SCALE: N.T.S.	DWG. BY: T.J.H.	CHK. BY: RW	DRAWING NO.: S-2003	SHEET 2 OF 6
--------------	---------------	-----------------	-------------	---------------------	--------------

APPROVED AS COMPLYING WITH THE SOUTH FLORIDA BUILDING CODE
BY: [Signature]
Acceptance No. 22-6418, C.1
Expiration Date 2/15/07
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 20-0307-06

PRODUCT REVIEWED
as complying with the Florida Building Code
Acceptance No. 22-6418, C.1
Expiration Date 2/15/07
By: [Signature]
Florida Trade Product Council
Division




1 HORIZONTAL CROSS SECTION
4 SINGLE W/SIDELITES



NOTE:

1. SIDELITE IS DIRECT SET INTO JAMB WITH #10 x 2" PH.F.H. WOOD SCREWS AT 6" O.C. ON VERTICAL LEG JAMBS ONLY.
2. SPACING OF SCREW ITEM #27 IS AS FOLLOWS FOR BOTH 6-8 AND 8-0 MODELS: FROM THE BOTTOM UP AND THE TOP DOWN SPACING IS 1", 3", 5", 7", 10" & 10".
3. SPACING OF SCREW ITEM #29 IS AS FOLLOWS FOR BOTH 6-8 AND 8-0 MODELS: FROM THE BOTTOM UP ON SIDES, 6.438" & (8-0) (7) MORE AT 9.893" & (6-8) (6) MORE AT 9.21" O.C. TOP & BOTTOM, 3.219" FROM THE END IN & (3) MORE AT 5.896" O.C.

2 HORIZONTAL CROSS SECTION
4 DOUBLE



3 DETAIL SEE NOTE 3

THERMA TRU®
108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811


PRODUCT:
THERMA TRU WOODEDGE
OUTSWING UP TO 12-0 x
8-0 W/3-0 SIDELITES

NO.	DATE	REVISIONS
2	3/09/01	GENERAL REVISION RW
1	4/11/00	GENERAL REVISION TJH

RW
BUILDING
CONSULTANTS,
INC.
E13.694.3831

PRODUCT REVIEWED
as supplied with the Florida
Building Code
Acceptance No. C-2-0418 C1
BY: TJH
Expiration Date: 6/10/03
By: Miami Dade Product Control
Division

APPROVED AS COMPLYING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE: 3/3/00
SCALE: N.T.S.
DWG. BY: TJH
CHK. BY: RW
DRAWING NO.: S-2003
ACCEPTANCE NO. 00-0607-06



DATE: 3/2/00		SCALE: N.T.S.		DWG. BY: TJH		CHK. BY: RW		DRAWING NO.: S-2003		SHEET 5 OF 6	
<div style="border: 1px solid black; padding: 5px; text-align: center;">RW BUILDING CONSULTANTS, INC. 813.684.3831</div>											
REVISED											
		NO.		DATE							
		1		4/11/00		GENERAL REVISION		REFEED REVISION		TJH	
		2		5/09/01		GENERAL REVISION		REFEED REVISION		RW	
		BY									

THERMA TRU®
108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811

PRODUCT REVIEWED
 as complying with the Florida
 Building Code
 Acceptance No. C-2-C-418-C1
 Expiration Date 07/15/12

APPROVED AS COMPLYING WITH THE
 SOUTH FLORIDA BUILDING CODE
 DATE APRIL 03, 2008
 BY J. K. G. / C. G. G.

PRODUCT CONTROL DIVISION
 BUILDING CODE COMPLIANCE OFFICE
 ACCEPTANCE NO. 60-0207-06

By [Signature]
 Miami-Dade Product Control
 Division



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

MI Home Products, Inc.
650 West Market Street
Gratz, PA 17030

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "BetterBilt D185SH/D3185SH" Aluminum Single Hung Window

APPROVAL DOCUMENT: Drawing No. S-2422, titled "Non-Impact Single Hung Window Rectangle Circle Top & Oriel", sheets 1 through 5 of 5, prepared by RW Building Consultants, inc, dated 10/27/03 with revision "2", dated 02/10/04, signed and sealed by Wendell Haney, P.E., bearing the Miami-Dade County Product Control Approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by **Theodore Berman, P.E.**



NOA No 03-1215.02
Expiration Date: March 04, 2009
Approval Date: March 04, 2004
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
2. Drawing No. **S-2422**, titled "Non-Impact Single Hung Window Rectangle Circle Top & Oriel", sheets 1 through 5 of 5, prepared by RW Building Consultants, inc, dated 10/27/03 with revision "2", dated 02/10/04, signed and sealed by Wendell Haney, P.E.

B. TESTS

1. Test reports on 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Forced Entry Test, per FBC 2411.3.2.1 and TAS 202-94
along with marked-up drawings and installation diagram of an aluminum single hung window, prepared by Architectural Testing, Inc., Test Report No. **ATI 03056**, dated 11/11/03, signed by Joseph A. Reed, P.E.

C. CALCULATIONS

1. Anchor Calculations, ASTM-E1300-98, and structural analysis, prepared by R.W. Building Consultants, Inc., dated 12/11/03, signed and sealed by Lyndon F. Schmidt, P.E.
2. Revised Anchor Calculations, and structural analysis, prepared by R.W. Building Consultants, Inc., dated 02/10/04, signed and sealed by Lyndon F. Schmidt, P.E.

D. QUALITY ASSURANCE

1. Miami Dade Building Code Compliance Office (BCCO).

E. MATERIAL CERTIFICATIONS


1. None.

F. STATEMENTS

1. Statement letter of conformance and no financial interest, dated December 09, 2003, signed and sealed by Lyndon F. Schmidt, P.E.
2. Statement letter of no financial interest with the laboratory that performed the Test Report No. **ATI 03056**, dated November 08, 2003, signed by Stu White, Design Engineering Manager.

G. OTHER

1. Letter from the consultant stating that the product is in compliance with the Florida Building Code (FBC).



Theodore Berman, P.E.

Deputy Director, Product Control Division

NOA No 03-1215.02

Expiration Date: March 04, 2009


Approval Date: March 04, 2004




MI HOME PRODUCTS
650 WEST MARKET STREET • GRATZ, PA • 17030-0370
SERIES BETTERBILT D185SH/D3185SH
ALUMINUM SINGLE HUNG WINDOW

GENERAL NOTES:


1. THIS PRODUCT IS DESIGNED TO COMPLY WITH THE "HVHZ" OF THE FLORIDA BUILDING CODE
2. WOOD BUCKS MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO STRUCTURE AND TO BE REVIEWED BY BUILDING OFFICIAL.
3. PRODUCT ANCHORS SHALL BE AS LISTED AND SPACED AS SHOWN ON DETAILS. STUCCO ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
4. FOR DESIGN PRESSURE RATING SEE TABLE THIS SHEET.
5. INSTALLATION OF THIS SYSTEM IN HVHZ AREA REQUIRES THE USE OF APPROVED SHUTTER/EXTERNAL PROTECTION DEVICE COMPLYING WITH HVHZ REQUIREMENTS; INSTALLATION OF THIS SYSTEM OUTSIDE OF HVHZ SHALL MEET THE APPLICABLE CODE REQUIREMENTS FOR WINDBORNE DEBRIS PROTECTION.
6. THIS PRODUCT MEETS WATER REQUIREMENTS FOR HIGH VELOCITY HURRICANE ZONES.




53" x 73" SINGLE HUNG WINDOW
CIRCLE TOP ORIEL




53" x 73" SINGLE HUNG WINDOW
HALF CIRCLE TOP ORIEL



53" x 84" SINGLE HUNG WINDOW
CIRCLE TOP ORIEL



53" x 84" SINGLE HUNG WINDOW
HALF CIRCLE TOP ORIEL



36" MAX. OVERALL
FRAME WIDTH



36" MAX. OVERALL
FRAME WIDTH

53" x 73" SINGLE HUNG WINDOW

53" x 84" SINGLE HUNG WINDOW

PRODUCT:
NON-IMPACT SINGLE HUNG
WINDOW RECTANGLE
CIRCLE TOP & ORIEL
PART OR ASSEMBLY:
GENERAL NOTES &
TYPICAL ELEVATIONS

NO.	DATE	REVISIONS
1	01/04	REVISED PER DADE LETTER
2	2/10/04	CORRECT DP TABLE

DATE: 10/27/03
SCALE: N.T.S.
DWG. BY: TJH
CHK. BY: RW
DRAWING NO.: S-2422
SHEET 1 of 5


SHEET #	DESCRIPTION
1	GENERAL NOTES & TYPICAL ELEVATIONS
2	VERTICAL CROSS SECTIONS
3	HORIZONTAL CROSS SECTIONS & GLAZING DETAIL
4	ANCHORING LOCATIONS
5	COMPONENTS, BILL OF MATERIALS


GLASS	MAX. SIZE	DP POS.	DP NEG.
1/8" Temp.	OA 53" x 73"	+56.7	-69.3
1/8" Temp.	OA 37" x 84"	+56.7	-69.3
3/16" Ann.	OA 53" x 73"	+42.0	-42.0
3/16" Ann.	OA 37" x 84"	+56.7	-58.0

ALL ELEVATIONS ARE VIEWED FROM EXTERIOR

Approved as complying with the
Florida Building Code
P.O. Box 230 Venice FL 33595
Phone No. 813.888.9197
BUILDING CONSULTANTS, INC.
Product Approval Documents Prepared By:
R.W. Mendel
Certificate of Professional Engineer
Florida Board of Professional Engineers
2/10/04

DATE: 10/27/03 SCALE: N.T.S. DWG. BY: T.J.H. CHK. BY: RW DRAWING NO.: S-2422 SHEET 2 of 5		Approved as complying with the Florida Building Code Presc. 02102-104 NOMAD 02-1215-02 National Trade Products Council Division By: <i>Wendell Hodge</i>	
REVISIONS NO. DATE 1 01/04 REVISED PER DADE LETTER 2 2/10/04 CORRECT DP TABLE		PRODUCT: NON-IMPACT SINGLE HUNG WINDOWS RECTANGLE, CIRCLE TOP & ORIAL PART OR ASSEMBLY: CROSS SECTIONS VERTICAL	
BUILDING CONSULTANTS, INC. P.O. Box 230 Venice, FL 33595 Phone No: 813.659.9197 Certificate of Professional Engineers Florida Board of Professional Engineers No. 9813 2/10/04 Wendell Hodge, P.E. No. 54158		Product Approval Documents Prepared By: <i>R.W.</i>	






NOTES:

1. FOR UNITS SMALLER THAN 30"x60" DO NOT INSTALL ANCHOR AT CENTER LOCATION.
2. FOR UNITS SMALLER THAN 53"x60" OR SMALLER THAN 30"x66" DO NOT INSTALL ANCHOR AT CENTER LOCATION.
3. FOR UNITS SMALLER THAN 36"x66" DO NOT INSTALL ANCHORS AT EITHER SIDE OF CENTER ANCHOR AT HEAD AND SILL JAMBS.

SHEET 4 OF 5		S-2422		DRAWING NO:		CHK BY: RW		CHK BY: TJH		SCALE: N.T.S.		DATE: 10/27/03	
												NO. DATE	
												2 2/10/04	
												1 01/04	
												CORRECT DP TABLE	
												REVISED PER DADE LETTER	
												WH	
												BY	
REVISIONS													

BILL OF MATERIALS		
ITEM	DESCRIPTION	MATERIAL
1	EXTRUDED ALUMINUM SINGLE HUNG 1/2" HEAD #CM-18501 BY MI METALS	ALUM.
2	EXTRUDED ALUMINUM SINGLE HUNG 1/2" SILL #CM-18502 BY MI METALS	ALUM.
3	EXTRUDED ALUMINUM SINGLE HUNG 1/2" JAMB #CM-18503 BY MI METALS	ALUM.
4	EXTRUDED ALUMINUM SINGLE HUNG FIXED MEETING RAIL #CM-18504 BY MI METALS	ALUM.
5	EXTRUDED ALUMINUM SINGLE HUNG SASH LOCK RAIL #CM-18505 BY MI METALS	ALUM.
6	EXTRUDED ALUMINUM SINGLE HUNG SASH BOTTOM RAIL #CM-18506 BY MI METALS	ALUM.
7	EXTRUDED ALUMINUM SINGLE HUNG SASH STILE #CM-18507 BY MI METALS	ALUM.
8	SASH CAM #I-185 BY BSI	-
9	GLAZING BEAD #V-185 BY MI PLASTICS	-
10	LOCK #30240-402 BY REFLECTOLITE	-
11	MAIN FRAME SCREW #8 x 3/4" PHILLIPS PAN HEAD	STEEL
12	MEETING RAIL SCREW #8 x 1 1/4" PHILLIPS PAN HEAD	STEEL
13	SASH SCREW #6 x 3/4" PHILLIPS PAN HEAD	STEEL
14	LOCK SCREW #8 x 5/8" PHILLIPS FLAT HEAD -PTD	STEEL
15	SASH GUIDE #80-02-8207 BY PLASTICS, AZ	-
16	WINDOW SCREEN	-
17	FIN WEATHERSTRIPPING .187" x .250" BY AMESBURY	-
18	BULB SEAL #32002 BY AMESBURY	-
19	DUST PLUG 5/8" x 7/8" x .25" BY AMESBURY	-
20	5/8" BLOCK & TACKLE 150 SERIES BY BSI	-
21	GLASS "A" SGL GLAZED 3/16" ANN. BY GUARDIAN	-
22	GLASS "B" SGL GLAZED 1/8" TEMP. BY GUARDIAN	-
23	BACKBEDDING #SM-2100 BY SCHNEE MOREHEAD	SILICONE
24	BACKBEDDING PERFECTGLAZE-H (HOTMELT)	-
25	GLASS SHIM 1/8" x 1/4" x 1" BY SECON	-
26	1/4" MAX SHIM	-
27	#12 X 2" PHILLIPS FLAT HEAD SHEET METAL SCREW	STEEL
28	3/16" x 3 1/4" ELCO TAPCON ANCHOR	STEEL
29	3/16 x 2 3/4" ELCO TAPCON ANCHOR	STEEL



Approved as existing with the
Florida Building Code
Date 03/03/04
NOA 03-125-02
Miami Building Products Company
By: *[Signature]*

Product Approval Document Prepared By:
BUILDING CONSULTANTS, INC.
P.O. Box 230 Venice, FL 33595
Phone No.: 813.659.9197
Certificate Of Authorization No. 9813
Florida Board of Professional Engineers
2/10/04
Wendell Hanks, P.E. NO. 37156

PRODUCT:
NON-IMPACT SINGLE HUNG
CIRCLE TOP & OREAR
PART OR ASSEMBLY:
BILL OF MATERIALS
& UNIT COMPONENTS

REVISIONS	
NO.	DATE
1	01/04
2	2/10/04
CORRECT DP TABLE	
REVISED PER DATE LETTER	
BY	WH
BY	RW

DATE: 10/27/03
SCALE: N.T.S.
DWG. BY: TJH
CHK. BY: RW
DRAWING NO.: S-2422
SHEET 5 OF 5



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Mi Home Products, Inc.
650 West Market Street
Gratz, PA 17030

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "Betterbilt D485/D3485" Aluminum Sliding Patio Door

APPROVAL DOCUMENT: Drawing No. S-2425, titled "Non-Impact Aluminum Sliding Patio Door Up to 6'0 x 6'8", sheets 1 through 5 of 5, prepared by R.W. Building Consultants, Inc., dated 12/18/03, signed and sealed by Lyndon F. Schmidt, P.E., bearing the Miami-Dade County Product Control Approval stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA consists of this page 1 and evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by **Theodore Berman, P.E.**

CM
2/13/2004



NOA No 03-1224.01
Expiration Date: March 04, 2009
Approval Date: March 04, 2004
Page 1

Mi Home Products, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.

Drawing No. S-2425, titled "Non-Impact Aluminum Sliding Patio Door Up to 6'0 x 6'8", sheets 1 through 5 of 5, prepared by R.W. Building Consultants, Inc., dated 12/18/03, signed and sealed by Lyndon F. Schmidt, P.E.

B. TESTS

1. Test reports on 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Forced Entry Test, per FBC 2411.3.2.1 and TAS 202-94
along with marked-up drawings and installation diagram of an aluminum patio door, prepared by Architectural Testing, Test Report No. ATI-03064 dated 12/17/03, signed and sealed by Steven M. Urich, P.E.

C. CALCULATIONS

1. Anchor Calculations, ASTM-E1300-98, and structural analysis, prepared by R.W. Building Consultants, Inc., dated 12/22/03, signed and sealed by Lyndon Schmidt, P.E.
2. Revised Anchor Calculations and structural analysis, prepared by R.W. Building Consultants, Inc., dated 02/10/03, signed and sealed by Lyndon Schmidt, P.E.

D. QUALITY ASSURANCE

1. Miami Dade Building Code Compliance Office (BCCO).

E. MATERIAL CERTIFICATIONS


1. None.

F. STATEMENTS

1. Statement letter of compliance and of no financial interest, dated 12/18/03, signed and sealed by Lyndon F. Schmidt, P.E.
2. Letter from MI Home Products, Inc., dated 11/08/03, stating that they have no financial interest with the laboratory that performed the testing of their products, signed by Stu White.

G. OTHER

1. Letter from the consultant stating that the product is in compliance with the Florida Building Code.




Theodore Berman, P.E.
Deputy Director, Product Control Division
NOA No 03-1224.01
Expiration Date: March 04, 2009
Approval Date: March 04, 2004

MI HOME PRODUCTS
 650 WEST MARKET STREET • GRAFT, PA • 17030-0370
SERIES BETTERBILT D485/D3485
ALUMINUM SLIDING PATIO DOOR

- GENERAL NOTES:**
1. THIS PRODUCT IS DESIGNED TO COMPLY WITH THE HVHZ FLORIDA BUILDING CODE.
 2. WOOD BLOCKS MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO STRUCTURE AND TO BE REVIEWED BY BUILDING OFFICIAL.
 3. PRODUCT ANCHORS SHALL BE AS LISTED AND SPACED AS SHOWN ON DETAILS. ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
 4. FOR DESIGN PRESSURE RATING SEE TABLE THIS SHEET.
 5. INSTALLATION OF THIS SYSTEM IN HVHZ AREA REQUIRES THE USE OF APPROVED SHUTTER/EXTERNAL PROTECTION DEVICE COMPLYING WITH HVHZ REQUIREMENTS. INSTALLATION OF THIS SYSTEM OUTSIDE OF HVHZ SHALL MEET THE APPLICABLE CODE REQUIREMENTS FOR WINDBORNE DEBRIS PROTECTION.
 6. THIS PRODUCT MEETS WATER REQUIREMENTS FOR HIGH VELOCITY HURRICANE ZONES.

TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	GENERAL NOTES & TYPICAL ELEVATIONS
2	VERTICAL CROSS SECTIONS & CONSTRUCTION NOTES
3	HORIZONTAL CROSS SECTIONS
4	ANCHORING LOCATIONS & GLAZING DETAIL
5	BILL OF MATERIALS & UNIT COMPONENTS





ALL ELEVATIONS ARE VIEWED FROM EXTERIOR


DESIGN PRESSURE RATING
 +57.52 PSF -74.0 PSF

Approved as complying with the
 Florida Building Code
 Noted 08/04/04
 Noted 08/12/25/01
 Building Code Product Control
 By: [Signature]

DATE: 12/18/03		PRODUCT:		Product Approval Documents Prepared By: <i>RW</i> BUILDING CONSULTANTS, INC. P.O. Box 230 Volusia FL 32955 Phone No.: 813.659.9197 Florida Board of Professional Engineers Certificate Of Authorization No. 9813 <i>Lyndon F. Schmidt</i> 12/22/03 Lyndon F. Schmidt, P.E. NO. 43409
SCALE: N.T.S.		NON-IMPACT ALUMINUM SLIDING PATIO DOOR UP TO 6'0" x 6'8"		
DRW. BY: TJH		PART OR ASSEMBLY:		
CHK. BY: RW		GENERAL NOTES & TYPICAL ELEVATIONS		
DRAWING NO.: S-2425				
SHEET 1 OF 5				
</				




FRAME CONSTRUCTION NOTE:
THE FRAME CORNERS ARE BUTTED AND SECURED WITH (2) ITEM #19, A #8 x 5/8\"/>




Approved as shown with the
Florida Building Code
Date: 02/24/03
RMA/02-12425-01
Michael David Frederick, Owner
By: [Signature] 02/24/03

DATE: 12/18/03		SCALE: N.T.S.		DWG. BY: TJH		CHK. BY: RW		DRAWING NO.: S-2425		SHEET 2 OF 5	
NO.		DATE		BY		REVISIONS		PRODUCT: NON-IMPACT ALUMINUM SLIDING PATIO DOOR UP TO 6'0" x 6'8"			
								PART OR ASSEMBLY: VERTICAL CROSS SECTIONS & CONSTRUCTION NOTES			
								Product Approval Documents Prepared By: <i>RW</i> BUILDING CONSULTANTS, INC. P.O. Box 230 Valrico FL 33595 Phone No.: 813.659.9197 Florida Board of Professional Engineers Certificate of Authorization No. 9813 <i>Lyndon F. Schmidt</i> 12/22/03 Lyndon F. Schmidt, P.E. No. 43409			

Product Approval Documents Prepared By:
RW BUILDING CONSULTANTS, INC.
P.O. Box 230 Valrico FL 33595
Phone No.: 813.659.9167
Florida Board of Professional Engineers
Certificate Of Authorization No. 9813
12/22/03
Lyndon F. Schmidt, P.E. NO. 43409




1 HORIZONTAL CROSS SECTION
3 W/2X BUCK



1 HORIZONTAL CROSS SECTION
3 W/1X BUCK

Approved as representing with date
 Florida Building Code
 Book 08/04/04
 MOAB 05-122-901
 Miami-Dade Building Official
 by *Lyndon F. Schmidt*



DATE: 12/18/03		PRODUCT:		Product Approval Documents Prepared By: <i>RW</i> BUILDING CONSULTANTS, INC. P.O. Box 230 Valrico FL 33595 Phone No.: 813.659.9197 Florida Board of Professional Engineers Certificate Of Authorization No. 9813 <i>Lyndon F. Schmidt</i> 12/22/03 Lyndon F. Schmidt, P.E. NO. 43409	
SCALE: N.T.S.		NON-IMPACT ALUMINUM SLIDING PATIO DOOR UP TO 6'0" x 6'8"			
DWG. BY: TJH		PART OR ASSEMBLY:			
CHK. BY: RW		HORIZONTAL CROSS SECTIONS			
DRAWING NO.: S-2425		BY			
SHEET 3 OF 5		REVISIONS			



6'0" x 6'8" PATIO DOOR
SEE NOTES SHT. 4

- NOTES:
1. WHEN ANCHORING THE UNIT TO A 2X BUCK TO MASONRY USE ITEM #21, A #10 x 1 3/4" PHILLIPS FLAT HEAD SHEET METAL SCREW AT THE HEAD AND SIDES.
 2. WHEN ANCHORING THE UNIT THROUGH A 1X BUCK INTO MASONRY USE ITEM #20, A 3/16" x 2 3/4" TAPCON ANCHOR AT THE HEAD AND SIDES.
 3. USE (2) ANCHORS PER EACH ANCHORING LOCATION SHOWN ABOVE.

5'0" x 6'8" PATIO DOOR
SEE NOTES SHT. 4



5/32" TEMPERED GLASS
GLAZING DETAIL

DETAIL B
JAMB KEEPER ATTACHMENT

Approved as existing with the
Florida Building Code
Date: 03/04/04
RWA 03-12-24-01
Miami Design Freedom Council
By: *Lynden F. Schmidt*




DATE: 12/18/03
SCALE: N.T.S.
DWC: TJH
CHK: RW
DRAWING NO.: S-2425
SHEET 4 OF 5

NO.	DATE	REVISIONS	BY

PRODUCT:
NON-IMPACT ALUMINUM
SLIDING PATIO DOOR
UP TO 6'0" x 6'8"
PART OR ASSEMBLY:
ANCHORING LOCATIONS
& GLAZING DETAILS

Product Approval Documents Prepared By:
BUILDING CONSULTANTS, INC.
P.O. Box 230 Valrico FL 33595
Phone No.: 813.859.9197
Florida Board of Professional Engineers
Certificate of Authorization No. 9813
12/22/03
Lynden F. Schmidt, P.E. NO. 43409

BILL OF MATERIALS	
ITEM	MATERIAL
DESCRIPTION	
1 EXTRUDED ALUM. MAIN FRAME HEAD #4208 BY MI METALS	ALUM.
2 EXTRUDED ALUM. MAIN FRAME SILL #4235 BY MI METALS	ALUM.
3 EXTRUDED ALUM. MAIN FRAME JAMB #4210 BY MI METALS	-
4 EXTRUDED ALUM. PANEL SILL #4201 MI METALS	ALUM.
5 EXTRUDED ALUM. PANEL HEAD #4202 BY MI METALS	ALUM.
6 EXTRUDED ALUM. PANEL INTERLOCK #4204 BY MI METALS	ALUM.
7 EXTRUDED ALUM. PANEL LOCK JAMB #4206 BY MI METALS	ALUM.
8 GLAZING CHANNEL #80-02-4250 BY MI PLASTICS	V-FLK
9 GLAZING 5/32" TEMPERED GLASS	GLASS
10 MORTISE HANDLE SET #99-04-150 BY THRUH HARDWARE	STEEL
11 TANDEN PANEL ROLLER #99-17-195 BY ULTRA	STEEL
12 CENTER FIN SEAL .180 x .250 PANEL HEAD & INTERLOCK BY AMESBURY	SYN. PILE
13 SIDE FIN SEAL .180 x .350 PANEL SILL BY AMESBURY	SYN. PILE
14 CENTER FIN SEAL .187 x .290 PANEL JAMB BY AMESBURY	SYN. PILE
15 NO FIN SEAL .270 x .290 SILL BY AMESBURY	SYN. PILE
16 #6 x 3/4" SQ. DR. SCREW PANEL HEAD TO JAMB	STEEL
17 1/4"-20 x 3/4" SQ. DR. SCREW FOR PANEL ASSEMBLY	STEEL
18 INTERLOCK REINFORCEMENT #99-17-525 BY MAGNOLIA METALS	STEEL
19 #8 x 5/8" FLAT HEAD SCREW FRAME CORNERS	STEEL
20 3/16" x 2 3/4" TAPCON ANCHOR	STEEL
21 #10 x 1 3/4" SHEET METAL SCREW	STEEL
22 1/4" MAX. SHIM MATERIAL	-
23 3/16" x 1 3/4" TAPCON ANCHOR	STEEL
24 ROLLING SCREW DOOR ASSEMBLY	-
25 EXTRUDED ALUM. PANEL RETAINER #4222 BY MI METALS	ALUM.
26 #8 x 2" PHILLIPS PAN HEAD SHEET METAL SCREW	STEEL



DATE: 12/18/03									
SCALE: N.T.S.									
DWG. BY: TJH									
CHEK. BY: RW									
DRAWING NO.: S-2425									
	NO.	DATE							



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA
METRO-DADE FLAGLER BUILDING
140 WEST FLAGLER STREET, SUITE 1603
MIAMI, FLORIDA 33130-1563
(305) 375-2901 FAX (305) 375-2908

NOTICE OF ACCEPTANCE (NOA)

Therma-Tru Corporation
108 Mutzfeld Road
Butler, IN 46721

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by the BCCO and accepted by the Building Code and Product Review Committee (BCPRC) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The BCCO (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BCPRC reserves the right to revoke this acceptance, if it is determined by BCCO that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the South Florida Building Code, 1994 Edition for Miami-Dade County or Florida Building Code.

DESCRIPTION: Outswing Glazed Residential Steel Door w/Sidelites

APPROVAL DOCUMENT: Drawing No. S-2003, titled "Therma-Tru Wood edge Outswing", sheets 1 through 6 to 6, prepared by RW Consulting, dated 3/9/01, bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **renews** NOA # 00-0207.06 and, consists of this page 1 as well as approval document mentioned above. The submitted documentation was reviewed by **Raul Rodriguez**.



NOA No 02-0418.01
Expiration Date: April 05, 2007
Approval Date: May 23, 2002
Page 1

THERMA-TRU®

"CONSTRUCTION" AND "PREMIUM" SERIES
INSULATED STEEL DOOR WITH WOOD FRAMES.

GENERAL NOTES

1. THIS PRODUCT IS DESIGNED TO MEET THE SOUTH FLORIDA BUILDING CODE 1994 EDITION FOR MIAMI-DADE COUNTY.
2. WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE.
3. PRODUCT ANCHORS SHALL BE AS LISTED AND SPACED AS SHOWN ON DETAILS. ANCHOR EMBEDMENT TO S&S MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
4. MIAMI-DADE APPROVED IMPACT RESISTANT SHUTTERS ARE REQUIRED.
5. DESIGNED PRESSURE RATING SEE TABLE PAGE 1.
6. SIDELITES ARE AN OPTION AND CAN BE IN A SINGLE OR DOUBLE CONFIGURATION.

RESIDENTIAL INSULATED STEEL DOOR (Common to all frame conditions)

Door Leaf Construction:
Face sheets: 25 GA.(0.018") minimum thickness
Galvanized steel A-525 commercial quality, 4000 psi
per ASTM 620 with yield strength $F_y(\min.)=47,000$ psi
Core design: Polyurethane foam core,
with 1.9 lbs. density by BASF.
Construction: Flush or embossed type. The vertical
edges of the skin, are rolled formed to provide a
mechanical interlock with finger jointed pine stiles.
Wood composite end rails are butt jointed to stiles
at corners. Panels are sandwich glazed using a two
piece PVC lite frame with mitered & welded corners.


TABLE OF CONTENTS

SHEET #	DESCRIPTION
1	COMMON (GENERAL NOTES, TYPICAL ELEVATION)
2	VERTICAL CROSS SECTIONS & BILL OF MATERIALS
3	HORIZONTAL CROSS SECTIONS & DOOR MODELS
4	HORIZONTAL CROSS SECTIONS & GLAZING DETAILS
5	ANCHORING LOCATIONS
6	ANCHORING LOCATIONS

DESIGN PRESSURE RATING

WHERE WATER INFILTRATION REQUIREMENT IS NEEDED
POSITIVE
NEGATIVE

+ 48.0 PSF
- 51.0 PSF



ALL DOOR MODELS ARE VIEWED
FROM THE INTERIOR SIDE
(OUTSWING DOORS)

PRODUCT REVIEWED
as compliant with the Florida
Building Code
Acceptance No. 02-0218-01
Expiration Date 12/31/2004
By: [Signature]
Miami Dade Product Control
Division


APPROVED AS COMPLIING WITH THE
SOUTH FLORIDA BUILDING CODE
DATE: 4/11/00
BY: [Signature]
PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 02-0218-01

DATE: 3/3/00
SCALE: N.T.S.
DWG. BY: TJH
CHK. BY: RW
DRAWING NO.: S-2003
SHEET 1 OF 6

RW BUILDING
CONSULTANTS, INC.
813.684.3831

NO.	DATE	REVISIONS
1	4/11/00	GENERAL REVISION
2	3/09/01	GENERAL REVISION
3	8-0-W-3-0	OUTSWING UP TO 12-0"
4		8-0-W-3-0 SIDELITES
5		PART OR ASSEMBLY
6		ELEVATIONS AND
7		GENERAL NOTES

THERMA-TRU®
108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811




PRODUCT RENEWED
as complying with the Florida
Building Code
Acceptance No. 0-2-C-416, C-1
Expiration Date 04/15/2007

APPROVED AS COMPLYING WITH THE
DATE APRIL 05, 2007
BY 15449-1-Chuan He

PRODUCT CONTROL DIVISION
BUILDING CODE COMPLIANCE OFFICE
ACCEPTANCE NO. 20-0207-0.6

REVISIONS	BY	VERTICAL CROSS SECTIONS & BILL OF MATERIALS
GENERAL REVISION	TJH	
GENERAL REVISION	RW	PART OR ASSEMBLY
		8-0 W/3-0 SIDELITES
		OUTWING UP TO 12-0
		THERMA TRU WOODEDGE *
		PRODUCT:

108 MUTZFELD RD.
BUTLER, IN 46721
PH. (219) 868-5811



THERMA TRU®
 108 MUTZFELD Rd.
 BUTLER, IN 46721
 PH. (219) 868-5811


PRODUCT:	
THERMA TRU WOODEDGE OUTSWING UP TO 12-0 x 8-0 W/3-0 SIDELITES	
PART OR ASSEMBLY:	
NO.	DATE
2	3/09/01
1	4/11/00
REVISIONS	
BY	


RW BUILDING CONSULTANTS, INC.
 813.884.3831

PRODUCT RENEWED
 as complying with the Florida Building Code
 Acceptance No. C-2-0413-01
 Expiration Date 04/05/14
 By: [Signature]
 Division

APPROVED AS COMPLYING WITH THE
 SOUTH FLORIDA BUILDING CODE
 DATE: APRIL 03, 2001
 BY: [Signature]
 PRODUCT CONTROL DIVISION
 BUILDING CODE COMPLIANCE OFFICE
 ACCEPTANCE NO. 60-0207-566

DATE: 3/3/00
 SCALE: N.T.S.
 DWG. BY: TJH
 CHK. BY: RW
 DRAWING NO.: S-2003
 SHEET 3 OF 6





THERMA TRU®
 108 MUTZFELD RD.
 BUTLER, IN 46721
 PH. (219) 868-5811

REVISIONS	DATE	BY
1	4/11/00	TJH
2	3/09/01	RW

GENERAL REVISIONS
 PART OR ASSEMBLY
 THERMA TRU WOODEDGE
 OUTSWING UP TO 12-0" x
 8-0" W/3-0 SIDELITES
 ANCHORING LAYOUTS

NO.	DATE	BY
1	4/11/00	TJH
2	3/09/01	RW

GENERAL REVISIONS
 PART OR ASSEMBLY
 THERMA TRU WOODEDGE
 OUTSWING UP TO 12-0" x
 8-0" W/3-0 SIDELITES
 ANCHORING LAYOUTS

DATE: 3/2/00
 SCALE: N.T.S.
 DWG. BY: TJH
 CHK. BY: RW
 DRAWING NO.: S-2003
 SHEET 5 OF 5

APPROVED AS COMPLYING WITH THE
 SOUTH FLORIDA BUILDING CODE
 DATE: APRIL 23, 2001
 BY: [Signature]
 PRODUCT CONTROL DIVISION
 BUILDING CODE COMPLIANCE OFFICE
 ACCEPTANCE NO. 00-0207-06

NOTES: APPLICABLE TO ALL FRAMES
 1. HEAD JAMBS ARE JOINED TO THE SIDE JAMBS
 WITH (3) 16GA. .5" CROWN x 2" LG. STAPLES
 EACH END.
 2. THE THRESHOLDS ARE JOINED TO THE SIDE
 JAMBS WITH (2) 16GA. .5" CROWN x 2" LG.
 STAPLES EACH END.
 3. MULLIONS ARE ATTACHED AT THE HEAD & SILL TO
 SIDE JAMBS W/(3) 16GA. .5" CROWN x 2" LG.
 STAPLES.

DETAIL "E"
 ATTACH ASTRAGAL THROW BOLT
 STRIKE PLATE TO FRAME
 AS SHOWN.

DETAIL "D"
 HINGE DETAIL

DETAIL "F"
 MULLION DETAIL

Summary Energy Code Results

Residential Whole Building Performance Method A

Project Title:
St. Johns Model- Creek Run Lot#1

Code Only
Professional Version
Climate: North

1/4/2008

Building Loads			
Base		As-Built	
Summer:	26630 points	Summer:	22337 points
Winter:	19669 points	Winter:	18201 points
Hot Water:	9697 points	Hot Water:	9697 points
Total:	55996 points	Total:	50234 points

Energy Use			
Base		As-Built	
Cooling:	8655 points	Cooling:	5471 points
Heating:	10896 points	Heating:	7541 points
Hot Water:	10540 points	Hot Water:	10316 points
Total:	30091 points	Total:	23328 points

PASS
e-Ratio: 0.78

New Construction Subterranean Termite Soil Treatment Record

OMB Approval No. 2502-0525

This form is completed by the licensed Pest Control Company.

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is mandatory and is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when soil treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Operator and builder, unless stated otherwise.

Section 1: General Information (Treating Company Information)

Company Name: Aspen Pest Control, Inc.
Company Address: 301 NW Cole Terrace City: Lake City State: FL Zip: 32025
Company Business License No. JF104378 Company Phone No. 386-755-3611
FHA/VA Case No. (if any) _____

Section 2: Builder Information

Company Name: Trent Geibiege Const. Company Phone No. 397-0545

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) 398 SE Holly Trl.
Lake City, FL 32025
Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____
Approximate Depth of Footing: Outside 1' Inside 2' Type of Fill Sand

Section 4: Treatment Information

Date(s) of Treatment(s) 2/14/08
Brand Name of Product(s) Used Terminator
EPA Registration No. 7469-210
Approximate Final Mix Solution % 0.06%
Approximate Size of Treatment Area: Sq. ft. 2938 Linear ft. 362 Linear ft. of Masonry Voids 348
Approximate Total Gallons of Solution Applied 730 gals.
Was treatment completed on exterior? ☐ Yes ☒ No
Service Agreement Available? ☒ Yes ☐ No

Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____

Comments _____

Name of Applicator(s) S. Gregory Certification No. (if required by State law) JF104378

The applicator has used a product in accordance with the product label and state requirements. All treatment materials and methods used comply with state and federal regulations.

Authorized Signature Shannon Gregory Date 2/14/08

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form NPCA-99-B may still be used

form HUD-NPCA-99-B (04/2003)

CERTIFICATE OF OCCUPANCY

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 21-4S-17-08631-101

Building permit No. 000026709

Use Classification SFD, UTILITY

Fire: 0.00

Permit Holder TRENT GIEBEIG

Waste: 0.00

Owner of Building PETE GIEBEIG

Total: 0.00

Location: 398 SE HOLLY TERR., LAKE CITY, FL

Date: 10/27/2009

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)





26709
BRITT SURVEYING
830 West Duval Street • Lake City, FL 32055
Phone (386) 752-7163 • Fax (386) 752-5573

*Land Surveyors
and Mappers*

02/11/08

L-19115


To Whom It May Concern:

C/o: Trent Giebeig

Re: Lot 1 Creek Run

The elevation of the foundation is found to be 108.24 feet. The recommended finished floor elevation is 100.00 feet as per the plat of record. The highest adjacent grade is 105.46 feet and the lowest adjacent grade is 105.10 feet. The centerline of the adjacent road SE Holly Terrace is 106.65 feet. The elevations shown hereon are based on NGVD 29 Datum.

L. Scott Britt
PLS #5757



Project Information for: L265053

Builder: Trent Giebeig Construction, Inc.
Lot : 1
Subdivision: Creek Run
County: Columbia
Truss Count: 28

Design Program: MiTek 20/20 6.3
Building Code: FBC2004/TPI2002

Truss Design Load Information:

Gravity: **Wind:**

Roof (psf): 42.0 Wind Standard: ASCE 7-02 Wind Exposure: B
Floor (psf): N/A Wind Speed (mph): 110

Note: See the individual truss drawings for special loading conditions.

Contractor of Record, responsible for structural engineering:

Brian T. Giebeig Florida Registered Residential Contractor License No. RR282811523
Address: Trent Giebeig Construction, Inc. 462 Southwest Fairlington Court Lake City, Florida 320

Truss Design Engineer: Julius Lee, PE Florida P.E. License No. 34869

Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

Notes:


1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-2002 Section 2.2
2. The seal date shown on the individual truss component drawings must match the seal date on this index sheet.
3. The Truss Design Engineer's responsibility relative to this structure consists solely of the design of the individual truss components and does not include the design of any additional structural elements including but not limited to continuous lateral bracing elements in the web and chord planes. See Florida Administrative Code 61G15-31.003 sections 3 c) & 5 and Chapter 2 of the National Design Standard for Metal Plate Connected Wood Truss Construction ANSI/TPI 1-2002 for additional information on the responsibilities of the delegated "Truss Design Engineer". Builders FirstSource and Julius Lee, PE do not accept any additional delegations beyond the scope of work described in the referenced documents above.

No.	Drwg. #	Truss ID	Date
1	J1924728	CJ1	1/10/08
2	J1924729	CJ3	1/10/08
3	J1924730	CJ5	1/10/08
4	J1924731	EJ5	1/10/08
5	J1924732	EJ7	1/10/08
6	J1924733	HJ7	1/10/08
7	J1924734	HJ9	1/10/08
8	J1924735	HJ9A	1/10/08
9	J1924736	PB01	1/10/08
10	J1924737	T01	1/10/08
11	J1924738	T02	1/10/08
12	J1924739	T03	1/10/08
13	J1924740	T04	1/10/08
14	J1924741	T05	1/10/08
15	J1924742	T06	1/10/08
16	J1924743	T07	1/10/08
17	J1924744	T08	1/10/08
18	J1924745	T09	1/10/08
19	J1924746	T10	1/10/08
20	J1924747	T11	1/10/08
21	J1924748	T12	1/10/08
22	J1924749	T13	1/10/08
23	J1924750	T14	1/10/08
24	J1924751	T15	1/10/08
25	J1924752	T16	1/10/08
26	J1924753	T17	1/10/08
27	J1924754	T18	1/10/08
28	J1924755	T19	1/10/08

Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	CJ1	JACK	14	1	J1924728
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:11 2008 Page 1



Scale = 1:9.2

Plate Offsets (X,Y): [2:0-3-3,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.00	2	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.01	Vert(TL)	-0.00	2	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.00	Horz(TL)	0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
Weight: 7 lb										

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=256/0-3-8, 4=5/Mechanical, 3=-90/Mechanical

Max Horz 2=101(load case 6)
Max Uplift 2=-295(load case 6), 4=-11(load case 4), 3=-90(load case 1)
Max Grav 2=256(load case 1), 4=14(load case 2), 3=136(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/53, 2-3=-77/86
BOT CHORD 2-4=0/0

JOINT STRESS INDEX

2 = 0.14

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Continued on page 2

Julius Lee
Truss Design Engineer
Florida PE No. 24868
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	CJ1	JACK	14	1	J1924728
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:11 2008 Page 2

NOTES

- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 295 lb uplift at joint 2, 11 lb uplift at joint 4 and 90 lb uplift at joint 3.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida P.E. No. 24888
1400 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE


This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924729
L265053	CJ3	JACK	14	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:11 2008 Page 1



Scale = 1:14.3

Plate Offsets (X,Y): [2:0-3-3,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.28	Vert(LL)	0.01	2-4	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	-0.01	2-4	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 13 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=31/Mechanical, 2=250/0-3-8, 4=14/Mechanical
Max Horz 2=154(load case 6)
Max Uplift 3=-31(load case 7), 2=-235(load case 6), 4=-33(load case 4)
Max Grav 3=31(load case 4), 2=250(load case 1), 4=42(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-64/15
BOT CHORD 2-4=0/0

JOINT STRESS INDEX

2 = 0.12

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Julius Lee
Truss Design Engineer
Florida PE No. 34886
1400 Coastal Bay Blvd
Boca Raton, FL 33436

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	CJ3	JACK	14	1	J1924729
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:11 2008 Page 2

NOTES

- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 3, 235 lb uplift at joint 2 and 33 lb uplift at joint 4.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 24868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	CJ5	JACK	10	1	J1924730
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:12 2008 Page 2

NOTES

- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 96 lb uplift at joint 3, 251 lb uplift at joint 2 and 56 lb uplift at joint 4.

LOAD CASE(S) Standard

Julius Lane
Truss Design Engineer
Florida PE No. 34888
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE


This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 563 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	EJ5	JACK	7	1	J1924731
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:13 2008 Page 1



Scale = 1:19.5

Plate Offsets (X,Y): [2:0-3-4,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.28	Vert(LL)	-0.03	2-4	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.16	Vert(TL)	-0.05	2-4	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						Weight: 20 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=103/Mechanical, 2=295/0-3-8, 4=24/Mechanical

Max Horz 2=207(load case 6)

Max Uplift 3=-96(load case 6), 2=-191(load case 6)

Max Grav 3=103(load case 1), 2=295(load case 1), 4=72(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-81/40

BOT CHORD 2-4=0/0

JOINT STRESS INDEX

2 = 0.14

NOTES

1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.

2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Continued on page 2

Julius Lee
Truss Design Engineer
Florida PE No. 34885
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 563 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	EJ5	JACK	7	1	J1924731
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:13 2008 Page 2

NOTES

- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 96 lb uplift at joint 3 and 191 lb uplift at joint 2.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida P.E. No. 24868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE


This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	EJ7	JACK	29	1	J1924732
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:18:48 2008 Page 1



Scale: 1/2"=1'

Plate Offsets (X,Y): [2:0-3-4,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.41	Vert(LL)	0.31	2-4	>267	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.43	Vert(TL)	-0.16	2-4	>496	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 26 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS (lb/size) 3=154/Mechanical, 2=352/0-3-8, 4=45/Mechanical
Max Horz 2=188(load case 6)
Max Uplift 3=-103(load case 6), 2=-215(load case 6), 4=-65(load case 5)
Max Grav 3=154(load case 1), 2=352(load case 1), 4=94(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-123/61
BOT CHORD 2-4=0/0

JOINT STRESS INDEX

2 = 0.66

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 103 lb uplift at joint 3, 215 lb uplift at joint 2 and 65 lb uplift at joint 4.

LOAD CASE(S) Standard

January 10,2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Julius Lee
Truss Design Engineer
Florida P.E. No. 24888
1409 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with Mitek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling, Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	HJ7	MONO TRUSS	2	1	J1924733
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:14 2008 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54

Trapezoidal Loads (plf)

Vert: 2=-3(F=25, B=25)-to-3=-95(F=-21, B=-21), 2=-0(F=5, B=5)-to-4=-18(F=-4, B=-4)

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1400 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924734
L265053	HJ9	MONO TRUSS	4	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:14 2008 Page 1




Plate Offsets (X,Y): [2:0-1-12,0-0-7]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.60	Vert(LL)	0.10	6-7	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.39	Vert(TL)	-0.11	6-7	>999	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.31	Horz(TL)	0.01	5	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 46 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-3-4 oc bracing.

REACTIONS (lb/size) 4=267/Mechanical, 2=456/0-5-11, 5=219/Mechanical
Max Horz 2=316(load case 5)
Max Uplift 4=-249(load case 5), 2=-382(load case 5), 5=-190(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/58, 2-3=-573/278, 3-4=-127/74
BOT CHORD 2-7=-487/518, 6-7=-487/518, 5-6=0/0
WEBS 3-7=-94/191, 3-6=-547/514

JOINT STRESS INDEX

2 = 0.88, 3 = 0.21, 6 = 0.15 and 7 = 0.14

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 249 lb uplift at joint 4, 382 lb uplift at joint 2 and 190 lb uplift at joint 5.

Julius Lee
Truss Design Engineer
Florida PE No. 34869
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	HJ9	MONO TRUSS	4	1	J1924734
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:14 2008 Page 2

NOTES

5) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54

Trapezoidal Loads (plf)

Vert: 2=-3(F=25, B=25)-to-4=-134(F=-40, B=-40), 2=-0(F=5, B=5)-to-5=-25(F=-7, B=-7)

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924735
L265053	HJ9A	MONO TRUSS	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:15 2008 Page 1




Plate Offsets (X,Y): [2:0-2-0,0-0-7]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.59	Vert(LL)	0.03	6-7	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.39	Vert(TL)	-0.03	6-7	>999	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.21	Horz(TL)	0.01	5	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 45 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-11-2 oc bracing.

REACTIONS (lb/size) 4=265/Mechanical, 2=426/0-5-11, 5=-59/Mechanical, 6=309/0-5-8
Max Horz 2=316(load case 5)
Max Uplift 4=-248(load case 5), 2=-356(load case 5), 5=-62(load case 2), 6=-260(load case 5)
Max Grav 4=265(load case 1), 2=426(load case 1), 5=66(load case 5), 6=309(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/58, 2-3=-473/199, 3-4=-126/73
BOT CHORD 2-7=-409/428, 6-7=-409/428, 5-6=0/0
WEBS 3-7=-56/120, 3-6=-459/438

JOINT STRESS INDEX

2 = 0.87, 3 = 0.18, 6 = 0.12 and 7 = 0.09

NOTES

1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left exposed; Lumber DOL=1.60 plate grip

2) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

Continued on page 2

Julius Lee
Truss Design Engineer
Florida PE No. 31868
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	HJ9A	MONO TRUSS	1	1	J1924735
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:15 2008 Page 2

NOTES

- 3) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 248 lb uplift at joint 4, 356 lb uplift at joint 2, 62 lb uplift at joint 5 and 260 lb uplift at joint 6.
- 5) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 - Uniform Loads (plf)
 - Vert: 1-2=-54
 - Trapezoidal Loads (plf)
 - Vert: 2=-3(F=25, B=25)-to-4=-134(F=-40, B=-40), 2=-0(F=5, B=5)-to-5=-25(F=-7, B=-7)

Julius Lee
Truss Design Engineer
Florida PE No. 34869
1409 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling, Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	PB01	PIGGYBACK	13	1	J1924736
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:15 2008 Page 1




Plate Offsets (X,Y): [3:0-3:0,Edge]

LOADING (psf)	SPACING		CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	2-0-0	TC 0.12	Vert(LL)	-0.01	2-4	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	-0.01	2-4	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.00	Horz(TL)	0.01	5	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 10 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
4-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.

REACTIONS (lb/size) 1=120/0-3-8, 5=120/0-3-8
Max Horz 1=-30(load case 4)
Max Uplift 1=-25(load case 6), 5=-25(load case 7)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-53/36, 2-3=-167/95, 3-4=-167/95, 4-5=-53/36
BOT CHORD 2-4=-57/158

JOINT STRESS INDEX

2 = 0.14, 3 = 0.10 and 4 = 0.14

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Bearing at joint(s) 1, 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula.

Building designer should verify capacity of bearing surface.

Julius Lee
Truss Design Engineer
Florida PE No. 33888
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10,2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	PB01	PIGGYBACK	13	1	J1924736
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:15 2008 Page 2

NOTES

6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 25 lb uplift at joint 1 and 25 lb uplift at joint 5.

7) SEE MiTek STANDARD PIGGYBACK TRUSS CONNECTION DETAIL FOR CONNECTION TO BASE TRUSS

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 24889
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T01	HIP	1	1	J1924737
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:17 2008 Page 1




Plate Offsets (X,Y): [2:0-1-3,Edge], [4:0-5-0,0-2-8], [6:0-1-3,Edge], [9:0-3-0,0-3-4], [11:0-6-7,0-0-7], [13:0-0-7,0-0-1]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.99	Vert(LL)	0.24	9	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.82	Vert(TL)	-0.32	9-10	>817	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.40	Horz(TL)	0.12	6	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 135 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2 *Except*
11-12 2 X 4 SYP No.3, 12-13 2 X 4 SYP No.3
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-1 oc purlins. Except:
3 Rows at 1/4 pts 3-5
BOT CHORD Rigid ceiling directly applied or 3-11-4 oc bracing.
WEBS T-Brace: 2 X 4 SYP No.3 - 4-10, 4-8
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 2=1778/0-3-8, 6=1778/0-3-8
Max Horz 2=-109(load case 3)
Max Uplift 2=-1058(load case 4), 6=-1058(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-2997/1933, 3-4=-2565/1732, 4-5=-2565/1733, 5-6=-2997/1933, 6-7=0/54
BOT CHORD 2-10=-1697/2522, 9-10=-2545/3803, 8-9=-2545/3803, 6-8=-1588/2522
WEBS 3-10=-574/898, 4-10=-1445/1056, 4-9=0/222, 4-8=-1445/1056, 5-8=-574/898

Julius Lane
Truss Design Engineer
Florida PE No. 34863
1106 Coastal Bay Blvd.
Boynton Beach, FL 33436

JOINT STRESS INDEX

2 = 0.74, 3 = 0.85, 4 = 0.44, 4 = 0.00, 5 = 0.85, 6 = 0.74, 8 = 0.57, 9 = 0.80, 10 = 0.57, 11 = 0.15, 12 = 0.26, 13 = 0.15, 14 = 0.33, 15 = 0.33, 16 = 0.33, 17 = 0.33, 18 = 0.33, 19 = 0.33, 20 = 0.33 and 21 = 0.33

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T01	HIP	1	1	J1924737
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:17 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1058 lb uplift at joint 2 and 1058 lb uplift at joint 6.
- 7) Girder carries hip end with 5-0-0 end setback.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- 9) Truss designed for wind loads in plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail".

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-5=-178(F=-124), 5-7=-54, 2-10=-10, 8-10=-17(F=-7), 6-8=-10
Concentrated Loads (lb)
Vert: 10=-187(F) 8=-187(F)

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1409 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T02	COMMON	8	1	J1924738
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:17 2008 Page 1




Plate Offsets (X,Y): [2:0-3-4,0-1-8], [6:0-3-4,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.30	Vert(LL)	0.22	8-10	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.70	Vert(TL)	-0.40	8-10	>649	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.25	Horz(TL)	0.04	6	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						Weight: 110 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-11-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-6-0 oc bracing.

REACTIONS (lb/size) 2=1032/0-3-8, 6=1032/0-3-8
Max Horz 2=178(load case 5)
Max Uplift 2=-305(load case 6), 6=-305(load case 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1555/674, 3-4=-1396/680, 4-5=-1396/680, 5-6=-1555/674, 6-7=0/54
BOT CHORD 2-10=-419/1265, 9-10=-174/860, 8-9=-174/860, 6-8=-419/1265
WEBS 3-10=-228/198, 4-10=-257/585, 4-8=-257/585, 5-8=-228/198

JOINT STRESS INDEX

2 = 0.67, 3 = 0.33, 4 = 0.69, 5 = 0.33, 6 = 0.67, 8 = 0.45, 9 = 0.82 and 10 = 0.45

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Julius Lee
Truss Design Engineer
Florida PE No. 24868
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

Continued on page 2

January 10,2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T02	COMMON	8	1	J1924738
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:17 2008 Page 2

NOTES

- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 305 lb uplift at joint 2 and 305 lb uplift at joint 6.
- 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-7=-54, 2-10=-10, 8-10=-70(F=-60), 6-8=-10

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T03	MONO HIP	1	1	J1924739
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:18 2008 Page 1



Scale = 1:59.6




Plate Offsets (X,Y): [2:0-2-1,Edge], [5:0-4-0,0-3-0], [12:0-3-8,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.89	Vert(LL)	0.24	11	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.55	Vert(TL)	-0.43	11-12	>876	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.91	Horz(TL)	0.11	8	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 188 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.1D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-5-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-11-4 oc bracing.
WEBS I-Brace: 2 X 4 SYP No.3 - 6-8
T-Brace: 2 X 4 SYP No.3 - 4-12
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 8=2240/0-3-8, 2=2187/0-3-8
Max Horz 2=192(load case 5)
Max Uplift 8=-1036(load case 3), 2=-849(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/57, 2-3=-3770/1562, 3-4=-3219/1403, 4-5=-4401/1949, 5-6=-3353/1491, 6-7=-95/46, 7-8=-327/215
BOT CHORD 2-12=-1385/3171, 11-12=-1993/4378, 10-11=-1968/4252, 9-10=-1968/4252, 8-9=-1302/2764
WEBS 3-12=-572/1324, 4-12=-1402/805, 4-11=0/207, 5-11=-16/232, 5-9=-1268/673, 6-9=-388/1210, 6-8=-3224/1518

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

JOINT STRESS INDEX

Continued on page 2
2 = 0.70, 3 = 0.83, 4 = 0.43, 5 = 0.65, 6 = 0.93, 7 = 0.67, 8 = 0.54, 9 = 0.93, 10 = 0.88, 11 = 0.43 and 12 = 0.83

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 563 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T03	MONO HIP	1	1	J1924739
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:18 2008 Page 2

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) Provide adequate drainage to prevent water ponding.
- 3) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1036 lb uplift at joint 8 and 849 lb uplift at joint 2.
- 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-7=-118(F=-64), 2-12=-10, 8-12=-22(F=-12)
Concentrated Loads (lb)
Vert: 12=-411(F)

Julius Lee
Truss Design Engineer
Florida PE No. 24868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T04	MONO HIP	1	1	J1924740
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:19 2008 Page 1




Plate Offsets (X,Y): [2:0-0-11, Edge], [6:0-3-0, 0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.40	Vert(LL)	-0.13	2-13	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.45	Vert(TL)	-0.26	2-13	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.39	Horz(TL)	0.07	9	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 179 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-9-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-11-6 oc bracing.
WEBS T-Brace: 2 X 4 SYP No.3 - 7-9
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 9=1011/0-3-8, 2=1134/0-3-8
Max Horz 2=227(load case 6)
Max Uplift 9=-320(load case 4), 2=-264(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-1694/774, 3-4=-1479/718, 4-5=-1242/674, 5-6=-1480/778,
6-7=-1126/580, 7-8=-28/3, 8-9=-112/77
BOT CHORD 2-13=-810/1389, 12-13=-817/1499, 11-12=-817/1499, 10-11=-761/1416,
9-10=-439/810
WEBS 3-13=-191/168, 4-13=-185/474, 5-13=-380/245, 5-11=-38/77, 6-11=-33/170,
6-10=-547/341, 7-10=-277/623, 7-9=-1167/644

Julius Lane
Truss Design Engineer
Florida, P.E. No. 34883
1400 Coastal Bay Blvd.
Boynton Beach, FL 33435

JOINT STRESS INDEX

2 = 0.81, 3 = 0.33, 4 = 0.42, 5 = 0.42, 6 = 0.47, 7 = 0.47, 8 = 0.55, 9 = 0.49, 10 = 0.47, 11 = 0.42, 12 = 0.48 and 13 = 0.56

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T04	MONO HIP	1	1	J1924740
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:19 2008 Page 2

NOTES

- 1) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Provide adequate drainage to prevent water ponding.
- 3) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 320 lb uplift at joint 9 and 264 lb uplift at joint 2.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34869
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924741
L265053	T05	HIP	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:20 2008 Page 1




Plate Offsets (X,Y): [2:0-2-1,Edge]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.43	Vert(LL)	-0.29	2-12	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.64	Vert(TL)	-0.52	2-12	>731	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.44	Horz(TL)	0.06	8	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 184 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-8-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS T-Brace: 2 X 4 SYP No.3 - 5-12, 5-9
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 2=1134/0-3-8, 8=1011/0-3-8
Max Horz 2=207(load case 6)
Max Uplift 2=-282(load case 6), 8=-233(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1707/812, 3-4=-1416/695, 4-5=-1160/680, 5-6=-693/446,
6-7=-849/442, 7-8=-990/507
BOT CHORD 2-12=-775/1412, 11-12=-604/1242, 10-11=-604/1242, 9-10=-604/1242, 8-9=-14/16
WEBS 3-12=-280/237, 4-12=-61/376, 5-12=-237/197, 5-10=0/218, 5-9=-744/367,
6-9=0/183, 7-9=-382/836

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1400 Coastal Bay Blvd.
Gwynn Beach, FL 33435

JOINT STRESS INDEX

2 = 0.77, 3 = 0.33, 4 = 0.73, 5 = 0.56, 6 = 0.80, 7 = 0.56, 8 = 0.35, 9 = 0.78, 10 = 0.33, 11 = 0.43 and 12 = 0.56

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T05	HIP	1	1	J1924741
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:20 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 282 lb uplift at joint 2 and 233 lb uplift at joint 8.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1409 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T06	HIP	1	1	J1924742
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:21 2008 Page 1




Plate Offsets (X,Y): [2:0-3-3,0-1-8], [6:0-4-1,Edge], [7:Edge,0-1-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.68	Vert(LL)	-0.07	2-13	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.36	Vert(TL)	-0.15	2-13	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.37	Horz(TL)	0.05	8	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						Weight: 197 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-6-3 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-7-10 oc bracing.
WEBS T-Brace: 2 X 4 SYP No.3 - 4-10
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 2=1134/0-3-8, 8=1011/0-3-8
Max Horz 2=228(load case 5)
Max Uplift 2=-294(load case 6), 8=-178(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1665/736, 3-4=-1268/674, 4-5=-1030/642, 5-6=-1030/642,
6-7=-955/493, 7-8=-971/506
BOT CHORD 2-13=-680/1344, 12-13=-680/1344, 11-12=-469/1028, 10-11=-469/1028,
9-10=-325/742, 8-9=-42/60
WEBS 3-13=0/213, 3-12=-399/263, 4-12=-120/336, 4-10=-157/144, 5-10=-338/211,
6-10=-230/530, 6-9=-297/197, 7-9=-323/774

Julius Lee
Truss Design Engineer
Florida, PE No. 34869
1100 Coastal Bay Blvd.
Boynton Beach, FL 33436

JOINT STRESS INDEX

2 = 0.71, 3 = 0.40, 4 = 0.86, 5 = 0.33, 6 = 0.59, 7 = 0.64, 8 = 0.28, 9 = 0.43, 10 = 0.56, 11 = 0.37, 12 = 0.34 and 13 = 0.33

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Oonofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T06	HIP	1	1	J1924742
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:21 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 294 lb uplift at joint 2 and 178 lb uplift at joint 8.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida FE No. 24888
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE


This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T07	SPECIAL	1	1	J1924743
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:22 2008 Page 1



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T07	SPECIAL	1	1	J1924743
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:22 2008 Page 2

NOTES

- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 299 lb uplift at joint 2 and 159 lb uplift at joint 9.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 24869
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924744
L265053	T08	SPECIAL	3	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:23 2008 Page 1




Plate Offsets (X,Y): [2:0-3-8,0-1-8], [3:0-3-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.50	Vert(LL)	0.34 15-16	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.61	Vert(TL)	-0.60 15-16	>633	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.78	Horz(TL)	0.44 10	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 207 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2 *Except*
 8-11 2 X 4 SYP No.3
 WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or
 3-1-13 oc purlins, except end verticals, and
 2-0-0 oc purlins (5-7-12 max.): 6-7.
 BOT CHORD Rigid ceiling directly applied or 4-11-15 oc
 bracing.
 JOINTS 1 Brace at Jt(s): 13

REACTIONS (lb/size) 2=1142/0-3-8, 10=1037/0-3-8
 Max Horz 2=293(load case 5)
 Max Uplift 2=-306(load case 6), 10=-199(load case 7)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/52, 2-3=-3557/1661, 3-4=-3237/1493, 4-5=-2363/1089, 5-6=-2297/1177,
 6-7=-1185/679, 7-8=-1437/718, 8-9=-1224/542, 9-10=-1026/472
 BOT CHORD 2-16=-1569/3135, 15-16=-1229/2692, 14-15=-601/1702, 13-14=-415/1056,
 11-13=0/197, 8-13=-522/300, 11-12=0/0, 10-11=-57/0
 WEBS 3-16=-257/260, 4-16=-125/434, 4-15=-594/433, 5-15=-181/164, 6-15=-825/1768,
 6-14=-815/318, 7-14=-177/441, 8-14=-148/208, 9-13=-386/1007, 10-13=-14/83

Julius Lane
 Truss Design Engineer
 Florida PE No. 34863
 1166 Coastal Bay Blvd.
 Boynton Beach, FL 33435

JOINT STRESS INDEX

2 = 0.79, 3 = 0.40, 4 = 0.40, 5 = 0.33, 6 = 0.71, 7 = 0.47, 8 = 0.40, 9 = 0.76, 10 = 0.38, 11 = 0.80, 12 = 0.33, 13 = 0.65, 14 = 0.65, 15 = 0.93, 16 = 0.38 and 17 = 0.33

NOTES

1) Unbalanced roof live loads have been considered for this design.

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
 This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T08	SPECIAL	3	1	J1924744
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:23 2008 Page 2

NOTES

- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 306 lb uplift at joint 2 and 199 lb uplift at joint 10.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924745
L265053	T09	SPECIAL	2	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:24 2008 Page 1




Plate Offsets (X,Y): [3:0-3-0,0-3-0], [8:0-3-0,0-3-0], [10:0-3-4,0-1-8]

LOADING (psf)	SPACING		CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	2-0-0	TC 0.54	Vert(LL)	-0.22 15-16	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase 1.25		BC 0.50	Vert(TL)	-0.45 15-16	>847	240		
BCLL 10.0	* Rep Stress Incr YES		WB 0.76	Horz(TL)	0.29 12	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 211 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-7-12 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD Rigid ceiling directly applied or 4-9-10 oc bracing.

REACTIONS (lb/size) 2=945/0-3-8, 12=2315/0-3-8, 10=-615/0-3-8

Max Horz 2=-276(load case 4)

Max Uplift 2=-278(load case 6), 12=-474(load case 6), 10=-624(load case 10)

Max Grav 2=945(load case 1), 12=2315(load case 1), 10=100(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/52, 2-3=-2753/1146, 3-4=-2407/959, 4-5=-1492/528, 5-6=-1434/621, 6-7=-543/383, 7-8=-700/380, 8-9=-252/259, 9-10=-548/1835, 10-11=0/54

BOT CHORD 2-16=-863/2416, 15-16=-486/1912, 14-15=-186/1011, 13-14=-219/207, 12-13=-1660/681, 10-12=-1495/606

WEBS 3-16=-286/285, 4-16=-149/462, 4-15=-603/439, 5-15=-189/175, 6-15=-383/1307, 6-14=-790/277, 7-14=-4/146, 8-14=-213/667, 8-13=-972/351, 9-13=-460/1603, 9-12=-1715/703

Julius Lane
Truss Design Engineer
Florida PE No. 31868
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

JOINT STRESS INDEX

2 = 0.63, 3 = 0.37, 4 = 0.40, 5 = 0.33, 6 = 0.78, 7 = 0.34, 8 = 0.44, 9 = 0.86, 10 = 0.64, 12 = 0.96, 13 = 0.83, 14 = 0.65, 15 = 0.69 and 16 = 0.38

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T09	SPECIAL	2	1	J1924745
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:24 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 278 lb uplift at joint 2, 474 lb uplift at joint 12 and 624 lb uplift at joint 10.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34889
1109 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T10	SPECIAL	7	1	J1924746
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:34:47 2008 Page 1




Plate Offsets (X,Y): [1:0-2-4,0-0-15], [2:0-3-0,0-3-0], [7:0-2-12,0-3-4], [10:0-0-11,Edge], [13:0-2-10,Edge]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.96	Vert(LL)	-0.22 16-17	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.62	Vert(TL)	-0.45 16-17	>850	240	MT20H	187/143
BCLL 10.0	Rep Stress Incr	NO	WB 0.78	Horz(TL)	0.29 13	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
									Weight: 214 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2 *Except*
7-11 2 X 4 SYP No.1D
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-6-10
oc purlins, except
2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 4-4-13 oc bracing.

REACTIONS (lb/size) 1=817/0-3-8, 13=3572/0-4-3 (0-3-8 + bearing block), 10=-484/0-3-8

Max Horz 1=-298(load case 4)

Max Uplift 1=-185(load case 6), 13=-1026(load case 6), 10=-592(load case 10)

Max Grav 1=817(load case 1), 13=3572(load case 1), 10=46(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-2800/1266, 2-3=-2434/1055, 3-4=-1472/562, 4-5=-1404/649, 5-6=-516/395,
6-7=-686/409, 7-18=-162/318, 8-18=-409/370, 8-9=-846/2291, 9-10=-345/1357, 10-11=0/54

BOT CHORD 1-17=-986/2468, 16-17=-532/1910, 15-16=-211/997, 14-15=-199/212, 13-14=-2008/932,
12-13=-1114/398, 10-12=-1114/398

WEBS 2-17=-310/318, 3-17=-201/472, 3-16=-619/460, 4-16=-179/163, 5-16=-397/1289,
5-15=-816/291, 6-15=-59/171, 7-15=-177/646, 7-14=-1180/537, 8-14=-758/1938,
8-13=-2544/1376, 9-13=-756/468

Julius Lane
Truss Design Engineer
Florida PE No. 31888
1169 Coastal Bay Blvd.
Boynton Beach, FL 33435

JOINT STRESS INDEX

1 = 0.83, 2 = 0.45, 3 = 0.42, 4 = 0.34, 5 = 0.80, 6 = 0.21, 7 = 0.75, 8 = 0.73, 9 = 0.37, 10 = 0.71, 12 = 0.00, 12 = 0.00, 13 = 0.99, 13 = 0.00, 14 = 0.95, 15 = 0.67, 16 = 0.71 and 17 = 0.39

NOTES

1) 2 X 4 SYP No.2 bearing block 12" long at jt. 13 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SYP.

2) Unbalanced roof live loads have been considered for this design.

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T10	SPECIAL	7	1	J1924746
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:34:47 2008 Page 2

NOTES

- 3) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf, Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 4) Provide adequate drainage to prevent water ponding.
- 5) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) All plates are MT20 plates unless otherwise indicated.
- 7) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 8) Bearing at joint(s) 1 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 185 lb uplift at joint 1, 1026 lb uplift at joint 13 and 592 lb uplift at joint 10.

Loading has been calculated by the truss manufacturer. It is the responsibility of the Architect/Engineer of Record to verify and approve the loading.

LOAD CASE(S) Standard Except:

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 - Uniform Loads (plf)
 - Vert: 1-5=-54, 5-6=-54, 6-18=-54, 9-11=-54, 1-16=-10, 13-16=-10, 10-13=-10
 - Concentrated Loads (lb)
 - Vert: 9=-358
 - Trapezoidal Loads (plf)
 - Vert: 18=-137-to-9=-221

Julius Lee
Truss Design Engineer
Florida P.E. No. 24868
1400 Coastal Hwy Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T11	HIP	1	1	J1924747
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:27 2008 Page 1




Plate Offsets (X,Y): [2:0-2-1,Edge], [6:0-3-0,0-3-4], [8:0-2-1,Edge]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.72	Vert(LL)	0.25	16	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.56	Vert(TL)	-0.45	16-17	>845	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 1.00	Horz(TL)	0.11	11	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 229 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.1D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-7-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 5-10-5 oc bracing.
WEBS T-Brace: 2 X 4 SYP No.3 - 4-17, 6-13
Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 2=2142/0-3-8, 11=3131/0-3-11 (0-3-8 + bearing block)
Max Horz 2=111(load case 4)
Max Uplift 2=-909(load case 4), 11=-1375(load case 6)
Max Grav 2=2183(load case 9), 11=3131(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/57, 2-3=-3755/1685, 3-4=-3224/1512, 4-5=-4377/2036, 5-6=-3666/1690, 6-7=-540/277, 7-8=-385/568, 8-9=0/56
BOT CHORD 2-18=-1479/3159, 17-18=-1474/3174, 16-17=-2078/4350, 15-16=-2019/4286, 14-15=-2019/4286, 13-14=-1446/3050, 12-13=-148/471, 11-12=-148/471, 10-11=-402/443, 8-10=-402/443
WEBS 3-18=-104/57, 3-17=-620/1398, 4-17=-1369/805, 4-16=0/171, 5-16=-27/209, 5-14=-1053/560, 6-14=-413/1196, 6-13=-3077/1536, 7-13=-744/1893, 7-11=-2683/1078

Julius Lee
Truss Design Engineer
Florida P.E. No. 34865
1150 Coastal Bay Blvd
Boynton Beach, FL 33435

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T11	HIP	1	1	J1924747
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:27 2008 Page 2

JOINT STRESS INDEX

2 = 0.70, 3 = 0.82, 4 = 0.90, 5 = 0.38, 6 = 0.93, 7 = 0.82, 8 = 0.70, 10 = 0.00, 10 = 0.00, 11 = 0.43, 11 = 0.00, 12 = 0.00, 12 = 0.00, 13 = 0.74, 14 = 0.59, 15 = 0.86, 16 = 0.59, 17 = 0.74 and 18 = 0.43

NOTES

- 2 X 6 SYP No.1D bearing block 12" long at jt. 11 attached to front face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners. Bearing is assumed to be SYP.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS; cantilever right exposed ; Lumber DOL=1.60 plate grip DOL=1.60.
- Provide adequate drainage to prevent water ponding.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 909 lb uplift at joint 2 and 1375 lb uplift at joint 11.
- Girder carries hip end with 7-0-0 end setback.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-7=-118(F=-64), 7-9=-54, 2-17=-10, 13-17=-22(F=-12), 8-13=-10
Concentrated Loads (lb)
Vert: 17=-411(F) 13=-411(F)

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T12	HIP	1	1	J1924748
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:28 2008 Page 2

JOINT STRESS INDEX

2 = 0.67, 3 = 0.33, 4 = 0.44, 5 = 0.41, 6 = 0.41, 7 = 0.44, 8 = 0.33, 9 = 0.67, 11 = 0.49, 12 = 0.48, 13 = 0.72, 14 = 0.48 and 15 = 0.49

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 268 lb uplift at joint 2, 504 lb uplift at joint 11 and 220 lb uplift at joint 9.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 24888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T13	HIP	1	1	J1924749
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:29 2008 Page 1




Plate Offsets (X,Y): [2:0-3-3,0-1-8], [4:0-4-1,Edge], [6:0-4-1,Edge], [8:0-3-3,0-1-8], [12:0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.44	Vert(LL)	-0.09 12-13	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.36	Vert(TL)	-0.19 12-13	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.70	Horz(TL)	0.04 10	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
									Weight: 210 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-8-14 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 2=1095/0-3-8, 10=1427/0-3-8, 8=122/0-6-0
Max Horz 2=-178(load case 4)
Max Uplift 2=-280(load case 6), 10=-375(load case 4), 8=-237(load case 7)
Max Grav 2=1095(load case 1), 10=1427(load case 1), 8=163(load case 11)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1609/739, 3-4=-1300/703, 4-5=-1133/710, 5-6=-1133/710,
6-7=-669/415, 7-8=-117/430, 8-9=0/54
BOT CHORD 2-14=-461/1303, 13-14=-461/1303, 12-13=-349/1078, 11-12=-119/515,
10-11=-313/238, 8-10=-313/238
WEBS 3-14=0/162, 3-13=-285/190, 4-13=-75/317, 4-12=-186/203, 5-12=-466/328,
6-12=-389/822, 6-11=-539/275, 7-11=-365/1018, 7-10=-1360/657

JOINT STRESS INDEX

2 = 0.69, 3 = 0.69, 4 = 0.57, 5 = 0.33, 6 = 0.57, 7 = 0.69, 8 = 0.69, 10 = 0.48, 11 = 0.58, 12 = 0.47, 13 = 0.58 and 14 = 0.48

NOTES

1) Unbalanced roof live loads have been considered for this design.

Julius Lee
Truss Design Engineer
Florida PE No. 24888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

Continued on page 2

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924749
L265053	T13	HIP	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:29 2008 Page 2

NOTES

- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 280 lb uplift at joint 2, 375 lb uplift at joint 10 and 237 lb uplift at joint 8.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 24885
1300 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924750
L265053	T14	HIP	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:30 2008 Page 1




Plate Offsets (X,Y): [2:0-3-3,0-1-8], [8:0-3-3,0-1-8], [12:0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.39	Vert(LL)	0.09 8-10	>807	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.35	Vert(TL)	-0.14 13-14	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.52	Horz(TL)	0.04 10	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)						
								Weight: 220 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-7-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS T-Brace: 2 X 4 SYP No.3 - 4-12

Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
Brace must cover 90% of web length.

REACTIONS (lb/size) 2=1099/0-3-8, 10=1414/0-3-8, 8=132/0-3-8
Max Horz 2=-210(load case 4)
Max Uplift 2=-292(load case 6), 10=-298(load case 4), 8=-235(load case 7)
Max Grav 2=1099(load case 1), 10=1414(load case 1), 8=183(load case 11)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1610/721, 3-4=-1198/667, 4-5=-946/636, 5-6=-946/636, 6-7=-807/492, 7-8=-119/456, 8-9=0/54
BOT CHORD 2-14=-433/1294, 13-14=-443/1269, 12-13=-285/969, 11-12=-120/617, 10-11=-6/120, 8-10=-304/255
WEBS 3-14=0/223, 3-13=-385/273, 4-13=-123/345, 4-12=-168/114, 5-12=-345/233, 6-12=-261/577, 6-11=-348/169, 7-11=-198/676, 7-10=-1374/670

Julius Lee
Truss Design Engineer
Florida PE No. 24888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

JOINT STRESS INDEX

Continued on page 2 2 = 0.75, 3 = 0.50, 4 = 0.80, 5 = 0.33, 6 = 0.80, 7 = 0.50, 8 = 0.75, 10 = 0.50, 11 = 0.39, 12 = 0.34, 13 = 0.39 and 14 = 0.50 January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924750
L265053	T14	HIP	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:31 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCFL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 292 lb uplift at joint 2, 298 lb uplift at joint 10 and 235 lb uplift at joint 8.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T15	HIP	1	1	J1924751
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:23:27 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 303 lb uplift at joint 2, 278 lb uplift at joint 9 and 236 lb uplift at joint 7.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1100 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN	J1924752
L265053	T16	HIP	3	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:35:59 2008 Page 2

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 320 lb uplift at joint 2, 284 lb uplift at joint 10 and 823 lb uplift at joint 12.

Loading has been calculated by the truss manufacturer. It is the responsibility of the Architect/Engineer of Record to verify and approve the loading.

LOAD CASE(S) Standard Except:

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 - Uniform Loads (plf)
 - Vert: 1-5=-54, 5-6=-54, 6-7=-54, 9-11=-54, 2-10=-10
 - Concentrated Loads (lb)
 - Vert: 9=-358
 - Trapezoidal Loads (plf)
 - Vert: 7=-135-to-9=-221

Julius Lee
Truss Design Engineer
Florida PE No. 24868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T17	HIP	1	1	J1924753
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:33 2008 Page 1




Plate Offsets (X,Y): [2:0-3-3,0-1-8], [3:0-4-1,Edge], [5:0-3-3,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.41	Vert(LL)	0.13	2-8	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.37	Vert(TL)	-0.13	2-8	>999	240		
BCLL 10.0	* Rep Stress Incr	NO	WB 0.19	Horz(TL)	0.03	5	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 76 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-7-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-11-5 oc bracing.

REACTIONS (lb/size) 2=1103/0-3-8, 5=1103/0-3-8
Max Horz 2=113(load case 4)
Max Uplift 2=-673(load case 5), 5=-673(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=-1603/876, 3-4=-1310/811, 4-5=-1606/877, 5-6=0/54
BOT CHORD 2-8=-764/1291, 7-8=-776/1307, 5-7=-692/1294
WEBS 3-8=-359/480, 3-7=-176/166, 4-7=-458/593

JOINT STRESS INDEX

2 = 0.69, 3 = 0.52, 4 = 0.69, 5 = 0.69, 7 = 0.38 and 8 = 0.34

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
- Provide adequate drainage to prevent water ponding.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Continued on page 2

January 10,2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T17	HIP	1	1	J1924753
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:33 2008 Page 2

NOTES

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 673 lb uplift at joint 2 and 673 lb uplift at joint 5.
- 7) Girder carries hip end with 7'-0" end setback.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-3=-54, 3-4=-118(F=-64), 4-6=-54, 2-8=-10, 7-8=-22(F=-12), 5-7=-10

Concentrated Loads (lb)

Vert: 8=-411(F) 7=-411(F)

Julius Lee
Truss Design Engineer
Florida P.E. No. 24869
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T18	COMMON	3	1	J1924754
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:34 2008 Page 1




Plate Offsets (X,Y): [2:0-0-11,Edge], [3:0-5-4,0-2-4], [4:0-0-11,Edge]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.46	Vert(LL)	0.23	2-6	>803	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.39	Vert(TL)	-0.14	2-6	>999	240		
BCLL 10.0	* Rep Stress Incr	YES	WB 0.19	Horz(TL)	-0.01	4	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
										Weight: 65 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-1-10 oc bracing.

REACTIONS (lb/size) 2=619/0-3-8, 4=619/0-3-8
Max Horz 2=129(load case 5)
Max Uplift 2=-402(load case 6), 4=-402(load case 7)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-662/811, 3-4=-662/811, 4-5=0/54
BOT CHORD 2-6=-516/482, 4-6=-516/482
WEBS 3-6=-490/274

JOINT STRESS INDEX

2 = 0.71, 3 = 0.89, 4 = 0.71 and 6 = 0.19

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

Continued on page 2
All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi

Julius Lee
Truss Design Engineer
Florida PE No. 24888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T18	COMMON	3	1	J1924754
					Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.300 s Feb 15 2006 MiTek Industries, Inc. Wed Jan 09 17:45:34 2008 Page 2

NOTES

- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 402 lb uplift at joint 2 and 402 lb uplift at joint 4.

LOAD CASE(S) Standard

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10, 2008

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T19	COMMON	8	1	J1924755
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:33:38 2008 Page 1




Plate Offsets (X,Y): [2:0-3-5,0-1-8], [3:0-3-0,Edge], [4:0-3-5,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.09	Vert(LL)	-0.01	2-4	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.08	Vert(TL)	-0.01	2-4	>999	240		
BCLL 10.0	Rep Stress Incr	NO	WB 0.00	Horz(TL)	0.00	4	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 15 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-6-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=192/0-3-8, 4=192/0-3-8
Max Horz 2=-32(load case 7)
Max Uplift 2=-87(load case 6), 4=-87(load case 7)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/31, 2-3=-88/26, 3-4=-88/26, 4-5=0/31
BOT CHORD 2-4=0/62

JOINT STRESS INDEX

2 = 0.09, 3 = 0.01 and 4 = 0.09

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-02; 110mph (3-second gust); h=15ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- *This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SYP No.2 crushing capacity of 565.00 psi
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 87 lb uplift at joint 2 and 87 lb uplift at joint 4.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- Truss designed for wind loads in plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail".

Julius Lee
Truss Design Engineer
Florida PE No. 34888
1400 Coastal Bay Blvd
Boynton Beach, FL 33435

January 10,2008

Continued on page 2

Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE
This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719



Job	Truss	Truss Type	Qty	Ply	GIEBEIG - LOT 1 CREEK RUN
L265053	T19	COMMON	8	1	J1924755
Job Reference (optional)					

Builders FirstSource, Lake City, FL 32055

6.300 s Apr 19 2006 MiTek Industries, Inc. Thu Jan 10 08:33:38 2008 Page 2

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-64(F=-10), 3-5=-64(F=-10), 2-4=-10

Julius Lee
Truss Design Engineer
Florida PE No. 34868
1100 Coastal Bay Blvd.
Boynton Beach, FL 33435

January 10, 2008


Warning - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE

This design is based only upon the parameters shown for an individual building component that is installed and loaded vertically and fabricated with MiTek connectors. Applicability of design parameters and proper incorporation of component into the overall building structure, including all temporary and permanent bracing, is the responsibility of building designer and / or contractor per ANSI / TPI 1 as referenced by the building code. For general guidance regarding storage, delivery, erection and bracing, consult BCSI-1 or HIB-91 Handling Installing and Bracing Recommendation available from the Wood Truss Council of America, 1 WTCA Center, 6300 Enterprise Lane, Madison, WI 53719 or the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719




Symbols

PLATE LOCATION AND ORIENTATION



*Center plate on joint unless dimensions indicate otherwise. Dimensions are in inches. Apply plates to both sides of truss and securely seat.



*For 4 x 2 orientation, locate plates 1/8" from outside edge of truss and vertical web.



*This symbol indicates the required direction of slots in connector plates.

PLATE SIZE

4 X 4


The first dimension is the width perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING




Indicates location of required continuous lateral bracing.

BEARING



Indicates location of joints at which bearings (supports) occur.

Numbering System



JOINTS AND CHORDS ARE NUMBERED CLOCKWISE AROUND THE TRUSS STARTING AT THE LOWEST JOINT FARTHEST TO THE LEFT.

WEBS ARE NUMBERED FROM LEFT TO RIGHT

CONNECTOR PLATE CODE APPROVALS

BOCA	96-31, 96-67
ICBO	3907, 4922
SBCCI	9667, 9432A
WISC/DILHR	960022-W, 970036-N
NER	561



MITek Engineering Reference Sheet: MII-7473



General Safety Notes


Failure to Follow Could Cause Property Damage or Personal Injury

1. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
2. Cut members to bear tightly against each other.
3. Place plates on each face of truss at each joint and embed fully. Avoid knots and wane at joint locations.
4. Unless otherwise noted, locate chord splices at 1/4 panel length ($\pm 6"$ from adjacent joint.)
5. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
6. Unless expressly noted, this design is not applicable for use with fire retardant or preservative treated lumber.
7. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
8. Plate type, size and location dimensions shown indicate minimum plating requirements.
9. Lumber shall be of the species and size, and in all respects, equal to or better than the grade specified.
10. Top chords must be sheathed or purlins provided at spacing shown on design.
11. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
12. Anchorage and / or load transferring connections to trusses are the responsibility of others unless shown.
13. Do not overload roof or floor trusses with stocks of construction materials.
14. Do not cut or alter truss member or plate without prior approval of a professional engineer.
15. Care should be exercised in handling, erection and installation of trusses.

© 1993 MITek® Holdings, Inc.

ASCE 7-02: 130 MPH WIND SPEED, 15' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

MAX GABLE VERTICAL LENGTH																	
CABLE VERTICAL SPACING	2X4 BRACE SPECIES	GRADE	NO BRACES	BRACE													
				(1) 1X4 "L" BRACE *		(1) 2X4 "L" BRACE *		(2) 2X4 "L" BRACE **		(1) 2X6 "L" BRACE *		(2) 2X6 "L" BRACE *					
12" O.C.	SPF	#1 / #2	3' 4"	6' 10"	6' 0"	6' 11"	7' 1"	8' 3"	8' 6"	10' 10"	11' 2"	12' 11"	13' 3"				
			#3	3' 3"	4' 11"	4' 11"	6' 6"	6' 6"	8' 3"	8' 3"	10' 1"	10' 1"	12' 11"	12' 11"			
			STUD	3' 3"	4' 11"	4' 11"	6' 5"	6' 5"	8' 3"	8' 3"	10' 0"	10' 0"	12' 11"	12' 11"			
			STANDARD	3' 3"	4' 2"	4' 2"	5' 6"	5' 6"	7' 5"	7' 5"	8' 8"	8' 8"	11' 8"	11' 8"			
16" O.C.	HF	#1 <td>3' 8"</td> <td>5' 10"</td> <td>6' 3"</td> <td>6' 11"</td> <td>7' 5"</td> <td>8' 3"</td> <td>8' 11"</td> <td>10' 10"</td> <td>11' 8"</td> <td>12' 11"</td> <td>13' 11"</td>	3' 8"	5' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"				
			#2	3' 7"	5' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"			
			#3	3' 6"	5' 0"	6' 0"	6' 8"	6' 8"	8' 3"	8' 6"	10' 4"	10' 4"	12' 11"	13' 7"			
			STUD	3' 6"	5' 0"	6' 0"	6' 8"	6' 8"	8' 3"	8' 6"	10' 3"	10' 3"	12' 11"	13' 7"			
24" O.C.	SP	#1 / #2 <td>3' 10"</td> <td>6' 8"</td> <td>6' 10"</td> <td>7' 11"</td> <td>8' 1"</td> <td>9' 5"</td> <td>9' 8"</td> <td>10' 8"</td> <td>12' 6"</td> <td>12' 9"</td> <td>14' 0"</td>	3' 10"	6' 8"	6' 10"	7' 11"	8' 1"	9' 5"	9' 8"	10' 8"	12' 6"	12' 9"	14' 0"				
			#3	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"			
			STUD	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"			
			STANDARD	3' 9"	5' 2"	6' 2"	6' 10"	6' 10"	8' 2"	9' 2"	10' 7"	10' 7"	14' 0"	14' 0"			
12" O.C.	SPF	#1 <td>4' 3"</td> <td>5' 8"</td> <td>7' 2"</td> <td>7' 11"</td> <td>8' 6"</td> <td>9' 5"</td> <td>10' 2"</td> <td>12' 5"</td> <td>13' 5"</td> <td>14' 0"</td> <td>14' 0"</td>	4' 3"	5' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"				
			#2	4' 2"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"			
			#3	4' 0"	6' 2"	6' 2"	7' 11"	8' 2"	9' 6"	9' 11"	12' 6"	12' 8"	14' 0"	14' 0"			
			STUD	4' 0"	6' 1"	6' 1"	7' 11"	8' 1"	9' 5"	9' 11"	12' 5"	12' 6"	14' 0"	14' 0"			
16" O.C.	DFL	STANDARD <td>3' 10"</td> <td>5' 3"</td> <td>5' 3"</td> <td>6' 11"</td> <td>6' 11"</td> <td>9' 4"</td> <td>9' 4"</td> <td>10' 10"</td> <td>10' 10"</td> <td>14' 0"</td> <td>14' 0"</td>	3' 10"	5' 3"	5' 3"	6' 11"	6' 11"	9' 4"	9' 4"	10' 10"	10' 10"	14' 0"	14' 0"				
			24" O.C.	SPF	#1 / #2 <td>4' 3"</td> <td>6' 11"</td> <td>7' 4"</td> <td>8' 9"</td> <td>8' 11"</td> <td>10' 6"</td> <td>13' 8"</td> <td>13' 8"</td> <td>14' 0"</td> <td>14' 0"</td>	4' 3"	6' 11"	7' 4"	8' 9"	8' 11"	10' 6"	13' 8"	13' 8"	14' 0"	14' 0"		
						#3	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	13' 8"	14' 0"	14' 0"
						STUD	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	13' 8"	14' 0"	14' 0"
STANDARD	4' 2"	6' 11"				6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	13' 8"	14' 0"	14' 0"			
12" O.C.	HF	#1 <td>4' 8"</td> <td>7' 4"</td> <td>7' 4"</td> <td>8' 9"</td> <td>8' 9"</td> <td>10' 5"</td> <td>11' 2"</td> <td>13' 8"</td> <td>14' 0"</td> <td>14' 0"</td> <td>14' 0"</td>	4' 8"	7' 4"	7' 4"	8' 9"	8' 9"	10' 5"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"				
			#2	4' 7"	7' 4"	7' 4"	8' 9"	8' 9"	10' 5"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"			
			#3	4' 4"	7' 2"	7' 2"	8' 9"	8' 9"	10' 5"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"			
			STUD	4' 4"	7' 2"	7' 2"	8' 9"	8' 9"	10' 5"	11' 2"	13' 8"	14' 0"	14' 0"	14' 0"			
16" O.C.	DFL	STANDARD <td>4' 3"</td> <td>6' 1"</td> <td>6' 1"</td> <td>8' 0"</td> <td>8' 0"</td> <td>10' 5"</td> <td>10' 11"</td> <td>13' 8"</td> <td>14' 0"</td> <td>14' 0"</td> <td>14' 0"</td>	4' 3"	6' 1"	6' 1"	8' 0"	8' 0"	10' 5"	10' 11"	13' 8"	14' 0"	14' 0"	14' 0"				
			24" O.C.	SP	#1 <td>4' 3"</td> <td>6' 1"</td> <td>6' 1"</td> <td>8' 0"</td> <td>8' 0"</td> <td>10' 5"</td> <td>10' 11"</td> <td>13' 8"</td> <td>14' 0"</td> <td>14' 0"</td>	4' 3"	6' 1"	6' 1"	8' 0"	8' 0"	10' 5"	10' 11"	13' 8"	14' 0"	14' 0"		
						#2	4' 3"	6' 1"	6' 1"	8' 0"	8' 0"	10' 5"	10' 11"	13' 8"	14' 0"	14' 0"	
						#3	4' 3"	6' 1"	6' 1"	8' 0"	8' 0"	10' 5"	10' 11"	13' 8"	14' 0"	14' 0"	
STUD	4' 3"	6' 1"				6' 1"	8' 0"	8' 0"	10' 5"	10' 11"	13' 8"	14' 0"	14' 0"				



BRACING GROUP SPECIES AND GRADES:			
GROUP A:		GROUP B:	
SPRUCE-PINE-FIR	HEM-FIR	SPRUCE-PINE-FIR	HEM-FIR
#1 / #2 STANDARD	#1 / #2 STANDARD	#1 / #2 STANDARD	#1 / #2 STANDARD
#3 STANDARD	#3 STANDARD	#3 STANDARD	#3 STANDARD
DOUGLAS FIR-LARCH	SOUTHERN PINE	DOUGLAS FIR-LARCH	SOUTHERN PINE
#1 STANDARD	#1 STANDARD	#1 STANDARD	#1 STANDARD
#2 STANDARD	#2 STANDARD	#2 STANDARD	#2 STANDARD

CABLE TRUSS DETAIL NOTES:

LIVE LOAD DEPOSITION CRITERIA IS 1/240.
 PROVIDE UPLIFT CONNECTIONS FOR 136 PLF OVER CONTINUOUS BEARING (6 PSF TC DEAD LOAD).
 CABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 8' 0" OVERHANG, OR 12' PLWOOD OVERHANG.
 ATTACH EACH "L" BRACE WITH 10d NAILS.
 * FOR (1) "L" BRACE: SPACE NAILS AT 8" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
 ** FOR (2) "L" BRACES: SPACE NAILS AT 8" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.
 "L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

CABLE VERTICAL PLATE SIZES			
VERTICAL LENGTH	NO SPLICE	LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0"	BUT	LESS THAN 11' 8"	2X4
GREATER THAN 11' 8"			2.5X4

* REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE AND HEEL PLATES.


WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO 303-1-03 (BUILDING DEPARTMENT SAFETY INFORMATION) PUBLISHED BY THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY, 101 BUREAU OF STANDARDS, 4TH FLOOR, WASHINGTON, D.C. 20535. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED BRIDGING.

JULIUS LEE'S
 CONS. ENGINEERS P.A.
 1465 ST. 4TH AVENUE
 DELRAY BEACH, FL 33444-8161

No. 34869
 STATE OF FLORIDA

MAX. TOT. LD. 60 PSF
 MAX. SPACING 24.0"

REF ASCE7-02-CAB10015
 DATE 11/26/03
 DRWG MTKA STD CABLE 16 E HT
 -ENG



BRACING GROUP SPECIES AND GRADES:		
GROUP A:		
SPRUCE-PINE-TR	MDL-FIR	
#1 / #2	#2	STUD
#3	#3	STANDARD
STUD		
DOUGLAS FIR-LARCH		
#3		
STUD		
STANDARD		
GROUP B:		
HEB-FIR		
#1 & BTR		
#1		
SOUTHERN PINE		
#1		
#2		
DOUGLAS FIR-LARCH		
#1		
#2		

CABLE TRUSS DETAIL NOTES:

LIVE LOAD DEFLECTION CRITERIA IS $L/240$.
 PROVIDE UPLIFT CONNECTIONS FOR 180 PLF OVER
 CONTINUOUS BEARING (6 PSF PER DEAD LOAD).
 CABLE END SUPPORTS LOAD FROM $4' \times 0"$
 OUTDOORS WITH $2' \times 0"$ OVERHANG, OR $12"$
 PLYWOOD OVERHANG.

ATTACH T¹ BRACE WITH 10d NAILS.
* FOR (1) T¹ BRACE: SPACE NAILS AT 8" O.C.
IN 18" END ZONES AND 4" O.C. BETWEEN ZONES
* FOR (2) T¹ BRACES: SPACE NAILS AT 3" O.C.
IN 18" END ZONES AND 6" O.C. BETWEEN ZONES

CABLE VERTICAL PLATE SIZES	
VERTICAL LENGTH	NO SPlice
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR
PEAK, SPLICE, AND HEEL PLATES.

MANUFACTURING, MASSSES RES-BUILD, EXTENSIVE CARE IN FABRICATING, HANDING, SHIPPING, DISTRIBUTING AND MOVING. REFER TO BC51-19-3 CALIBRATING, COMPONENT SAFETY INFORMATION, PUBLISHED BY THE STRUSSER PLATE INSTITUTE, 3982 DOWNSIDE RD., SUITE 200, HENDERSON, NV, 89079 AND VICA (VIBRO TRUSS CO.) OF AMERICA, 6500 ENTERPRISE BL., MARIETTA, GA 30067 FOR SAFETY PRACTICES, PRIOR TO PERFORMING THESE TONATIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE POSITIVE ATTACHMENT TO STRUCTURAL PANELS, AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.


1456 SW 4th AVENUE
DELRAY BEACH, FL. 33444-2161

No: 34868
STATE OF FLORIDA


MAX. TOT. LD. 60 PSF
MAX. SPACING 24.0"

REF	ASCE7-02-CAB13030
DATE	11/26/03
DWG	M/PEK STD CABLE 30' E MT
-ENG	


TYPICAL ATTIC TRUSS BRACING



TYPICAL ALTERNATE BRACING DETAIL FOR EXTERIOR FLAT GIRDER TRUSS





GABLE END TRUSS DETAIL



MINIMUM BC BRACING ON GABLE TRUSS. OTHER PERMANENT BRACING DESIGNS BY ARCHITECT OR BOB

TYPICAL WALL GIRDER VERTICAL WEB BRACING DETAIL



JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4TH AVENUE
DELRAY BEACH, FL 33444-2161

No. 34869
STATE OF FLORIDA

TOP CHORD 2X4 #2 OR BETTER
BOT CHORD 2X4 #2 OR BETTER
WEBS 2X4 #3 OR BETTER

PIGGYBACK DETAIL

REFER TO SEALED DESIGN FOR DASHED PLATES.

SPACE PIGGYBACK VERTICALS AT 4' OC MAX.

TOP AND BOTTOM CHORD SPLICES MUST BE STAGGERED SO THAT ONE SPLICE IS NOT DIRECTLY OVER ANOTHER.

PIGGYBACK BOTTOM CHORD MAY BE OMITTED. ATTACH VERTICAL WEBS TO TRUSS TOP CHORD WITH 1.5X3 PLATE.

ATTACH PURLINS TO TOP OF FLAT TOP CHORD. IF PIGGYBACK IS SOLID LUMBER OR THE BOTTOM CHORD IS OMITTED, PURLINS MAY BE APPLIED BENEATH THE TOP CHORD OF SUPPORTING TRUSS.

REFER TO ENGINEER'S SEALED DESIGN FOR REQUIRED PURLIN SPACING.

THIS DETAIL IS APPLICABLE FOR THE FOLLOWING WIND CONDITIONS:

110 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG.

LOCATED ANYWHERE IN ROOF, 1 MI FROM COAST

CAT I, EXP C, WIND TC DL=5 PSF, WIND BC DL=5 PSF


110 MPH WIND, 30' MEAN HGT, FBC

ENCLOSED BLDG, LOCATED ANYWHERE IN ROOF

WIND TC DL=5 PSF, WIND BC DL=5 PSF


130 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II, EXP. C, WIND TC DL=6 PSF, WIND BC DL=6 PSF

FRONT FACE (E*) PLATES MAY BE OFFSET FROM BACK FACE PLATES AS LONG AS BOTH FACES ARE SPACED 4' OC MAX.



EITHER PLATE LOCATION IS ACCEPTABLE

OPTIONAL SPLICE



*ATTACH PIGGYBACK WITH 3X6 TRUSS OR ALPINE PIGGYBACK SPECIAL PLATE.


WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST PRACTICES BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY THE TRUSS COUNCIL OF AMERICA, 1400 SH AND AVENUE, SUITE 200, WESTLAND, MI 48090-1500, TEL: 313-779-1000, FAX: 313-779-1001, WWW.TRUSSCOUNCIL.ORG FOR THE LATEST INFORMATION. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JOINT TYPE	SPANS UP TO			
	30'	34'	38'	62'
A	2X4	2.5X4	2.5X4	3X6
B	4X6	5X6	5X6	5X6
C	1.5X3	1.5X4	1.5X4	1.5X4
D	5X4	6X6	6X6	5X6
E	4X6 OR 3X6 TRUSS AT 4' OC, ROTATED VERTICALLY			

ATTACH TRUSS PLATES WITH (8) 0.120" X 1.375" NAILS, OR EQUAL, PER FACE PER PLY. (4) NAILS IN EACH MEMBER TO BE CONNECTED. REFER TO DRAWING 160 TL FOR TRUSS INFORMATION.

WEB LENGTH	WEB BRACING CHART
0' TO 7'9"	NO BRACING
7'9" TO 10'	1X4 "T" BRACE, SAME GRADE, SPECIES AS WEB MEMBER, OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 8d NAILS AT 4' OC.
10' TO 14'	2X4 "T" BRACE, SAME GRADE, SPECIES AS WEB MEMBER, OR BETTER, AND 80% LENGTH OF WEB MEMBER. ATTACH WITH 16d NAILS AT 4' OC.

* PIGGYBACK SPECIAL PLATE
ATTACH TEETH TO THE PIGGYBACK AT THE TIME OF FABRICATION. ATTACH TO SUPPORTING TRUSS WITH (4) 0.120" X 1.375" NAILS PER FACE PER PLY. APPLY PIGGYBACK SPECIAL PLATE TO EACH TRUSS FACE AND SPACE 4' OC OR LESS.



THIS DRAWING REPLACES DRAWINGS 634.016 634.017 & 847.045

JULIUS LEE'S
CONS. ENGINEERS P.A.
1400 SH AND AVENUE
SUITE 200
WESTLAND, MI 48090-1500
TEL: 313-779-1000
FAX: 313-779-1001
WWW.TRUSSCOUNCIL.ORG

MAX LOADING	REF
55 PSF AT	PIGGYBACK
1.33 DUR. FAC.	DATE 09/12/07
50 PSF AT	DRWG/ITEK STD PIGGY
1.25 DUR. FAC.	-ENG JL
47 PSF AT	
1.15 DUR. FAC.	
SPACING 24.0"	

No. 34868
STATE OF FLORIDA





VALLEY TRUSS DETAIL

TOP CHORD 2X4 SP #2 OR SPF #1/#2 OR BETTER.
BOT CHORD 2X3(*) OR 2X4 SP #2N OR SPF #1/#2 OR BETTER.
WEBS 2X4 SP #3 OR BETTER.


* 2X3 MAY BE RIPPED FROM A 2X6 (PITCHED OR SQUARE).

** ATTACH EACH VALLEY TO EVERY SUPPORTING TRUSS WITH:

(2) 16d BOX (0.135" X 3.5") NAILS TOE-NAILLED FOR
FBC 2004 110 MPH, ASCE 7-02 110 MPH WIND OR (3) 16d FOR
ASCE 7-02 130 MPH WIND. 15' MEAN HEIGHT, ENCLOSED
BUILDING, EXP. C, RESIDENTIAL, WIND TC DL=6 PSF.



SUPPORTING TRUSSES AT 24" OC MAXIMUM SPACING.




PITCHED CUT
BOTTOM CHORD
VALLEY

SQUARE CUT
BOTTOM CHORD
VALLEY

OPTIONAL STUB
END DETAIL

OPTIONAL HIP
JOINT DETAIL



COMMON TRUSSES
AT 24" OC

PARTIAL FRAMING
PLAN

UNLESS SPECIFIED ON ENGINEER'S SEALED DESIGN, APPLY 1X4 "I"-BRACE, 80%
LENGTH OF WEB, VALLEY WEB, SAME SPECIES AND GRADE OR BETTER, ATTACHED
WITH 8d BOX (0.113" X 2.5") NAILS AT 6" OC, OR CONTINUOUS LATERAL BRACING,
EQUALLY SPACED, FOR VERTICAL VALLEY WEBS GREATER THAN 7'9".

MAXIMUM VALLEY VERTICAL HEIGHT MAY NOT EXCEED 12'0".

TOP CHORD OF TRUSS BENEATH VALLEY SET MUST BE BRACED WITH:
PROPERLY ATTACHED, RATED SHEATHING APPLIED PRIOR TO VALLEY TRUSS
INSTALLATION

OR
PURLINS AT 24" OC OR AS OTHERWISE SPECIFIED ON ENGINEERS' SEALED DESIGN
OR
BY VALLEY TRUSSES USED IN LIEU OF PURLIN SPACING AS SPECIFIED ON
ENGINEERS' SEALED DESIGN.

*** NOTE THAT THE PURLIN SPACING FOR BRACING THE TOP CHORD OF THE TRUSS
BENEATH THE VALLEY IS MEASURED ALONG THE SLOPE OF THE TOP CHORD.
++ LARGER SPANS MAY BE BUILT AS LONG AS THE VERTICAL HEIGHT DOES
NOT EXCEED 12'0".
BOTTOM CHORD MAY BE SQUARE OR PITCHED CUT AS SHOWN.

NO VARIATIONS TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND
BRACING. REFER TO BEST PRACTICE BUILDING CODES AND SPECIFICATIONS, PUBLISHED BY THE TRUSS
OF AMERICA, 1455 SW 4TH AVENUE, SUITE 200, MIAMI, FL 33135, FOR THE LATEST TRUSS CONSTRUCTION
PRACTICES. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED
STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.

1455 SW 4TH AVENUE
DELRAY BEACH, FL 33444-2101

No: 34869
STATE OF FLORIDA

TC LL	20	20	PSF	REF	VALLEY DETAIL
BC DL	7	15	PSF	DATE	11/26/03
BC DL	5	5	PSF	DRWG	VALTRUSS1103
BC LL	0	0	PSF	-ENG	JL
TOT. LD.	32	40	PSF		
DUR.FAC.	1.25	1.25			
SPACING	24"				

THIS DRAWING REPLACES DRAWING A105

TOE-NAIL DETAIL

TOE-NAILS TO BE DRIVEN AT AN ANGLE OF APPROXIMATELY THIRTY DEGREES WITH THE PIECE AND STARTED APPROXIMATELY ONE-THIRD THE LENGTH OF THE NAIL FROM THE END OF THE MEMBER.

PER ANSI/AP&PA NDS-2001 SECTION 12.4.1 - EDGE DISTANCE, END DISTANCE, SPACING, EDGE DISTANCES, END DISTANCES AND SPACINGS FOR NAILS AND SPIKES SHALL BE SUFFICIENT TO PREVENT SPLITTING OF THE WOOD.



THE NUMBER OF TOE-NAILS TO BE USED IN A SPECIFIC APPLICATION IS DEPENDENT UPON PROPERTIES FOR THE CHORD SIZE, LUMBER SPECIES, AND NAIL TYPE. PROPER CONSTRUCTION PRACTICES AS WELL AS GOOD JUDGEMENT SHOULD DETERMINE THE NUMBER OF NAILS TO BE USED.

THIS DETAIL DISPLAYS A TOE-NAILED CONNECTION FOR JACK FRAMING INTO A SINGLE OR DOUBLE PLY SUPPORTING GIRDER.

MAXIMUM VERTICAL RESISTANCE OF 16d (0.162"x3.5") COMMON TOE-NAILS

NUMBER OF TOE-NAILS	SOUTHERN PINE		DOUGLAS FIR-LARCH		HEM-FIR		SPRUCE PINE FIR	
	1 PLY	2 PILES	1 PLY	2 PILES	1 PLY	2 PILES	1 PLY	2 PILES
2	197#	256#	181#	234#	156#	203#	154#	199#
3	296#	383#	271#	351#	234#	304#	230#	298#
4	394#	511#	361#	468#	312#	406#	307#	397#
5	493#	639#	452#	585#	390#	507#	384#	496#

ALL VALUES MAY BE MULTIPLIED BY APPROPRIATE DURATION OF LOAD FACTOR.



ALTERNATIVE CONDITION

THIS DRAWING REPLACES DRAWING 784040

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-43 BUILDING CONCRETE SAFETY INFORMATION PUBLISHED BY THE NATIONAL PLATE INSTITUTE, 383 PINEHURST DR., SUITE 200, NATION, VI, 20719 AND VICA (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE LN, MADISON, VI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.

1450 ST 4TH AVENUE
DELRAY BEACH, FL 33444-2161

TC LL	PSF	REF	TOE-NAIL
TC DL	PSF	DATE	09/12/07
BC DL	PSF	DRWG	CNTONAIL1103
BC LL	PSF	-ENG	JL
TOT. LD.	PSF		

No. 34689

STATE OF FLORIDA


DUR. FAC. 1.00
SPACING

1/2" DIAMETER BOLT SPACING FOR LOAD APPLIED PARALLEL TO GRAIN.

* GRADE AND SPECIES AS SPECIFIED ON THE ALPINE DESIGN.
BOLT HOLES SHALL BE A MINIMUM OF 1/32" TO A MAXIMUM OF 1/16" LARGER THAN BOLT DIAMETER.

TYPICAL LOCATION OF 1/2" DIAMETER THRU BOLTS. BOLT QUANTITIES AS NOTED ON SEALED DESIGN MUST BE APPLIED IN ONE OF THE PATTERNS SHOWN BELOW.

WASHERS REQUIRED UNDER BOLT HEAD AND NUT



2X6 DETAIL

2X8 DETAIL

THIS DRAWING REPLACES DRAWING A828.016

** VARIATION: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC&I-DO BUILDING DEPARTMENT SAFETY INFORMATION, PUBLISHED BY THE TRUSS PLATE INSTITUTE, 360 OGDON RD., SUITE 200, MADISON, WI 53719 AND WCA CYCLO TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 BY 4TH AVENUE
DEARBORN GEAR, MI 48114-2161

No. 34969
STATE OF FLORIDA

TC LL	PSF	REF	BOLT SPACING
TC DL	PSF	DATE	11/26/03
BC DL	PSF	DRWG	CNBOLTSPI103
BC LL	PSF	-ENG	JL
TOT. LD.	PSF		
DUR. FAC.			
SPACING			

TRULOX CONNECTION DETAIL




11 GAUGE (0.120" X 1.375") NAILS REQUIRED FOR TRULOX PLATE ATTACHMENT. FILL ROWS COMPLETELY WHERE SHOWN (Φ).

* NAILS MAY BE OMITTED FROM THESE ROWS.

THIS DETAIL MAY BE USED WITH SO. PINE, DOUGLAS-FIR OR HEM-FIR CHORDS WITH A MINIMUM 1.00 DURATION OF LOAD OR SPRUCE-PINE-FIR CHORDS WITH A MINIMUM 1.15 DURATION OF LOAD. CHORD SIZE OF BOTH TRUSSES MUST EXCEED THE TRULOX PLATE WIDTH.

TRULOX PLATE IS CENTERED ON THE CHORDS AND BENT BETWEEN NAIL ROWS.

REFER TO ENGINEER'S SEALED DESIGN REFERENCING THIS DETAIL FOR LUMBER, PLATES, AND OTHER INFORMATION NOT SHOWN.



TRULOX PLATE SIZE	REQUIRED NAILS PER TRUSS	MAXIMUM LOAD UP OR DOWN
3X6	9	350#
5X6	15	990#

MINIMUM 5X6 TRULOX PLATE.

THIS DRAWING REPLACES DRAWINGS 1,158,989 1,158,989/R 1,154,844 1,152,217 1,152,017 1,159,154 & 1,151,524


WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO AC308 (1-83) FOR TRUSSING CONCEPTS AND DETAILS. FOR TRUSSING DETAILS, REFER TO THE TRUSSING MANUAL, 3RD EDITION, DR. S. R. MOORE, V.I. 33719 AND V.I. 33720 TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, VI 33719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2161


REF	TRULOX
DATE	11/26/03
DRWG	CNTRULOX1103
-ENG	JL

No: 34869
STATE OF FLORIDA

STRONG BACK DETAIL SYSTEM-42 OR FLAT TRUSS




ALTERNATE DETAIL FOR STRONG BACK WITH VERTICAL NOT LINING UP



JULIUS LEE'S
CONS. ENGINEERS P.A.
1455 SW 4th AVENUE
MIAMI BEACH, FL 33141-2161

No. 34669
STATE OF FLORIDA



Notice of Prevention for Subterranean Termites

(As required by Florida Building Code (FBC) 104.2.6)



17856 U.S. 129 • McALPIN, FLORIDA 32062
(386) 362-3887 • 1-800-771-3887 • Fax: (386) 364-3529

#000026710

Address of Treatment or Lot/Block of Treatment

Date

Time

Applicator

Product Used

Chemical used (active ingredient)

Number of gallons applied

Percent Concentration

Area treated (square feet)

Linear feet treated

Stage of treatment (Horizontal, Vertical, Adjoining Slab, retreat of disturbed area)

As per 104.2.6 - If soil chemical barrier method for Subterranean termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial and date this line.

Notice of Prevention for Subterranean Termites

(As required by Florida Building Code (FBC) 104.2.6)



17856 U.S. 129 • McALPIN, FLORIDA 32062
(386) 362-3887 • 1-800-771-3887 • Fax: (386) 364-3529

Permit #000026710

KARANTINOS 954 S.W. MOUNT CARMEL AVE. LAKE CITY FL.

Address of Treatment or Lot/Block of Treatment

Date

Time

Applicator

Product Used

Chemical used (active ingredient)

Number of gallons applied

Percent Concentration

Area treated (square feet)

Linear feet treated

Stage of treatment (Horizontal, Vertical, Adjoining Slab, retreat of disturbed area)

As per 104.2.6 - If soil chemical barrier method for Subterranean termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial and date this line.

Notice of Prevention for Subterranean Termites

(As required by Florida Building Code (FBC) 104.2.6)



17856 U.S. 129 • McALPIN, FLORIDA 32062
(386) 362-3887 • 1-800-771-3887 • Fax: (386) 364-3529

#000026710

KARANTINOS 954 SW MOUNT CARMEL AVE LAKE CITY FL

Address of Treatment or Lot/Block of Treatment

Date

Time

Applicator

Product Used

Chemical used (active ingredient)

Number of gallons applied

Percent Concentration

Area treated (square feet)

Linear feet treated

Stage of treatment (Horizontal, Vertical, Adjoining Slab, retreat of disturbed area)

As per 104.2.6 - If soil chemical barrier method for Subterranean termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial and date this line.