

DATE 11/16/2005

Columbia County Building Permit

PERMIT 000023854

This Permit Expires One Year From the Date of Issue

APPLICANT SUSAN FAIR
ADDRESS 180 NW AMENITY STREET LAKE CITY FL 32055
OWNER RITA MAZDZER
ADDRESS 154 SE GREGORY GLEN LAKE CITY FL 32025
CONTRACTOR BRYAN ZECHER
LOCATION OF PROPERTY BAYA, TR ON OLD COUNTRY CLUB RD, TL ON GREGORY GLEN, 2ND LOT ON RIGHT
TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 75000.00
HEATED FLOOR AREA 1500.00 TOTAL AREA 1974.00 HEIGHT .00 STORIES 1
FOUNDATION CONC WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB
LAND USE & ZONING RSF-2 MAX. HEIGHT 18
Minimum Set Back Requirements: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 0 FLOOD ZONE XPP DEVELOPMENT PERMIT NO.
PARCEL ID 15-4S-17-08359-130 SUBDIVISION COUNTRY CLUB EST.
LOT 30 BLOCK PHASE UNIT TOTAL ACRES

000000887
Culvert Permit No. Culvert Waiver Contractor's License Number CBC054575 Applicant/Owner/Contractor
CULVERT 05-1065-N BK JH Approved for Issuance Y
Driveway Connection Septic Tank Number LU & Zoning checked by New Resident
COMMENTS: ONE FOOT ABOVE THE ROAD, NOC ON FILE, ALTERNATE TERMIT TREAT RECEIVED

Check # or Cash 2074

FOR BUILDING & ZONING DEPARTMENT ONLY

Temporary Power Foundation Monolithic date/app. by (footer/Slab)
Under slab rough-in plumbing Slab Sheathing/Nailing date/app. by
Framing Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in Heat & Air Duct Peri. beam (Lintel) date/app. by
Permanent power C.O. Final Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing Pool date/app. by
Reconnection Pump pole Utility Pole date/app. by
M/H Pole Travel Trailer Re-roof date/app. by

BUILDING PERMIT FEE \$ 375.00 CERTIFICATION FEE \$ 9.87 SURCHARGE FEE \$ 9.87
MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 116 CULVERT FEE \$ 25.00 TOTAL FEE 469.74
INSPECTORS OFFICE [Signature] CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY, AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.
"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."
This Permit Must Be Prominently Posted on Premises During Construction
PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.
The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions



UNIVERSAL
ENGINEERING SCIENCES
Consultant In: Geotechnical Engineering,
Environmental Sciences, Construction Materials Testing
4475 SW 35th Terrace, Gainesville, Florida 32608 (352) 372-3392

Order No.: 27915-001-01
Report No.: 6380
Date: November 14, 2005

**REPORT ON
IN-PLACE DENSITY TESTS**

23854

Client: Cornerstone Development
P.O. Box 1867
Lake City, FL 32056

Project: Country Side Estates, Lot No. 30, Permit Not Posted, Lake City, Columbia County, FL

Area Tested: Fill Beneath Proposed Building Pad

Course: Final Grade

Depth of Test: 0-1'


Type of Test: ASTM D-2922

Date Tested: 11-09-05

Remarks: The tests below meet the minimum 95 percent relative soil compaction requirement of Laboratory Modified Proctor maximum dry density (ASTM D-1557).

TEST LOCATION		LABORATORY RESULTS		FIELD TEST RESULTS		
Description of Test Location		Maximum Density (pcf)	Optimum Moisture (%)	Dry Density (pcf)	Field Moisture (%)	Soil Compaction (%)
1.	Approximate Center of Pad	112.0	11.0	106.5	8.4	95.1
2.	Approximate Center of North End of Pad	112.0	11.0	106.8	8.0	95.4
3.	Approximate Center of East Side of Pad	112.0	11.0	106.4	8.8	95.0

Technician: TI/ec


Andrew T. Schmid, P.E.
FL Professional Engineer No. 56022

Handwritten text, possibly a signature or date, located in the lower-left quadrant of the page.

OLD Application

Columbia County Building Permit Application

For Office Use Only Application # 0511-28 Date Received 7/1/05 By NW Permit # 887/23854
Application Approved by - Zoning Official BLK Date 15.11.05 Plans Examiner OK JTH Date 11-10-05
Flood Zone X Per Development Permit N/A Zoning RSF-2 Land Use Plan Map Category Res Low Dv
Comments PHAT

Applicants Name CHRIS COX SUSAN FAIR Phone 386-867-0633
Address 252 NW IVY GLEN LAKE CITY FL. 32055 Phone _____
Owners Name RITA MAZDZER
911 Address 154 SE GREGORY GLEN, LAKE CITY, FL 32025
Contractors Name BRYAN ZECHER CONSTRUCTION Phone 386-752-8653
Address P.O. BOX 815, LAKE CITY, FL 32056
Fee Simple Owner Name & Address N/A
Bonding Co. Name & Address N/A
Architect/Engineer Name & Address MARK DISOSWAY PO BOX 868 LAKE CITY FL 32056
Mortgage Lenders Name & Address NA

Property ID Number 15-45-17-08359-130 Estimated Cost of Construction 60,000.00
Subdivision Name COUNTRYSIDE ESTATES Lot 30 Block _____ Unit _____ Phase _____
Driving Directions BAYA TO COUNTRY CLUB ROAD, GO SOUTH ON COUNTRY CLUB ROAD 1 1/2 - 2 miles, SUBDIVISION IS ON THE LEFT. TAKE LEFT AT SE GREGORY GLEN.

Type of Construction FRAME & HARDY Number of Existing Dwellings on Property 1
Total Acreage 42 Lot Size 50 acres Do you need a Culvert Permit or Culvert Waiver or Have an Existing D
Actual Distance of Structure from Property Lines - Front 27' Side 57' Side 57' Rear 62'
Total Building Height 18' 9" Number of Stories 1 Heated Floor Area 1500 Roof Pitch 6/12
Porch 44 Garage 430 TOTAL 1974

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Chris W. Cox
Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA.

Sworn to (or affirmed) and subscribed before me
this 2nd day of NOVEMBER 20 05.
Personally known ✓ or Produced Identification _____

X
Contractor Signature
Contractors License Number CBC05457
Competency Card Number _____

NOTARY STAMP/SEAL

Chris W. Cox
Notary Signature



11/10/1910

88-1400

10/10/1910

10/10/1910

10/10/1910

10/10/1910

10/10/1910

Warranty Deed

Inst: 2005025015 Date: 10/07/2005

Doc Stamp-Deed : 175.00

DC, P. DeWitt Cason, Columbia County, Florida



This Indenture, made, October 7, 2005 A.D.

Between

Cornerstone Development Group, LLC whose post office address is: 180 Northwest Amenity Court, Lake City, Florida 32055 a Limited Liability Company existing under the laws of the State of Florida, Grantor

and Rita Mazdzer whose post office address is: 152 Southeast Hubble Street, Lake City, Florida 32025, Grantee,

STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY, that the above and foregoing
is a true copy of the original filed in this office.
P. DEWITT CASON, CLERK OF COURTS

By [Signature] Deputy Clerk

Date 10/07/05

Witnesseth, that the said Grantor, for and in consideration of the sum of Ten and No/100 Dollars (\$10.00), to it in hand paid by the said Grantee, the receipt whereof is hereby acknowledged, has granted, bargained and sold to the said Grantee forever, the following described land, situate, lying and being in the County of Columbia, State of Florida, to wit:

Lot 30, of Country Side Estates, a Subdivision, according to the Plat thereof, as recorded in Plat Book 8, at Pages 1 and 2, of the Public Records of Columbia County, Florida

Subject to taxes for the current year, covenants, restrictions and easements of record, if any.

Parcel Identification Number: R08359-016

And the said Grantor does hereby fully warrant the title to said land, and will defend the same against the lawful claims of all persons whomsoever.

In Witness Whereof, the said Grantor has caused this instrument to be executed in its name by its duly authorized office and caused its corporate seal to be affixed the day and year first above written.

Signed and Sealed in Our Presence:

[Signature]
Witness: LYNDI SKINNER

[Signature]
Witness: Megan Marable

Cornerstone Development Group, LLC

By: [Signature]
Frank Soucinek, Managing Member

By: [Signature]
Bryan Zecher, Member

State of Florida
County of Columbia

The foregoing instrument was acknowledged before me this 7th day of October, 2005, by Frank Soucinek, the Managing Member Bryan Zecher, Member of Cornerstone Development Group, LLC A Limited Liability Company existing under the laws of the State of Florida. They are personally known to me or has produced Known as identification.

[Signature] (Seal)
Notary Public
Notary Printed Name: _____

My Commission Expires:

Prepared by:
Lyndi Skinner/Elaine R. Davis, an employee of
American Title Services of Lake City, Inc.,
330 SW Main Boulevard
Lake City, Florida 32025

File Number: 05-718




Lyndi Skinner
My Commission DD150708
Expires September 17, 2006

STATE OF FLORIDA
DEPARTMENT OF HEALTH
APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number 05-1865N

PART II - SITEPLAN

Scale: 1 inch = 50 feet.



Notes:

Site Plan submitted by:

Plan Approved ☒

By

Not Approved ☐

Columbin

MASTER CONTRACTOR

Date 10-18-05

County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

DH 4015, 10/96 (Replaces HRS-H Form 4016 which may be used)
(Stock Number: 5744-002-4015-6)

Page 2




Permit Number:

Tax Folio Number: R08359-016

State of: Florida
County of: Columbia

File Number: 05-718



STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY, that the above and foregoing
is a true copy of the original filed in this office.
P. DeWITT CASON, CLERK OF COURTS

By

Date

P. DeWitt Cason
Deputy Clerk
10/07/05

Inst: 2005025017 Date: 10/07/2005 Time: 13:20
DC, P. DeWitt Cason, Columbia County B: 1061 P: 369

NOTICE OF COMMENCEMENT

The undersigned hereby gives notice that improvement will be made to certain real property, and, in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

1. Description of Property:

Lot 30, of Country Side Estates, a Subdivision, according to the Plat thereof, as recorded in Plat Book 8, at Pages 1 and 2, of the Public Records of Columbia County, Florida

2. General Description of Improvements: Construction of Dwelling

3. Owner Information:

- a. Name and Address: Rita Mazdzer
152 Southeast Hubble Street, Lake City, FL 32025
- b. Interest in property: Fee Simple
- c. Names and address of fee simple title holder (if other than owner):


4. Contractor: Bryan Zecher Contruction

5. Surety: N/A

6. Lender: First Federal Savings Bank of Florida, 4705 West U. S. Highway 90
Post Office Box 2029 (32056), Lake City, Florida 32055

7. Persons within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by Section 713.13(1) (a)7., Florida Statutes. NONE

8. In addition to himself. Owner designates the following persons to receive a copy of the Lienor's Notice as




COLUMBIA COUNTY 9-1-1 ADDRESSING

263 NW Lake City Ave. • P. O. Box 2949 • Lake City, FL 32056-2949
 PHONE: (386) 752-8787 • FAX (386) 758-1361 • Email: ron_croft@columbiacountyfla.com

52025

Addresses for Country Side Estates Subdivision:

Lot #:	Address Assigned:	Lot #:	Address Assigned:
1	165 SE Victoria Glen	16	123 SE Gregory Glen
2	195 SE Victoria Glen	17	153 SE Gregory Glen
3	223 SE Victoria Glen	18	183 SE Gregory Glen
4	251 SE Victoria Glen	19	215 SE Gregory Glen
5	281 SE Victoria Glen	20	245 SE Gregory Glen
6	311 SE Victoria Glen	21	275 SE Gregory Glen
7	329 SE Victoria Glen	22	309 SE Gregory Glen
8	328 SE Victoria Glen	23	329 SE Gregory Glen
9	306 SE Victoria Glen	24	330 SE Gregory Glen
10	274 SE Victoria Glen	25	308 SE Gregory Glen
11	244 SE Victoria Glen	26	276 SE Gregory Glen
12	214 SE Victoria Glen	27	246 SE Gregory Glen
13	182 SE Victoria Glen	28	216 SE Gregory Glen
14	152 SE Victoria Glen	29	184 SE Gregory Glen
15	122 SE Victoria Glen	30	154 SE Gregory Glen
		31	3239 SE Country Club Rd 124 SE Gregory Glen




1500/1974 - 469.74
 1200/1665 - 391.64

BLDG AND ZONING



COUNTRYSIDE ESTATES
 COLUMBIA COUNTY
 LOT 30 SITE PLAN



- CODE
- = NEW HOME
 - = POWER
 - = WATER
 - = SEPTIC

SE. GREGORY GLEN



FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	The Samuel Model	Builder:	Bryan Zecher Construction
Address:	Lot: , Sub: , Plat:	Permitting Office:	Columbia
City, State:	,	Permit Number:	23854
Owner:	Model Home	Jurisdiction Number:	221000
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	Cap: 34.0 kBtu/hr
2. Single family or multi-family	Single family	a. Central Unit	SEER: 12.00
3. Number of units, if multi-family	1	b. N/A	
4. Number of Bedrooms	3	c. N/A	
5. Is this a worst case?	Yes	13. Heating systems	Cap: 34.0 kBtu/hr
6. Conditioned floor area (ft²)	1500 ft²	a. Electric Heat Pump	HSPF: 7.60
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		b. N/A	
a. U-factor:	Description Area	c. N/A	
(or Single or Double DEFAULT) 7a. (Dble Default) 110.0 ft²		14. Hot water systems	Cap: 40.0 gallons
b. SHGC:		a. Electric Resistance	EF: 0.93
(or Clear or Tint DEFAULT) 7b. (Clear) 110.0 ft²		b. N/A	
8. Floor types	R=0.0, 196.0(p) ft	c. Conservation credits	
a. Slab-On-Grade Edge Insulation		(HR-Heat recovery, Solar	
b. N/A		DHP-Dedicated heat pump)	
c. N/A		15. HVAC credits	
9. Wall types	R=13.0, 172.0 ft²	(CF-Ceiling fan, CV-Cross ventilation,	
a. Frame, Wood, Adjacent	R=13.0, 1121.0 ft²	HF-Whole house fan,	
b. Frame, Wood, Exterior		PT-Programmable Thermostat,	
c. N/A		MZ-C-Multizone cooling,	
d. N/A		MZ-H-Multizone heating)	
e. N/A			
10. Ceiling types	R=30.0, 1754.0 ft²		
a. Under Attic			
b. N/A			
c. N/A			
11. Ducts	Sup. R=6.0, 150.0 ft		
a. Sup: Unc. Ret: Unc. AH: Garage			
b. N/A			

Glass/Floor Area: 0.14

Total as-built points: 23520
Total base points: 23819**PASS**

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: [Signature]DATE: 11/3/05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: [Signature]DATE: 11-5-05

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL: _____

DATE: _____



1 Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.0)




SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

BASE				AS-BUILT										
GLASS TYPES .18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang			Area X SPM X SOF = Points						
					Ornt	Len	Hgt							
.18	1500.0	20.04	5410.8	Double, Clear	S	2.0	5.5	45.0	35.87	0.75	1208.6			
				Double, Clear	SW	14.5	7.0	10.0	40.16	0.39	157.3			
				Double, Clear	S	12.0	5.3	45.0	35.87	0.44	716.2			
				Double, Clear	SE	8.5	7.0	10.0	42.75	0.46	195.4			
				Double, Clear	W	2.0	1.5	3.0	38.52	0.47	54.1			
				Double, Clear	N	9.5	7.5	6.0	19.20	0.67	77.7			
				Double, Clear	N	2.0	5.5	30.0	19.20	0.89	510.4			
				Double, Clear	N	2.0	8.0	30.0	19.20	0.94	540.7			
				Double, Clear	E	2.0	3.5	6.0	42.06	0.68	171.6			
				Double, Clear	E	2.0	5.5	30.0	42.06	0.82	1039.9			
				As-Built Total:							215.0	4672.0		
				WALL TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points			
				Adjacent	172.0	0.70	120.4	Frame, Wood, Adjacent	13.0		172.0	0.60	103.2	
Exterior	1121.0	1.70	1905.7	Frame, Wood, Exterior	13.0		1121.0	1.50	1681.5					
Base Total: 1293.0 2026.1				As-Built Total:		1293.0		1784.7						
DOOR TYPES Area X BSPM = Points				Type	Area X SPM = Points									
Adjacent	20.0	2.40	48.0	Exterior Insulated	20.0 4.10 82.0									
Exterior	40.0	6.10	244.0	Exterior Insulated	20.0 4.10 82.0									
				Adjacent Insulated	20.0 1.60 32.0									
Base Total: 60.0 292.0				As-Built Total:		60.0		196.0						
CEILING TYPES Area X BSPM = Points				Type	R-Value		Area X SPM X SCM = Points							
Under Attic	1500.0	1.73	2595.0	Under Attic	30.0		1754.0	1.73 X 1.00		3034.4				
Base Total: 1500.0 2595.0				As-Built Total:		1754.0		3034.4						
FLOOR TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points							
Slab	196.0(p)	-37.0	-7252.0	Slab-On-Grade Edge Insulation	0.0		196.0(p)	-41.20		-8075.2				
Raised	0.0	0.00	0.0											
Base Total: -7252.0				As-Built Total:		196.0		-8075.2						
INFILTRATION Area X BSPM = Points				Area X SPM = Points										
1500.0 10.21 15315.0				1500.0 10.21 15315.0										



SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

BASE				AS-BUILT									
Summer Base Points: 18386.9				Summer As-Built Points: 16926.9									
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component (System - Points)	X	Cap Ratio	X	Duct Multiplier (DM x DSM x AHU)	X	System Multiplier	X	Credit Multiplier	= Cooling Points
18386.9		0.4266	7843.9	(sys 1: Central Unit 34000 btuh ,SEER/EFF(12.0) Ducts:Unc(S),Unc(R),Gar(AH),R6.0(INS) 16927 1.00 (1.09 x 1.147 x 1.00) 0.284 1.000 6019.0 16926.9 1.00 1.250 0.284 1.000 6019.0									



WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

BASE				AS-BUILT						
GLASS TYPES .18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points			
.18	1500.0	12.74	3439.8	Double, Clear	S	2.0 5.5	45.0 13.30 1.32	787.4		
				Double, Clear	SW	14.5 7.0	10.0 16.74 1.94	324.1		
				Double, Clear	S	12.0 5.3	45.0 13.30 3.57	2133.3		
				Double, Clear	SE	8.5 7.0	10.0 14.71 2.13	312.7		
				Double, Clear	W	2.0 1.5	3.0 20.73 1.20	74.3		
				Double, Clear	N	9.5 7.5	6.0 24.58 1.02	150.6		
				Double, Clear	N	2.0 5.5	30.0 24.58 1.01	741.4		
				Double, Clear	N	2.0 8.0	30.0 24.58 1.00	739.1		
				Double, Clear	E	2.0 3.5	6.0 18.79 1.15	129.3		
				Double, Clear	E	2.0 5.5	30.0 18.79 1.07	603.4		
				As-Built Total:			215.0	5995.6		
WALL TYPES Area X BWPM = Points				Type	R-Value	Area X WPM = Points				
Adjacent	172.0	3.60	619.2	Frame, Wood, Adjacent	13.0	172.0 3.30	567.6			
Exterior	1121.0	3.70	4147.7	Frame, Wood, Exterior	13.0	1121.0 3.40	3811.4			
Base Total: 1293.0 4766.9				As-Built Total:			1293.0	4379.0		
DOOR TYPES Area X BWPM = Points				Type		Area X WPM = Points				
Adjacent	20.0	11.50	230.0	Exterior Insulated		20.0 8.40	168.0			
Exterior	40.0	12.30	492.0	Exterior Insulated		20.0 8.40	168.0			
				Adjacent Insulated		20.0 8.00	160.0			
Base Total: 60.0 722.0				As-Built Total:			60.0	496.0		
CEILING TYPES Area X BWPM = Points				Type	R-Value	Area X WPM X WCM = Points				
Under Attic	1500.0	2.05	3075.0	Under Attic	30.0	1754.0 2.05 X 1.00	3595.7			
Base Total: 1500.0 3075.0				As-Built Total:			1754.0	3595.7		
FLOOR TYPES Area X BWPM = Points				Type	R-Value	Area X WPM = Points				
Slab	196.0(p)	8.9	1744.4	Slab-On-Grade Edge Insulation	0.0	196.0(p) 18.80	3684.8			
Raised	0.0	0.00	0.0							
Base Total: 1744.4				As-Built Total:			196.0	3684.8		
INFILTRATION Area X BWPM = Points				Area X WPM = Points						
	1500.0	-0.59	-885.0	1500.0 -0.59 -885.0						



WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

BASE				AS-BUILT									
Winter Base Points: 12863.1				Winter As-Built Points: 17266.1									
Total Winter Points	X	System Multiplier	= Heating Points	Total Component (System - Points)	X	Cap Ratio (DM x DSM x AHU)	X	Duct Multiplier	X	System Multiplier	X	Credit Multiplier	= Heating Points
12863.1		0.6274	8070.3	(sys 1: Electric Heat Pump 34000 btuh ,EFF(7.6) Ducts:Unc(S),Unc(R),Gar(AH),R6.0 17266.1 1.000 (1.069 x 1.169 x 1.00) 0.449 1.000 9681.1 17266.1 1.00 1.250 0.449 1.000 9681.1									

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

BASE				AS-BUILT					
WATER HEATING				Tank	EF	Number of	X	Tank	X
Number of	X	Multiplier	=	Total	Volume	Bedrooms		Ratio	Multiplier
Bedrooms									
3		2635.00		7905.0	40.0	0.93	3	1.00	2606.67
					As-Built Total:				7820.0

CODE COMPLIANCE STATUS							
BASE				AS-BUILT			
Cooling	+	Heating	+	Hot Water	=	Total	
Points		Points		Points		Points	
7844		8070		7905		23819	

Cooling	+	Heating	+	Hot Water	=	Total	
Points		Points		Points		Points	
6019		9681		7820		23520	

PASS





Code Compliance Checklist
Residential Whole Building Performance Method A - Details

ADDRESS: Lot: , Sub: , Plat: , , ,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum:.3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 612.1.ABC.3.2. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	



ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 83.2

The higher the score, the more efficient the home.

Model Home, Lot: , Sub: , Plat: , , ,

1. New construction or existing	New	12. Cooling systems	Cap: 34.0 kBtu/hr
2. Single family or multi-family	Single family	a. Central Unit	SEER: 12.00
3. Number of units, if multi-family	1	b. N/A	
4. Number of Bedrooms	3	c. N/A	
5. Is this a worst case?	Yes		
6. Conditioned floor area (ft ²)	1500 ft ²	13. Heating systems	Cap: 34.0 kBtu/hr
7. Glass type ¹ and area: (Label reqd. by 13-104.4.5 if not default)		a. Electric Heat Pump	HSPF: 7.60
a. U-factor:	Description Area	b. N/A	
(or Single or Double DEFAULT)	7a. (Dble Default) 110.0 ft ²	c. N/A	
b. SHGC:	7b. (Clear) 110.0 ft ²	14. Hot water systems	Cap: 40.0 gallons
(or Clear or Tint DEFAULT)		a. Electric Resistance	EF: 0.93
8. Floor types	R=0.0, 196.0(p) ft	b. N/A	
a. Slab-On-Grade Edge Insulation		c. Conservation credits	
b. N/A		(HR-Heat recovery, Solar	
c. N/A		DHP-Dedicated heat pump)	
9. Wall types	R=13.0, 172.0 ft ²	15. HVAC credits	
a. Frame, Wood, Adjacent	R=13.0, 1121.0 ft ²	(CF-Ceiling fan, CV-Cross ventilation,	
b. Frame, Wood, Exterior		HF-Whole house fan,	
c. N/A		PT-Programmable Thermostat,	
d. N/A		MZ-C-Multizone cooling,	
e. N/A		MZ-H-Multizone heating)	
10. Ceiling types	R=30.0, 1754.0 ft ²		
a. Under Attic			
b. N/A			
c. N/A			
11. Ducts	Sup. R=6.0, 150.0 ft		
a. Sup: Unc. Ret: Unc. AH: Garage			
b. N/A			

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: Chris G.

Date: 11-5-05

Address of New Home: 154 SE GREGORY AVE

City/FL Zip: LAKELAND FL 33005

*NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStarTM designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.

¹ Predominant glass type. For actual glass type and areas, see Summer & Winter Glass output on pages 2&4.
EnergyGauge® (Version: FLRCSB v4.0)





**Columbia County Building Department
Culvert Permit**

**Culvert Permit No.
000000887**

DATE 11/16/2005 PARCEL ID # 15-4S-17-08359-130
APPLICANT SUSAN FAIR PHONE 752-5218
ADDRESS 180 NW AMENITY COURT LAKE CITY FL 32055
OWNER RITA MAZDZER PHONE _____
ADDRESS 154 SE GREGORY GLEN LAKE CITY FL 32025
CONTRACTOR BRYAN ZECHER PHONE 752-8653
LOCATION OF PROPERTY BAYA, TR ON OLD COUNTRY CLUB ROAD, TL ON GREGORY GLEN, 2ND LOT
ON RIGHT _____
SUBDIVISION/LOT/BLOCK/PHASE/UNIT COUNTRY SIDE EST 30
SIGNATURE *Susan Fair*

INSTALLATION REQUIREMENTS



Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
 - b) the driveway to be served will be paved or formed with concrete.
- Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.



Culvert installation shall conform to the approved site plan standards.



Department of Transportation Permit installation approved standards.



Other _____

**ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALLATION OF THE CULVERT.**

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001 ONE (1) AND TWO (2) FAMILY DWELLINGS ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE ----- 110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant	Plans Examiner	
☒	☒	All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
☒	☒	Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.
☒	☒	Site Plan including: a) Dimensions of lot b) Dimensions of building set backs c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements. d) Provide a full legal description of property.
☒	☒	Wind-load Engineering Summary, calculations and any details required a) Plans or specifications must state compliance with FBC Section 1606 b) The following information must be shown as per section 1606.1.7 FBC a. Basic wind speed (MPH) b. Wind importance factor (I) and building category c. Wind exposure - if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated d. The applicable internal pressure coefficient e. Components and Cladding. The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional
☒	☒	Elevations including: a) All sides b) Roof pitch c) Overhang dimensions and detail with attic ventilation d) Location, size and height above roof of chimneys e) Location and size of skylights f) Building height g) Number of stories

See
NOTE
1



NA

c. Crawl space (if applicable)

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termiticide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

Floor Framing System:

b) Floor joist size and spacing

c) Girder size and spacing

d) Attachment of joist to girder

e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified

b) Ceiling fans

c) Smoke detectors

d) Service panel and sub-panel size and location(s)

e) Meter location with type of service entrance (overhead or underground)

f) Appliances and HVAC equipment

g) Arc Fault Circuits (AFCI) in bedrooms

HVAC information

a) Manual J sizing equipment or equivalent computation

b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment *N/A*

Disclosure Statement for Owner Builders


Notice Of Commencement

Private Potable Water — Private water system


Size of pump motor

Size of pressure tank

) Cycle stop valve if used



46-8-0



BEARING HEIGHT SCHEDULE



8'

2' 0"/H
6/12

NOTES:

- 1.) REFER TO HIP 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.
- 2.) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V105 FOR ALTERNATE BRACING REQUIREMENTS.
- 3.) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
- 4.) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
- 5.) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6.) SY42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
- 7.) ALL ROOF TRUSS HANGERS TO BE SIMPSON HU526 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SIMPSON THA422 UNLESS OTHERWISE NOTED.
- 8.) BEAM/HEADER/INTEL (HDR) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VOIDS ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS. REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Requested Delivery Date : _____

Approved by: _____ Date: _____



PHONE: 904-437-3349 FAX: 904-437-3994

Jacksonville

PHONE: 904-772-6100 FAX: 904-772-1973

Lake City

PHONE: 904-755-6894 FAX: 904-755-7973

Sanford

PHONE: 407-322-0059 FAX: 407-322-5553

BUILDER: BRYAN ZECHER

LEGAL ADDRESS: LOT 30-1 CSE

MODEL: THE SAMUEL

REVISION: SCALE: NTS

DATE: 10-14-05

DRAWN BY: JRD

JOB #: L136745



Log On

[DBPR Home](#) | [Online Services Home](#) | [Help](#) | [Site Map](#)

10:00:13 AM

Public Services

- [Search for a Licensee](#)
- [Apply for a License](#)
- [View Application Status](#)
- [Apply to Retake Exam](#)
- [Find Exam Information](#)
- [Find a CE Course](#)
- [File a Complaint](#)
- [AB&T Delinquent Invoice & Activity List Search](#)

User Services

- Renew a License
- Change License Status
- Maintain Account
- Change My Address
- View Messages
- Change My PIN
- View Continuing Ed



Term Glossary



Online Help

Licensee Details

Licensee Information

Name: **ZECHER, BRYAN CHRISTIAN (Primary Name)**
BRYAN ZECHER CONSTRUCTION INC (DBA)

Main Address: **P O BOX 815**
LAKE CITY, Florida 32056

Lic. Location: **465 NW ORANGE ST**
LAKE CITY, FL 32055 United States
Columbia

License Information

License Type:	Certified Building Contractor
Rank:	Cert Building
License Number:	CBC054575
Status:	Current, Active
Licensure Date:	12/05/1991
Expires:	08/31/2006

Special Qualifications	Effective Date
------------------------	----------------

[illegible]

Qualified Business License
Required

[View Related License Information](#)[View License Complaint](#)[New Search](#)

F

[Terms of Use](#) | [Privacy Statement](#) |

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9186
15140 S. FLORIDA AVE. STE B, LUTZ, FL 33549

THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 80967
STRUCTURAL ENGINEERING AND INSPECTIONS INC., EB 9186
76105 N. FLORIDA AVE. STE B, LUTZ, FL 33549, KRJ... 10/11/2004


Scale = 1:7.2

BRACING	Structural wood sheathing directly applied or 1-0-0 oc purlins.
TOP CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
BOT CHORD	

LOAD CASE(S) Standard

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549





LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.29	Vert(LL)	-0.00	2-4	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.06	Vert(TL)	-0.01	2-4	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2004/TPI2002		(Matrix)							
									Weight: 13 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (lb/size) 3=31/Mechanical, 2=278/0-3-8, 4=42/Mechanical
Max Horz 2=132(load case 5)
Max Uplift3=28(load case 6), 2=-203(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-57/7
BOT CHORD 2-4=0/0


NOTES
1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 3 and 203 lb uplift at joint 2.

LOAD CASE(S) Standard

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549







Job

L136745

Truss

CJ5A

Truss Type

MONO SCISSOR

Qty

2

Ply

1

BRYAN ZECHER- LOT30-1 CSE

Dwg.#101705124

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Fri Oct 14 14:13:22 2005 Page 1

Scale = 1:15.0

Plate Offsets (X,Y): [2-0-2-4,0-1-8]										
LOADING (psf)		SPACING 2-0-0		CSI		DEFL		PLATES GRIP		
TCLL	20.0	Plates Increase	1.25	TC	0.29	in (loc)	l/defl	L/d	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.16	Vert(LL)	-0.03 2-4	>999 240		
BCLL	10.0	Rep Stress Incr	YES	WB	0.00	Vert(TL)	-0.05 2-4	>999 180		
BCDL	5.0	Code FBC2004/TPI2002		(Matrix)		Horz(TL)	-0.00 3	n/a n/a		
Weight: 20 lb										

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=103/Mechanical, 2=343/0-3-8, 4=72/Mechanical
Max Horz 2=177(load case 5)
Max Uplift 3=-89(load case 5), 2=-198(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/46, 2-3=-90/36
BOT CHORD 2-4=-18/18

NOTES
1) Wind: ASCE 7-02: 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Refer to girder(s) for truss to truss connections.
3) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 89 lb uplift at joint 3 and 198 lb uplift at joint 2.

LOAD CASE(S) Standard

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job: L136745 Truss: EJ7 Truss Type: MONO TRUSS Qty: 15 Ply: 1 BRYAN ZECHER- LOT30-1 CSE Dwg.#101705125

Builders FirstSource, Lake City, FL 32055 6.200 s Jul 13 2005 Mittek Industries, Inc. Fri Oct 14 14:13:22 2005 Page 1

Job Reference (optional)

Diagram showing a truss structure with dimensions and components. The truss is labeled with dimensions: 2-0-0, 7-0-0, 2-0-0, 7-0-0, 3-0-0, 7-0-0, 7-0-0. The truss is supported by a wall at the left end and a roller support at the right end. The truss is labeled with components: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.

Scale = 1:16.0

LOADING (psf)		SPACING		CSI		DEFL				PLATES		GRIP	
TCLL	20.0	Plates Increase	1.25	TC	0.48	in	(loc)	l/defl	L/d	MT20	244/190		
TCDL	7.0	Lumber Increase	1.25	BC	0.35	Vert(LL)	-0.12	2-4	>664				
BCDL	10.0	Rep Stress Incr	YES	WB	0.00	Vert(TL)	-0.21	2-4	>397				
BCDL	5.0	Code FBC2004/TPI2002		(Matrix)		Horz(TL)	-0.00	3	n/a				
										Weight: 26 lb			

LUMBER		BRACING	
TOP CHORD	2 X 4 SYP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2 X 4 SYP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (lb/size) 3=162/Mechanical, 2=419/0-3-8, 4=104/Mechanical
Max Horz 2=224(load case 5)
Max Uplift 3=-134(load case 5), 2=-210(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-119/58
BOT CHORD 2-4=0/0

NOTES
1) Wind: ASCE 7-02: 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 3 and 210 lb uplift at joint 2.

LOAD CASE(S) Standard

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



LOADING (psf)		SPACING		CSI		DEFL		PLATES		GRIP	
TCLL	20.0	Plates Increase	1.25	TC	0.61	in	(loc)	I/defl	L/d	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.57	Vert(LL)	-0.10	6-7	>999		
BCCL	10.0	Rep Stress Incr	NO	WB	0.49	Vert(TL)	-0.17	6-7	>686		
BCDL	5.0	Code FBC2004/TPI2002		(Matrix)		Horz(TL)	0.01	5	n/a		
										Weight: 45 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2

BOT CHORD 2 X 4 SYP No.2

WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (lb/size) 4=269/Mechanical, 2=532/0-4-15, 5=377/Mechanical
Max Horz 2=269(load case 2)
Max Uplift 4=231(load case 2), 2=-278(load case 2), 5=-63(load case 2)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/50, 2-3=-888/121, 3-4=-105/66
BOT CHORD 2-7=-309/823, 6-7=-309/823, 5-6=0/0
WEBS 3-7=0/180, 3-6=-856/321


NOTES
1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 231 lb uplift at joint 4, 278 lb uplift at joint 2 and 63 lb uplift at joint 5.
4) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


LOAD CASE(S) Standard
1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-2=-54
Trapezoidal Loads (plf)
Vert: 2=-3(F=26, B=26)-to 4=-134(F=-40, B=-40), 2=-0(F=15, B=15)-to 5=-74(F=-22, B=-22)

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549












Plate Offsets (X,Y): [2-0-0-10-Edge]														
LOADING (psf)	SPACING		2-0-0	CSI		DEFL			in	(loc)	l/defl	L/d	PLATES	GRIP
	Plates Increase		1.25	TC	0.55	Vert(LL)	-0.16	2-12	>999	240			MT20	244/190
	Lumber Increase		1.25	BC	0.54	Vert(TL)	-0.28	2-12	>999	180				
	Rep Stress Incr		YES	WB	0.38	Horz(TL)	0.06	9	n/a	n/a				
	Code FBC2004/TPI2002			(Matrix)									Weight: 139 lb	
TCLL	20.0													
TCDL	7.0													
BCLL	10.0													
BCDL	5.0													

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-3-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-11-8 oc bracing.
WEBS 1 Row at midpt 7-9


REACTIONS (lb/size) 9=1089/0-3-8, 2=1214/0-3-8
Max Horz 2=272(load case 5)
Max Uplift 9=396(load case 4), 2=442(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-1908/743, 3-4=-1670/641, 4-5=-1463/629, 5-6=-1403/557, 6-7=-1403/557, 7-8=-59/10, 8-9=-153/102
BOT CHORD 2-12=-809/1658, 11-12=-669/1549, 10-11=-669/1549, 9-10=-477/1095
WEBS 3-12=-236/204, 4-12=-66/449, 5-12=-113/162, 5-10=-278/213, 7-10=-150/581, 7-9=-1315/593

NOTES
1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Provide adequate drainage to prevent water ponding.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 396 lb uplift at joint 9 and 442 lb uplift at joint 2.

LOAD CASE(S) Standard

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549






Plate Offsets (X,Y): [2'-0"-1'-11",Edge]									
LOADING (psf)		SPACING		CSI		DEFL		PLATES	
TCCL	20.0	Plates Increase	2'-0"-0	TC	0.61	in	(loc)	L/d	GRIP
TCCL	7.0	Lumber Increase	1.25	BC	0.69	in	(loc)	L/d	244/190
BCCL	10.0	Rep Stress Incr	YES	WB	0.55	in	(loc)	L/d	
BCCL	5.0	Code FBC2004/TPI2002		(Matrix)		in	(loc)	L/d	
					Weight: 143 lb				

LUMBER		BRACING	
TOP CHORD	2 X 4 SYP No.2	TOP CHORD	Structural wood sheathing directly applied or 4'-0"-12' oc purlins, except end verticals.
BOT CHORD	2 X 4 SYP No.2	BOT CHORD	Rigid ceiling directly applied or 6'-10"-3' oc bracing.
WEBS	2 X 4 SYP No.3	WEBS	1 Row at midpt 5-7


REACTIONS (lb/size) 7=1089/0-3-8, 2=1214/0-3-8
Max Horz 2=318(load case 5)
Max Uplift7=388(load case 4), 2=450(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-1841/728, 3-4=-1526/585, 4-5=-1317/588, 5-6=-52/19, 6-7=-185/131
BOT CHORD 2-10=-836/1602, 9-10=-485/1118, 8-9=-485/1118, 7-8=-485/1118
WEBS 3-10=-329/279, 4-10=0/309, 5-10=-131/246, 5-8=0/202, 5-7=-1326/579

NOTES
1) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCCL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Provide adequate drainage to prevent water ponding.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 388 lb uplift at joint 7 and 450 lb uplift at joint 2.


LOAD CASE(S) Standard


OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549






OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549










Plate Offsets (X,Y): [2:0-4-1,0-0-5], [3:0-6-3,Edge], [7:0-2-12,0-3-4], [9:0-3-8,0-3-0], [15:0-3-8,0-2-8], [20:0-6-8,0-5-12]												
LOADING (psf)	SPACING		2-0-0	CSI	DEFL				PLATES	GRIP		
	Plates Increase 1.25				in (loc) l/defl L/d							
	Lumber Increase 1.25				TC 0.68							
	Rep Stress Incr NO				BC 0.76							
	Code FBC2004/TPI2002				WB 0.75							
TCLL 20.0				(Matrix)	Vert(LL) -1.01 17 >376 240						MT20	244/190
TCDL 7.0					Vert(TL) -1.61 17 >235 180						MT18H	244/190
BCLL 10.0					Horz(TL) 0.78 11 n/a n/a							
BCDL 5.0												
Weight: 447 lb												

LUMBER		BRACING	
TOP CHORD 2 X 4 SYP No.1D *Except*		TOP CHORD Structural wood sheathing directly applied or 3-0-8 oc purlins, except end verticals.	
T3 2 X 4 SYP No.2		BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.	
BOT CHORD 2 X 8 SYP 2400F 2.0E *Except*			
B3 2 X 8 SYP No.1D			
WEBS 2 X 4 SYP No.3 *Except*			
W8 2 X 4 SYP No.1D, W11 2 X 4 SYP No.2			

REACTIONS (lb/size) 2=2863/0-3-8, 11=3063/0-3-8
Max Horz 2=228(load case 4)
Max Uplift 2=1023(load case 4), 11=1222(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/52, 2-3=12552/4510, 3-4=12183/4495, 4-5=15102/5614, 5-6=16741/6264, 6-7=16132/6078, 7-22=12452/4729, 8-22=12452/4729, 8-9=10131/3872, 9-10=3283/1285, 10-11=2823/1187
BOT CHORD 2-20=4227/11590, 20-23=3949/10706, 19-23=3948/10703, 18-19=5417/14528, 17-18=6104/16242, 16-17=6289/16660, 16-24=5891/15536, 15-24=5891/15536, 13-15=65/514, 8-15=349/300, 13-14=0/0, 12-13=1043/2690, 11-12=48/83
WEBS 4-19=2623/1097, 4-18=399/1141, 5-18=1315/586, 5-17=237/657, 6-17=23/106, 6-16=609/243, 7-16=372/1185, 7-15=3315/1248, 12-15=271/664, 9-15=2745/7267, 9-12=3036/1370, 10-12=1593/4122, 3-19=1726/4669, 3-20=253/926

- NOTES**
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 400 lb down and 151 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 2-ply truss to be connected together with 0.131"x3" Nails as follows:
Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2 X 8 - 2 rows at 0-9-0 oc.
Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 400 lb down and 151 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1023 lb uplift at joint 2 and 1222 lb uplift at joint 11.
 - Girder carries tie-in span(s): 3-0-0 from 7-0-0 to 22-3-8; 7-0-0 from 7-0-0 to 22-3-8
 - Girder carries hip end with 0-0-0 right side setback, 22-3-8 left side setback, and 7-0-0 end setback.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 400 lb down and 151 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-22=69(F=-15), 10-22=118(F=64), 2-20=30, 20-23=30, 23-24=129(F=99), 15-24=65(F=35), 13-14=65(F=35), 11-13=65(F=35)


Continued on page 2

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



Job	Truss	Truss Type	Qty	Ply	BRYAN ZECHER- LOT30-1 CSE	Dwg.#101705139
L136745	T09	SPECIAL	1	2	Job Reference (optional)	J1481244
Builders FirstSource, Lake City, FL 32055			6.200 s Jul 13 2005 Mitek Industries, Inc. Fri Oct 14 14:13:32 2005 Page 2			
LOAD CASE(S) Standard Concentrated Loads (lb) Vert: 23=400(F)						

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



Job: L136745 Truss: T10 Truss Type: SPECIAL Qty: 1 Ply: 1 BRYAN ZECHER- LOT30-1 CSE Dwg.#101705140

Builders FirstSource, Lake City, FL 32055 6.200 s Jul 13 2005 MiTek Industries, Inc. Fri Oct 14 14:13:33 2005 Page 1

Job Reference (optional)

2-0-0 3-8-9 6-3-8 9-0-0 15-11-12 22-9-12 29-9-8 31-10-8
2-0-0 3-8-9 2-6-15 2-8-8 6-11-12 6-10-0 6-11-12 2-1-0

Scale = 1:57.6

Plate Offsets (X,Y): [2:0-4-1,0-0-11], [6:0-4-0,0-3-0], [7:0-3-3,Edge]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.90	Vert(LL)	-0.77	11	>494	240	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.98	Vert(TL)	-1.30	11	>292	180	MT18H	244/190
BCLL 10.0	Lumber Increase 1.25	WB 0.73	Horz(TL)	0.57	9	n/a	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)							
	Code FBC2004/TPI2002								

Weight: 203 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 6 SYP No.1D *Except*
WEBS B5 2 X 4 SYP No.3, B4 2 X 4 SYP No.2
2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-7-12 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing. Except:
WEBS 1 Row at midpt 12-13
JOINTS 1 Row at midpt 6-12
1 Brace at Jt(s): 12


REACTIONS (lb/size) 2=1468/0-3-8, 9=1456/0-3-8
Max Horz 2=241(load case 5)
Max Uplift 2=497(load case 5), 9=399(load case 3)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/49, 2-3=6098/2395, 3-4=3985/1610, 4-5=4389/1736, 5-6=4389/1736, 6-7=1336/427, 7-8=1410/381, 8-9=1685/449
BOT CHORD 2-17=2317/5634, 16-17=-2144/5162, 15-16=-1452/3636, 14-15=-1357/3705, 13-14=-1357/3705, 12-13=-1357/3703, 10-12=0/319, 7-12=0/347, 10-11=0/0, 9-10=-118/0
WEBS 3-17=530/1518, 3-16=-1739/782, 4-16=431/1182, 4-15=-395/948, 5-15=-367/271, 6-15=350/734, 6-13=0/208, 6-12=-2514/1038, 8-12=-428/1661, 9-12=0/158

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 497 lb uplift at joint 2 and 399 lb uplift at joint 9.

LOAD CASE(S) Standard

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549








Plate Offsets (X,Y): [4:0-1-12,0-3-0], [8:0-3-0,0-3-0], [10:0-3-5,0-0-11], [12:0-3-8,0-1-8]									
LOADING (psf)		SPACING		CSI		DEFL		PLATES	
TCLL	20.0	Plates Increase	2-0-0	TC	0.33	in	(loc)	L/defl	L/d
TCDL	7.0	Lumber Increase	1.25	BC	0.84	Vert(LL)	-0.57	17	>686
BCLL	10.0	Rep Stress Incr	YES	WB	0.78	Vert(TL)	-0.97	17	>403
BCDL	5.0	Code FBC2004/TPI2002		(Matrix)		Horz(TL)	0.15	10	n/a
								Weight: 233 lb	

LUMBER		BRACING	
TOP CHORD	2 X 4 SYP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-2-0 oc purlins.
BOT CHORD	2 X 4 SYP No.2 "Except"	BOT CHORD	Rigid ceiling directly applied or 4-0-9 oc bracing.
WEBS	B2 2 X 4 SYP No.3, B6 2 X 4 SYP No.3	WEBS	1 Row at midpt 8-18
	2 X 4 SYP No.3	JOINTS	1 Brace at Jt(s): 15, 16


REACTIONS (lb/size) 2=329/0-3-8, 23=1715/0-3-8, 10=1545/0-3-8
Max Horz 2=157(load case 5)
Max Uplift 2=279(load case 5), 23=576(load case 5), 10=576(load case 6)
Max Grav 2=340(load case 9), 23=1715(load case 1), 10=1545(load case 1)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-58/277, 3-4=-1855/798, 4-5=-1745/799, 5-6=-1847/800, 6-7=-1815/842, 7-8=-2096/861, 8-9=-3681/1292, 9-10=-2681/1018, 10-11=0/47
BOT CHORD 2-23=-33/0, 22-23=-1623/603, 3-22=-1551/609, 21-22=-126/85, 20-21=-417/1610, 19-20=-417/1610, 18-19=-272/1588, 16-18=-887/3296, 15-16=-883/3317, 13-15=-100/50, 8-15=-211/1137, 14-17=0/0, 13-14=0/0, 12-13=-94/77, 10-12=-737/2319
WEBS 3-21=-517/1787, 5-21=-265/166, 5-19=-99/166, 6-19=-49/203, 6-18=-129/503, 7-18=-154/598, 8-18=-1662/625, 12-15=-701/2446, 9-15=-131/929, 9-12=-826/327, 14-16=-7/345


- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - Provide adequate drainage to prevent water ponding.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 279 lb uplift at joint 2, 576 lb uplift at joint 23 and 576 lb uplift at joint 10.

LOAD CASE(S) Standard

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549







Job

L136745

Truss

T16

Truss Type

SPECIAL

Qty

1

Ply

1

BRYAN ZECHER- LOT30-1 CSE

Dwg.#101705146

Job Reference (optional)

6.200 s Jul 13 2005 Mitek Industries, Inc. Fri Oct 14 14:13:38 2005 Page 1

Builders FirstSource, Lake City, FL 32055

-2-0-0

6-3-8

14-0-3

19-4-12

24-7-7

28-2-8

33-2-12

38-9-8

40-9-8

2-0-0

6-3-8

7-8-11

5-4-9

5-2-12


3-7-1




5-0-4

5-6-12

2-0-0

Scale = 1/11.0





LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	Plates Increase 2-0-0	TC 0.43	in (loc) l/def L/d	MT20	244/190
TCCL 7.0	Lumber Increase 1.25	BC 0.81	Vert(LL) 0.16 10-12 >559 240		
BCCL 10.0	Rep Stress Incr YES	WB 0.38	Vert(TL) -0.56 13-14 >532 180		
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)	Horz(TL) 0.03 10 n/a n/a		
				Weight: 201 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	TOP CHORD Structural wood sheathing directly applied or 4-11-14 oc purlins.
BOT CHORD 2 X 4 SYP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 4-3-1 oc bracing.
B2 2 X 4 SYP No.3, B5 2 X 4 SYP No.3	WEBS 1 Row at midpt 7-13
WEBS 2 X 4 SYP No.3	

REACTIONS (lb/size) 2=355/0-3-8, 18=1306/0-3-8, 12=1414/0-3-8, 10=391/0-3-8
Max Horz 2=174(load case 5)
Max Uplift 2=287(load case 6), 18=536(load case 5), 12=464(load case 6), 10=413(load case 6)
Max Grav 2=355(load case 1), 18=1306(load case 1), 12=1414(load case 1), 10=391(load case 10)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/47, 2-3=-96/320, 3-4=-1354/663, 4-5=-1250/677, 5-6=-1023/613, 6-7=-1017/608, 7-8=-123/432, 8-9=-206/410, 9-10=-85/306, 10-11=0/47
BOT CHORD 2-18=-54/27, 17-18=-1209/499, 3-17=-1073/523, 16-17=-133/286, 15-16=-273/1120, 14-15=-273/1120, 13-14=-210/899, 12-13=-1283/492, 9-13=-472/376, 10-12=-92/2
WEBS 3-16=-156/842, 5-16=0/71, 5-14=-402/310, 6-14=-333/580, 7-14=-123/254, 7-13=-1010/248

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
3) All plates are 3x6 MT20 unless otherwise indicated.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 287 lb uplift at joint 2, 536 lb uplift at joint 18, 464 lb uplift at joint 12 and 413 lb uplift at joint 10.

LOAD CASE(S) Standard

OCTOBER 17, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job

L136745

Truss

T18

Truss Type

COMMON

Qty

7

Ply

1

BRYAN ZECHER- LOT30-1 CSE

Dwg.#101705148

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Fri Oct 14 14:13:39 2005 Page 1

-2-0-0

2-0-0

5-9-8

5-9-8

11-7-0

5-9-8

13-7-0

2-0-0

Scale = 1:25.0

1

2

3

4

5

0.00 (12)

0.00 (12)

0.00 (12)

0.00 (12)

3x6 =

3x6 =

4x6 =

3x6 =

W1

B1

6' 2x4 II

5-9-8

11-7-0

5-9-8

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.29	Vert(LL) -0.03 2-6 >999 240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.21	Vert(TL) -0.05 2-6 >999 180		
BCLL 10.0	Rep Stress Incr YES	WB 0.06	Horz(TL) 0.01 4 n/a n/a		
BCDL 5.0	Code FBC2004/TPI2002	(Matrix)			
				Weight: 47 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2

BOT CHORD 2 X 4 SYP No.2

WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=590/0-3-8, 4=590/0-3-8

Max Horz 2=-79(load case 6)

Max Uplift 2=-284(load case 5), 4=-284(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/47, 2-3=-630/247, 3-4=-630/247, 4-5=0/47

BOT CHORD 2-6=-66/501, 4-6=-66/501

WEBS 3-6=0/193

NOTES

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-02; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.

3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 284 lb uplift at joint 2 and 284 lb uplift at joint 4.

LOAD CASE(S) Standard

OCTOBER 17,2005 TRUSS DESIGN ENGINEER:

THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987


STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196

16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




Symbols

PLATE LOCATION AND ORIENTATION



* Center plate on joint unless dimensions indicate otherwise. Dimensions are in inches. Apply plates to both sides of truss and secure seal.



* For 4 x 2 orientation, locate plates 1/8" from outside edge of truss and vertical web.



* This symbol indicates the required direction of slots in connector plates.

PLATE SIZE

4 X 4


The first dimension is the width perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING




Indicates location of required continuous lateral bracing.

BEARING



Indicates location of joints at which bearings (supports) occur.

Numbering System



JOINTS AND CHORDS ARE NUMBERED CLOCKWISE AROUND THE TRUSS STARTING AT THE LOWEST JOINT FARTHEST TO THE LEFT.

WEBS ARE NUMBERED FROM LEFT TO RIGHT

CONNECTOR PLATE CODE APPROVALS

BOCA	96-31, 96-67
ICBO	3907, 4922
SBCCI	9667, 9432A
WISC/DILLHR	960022-W, 970036-N
NER	561



Mitek Engineering Reference Sheet: MIT-7473




General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
2. Cut members to bear tightly against each other.
3. Place plates on each face of truss at each joint and embed fully. Avoid knots and wane at joint locations.
4. Unless otherwise noted, locate chord splices at 1/4 panel length (± 6" from adjacent joint.)
5. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
6. Unless expressly noted, this design is not applicable for use with fire retardant or preservative treated lumber.
7. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
8. Plate type, size and location dimensions shown indicate minimum plating requirements.
9. Lumber shall be of the species and size, and in all respects, equal to or better than the grade specified.
10. Top chords must be sheathed or purlins provided at spacing shown on design.
11. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
12. Anchorage and / or load transferring connections to trusses are the responsibility of others unless shown.
13. Do not overload roof or floor trusses with stacks of construction materials.
14. Do not cut or alter truss member or plate without prior approval of a professional engineer.
15. Care should be exercised in handling, erection and installation of trusses.

© 1993 MITek® Holdings, Inc.



Residential System Sizing Calculation

Model Home

Summary
Project Title:
TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North


11/3/2005

Location for weather data: Gainesville - Defaults: Latitude(29) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(51gr.)			
Winter design temperature	31 F	Summer design temperature	93 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	39 F	Summer temperature difference	18 F
Total heating load calculation		Total cooling load calculation	
29218 Btuh		27764 Btuh	
% of calc	Btuh	% of calc	Btuh
Submitted heating capacity	116.4	Submitted cooling capacity	125.6
Total (Electric Heat Pump)	34000	Sensible (SHR = 0.75)	25500
Heat Pump + Auxiliary(0.0kW)	116.4	Latent	8500
	34000	Total (Electric Heat Pump)	34000

WINTER CALCULATIONS

Winter Heating Load (for 1500 sqft)


Load component			
Window total	215	sqft	6085
Wall total	1293	sqft	3750
Door total	60	sqft	921
Ceiling total	1754	sqft	2280
Floor total	196	ft	6194
Infiltration	200	cfm	8597
Subtotal			27827
Duct loss			1391
TOTAL HEAT LOSS			29218



SUMMER CALCULATIONS

Summer Cooling Load (for 1500 sqft)

Load component			
Window total	215	sqft	6757
Wall total	1293	sqft	2129
Door total	60	sqft	608
Ceiling total	1754	sqft	2491
Floor total			0
Infiltration	175	cfm	3472
Internal gain			3000
Subtotal(sensible)			18457
Duct gain			1846
Total sensible gain			20303
Latent gain(infiltration)			6081
Latent gain(internal)			1380
Total latent gain			7461
TOTAL HEAT GAIN			27764



EnergyGauge® System Sizing based on ACCA Manual J.
PREPARED BY:
DATE: 11/3/05

System Sizing Calculations - Winter

Residential Load - Component Details

Model Home

Project Title:
TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults) Winter Temperature Difference: 39.0 F
11/3/2005

Window	Panes/SHGC/Frame/U	Orientation	Area X	HTM=	Load
1	2, Clear, Metal, DEF	N	45.0	28.3	1274 Btuh
2	2, Clear, Metal, DEF	NE	10.0	28.3	283 Btuh
3	2, Clear, Metal, DEF	N	45.0	28.3	1274 Btuh
4	2, Clear, Metal, DEF	NW	10.0	28.3	283 Btuh
5	2, Clear, Metal, DEF	E	3.0	28.3	85 Btuh
6	2, Clear, Metal, DEF	S	6.0	28.3	170 Btuh
7	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
8	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
9	2, Clear, Metal, DEF	W	6.0	28.3	170 Btuh
10	2, Clear, Metal, DEF	W	30.0	28.3	849 Btuh
Window Total					
215					
Type R-Value Area X HTM=					
Frame - Adjacent 13.0 172 1.6					
Frame - Exterior 13.0 1121 3.1					
Wall Total					
1293					
Type R-Value Area X HTM=					
Insulated - Exterior 18.3 20 18.3					
Insulated - Exterior 18.3 20 18.3					
Insulated - Adjac 9.4					
Door Total					
60					
Type R-Value Area X HTM=					
Under Attic 30.0 1754 1.3					
Ceiling Total					
1754					
Type R-Value Size X HTM=					
Slab-On-Grade Edge Insul 0 196.0 ft(p) 31.6					
Floor Total					
196					
Type R-Value Size X HTM=					
ACH X Building Volume 0.80 15000(sqft) 200					
Natural Mechanical Infiltration Total					
0 200					
Load					
8597 Btuh					

Totals for Heating		
Subtotal	Duct Loss(using duct multiplier of 0.05)	27827 Btuh
		1391 Btuh
		29218 Btuh

Model Home

Project Title:
TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

11/3/2005

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(Frame types - metal, wood or insulated metal)


(U - Window U-Factor or 'DEF' for default)

(HTM - Manual Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

Manual J Winter Calculations

Residential Load - Component Details (continued)



System Sizing Calculations - Summer

Residential Load - Component Details

Model Home

Project Title:

TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

Reference City: Gainesville (Defaults) Summer Temperature Difference: 18.0 F

11/3/2005

Window		Type	Overhang	Window Area(sqft)	HTM	Load
10	2, Clear, DEF, N, N	N	1.5	45.0	22	990 Btuh
	2, Clear, DEF, N, N	NE	14	10.0	22	990 Btuh
	2, Clear, DEF, N, N	N	11.5	45.0	22	500 Btuh
	2, Clear, DEF, N, N	NW	8	10.0	22	990 Btuh
	2, Clear, DEF, N, N	E	1.5	3.0	22	500 Btuh
	2, Clear, DEF, N, N	S	9	6.0	22	92 Btuh
	2, Clear, DEF, N, N	S	1.5	0.0	22	132 Btuh
	2, Clear, DEF, N, N	S	1.5	0.0	22	660 Btuh
	2, Clear, DEF, N, N	S	1.5	0.0	22	660 Btuh
	2, Clear, DEF, N, N	W	1.5	6.0	22	408 Btuh
9	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
8	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
7	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
6	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
5	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
4	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
3	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
2	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
1	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
	2, Clear, DEF, N, N	W	1.5	30.0	22	1825 Btuh
Window Total		215		215		6757 Btuh
Type		R-Value		Area		Load
Frame - Adjacent		13.0		172.0		179 Btuh
Frame - Exterior		13.0		1121.0		1951 Btuh
Wall Total		1293.0		1293.0		2129 Btuh
Doors	Type	Area		HTM		Load
	Insulated - Exterior	20.0		10.1		203 Btuh
	Insulated - Exterior	20.0		10.1		203 Btuh
	Insulated - Adjac	20.0		10.1		203 Btuh
Door Total		60.0		60.0		608 Btuh
Ceilings	Type/Color	R-Value		Area		Load
	Under Attic/Dark	30.0		1754.0		2491 Btuh
Ceiling Total		1754.0		1.4		2491 Btuh
Floors	Type	R-Value		Size		Load
	Slab-On-Grade Edge Insulation	0.0		196.0 ft(p)		0 Btuh
Floor Total		196.0		HTM		0 Btuh
Infiltration	Type	ACH		Volume		Load
	Natural	0.70		15000		3472 Btuh
Mechanical		CFM=		175.4		0 Btuh
Infiltration Total		175		175		3472 Btuh
Internal gain		Occupants		Btuh/occupant		Load
		6		X 300 +		3000 Btuh
		Appliance		1200		1200 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Model Home


Project Title:
The Samuel Model

Class 3 Rating
Registration No. 0
Climate: North

11/3/2005

Totals for Cooling		Subtotal	18457 Btuh
Duct gain (using duct multiplier of 0.10)		1846 Btuh	
Total sensible gain		20303 Btuh	
Latent infiltration gain (for 51 gr. humidity difference)		6081 Btuh	
Latent occupant gain (6 people @ 230 Btuh per person)		1380 Btuh	
Latent other gain		0 Btuh	
TOTAL GAIN		27764 Btuh	

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds/Drapes(B) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(Ornt - compass orientation)



WOODFORD PLYWOOD, INC.
"Structural Wood Products"

Distributed by:

11950 West Beaver Street
Jacksonville, Florida 32220
(904) 685-9080
(800) 447-6566
FAX (904) 685-9160

Power Header® is a trademark of
Anthony Forest Products Company
Post Office Box 1877 • El Dorado, Arkansas 71731
Internet address: <http://www.anthonyforest.com>
e-mail: info@anthonyforest.com
© 2001 Anthony Forest Products Company

For more information on Power Header®,
or other laminated structural products from
Anthony Forest Products Company please call
1-800-221-2326 or FAX at 870-862-6502.

900 / 600	3-1/2" x 16-3/4"	3-1/2" x 17-7/8"	3-1/2" x 18"	3-1/2" x 16"	3-1/2" x 18"
750 / 480	3-1/2" x 15-1/8"	3-1/2" x 16-1/2"	3-1/2" x 16-1/2"	3-1/2" x 16"	3-1/2" x 18"
765 / 510	3-1/2" x 14"	3-1/2" x 15-1/8"	3-1/2" x 15"	3-1/2" x 14"	3-1/2" x 16"
640 / 400	3-1/2" x 12-5/8"	3-1/2" x 13-3/4"	3-1/2" x 13-1/2"	3-1/2" x 14"	3-1/2" x 14"
990 / 720	3-1/2" x 9-3/4"	3-1/2" x 9-5/8"	3-1/2" x 10-1/2"	3-1/2" x 9-1/4"	3-1/2" x 11-1/4"
810 / 540	3-1/2" x 8-1/8"	3-1/2" x 9-5/8"	3-1/2" x 9"	3-1/2" x 9-1/4"	3-1/2" x 11-1/4"

GARAGE HEADER COMPARISONS

- NOTES:
1. Beam weights are based on 38 pcf.
 2. Moment capacities are based on a span of 21 feet and must be modified for other spans.
 3. Flexural Stress, F_b , shall be modified by the Volume Factor, C_v , as outlined in ATC 117 - Design 1993 and the NDS for Wood Construction 1997.
 4. Allowable design properties and load capacities are based on a load duration of 100 percent and dry use conditions.
 5. The ATC NER 466 was used in calculating the above allowable design stresses for Power Header®.

3908	4550	5250	5892	6533	7175	7817
8865	12015	15996	20145	24772	29877	35460
326	514	789	1115	1521	2014	2604
7.7	9.0	10.4	11.7	12.9	14.2	15.5

ENGINEERED WOOD SECTION PROPERTIES AND LOAD CAPACITIES
ALLOWABLE DESIGN STRESSES (PSI):

FLEXURAL STRESS (F_b) =
COMPRESSION PERP. TO GRAIN ($F_{c\perp}$) =
HORIZONTAL SHEAR (F_v) =
MODULUS OF ELASTICITY (MOE) =

2600
740
225
 1.9×10^6

Anthony POWER HEADER®

GARAGE HEADER
26F_b - 1.9E

To size a garage header supporting roof only, determine the total load & live load in pounds per lineal foot (PLF). Check the appropriate PLF table for a header supporting roof loads only (125% Non-Snow vs. 115% Snow) and select a member with a total load and live load capacity which meets or exceeds the design load for the rough opening size. For a garage header supporting roof, wall, and floor framing, determine the total load and live load in pounds per lineal foot (PLF). Select a header size from the roof, wall, and floor table (100% load duration) which has a total load and live load capacity equal to or greater than the design load for the appropriate rough opening.

GARAGE HEADER SIZING USING PLF TABLES:

1. Values shown are the maximum uniform loads in pounds per lineal foot (PLF) that can be applied to the header. Header weight has been subtracted from the allowable total load.
2. Tables are based on simple span uniform load conditions using a design span equal to the center-to-center of bearing. Non-shaded areas are based on 3" of bearing at each support, shaded areas on 4.5" of bearing, and shaded & outlined areas on 6" of bearing at supports.
3. Headers are assumed to be loaded on the top edge with continuous lateral support along compression edge.
4. When no live load is listed, total load controls.
5. Deflection limits are listed within the PLF table heading.

3-1/2" WIDTH GARAGE HEADER PLF CAPACITY									
562	778	888	1056	1363	1582				
107	153	169	245	260	380	268	540	501	715
76	107	120	171	185	267	261	380	356	521


3-1/2" WIDTH GARAGE HEADER PLF CAPACITY									
844	975	1322							
161	207	254	330	390	510	552	724	752	897
114	145	180	231	277	359	391	510	534	699

3-1/2" WIDTH GARAGE HEADER PLF CAPACITY									
844	896	1216	1573						
161	207	254	330	390	510	552	669	752	824
114	145	180	231	277	359	391	510	534	653


3-1/2" WIDTH GARAGE HEADER PLF CAPACITY

Anthony Power Header

26F_b - 1.9E



*This glass list may also be used in the following door styles: 5-Panel, 5-Panel with Screen, Elevation 5-Panel, Elevation 5-Panel with Screen



APPROVED DOOR STYLES
1/4 GLASS:

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed - see M-01-VL-WA0002-00 for

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed - see M-01-VL-WA0002-00 for

DO NOT EXCEED DOOR WEIGHT OF 150 LBS. (68 KG.)
DO NOT EXCEED DOOR HEIGHT OF 8'0" (244 CM.)

Hurricane protective system (shutters) is REQUIRED


Large Missile Impact Resistance

+40.5/-40.5

Design Pressure

Minimum and Max. = 6'0" x 5'0"

Double Door



Note:
Units of other sizes are covered by this
report as long as the panels used do not
exceed 3'0" x 6'8".

APPROVED ARRANGEMENT:

WOOD-EDGE STEEL DOORS

XX
Glazed Inswing Unit

COP-WL-JH4142-02




Test Data Review Certificate #J025417A
and CCR/TEST REPORT VERIFICATION MAINT
#J025417A-001 provides additional
information - available from the ILSWH
website (www.masonite.com). The
website website (www.masonite.com)
or the Masonite Technical Center

2

[illegible]


PRODUCT COMPLIANCE LABELING:

CERTIFIED TEST REPORTS:



WOOD-EDGE STEEL DOORS

COP-WL-JH4142-02



APPROVED DOOR STYLES:

MINIMUM INSTALLATION DETAIL:

Compliance requires that information systems have been reviewed - 2000-2001

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum standards have been followed - 2007-2008

THE INFORMATION CONTAINED HEREIN IS UNCLASSIFIED DATE 08-11-2010 BY 60322 UCBAW/BJS/STP

Hurricane protective system (shutters) is NOT REQUIRED.

Large Missile Impact Resistance


 $0.99- / 0.99+$

Design Pressure

553-01 = SITE DATA WORKSHEET

Single Door

Note:
Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".



APPROVED ARRANGEMENT:

WOOD-EDGE STEEL DOORS

Opaque Inswing Unit

X

COP-WL-JH4101-02



Let Us Review Certificate #J02647A
and COR/First Respond Validation Matrix
#J02647A-001 provides additional
information - available how do IIS/WN
website (www.fda.gov/oc/), the
MAGNUS (www.magnus.com)
of the National Technical

WOOD-EDGE STEEL DOORS

X
Opaque Inswing Unit

COP-WL-JH4101-02

CERTIFIED TEST REPORTS:

NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA201, PA202 and PA203.

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN ACCORDANCE WITH
MIAMI-DADE BCCO
PA201, PA202 & PA203
COMPANY NAME
CITY STATE


To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Ballhazor, P.E. - License Number 56533

Kurt Ballhazor

Test Data Review Certificate #3026417A
and COP/Unit Report Miami
#3026417A-001 provided according
to Miami-Dade BCCO PA201, PA202
and PA203 (www.miamidade.com). The
Miami-Dade Building Department
of the National Technical Center.





WINDOWS



AA1A/NWDA 101/L.S.2-97
TEST REPORT SUMMARY

Rendered to:

MH HOME PRODUCTS, INC.

SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess

Mark A. Hess, Technician

MAH:mjb



Architectural Testing



AAMA/NWDA 101/S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Graft, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contacted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethtown, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWDA 101/S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.*

Test Specimen Description

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl gasket. The fixed lite was interior glazed utilizing a flexible vinyl wrap around spacer system. The active sash was channel glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4125
www.architest.com

1 APRIL 2002

ALL TESTS PASSED



Test Specimen Description: (Continued)

Weatherstripping:

Description	Quantity	Location
0.230" high by 0.270" backed polypropylene with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypropylene with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail


Frame Construction: The frame was constructed of extruded aluminum with capped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.


Sash Construction: The sash was constructed of extruded aluminum with capped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock with keeper	2	Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail





Test Specimen Description: (Continued)

Weatherstripping:

Description	Quantity	Location
0.230" high by 0.270" backed polypropylene with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypropylene with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail


Frame Construction: The frame was constructed of extruded aluminum with capped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.


Sash Construction: The sash was constructed of extruded aluminum with capped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock with keeper	2	Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail





Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

Paragraph	Title of Test - Test Method	Results	Allowed
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
Air Infiltration (ASTM E 283-91)			
	@ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max

Note #1: The tested specimen meets the performance levels specified in ASTM E 283-91.

Water Resistance (ASTM E 541-00)
(with and without screen)
WTP = 2.86 psf

No leakage

No leakage

2.1.4.1

Uniform Load Deflection (ASTM E 330-97)
(Measurements reported were taken on the meeting rail)
(Loads were held for 33 seconds)
@ 25.9 psf (positive) 0.42"
@ 34.7 psf (negative) 0.43"

0.26" max.

0.26" max.

*Exceeds L/175 for deflection, but passes all other test requirements.

2.1.4.2

Uniform Load Structural (ASTM E 330-97)
(Measurements reported were taken on the meeting rail)
(Loads were held for 10 seconds)
@ 38.9 psf (positive) 0.02"
@ 52.1 psf (negative) 0.02"

0.18" max.

0.18" max.



Allen H. Reys
1 APRIL 2012

Test Specimen Description: (Continued)

Paragraph	Title of Test - Test Method	Results	Allowed
-----------	-----------------------------	---------	---------


2.2.1.6.2	Deglazing Test (ASTM E 987)	In operating direction at 70 lbs	
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
Forced Entry Resistance (ASTM F 588-97)			
	Type: A		
	Grade: 10		

Lock Manipulation Test:	No entry	No entry
Tests A1 through A5	No entry	No entry
Test A7	No entry	No entry
Lock Manipulation Test:	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00)	(with and without screen)	WTP = 6.00 psf	No leakage
	Uniform Load Deflection (ASTM E 330-97)	(Measurements reported were taken on the meeting rail)	(Loads were held for 33 seconds)	0.47" max
			@ 45.0 psf (positive)	0.26" max
			@ 47.2 psf (negative)	0.26" max
*Exceeds L/175 for deflection, but passes all other test requirements.				

Uniform Load Structural (ASTM E 330-97)	(Measurements reported were taken on the meeting rail)	(Loads were held for 10 seconds)	@ 67.5 psf (positive)	0.05"
			@ 70.8 psf (negative)	0.05"





MLA-H:nb
01-41134.01

Mark A. Hess
Technician

Allen H. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002

For ARCHITECTURAL TESTING, INC:

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

SHINGLES



March 6, 2002

Subject: Elk Product Approval Information

All Prestique® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami - Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:
ASTM D3462
PA 100 (110 mph uplift and wind driven rain resistance)
PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestique and Capstone products are listed below. Also listed below are the Miami - Dade Notice of Acceptance Numbers (NOA).

Related Profile, Prestique High Definition, Prestique 25, or Prestique 30 -
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226 04

Prestique 15 or Prestique 1" -
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226 05



Prestique Plus or Prestique Gallery Collection -
PA 100 = 4 nails
PA 107 = 4 nails
MD NOA# = 01-1226 03

Capstone®
PA 100 = 4 Nails
PA 107 = 4 Nails
MD NOA# = 01-0523 01

* As per the Elk Limited Warranty, six nails are required for the Elk High Wind Warranty.
If there are any questions please contact:

Mike Reed - Technical Manager or Daniel Delorme - QA Engineer
(205) 342-0287
(205) 342-0298

[Faint handwritten notes at the bottom of the page]



www.elkcorp.com

1. The first step in the process of the investigation is the identification of the problem. This is done by the investigator who is responsible for the investigation. The investigator must identify the problem and the scope of the investigation.

2. The second step is the collection of data. This is done by the investigator who is responsible for the investigation. The investigator must collect data from the sources available to him.

3. The third step is the analysis of the data. This is done by the investigator who is responsible for the investigation. The investigator must analyze the data and determine the cause of the problem.

4. The fourth step is the development of a solution. This is done by the investigator who is responsible for the investigation. The investigator must develop a solution to the problem.

5. The fifth step is the implementation of the solution. This is done by the investigator who is responsible for the investigation. The investigator must implement the solution and monitor the results.

6. The sixth step is the evaluation of the results. This is done by the investigator who is responsible for the investigation. The investigator must evaluate the results and determine if the solution was effective.

7. The seventh step is the reporting of the results. This is done by the investigator who is responsible for the investigation. The investigator must report the results to the appropriate authorities.

8. The eighth step is the follow-up. This is done by the investigator who is responsible for the investigation. The investigator must follow-up on the results and determine if the problem has been resolved.

9. The ninth step is the documentation of the results. This is done by the investigator who is responsible for the investigation. The investigator must document the results and make them available to the appropriate authorities.

10. The tenth step is the conclusion. This is done by the investigator who is responsible for the investigation. The investigator must conclude the investigation and determine if the problem has been resolved.

[illegible][illegible]

[illegible]

1. The first part of the document is a list of names and addresses, which are arranged in a columnar format. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The list includes names such as "John Doe", "Jane Smith", and "Robert Johnson", along with their respective addresses.

2. The second part of the document is a table with two columns. The first column contains names, and the second column contains addresses. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The table lists several individuals and their corresponding addresses.

3. The third part of the document is a list of names and addresses, which are arranged in a columnar format. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The list includes names such as "John Doe", "Jane Smith", and "Robert Johnson", along with their respective addresses.

4. The fourth part of the document is a table with two columns. The first column contains names, and the second column contains addresses. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The table lists several individuals and their corresponding addresses.

5. The fifth part of the document is a list of names and addresses, which are arranged in a columnar format. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The list includes names such as "John Doe", "Jane Smith", and "Robert Johnson", along with their respective addresses.

6. The sixth part of the document is a table with two columns. The first column contains names, and the second column contains addresses. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The table lists several individuals and their corresponding addresses.

7. The seventh part of the document is a list of names and addresses, which are arranged in a columnar format. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The list includes names such as "John Doe", "Jane Smith", and "Robert Johnson", along with their respective addresses.

8. The eighth part of the document is a table with two columns. The first column contains names, and the second column contains addresses. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The table lists several individuals and their corresponding addresses.

9. The ninth part of the document is a list of names and addresses, which are arranged in a columnar format. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The list includes names such as "John Doe", "Jane Smith", and "Robert Johnson", along with their respective addresses.

10. The tenth part of the document is a table with two columns. The first column contains names, and the second column contains addresses. The names are written in a cursive script, and the addresses are written in a more formal, printed style. The table lists several individuals and their corresponding addresses.

DATE	DESCRIPTION	AMOUNT	CHECK NO.	BANK
10/1/78	DEPOSIT	100.00		WELLS FARGO
10/2/78	DEPOSIT	200.00		WELLS FARGO
10/3/78	DEPOSIT	150.00		WELLS FARGO
10/4/78	DEPOSIT	300.00		WELLS FARGO
10/5/78	DEPOSIT	100.00		WELLS FARGO
10/6/78	DEPOSIT	250.00		WELLS FARGO
10/7/78	DEPOSIT	180.00		WELLS FARGO
10/8/78	DEPOSIT	120.00		WELLS FARGO
10/9/78	DEPOSIT	220.00		WELLS FARGO
10/10/78	DEPOSIT	160.00		WELLS FARGO
10/11/78	DEPOSIT	280.00		WELLS FARGO
10/12/78	DEPOSIT	140.00		WELLS FARGO
10/13/78	DEPOSIT	210.00		WELLS FARGO
10/14/78	DEPOSIT	190.00		WELLS FARGO
10/15/78	DEPOSIT	230.00		WELLS FARGO
10/16/78	DEPOSIT	170.00		WELLS FARGO
10/17/78	DEPOSIT	260.00		WELLS FARGO
10/18/78	DEPOSIT	130.00		WELLS FARGO
10/19/78	DEPOSIT	240.00		WELLS FARGO
10/20/78	DEPOSIT	110.00		WELLS FARGO
10/21/78	DEPOSIT	270.00		WELLS FARGO
10/22/78	DEPOSIT	150.00		WELLS FARGO
10/23/78	DEPOSIT	290.00		WELLS FARGO
10/24/78	DEPOSIT	120.00		WELLS FARGO
10/25/78	DEPOSIT	200.00		WELLS FARGO
10/26/78	DEPOSIT	180.00		WELLS FARGO
10/27/78	DEPOSIT	220.00		WELLS FARGO
10/28/78	DEPOSIT	160.00		WELLS FARGO
10/29/78	DEPOSIT	280.00		WELLS FARGO
10/30/78	DEPOSIT	140.00		WELLS FARGO
10/31/78	DEPOSIT	210.00		WELLS FARGO
11/1/78	DEPOSIT	190.00		WELLS FARGO
11/2/78	DEPOSIT	230.00		WELLS FARGO
11/3/78	DEPOSIT	170.00		WELLS FARGO
11/4/78	DEPOSIT	260.00		WELLS FARGO
11/5/78	DEPOSIT	130.00		WELLS FARGO
11/6/78	DEPOSIT	240.00		WELLS FARGO
11/7/78	DEPOSIT	110.00		WELLS FARGO
11/8/78	DEPOSIT	270.00		WELLS FARGO
11/9/78	DEPOSIT	150.00		WELLS FARGO
11/10/78	DEPOSIT	290.00		WELLS FARGO
11/11/78	DEPOSIT	120.00		WELLS FARGO
11/12/78	DEPOSIT	200.00		WELLS FARGO
11/13/78	DEPOSIT	180.00		WELLS FARGO
11/14/78	DEPOSIT	220.00		WELLS FARGO
11/15/78	DEPOSIT	160.00		WELLS FARGO
11/16/78	DEPOSIT	280.00		WELLS FARGO
11/17/78	DEPOSIT	140.00		WELLS FARGO
11/18/78	DEPOSIT	210.00		WELLS FARGO
11/19/78	DEPOSIT	190.00		WELLS FARGO
11/20/78	DEPOSIT	230.00		WELLS FARGO
11/21/78	DEPOSIT	170.00		WELLS FARGO
11/22/78	DEPOSIT	260.00		WELLS FARGO
11/23/78	DEPOSIT	130.00		WELLS FARGO
11/24/78	DEPOSIT	240.00		WELLS FARGO
11/25/78	DEPOSIT	110.00		WELLS FARGO
11/26/78	DEPOSIT	270.00		WELLS FARGO
11/27/78	DEPOSIT	150.00		WELLS FARGO
11/28/78	DEPOSIT	290.00		WELLS FARGO
11/29/78	DEPOSIT	120.00		WELLS FARGO
11/30/78	DEPOSIT	200.00		WELLS FARGO
12/1/78	DEPOSIT	180.00		WELLS FARGO
12/2/78	DEPOSIT	220.00		WELLS FARGO
12/3/78	DEPOSIT	160.00		WELLS FARGO
12/4/78	DEPOSIT	280.00		WELLS FARGO
12/5/78	DEPOSIT	140.00		WELLS FARGO
12/6/78	DEPOSIT	210.00		WELLS FARGO
12/7/78	DEPOSIT	190.00		WELLS FARGO
12/8/78	DEPOSIT	230.00		WELLS FARGO
12/9/78	DEPOSIT	170.00		WELLS FARGO

[illegible]

מס' תעודת זהות	שם	תאריך	מס' תעודת זהות	שם	תאריך
15	מ. ל. גולד	1950	15	מ. ל. גולד	1950
16	מ. ל. גולד	1950	16	מ. ל. גולד	1950
17	מ. ל. גולד	1950	17	מ. ל. גולד	1950
18	מ. ל. גולד	1950	18	מ. ל. גולד	1950
19	מ. ל. גולד	1950	19	מ. ל. גולד	1950
20	מ. ל. גולד	1950	20	מ. ל. גולד	1950
21	מ. ל. גולד	1950	21	מ. ל. גולד	1950
22	מ. ל. גולד	1950	22	מ. ל. גולד	1950
23	מ. ל. גולד	1950	23	מ. ל. גולד	1950
24	מ. ל. גולד	1950	24	מ. ל. גולד	1950
25	מ. ל. גולד	1950	25	מ. ל. גולד	1950
26	מ. ל. גולד	1950	26	מ. ל. גולד	1950
27	מ. ל. גולד	1950	27	מ. ל. גולד	1950
28	מ. ל. גולד	1950	28	מ. ל. גולד	1950
29	מ. ל. גולד	1950	29	מ. ל. גולד	1950
30	מ. ל. גולד	1950	30	מ. ל. גולד	1950




PRESTIGE
HIGH DEFINITION

RAISED PROFILE

TRÖY & LISA UNDERHILL


DOOR WIDTH	CENTER STILE	END STILE	ROLLER SHIRT	BRACKET	STRUTS/SECT.	ROLLER	VERTICAL TRACK	JAMB LOAD CASE (10 PER FT-HIT)	HARDWARE	STD.
16"	3	SINGLE	HS1	HS3	2" X 7/16"	.049"	100			

DOOR TESTED WAS 281 SERIES.
 SERIES 280 THRU 289 ARE EQUIVALENT CONSTRUCTION 25CA STEEL
 AND END CAPS
 SERIES 180 ARE SAME CONSTRUCTION AS SERIES 280 ONLY 24GA STEEL



1. TESTED IN ACCORDANCE WITH STANDARD BUILDING CODE, CHAPTER 17, TO A POSITIVE AND NEGATIVE 37.5 PSF.
2. DASH NUMBERS REPRESENT VARIOUS SECTION HEIGHTS.
3. FOUR SECTION 7\"/>

9. THE STRUT PLACEMENT ON D
 CONSISTENT WITH THE DOOR
 SECTIONS ARE TO BE PLACED
 REDUCED BY THE DIFFERENCE
 11. SORE# P/N 605911-0001 IS
 12. POST TO BE INSTALLED ONLY
 13. STRUT PLACEMENTS CAN VARY
 14. QUANTITY FOR LOOKS CAN BE



26F_b - 1.9E
GARAGE HEAD ER

ENGINEERED WOOD SECTION PROPERTIES AND LOAD CAPACITIES

ALLOWABLE DESIGN STRESSES (FSD):
FLEXURAL STRESS (F_b) =
COMPRESSION PERP. TO GRAIN (F_c) =
HORIZONTAL SHEAR (F_v) =
MODULUS OF ELASTICITY (MOE) =
2600
740
225
1.9 x 10⁶

SPACING (IN)	SPACING (FT)	W ₁ (IN ⁴)	W ₂ (IN ⁴)	W ₃ (IN ⁴)	W ₄ (IN ⁴)	W ₅ (IN ⁴)	W ₆ (IN ⁴)
15.5	1.3	15.5	15.5	15.5	15.5	15.5	15.5
26.04	2.17	26.04	26.04	26.04	26.04	26.04	26.04
32.6	2.72	32.6	32.6	32.6	32.6	32.6	32.6
88.65	7.39	88.65	88.65	88.65	88.65	88.65	88.65
3908	32.57	3908	3908	3908	3908	3908	3908
4550	37.92	4550	4550	4550	4550	4550	4550
5250	43.75	5250	5250	5250	5250	5250	5250
5892	49.10	5892	5892	5892	5892	5892	5892
6533	54.44	6533	6533	6533	6533	6533	6533
7175	60.00	7175	7175	7175	7175	7175	7175
7817	65.14	7817	7817	7817	7817	7817	7817

NOTES:

1. Beam weights are based on 38 pcf.
2. Moment capacities are based on a span of 21 feet and must be modified for other spans.
3. Flexural stress, F_b, shall be modified by the Volume Factor, C_v, as outlined in ATC 117 - Design 1993 and the NDS for Wood Construction 1997.
4. Allowable design properties and load capacities are based on a load duration of 100 percent and dry use conditions.
5. The ATC NER 466 was used in calculating the above allowable design stresses for Power Header.

GARAGE HEADER COMPARISONS

SPACING (IN)	SPACING (FT)	W ₁ (IN ⁴)	W ₂ (IN ⁴)	W ₃ (IN ⁴)	W ₄ (IN ⁴)	W ₅ (IN ⁴)	W ₆ (IN ⁴)
810 / 54.0	6.92	810 / 54.0	810 / 54.0	810 / 54.0	810 / 54.0	810 / 54.0	810 / 54.0
990 / 72.0	8.33	990 / 72.0	990 / 72.0	990 / 72.0	990 / 72.0	990 / 72.0	990 / 72.0
640 / 40.0	5.00	640 / 40.0	640 / 40.0	640 / 40.0	640 / 40.0	640 / 40.0	640 / 40.0
765 / 51.0	6.04	765 / 51.0	765 / 51.0	765 / 51.0	765 / 51.0	765 / 51.0	765 / 51.0
750 / 48.0	5.67	750 / 48.0	750 / 48.0	750 / 48.0	750 / 48.0	750 / 48.0	750 / 48.0
500 / 60.0	5.00	500 / 60.0	500 / 60.0	500 / 60.0	500 / 60.0	500 / 60.0	500 / 60.0

For more information on Power Header®, or other laminated structural products from Anthony Forest Products Company please call 1-800-221-2326 or FAX at 870-862-6502.

Power Header® is a trademark of Anthony Forest Products Company
Post Office Box 1877 • El Dorado, Arkansas 71731
Internet address: <http://www.anthonystore.com>
e-mail: info@anthonystore.com
© 2001 Anthony Forest Products Company

Distributed by:

WOODFORD PLYWOOD, INC.
"Engineered Wood Products"

11950 West Beaver Street
Jacksonville, Florida 32220
(904) 685-9060
(800) 447-5568
FAX (904) 685-9160

To size a garage header supporting roof loads only, determine the total load & live load in pounds per lineal foot (PLF). Check the appropriate PLF table for a header supporting roof loads only (125% Non-Snow vs. 115% Snow) and select a member with a total load and live load capacity which meets or exceeds the design load for the rough opening size. For a garage header supporting roof, wall, and floor framing, determine the total load and live load in pounds per lineal foot (PLF). Select a header size from the roof, wall, and floor table (100% load duration) which has a total load and live load capacity equal to or greater than the design load for the appropriate rough opening.

GARAGE HEADER SIZING USING PLF TABLES:

- NOTES:
1. Values shown are the maximum uniform loads in pounds per lineal foot (PLF) that can be applied to the header. Header weight has been subtracted from the allowable total load.
 2. Tables are based on simple span uniform load conditions using a design span equal to the center-to-center of bearing. Non-shaded areas are based on 3' of bearing at each support, shaded areas on 4.5' of bearing, and shaded & outlined areas on 6' of bearing at supports.
 3. Headers are assumed to be loaded on the top edge with continuous lateral support along compression edge.
 4. When no live load is listed, total load controls.
 5. Deflection limits are listed within the PLF table heading.

76	107	120	171	185	267	261	380	356	321	471	684	609	813
562	778	888	1056	1363	1367	1582		501	715	664	864	840	
107	153	169	245	260	380	368	540						


114	145	180	231	277	359	391	510	534	699	693			
844	975	1322						752	897				
161	207	254	330	390	510	552	724						

114	145	180	231	277	359	391	510	534	653	707	789		
844	896	1216						752	824				
161	207	254	330	390	510	552	669						

3-1/2" WIDTH GARAGE HEADER PLF CAPACITY

Anthony Power Header®

26F_b - 1.9E



1st DEB REVIEW COMPLETE 1/20/54
AND COPIES RECD VANDERBILT
2054472-A-001 PROVIDES ADDITIONAL
INFORMATION - AVAILABLE FROM THE ILSA
BUREAU (BUREAU OF INVESTIGATION)
AT THE NATIONAL DEFENSE CENTER




to the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

TESTED IN
ACCORDANCE WITH
MIL-STD-883C PAGE 2
COMPANY NAME
CITY STATE

PRODUCT COMPLIANCE LABELING:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12, NCTL 210-2125-1, 2, 3
 Certifying Engineer and License Number Barry D. Portney, FE / 16253
 Unit Tested in Accordance with Miami-Dade ECCO PA202.
 Evaluation report NCTL-210-2794-1
 Door panels constructed from 26-gauge 0.017" thick steel skins. Both sides constructed from 4000
 Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel interior.
 cavity of slab filled with rigid polystyrene foam core. Slab gasket with insulated glass mounted on 1.5 x 0.5
 plastic lip life surround
 Frame constructed of wood with an extruded aluminum interior

CERTIFIED TEST REPORTS:




3/4 GLASS:

APPROVED DOOR STYLES:

WOOD-EDGE STEEL DOORS

XX
Glazed Inswing Unit

COP-WL-JH4142-02




APPROVED DOOR STYLES:

MINIMUM ASSEMBLY DETAIL:
Compliance requires that minimum assembly details have been followed - see MID-WL-M4000-02

MINIMUM INSTALLATION DETAIL:
Compliance requires that minimum installation details have been followed - see MID-WL-M4000-02

Single Door
Maximum unit size = 3'0" x 6'8"
Design Pressure
+66.0/-66.0
Limited water uplifts typical of standard design is also
Large Missile Impact Resistance
Hurricane protective system (shutters) is NOT REQUIRED.
Actual design pressure and uplift resistance determined by a specific loading design and engineering calculation in accordance with ASCE 7-98.



Note:
Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".

Test Data Review Certificate #2005447A and COP/TEST Report Validation Matrix #2005447A-001 provides additional information - available from the ILSWH website (www.ilswh.com). The website (www.masonite.com) or the Masonite Technical Center



APPROVED ARRANGEMENT:

WOOD-EDGE STEEL DOORS

X
Opaque Inswing Unit

COP-WL-JH4101-02

2

State of Florida, Professional Engineer
Kurt Ballhazor, P.E. - License Number 56533

Kurt Ballhazor

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

Test Data Review Certificate / 2025447A
and CDP/17-001 provides additional
information - available from the ITS WH
Masonite website (www.masonite.com).
of the Masonite Technical Center.



TESTED IN ACCORDANCE WITH
MIAMI-DADE BCCO
PA201, PA202 & PA203
COMPANY NAME
CITY STATE

PRODUCT COMPLIANCE LABELING:

Unit Tested in Accordance with Miami-Dade BCCO PA201, PA202 and PA203.
Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.
Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood.
Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior
cavity of slab filled with rigid polyurethane foam core.
Frame constructed of wood with an extruded aluminum threshold.

NCTL 210-2185-1, 2, 3

CERTIFIED TEST REPORTS:

WOOD-EDGE STEEL DOORS

Opaque Inswing Unit

X

COP-WL-JH4101-02

WINDOWS



AAMA/WWDA 101A.S.2-97
TEST REPORT SUMMARY

Rendered to:

MH HOME PRODUCTS, INC.

SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf
Operating Force	-47.2 psf
Air Infiltration	11 lb max.
Water Resistance	0.13 cfm/ft
Structural Test Pressure	6.00 psf
Deblazing	+67.5 psf
Forced Entry Resistance	-70.8 psf
	Passed
	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test-specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess
Mark A. Hess, Technician

MAH:mjb



Allen H. Russell
1 APRIL 2002

Architectural Testing

AAMA/NWDA 101/S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.

650 West Market Street

P.O. Box 370

Gatz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contacted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethtown, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWDA 101/S.2-97, Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors.

Test Specimen Description

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced poly spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4125
www.architest.com

1 APRIL 2002



Test Specimen Description: (Continued)

Weatherstripping:

Description	Quantity	Location
0.230" high by 0.270" backed polypropylene with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypropylene with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail


Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock with keeper	2	Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail



Test Specimen Description: (Continued)

Weatherstripping:

Description	Quantity	Location
0.230" high by 0.270" backed polypropylene with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypropylene with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, beveled, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, beveled, and sealed corners fastened with two #8 x 1-1/2" screws through the rail into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

Description	Quantity	Location
Metal cam lock with keeper	2	Midspar, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail



Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows

Paragraph	Title of Test - Test Method	Results	Allowed
-----------	-----------------------------	---------	---------

2.2.1.6.1 Operating Force

11 lbs

50 lbs max

Air Infiltration (ASTM E 283-91)

@ 1.57 psf (25 mph)

0.13 cfm/ft²

0.3 cfm/ft² max

Note #1: The tested specimen meets the performance levels specified in ASTM E 283-91 and 101/1.5. 2-97 for air infiltration.

Water Resistance (ASTM E 547-00)

(with and without screen)

WTP = 2.86 psf

No leakage

No leakage

2.1.4.1

Uniform Load Deflection (ASTM E 330-97)

(Measurements reported were taken on the meeting rail)

(Loads were held for 33 seconds)

@ 25.9 psf (positive)

0.42"

@ 34.7 psf (negative)

0.43"

0.26" max

*Exceeds L/175 for deflection, but passes all other test requirements.

2.1.4.2

Uniform Load Structural (ASTM E 330-97)

(Measurements reported were taken on the meeting rail)

(Loads were held for 10 seconds)

@ 38.9 psf (positive)

0.02"

@ 52.1 psf (negative)

0.02"

0.18" max



Allen H. Reeves
1 APRIL 2002

Test Specimen Description: (Continued)


Paragraph	Title of Test - Test Method	Results	Allowed
-----------	-----------------------------	---------	---------

2.2.1.6.2	Deglazing Test (ASTM E 987)	In operating direction at 70 lbs	
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 558-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test:	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test:	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00)	(with and without screen)	WTP = 6.00 psf	No leakage
	Uniform Load Deflection (ASTM E 330-97)	(Measurements reported were taken on the meeting rail)		
		(Loads were held for 33 seconds)		
		@ 45.0 psf (positive)	0.47"	0.26" max.
		@ 47.2 psf (negative)	0.46"	0.26" max.
	*Exceeds L/175 for deflection, but passes all other test requirements.			

Uniform Load Structural (ASTM E 330-97)	(Measurements reported were taken on the meeting rail)	
	(Loads were held for 10 seconds)	
	@ 67.5 psf (positive)	0.05"
	@ 70.8 psf (negative)	0.05"



Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess
Technician

SLAH:nb
01-41134.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



noted on US: 4:30 PM ROY & LISA UNDERHILL

VA-25-2002 04:55pm F-00-ELK CORP OF ALABAMA

20375347EE

VA-25-2002 04:55pm F-00-ELK CORP OF ALABAMA

SHINGLES



March 6, 2002

Subject: Elk Product Approval Information

All Prestigee® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami - Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:
ASTM D3462
PA 100 (110 mph uplift and wind driven rain resistance)
PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestigee and Capstone products are listed below. Also listed below are the Miami - Dade Notice of Acceptance Numbers (NOA).

Fasted Profile, Prestigee High Definition, Prestigee DL or Prestigee 30 -
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226 05


Prestigee 1.5 or Prestigee 1" -
PA 100 = 4 nails
PA 107 = 5 nails
MD NOA# = 01-1226 05

Prestigee Plus or Prestigee Gallery Collection -
PA 100 = 4 nails
PA 107 = 4 nails
MD NOA# = 01-1226 05

Capstone®
PA 100 = 4 nails
PA 107 = 4 nails
MD NOA# = 01-0523 01

* As per the Elk Limited Warranty, six nails are required for the Elk High Wind Warranty. If there are any questions please contact:

Mike Reed - Technical Manager or Daniel DeJernette - QA Engineer
(205) 342-0287



101) אברהם אבינו היה צדיק וישר בעיני יי' ויהי צדיק וישר
 102) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 103) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 104) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 105) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 106) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 107) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 108) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 109) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר
 110) ויהי צדיק וישר בעיני יי' ויהי צדיק וישר בעיני יי' ויהי צדיק וישר

1. The first part of the report, "Introduction", discusses the importance of the study and the objectives of the research. It also provides a brief overview of the methodology used in the study.

2. The second part of the report, "Literature Review", discusses the existing literature on the topic. It identifies the gaps in the literature and provides a critical analysis of the existing studies.

3. The third part of the report, "Methodology", describes the research design, the sample, and the data collection methods. It also discusses the statistical methods used in the analysis.

4. The fourth part of the report, "Results", presents the findings of the study. It includes tables and figures to illustrate the data and discusses the statistical significance of the results.

5. The fifth part of the report, "Conclusion", summarizes the main findings of the study and discusses the implications for future research. It also provides recommendations for policy and practice.

6. The final part of the report, "References", lists the sources used in the study.

[illegible]


1111 AND RIDGE SHAPES

[illegible]

PRESTIGE:
HIGH DEFINITION

RAISED PROFILE

Rolling Products Specifications - TUSCALOOSA, AL.



GREGORY GLEN
OF
COUNTRY

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 15-4S-17-08359-130

Building permit No. 000023854

Use Classification SFD, UTILITY

Fire: 47.36

Permit Holder BRYAN ZECHER

Waste: 98.00

Owner of Building RITA MAZDZER

Total: 145.36

Location: 154 SE GREGORY GLEN(COUNTRY SIDE ESTATES, LOT 30)

Date: 02/24/2006



Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

Notice of Intent for Preventative Treatment for Termites

(As required by Florida Building Code 104.2.6)

Date: Oct. 7, 2005

154 SE Gregory Glen

(Address of Treatment or Lot/Block of Treatment)

Lake City

City

Florida Pest Control & Chemical Co.

www.flapest.com

Product to be used: Bora-Care Termiticide (Wood Treatment)

Chemical to be used: 23% Disodium Octaborate Tetrahydrate

Application will be performed onto structural wood at dried-in stage of construction. Bora-Care Termiticide application shall be applied according to EPA registered label directions as stated in the Florida Building Code Section 1861.1.8

(Information to be provided to local building code offices prior to concrete foundation installation.)

804

Notice of Treatment 11758

Applicator: Florida Pest Control & Chemical Co. (www.flapest.com)

Address: Bora-Hol

City: Lake City Phone: 782-1103

Site Location: Subdivision Countryside Estates

Lot # 30 Block # 2284

Address 154 SE Gregory Glen

Product used

☐ Premise

Active Ingredient

Imidacloprid

% Concentration

0.1%

☐ Termidor

Fipronil

0.12%

☒ Bora-Care

Disodium Octaborate Tetrahydrate

23.0%

Type treatment:

☐ Soil

☒ Wood

Area Treated

Square feet

Linear feet

Gallons Applied

1974

625

5

As per Florida Building Code 104.2.6 - If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line

1/3/06

Date

1100

Time

Fosy Gamm

Print Technician's Name

Remarks:

Applicator - White

Permit File - Canary

Permit Holder - Pink

10/05 ©