




**ROOF VENTILATION:**  
R806.2 Minimum vent area.  
The minimum net free ventilating area shall be 1/150 of the area of the vented space.  
Exception: The minimum net free ventilation area shall be 1/300 of the vented space provided one or more of the following conditions are met:  
1. In Climate Zones 6, 7 and 8, a Class I or II vapor retarder is installed on the warm-in-winter side of the ceiling.  
2. At least 40 percent and not more than 50 percent of the required ventilating area is provided by ventilators located in the upper portion of the attic or rafter space.  
Upper ventilators shall be located no more than 3 feet below the ridge or highest point of the space, measured vertically, with the balance of the required ventilation provided by eave or cornice vents. Where the location of wall or roof framing members conflicts with the installation of upper ventilators, installation more than 3 feet below the ridge or highest point of the space shall be permitted.




**LEFT ELEVATION**  
SCALE: 1/4" = 1'-0"



**FRONT ELEVATION**  
SCALE: 1/4" = 1'-0"



**REAR ELEVATION**  
SCALE: 1/4" = 1'-0"



**RIGHT ELEVATION**  
SCALE: 1/4" = 1'-0"

Amira Builders

Warren Depree Res.

PROJECT ADDRESS:  
1130 SW Bluff Drive  
Fort White, FL 32038

FL PE 53915  
This item has been digitally signed and sealed by  
Mark Disosway P.E. on digital signature date.  
Printed copies of this document are not considered  
signed and sealed and the signature must be  
verified on any electronic copies.



C=US, O=Florida,  
dnQualifier=A014  
10C0000017E97  
DE07CA000746F  
0, CN=Mark d  
Disosway  
2024-04-24 10:  
15:11

**DIMENSIONS:**  
Stated dimensions supercede scaled  
dimensions. Refer all questions to  
Mark Disosway, P.E. for resolution.  
Do not proceed without clarification.

**COPYRIGHTS AND PROPERTY RIGHTS:**  
Mark Disosway, P.E. hereby expressly reserves  
its common law copyrights and property right in  
these instruments of service. This document is  
not to be reproduced, altered or copied in any  
form or manner without first the express written  
permission and consent of Mark Disosway.

**CERTIFICATION:** I hereby certify that I have  
examined this plan, and that the applicable  
portions of the plan, relating to wind engineering  
comply with the 8th Edition Florida  
Building Code Residential (2023)  
to the best of my knowledge.

**LIMITATION:** This design is valid for one  
building, at specified location.


**Mark Disosway P.E.**  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.754.5419  
disoswaydesign@gmail.com

**JOB NUMBER:**  
240334


**1**  
OF 6 SHEETS

- ELECTRICAL PLAN NOTES:**
- E-1 WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS.
- E-2 CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.
- E-3 ALL INSTALLATIONS SHALL BE PER NAT'L. ELECTRIC CODE.
- E-4 ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.
- E-5 TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNER'S DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF NEC-LATEST EDITION.
- E-6 ELECTRICAL CONTR SHALL BE RESPONSIBLE FOR THE DESIGN & SIZING OF ELECTRICAL SERVICE AND CIRCUITS.
- E-7 ENTRY OF SERVICE ( UNDERGROUND OR OVERHEAD ) TO BE DETERMINED BY POWER COMPANY.
- E-8 ALL 120-VOLT, SINGLE-PHASE, 15- AND 20-AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUN ROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT.
- E-9 ALL OUTLETS TO BE LOCATED ABOVE BASE FLOOD ELEVATION.
- E-10 A SERVICE DISCONNECT WITH OVER CURRENT PROTECTION SHALL BE INSTALLED OUTSIDE OF THE BUILDING, ON THE LOAD SIDE OF THE METER, AT THE PLACE ELECTRIC CONDUCTORS ENTER THE BUILDING.
- E-11 SERVICE ENTRANCE CONDUCTORS MAY NOT BE LOCATED INSIDE OF THE OF THE BUILDING WITHOUT SPECIAL APPROVAL OF THE BUILDING OFFICIAL.
- E-12 CARBON MONOXIDE ALARMS SHALL BE REQUIRED WITHIN 10' OF ALL ROOMS FOR SLEEPING PURPOSES IN BUILDINGS HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, A FIREPLACE, OR ATTACHED GARAGE.
- E-13 ALL OUTLETS LOCATED IN RESIDENTIAL TO BE TAMPER-RESISTANT PER NEC.
- E-14 A MINIMUM OF 75% OF PERMANENTLY INSTALLED LAMPS OR LIGHTING FIXTURES SHALL BE HIGH EFFICACY FBC EC SEC. R404.1

| ELECTRICAL LEGEND |                                      |
|-------------------|--------------------------------------|
|                   | CEILING FAN (PRE-WIRE FOR LIGHT KIT) |
|                   | DOUBLE SECURITY LIGHT                |
|                   | 2X4 FLUORESCENT LIGHT FIXTURE        |
|                   | RECESSED CAN LIGHT                   |
|                   | BATH EXHAUST FAN WITH LIGHT          |
|                   | BATH EXHAUST FAN                     |
|                   | LIGHT FIXTURE                        |
|                   | DUPLEX OUTLET                        |
|                   | 220v OUTLET                          |
|                   | GFI DUPLEX OUTLET                    |
|                   | SMOKE DETECTOR                       |
|                   | WALL SWITCH                          |
|                   | 3 WAY WALL SWITCH                    |
|                   | 4 WAY WALL SWITCH                    |
|                   | WATER PROOF GFI OUTLET               |
|                   | PHONE JACK                           |
|                   | TELEVISION JACK                      |
|                   | GARAGE DOOR OPENER                   |
|                   | CARBON MONOXIDE ALARM                |



**ELECTRICAL PLAN**  
SCALE: 1/4" = 1'-0"



**FLOOR PLAN**  
SCALE: 1/4" = 1'-0"  
ALL CEILING HEIGHTS TO BE 9'-0" UNLESS NOTED OTHERWISE

| AREA SCHEDULE |              |
|---------------|--------------|
| NAME          | AREA         |
| Living        | 1536 sq. ft. |
| Front Porch   | 51 sq. ft.   |
| Rear Porch    | 320 sq. ft.  |
| Total         | 1907 sq. ft. |

Amira Builders

Warren Depree Res.

PROJECT ADDRESS:  
1130 SW Bluff Drive  
Fort White, FL 32038

FL PE 53915

This item has been digitally signed and sealed by Mark Disosway P.E. on digital signature data. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Florida, dnQualifier=A01410C0000017E97DE07CA000746F0, CN=Mark d Disosway  
2024-04-24 10:15:36

**DIMENSIONS:**  
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

**COPYRIGHTS AND PROPERTY RIGHTS:**  
Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

**CERTIFICATION:** I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 8th Edition Florida Building Code Residential (2023) to the best of my knowledge.


**LIMITATION:** This design is valid for one building, at specified location.

**Mark Disosway P.E.**  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.754.5419  
disoswaydesign@gmail.com

**JOB NUMBER:**  
240334

**2**  
OF 6 SHEETS






COLUMN LAYOUT  
SCALE: 1/4" = 1'-0"

Amira Builders

Warren Depree Res.

PROJECT ADDRESS:  
1130 SW Bluff Drive  
Fort White, FL 32038

FL PE 53915  
This item has been digitally signed and sealed by  
Mark Disosway P.E. on digital signature date.  
Printed copies of this document are not considered  
signed and sealed and the signature must be  
verified on any electronic copies.



C=US, O=Florida,  
dnQualifier=A014  
10C0000017E97  
DE07CA000746F  
0, CN=Mark d  
Disosway  
2024-04-24 10:  
15:52

DIMENSIONS:  
Stated dimensions supercede scaled  
dimensions. Refer all questions to  
Mark Disosway, P.E. for resolution.  
Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS:  
Mark Disosway, P.E. hereby expressly reserves  
its common law copyrights and property right in  
these instruments of service. This document is  
not to be reproduced, altered or copied in any  
form or manner without first the express written  
permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have  
examined this plan, and that the applicable  
portions of the plan, relating to wind engineering  
comply with the 2018 Edition Florida  
Building Code Residential (2023)  
to the best of my knowledge.


LIMITATION: This design is valid for one  
building, at specified location.

Mark Disosway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.754.5419  
disoswaydesign@gmail.com


JOB NUMBER:  
240334

3  
OF 6 SHEETS






ONE STORY WALL SECTION  
SCALE: 3/4" = 1'-0"




(TYP.) INTERSECTING WALL FRAMING  
WOOD FRAME



(TYP.) CORNER FRAMING  
WOOD FRAME


| ROOF SHEATHING FASTENING TABLE (RAFTER / TRUSS SG = 0.49) |                                    |  |                                |   |
|---|------------------------------------|--|--------------------------------|---|
| Wind Speed  | Sheathing Thickness Plywood Or OSB | Required Nail  | Nail spacing along panel edges | Nail spacing along intermediate supports in the panel field |
| 120 mph Exp. B  | 7/16"                              | ASTM F1667 RSRs-01 (2 3/8" x 0.131")                                     | 6" oc                          | 12" oc  |
| 120 mph Exp. C  | 7/16"                              | ASTM F1667 RSRs-01 (2 3/8" x 0.131")                                     | 6" oc                          | 6" oc   |
| 130 mph Exp. B  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131") or ASTM F1667 RSRs-04 (3" x 0.120") | 6" oc                          | 6" oc   |
| 130 mph Exp. C  | 19/32"                             | ASTM F1667 RSRs-01 (2 3/8" x 0.131")                                     | 6" oc                          | 6" oc   |
| 130 mph Exp. D  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131") or ASTM F1667 RSRs-04 (3" x 0.120") | 6" oc                          | 6" oc   |
| 140 mph Exp. B  | 7/16"                              | ASTM F1667 RSRs-01 (2 3/8" x 0.131")                                     | 6" oc                          | 6" oc   |
| 140 mph Exp. C  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131") or ASTM F1667 RSRs-04 (3" x 0.120") | 6" oc                          | 6" oc   |
| 140 mph Exp. D  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131")                                     | 6" oc                          | 6" oc   |
| 150 mph Exp. C  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131") or ASTM F1667 RSRs-04 (3" x 0.120") | 6" oc                          | 6" oc   |
| 150 mph Exp. D  | 19/32"                             | ASTM F1667 RSRs-03 (2 1/2" x 0.131")                                     | 4" oc                          | 4" oc   |

Note: For sheathing located a minimum of 4 feet from the perimeter edge of the roof, including 4 feet on each side of ridges and hips, nail spacing is permitted to be 8 inches on center along panel edges and 6 inches on center along intermediate supports in the panel field. Note: This table specifies the code minimum thickness of roof sheathing. The thickness of the sheathing may need to be increased based in the type of roofing material being used. See manufacturer Florida product approval.




SPACE RAT RUN & DIAGONAL BRACE 6'-0" O.C.  
FOR GABLE HEIGHT UP TO 25'-0" 130 MPH, EXP. C, ENCLOSED


(TYP.) GABLE BRACING DETAIL  
WOOD FRAME




TYPICAL HEADER STRAPING DETAIL  
WOOD FRAME w/ STRAPS & ANCHORS



(TYP.) WALL CONNECTIONS  
ONE STORY WOOD FRAME



SHEATHING FOR UPLIFT ATTACHMENT DETAILS  
ONE STORY WOOD FRAME




(TYP.) GABLE WALL w/ VAULTED CEILING  
WOOD FRAME


| HEADER STRAP TABLE |                                 |  |  |
|--------------------|---------------------------------|--|--|
| Top Connection     | Bottom Connection               |  |  |
| SPH4/6             | MSTA24, 18-10d stud to rim beam |  |  |

| SILL PLATE SPANS FOR 10'-0" WALL HEIGHT |                       |         |         |         |
|---|-----------------------|---------|---------|---------|
| DESIGN                                  | MAX. SPANS FOR SPF #2 |         |         |         |
| WIND SPEED                              | (1) 2x4               | (2) 2x4 | (1) 2x6 | (2) 2x6 |
| 130 MPH EXP. C                          | 5'-2"                 | 7'-9"   | 7'-7"   | 11'-3"  |


BASED ON WFCM TABLE A-3.20B  
FOR OTHER WALL HEIGHTS (H) SILL SPAN SHALL BE DIVIDED BY (H/10)




TYPICAL CMU COLUMN SECTION HOUSE & PORCH  
SCALE: 3/4" = 1'-0"



TYPICAL CMU COLUMN SECTION HOUSE & PORCH  
SCALE: 3/4" = 1'-0"



(TYP.) PORCH POST  
ONE STORY WOOD



TYPICAL CMU COLUMN SECTION HOUSE & PORCH  
SCALE: 3/4" = 1'-0"

| CONNECTOR TABLE |            |                       |                   |                          |
|-----------------|------------|-----------------------|-------------------|--------------------------|
| Uplift SP       | Uplift SPF | Truss Connector       | To Plate          | To Truss/Rafter          |
| 805             | 505        | SDWC15600             |                   |                          |
| 400             | 260        | H3                    | 4-131"x1 1/2"     | 4-131"x1 1/2"            |
| 825             | 540        | H2.5A                 | 5-131"x1 1/2"     | 5-131"x1 1/2"            |
| 1040            | 1015       | H10A                  | 9-148"x1 1/2"     | 9-148"x1 1/2"            |
| 645             | 515        | LTS12-20              | 6-148"x1 1/2"     | 6-148"x1 1/2"            |
| 990             | 850        | STS12-30              | 7-148"x1 1/2"     | 7-148"x1 1/2"            |
| 1415            | 1215       | HTS21-30              | 8-148"x1 1/2"     | 8-148"x1 1/2"            |
| 1235            | 1235       | LSTA21                | 8-148"x1 1/2"     | 8-148"x1 1/2"            |
| 1640            | 1460       | MSTA24                | 9-148"x1 1/2"     | 9-148"x1 1/2"            |
| 2145            | 1835       | DTT22                 | 7-148"x1 1/2"     | 7-148"x1 1/2"            |
| Uplift SP       | Uplift SPF | Strap Ties            | To One Member     | To Other Member          |
| 1235            | 1235       | LSTA21                | 8-148"x1 1/2"     | 8-148"x1 1/2"            |
| 1640            | 1460       | MSTA24                | 9-148"x1 1/2"     | 9-148"x1 1/2"            |
| 2145            | 1835       | DTT22                 | 7-148"x1 1/2"     | 7-148"x1 1/2"            |
| Uplift SP       | Uplift SPF | Post Plate Ties       | To Stud           | To Plate                 |
| 555             | 535        | SP1                   | 4-148"x3"         | 4-148"x3"                |
| 1010            | 605        | SP2                   | 6-148"x3"         | 6-148"x3"                |
| 1280            | 1100       | SPH4/6                | 12-148"x1 1/2"    | wrap under or over plate |
| 771             | 771        | LSTA24                | 10-148"x1 1/2"    | wrap under or over plate |
| 1235            | 1235       | LSTA24                | 14-148"x1 1/2"    | wrap under or over plate |
| Uplift SP       | Uplift SPF | Holdowns @ Stemwall   | To Stud / Post    | Anchor                   |
| 2145            | 1835       | DTT22                 | 8-SDS 1/4"x1 1/2" | 1/2"x12" Titen HD        |
| 4235            | 3640       | HTT4                  | 18-162"x2 1/2"    | 1/2"x12" Titen HD        |
| Uplift SP       | Uplift SPF | Holdowns @ Mono       | To Stud / Post    | Anchor                   |
| 2145            | 1835       | DTT22                 | 8-SDS 1/4"x1 1/2" | 1/2"x12" Titen HD        |
| 4235            | 3640       | HTT4                  | 18-162"x2 1/2"    | 1/2"x12" Titen HD        |
| Uplift SP       | Uplift SPF | Post Bases @ Stemwall | To Post           | Anchor                   |
| 1900            | ABU44Z     | ABU44Z                | 12-162"x3 1/2"    | 5/8"x12" Drill & Epoxy   |
| 2475            | ABU62Z     | ABU62Z                | 12-162"x3 1/2"    | 5/8"x7" Drill & Epoxy    |

EXTERIOR WALL STUD TABLE FOR SPF #2 STUDS:

THIS STUD HEIGHT TABLE IS PER 2012 WFCM, TABLE 3.20B5, EXTERIOR LOAD BEARING & NON LOAD BEARING STUD LENGTHS FOR WALLS WITH OSB EXTERIOR AND 1/2" GYP INTERIOR RESISTING INTERIOR ZONE WINDLOADS, 130 MPH, EXPOSURE C, STUD DEFLECTION LIMIT H/240 (NOT OK FOR BRITTLE FINISH). STUD SPACINGS SHALL BE MULTIPLIED BY 0.8 FOR FRAMING LOCATED WITHIN 4 FEET OF CORNERS FOR END ZONE LOADING. (END ZONE EXAMPLE 16" O.C. x 0.8 = 12.8" O.C.)

|                  |                       |
|------------------|-----------------------|
| (1) 2x4 @ 16" OC | TO 10'-1" STUD HEIGHT |
| (1) 2x4 @ 12" OC | TO 11'-2" STUD HEIGHT |
| (1) 2x6 @ 16" OC | TO 15'-7" STUD HEIGHT |
| (1) 2x6 @ 12" OC | TO 17'-3" STUD HEIGHT |
| (1) 2x8 @ 16" OC | TO 22'-0" STUD HEIGHT |

| GRADE & SPECIES TABLE |              |      |     |
|-----------------------|--------------|------|-----|
|                       | SP #2        | Fb   | E   |
| 2x8                   |              | 925  | 1.4 |
| 2x10                  |              | 800  | 1.4 |
| 2x12                  |              | 750  | 1.4 |
| GLB                   | 24F-V3 SP    | 2600 | 1.9 |
| LSL                   | TIMBERSTRAND | 1700 | 1.7 |
| LVL                   | MICROLAM     | 2950 | 2.0 |
| PSL                   | PARALAM      | 2900 | 2.0 |

**GENERAL NOTES:**

TRUSSES: TRUSSES SHALL BE DESIGNED BY A FLORIDA LICENSED ENGINEER IN ACCORDANCE WITH THE FBCL. TRUSS ENGINEERING SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS. TRUSS ENGINEERING IS THE RESPONSIBILITY OF THE TRUSS MANUFACTURER AND SHALL BE SIGNED & SEALED BY THE MANUFACTURER'S DESIGN ENGINEER. IT IS THE BUILDER'S RESPONSIBILITY TO VERIFY THE TRUSS DESIGNER FULLY SATISFIED ALL THE ABOVE REQUIREMENTS AND TO SELECT UPLIFT CONNECTIONS BASED ON TRUSS ENGINEERING UPLIFT AND PROVIDE FOOTINGS FOR INTERIOR BEARING WALLS. BUILDER IS TO FURNISH TRUSS ENGINEERING TO WIND LOAD ENGINEER FOR REVIEW OF TRUSS REACTIONS ON THE BUILDING STRUCTURE. STRAP 2X6 RAFTERS WITH MIN. UPLIFT CONNECTION 415LB EACH END, 2X6 RAFTERS 700 LB EACH END.

SITE PREPARATION: SITE ANALYSIS AND PREPARATION IS NOT PART OF THIS PLAN.

FOUNDATION: CONFIRM THAT THE FOUNDATION DESIGN & SITE CONDITIONS MEET GRAVITY LOAD REQUIREMENTS (ASSUME 1500 PSF BEARING CAPACITY UNLESS VISUAL OBSERVATION OR SOILS TEST PROVES OTHERWISE).

CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS, F<sub>c</sub> = 2500 PSI.

WELDED WIRE REINFORCED SLAB: 6" x 6" W14 x W14, F<sub>y</sub> = 80ksi, WELDED WIRE REINFORCEMENT FABRIC (W.W.R.) CONFORMING TO ASTM A185, LOCATED IN MIDDLE OF THE SLAB, SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 3'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTH: 12 INCH TO 2 INCHES. DOSAGE AMOUNTS FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD PER THE MANUFACTURER'S RECOMMENDATIONS. FIBERS TO COMPLY WITH ASTM C 1118. SUPPLIER TO PROVIDE ASTM C 1118 CERTIFICATION OF COMPLIANCE WHEN REQUESTED BY BUILDING OFFICIAL.

CONTROL JOINTS: WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1:5 AND TYPICAL SPACING OF CUTS TO BE LEFT. DO NOT CUT W/WW OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

REBAR: ASTM A615, GRADE 40, DEFORMED BARS, F<sub>y</sub> = 40 KSI. ALL LAP SPLICES 40" DB (25" FOR #5 BARS), UNO, ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH 318-05, UNO.

ROOF SHEATHING: ALL ROOFS ARE HORIZONTAL. DIAPHRAGMS, SHEATHING, UNBLOCKED, APPLIED PERPENDICULAR TO FRAMING, OVER A MINIMUM OF 3 FRAMING MEMBERS, WITH PANEL EDGES STAGGERED.

STRUCTURAL CONNECTORS: MANUFACTURERS AND PRODUCT NUMBER FOR CONNECTORS, ANCHORS, AND REINFORCEMENT ARE LISTED FOR EXAMPLE NOT ENDORSEMENT. AN EQUIVALENT DEVICE OF THE SAME OR OTHER MANUFACTURER CAN BE SUBSTITUTED FOR ANY DEVICES LISTED IN THE EXAMPLE TABLES AS LONG AS IT MEETS THE REQUIRED LOAD CAPACITIES. MANUFACTURER'S INSTALLATION INSTRUCTIONS MUST BE FOLLOWED TO ACHIEVE RATED LOADS.

ANCHOR BOLTS: A-307 ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 10" IN GROUTED CMU.

**BUILDER'S RESPONSIBILITY:**

THE BUILDER AND OWNER ARE RESPONSIBLE FOR THE FOLLOWING, WHICH ARE SPECIFICALLY NOT PART OF THE WIND LOAD ENGINEER'S SCOPE OF WORK.

CONFIRM SITE CONDITIONS, FOUNDATION BEARING CAPACITY, GRADE AND BACKFILL HEIGHT, WIND SPEED AND DEBRIS ZONE, AND FLOOD ZONE.

PROVIDE MATERIALS AND CONSTRUCTION TECHNIQUES, WHICH COMPLY WITH FBCL REQUIREMENTS FOR THE STATED WIND VELOCITY AND DESIGN PRESSURES.

PROVIDE A CONTINUOUS LOAD PATH FROM TRUSSES TO FOUNDATION. IF YOU BELIEVE THE PLAN OMTS A CONTINUOUS LOAD PATH CONNECTION, CALL THE WIND LOAD ENGINEER IMMEDIATELY.

VERIFY THE TRUSS MANUFACTURER'S SEALED ENGINEERING INCLUDES TRUSS DESIGN, PLACEMENT PLANS, TEMPORARY AND PERMANENT BRACING DETAILS, TRUSS-TO-TRUSS CONNECTIONS, AND UPLIFT AND REACTION LOADS FOR ALL BEARING LOCATIONS.

**ROOF SYSTEM DESIGN:**

THE SEAL ON THESE PLANS FOR COMPLIANCE WITH FBCL, IS BASED ON REACTIONS, UPLIFTS, AND BEARING LOCATIONS IN TRUSS ENGINEERING SUBMITTED TO THE WIND LOAD ENGINEER. IT IS THE RESPONSIBILITY OF THE BUILDER TO CHECK ALL DETAILS OF THE COMPLETE ROOF SYSTEM DESIGN SUBMITTED BY THE TRUSS MANUFACTURER AND HAVE IT SIGNED, AND SEALED BY A DESIGN PROFESSIONAL FOR CORRECT APPLICATION OF FBCL REQUIRED LOADS AND ANY SPECIAL LOADS. THE BUILDER IS RESPONSIBLE TO REVIEW EACH INDIVIDUAL TRUSS MEMBER AND THE TRUSS ROOF SYSTEM AS A WHOLE AND TO PROVIDE RESTRAINT FOR ANY LATERAL BRACING. THE BUILDER SHOULD USE CARE CHECKING THE ROOF DESIGN BECAUSE THE WIND LOAD ENGINEER IS SPECIFICALLY NOT RESPONSIBLE FOR THE TRUSS LAYOUT WHICH WAS CREATED BY THE TRUSS MANUFACTURER AND THE TRUSS DESIGNER ALSO DENIES RESPONSIBILITY FOR THE LAYOUT PER NOTES ON THEIR SEALED SHEETS.

Amira Builders

Warren Depree Res.

FL PE 53915

This item has been digitally signed and sealed by Mark Disoway P.E. on digital signature date: 2024-04-24 10:16:11

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Florida, dnQualifier=A01410C0000017E970, CN=Mark d Disoway

2024-04-24 10:16:11

DIMENSIONS: Stated dimensions supersede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 8th Edition Florida Building Code Residential (2023) to the best of my knowledge.


LIMITATION: This design is valid for one building, at specified location.

Mark Disoway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.754.5419  
disowaydesign@gmail.com

JOB NUMBER:  
240334


S-1  
OF 6 SHEETS





| MASONRY NOTE:<br>CONTRACTOR CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATION FOR MASONRY STRUCTURES" (ACI 530.1/ASCE 6/MS 602). THE CONTRACTOR AND MASON MUST IMMEDIATELY, BEFORE PROCEEDING, NOTIFY THE ENGINEER OF ANY CONFLICTS BETWEEN ACI 530.1-02 AND THE REQUIREMENTS OF THIS PROJECT. ANY EXCEPTIONS TO ACI 530.1-02 MUST BE APPROVED BY THE ENGINEER IN WRITING. |                                  |  |
|--|----------------------------------|--|
|  | ACI308.1-02 Section              | Specific Requirements  |
| 1.4A   | Compressive strength             | If block bearing walls (see MS 1500) per   |
| 2.1  | Mortar                           | ASTM C 270, Type N, UNO  |
| 2.2  | Grout                            | ASTM C 476, admixtures require approval  |
| 2.3  | CMU standard                     | ASTM C 590-02, Normal weight, hollow<br>and surface finish, 8" x 16" x 16" minimum<br>bond and 12"x12"x8" or 16"x16"x8" column<br>block  |
| 2.3  | Clay brick standard              | ASTM C 214-02, 214-02, Type FBS,<br>5.5"x2.75"x11.5"   |
| 2.4  | Reinforcing bars, #3 - #11       | ASTM E15, Grade 40, Fy = 40 ksi, UTS<br>58 ksi min 40 bar dist. (SST) 50%  |
| 2.4F   | Coating for corrosion protection | Anchors, steel metal ties completely<br>embedded in mortar or grout, ASTM<br>A305, Class 600, 0.60 in. x 0.405 in.   |
| 2.4F   | Coating for corrosion protection | Joint reinforcement in walls exposed to<br>moisture or wet soils, anchors, steel metal<br>ties not completely embedded in mortar or<br>grout, ASTM A153, Class B2, 1/8" x 1/8" x<br>0.405 in |
| 3.3.E.2  | Pipes, conduits, and accessories | Any not shown on the project drawings<br>require engineering approval.   |
| 3.3.E.7  | Movement joints                  | Contractor assumes responsibility for type<br>and location of movement joints. If not<br>detailed on project drawings.   |

**OWNER / BUILDER  
TO REVIEW THE PLACEMENT  
OF FLOOR TRUSSES BEFORE  
CONSTRUCTION TO INSURE  
TRUSSES DO NOT INTERFERE  
WITH ANY ELECTRICAL,  
PLUMBING, OR HVAC REQUIERMENTS**



Amira Builders

Warren Depree Res.

**PROJECT ADDRESS:**  
1130 SW Bluff Drive  
Fort White, FL 32038

PE 53915

This item has been digitally signed and sealed by Mark Disosway PE on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

C=US, O=Florida  
dnQualifier=A01  
10C0000017E97  
DE07CA000746  
0, CN=Mark d  
Disosway  
2024-04-24 10:  
16:30

**DIMENSIONS:**  
Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

**COPYRIGHTS AND PROPERTY RIGHTS:** Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

**CERTIFICATION:** I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 8th Edition Florida Building Code Residential (2023) to the best of my knowledge.

**LIMITATION:** This design is valid for one building, at specified location.

**Mark Disosway P.E.**  
**163 SW Midtown Place**  
**Suite 103**  
**Lake City, Florida 32025**  
**386.754.5419**  
**disoswaydesign@gmail.com**

JOB NUMBER:  
240334



**S-2**

OF 6 SHEETS

| UNLESS NOTED OTHERWISE (MINIMUM REQUIERMENTS)<br>***SEE STRUCTURAL PLAN FOR ANY SPECIFIC CALL OUTS*** |  |
|---|--|
| BEAM / HEADERS (SIZE)   | ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X6 SP #2 (UNO)                                  |
| HEADERS (JACK & KING STUDS)   | ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE (1) JACK STUD & (1) KING STUD EACH SIDE (UNO)                           |
| HEADERS (STRAPING)  | ALL HEADERS w/ UPLIFT TO BE STRAPPED DOWN @ EACH SIDE WITH (1) SPH @ TOP OF WALL & (1) MSTA24 STRAP TO RIM BEAM BOTTOM |
| JACK STUDS UNDER GIRDER TRUSS   | USE ONE JACK STUD GIRDER SUPPORT PER 2000 LB LOAD  |

| ACTUAL vs REQUIRED SHEARWALL |            |              |
|------------------------------|------------|--------------|
|                              | TRANSVERSE | LONGITUDINAL |
| ACTUAL                       | 13365 LBF  | 16137 LBF    |
| REQUIRED                     | 12955 LBF  | 5560 LBF     |

HEADER LEGEND



STRUCTURAL PLAN

SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

SN-1 DIMENSIONS ON STRUCTURAL SHEETS ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS

SN-2 PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCSI-03. BCSI-B1, BCSI-B2, & BCSI-B3. BCSI-B1, BCSI-B2, & BCSI-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE

Amira Builders

Warren Depree Res.

PROJECT ADDRESS:  
1130 SW Bluff Drive  
Fort White, FL 32038

FL PE 53915

This item has been digitally signed and sealed by Mark Disoway P.E. on digital signature date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



C=US, O=Florida, dnQualifier=A014 10C0000017E97D E07CA000746F0, CN=Mark d Disoway 2024-04-24 10:17:04

DIMENSIONS: Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disoway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disoway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disoway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 5th Edition Florida Building Code Residential (2023) to the level of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

Mark Disoway P.E.  
163 SW Midtown Place  
Suite 103  
Lake City, Florida 32025  
386.754.5419  
disowaydesign@gmail.com

JOB NUMBER:  
240334

S-3  
OF 6 SHEETS