



*CJ Custom Carpentry, Inc.
222 SW Cross Pointe Ct
Lake City, FL 32024
386-754-6924 Office
CGC1513223*

SCOPE OF WORK

Project: Kim Davis kitchen remodel

Address: 438 SE Llewellyn Ave, Lake City, FL 32025

Remove existing laundry room window, frame up install hardi panel on outside and drywall interior. Remove laundry wall.

Tear out and haul away soffits, cabinets, c-tops. Trench floor for electric to island.

Drywall repair soffit area, removed window, removed wall area. Drywall new wall.

Rework electric in kitchen area per new design. Update devices, install 6 LED can lights in ceiling. Relocate light switches in removed walls and outlets. Install microwave. Run HR for microwave. Run electric to new island per code. Customer to provide electric materials.

Fill in step down floor to kitchen height.

Install cabinets per design.

Kim Davis Kitchen

List of materials for electric

1 roll SKU 268844
1 roll SKU 268917
1 pc. SKU 826616
12 pcs. SKU 710615
1 box SKU 697820
2 pcs SKU 265610
5 pcs SKU 141206
2 pcs SKU 745081
4 pcs SKU 1003580184
(6) 6" LED wafer ceiling lights