

INPUT SUMMARY CHECKLIST REPORT

PROJECT

Title:	Yasmanis Residence	Bedrooms:	4	Address Type:	Street Address
Building Type:	User	Conditioned Area:	1810	Lot #	
Owner Name:	Yasmanis Reyes	Total Stories:	1	Block/Subdivision:	
# of Units:	1	Worst Case:	No	PlatBook:	
Builder Name:		Rotate Angle:	0	Street:	162 NW CREWS GLEN
Permit Office:	Columbia County	Cross Ventilation:	Yes	County:	Columbia
Jurisdiction:		Whole House Fan:	No	City, State, Zip:	LAKE CITY , FL , 32055
Family Type:	Detached				
New/Existing:	New (From Plans)				
Comment:					

CLIMATE

✓	Design Location	TMY Site	Design Temp		Int Design Temp		Heating Degree Days	Design Moisture	Daily Temp Range
			97.5 %	2.5 %	Winter	Summer			
_____	FL, Gainesville	FL_GAINESVILLE_REGI	32	92	70	75	1305.5	51	Medium

BLOCKS

Number	Name	Area	Volume
1	Block1	1810	14480

SPACES

Number	Name	Area	Volume	Kitchen	Occupants	Bedrooms	Infil ID	Finished	Cooled	Heated
1	Main	1810	14480	Yes	8	4	1	Yes	Yes	Yes

FLOORS

✓	#	Floor Type	Space	Perimeter	R-Value	Area		Tile	Wood	Carpet
_____	1	Slab-On-Grade Edge Insulation	Main	181 ft	0	1810 ft²	----	0	0	1

ROOF

✓	#	Type	Materials	Roof Area	Gable Area	Roof Color	Rad Barr	Solar Absor.	SA Tested	Emitt	Emitt Tested	Deck Insul.	Pitch (deg)
_____	1	Hip	Composition shingles	2024 ft²	0 ft²	Medium	Y	0.96	No	0.9	No	0	26.57

ATTIC

✓	#	Type	Ventilation	Vent Ratio (1 in)	Area	RBS	IRCC
_____	1	Full attic	Vented	300	1810 ft²	Y	N

CEILING

✓	#	Ceiling Type	Space	R-Value	Ins Type	Area	Framing Frac	Truss Type
_____	1	Under Attic (Vented)	Main	38	Double Batt	1900.5 ft²	0.11	Wood

INPUT SUMMARY CHECKLIST REPORT

WALLS

✓ #	Ornt	Adjacent To	Wall Type	Space	Cavity R-Value	Width Ft	In	Height Ft	In	Area	Sheathing R-Value	Framing Fraction	Solar Absor.	Below Grade%
1	W	Exterior	Concrete Block - Int Insul	Main	5	14	8	8		117.3 ft²		0	0.75	0
2	S	Exterior	Concrete Block - Int Insul	Main	5	4		8		32.0 ft²		0	0.75	0
3	W	Exterior	Concrete Block - Int Insul	Main	5	8		8		64.0 ft²		0	0.75	0
4	N	Exterior	Concrete Block - Int Insul	Main	5	4		8		32.0 ft²		0	0.75	0
5	W	Exterior	Concrete Block - Int Insul	Main	5	14	8	8		117.3 ft²		0	0.75	0
6	S	Exterior	Concrete Block - Int Insul	Main	5	49	4	8		394.7 ft²		0	0.75	0
7	E	Exterior	Concrete Block - Int Insul	Main	5	37	4	8		298.7 ft²		0	0.75	0
8	N	Exterior	Concrete Block - Int Insul	Main	5	49	4	8		394.7 ft²		0	0.75	0

DOORS

✓ #	Ornt	Door Type	Space	Storms	U-Value	Width Ft	In	Height Ft	In	Area
1	W	Insulated	Main	None	.46	3		6	8	20 ft²

WINDOWS

Orientation shown is the entered, Proposed orientation.

✓ #	Ornt	Wall ID	Frame	Panes	NFRC	U-Factor	SHGC	Imp	Area	Overhang Depth	Separation	Int Shade	Screening
1	W	1	Vinyl	Low-E Double	Yes	0.36	0.25	N	15.0 ft²	1 ft 6 in	0 ft 6 in	None	None
2	W	5	Vinyl	Low-E Double	Yes	0.36	0.25	N	15.0 ft²	1 ft 6 in	0 ft 6 in	None	None
3	S	6	Vinyl	Low-E Double	Yes	0.36	0.25	N	3.0 ft²	1 ft 6 in	0 ft 6 in	None	None
4	S	6	Vinyl	Low-E Double	Yes	0.36	0.25	N	15.0 ft²	1 ft 6 in	0 ft 6 in	None	None
5	S	6	Vinyl	Low-E Double	Yes	0.36	0.25	N	6.0 ft²	1 ft 6 in	0 ft 6 in	None	None
6	E	7	Vinyl	Low-E Double	Yes	0.36	0.25	N	30.0 ft²	13 ft 6 in	0 ft 6 in	None	None
7	E	7	Metal	Low-E Double	Yes	0.36	0.25	N	40.0 ft²	13 ft 6 in	0 ft 6 in	None	None
8	N	8	Vinyl	Low-E Double	Yes	0.36	0.25	N	30.0 ft²	1 ft 6 in	0 ft 6 in	None	None
9	N	8	Vinyl	Low-E Double	Yes	0.36	0.25	N	12.0 ft²	1 ft 6 in	0 ft 6 in	None	None

INFILTRATION

#	Scope	Method	SLA	CFM 50	ELA	EqLA	ACH	ACH 50
1	Wholehouse	Proposed ACH(50)	.000254	1206.7	66.2	124.29	.098	5

HEATING SYSTEM

✓ #	System Type	Subtype	Speed	Efficiency	Capacity	Block	Ducts
1	Electric Heat Pump/	None	Single	HSPF:8.2	26.94 kBtu/hr	1	sys#1

INPUT SUMMARY CHECKLIST REPORT

COOLING SYSTEM

✓	#	System Type	Subtype	Subtype	Efficiency	Capacity	Air Flow	SHR	Block	Ducts
✓	1	Central Unit/	None	Single	SEER: 14	20.01 kBtu/hr	600 cfm	0.7	1	sys#1

HOT WATER SYSTEM

✓	#	System Type	SubType	Location	EF	Cap	Use	SetPnt	Conservation
✓	1	Propane	None	Exterior	0.59	50 gal	40 gal	120 deg	None

SOLAR HOT WATER SYSTEM

✓	FSEC	Company Name	System Model#	Collector Model#	Collector Area	Storage Volume	FEF
✓	None	None			ft²		

DUCTS

✓	#	Location	Supply R-Value	Supply Area	Location	Return Area	Leakage Type	Air Handler	CFM 25 TOT	CFM25 OUT	QN	RLF	HVAC # Heat	HVAC # Cool
✓	1	Attic	6	452.5 ft²	Attic	90.5 ft²	Default Leakage	Main	(Default)	c(Default)	c		1	1

TEMPERATURES

Programable Thermostat: Y		Ceiling Fans:												
Cooling	☐ Jan	☐ Feb	☐ Mar	☐ Apr	☐ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☐ Oct	☐ Nov	☐ Dec		
Heating	☒ Jan	☒ Feb	☒ Mar	☐ Apr	☐ May	☐ Jun	☐ Jul	☐ Aug	☐ Sep	☐ Oct	☒ Nov	☒ Dec		
Venting	☐ Jan	☐ Feb	☒ Mar	☒ Apr	☐ May	☐ Jun	☐ Jul	☐ Aug	☐ Sep	☒ Oct	☒ Nov	☐ Dec		
Thermostat Schedule: HERS 2006 Reference		Hours												
Schedule Type		1	2	3	4	5	6	7	8	9	10	11	12	
Cooling (WD)	AM	78	78	78	78	78	78	78	78	80	80	80	80	
	PM	80	80	78	78	78	78	78	78	78	78	78	78	
Cooling (WEH)	AM	78	78	78	78	78	78	78	78	78	78	78	78	
	PM	78	78	78	78	78	78	78	78	78	78	78	78	
Heating (WD)	AM	66	66	66	66	66	68	68	68	68	68	68	68	
	PM	68	68	68	68	68	68	68	68	68	68	68	66	
Heating (WEH)	AM	66	66	66	66	66	68	68	68	68	68	68	68	
	PM	68	68	68	68	68	68	68	68	68	68	66	66	

MASS

Mass Type	Area	Thickness	Furniture Fraction	Space
Default(8 lbs/sq.ft.)	0 ft²	0 ft	0.3	1st Floor
Default(8 lbs/sq.ft.)	0 ft²	0 ft	0.3	2nd Floor

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE INDEX* = 83

The lower the EnergyPerformance Index, the more efficient the home.

162 NW CREWS GLEN, LAKE CITY, FL, 32055

1. New construction or existing	New (From Plans)	10. Wall Type and Insulation	Insulation	Area
2. Single family or multiple family	Detached	a. Concrete Block - Int Insul, Exterior	R=5.0	1450.70 ft ²
3. Number of units, if multiple family	1	b. N/A	R=	ft ²
4. Number of Bedrooms	4	c. N/A	R=	ft ²
5. Is this a worst case?	No	d. N/A	R=	ft ²
6. Conditioned floor area (ft ²)	1810	11. Ceiling Type and insulation level	Insulation	Area
7. Windows**	Description	a. Under Attic (Vented)	R=38.0	1900.50 ft ²
a. U-Factor:	DbI, U=0.36	b. N/A	R=	ft ²
SHGC:	SHGC=0.25	c. N/A	R=	ft ²
b. U-Factor:	N/A	12. Ducts, location & insulation level	R	ft ²
SHGC:		a. Sup: Attic, Ret: Attic, AH: Main	6	452.5
c. U-Factor:	N/A			
SHGC:		13. Cooling systems	kBtu/hr	Efficiency
d. U-Factor:	N/A	a. Central Unit	20.0	SEER:14.00
SHGC:				
Area Weighted Average Overhang Depth:	6.560 ft.	14. Heating systems	kBtu/hr	Efficiency
Area Weighted Average SHGC:	0.250	a. Electric Heat Pump	26.9	HSPF:8.20
8. Skylights	Description	15. Hot water systems		
a. U-Factor(AVG):	N/A	a. Propane	Cap: 50 gallons	
SHGC(AVG):	N/A		EF: 0.59	
9. Floor Types	Insulation	b. Conservation features		
a. Slab-On-Grade Edge Insulation	R=0.0	None		
b. N/A	R=	Credits (Performance method)		CV, Pstat
c. N/A	R=			

I certify that this home has complied with the Florida Energy Efficiency Code for Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



*Note: This is not a Building Energy Rating. If your Index is below 70, your home may qualify for energy efficient mortgage (EEM) incentives if you obtain a Florida Energy Rating. For information about the Florida Building Code, Energy Conservation, contact the Florida Building Commission's support staff.

**Label required by Section R303.1.3 of the Florida Building Code, Energy Conservation, if not DEFAULT.

Envelope Leakage Test Report (Blower Door Test)

Residential Prescriptive, Performance or ERI Method Compliance

2020 Florida Building Code, Energy Conservation, 7th Edition

Jurisdiction:	Permit #:
Job Information	
Builder:	Community:
Address: 162 NW CREWS GLEN	
City: LAKE CITY	State: FL
Zip: 32055	
Air Leakage Test Results <i>Passing results must meet either the Performance, Prescriptive, or ERI Method</i>	
☐ PRESCRIPTIVE METHOD -The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.	
☐ PERFORMANCE or ERI METHOD -The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2020 (Performance) or R406-2020 (ERI), section labeled as infiltration, sub-section ACH50. ACH(50) specified on Form R405-2020-Energy Calc (Performance) or R406-2020 (ERI): 5.000	
$\frac{\text{CFM}(50)}{\text{Building Volume}} \times 60 \div \frac{14480}{\text{ACH}(50)} =$ PASS ☐ When ACH(50) is less than 3, Mechanical Ventilation installation must be verified by building department. <u>Method for calculating building volume:</u> ☐ Retrieved from architectural plans ☒ Code software calculated ☐ Field measured and calculated	
R402.4.1.2 Testing. Testing shall be conducted in accordance with ANSI/RESNET/ICC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascals). Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7) <i>Florida Statutes</i> or individuals licensed as set forth in Section 489.105(3)(f), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to the code official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope. During testing: 1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures. 2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures. 3. Interior doors, if installed at the time of the test, shall be open. 4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed. 5. Heating and cooling systems, if installed at the time of the test, shall be turned off. 6. Supply and return registers, if installed at the time of the test, shall be fully open.	
Testing Company	
Company Name: _____ Phone: _____ I hereby verify that the above Air Leakage results are in accordance with the 2020 7th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.	
Signature of Tester: _____ Date of Test: _____	
Printed Name of Tester: _____	
License/Certification #: _____ Issuing Authority: _____	