

DATE 11/03/2010

Columbia County Building Permit
This Permit Must Be Prominently Posted on Premises During Construction**PERMIT**
000028976

APPLICANT JOEL PHINNEY PHONE 867-1499
ADDRESS 120 SW SMITH LN LAKE CITY FL 32024
OWNER TROY JUSTIN LAND PHONE 386-590-1744
ADDRESS 787 NW LOWER SPRINGS RD LAKE CITY FL 32055
CONTRACTOR JOEL PHINNEY PHONE 867-1499
LOCATION OF PROPERTY 90 WEST, R LAKE JEFFERY RD, R LOWER SPRINGS RD, 3/4 MILE ON
JUST PAST SAULSBY GLN ON RIGHT
TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 141100.00
HEATED FLOOR AREA 1911.00 TOTAL AREA 2822.00 HEIGHT 21.00 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB
LAND USE & ZONING AG-3 MAX. HEIGHT 35
Minimum Set Back Requirements: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO. _____

PARCEL ID 01-3S-15-00127-009 SUBDIVISION _____
LOT _____ BLOCK _____ PHASE _____ UNIT _____ TOTAL ACRES 10.29
000001854 CBC1256243
Culvert Permit No. Culvert Waiver Contractor's License Number TC N
CULVERT 10-0441 BK TC N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: FLOOR ONE FOOT ABOVE THE ROAD, NOC ON FILESFD IS BEING CONSTRUCTED ON 00127-009 PARCEL NUMBERCheck # or Cash 1263**FOR BUILDING & ZONING DEPARTMENT ONLY**

(footer/Slab)

Temporary Power _____ date/app. by _____ Foundation _____ date/app. by _____ Monolithic _____ date/app. by _____
Under slab rough-in plumbing _____ date/app. by _____ Slab _____ date/app. by _____ Sheathing/Nailing _____ date/app. by _____
Framing _____ date/app. by _____ Insulation _____ date/app. by _____
Rough-in plumbing above slab and below wood floor _____ date/app. by _____ Electrical rough-in _____ date/app. by _____
Heat & Air Duct _____ date/app. by _____ Peri. beam (Lintel) _____ date/app. by _____ Pool _____ date/app. by _____
Permanent power _____ date/app. by _____ C.O. Final _____ date/app. by _____ Culvert _____ date/app. by _____
Pump pole _____ date/app. by _____ Utility Pole _____ date/app. by _____ M/H tie downs, blocking, electricity and plumbing _____ date/app. by _____
Reconnection _____ date/app. by _____ RV _____ date/app. by _____ Re-roof _____ date/app. by _____

BUILDING PERMIT FEE \$ 710.00 CERTIFICATION FEE \$ 14.11 SURCHARGE FEE \$ 14.11
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$ _____
FLOOD DEVELOPMENT FEE \$ _____ FLOOD ZONE FEE \$ _____ CULVERT FEE \$ 25.00 **TOTAL FEE** 813.22
INSPECTORS OFFICE _____ CLERKS OFFICE _____

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECEIVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECEIVED AN APPROVED INSPECTION WITHIN 180 DAYS OF THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

For Office Use Only Application # 1009-42 Date Received 9/21/10 By G Permit # 1854/28976
 Zoning Official BK Date 27.09.10 Flood Zone X Land Use A-3 Zoning A-3
 FEMA Map # N/A Elevation N/A MFE 1' above River N/A Plans Examiner T.C. Date 9-24-10
 Comments House is being constructed on 00127-009 parcel #
☒ NOC ☒ EH ☐ Deed or PA ☐ Site Plan ☐ State Road Info ☐ Parent Parcel # 1 ☒ Letter to Sign Authorized Person
☐ Dev Permit # ☐ In Floodway ☒ Letter of Auth. from Contractor ☐ F W Comp. letter
 IMPACT FEES: EMS Fire Corr Road/Code 14UF
 School = TOTAL N/A Suspended Existing well

Septic Permit No. 10-0441Fax 752-2282Name Authorized Person Signing Permit Joel PhinneyPhone 252-2281Address 120 SW Smith LnOwners Name Troy Justin LandPhone 386-590-1744911 Address 787 NW Lower Springs Rd Lake City FL 32055Contractors Name Joel PhinneyPhone 867-1499Address 120 SW Smith Lane Lake City FL 32024Fee Simple Owner Name & Address NABonding Co. Name & Address NAArchitect/Engineer Name & Address Jonathan Morris Nick GeislerMortgage Lenders Name & Address First Federal BankCircle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progress EnergyProperty ID Number 01-35-15-00127-009 Estimated Cost of Construction 183 KSubdivision Name Lot Block Unit Phase Driving Directions 90 West, Turn R on Lake Jeffery Rd, cross I-75
turn R on Lower Springs Rd 3/4 mile on R past Salsby RdNumber of Existing Dwellings on Property 0Construction of Single family dwellingTotal Acreage 10.89 Lot Size Do you need a Culvert Permit or Culvert Waiver or Have an Existing DriveTotal Building Height 2' 1"Actual Distance of Structure from Property Lines - Front 339' Side 367' Side 143' Rear 286'Number of Stories 1 Heated Floor Area 1911 Total Floor Area 2822 Roof Pitch 6-12

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standard of all laws regulating construction in this jurisdiction.

Columbia County Building Permit Application

TIME LIMITATIONS OF APPLICATION : An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

TIME LIMITATIONS OF PERMITS: Every permit issued shall become invalid unless the work authorized by such permit is commenced within 180 days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous approved inspection.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment: According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE: **YOU ARE HEREBY NOTIFIED** as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I CERTIFY THAT ALL THE FOREGOING INFORMATION IS ACCURATE AND THAT ALL WORK WILL BE DONE IN COMPLIANCE WITH ALL APPLICABLE LAWS REGULATING CONSTRUCTION AND ZONING.

NOTICE TO OWNER: There are some properties that may have deed restrictions recorded upon them. These restrictions may limit or prohibit the work applied for in your building permit. It may be to your advantage to check and see if your property is encumbered by any restrictions.

(Owners Must Sign All Applications Before Permit Issuance.)

Owners Signature _____

****OWNER BUILDERS MUST PERSONALLY APPEAR AND SIGN THE BUILDING PERMIT.**

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit including all application and permit time limitations.


Contractor's Signature (Permitee) _____

Contractor's License Number CBC #1256243
Columbia County
Competency Card Number _____

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 3rd day of August 2010.
Personally known ☒ or Produced Identification _____

State of Florida Notary Signature (For the Contractor) _____

SEAL:



SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER _____

CONTRACTOR

Skylar Homes, Inc

PHONE

386-754-6667

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is REQUIRED that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL <u>OK</u> High Springs Plumbing Electric	Print Name <u>Donald R Davis</u> License #: <u>EC0002306</u>	Signature <u>Donald R Davis</u> Phone #: <u>386 623 0499</u>
MECHANICAL/A/C <u>OK</u>	Print Name <u>Separate Sheet</u> License #:	Signature _____ Phone #:
PLUMBING/GAS <u>OK</u>	Print Name <u>SUWANNEE PLMG</u> License #: <u>CFC1426088</u>	Signature <u>Fred Russell</u> Phone #: <u>386-208-5199</u>
ROOFING <u>OK</u> <u>494</u>	Print Name <u>Caleb Laughlin</u> License #: <u>CCC1327718</u>	Signature <u>[Signature]</u> Phone #: <u>386-752-4022</u>

SHEET METAL <u>X</u>	Print Name <u>Non</u> License #:	Signature _____ Phone #:
FIRE SYSTEM/SPRINKLER <u>X</u>	Print Name <u>Non</u> License #:	Signature _____ Phone #:
SOLAR <u>X</u>	Print Name <u>Non</u> License #:	Signature _____ Phone #:

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON	<u>Separate Sheet</u>		
CONCRETE FINISHER	<u>Separate Sheet</u>		
<u>OK</u> FRAMING	<u>OK</u> 000804	<u>Brian North Fla Tim</u>	<u>[Signature]</u>
<u>OK</u> INSULATION	000628	<u>Bobby O Jackson</u>	<u>Bobby Jackson</u>
STUCCO	<u>NIA</u>		
<u>OK</u> DRYWALL	000627	<u>Bobby O Jackson</u>	<u>Bobby Jackson</u>
PLASTER	<u>NIA</u>		
<u>OK</u> CABINET INSTALLER	<u>OK</u> C061256243	<u>Joel Phinney</u>	<u>[Signature]</u>
<u>OK</u> PAINTING	1016 <u>↓</u>	<u>↓</u>	<u>[Signature]</u>
ACOUSTICAL CEILING	<u>Non</u>		
GLASS	<u>Separate Sheet</u>		
<u>OK</u> CERAMIC TILE	<u>OK</u> C061256243	<u>Joel Phinney</u>	<u>[Signature]</u>
<u>OK</u> FLOOR COVERING	1016 <u>↓</u>	<u>↓</u>	<u>[Signature]</u>
ALUM/VINYL SIDING			
<u>OK</u> GARAGE DOOR	<u>OK</u> 000873	<u>Dale R. Nickelson dba Evergreen Building Products</u>	<u>Dale R. Nickelson</u>
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

1007-42
Sep. 21. 2010 10:01AM

No. 40261 P. 2/2

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER _____ CONTRACTOR _____ PHONE _____

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
MECHANICAL/ A/C	Print Name <u>Benn I Jones Jr</u> License #: <u>CAC051486</u>	Signature <u>[Signature]</u> Phone #: <u>386-782-5389</u>
PLUMBING/ GAS	Print Name _____ License #: _____	Signature _____ Phone #: _____
ROOFING	Print Name _____ License #: _____	Signature _____ Phone #: _____
SHEET METAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION			
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS	122	Richard Bennett	[Signature]
CERAMIC TILE			
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; Identification of minimum premium policy.—Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

Contractor Permit Subcontractor form 5/09

roy curve

BOUNDARY SURVEY
IN SECTION 1, TOWNSHIP 3 SOUTH, RANGE 15 EAST
COLUMBIA COUNTY, FLORIDA

DESCRIPTION:

P.O.B. 118E, PG. 2170
of the NW 1/4 and the SW 1/4 of the NE 1/4 of Section 1, Township 9 South, Range 16 East, Columbia County, Florida, more particularly described as follows: COMMENCE at the NW Corner of the NW 1/4 of said Section 1 and run S 89° 24' E, 153.5 feet along the North boundary of said Section 1 to the corner of the SE 1/4 of the NW 1/4 of the westernly 1/3 of the NW 1/4 of the NE 1/4 of said Section 1; thence N 1° 16' E, 320.28 feet along said East line, Thence S 51° 41' N, 668.13 feet to a point on the Northeastern boundary of said Section 1 which intersects the West line of said Section 1; thence Right-of-Way line of lower Spring Road, bearing N 31° 16' E, 304.92 feet to the POINT OF BEGINNING.

1500

[illegible]

NOTES:

- 1) Memorandum is as shown and designated on the face of the plat.
- 2) Boundary based on measurements taken in place, descriptions furnished by C-61, plat survey by J. Bennett, Inc., and other prior survey by County.
- 3) Survey prepared from lot, property line and based on older referenced survey.
- 4) Historic improvements, if present, were not located with this survey.
- 5) Geologic cross-sections, if present, were not located with this survey.
- 6) The survey was made under benefit of a 100 acre survey, the County of Columbia County, Oregon, and the same is subject to the same. The public records shows recording this, and that all zoning, easements & other interests are shown and are not shown. The survey is subject to all other interests only as related with a title search.
- 7) Date of field survey completion: April 13, 2010
- 8) Examination of the Flood Insurance Rate Map (FIRM) for Columbia County shows that, per and more, the described parcel is within Flood Hazard Zone 100. The Flood Insurance Rate Map is on file at the County Recorder's Office. Map No. 1202200100.
- 9) A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 10) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 11) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 12) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 13) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 14) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 15) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 16) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 17) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 18) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 19) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.
- 20) The A3121 Easement, recorded in 010 Book 616, Page 26, of the Public Records of Columbia County, Oregon, does not affect this parcel, based on the survey.

First Federal Bank of Florida
North Central Florida Title
Old Republic National Title Insurance Company

REVISOR: 05/11/2010 Legal Updates & Surveyor's Note removed.

Donald F. Lee and Associates, Inc. PUBLISHED

 **SURVEYORS - ENGINEERS**
140 Northwest Ridgewood Avenue, Lake City, Florida 32053
Phone: (386) 755-6165 FAX: (386) 755-6167

Date: 04/23/2010	Scale: 1"=50'
------------------	---------------

TROY LAND	
Work Order: 09-5316	
Folio: 09-580	

DocId: 140	File: 8-26-42-
------------	----------------

100

This Instrument Prepared by & return to:

Name: **TRISH LANG, an employee of
NORTH CENTRAL FLORIDA TITLE,
LLC**
Address: **343 NW COLE TERRACE, SUITE 101
LAKE CITY, FLORIDA 32055
File No. 10Y-04011TL**

Instr: 201012014130 Date: 9/1/2010 Time: 11:25 AM
Doc Stamp: Deed 0.70
DC, P. DeWitt Cason, Columbia County Page 1 of 2 B:1200 P:1620

Parcel I.D. #: **00127-008 & 009**

SPACE ABOVE THIS LINE FOR PROCESSING DATA

SPACE ABOVE THIS LINE FOR RECORDING DATA

THIS WARRANTY DEED Made the 1ST day of **SEPTEMBER, A.D. 2010**, by **JUSTIN TROY LAND, A SINGLE PERSON**, hereinafter called the grantor, to **JUSTIN TROY LAND, A SINGLE PERSON**, whose post office address is **13508 120TH STREET, LIVE OAK, FLORIDA 32060**, hereinafter called the grantee

(Wherever used herein the terms "grantor" and "grantee" include all the parties to this instrument, singular and plural, the heirs, legal representatives and assigns of individuals, ad the successors and assigns of corporations, wherever the context so admits or requires.)

Witnesseth: That the grantor, for and in consideration of the sum of \$10.00 and other valuable consideration, receipt whereof is hereby acknowledged, does hereby grant, bargain, sell, alien, remise, release, convey and confirm unto the grantee all that certain land situate in **Columbia County, State of Florida**, viz:

PARCEL A

A PART OF THE NE ¼ OF NW ¼ AND THE NW ¼ OF NE ¼ OF SECTION 1, TOWNSHIP 3 SOUTH, RANGE 15 EAST, COLUMBIA COUNTY, FLORIDA, MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE NE CORNER OF THE NW ¼ OF SAID SECTION 1, AND RUN S 89°59'44" E, 443.62 FEET ALONG THE NORTH LINE OF SAID SECTION 1; THENCE S 00°57'04" W, 268.13 FEET ALONG THE EAST LINE OF THE WESTERLY 1/3 OF THE NW ¼ OF NE ¼ OF SAID SECTION 1 TO THE POINT OF BEGINNING; THENCE CONTINUE S 00°57'04" W, 369.28 FEET ALONG SAID EAST LINE; THENCE S 51°44'16" W, 665.13 FEET TO A POINT ON THE NORTHEASTERLY MAINTAINED RIGHT OF WAY LINE OF LOWER SPRINGS ROAD; THENCE N 39°31'47" W, 286.18 FEET ALONG SAID RIGHT OF WAY LINE; THENCE N 51°44'16" E, 904.92 FEET TO THE POINT OF BEGINNING.

AND ALSO

PARCEL B

A PART OF THE NORTHEAST ¼ OF THE NORTHWEST ¼ AND THE NORTHWEST ¼ OF THE NORTHEAST ¼ OF SECTION 1, TOWNSHIP 3 SOUTH, RANGE 15 EAST, COLUMBIA COUNTY, FLORIDA, MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE NORTHEAST CORNER OF THE NORTHWEST ¼ OF SAID SECTION 1, AND RUN SOUTH 89°59'44" EAST, 416.89 FEET ALONG THE NORTH LINE OF SAID SECTION 1 TO THE POINT OF BEGINNING; THENCE CONTINUE SOUTH 89°59'44" EAST, 26.73 FEET ALONG THE NORTH LINE OF SAID SECTION 1; THENCE SOUTH 00°57'04" WEST, 268.13 FEET ALONG THE EAST LINE OF THE WESTERLY 1/3 OF THE NORTHWEST ¼ OF THE NORTHEAST ¼ OF SAID SECTION 1; THENCE SOUTH 51°44'16" WEST, 904.92 FEET TO A POINT ON THE NORTHEASTERLY MAINTAINED RIGHT OF WAY LINE OF LOWER SPRINGS ROAD; THENCE NORTH 39°31'47" WEST, 224.36 FEET ALONG SAID NORTHEASTERLY RIGHT OF WAY; THENCE NORTH 51°59'44" EAST, 1,058.41 FEET TO THE POINT OF BEGINNING.


Together with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.

To Have and to Hold the same in fee simple forever.


And the grantor hereby covenants with said grantee that he is lawfully seized of said land in fee simple; that he has good right and lawful authority to sell and convey said land, and hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever, and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2009.

In Witness Whereof, the said grantor has signed and sealed these presents, the day and year first above written.


Signed, sealed and delivered in the presence of:


Witness Signature Regina Simpkins

Printed Name


Witness Signature PATRICIA LANG


Printed Name

 L.S.
JUSTIN TROY LAND
Address: 13508 120TH STREET, LIVE OAK,
FLORIDA 32060

STATE OF FLORIDA
COUNTY OF COLUMBIA

The foregoing instrument was acknowledged before me this 1ST day of SEPTEMBER, 2010, by JUSTIN TROY LAND, who is known to me or who has produced Driver's License as identification.


Notary Public Regina Simpkins
My commission expires 1-4-13



COLUMBIA COUNTY 9-1-1 ADDRESSING

P. O. Box 1787, Lake City, FL 32056-1787

PHONE: (386) 758-1125 • FAX: (386) 758-1365 • Email: ron_croft@columbiacountyfla.com

Addressing Maintenance

To maintain the Countywide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE REQUESTED: 7/29/2010 DATE ISSUED: 8/2/2010

ENHANCED 9-1-1 ADDRESS:

787 NW LOWER SPRINGS RD

LAKE CITY FL 32055

PROPERTY APPRAISER PARCEL NUMBER:

01-3S-15-00127-009

Remarks:

Address Issued By:



Columbia County 9-1-1 Addressing / GIS Department

NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION INFORMATION BE FOUND TO BE IN ERROR, THIS ADDRESS IS SUBJECT TO CHANGE.

THIS INSTRUMENT PREPARED BY
AND RETURN TO:
NORTH CENTRAL FLORIDA TITLE, LLC
343 NW COLE TERRACE
SUITE 101
LAKE CITY, FLORIDA 32055

Parcel I.D. #: 00127-008 & 009
Permit No.

Inst: 201012011277 Date: 7/15/2010 Time: 3:21 PM
DC, P. DeWitt Cason, Columbia County Page 1 of 2 B: 1197 P: 2419

SPACE ABOVE THIS LINE FOR PROCESSING DATA

SPACE ABOVE THIS LINE FOR RECORDING DATA

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF COLUMBIA

THE UNDERSIGNED hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement. This Notice shall be void and of no force and effect if construction is not commenced within ninety (90) days after recordation.

1. Description of property: (Legal description of property, and street address if available)

TBD NW LOWER SPRINGS ROAD, LAKE CITY, FLORIDA 32055
PARCEL A

A PART OF THE NE ¼ OF NW ¼ AND THE NW ¼ OF NE ¼ OF SECTION 1, TOWNSHIP 3 SOUTH, RANGE 15 EAST, COLUMBIA COUNTY, FLORIDA, MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE NE CORNER OF THE NW ¼ OF SAID SECTION 1, AND RUN S 89°59'44" E, 443.62 FEET ALONG THE NORTH LINE OF SAID SECTION 1; THENCE S 00°57'04" W, 268.13 FEET ALONG THE EAST LINE OF THE WESTERLY 1/3 OF THE NW ¼ OF NE ¼ OF SAID SECTION 1 TO THE POINT OF BEGINNING; THENCE CONTINUE S 00°57'04" W, 369.28 FEET ALONG SAID EAST LINE; THENCE S 51°44'16" W, 665.13 FEET TO A POINT ON THE NORTHEASTERLY MAINTAINED RIGHT OF WAY LINE OF LOWER SPRINGS ROAD; THENCE N 39°31'47" W, 286.18 FEET ALONG SAID RIGHT OF WAY LINE; THENCE N 51°44'16" E, 904.92 FEET TO THE POINT OF BEGINNING.

AND ALSO

PARCEL B

A PART OF THE NORTHEAST ¼ OF THE NORTHWEST ¼ AND THE NORTHWEST ¼ OF THE NORTHEAST ¼ OF SECTION 1, TOWNSHIP 3 SOUTH, RANGE 15 EAST, COLUMBIA COUNTY, FLORIDA, MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCE AT THE NORTHEAST CORNER OF THE NORTHWEST ¼ OF SAID SECTION 1, AND RUN SOUTH 89°59'44" EAST, 416.89 FEET ALONG THE NORTH LINE OF SAID SECTION 1 TO THE POINT OF BEGINNING; THENCE CONTINUE SOUTH 89°59'44" EAST, 26.73 FEET ALONG THE NORTH LINE OF SAID SECTION 1; THENCE SOUTH 00°57'04" WEST, 268.13 FEET ALONG THE EAST LINE OF THE WESTERLY 1/3 OF THE NORTHWEST ¼ OF THE NORTHEAST ¼ OF SAID SECTION 1; THENCE SOUTH 51°44'16" WEST, 904.92 FEET TO A POINT ON THE NORTHEASTERLY MAINTAINED RIGHT OF WAY LINE OF LOWER SPRINGS ROAD; THENCE NORTH 39°31'47" WEST, 224.36 FEET ALONG SAID NORTHEASTERLY RIGHT OF WAY; THENCE NORTH 51°59'44" EAST, 1,058.41 FEET TO THE POINT OF BEGINNING.

2. General description of improvement: CONSTRUCTION OF A SINGLE FAMILY DWELLING

3. Owner information:

- a. Name and address:
JUSTIN TROY LAND
13508 120TH STREET, LIVE OAK, FLORIDA 32060
- b. Interest in property: Fee Simple
- c. Name and Address of Fee Simple Titleholder (if other than owner):

4. Contractor: (Name and Address)

SKYLINE HOMES, INC.
120 SW SMITH LANE, LAKE CITY, FLORIDA 32024
Telephone Number: 386-867-1499

5. Surety (if any):

- a. Name and Address:
Telephone Number: _____
- b. Amount of Bond \$ _____

6. Lender: (Name and Address)


FIRST FEDERAL BANK OF FLORIDA
4705 WEST U.S. HWY 90, P.O. BOX 2029, LAKE CITY, FL 32056
Telephone Number: 755-0600

Telephone Number: 755-0600

7. Persons within the State of Florida designated by Owner upon whom notice or other documents may be served as provided by Section 713.13(1)(a)(7), Florida Statutes: (Name and Address)
N/A
8. In addition to himself, Owner designates the following person(s) to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes: (Name and Address)
FIRST FEDERAL BANK OF FLORIDA
4705 WEST U.S. HWY 90, P.O. BOX 2029, LAKE CITY, FL 32056
Telephone Number: 755-0600
9. Expiration date of Notice of Commencement (the expiration date is 1 year from the date of recording unless a different date is specified) _____

WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.


Signature of Owner(s) or Owner's Authorized Officer/Director/Partner/Manager:


JUSTIN TROY LAND {SEAL}

_____{SEAL}

The foregoing instrument was acknowledged before me this 13th day of July, 2010, by JUSTIN TROY LAND, who is personally known to me or who has produced

as identification.


Notary Public
My Commission Expires: 12-14-10



PATRICIA H. LANG
Commission DD 622516
Expires December 14, 2010
Bonded Third Party Fidelity Insurance 800-985-7019

10-12-10;12:13PM

LINDA RODER

#386 758-2187

1/ 2



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM

PERMIT #: **12-SC-1279901**
APPLICATION #: **AP979474**
DATE PAID: **9/21/10**
FEE PAID: **310.00**
RECEIPT #: **1494738**
DOCUMENT #: **PR823980**

CONSTRUCTION PERMIT FOR: OSTDS NewAPPLICANT: TROY-10-0441 LANDPROPERTY ADDRESS: LOWER SPRINGS Rd Lake City, FL 32055

LOT: _____ BLOCK: _____ SUBDIVISION: _____

PROPERTY ID #: 00127-008/009[SECTION, TOWNSHIP, RANGE, PARCEL NUMBER]
[OR TAX ID NUMBER]

SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATIONS AND STANDARDS OF SECTION 381.0065, F.S., AND CHAPTER 64E-6, F.A.C. DEPARTMENT APPROVAL OF SYSTEM DOES NOT GUARANTEE SATISFACTORY PERFORMANCE FOR ANY SPECIFIC PERIOD OF TIME. ANY CHANGE IN MATERIAL FACTS, WHICH SERVED AS A BASIS FOR ISSUANCE OF THIS PERMIT, REQUIRE THE APPLICANT TO MODIFY THE PERMIT APPLICATION. SUCH MODIFICATIONS MAY RESULT IN THIS PERMIT BEING MADE NULL AND VOID. ISSUANCE OF THIS PERMIT DOES NOT EXEMPT THE APPLICANT FROM COMPLIANCE WITH OTHER FEDERAL, STATE, OR LOCAL PERMITTING REQUIRED FOR DEVELOPMENT OF THIS PROPERTY.

SYSTEM DESIGN AND SPECIFICATIONS

T [900] GALLONS / GPD Septic CAPACITY
A [] GALLONS / GPD N/A CAPACITY
N [] GALLONS GREASE INTERCEPTOR CAPACITY [MAXIMUM CAPACITY SINGLE TANK:1250 GALLONS]
K [] GALLONS DOSING TANK CAPACITY [] GALLONS @ [] DOSES PER 24 HRS #Pumps []

D [375] SQUARE FEET Drainfield SYSTEMR [] SQUARE FEET N/A SYSTEM

A TYPE SYSTEM: [X] STANDARD [] FILLED [] MOUND []

I CONFIGURATION: [X] TRENCH [] BED []

F LOCATION OF BENCHMARK: Nail in 6" post South of system site.I ELEVATION OF PROPOSED SYSTEM SITE [60.00] [INCHES] FT [] ABOVE / BELOW BENCHMARK/REFERENCE POINTE BOTTOM OF DRAINFIELD TO BE [84.00] [INCHES] FT [] ABOVE / BELOW BENCHMARK/REFERENCE POINT

L

D FILL REQUIRED: [0.00] INCHES EXCAVATION REQUIRED: [0.00] INCHES

The licensed contractor installing the system is responsible for installing the minimum category of tank in accordance with s. 64E-6.013(3)(f), FAC.

SPECIFICATIONS BY: PAUL LLOYDTITLE: PSEAPPROVED BY: Jeremy K GiffordTITLE: Environmental Specialist I

Columbia CHD

DATE ISSUED: 08/08/2010EXPIRATION DATE: 04/08/2012

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)

Incorporated: 64E-6.003, FAC

Page 1 of 3

v 1.1.4

AP979474

SE827136

New Construction Subterranean Termite Service Record

OMB Approval No. 2502-0525
(exp. 02/29/2012)

This form is completed by the licensed Pest Control Company.

28976

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential, therefore, no assurance of confidentiality is provided.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Company and builder, unless stated otherwise.

Section 1: General Information (Pest Control Company Information)

Company Name Aspen Pest Control, Inc.
Company Address P.O. Box 1795 City Lake City State FL Zip 32058
Company Business License No. JB109476 Company Phone No. 386-755-3611
FHA/VA Case No. (if any) _____

Section 2: Builder Information

Company Name Skyline Homes Phone No. 867-1499

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) Troy Justin Land
181 NW Lower Springs Rd Lake City, FL 32055

Section 4: Service Information

Date(s) of Service(s) 12-1-2010
Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____

Check all that apply:

- ☒ A. Soil Applied Liquid Termiticide
Brand Name of Termiticide: Maxx-Thor EPA Registration No. 83925-6
Approx. Dilution (%): .06 Approx. Total Gallons Mix Applied: 400 Treatment completed on exterior: ☐ Yes ☒ No
- ☐ B. Wood Applied Liquid Termiticide
Brand Name of Termiticide: _____ EPA Registration No. _____
Approx. Dilution (%): _____ Approx. Total Gallons Mix Applied: _____
- ☐ C. Bait System Installed
Name of System _____ EPA Registration No. _____ Number of Stations Installed _____
- ☐ D. Physical Barrier System Installed
Name of System _____ Attach installation information (required)

Service Agreement Available? ☒ Yes ☐ No

Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____

Comments _____

Name of Applicator(s) C. Lacey Certification No. (if required by State law) JB104376

The applicator has used a product in accordance with the product label and state requirements. All materials and methods used comply with state and federal regulations.

Authorized Signature [Signature] Date 12-1-2010

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form NPCA-99-B may still be used

Reorder Product #2581 From CROWNMAX • 1-800-252-4011

form HUD-NPMA-99-B

Sep. 14. 2010 3:48PM

SUBCONTRACTOR VERIFICATION FORM

Permit # 28976 APPLICATION NUMBER CONTRACTOR Joel Phinney PHONE 386-867-1499

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
MECHANICAL/ A/C	Print Name _____ License #: _____	Signature _____ Phone #: _____
PLUMBING/ GAS	Print Name _____ License #: _____	Signature _____ Phone #: _____
ROOFING 1095 ✓	Print Name <u>ANTHONY SULLIVAN</u> License #: <u>CC 1226257 / CC 1252728</u>	Signature _____ Phone #: <u>386-362-2597</u>
SHEET METAL 1096 ✓	Print Name <u>ANTHONY SULLIVAN</u> License #: <u>CC 1226257 / CC 1252728</u>	Signature _____ Phone #: <u>386-362-2597</u>
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION			
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE			
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; Identification of minimum premium policy.—Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

Contractor Forms; Subcontractor Forms 6/09

Permit

SUBCONTRACTOR VERIFICATION FORM

NUMBER

28976

CONTRACTOR

JOEL WINNEY

PHONE

867-1499

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
MECHANICAL/ A/C	Print Name <u>Glenn T. Jones Inc.</u> License #: <u>CACB 51486</u>	Signature <u>[Signature]</u> Phone #: <u>386-782-5389</u>
PLUMBING/ GAS	Print Name _____ License #: _____	Signature _____ Phone #: _____
ROOFING	Print Name _____ License #: _____	Signature _____ Phone #: _____
SHEET METAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION			
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE			
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

Permit

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER

28976

CONTRACTOR

Joel Philiney

PHONE

386 781 1499

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
MECHANICAL/ A/C _____	Print Name _____ License #: _____	Signature _____ Phone #: _____
PLUMBING/ GAS	Print Name _____ License #: _____	Signature _____ Phone #: _____
ROOFING	Print Name _____ License #: _____	Signature _____ Phone #: _____
SHEET METAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION			
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE ✓	1044	Amos Rimert LLC	[Signature]
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

Permit 28976

SUBCONTRACTOR VERIFICATION FORM

APPLICATION NUMBER

CONTRACTOR

Joe Phinney

PHONE

386-867-1499

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is **REQUIRED** that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
MECHANICAL/ A/C _____	Print Name _____ License #: _____	Signature _____ Phone #: _____
PLUMBING/ GAS	Print Name _____ License #: _____	Signature _____ Phone #: _____
ROOFING	Print Name _____ License #: _____	Signature _____ Phone #: _____
SHEET METAL	Print Name _____ License #: _____	Signature _____ Phone #: _____
FIRE SYSTEM/ SPRINKLER	Print Name _____ License #: _____	Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____	Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION	000957	PATSY BOWEN	Patsy Bowen
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE			
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; Identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

Contractor Form: Subcontractor form: 6/09

COLUMBIA COUNTY OFFICE OF THE CLERK

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 01-3S-15-00127-009

Building permit No. 000028976

Use Classification SFD, UTILITY

Fire: 25.68

Permit Holder JOEL PHINNEY

Waste: 67.00

Owner of Building TROY JUSTIN LAND

Total: 92.68

Location: 787 NW LOWER SPRINGS ROAD, LAKE CITY, FL 32055

Date: 06/30/2011

Joey C.

Building Inspector



POST IN A CONSPICUOUS PLACE
(Business Places Only)

D.H.N. CORNIE "RUSH"

**Columbia County Building Department
Culvert Waiver****Culvert Waiver No.
000001854**

DATE: 06/28/2011

BUILDING PERMIT NO. 28976

APPLICANT JOEL PHINNEY

PHONE 867-1499

ADDRESS 120 SW SMITH LN

LAKE CITY

FL 32024

OWNER TROY JUSTIN LAND

PHONE 386-590-1744

ADDRESS 787 NW LOWER SPRINGS RD

LAKE CITY

FL 32055

CONTRACTOR JOEL PHINNEY

PHONE 867-1499


LOCATION OF PROPERTY 90 WEST, R LAKE JEFFERY RD, R LOWER SPRINGS RD, 3/4 MILE ON RIGHT

JUST PAST SAULSBY GLN ON RIGHT.

SUBDIVISION/LOT/BLOCK/PHASE/UNIT

PARCEL ID # 01-3S-15-00127-009

I HEREBY CERTIFY THAT I UNDERSTAND AND WILL FULLY COMPLY WITH THE DECISION OF THE COLUMBIA
COUNTY PUBLIC WORKS DEPARTMENT IN CONNECTION WITH THE HEREIN PROPOSED APPLICATION.

SIGNATURE: 

A SEPARATE CHECK IS REQUIRED
MAKE CHECKS PAYABLE TO BCC

Amount Paid 50.00

PUBLIC WORKS DEPARTMENT USE ONLY


I HEREBY CERTIFY THAT I HAVE EXAMINED THIS APPLICATION AND DETERMINED THAT THE
CULVERT WAIVER IS:



APPROVED

NOT APPROVED - NEEDS A CULVERT PERMIT

COMMENTS:

SIGNED: 

DATE: 29 June 11

ANY QUESTIONS PLEASE CONTACT THE PUBLIC WORKS DEPARTMENT AT 386-752-5955.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160



Joel: 24N. Connie 11/25/11
**Columbia County Building Department
Culvert Waiver**

**Culvert Waiver No.
000001854**

DATE: 06/28/2011

BUILDING PERMIT NO. 28976

APPLICANT JOEL PHINNEY PHONE 867-1499

ADDRESS 120 SW SMITH LN LAKE CITY FL 32024

OWNER TROY JUSTIN LAND PHONE 386-590-1744

ADDRESS 787 NW LOWER SPRINGS RD LAKE CITY FL 32055

CONTRACTOR JOEL PHINNEY PHONE 867-1499

LOCATION OF PROPERTY 90 WEST, R LAKE JEFFERY RD, R LOWER SPRINGS RD, 3/4 MILE ON RIGHT
JUST PAST SAULSBY GLN ON RIGHT.

SUBDIVISION/LOT/BLOCK/PHASE/UNIT _____

PARCEL ID # 01-3S-15-00127-009

I HEREBY CERTIFY THAT I UNDERSTAND AND WILL FULLY COMPLY WITH THE DECISION OF THE COLUMBIA
COUNTY PUBLIC WORKS DEPARTMENT IN CONNECTION WITH THE HEREIN PROPOSED APPLICATION.

SIGNATURE: *[Signature]*

A SEPARATE CHECK IS REQUIRED
MAKE CHECKS PAYABLE TO BCC

Amount Paid 50.00

PUBLIC WORKS DEPARTMENT USE ONLY

I HEREBY CERTIFY THAT I HAVE EXAMINED THIS APPLICATION AND DETERMINED THAT THE
CULVERT WAIVER IS:

APPROVED _____ NOT APPROVED - NEEDS A CULVERT PERMIT

COMMENTS: _____

SIGNED: _____ DATE: _____

ANY QUESTIONS PLEASE CONTACT THE PUBLIC WORKS DEPARTMENT AT 386-752-5955.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160





Builders Statement

InsulSafe® SP Fiber Glass Blowing Insulation

#28976

Troy Land

Homeowner Name / Jobsite Name

787 NW Lower Springs Rd

Home Address

Thomas

Installer / Contractor (sign)

Company Name

Date

Builder (sign)

Company Name

Date

Inspected By (sign if required)

Date

OPEN ATTIC APPLICATION

R-VALUE	MINIMUM BAGS PER 1000 SQ. FT.	MAXIMUM NET SQ. FT. PER BAG COVERAGE	MINIMUM WEIGHT— POUNDS PER SQ. FT.	MINIMUM INSTALLED THICKNESS	MINIMUM SETTLED THICKNESS
To obtain a thermal resistance (R) of:	Bags per 1000 sq. ft. of net area:	Contents of bag shall not cover more than: (sq. ft.)	Weight per sq. ft. of installed insulation shall not be less than: (lbs.)	Installed insulation shall not be less than: (in.)	Minimum settled insulation shall not be less than: (in.)
60	31.4	31.9	0.972	22.00	22.00
49	25.2	39.7	0.780	18.50	18.50
44	22.4	44.6	0.695	16.75	16.75
38	19.1	52.5	0.591	14.50	14.50
<u>30</u>	14.9	67.1	0.462	<u>11.75</u>	11.75
26	12.8	77.9	0.398	10.25	10.25
22	10.8	92.9	0.334	8.75	8.75
19	9.3	107.4	0.289	7.75	7.75
13	6.2	161.7	0.192	5.25	5.25
11	5.3	190.5	0.163	4.50	4.50

	R-VALUE	THICKNESS	NET AREA (SQ. FT.)	INSULSAFE SP (✓)	BAGS USED	BATTS/ROLLS (✓)
CEILINGS	30	11.75	1730	✓	28	X
WALLS						
FLOORS						

THERMAL PERFORMANCE—ATTIC BLOWING APPLICATION

- In accordance with the chart above, you must install the minimum number of bags per 1,000 sq. ft. of net area for each R-Value listed.
- The maximum net coverage must not exceed that specified for each R-Value.
- The insulation must be installed at or above the specified installed thickness for each R-Value.
- Failure to install the required minimum weight per sq. ft. of insulation at or above the initial installed thickness will result in reduced R-Value.
- This product should not be mixed with other blown insulations or the thermal claims will become invalid.

DANGER: RECESSED LIGHT FIXTURES—TO PREVENT OVERHEATING, DO NOT INSULATE ON TOP OR WITHIN 3" OF SUCH DEVICES. THIS WARNING DOES NOT APPLY TO TYPE IC LIGHT FIXTURES OR TO FLUORESCENT FIXTURES WITH THERMALLY PROTECTED BALLASTS.



COLUMBIA COUNTY BUILDING DEPARTMENT RESIDENTIAL CHECK LIST REQUIREMENTS

MINIMUM PLAN REQUIREMENTS FOR THE FLORIDA BUILDING CODE RESIDENTIAL 2007 ONE (1) AND TWO (2) FAMILY DWELLINGS

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

ALL BUILDING PLANS MUST INDICATE COMPLIANCE with the Current 2007 FLORIDA BUILDING CODES RESIDENTIAL. ALL PLANS OR DRAWINGS SHALL PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FIGURE R301.2(4) of the FLORIDA BUILDING CODES RESIDENTIAL (Florida Wind speed map) SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

GENERAL REQUIREMENTS APPLICANT MUST CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		If not include If not possible If not applicable
---	--	---

			Yes	No	N/A
1	Two (2) complete sets of plans containing the following:		☒		
2	All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void		☒		
3	Condition space (Sq. Ft.)	Total (Sq. Ft.) under roof	IIIIII	IIIIII	IIII

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL R101.2.1

Site Plan information including:

4	Dimensions of lot or parcel of land	☒		
5	Dimensions of all building set backs	☒		
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.	☒		
7	Provide a full legal description of property.	☒		

Wind-load Engineering Summary, calculations and any details required

GENERAL REQUIREMENTS		Indicate include, exclude, or not applicable		
APPLICANT MUST CHECK ALL APPLICABLE BOXES BEFORE SUBMITTING		IIIII	IIII	IIIII
		YES	NO	N/A
8	Plans or specifications must show compliance with FBCR Chapter 3	☒		
9	Basic wind speed (3-second gust), miles per hour			
10	(Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated)	☒		
11	Wind importance factor and nature of occupancy	☒		
12	The applicable internal pressure coefficient, Components and Cladding	☒		
13	The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component, cladding materials not specifically designed by the registered design professional.	☒		

Elevations Drawing including:

14	All side views of the structure	☒		
15	Roof pitch			
16	Overhang dimensions and detail with attic ventilation			
17	Location, size and height above roof of chimneys			
18	Location and size of skylights with Florida Product Approval	☒		
18	Number of stories	☒		
20A	Building height from the established grade to the roofs highest peak			

Floor Plan including:

20	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies			
21	Raised floor surfaces located more than 30 inches above the floor or grade			
22	All exterior and interior shear walls indicated			
23	Shear wall opening shown (Windows, Doors and Garage doors)			
24	Emergency escape and rescue opening shown in each bedroom (net clear opening shown)			
25	Safety glazing of glass where needed			
26	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 of FBCR)	☒		
27	Stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails (see FBCR SECTION 311)			
28	Identify accessibility of bathroom (see FBCR SECTION 322)			

All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the p (see Florida product approval form)

GENERAL REQUIREMENTS		APPLICABLE	
APPLICANT: PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTING		APPLICABLE	

FBCR 403: Foundation Plans

		YES	NO	N/A
29	Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	☒	☐	☐
30	All posts and/or column footing including size and reinforcing	☐	☐	☐
31	Any special support required by soil analysis such as piling.	☐	☐	☐
32	Assumed load-bearing value of soil Pound Per Square Foot	☐	☐	☐
33	Location of horizontal and vertical steel, for foundation or walls (include # size and type)	☐	☐	☐

FBCR 506: CONCRETE SLAB ON GRADE

34	Show Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)	☒	☐	☐
35	Show control joints, synthetic fiber reinforcement or welded fire fabric reinforcement and Supports	☐	☐	☐

FBCR 320: PROTECTION AGAINST TERMITES

36	Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or submit other approved termite protection methods. Protection shall be provided by registered termiticides	☒	☐	☐
----	---	-------------------------------------	--------------------------	--------------------------

FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)

37	Show all materials making up walls, wall height, and Block size, mortar type	☐	☐	☐
38	Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement	☐	☐	☐

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer Architect

Floor Framing System: First and/or second story

39	Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer	☒	☐	☐
40	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or piers	☐	☐	☐
41	Girder type, size and spacing to load bearing walls, stem wall and/or piers	☐	☐	☐
42	Attachment of joist to girder	☐	☐	☐
43	Wind load requirements where applicable	☐	☐	☐
44	Show required under-floor crawl space	☐	☐	☐
45	Show required amount of ventilation opening for under-floor spaces	☐	☐	☐
46	Show required covering of ventilation opening	☐	☐	☐
47	Show the required access opening to access to under-floor spaces	☐	☐	☐
	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges &	☐	☐	☐

48	intermediate of the areas structural panel sheathing			
49	Show Draftstopping, Fire caulking and Fire blocking			
50	Show fireproofing requirements for garages attached to living spaces, per FBCR section 309			
51	Provide live and dead load rating of floor framing systems (psf).			

FBCR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION

GENERAL REQUIREMENTS		TRANSFERRED FROM PREVIOUS EDITIONS		
APPLICABLE TO ALL WALLS EXCEPT FOR THE FOLLOWING		APPLICABLE		
		YES	NO	N/A
52	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls	☒		
53	Fastener schedule for structural members per table FBCR 602.3 are to be shown			
54	Show Wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing			
55	Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems			
56	Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FBCR Table 502.5 (1)			
57	Indicate where pressure treated wood will be placed			
58	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas			
59	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail			

FBCR : ROOF SYSTEMS:

60	Truss design drawing shall meet section FBCR 802.10 Wood trusses	☒		
61	Include a layout and truss details, signed and sealed by Florida Professional Engineer			
62	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters			
63	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details			
64	Provide dead load rating of trusses			

FBCR 802:Conventional Roof Framing Layout

65	Rafter and ridge beams sizes, span, species and spacing			
66	Connectors to wall assemblies' include assemblies' resistance to uplift rating			
67	Valley framing and support details			
68	Provide dead load rating of rafter system			

FBCR Table 602,3(2) & FBCR 803 ROOF SHEATHING

69	Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness			
70	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas			

FBCR ROOF ASSEMBLIES FRC Chapter 9

71	Include all materials which will make up the roof assembles covering			
72	Submit Florida Product Approval numbers for each component of the roof assembles covering			

FBCR Chapter 11 Energy Efficiency Code for residential building

Residential construction shall comply with this code by using the following compliance methods in the FBCR chapter 11 Residential buildings compliance methods. Two of the required forms are to be submitted, showing dimensions condition area equal to the total condition living space area

GENERAL REQUIREMENTS		APPLICABLE		
APPLICANT		YES	NO	N/A
73	Show the insulation R value for the following areas of the structure			
74	Attic space			
75	Exterior wall cavity			
76	Crawl space			

HVAC information

77	Submit two copies of a Manual J sizing equipment or equivalent computation study			
78	Exhaust fans locations in bathrooms			
79	Show clothes dryer route and total run of exhaust duct			

Plumbing Fixture layout shown

80	All fixtures waste water lines shall be shown on the foundation plan			
81	Show the location of water heater			

Private Potable Water

existing well

82	Pump motor horse power			
83	Reservoir pressure tank gallon capacity			
84	Rating of cycle stop valve if used			

Electrical layout shown including


85	Switches, outlets/receptacles, lighting and all required GFCI outlets identified			
86	Ceiling fans			
87	Smoke detectors & Carbon dioxide detectors			
88	Service panel, sub-panel, location(s) and total ampere ratings			
89	On the electrical plans identify the electrical service overcurrent protection device for the main disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type.			

90	Appliances and HVAC equipment and disconnects		
91	Arc Fault Circuits (AFCI) in bedrooms		

Disclosure Statement for Owner Builders If you as the applicant will be acting as an owner/builder under section 489.103(7) of the Florida Statutes, submit the required owner builder disclosure statement form.

Notice Of Commencement

A notice of commencement form recorded in the Columbia County Clerk Office is required to be filed with the building department Before Any Inspections can be preformed.



THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

		YES	NO	N/A
92	Building Permit Application A current Building Permit Application form is to be completed and submitted for all residential projects	☒	☐	☐
93	Parcel Number The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested	☒	☐	☐
94	Environmental Health Permit or Sewer Tap Approval A copy of a approved Columbia County Environmental Health (386) 758-1058	☐	☐	☐
95	City of Lake City A permit showing an approved waste water sewer tap	☐	☐	☐
96	Toilet facilities shall be provided for all construction sites	☐	☐	☐
97	Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White an approval land use development letter issued by the Town of Fort is required to be submitted with the application for a building permit.	☐	☐	☐
98	Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations	☐	☐	☐
99	CERTIFIED FINISHED FLOOR ELEVATIONS will be required on any project where the base flood elevation (100 year flood) has been established	☐	☐	☐
100	A development permit will also be required. Development permit cost is \$50.00	☐	☐	☐
101	Driveway Connection: If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.	☐	☐	☐
102	911 Address: If the project is located in an area where a 911 address has not been issued, then application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125	☒	☐	☐

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs Residential Performance Method A

Project Name: 1007042SkylineConstructionTroyLandResidence
 Street:
 City, State, Zip: Lake City, FL, 32024-
 Owner: Troy Land
 Design Location: FL, Gainesville

Builder Name: Skyline Construction
 Permit Office: 28976
 Permit Number: Columbia County
 Jurisdiction: 221000

1. New construction or existing	New (From Plans)	
2. Single family or multiple family	Single-family	
3. Number of units, if multiple family	1	
4. Number of Bedrooms	3	
5. Is this a worst case?	Yes	
6. Conditioned floor area (ft ²)	1911	
7. Windows	Description	Area
a. U-Factor:	Dbl, U=0.35	253.00 ft ²
SHGC:	SHGC=0.35	
b. U-Factor:	Dbl, U=0.87	36.00 ft ²
SHGC:	SHGC=0.66	
c. U-Factor:	N/A	ft ²
SHGC:		
d. U-Factor:	N/A	ft ²
SHGC:		
e. U-Factor:	N/A	ft ²
SHGC:		
8. Floor Types	Insulation	Area
a. Slab-On-Grade Edge Insulation	R=0.0	1911.00 ft ²
b. N/A	R=	ft ²
c. N/A	R=	ft ²

9. Wall Types	Insulation	Area
a. Frame - Wood, Exterior	R=13.0	1804.10 ft ²
b. Frame - Wood, Adjacent	R=13.0	402.67 ft ²
c. N/A	R=	ft ²
d. N/A	R=	ft ²
10. Ceiling Types	Insulation	Area
a. Under Attic (Vented)	R=30.0	1911.00 ft ²
b. Knee Wall (Vented)	R=30.0	150.00 ft ²
c. N/A	R=	ft ²
11. Ducts		
a. Sup: Attic Ret: Attic AH: Interior Sup. R= 6,	382.2 ft ²	
12. Cooling systems		
a. Central Unit	Cap: 44.0 kBtu/hr	SEER: 13
13. Heating systems		
a. Electric Heat Pump	Cap: 44.0 kBtu/hr	HSPF: 7.7
14. Hot water systems		
a. Electric	Cap: 40 gallons	EF: 0.92
b. Conservation features	None	
15. Credits	None	

Glass/Floor Area: 0.151

Total As-Built Modified Loads: 33.31

Total Baseline Loads: 41.41

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: _____

DATE: 7/23/10 EVAN BEAMBLEY

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: _____


DATE: 8/2/10

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____



PROJECT

Title: 1007042SkylineConstructionT	Bedrooms: 3	Address Type: Street Address
Building Type: FLAsBuilt	Conditioned Area: 1911	Lot #
Owner: Troy Land	Total Stories: 1	SubDivision:
# of Units: 1	Worst Case: Yes	PlatBook:
Builder Name: Skyline Construction	Rotate Angle: 90	Street:
Permit Office:	Cross Ventilation:	County: Columbia
Jurisdiction:	Whole House Fan:	City, State, Zip: Lake City , FL , 32024-
Family Type: Single-family		
New/Existing: New (From Plans)		
Comment:		

CLIMATE

	Design Location	TMY Site	IECC Zone	Design Temp 97.5 %	Design Temp 2.5 %	Int Design Temp Winter	Int Design Temp Summer	Heating Degree Days	Design Moisture	Daily Temp Range
✓	FL, Gainesville	FL_GAINESVILLE_REGI	2	32	92	75	70	1305.5	51	Medium

FLOORS

	#	Floor Type	Perimeter	R-Value	Area	Tile	Wood	Carpet
✓	1	Slab-On-Grade Edge Insulatio	247 ft	0	1911 ft²	0.3	0.3	0.4

ROOF

	#	Type	Materials	Roof Area	Gable Area	Roof Color	Solar Absor.	Tested	Deck Insul.	Pitch
✓	1	Gable or shed	Composition shingles	2137 ft²	478 ft²	Dark	0.96	No	0	26.6 deg

ATTIC

	#	Type	Ventilation	Vent Ratio (1 in)	Area	RBS	IRCC
✓	1	Full attic	Vented	300	1911 ft²	N	N

CEILING

	#	Ceiling Type	R-Value	Area	Framing Frac	Truss Type
✓	1	Under Attic (Vented)	30	1911 ft²	0.11	Wood
	2	Knee Wall (Vented)	30	150 ft²	0.11	Wood

WALLS

	#	Ornt	Adjacent To	Wall Type	Cavity R-Value	Area	Sheathing R-Value	Framing Fraction	Solar Absor.
✓	1	N	Exterior	Frame - Wood	13	615 ft²		0.23	0.75
	2	NW	Exterior	Frame - Wood	13	28.33 ft²		0.23	0.75
	3	NE	Exterior	Frame - Wood	13	28.33 ft²		0.23	0.75
	4	E	Exterior	Frame - Wood	13	414.67 ft²		0.23	0.75
	5	S	Exterior	Frame - Wood	13	467.13 ft²		0.23	0.75
	6	W	Exterior	Frame - Wood	13	250.67 ft²		0.23	0.75
	7	S	Garage	Frame - Wood	13	402.67 ft²		0.23	0.01

DOORS

✓	#	Ornt	Door Type	Storms	U-Value	Area
_____	1	E	Insulated	None	0.400000	6.666666
_____	2	N	Insulated	None	0.400000	6.666666
_____	3	S	Insulated	None	0.4	6.666666
_____	4	S	Insulated	None	0.400000	20 ft²
_____	5	S	Insulated	None	0.4	16.666666

WINDOWS

Orientation shown is the entered orientation (=>) changed to Worst Case.

✓	#	Ornt	Frame	Panes	NFRC	U-Factor	SHGC	Storms	Area	Overhang		Int Shade	Screening
										Depth	Separation		
_____	1	N=>E	Metal	Low-E Double	Yes	0.87	0.66	N	36 ft²	1 ft 6 in	2 ft 0 in	HERS 2006	None
_____	2	NW=>NE	Metal	Low-E Double	Yes	0.35	0.35	N	12 ft²	99 ft 0 in	2 ft 0 in	HERS 2006	None
_____	3	N=>E	Metal	Low-E Double	Yes	0.35	0.35	N	24 ft²	9 ft 16 in	2 ft 0 in	HERS 2006	None
_____	4	NE=>SE	Metal	Low-E Double	Yes	0.35	0.35	N	12 ft²	14 ft 8 in	2 ft 0 in	HERS 2006	None
_____	5	N=>E	Metal	Low-E Double	Yes	0.35	0.35	N	13.333333	11 ft 8 in	2 ft 0 in	HERS 2006	None
_____	6	N=>E	Metal	Low-E Double	Yes	0.35	0.35	N	18 ft²	11 ft 8 in	2 ft 0 in	HERS 2006	None
_____	7	N=>E	Metal	Low-E Double	Yes	0.35	0.35	N	20 ft²	1 ft 6 in	3 ft 0 in	HERS 2006	None
_____	8	E=>S	Metal	Low-E Double	Yes	0.35	0.35	N	40 ft²	0 ft 0 in	0 ft 0 in	HERS 2006	None
_____	9	E=>S	Metal	Low-E Double	Yes	0.35	0.35	N	4 ft²	0 ft 0 in	0 ft 0 in	HERS 2006	None
_____	10	S=>W	Metal	Low-E Double	Yes	0.35	0.35	N	20 ft²	1 ft 6 in	1 ft 0 in	HERS 2006	None
_____	11	S=>W	Metal	Low-E Double	Yes	0.35	0.35	N	36 ft²	9 ft 6 in	2 ft 0 in	HERS 2006	None
_____	12	S=>W	Metal	Low-E Double	Yes	0.35	0.35	N	13.333333	9 ft 6 in	2 ft 0 in	HERS 2006	None
_____	13	S=>W	Metal	Low-E Double	Yes	0.35	0.35	N	12 ft²	1 ft 6 in	2 ft 0 in	HERS 2006	None
_____	14	S=>W	Metal	Low-E Double	Yes	0.35	0.35	N	9 ft²	1 ft 6 in	1 ft 0 in	HERS 2006	None
_____	15	W=>N	Metal	Low-E Double	Yes	0.35	0.35	N	6 ft²	1 ft 6 in	1 ft 0 in	HERS 2006	None
_____	16	E=>S	Metal	Low-E Double	Yes	0.35	0.35	N	13.333333	99 ft 0 in	2 ft 0 in	HERS 2006	None

INFILTRATION & VENTING

✓	Method	SLA	CFM 50	ACH 50	ELA	EqLA	---- Forced Ventilation ----		Run Time	Fan
							Supply CFM	Exhaust CFM	Fraction	Watts
_____	Default	0.00036	1805	5.67	99.1	186.3	0 cfm	0 cfm	0	0

GARAGE

✓	#	Floor Area	Ceiling Area	Exposed Wall Perimeter	Avg. Wall Height	Exposed Wall Insulation
_____	1	457.15 ft²	457.15 ft²	43 ft	8 ft	(invalid)

COOLING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Air Flow	SHR	Ducts
_____	1	Central Unit	None	SEER: 13	44 kBtu/hr	1320 cfm	0.75	sys#1

HEATING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Ducts
_____	1	Electric Heat Pump	None	HSPF: 7.7	44 kBtu/hr	sys#1

HOT WATER SYSTEM

✓	#	System Type	EF	Cap	Use	SetPnt	Conservation
_____	1	Electric	0.92	40 gal	60 gal	120 deg	None

SOLAR HOT WATER SYSTEM

✓	FSEC	Cert #	Company Name	System Model #	Collector Model #	Collector Area	Storage Volume	FEF
_____	None	None				ft²		

DUCTS

✓	#	Location	Supply R-Value	Supply Area	Location	Return Area	Leakage Type	Air Handler	CFM 25	Percent Leakage	QN	RLF
_____	1	Attic	6	382.2 ft	Attic	95.55 ft	Default Leakage	Interior	(Default)	(Default) %		

TEMPERATURES

Programable Thermostat: None

Ceiling Fans:

Cooling	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Heating	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Venting	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec

Thermostat Schedule: HERS 2006 Reference

Schedule Type		1	2	3	4	5	6	7	8	9	10	11	12
Cooling (WD)	AM	78	78	78	78	78	78	78	78	78	78	78	78
	PM	78	78	78	78	78	78	78	78	78	78	78	78
Cooling (WEH)	AM	78	78	78	78	78	78	78	78	78	78	78	78
	PM	78	78	78	78	78	78	78	78	78	78	78	78
Heating (WD)	AM	68	68	68	68	68	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	68	68
Heating (WEH)	AM	68	68	68	68	68	68	68	68	68	68	68	68
	PM	68	68	68	68	68	68	68	68	68	68	68	68

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS:

Lake City, FL, 32024-

PERMIT #:

INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	N1106.AB.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	N1106.AB.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	N1106.AB.1.2.2	Penetrations/openings > 1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	N1106.AB.1.2.3	Between walls & ceilings; penetrations of ceiling plane to top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	N1106.AB.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	N1106.AB.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	N1106.AB.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	N1112.AB.3	Comply with efficiency requirements in Table N112.ABC.3. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	N1112.AB.2.3	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%. Heat pump pool heaters shall have a minimum COP of 4.0.	
Shower heads	N1112.AB.2.4	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	N1110.AB	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated and installed in accordance with the criteria of Section N1110.AB. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	N1107.AB.2	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	N1104.AB.1 N1102.B.1.1	Ceilings-Min. R-19. Common walls-frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE INDEX* = 80

The lower the EnergyPerformance Index, the more efficient the home.

, Lake City, FL, 32024-

1. New construction or existing	New (From Plans)		9. Wall Types	Insulation	Area
2. Single family or multiple family	Single-family		a. Frame - Wood, Exterior	R=13.0	1804.10 ft ²
3. Number of units, if multiple family	1		b. Frame - Wood, Adjacent	R=13.0	402.67 ft ²
4. Number of Bedrooms	3		c. N/A	R=	ft ²
5. Is this a worst case?	Yes		d. N/A	R=	ft ²
6. Conditioned floor area (ft ²)	1911		10. Ceiling Types	Insulation	Area
7. Windows**	Description	Area	a. Under Attic (Vented)	R=30.0	1911.00 ft ²
a. U-Factor:	Dbl, U=0.35	253.00 ft ²	b. Knee Wall (Vented)	R=30.0	150.00 ft ²
SHGC:	SHGC=0.35		c. N/A	R=	ft ²
b. U-Factor:	Dbl, U=0.87	36.00 ft ²	11. Ducts		
SHGC:	SHGC=0.66		a. Sup: Attic Ret: Attic AH: Interior Sup. R= 6,	382.2 ft ²	
c. U-Factor:	N/A	ft ²	12. Cooling systems		
SHGC:			a. Central Unit	Cap: 44.0 kBtu/hr	SEER: 13
d. U-Factor:	N/A	ft ²	13. Heating systems		
SHGC:			a. Electric Heat Pump	Cap: 44.0 kBtu/hr	HSPF: 7.7
e. U-Factor:	N/A	ft ²	14. Hot water systems		
SHGC:			a. Electric	Cap: 40 gallons	EF: 0.92
8. Floor Types	Insulation	Area	b. Conservation features	None	
a. Slab-On-Grade Edge Insulation	R=0.0	1911.00 ft ²	None		
b. N/A	R=	ft ²	15. Credits	None	
c. N/A	R=	ft ²			

I certify that this home has complied with the Florida Energy Efficiency Code for Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____

Date: _____

Address of New Home: _____

City/FL Zip: _____



*Note: The home's estimated Energy Performance Index is only available through the EnergyGauge USA - FlaRes2008 computer program. This is not a Building Energy Rating. If your Index is below 100, your home may qualify for incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at (321) 638-1492 or see the Energy Gauge web site at energygauge.com for information and a list of certified Raters. For information about Florida's Energy Efficiency Code for Building Construction, contact the Department of Community Affairs at (850) 487-1824.

**Label required by Section 13-104.4.5 of the Florida Building Code, Building, or Section B2.1.1 of Appendix G of the Florida Building Code, Residential, if not DEFAULT.

Location:

Project Name: *Justin Troy Land*

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit on or after April 1, 2004. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			
1. Swinging	<i>Mayfair</i>	<i>entry door</i>	<i>FL 1311</i>
2. Sliding			
3. Sectional			
4. Roll up	<i>General American</i>	<i>garage door</i>	<i>FL 2868</i>
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung	<i>Danwid</i>	<i>Single Hung windows</i>	<i>FL 1369</i>
2. Horizontal Slider			
3. Casement			
4. Double Hung			
5. Fixed			
6. Awning			
7. Pass-through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11 Dual Action			
12. Other			
C. PANEL WALL			
1. Siding	<i>James Hardie</i>	<i>hardiboard siding</i>	<i>FL 889-R1</i>
2. Soffits	<i>Ashley</i>	<i>Aluminum</i>	<i>FL 406</i>
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
1. Asphalt Shingles	<i>Tamko</i>	<i>30-year Shingles Asphalt</i>	<i>FL 673</i>
2. Underlayments			
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Subcategory (cont.)	Manufacturer	Product Description	Approval number(s)
Liquid Applied Roof Sys			
Cements-Adhesives - Coatings			
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor			
2. Truss plates			
3. Engineered lumber			
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspection

Linda Roder
Contractor or Contractor's Authorized Agent Signature

Linda Roder 9-20-10
Print Name Date

Location

Permit # (FOR STAFF USE ONLY)

Residential System Sizing Calculation

Summary

Troy Land

Project Title:

1007042SkylineConstructionTroyLandResidence

Lake City, FL 32024-


7/23/2010

Location for weather data: Gainesville, FL - Defaults: Latitude(29.7) Altitude(152 ft.) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(54gr.)			
Winter design temperature(MJ8 99%)	33 F	Summer design temperature(MJ8 99%)	92 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	37 F	Summer temperature difference	17 F
Total heating load calculation	35382 Btuh	Total cooling load calculation	36773 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	124.4 44000	Sensible (SHR = 0.75)	110.7 33000
Heat Pump + Auxiliary(0.0kW)	124.4 44000	Latent	157.9 11000
		Total (Electric Heat Pump)	119.7 44000

WINTER CALCULATIONS

Winter Heating Load (for 1911 sqft)


Load component		Load	
Window total	289 sqft	4435	Btuh
Wall total	1861 sqft	6112	Btuh
Door total	57 sqft	839	Btuh
Ceiling total	2061 sqft	2429	Btuh
Floor total	1911 sqft	10784	Btuh
Infiltration	159 cfm	6451	Btuh
Duct loss		4333	Btuh
Subtotal		35382	Btuh
Ventilation	0 cfm	0	Btuh
TOTAL HEAT LOSS		35382	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 1911 sqft)

Load component		Load	
Window total	289 sqft	10399	Btuh
Wall total	1861 sqft	3671	Btuh
Door total	57 sqft	635	Btuh
Ceiling total	2061 sqft	3413	Btuh
Floor total		0	Btuh
Infiltration	127 cfm	2371	Btuh
Internal gain		3780	Btuh
Duct gain		5538	Btuh
Sens. Ventilation	0 cfm	0	Btuh
Blower Load		0	Btuh
Total sensible gain		29806	Btuh
Latent gain(ducts)		1110	Btuh
Latent gain(infiltration)		4656	Btuh
Latent gain(ventilation)		0	Btuh
Latent gain(internal/occupants/other)		1200	Btuh
Total latent gain		6966	Btuh
TOTAL HEAT GAIN		36773	Btuh



8th Edition

EnergyGauge® System Sizing

PREPARED BY:

DATE: 7/23/10 EVAN BERNLEY

System Sizing Calculations - Winter

Residential Load - Whole House Component Details

Troy Land

Project Title:

1007042SkylineConstructionTroyLandResidence

Lake City, FL 32024-

Building Type: User

7/23/2010

Reference City: Gainesville, FL (Defaults) Winter Temperature Difference: 37.0 F (MJ8 99%)

This calculation is for Worst Case. The house has been rotated 225 degrees.

Component Loads for Whole House

Window	Panes/Type	Frame	U	Orientation	Area(sqft)	X	HTM=	Load
1	2, NFRC 0.66	Metal	0.87	SW	36.0		32.2	1159 Btuh
2	2, NFRC 0.35	Metal	0.35	S	12.0		12.9	155 Btuh
3	2, NFRC 0.35	Metal	0.35	SW	24.0		12.9	311 Btuh
4	2, NFRC 0.35	Metal	0.35	W	12.0		12.9	155 Btuh
5	2, NFRC 0.35	Metal	0.35	SW	13.3		12.9	173 Btuh
6	2, NFRC 0.35	Metal	0.35	SW	18.0		12.9	233 Btuh
7	2, NFRC 0.35	Metal	0.35	SW	20.0		12.9	259 Btuh
8	2, NFRC 0.35	Metal	0.35	NW	40.0		12.9	518 Btuh
9	2, NFRC 0.35	Metal	0.35	NW	4.0		12.9	52 Btuh
10	2, NFRC 0.35	Metal	0.35	NE	20.0		12.9	259 Btuh
11	2, NFRC 0.35	Metal	0.35	NE	36.0		12.9	466 Btuh
12	2, NFRC 0.35	Metal	0.35	NE	13.3		12.9	173 Btuh
13	2, NFRC 0.35	Metal	0.35	NE	12.0		12.9	155 Btuh
14	2, NFRC 0.35	Metal	0.35	NE	9.0		12.9	117 Btuh
15	2, NFRC 0.35	Metal	0.35	SE	6.0		12.9	78 Btuh
16	2, NFRC 0.35	Metal	0.35	NW	13.3		12.9	173 Btuh
Window Total					289.0(sqft)			4435 Btuh
Walls	Type	Ornt.	Ueff.	R-Value (Cav/Sh)	Area	X	HTM=	Load
1	Frame - Wood	- Ext	(0.089)	13.0/0.0	497		3.28	1632 Btuh
2	Frame - Wood	- Ext	(0.089)	13.0/0.0	16		3.28	54 Btuh
3	Frame - Wood	- Ext	(0.089)	13.0/0.0	16		3.28	54 Btuh
4	Frame - Wood	- Ext	(0.089)	13.0/0.0	351		3.28	1152 Btuh
5	Frame - Wood	- Ext	(0.089)	13.0/0.0	370		3.28	1216 Btuh
6	Frame - Wood	- Ext	(0.089)	13.0/0.0	245		3.28	803 Btuh
7	Frame - Wood	- Adj	(0.089)	13.0/0.0	366		3.28	1202 Btuh
Wall Total					1861(sqft)			6112 Btuh
Doors	Type	Storm	Ueff.		Area	X	HTM=	Load
1	Insulated - Exterior,	n	(0.400)		7		14.8	99 Btuh
2	Insulated - Exterior,	n	(0.400)		7		14.8	99 Btuh
3	Insulated - Exterior,	n	(0.400)		7		14.8	99 Btuh
4	Insulated - Garage,	n	(0.400)		20		14.8	296 Btuh
5	Insulated - Garage,	n	(0.400)		17		14.8	247 Btuh
Door Total					57(sqft)			839Btuh
Ceilings	Type/Color/Surface	Ueff.	R-Value		Area	X	HTM=	Load
1	Vented Attic/D/Shing	(0.032)	30.0/0.0		1911		1.2	2252 Btuh
2	Knee Wall/D/Shing	(0.032)	30.0/0.0		150		1.2	177 Btuh
Ceiling Total					2061(sqft)			2429Btuh
Floors	Type	Ueff.	R-Value		Size	X	HTM=	Load
1	Slab On Grade	(1.180)	0.0		247.0 ft(perim.)		43.7	10784 Btuh
Floor Total					1911 sqft			10784 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

Troy Land

Project Title:

1007042SkylineConstructionTroyLandResidence

Lake City, FL 32024-

Building Type: User

7/23/2010

	Envelope Subtotal:					24598 Btuh
Infiltration	Type Natural	ACH 0.50	Volume(cuft) 19110	Wall Ratio 1.00	CFM= 159.3	6451 Btuh
Duct load	Average sealed, R6.0, Supply(Att), Return(Att) (DLM of 0.140)					4333 Btuh
All Zones	Sensible Subtotal All Zones					35382 Btuh

WHOLE HOUSE TOTALS

Totals for Heating	Subtotal Sensible Heat Loss	35382 Btuh
	Ventilation Sensible Heat Loss	0 Btuh
	Total Heat Loss	35382 Btuh

EQUIPMENT

1. Electric Heat Pump	#	44000 Btuh
-----------------------	---	------------

Key: Window types - NFRC (Requires U-Factor and Shading coefficient(SHGC) of glass as numerical values)
or - Glass as 'Clear' or 'Tint' (Uses U-Factor and SHGC defaults)

U - (Window U-Factor)

HTM - (ManualJ Heat Transfer Multiplier)



Version 8

System Sizing Calculations - Summer

Residential Load - Whole House Component Details

Troy Land

Project Title:

1007042SkylineConstructionTroyLandResidence

Lake City, FL 32024-

7/23/2010

Reference City: Gainesville, FL

Temperature Difference: 17.0F(MJ8 99%)

Humidity difference: 54gr.

This calculation is for Worst Case. The house has been rotated 225 degrees.

Component Loads for Whole House

Window	Type*					Overhang		Window Area(sqft)			HTM		Load		
	Panes	SHGC	U	InSh	IS Ornt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded			
1	2 NFRC	0.66, 0.87	No	No	SW	1.5ft	2.0ft	36.0	2.8	33.2	29	62	2141	Btuh	
2	2 NFRC	0.35, 0.35	No	No	S	99.0f	2.0ft	12.0	12.0	0.0	13	16	160	Btuh	
3	2 NFRC	0.35, 0.35	No	No	SW	10.3f	2.0ft	24.0	24.0	0.0	13	31	319	Btuh	
4	2 NFRC	0.35, 0.35	No	No	W	14.7f	2.0ft	12.0	12.0	0.0	13	40	160	Btuh	
5	2 NFRC	0.35, 0.35	No	No	SW	11.7f	2.0ft	13.3	13.3	0.0	13	31	177	Btuh	
6	2 NFRC	0.35, 0.35	No	No	SW	11.7f	2.0ft	18.0	18.0	0.0	13	31	240	Btuh	
7	2 NFRC	0.35, 0.35	No	No	SW	1.5ft	3.0ft	20.0	0.0	20.0	13	31	621	Btuh	
8	2 NFRC	0.35, 0.35	No	No	NW	0.0ft	0.0ft	40.0	0.0	40.0	13	29	1179	Btuh	
9	2 NFRC	0.35, 0.35	No	No	NW	0.0ft	0.0ft	4.0	0.0	4.0	13	29	118	Btuh	
10	2 NFRC	0.35, 0.35	No	No	NE	1.5ft	1.0ft	20.0	0.0	20.0	13	29	589	Btuh	
11	2 NFRC	0.35, 0.35	No	No	NE	9.5ft	2.0ft	36.0	0.0	36.0	13	29	1061	Btuh	
12	2 NFRC	0.35, 0.35	No	No	NE	9.5ft	2.0ft	13.3	0.0	13.3	13	29	393	Btuh	
13	2 NFRC	0.35, 0.35	No	No	NE	1.5ft	2.0ft	12.0	0.0	12.0	13	29	354	Btuh	
14	2 NFRC	0.35, 0.35	No	No	NE	1.5ft	1.0ft	9.0	0.0	9.0	13	29	265	Btuh	
15	2 NFRC	0.35, 0.35	No	No	SE	1.5ft	1.0ft	6.0	2.9	3.1	13	31	134	Btuh	
16	2 NFRC	0.35, 0.35	No	No	NW	99.0f	2.0ft	13.3	0.0	13.3	13	29	393	Btuh	
	Excursion												2095	Btuh	
	Window Total							289 (sqft)						10399	Btuh
Walls	Type					U-Value	R-Value	Area(sqft)		HTM		Load			
							Cav/Sheath								
1	Frame - Wood - Ext					0.09	13.0/0.0	497.0		2.1		1037 Btuh			
2	Frame - Wood - Ext					0.09	13.0/0.0	16.3		2.1		34 Btuh			
3	Frame - Wood - Ext					0.09	13.0/0.0	16.3		2.1		34 Btuh			
4	Frame - Wood - Ext					0.09	13.0/0.0	350.7		2.1		731 Btuh			
5	Frame - Wood - Ext					0.09	13.0/0.0	370.1		2.1		772 Btuh			
6	Frame - Wood - Ext					0.09	13.0/0.0	244.7		2.1		510 Btuh			
7	Frame - Wood - Adj					0.09	13.0/0.0	366.0		1.5		552 Btuh			
	Wall Total							1861 (sqft)				3671 Btuh			
Doors	Type							Area (sqft)		HTM		Load			
1	Insulated - Exterior							6.7		11.2		75 Btuh			
2	Insulated - Exterior							6.7		11.2		75 Btuh			
3	Insulated - Exterior							6.7		11.2		75 Btuh			
4	Insulated - Garage							20.0		11.2		224 Btuh			
5	Insulated - Garage							16.7		11.2		187 Btuh			
	Door Total							57 (sqft)				635 Btuh			
Ceilings	Type/Color/Surface					U-Value	R-Value	Area(sqft)		HTM		Load			
1	Vented Attic/DarkShingle					0.032	30.0/0.0	1911.0		1.66		3165 Btuh			
2	Knee Wall/DarkShingle					0.032	30.0/0.0	150.0		1.66		248 Btuh			
	Ceiling Total							2061 (sqft)				3413 Btuh			
Floors	Type						R-Value	Size		HTM		Load			
1	Slab On Grade						0.0	1911 (ft-perimeter)		0.0		0 Btuh			
	Floor Total							1911.0 (sqft)				0 Btuh			
	Envelope Subtotal:												18118 Btuh		

Manual J Summer Calculations

Residential Load - Component Details (continued)

Troy Land

Project Title:

Climate:FL_GAINESVILLE_REGIONAL_A

1007042SkylineConstructionTroyLandResidence

Lake City, FL 32024-

7/23/2010

Infiltration	Type	ACH	Volume(cuft)	Wall Ratio	CFM=	Load
	SensibleNatural	0.40	19110	1861	159.3	2371 Btuh
Internal gain		Occupants	Btuh/occupant		Appliance	Load
		4	X 230 +		2400	3320 Btuh
	Sensible Envelope Load:					23809 Btuh
Duct load	Average sealed, Supply(R6.0-Attic), Return(R6.0-Attic)			(DGM of 0.228)		5538 Btuh
	Sensible Load All Zones					29346 Btuh

Manual J Summer Calculations

Residential Load - Component Details (continued)

Troy Land

Project Title:

Climate:FL_GAINESVILLE_REGIONAL_A

Lake City, FL 32024-

1007042SkylineConstructionTroyLandResidence

7/23/2010

WHOLE HOUSE TOTALS

Whole House Totals for Cooling	Sensible Envelope Load All Zones	24269 Btuh
	Sensible Duct Load	5538 Btuh
	Total Sensible Zone Loads	29806 Btuh
	Sensible ventilation	0 Btuh
	Blower	0 Btuh
	Total sensible gain	29806 Btuh
	Latent infiltration gain (for 54 gr. humidity difference)	4656 Btuh
	Latent ventilation gain	0 Btuh
	Latent duct gain	1110 Btuh
	Latent occupant gain (6 people @ 200 Btuh per person)	1200 Btuh
	Latent other gain	0 Btuh
	Latent total gain	6966 Btuh
	TOTAL GAIN	36773 Btuh

EQUIPMENT

1. Central Unit	#	44000 Btuh
-----------------	---	------------

*Key: Window types (Panels - Number and type of panes of glass)

(SHGC - Shading coefficient of glass as SHGC numerical value)

(U - Window U-Factor)

(InSh - Interior shading device: none(No), Blinds(B), Draperies(D) or Roller Shades(R))

- For Blinds: Assume medium color, half closed

For Draperies: Assume medium weave, half closed

For Roller shades: Assume translucent, half closed

(IS - Insect screen: none(N), Full(F) or Half(½))

(Ornt - compass orientation)



Version 8

Julius Lee



RE: 327354 - TROY LAND RES.

**1109 Coastal Bay Blvd.
Boynton Beach, FL 33435**

Site Information:

Project Customer: SKYLINE HOMES Project Name: 327354 Model: TROY LAND RES.
Lot/Block: Subdivision:
Address: 100 NW LOWER SPRINGS RD
City: COLUMBIA CTY State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: JOEL R. PHINNEY License #: CBC1256243
Address: 120 SW SMITH LANE
City: LAKE CITY State: FL

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2007/TPI2002 Design Program: MiTek 20/20 7.1
Wind Code: ASCE 7-05 Wind Speed: 110 mph Floor Load: N/A psf
Roof Load: 32.0 psf

This package includes 34 individual, dated Truss Design Drawings and 0 Additional Drawings.
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

This document processed per section 16G15-23.003 of the Florida Board of Professionals Rules

In the event of changes from Builder or E.O.R. additional coversheets and drawings may accompany this coversheet. The latest approval dates supersede and replace the previous drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I4395694	CJ1	7/12/010	18	I4395711	T09	7/12/010
2	I4395695	EJ3	7/12/010	19	I4395712	T10	7/12/010
3	I4395696	EJ3A	7/12/010	20	I4395713	T11	7/12/010
4	I4395697	EJ3B	7/12/010	21	I4395714	T12	7/12/010
5	I4395698	EJ6	7/12/010	22	I4395715	T13	7/12/010
6	I4395699	EJ7	7/12/010	23	I4395716	T14	7/12/010
7	I4395700	EJ7G	7/12/010	24	I4395717	T15	7/12/010
8	I4395701	HJ4	7/12/010	25	I4395718	T16	7/12/010
9	I4395702	T01	7/12/010	26	I4395719	T17	7/12/010
10	I4395703	T01G	7/12/010	27	I4395720	T18	7/12/010
11	I4395704	T02	7/12/010	28	I4395721	T18G	7/12/010
12	I4395705	T03	7/12/010	29	I4395722	T19	7/12/010
13	I4395706	T04	7/12/010	30	I4395723	T20	7/12/010
14	I4395707	T05	7/12/010	31	I4395724	T20G	7/12/010
15	I4395708	T06	7/12/010	32	I4395725	T21	7/12/010
16	I4395709	T07	7/12/010	33	I4395726	T21G	7/12/010
17	I4395710	T08	7/12/010	34	I4395727	T22	7/12/010


1,027
uplift

The truss drawing(s) referenced above have been prepared by MiTek Industries, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Lake City).

Truss Design Engineer's Name: Julius Lee

My license renewal date for the state of Florida is February 28, 2011.


NOTE: The seal on these drawings indicate acceptance of professional engineering responsibility solely for the truss components shown. The suitability and use of this component for any particular building is the responsibility of the building designer, per ANSI/TPI-1 Chapter 2.



Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395694
327354	CJ1	JACK	2	1	Job Reference (optional)	

Builders FrstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:06 2010 Page 1



Scale = 1:8.3

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.16	Vert(LL) -0.00 2 >999 360	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.01	Vert(TL) -0.00 2 >999 240		
BCLL 0.0	Rep Stress Incr YES	WB 0.00	Horz(TL) 0.00 3 n/a n/a		
BCDL 5.0	Code FBC2007/TPI2002	(Matrix)	Wind(LL) 0.00 2 **** 240		
				Weight: 6 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=182/0-5-8, 4=5/Mechanical, 3=-43/Mechanical
Max Horz 2=70(LC 6)
Max Uplift 2=-183(LC 6), 3=-43(LC 1)
Max Grav 2=182(LC 1), 4=14(LC 2), 3=64(LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (8-9)

- 1) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SYP No.2.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 183 lb uplift at joint 2 and 43 lb uplift at joint 3.
- 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- 8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 9) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869: Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.
Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and 8CSI1 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job 327354	Truss EJ3A	Truss Type JACK	Qty 2	Ply 1	TROY LAND RES. Job Reference (optional) 7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:07 2010 Page 1	I4395696
---------------	---------------	--------------------	----------	----------	---	----------

Builders FrstSource, Lake City, FL 32055

Scale = 1:22.7

LOADING (psf) TCDL 20.0 BCDL 0.0 * BCDL 5.0	SPACING 2-0-0 Plates Increase 1.25 Lumber Increase 1.25 Rep Stress Incr YES Code FBC2007/TPI2002	CSI TC 0.70 BC 0.34 WB 0.00 (Matrix)	DEFL in (loc) l/defl L/d Vert(LL) -0.00 4-5 >999 360 Vert(TL) -0.00 4-5 >999 240 Horz(TL) -0.12 3 n/a n/a Wind(LL) 0.02 4-5 >999 240	PLATES GRIP MT20 244/190 Weight: 15 lb
---	---	---	---	---

LUMBER

TOP CHORD 2 X 4 SYP No.2

BOT CHORD 2 X 4 SYP No.2

WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-8 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=207/0-5-0, 3=49/Mechanical, 4=11/Mechanical
 Max Horz 5=167(LC 6)
 Max Uplift 5=-49(LC 6), 3=-87(LC 6), 4=-46(LC 6)
 Max Grav 5=207(LC 1), 3=49(LC 1), 4=38(LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (8-9)

- 1) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SYP No.2 .
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 5, 87 lb uplift at joint 3 and 46 lb uplift at joint 4.
- 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- 8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 9) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 BEFORE USE.


Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oro Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395698
327354	EJ6	JACK	4	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:07 2010 Page 1



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.42	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.26	Vert(LL) -0.07 2-4 >999 360		
BCLL 0.0 *	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.13 2-4 >580 240		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.00 3 n/a n/a		
	Code FBC2007/TPI2002		Wind(LL) 0.00 2 **** 240		
				Weight: 23 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=151/Mechanical, 2=301/0-5-8, 4=30/Mechanical
Max Horz 2=193(LC 6)
Max Uplift 3=137(LC 6), 2=171(LC 6)
Max Grav 3=151(LC 1), 2=301(LC 1), 4=91(LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (8-9)

- 1) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) All bearings are assumed to be SYP No.2.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 137 lb uplift at joint 3 and 171 lb uplift at joint 2.
- 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- 8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 9) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, DSB-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Ondra Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395700
327354	EJ7G	GABLE	1	1	Job Reference (optional)	

Builders FrstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:08 2010 Page 1




Plate Offsets (X,Y): [2-0-3-8,Edge], [2-0-2-8,Edge], [5-0-3-0-0-2-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.22	Vert(LL)	-0.00	1	n/r	120	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	-0.00	1	n/r	90		
BCLL 0.0	Rep Stress Incr	NO	WB 0.06	Horz(TL)	0.00	8	n/a	n/a		
BCDL 5.0	Code FBC2007/TPI2002		(Matrix)							
									Weight: 34 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3
OTHERS 2 X 4 SYP No.3

BRACING

TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.

Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS

All bearings 7-6-8.
(b) - Max Horz 2=126(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 8, 9 except 2=200(LC 6), 10=138(LC 6)
Max Grav All reactions 250 lb or less at joint(s) 8, 9 except 2=320(LC 1), 10=301(LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


WEBS 4-10=-260/259

NOTES (13-14)

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1-2002.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SYP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 9 except (jt=lb) 2=200, 10=138.
- "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-5=-87(F=-33), 5-7=-87(F=-33), 2-8=-10




July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI1 Quality Criteria, D5B-89 and BCS11 Building Component Safety Information available from Truss Plate Institute, 583 D'Oroffia Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435



Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395704
327354	T02	SPECIAL	1	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:09 2010 Page 1




Plate Offsets (X,Y): [2.0-2.10.0-1.8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.57	Vert(LL)	-0.27 14-15	>961	360	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.83	Vert(TL)	-0.40 14-15	>653	240		
BCLL 0.0	Rep Stress Incr	NO	WB 0.50	Horz(TL)	0.02 11	n/a	n/a		
BCDL 5.0	Code FBC2007/TPI2002		(Matrix)	Wind(LL)	0.08 14-15	>999	240		
								Weight: 162 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2
BOT CHORD 2 X 4 SYP No.2
WEBS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-0-6 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=902/0-5-8, 11=2087/0-3-8
Max Horz 2=169(LC 5)
Max Uplift 2=182(LC 5), 11=826(LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1489/149, 3-4=-1336/162, 4-5=-991/0, 5-6=-389/58, 6-16=-625/1102, 16-17=-625/1102, 7-17=-625/1102
BOT CHORD 2-15=-207/1256, 15-20=-40/753, 20-21=-40/753, 13-14=0/717, 12-13=0/717, 11-12=-537/445
WEBS 3-15=-260/163, 4-15=-157/705, 5-14=-231/453, 5-12=-1149/264, 6-12=-218/998, 6-11=-1333/435, 7-11=-1179/686, 7-10=-38/398, 8-10=-314/161

NOTES (11-12)

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 5.0psf.
- All bearings are assumed to be SYP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=182, 11=826.
- "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 137 lb down and 125 lb up at 22-8-12, 137 lb down and 125 lb up at 24-8-12, and 137 lb down and 125 lb up at 26-8-12, and 137 lb down and 125 lb up at 28-8-12 on top chord, and 61 lb down at 22-8-12, 61 lb down at 24-8-12, and 61 lb down at 26-8-12, and 61 lb down at 28-8-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

Continued on page 2



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395705
327354	T03	SPECIAL	1	1	Job Reference (optional)	

1-6-0 5-11-4 11-3-0 14-1-9 18-2-12 30-0-0

1-6-0 5-11-4 5-3-12 2-10-8 4-1-4 11-9-4



Scale = 1:56.3

Plate Offsets (X,Y): [2-0-2-10-0-1-8]											
LOADING (psf)		SPACING 2-0-0		CSI		DEFL in (loc) l/defl L/d				PLATES GRIP	
TCLL	20.0	Plates Increase 1.25		TC	0.89	Vert(LL)	-0.14	14-15	>999	360	MT20 244/190
TCDL	7.0	Lumber Increase 1.25		BC	0.95	Vert(TL)	-0.54	9	>170	90	
BCDL	0.0	Rep Stress Incr NO		WB	0.80	Horz(TL)	0.03	12	n/a	n/a	
BCDL	5.0	Code FBC2007/TPI2002		(Matrix)		Wind(LL)	0.19	14-15	>999	240	Weight: 168 lb

REACTIONS (lb/size) 2=917/0-5-8, 12=1513/0-3-8
Max Horz 2=189(LC 6)
Max Uplift 2=-273(LC 6), 12=-354(LC 7)

NOTES (10-11)

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-05; 110mph (3-second gust); TCFL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) All bearings are assumed to be SYP No.2 .
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=274 12=354.
- 8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- 10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 11) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

Continued on page 2 July 12, 2010

July 12, 2010

Job 327354	Truss T04	Truss Type SPECIAL	Qty 1	Ply 1	TROY LAND RES. Job Reference (optional)	14395706
Builders FrstSource, Lake City, FL 32055			7/14/09 Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:10 2010 Page 1			

-1-6-0 | 5-11-4 | 10-4-8 | 17-3-14 | 21-6-4 | 26-0-0 | 30-0-0

1-6-0 | 5-11-4 | 4-5-4 | 6-11-6 | 4-2-6 | 4-5-13 | 4-0-0

Scale = 1:55.3

Plate Offsets (X,Y): [2-0-1-4, 0-0-2], [4-0-3-0, 0-2-0]							
LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.43	Vert(LL) -0.21 14-15	>999	360	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.77	Vert(TL) -0.43 14-15	>719	240		
BCLL 0.0	Rep Stress Incr NO	WB 0.89	Horz(TL) 0.06 11	n/a	n/a		
BCDL 5.0	Code FBC2007/TPI2002	(Matrix)	Wind(LL) 0.27 14-15	>999	240		
						Weight: 170 lb	


LUMBER TOP CHORD 2 X 4 SYP No.2 BOT CHORD 2 X 4 SYP No.2 "Except" B3: 2 X 4 SYP No.3 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD Structural wood sheathing directly applied or 4-3-8 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 5-11-10 oc bracing. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
---	--

REACTIONS (lb/size) 2=1148/0-5-8, 11=1283/0-3-8
 Max Horz 2=204(LC 6)
 Max Uplift 2=-298(LC 6), 11=-349(LC 5)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1996/1017, 3-4=-1845/1023, 4-5=-1332/759, 5-6=-638/357
 BOT CHORD 2-15=-1077/1702, 14-15=-805/1328, 13-14=-687/1183, 12-13=-687/1183, 11-12=-357/638,
 10-11=-400/231, 7-10=-277/195
 WEBS 4-15=-332/574, 5-14=-175/371, 5-12=-872/528, 6-12=-351/696, 6-11=-1115/613

NOTES (9-10)
 1) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 2) Provide adequate drainage to prevent water ponding.
 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 5) All bearings are assumed to be SYP No.2.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=298, 11=349.
 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 9) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 10) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-4=-54, 4-8=-54, 2-15=-10, 14-15=-70(F=-60), 11-14=-10, 9-10=-10



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oonofrio Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.
327354	T05	SPECIAL	1	1	

I4395707

Job Reference (optional)

Builders FrstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-8=-54, 2-15=-10, 15-16=-70(F=-60), 16-17=-110(F=-60), 14-17=-70(F=-60), 13-14=-10, 13-18=-50, 11-18=-10, 9-10=-10



July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.
 Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component.
 Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown
 is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the
 erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding
 fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and ECSI1 Building Component**
Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395708
327354	T06	SPECIAL	1	1	Job Reference (optional)	

Builders FrstSource, Lake City, FL 32055


7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-54, 5-7=-54, 2-14=-10, 14-16=-70(F=-60), 16-17=-110(F=-60), 13-17=-70(F=-60), 13-18=-50, 11-18=-10, 11-19=-10, 10-19=-50, 9-20=-10, 20-21=-50, 8-21=-10



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D5B-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.
327354	T07	SPECIAL	1	1	Job Reference (optional)

I4395709

Builders FrstSource, Lake City, FL 32055


7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-54, 5-7=-54, 2-14=-10, 14-16=-70(F=-60), 16-17=-110(F=-60), 13-17=-70(F=-60), 12-13=-10, 12-18=-50, 11-18=-10, 10-11=-10, 9-19=-10, 8-19=-50



July 12, 2010

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.**

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, DSB-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	
327354	T08	SPECIAL	1	1	Job Reference (optional)	I4395710

Builders FrstSource, Lake City, FL 32055


7,140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:12 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-5=-54, 5-7=-54, 2-14=-10, 14-16=-70(F=-60), 16-17=-110(F=-60), 13-17=-70(F=-60), 13-18=-10, 18-19=-50, 11-19=-10, 10-11=-10, 9-20=-10, 8-20=-50



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D5B-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	
327354	T09	SPECIAL	1	1	Job Reference (optional)	14395711

Builders FirstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:12 2010 Page 2

- 11) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 12) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869: Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-3=-54, 3-7=-54, 7-9=-54, 2-15=-10, 14-15=-10, 8-13=-10

Concentrated Loads (lb)

Vert: 7=18(B) 15=-1(B) 4=5(B) 10=-10(B) 17=11(B) 18=5(B) 19=11(B) 20=11(B) 21=11(B) 22=11(B) 23=11(B) 24=11(B) 25=-146(B) 26=-1(B) 27=-4(B) 28=-4(B) 29=-4(B) 30=-4(B) 31=-4(B) 32=-4(B)





July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII 7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435



July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE.
Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not Truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oroffio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435



July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.
 Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.
327354	T17	SPECIAL	1	1	

I4395719

Builders FrstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:17 2010 Page 1



LOADING (psf)		SPACING		CSI		DEFL		PLATES		GRIP	
TCLL	20.0	Plates Increase	1.25	TC	0.32	Vert(LL)	-0.15 9-10 >999 360	MT20		244/190	
TCDL	7.0	Lumber Increase	1.25	BC	0.49	Vert(TL)	-0.24 9-10 >999 240				
BCLL	0.0	Rep Stress Incr	YES	WB	0.86	Horz(TL)	0.06 9 n/a n/a				
BCDL	5.0	Code FBC2007/TPI2002		(Matrix)		Wind(LL)	0.11 12 >999 240				
								Weight: 188 lb			

LUMBER

TOP CHORD 2 X 4 SYP No.2
 BOT CHORD 2 X 4 SYP No.2 *Except*
 B2: 2 X 4 SYP No.3
 WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-8-15 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-3-2 oc bracing.
 WEBS T-Brace: 2 X 4 SYP No.3 - 7-8
 Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance.
 Brace must cover 90% of web length.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=919/0-5-8, 9=1209/0-6-7
 Max Horz 2=316(LC 6)
 Max Uplift 2=-237(LC 6), 9=-284(LC 5)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1478/606, 3-4=-1671/906, 4-5=-874/446, 5-6=-719/452
 BOT CHORD 2-13=-893/1248, 4-11=-352/549, 10-11=-1023/1439, 10-14=-158/252, 14-15=-158/252
 WEBS 3-13=-408/387, 11-13=-948/1309, 4-10=-882/695, 6-10=-436/688, 6-9=-953/636

NOTES (9-10)

- 1) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 5.0psf.
- 5) All bearings are assumed to be SYP No.2
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=237 9=284.
- 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.
- 9) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- 10) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE M11 7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-87 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	I4395720
327354	T18	COMMON	9	1	Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MITek Industries, Inc. Mon Jul 12 09:46:17 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-18=-54, 5-19=-54, 5-9=-54, 2-20=-10, 20-21=-50, 21-22=-10, 22-23=-50, 23-24=-10, 24-25=-50, 8-25=-10

Concentrated Loads (lb)

Vert: 18=-138(F)

Trapezoidal Loads (plf)

Vert: 18=-206(F=-152)-to-19=-137(F=-83)



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	I4395721
327354	T18G	GABLE	2	1	Job Reference (optional)	

Builders FrstSource, Lake City, FL 32055 7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:19 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-6=-87(F=-33), 6-7=-87(F=-33), 7-12=-54, 2-47=-10, 47-48=-50, 48-49=-10, 49-50=-50, 50-51=-10, 51-52=-50, 11-52=-10



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job 327354	Truss T20G	Truss Type GABLE	Qty 1	Ply 1	TROY LAND RES. Job Reference (optional)	I4395724
---------------	---------------	---------------------	----------	----------	--	----------

Builders FirstSource, Lake City, FL 32055

7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:21 2010 Page 2

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-6=-87(F=-33), 6-7=-87(F=-33), 7-11=-54, 2-38=-10, 38-39=-50, 10-39=-10



July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, DSB-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job 327354	Truss T21G	Truss Type GABLE	Qty 1	Ply 1	TROY LAND RES.	I4395726
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:22 2010 Page 1			





Plate Offsets (X,Y): [2:0-3-8,Edge], [2:0-1-8,Edge], [33:0-3-0,0-0-4]					
LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)
TCLL 20.0	Plates Increase	1.25	TC 0.26	Vert(LL)	-0.01 23 n/r 120
TCDL 7.0	Lumber Increase	1.25	BC 0.07	Vert(TL)	-0.02 23 n/r 90
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.17	Horz(TL)	0.01 24 n/a n/a
BCDL 5.0	Code FBC2007/TPI2002		(Matrix)		
					Weight: 254 lb

LUMBER		BRACING	
TOP CHORD	2 X 4 SYP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2 X 4 SYP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2 X 4 SYP No.2 *Except* W1: 2 X 4 SYP No.3	WEBS	T-Brace: 2 X 4 SYP No.3 - 13-32, 12-34, 14-31 Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c., with 4in minimum end distance. Brace must cover 90% of web length.
OTHERS	2 X 4 SYP No.3		

REACTIONS All bearings 35-3-8.
(lb) - Max Horz 2=226(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 24 except 2=130(LC 6), 34=116(LC 6), 35=123(LC 6), 36=119(LC 6), 37=119(LC 6), 38=119(LC 6), 39=120(LC 6), 40=116(LC 6), 41=132(LC 6), 31=113(LC 7), 30=124(LC 7), 29=118(LC 7), 28=119(LC 7), 27=120(LC 7), 26=118(LC 7), 25=225(LC 7)
Max Grav All reactions 250 lb or less at joint(s) 32, 34, 35, 36, 37, 38, 39, 40, 31, 30, 29, 28, 27, 26, 25 except 2=314(LC 10), 24=269(LC 1), 41=295(LC 10)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 11-12=38/250, 12-13=43/304, 13-14=40/304, 14-15=36/250, 22-24=264/56
WEBS 4-41=257/177

- NOTES** (14-15)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1-2002.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - All bearings are assumed to be SYP No.2.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 24 except (it=lb) 2=130, 34=116, 35=123, 36=119, 37=119, 38=119, 39=120, 40=116, 41=132, 31=113, 30=124, 29=118, 28=119, 27=120, 26=118, 25=225.
 - "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 - Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE.
Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI1 Quality Criteria, D58-89 and BC511 Building Component Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job 327354	Truss T22	Truss Type KINGPOST	Qty 10	Ply 1	TROY LAND RES. Job Reference (optional)	I4395727
Builders FirstSource, Lake City, FL 32055			7.140 s Oct 1 2009 MiTek Industries, Inc. Mon Jul 12 09:46:22 2010 Page 1			

Scale = 1:10.7

LOADING (psf) TCLL 20.0 TCDL 7.0 BCCL 0.0 BCDL 5.0	SPACING 2-0-0 Plates Increase 1.25 Lumber Increase 1.25 Rep Stress Incr YES Code FBC2007/TPI2002	CSI TC 0.08 BC 0.02 WB 0.02 (Matrix)	DEFL in (loc) l/defl L/d Vert(LL) -0.00 6 >999 360 Vert(TL) -0.00 6 >999 240 Horz(TL) 0.00 4 n/a n/a Wind(LL) 0.00 2 >999 240	PLATES MT20 GRIP 244/190 Weight: 16 lb
---	---	---	--	--

LUMBER

TOP CHORD 2 X 4 SYP No.2

BOT CHORD 2 X 4 SYP No.2

WEBS 2 X 4 SYP No.3

REACTIONS (lb/size) 2=165/0-3-8, 4=165/0-3-8
 Max Horz 2=-31(LC 7)
 Max Uplift 2=-117(LC 6), 4=-117(LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (8-9)

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SYP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=117, 4=117.
- "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
- This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869: Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-6-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

July 12, 2010



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and BCS11 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

STEPDOWN CORNER SET

TOP CHORD 2X4 SO. PINE #2 or Better
BOT CHORD 2X4 SO. PINE #2 or Better
WEBS 2X4 SO. PINE #3 or Better

120 MPH MAX

Setback 7' or Better

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED.

UPLIFT: 400# or Less

BRG LOC:

UPLIFT BASED ON 7.2 PSF TOTAL DEAD LOAD. WIND
SPEED=120 "C" MPH. MEAN HGT=28 FT. ENCLOSED. (ASCE 7-02)

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED. TILE

UPLIFT: 400# or Less

BRG LOC:

UPLIFT BASED ON 15.0 PSF TOTAL DEAD LOAD. WIND
SPEED=120 "C" MPH. MEAN HGT (of jacks)=28 FT. ENCLOSED. (ASCE 7-02)

PROVIDE UPLIFT CONNECTIONS AT BEARINGS AS INDICATED.

UPLIFT: 400# or Less

BRG LOC:

UPLIFT BASED ON 7.2 PSF TOTAL DEAD LOAD. WIND
SPEED=120 "B" MPH. MEAN HGT (of jacks)=28 FT. ENCLOSED. (ASCE 7-02)

#2 HIP OR COMMON TRUSS

#1 HIP TRUSS

2' TYP.
MAX

or Less

CJ's
2' TYP.
MAX

1'

2' O.H. 1'
MAX



CJ's

2' TYP.
MAX

2' TYP.
MAX

* (3) 16d TOENAILS

** SEE EOR FOR TIE DOWN



END AND CORNER JACKS


HIP JACK

UPLIFT VALUES DO TAKE INTO ACCOUNT PORCHES EXPOSED
BC LIVE LOAD IS NON CONCURRENT 10*

CORNER SET SETBACK 7'0" MAX		UPLIFT VALUES DO TAKE INTO ACCOUNT PORCHES EXPOSED BC LIVE LOAD IS NON CONCURRENT 10*		REF 7' MAX STBK CS
				DATE Jun./27/2008
				DRWG
				-ENG
				REVIEWED
				By Julius Lee at 10:52 am, Jun 27, 2008
				20 MAX PSF
				10* MAX PSF
				5 MAX PSF
				20 MAX PSF
				20 MAX PSF
				10* MAX PSF
				5 MAX PSF
				DUR. FAC. 1.25
				SPACING 2' MAX

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 BUILDING COMPONENT SAFETY INFORMATION, PUBLISHED BY TPI TRUSS PLATE INSTITUTE, 563 D'ONOFRIO DR., SUITE 200, MADISON, VT 05719 AND VTC GOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, VT 05719 FOR SAFETY PRACTICES TO FOLLOW DURING THESE FUNCTIONS. UNLESS OTHERWISE SPECIFIED, ALL MATERIALS SHALL BE PROPERLY ATTACHED TO STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING, BRACING OR TRUSSES. ALPINE CORNER JACKS ARE MADE OF 20/18/16GA (W/H/S/X) ASTM A653 GRADE 40/60 (W/X/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY ID SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF THE PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



ASCE 7-02: 130 MPH WIND SPEED, 30' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

2X4 CABLE VERTICAL		BRACE		NO BRACES		(1) 1X4 "L" BRACE *		(2) 2X4 "L" BRACE *		(1) 2X0 "L" BRACE *		(2) 2X2 "L" BRACE *	
CABLE VERTICAL	SPACING	SPECIES	GRADE	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B
MAX GABLE VERTICAL LENGTH	12" O.C.	SPF	#1 / #2	5' 6"	6' 6"	6' 6"	6' 6"	6' 6"	6' 6"	10' 3"	10' 3"	12' 3"	12' 7"
		HF	#3	3' 1"	4' 5"	6' 10"	7' 10"	7' 10"	7' 10"	9' 1"	9' 1"	12' 3"	12' 3"
		STUD	STANDARD	3' 1"	4' 5"	6' 10"	7' 10"	7' 10"	7' 10"	9' 1"	9' 1"	12' 3"	12' 3"
		SP	#1	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
24" O.C.	24" O.C.	HF	#2	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		STUD	#3	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		SP	#1	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		DFL	#2	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
16" O.C.	16" O.C.	HF	#3	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		STUD	#1 / #2	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		SP	#3	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		DFL	#2	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
12" O.C.	12" O.C.	HF	#1	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		STUD	#2	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		SP	#3	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"
		DFL	#1	3' 6"	5' 8"	7' 0"	8' 5"	10' 3"	11' 1"	7' 10"	7' 10"	10' 7"	10' 7"

BRACING GROUP SPECIES AND GRADES:

GROUP A:	
SPRICE-PINE-FIR	HEM-FIR
#1 / #2 STANDARD	#3 STUD
#3 STUD	STANDARD

DOUGLAS FIR-LARCH	SOUTHERN PINE
#3 STUD	#3 STUD
STANDARD	STANDARD

GROUP B:

HEM-FIR	#1 A BTR
DOUGLAS FIR-LARCH	#1
SOUTHERN PINE	#2
STANDARD	#2



GABLE TRUSS DETAIL NOTES:

- LIVE LOAD DEFLECTION CRITERIA IS $L/240$.
- PROVIDE UPLIFT CONNECTIONS FOR 180 PSF OVER CONTINUOUS BEARING (6 PSF VC DEAD LOAD).
- CABLE END SUPPORTS LOAD FROM 4' 0" BUTLROCKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.
- ATTACH EACH "L" BRACE WITH 10d NAILS.
- * FOR (1) "L" BRACE: SPACE NAILS AT 8" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
- ** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.
- "L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES

VERTICAL LENGTH	NO SPLICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2X6

* REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE, AND BEEL PLATES.



JULIUS LEE'S
CONS. ENGINEERS P.A.
1456 SW 4th AVENUE
DELRAY BEACH, FL 33444-8181

ADVANCED TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI 1-03 BUILDING COMPONENT SAFETY (INFORMATION), PUBLISHED BY TPI TRUSS INSTITUTE, 983 D'UNFRED DR., SUITE 200, HANSEN, VA 50719, AND VTCA (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, WILMINGTON, VT 05399, FOR SAFETY PRACTICES PRIOR TO PURCHASING TRUSSES. ALL TRUSSES AND BRACING PANELS AND BUTTEN GIRD SHALL HAVE A PROPERLY ATTACHED REED CEILING.



REVIEWED
By Julius Lee at 12:00 pm, Jun 11, 2008

REF	ASCE 7-02-GAB130030
DATE	11/26/03
DWG	WEEK 9TH GABLE 90' 2 HT
ENG	-ENG
MAX. TOT. LD.	60 PSF
MAX. SPACING	24.0"

PIGGYBACK DETAIL

TOP CHORD 2X4 #3 OR BETTER
BOT CHORD 2X4 #2 OR BETTER
WEBS 2X4 #3 OR BETTER

REFER TO SEALED DESIGN FOR DASHED PLATES.

SPACE PIGGYBACK VERTICALS AT 4' OC MAX.

TOP AND BOTTOM CHORD SPLICES MUST BE STAGGERED SO THAT ONE SPlice IS NOT DIRECTLY OVER ANOTHER.

PIGGYBACK BOTTOM CHORD MAY BE OMITTED. ATTACH VERTICAL WEBS TO TRUSS TOP CHORD WITH 1.5X3 PLATE.

ATTACH PURLINS TO TOP OF FLAT TOP CHORD. IF PIGGYBACK IS SOLID LUMBER OR THE BOTTOM CHORD IS OMITTED, PURLINS MAY BE APPLIED BENEATH THE TOP CHORD OF SUPPORTING TRUSS.

REFER TO ENGINEER'S SEALED DESIGN FOR REQUIRED PURLIN SPACING.

THIS DETAIL IS APPLICABLE FOR THE FOLLOWING WIND CONDITIONS:

110 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, 1 MI FROM COAST

CAT I, EXP C, WIND TC DL=5 PSF, WIND BC DL=6 PSF

110 MPH WIND, 30' MEAN HGT, PBC

ENCLOSED BLDG, LOCATED ANYWHERE IN ROOF

WIND TC DL=5 PSF, WIND BC DL=6 PSF



FRONT FACE (B,*) PLATES MAY BE OFFSET FROM BACK FACE PLATES AS LONG AS BOTH FACES ARE SPACED 4' OC MAX.

130 MPH WIND, 30' MEAN HGT, ASCE 7-02, CLOSED BLDG, LOCATED ANYWHERE IN ROOF, CAT II, EXP. C, WIND TC DL=6 PSF, WIND BC DL=6 PSF


ATTACH TRULOX PLATES WITH (8) 0.120" X 1.375" NAILS, OR EQUAL, PER FACE PER PLY. (4) NAILS IN EACH MEMBER TO BE CONNECTED. REFER TO DRAWING 160 TL FOR TRULOX INFORMATION.

MAX SIZE OF 2X12 #2 OR BETTER

20' FLAT TOP CHORD MAX SPAN




OPTIONAL SPlice



* PIGGYBACK SPECIAL PLATE

ATTACH TEETH TO THE PIGGYBACK AT THE TIME OF FABRICATION. ATTACH TO SUPPORTING TRUSS WITH (4) 0.120" X 1.375" NAILS PER FACE PER PLY. APPLY PIGGYBACK SPECIAL PLATE TO EACH TRUSS FACE AND SPACE 4' OC OR LESS.



THIS DRAWING REPLACES DRAWINGS 634.016 634.017 & 847.045

JOINT TYPE	SPANS UP TO			
	30'	34'	38'	62'
A	2X4	2.6X4	2.6X4	3X6
B	4X8	5X8	5X8	5X8
C	1.5X3	1.5X4	1.5X4	1.5X4
D	5X4	5X5	5X5	5X6
E	4X8 OR 3X8 TRULOX AT 4' OC, ROTATED VERTICALLY			

MAX LOADING	REF	PIGGYBACK
55 PSF AT 1.33 DUR. FAC.	DATE	09/12/07
50 PSF AT 1.25 DUR. FAC.	DRWG/ITEK	STD PIGGY
47 PSF AT 1.15 DUR. FAC.	-ENG	JL
SPACING	24.0"	

JULIUS LEE'S
CONS. ENGINEERS P.A.
1400 SW 4TH AVENUE
DEER BEACH, FL 33444-2161

THIS DRAWING REPLACES DRAWINGS 634.016 634.017 & 847.045

REVIEWED
By Julius Lee at 11:59 am, Jun 11, 2008

PROFESSIONAL ENGINEER
STATE OF FLORIDA
NO. 34869

TOE-NAIL DETAIL

TOE-NAILS TO BE DRIVEN AT AN ANGLE OF APPROXIMATELY THIRTY DEGREES WITH THE PIECE AND STARTED APPROXIMATELY ONE-THIRD THE LENGTH OF THE NAIL FROM THE END OF THE MEMBER.

PER ANSI/AF&PA NDS-2001 SECTION 12.4.1 - EDGE DISTANCE, END DISTANCE, SPACING: "EDGE DISTANCES, END DISTANCES AND SPACINGS FOR NAILS AND SPIKES SHALL BE SUFFICIENT TO PREVENT SPLITTING OF THE WOOD."



THE NUMBER OF TOE-NAILS TO BE USED IN A SPECIFIC APPLICATION IS DEPENDENT UPON PROPERTIES FOR THE CHORD SIZE, LUMBER SPECIES, AND NAIL TYPE. PROPER CONSTRUCTION PRACTICES AS WELL AS GOOD JUDGEMENT SHOULD DETERMINE THE NUMBER OF NAILS TO BE USED.

THIS DETAIL DISPLAYS A TOE-NAILED CONNECTION FOR JACK FRAMING INTO A SINGLE OR DOUBLE PLY SUPPORTING GIRDER.

MAXIMUM VERTICAL RESISTANCE OF 16d (0.162"x3.5") COMMON TOE-NAILS


NUMBER OF TOE-NAILS	SOUTHERN PINE		DOUGLAS FIR-LARCH		HEM-FIR		SPRUCE PINE FIR	
	1 PLY	2 PLIES	1 PLY	2 PLIES	1 PLY	2 PLIES	1 PLY	2 PLIES
2	197#	256#	181#	234#	156#	203#	154#	199#
3	298#	383#	271#	351#	234#	304#	230#	298#
4	394#	511#	361#	468#	312#	406#	307#	397#
5	493#	639#	452#	585#	390#	507#	384#	496#

ALL VALUES MAY BE MULTIPLIED BY APPROPRIATE DURATION OF LOAD FACTOR.



THIS DRAWING REPLACES DRAWING 784040

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST PRACTICES FOR TRUSS SAFETY INFORMATION, PUBLISHED BY THE TRUSS ASSOCIATION OF AMERICA, 6800 ENTERPRISE LN, NATION, UT 84701. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID DECKING.	JULIUS LEE'S CONS. ENGINEERS P.A. 1400 ST 410 AVENUE DELRAY BEACH, FL 33444-2181		TC LL	PSF	REF	TOE-NAIL
			TC DL	PSF	DATE	09/12/07
			BC DL	PSF	DRWG	CNTONAIL1103
			BC LL	PSF	-ENG	JL
			TOT. LD.	PSF		
REVIEWED By Julius Lee at 11:59 am, Jun 11, 2008	No. 34869 STATE OF FLORIDA		DUR. FAC.	1.00		
			SPACING			



TRULOX CONNECTION DETAIL


11 GAUGE (0.120" X 1.375") NAILS REQUIRED FOR TRULOX PLATE ATTACHMENT. FILL ROWS COMPLETELY WHERE SHOWN (Φ).

* NAILS MAY BE OMITTED FROM THESE ROWS.

THIS DETAIL MAY BE USED WITH SO. PINE, DOUGLAS-FIR OR HEM-FIR CHORDS WITH A MINIMUM 1.00 DURATION OF LOAD OR SPRUCE-PINE-FIR CHORDS WITH A MINIMUM 1.15 DURATION OF LOAD. CHORD SIZE OF BOTH TRUSSES MUST EXCEED THE TRULOX PLATE WIDTH.

TRULOX PLATE IS CENTERED ON THE CHORDS AND BENT BETWEEN NAIL ROWS.

REFER TO ENGINEER'S SEALED DESIGN REFERENCING THIS DETAIL FOR LUMBER, PLATES, AND OTHER INFORMATION NOT SHOWN.



MINIMUM 3X6 TRULOX PLATE


TRULOX PLATE SIZE	REQUIRED NAILS PER TRUSS	MAXIMUM LOAD UP OR DOWN
3X6	9	350#
5X6	15	990#

MINIMUM 5X6 TRULOX PLATE

THIS DRAWING REPLACES DRAWINGS 1,158,988 1,158,988/R
1,154,844 1,152,217 1,152,017 1,159,154 & 1,151,524

REVIEWED

By Julius Lee at 11:58 am, Jun 11, 2008



WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND PACKAGING. REFER TO AISC 1-60 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS ASSOCIATION, 6300 ENTERPRISE LN, WATSON, UT 84093 FOR SAFETY PRACTICES PRIOR TO ERECTING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

JULIUS LEE'S
CONS. ENGINEERS P.A.

1455 SW 4th AVENUE
DELRAY BEACH, FL 33444-2181

No: 34869
STATE OF FLORIDA

REF TRULOX

DATE 11/26/03

DRWG CNTRULOX1103

-ENG JL


Maximum Uniform Load Applied to Either Outside Member (PLF)

Connector Type	Number of Rows	Connector Spacing	Connector Pattern					
			Assembly A	Assembly B	Assembly C	Assembly D	Assembly E	Assembly F
10d (0.128" x 3") Nail ⁽¹⁾	2	12"	370	280	280	245	370	340
		12"	565	415	415	465	580	425
		24"	505	380	520	860	1,075	505
		19.2"	635	475	655	880	1,290	505
1/2" A307 Through Bolts ⁽²⁾⁽⁴⁾	2	16"	760	570	785	695	1,075	505
		19.2"	850	640	850	765	1,075	505
		24"	680	510	640	555	860	425
		16"	1,020	765	765	680	860	425
SDS 1/4" x 3/8" (4)	2	24"				455	580	455
		19.2"				565	695	565
		16"				680	860	505
		12"				765	1,075	505
SDS 1/4" x 6" (3)(4)	2	24"				455	580	455
		19.2"				565	695	565
		16"				680	860	505
		12"				765	1,075	505
USP WS35 (4)	2	24"	480	360	400	480	525	350
		19.2"	600	450	480	525	660	440
		16"	715	540	540	660	790	525
		12"				765	1,075	505
USP WSB (3)(4)	2	24"				350	440	350
		19.2"				440	525	440
		16"				525	660	525
		12"				660	790	525
3 3/4" TrussLok ⁽⁴⁾	2	24"	635	475	475	425	525	350
		19.2"	795	595	595	530	660	440
		16"	955	715	715	635	790	525
		12"				765	1,075	505
5" TrussLok ⁽⁴⁾	2	24"	500	500	500	445	480	445
		19.2"	625	625	625	555	600	555
		16"	750	750	750	665	725	665
		12"				765	1,075	505
6 3/4" TrussLok ⁽⁴⁾	2	24"				445	480	445
		19.2"				555	600	555
		16"				665	725	665
		12"				765	1,075	505
6 3/4" TrussLok ⁽⁴⁾	2	24"				445	480	445
		19.2"				555	600	555
		16"				665	725	665
		12"				765	1,075	505

- (1) Nailed connection values may be doubled for 6" on-center or tripled for 4" on-center nail spacing.
- (2) Washers required. Bolt holes to be 1/8" maximum.
- (3) 6" SDS or WS screws can be used with Parallam® PSL and Microlam® LVL, but are not recommended for TimberStrand® LSL.
- (4) 24" on-center bolted and screwed connection values may be doubled for 12" on-center spacing.

General Notes

- Connections are based on NDS® 2005 or manufacturer's code report.
- Use specific gravity of 0.5 when designing lateral connections.
- Values listed are for 100% stress level. Increase 15% for snow-loaded roof conditions or 25% for non-snow roof conditions, where code allows.
- Bolt Lateral cells indicate Connector Pattern** must be installed on both sides. Stagger fasteners on opposite side of beam by 1/2 the required **Connector Spacing**.
- Verify adequacy of beam in allowable load tables on pages 16–33.
- 7" wide beams should be side-loaded only when loads are applied to both sides of the members (to minimize rotation).
- Minimum end distance for bolts and screws is 6".
- Beams wider than 7" require special consideration by the design professional.




Uniform Load Design Example

First, check the allowable load tables on pages 16–33 to verify that three pieces can carry the total load of 715 plf with proper live load deflection criteria. Maximum load applied to either outside member is 415 plf. For a 3-ply 1 3/4" assembly, two rows of 10d (0.128" x 3") nails at 12" on-center is good for only 280 plf. Therefore, use three rows of 10d (0.128" x 3") nails at 12" on-center (good for 415 plf).

Alternates:
Two rows of 1/2" bolts or SDS 1/4" x 3 1/2" screws at 19.2" on-center.

MULTIPLE-MEMBER CONNECTIONS FOR SIDE-LOADED BEAMS

Point Load—Maximum Point Load Applied to Either Outside Member (lbs)

Connector Type	Number of Connectors	Connector Pattern					
		Assembly A	Assembly B	Assembly C	Assembly D	Assembly E	Assembly F
							
		3 1/2" 2-ply	5 1/4" 3-ply	5 1/4" 2-ply	7" 3-ply	7" 2-ply	7" 4-ply
10d (0.128" x 3") Nail	6	1,110	835	835	740		
	12	2,225	1,670	1,670	1,485		
	18	3,335	2,505	2,505	2,225		
	24	4,450	3,335	3,335	2,965		
SDS Screws 1/4" x 3 1/2" or WS35 1/4" x 6" or WS6(1)	4	1,915	1,435(4)	1,435	1,275	1,860(2)	1,405(2)
	6	2,870	2,150(4)	2,150	1,915	2,785(2)	2,110(2)
	8	3,825	2,870(4)	2,870	2,550	3,715(2)	2,810(2)
	10	4,780	3,590(4)	3,590	3,225	4,540(2)	3,510(2)
3 3/8" or 5" TrussLok™	4	2,545	1,910(4)	1,910	1,695	1,925(3)	1,775(3)
	6	3,815	2,860(4)	2,860	2,545	2,890(3)	2,665(3)
	8	5,090	3,815(4)	3,815	3,390	3,855(3)	3,550(3)
	10	6,365	4,770(4)	4,770	4,275	4,815(3)	4,435(3)

(1) 6" SDS or WS screws can be used with Parallam® PSL and Microllam® LVL, but are not recommended for TimberStrand® LSL.

See General Notes on page 38


(2) 6" long screws required.

(3) 5" long screws required.


(4) 3 1/2" and 3 3/8" long screws must be installed on both sides.

Connections


4 or 6 or Screw Connection



8 Screw Connection




Nail Connection



There must be an equal number of nails on each side of the connection

Point Load Design Example



First, verify that a 3-ply 1 3/4" x 14" beam is capable of supporting the 3,000 lb point load as well as all other loads applied. The 3,000 lb point load is being transferred to the beam with a face mount hanger. For a 3-ply 1 3/4" assembly, eight 3 3/8" TrussLok™ screws are good for 3,815 lbs with a face mount hanger.

MULTIPLE-MEMBER CONNECTIONS FOR TOP-LOADED BEAMS

1 3/4" Wide Pieces

- Minimum of three rows of 10d (0.128" x 3") nails at 12" on-center.
- Minimum of four rows of 10d (0.128" x 3") nails at 12" on-center for 14" or deeper.
- If using 12d–16d (0.148"–0.162" diameter) nails, the number of nailing rows may be reduced by one.
- Minimum of two rows of SDS, WS, or TrussLok™ screws at 16" on-center. Use 3 3/8" minimum length with two or three plies; 5" minimum for 4-ply members. 6" SDS and WS screws are not recommended for use with TimberStrand® LSL. For 3- or 4-ply members, connectors must be installed

on both sides. Stagger fasteners on opposite side of beam by 1/2 of the required connector spacing.

- Load must be applied evenly across entire beam width. Otherwise, use connections for side-loaded beams.

3 1/2" Wide Pieces

- Minimum of two rows of SDS, WS, or TrussLok™ screws, 5" minimum length, at 16" on-center. 6" SDS and WS screws are not recommended for use with TimberStrand® LSL. Connectors must be installed on both sides. Stagger fasteners on opposite side of beam by 1/2 of the required connector spacing.


- Load must be applied evenly across entire beam width. Otherwise, use connections for side-loaded beams.

- Minimum of two rows of 1/2" bolts at 24" on-center staggered.




Multiple pieces can be nailed or bolted together to form a header or beam of the required size, up to a maximum width of 7"


STRONG BACK DETAIL SYSTEM-42 OR FLAT TRUSS



ALTERNATE DETAIL FOR STRONG BACK WITH VERTICAL NOT LINING UP



REVIEWED
By Julius lee at 11:58 am, Jun 11, 2008



JULIUS LEE'S
CONS. ENGINEERS P.A.
1456 SW 4th AVENUE
OZRAY BEACH, FL 33444-2161

No: 34669
STATE OF FLORIDA

* GRADE AND SPECIES AS SPECIFIED ON THE ALPINE DESIGN.
BOLT HOLES SHALL BE A MINIMUM OF 1/32" TO A MAXIMUM OF 1/16" LARGER THAN BOLT DIAMETER.

TYPICAL LOCATION OF 1/2" DIAMETER THRU BOLTS. BOLT QUANTITIES AS NOTED ON SEALED DESIGN MUST BE APPLIED IN ONE OF THE PATTERNS SHOWN BELOW.



A circular professional engineer seal for the State of Florida. The outer ring contains the text "FLORIDA PROFESSIONAL ENGINEER" with stars at the top and bottom. The inner circle contains the text "STATE OF FLORIDA" and "LICENSE NO. 84869". A signature, "J. Lee", is written across the seal.

[illegible]

REVIEWED
By julius lee at 11:59 am, Jun 11, 2008

**JULIUS LEE'S
CONS. ENGINEERS P.A.**
1425 BY 4th AVENUE
DETROIT MI 48201, Ph. 393-44-2161

TC LL	PSF	REF	BOLT SPACING
TC DL	PSF	DATE	11/26/03
BC DL	PSF	DRWG	CNBOLTSPI103
BC LL	PSF	-ENG JL	
TOT. LD.	PSF		
DUR. FAC.			
SPACING			





VALLEY TRUSS DETAIL

TOP CHORD 2X4 SP #2 OR SPF #1/#2 OR BETTER.
BOT CHORD 2X3(*) OR 2X4 SP #2N OR SPF #1/#2 OR BETTER.
WEBS 2X4 SP #3 OR BETTER.

* 2X3 MAY BE RIPPED FROM A 2X6 (PITCHED OR SQUARE).


** ATTACH EACH VALLEY TO EVERY SUPPORTING TRUSS WITH:

(2) 16d BOX (0.135" X 3.5") NAILS TOE-NAILED FOR
FBC 2004 110 MPH, ASCE 7-02 110 MPH WIND OR (3) 16d FOR
ASCE 7-02 130 MPH WIND. 15' MEAN HEIGHT, ENCLOSED
BUILDING, EXP. C. RESIDENTIAL, WIND TC DL=5 PSF.



UNLESS SPECIFIED ON ENGINEER'S SEALED DESIGN, APPLY 1X4 "T"-BRACE, 80% LENGTH OF WEB, VALLEY WEB, SAME SPECIES AND GRADE OR BETTER, ATTACHED WITH 8d BOX (0.113" X 2.5") NAILS AT 6" OC, OR CONTINUOUS LATERAL BRACING, EQUALLY SPACED, FOR VERTICAL VALLEY WEBS GREATER THAN 7'9".
MAXIMUM VALLEY VERTICAL HEIGHT MAY NOT EXCEED 12'0".
TOP CHORD OF TRUSS BENEATH VALLEY SET MUST BE BRACED WITH:
PROPERLY ATTACHED, RATED SHEATHING APPLIED PRIOR TO VALLEY TRUSS INSTALLATION
OR
PURLINS AT 24" OC OR AS OTHERWISE SPECIFIED ON ENGINEERS' SEALED DESIGN
BY VALLEY TRUSSES USED IN LIEU OF PURLIN SPACING AS SPECIFIED ON ENGINEERS' SEALED DESIGN.


*** NOTE THAT THE PURLIN SPACING FOR BRACING THE TOP CHORD OF THE TRUSS BENEATH THE VALLEY IS MEASURED ALONG THE SLOPE OF THE TOP CHORD.
++ LARGER SPANS MAY BE BUILT AS LONG AS THE VERTICAL HEIGHT DOES NOT EXCEED 12'0".
BOTTOM CHORD MAY BE SQUARE OR PITCHED CUT AS SHOWN.



SQUARE CUT
BOTTOM CHORD
VALLEY

OPTIONAL STUB
END DETAIL

OPTIONAL HIP
JOINT DETAIL




COMMON TRUSSES
AT 24" OC

PARTIAL FRAMING
PLAN

THIS DRAWING REPLACES DRAWING A105

VARIOUS TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO NEXT 1-20 BUILDING DEPARTMENT SAFETY INFORMATION, PUBLISHED BY THE TRUSS MANUFACTURERS ASSOCIATION, 15777 W. 37TH AVE., SUITE 200, WOODBRIDGE, VA 22191 AND A/CIA CUBED TRUSS GENERAL INSTRUCTIONS. TRUSSES OF ALL TYPES MUST BE PROPERLY BRACED AND SHIPPED TO PREVENT DAMAGE. STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.




REVIEWED
By Julius Lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S
CONS. ENGINEERS P.A.
1655 SW 4th Avenue
Deerfield Beach, FL 33441-8161


No. 34869
STATE OF FLORIDA

TC LL	20	20	PSF	REF	VALLEY DETAIL
TC DL	7	15	PSF	DATE	11/26/03
BC DL	5	5	PSF	DRWG	VALTRUSS1103
BC LL	0	0	PSF	-ENG	JL
TOT. LD.	32	40	PSF		
DUR.FAC.	1.25	1.25			
SPACING	24"				


TYPICAL ATTIC TRUSS BRACING






TYPICAL ALTERNATE BRACING DETAIL FOR EXTERIOR FLAT GIRDER TRUSS



CABLE END TRUSS DETAIL





TYPICAL WALL GIRDER VERTICAL WEB BRACING DETAIL



REVIEWED
By Julius Lee at 11:59 am, Jun 11, 2008

JULIUS LEE'S
CONS. ENGINEERS P.A.
1426 SW 4TH AVENUE
GIBRALTAR BEACH, FL 33444-2611
No. 34869
STATE OF FLORIDA

MAX GABLE VERTICAL LENGTH													
GABLE VERTICAL SPACING / SPECIES	BRACE GRADE	NO BRACES	(1) 1X4 "L" BRACE *		(1) 2X4 "L" BRACE *		(2) 2X4 "L" BRACE **		(1) 2X6 "L" BRACE *	(2) 2X8 "L" BRACE *		(2) 2X8 "L" BRACE *	
			GROUP A	GROUP B	GROUP A	GROUP B	GROUP A	GROUP B		GROUP A	GROUP B		
24" O.C.	SPF	#1 / #2	3' 4"	6' 10"	6' 0"	6' 11"	7' 1"	6' 3"	6' 6"	10' 10"	11' 2"	12' 11"	13' 3"
		#3	3' 3"	4' 11"	4' 11"	6' 6"	6' 6"	6' 3"	6' 3"	10' 1"	10' 1"	12' 11"	12' 11"
		STUD	3' 3"	4' 11"	4' 11"	6' 6"	6' 6"	6' 3"	6' 3"	10' 0"	10' 0"	12' 11"	12' 11"
		STANDARD	3' 3"	4' 2"	4' 2"	5' 6"	5' 6"	7' 5"	7' 5"	8' 3"	8' 3"	11' 3"	11' 3"
		#1	3' 8"	5' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"
		#2	3' 7"	6' 10"	6' 3"	6' 11"	7' 5"	8' 3"	8' 11"	10' 10"	11' 8"	12' 11"	13' 11"
	SP	#3	3' 6"	5' 0"	5' 0"	6' 3"	6' 3"	6' 3"	6' 3"	8' 3"	10' 4"	10' 4"	13' 7"
		STUD	3' 6"	5' 0"	5' 0"	6' 7"	6' 7"	8' 3"	8' 3"	10' 3"	10' 3"	12' 11"	13' 7"
		STANDARD	3' 4"	4' 3"	4' 3"	5' 8"	5' 8"	7' 8"	7' 8"	8' 10"	8' 10"	12' 0"	12' 0"
		#1 / #2	3' 10"	6' 8"	6' 10"	7' 11"	8' 1"	9' 5"	9' 5"	9' 8"	12' 6"	12' 9"	14' 0"
		#3	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
		STANDARD	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
16" O.C.	SPF	STUD	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
		#3	3' 8"	6' 2"	6' 2"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
		STANDARD	3' 8"	6' 2"	6' 2"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"	12' 4"	14' 0"	14' 0"
	HF	#1	4' 3"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"
		#2	4' 2"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"	13' 5"	14' 0"	14' 0"
		#3	4' 0"	6' 2"	6' 2"	7' 11"	8' 2"	9' 5"	9' 11"	12' 5"	12' 8"	14' 0"	14' 0"
SP	STUD	3' 10"	5' 3"	5' 3"	6' 11"	6' 11"	9' 4"	9' 4"	10' 10"	10' 10"	14' 0"	14' 0"	
	#1	4' 3"	7' 4"	7' 4"	8' 9"	8' 11"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"	
	#2	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"	
12" O.C.	SPF	STUD	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
		#1	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
		#2	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
	HF	STUD	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
		#1	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
		#2	4' 2"	6' 11"	6' 11"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"
SP	STUD	4' 4"	7' 2"	7' 2"	8' 9"	8' 9"	10' 5"	10' 5"	13' 8"	14' 0"	14' 0"	14' 0"	
	#												



REFER TO CHART ABOVE FOR MAX GABLE VERTICAL LENGTH.

DIAGONAL BRACE OPTION:
VERTICAL LENGTH MAY BE
DOUBLED WHEN DIAGONAL
BRACE IS USED. CONNECT
DIAGONAL BRACE FOR 840#
AT EACH END. MAX WEB
TOTAL LENGTH IS 14'.

VERTICAL LENGTH SHOWN
IN TABLE ABOVE.

CONNECT DIAGONAL AT
VERTICAL WEB

2X4 BP #2N, DT-L #2
SP# #1/#2, OR BETHEEN

■ **WARRON** ■ THESE REQUIRE EXISTENT CARE, FABRICATING, HOLDING, SHOPPING, INSTALLING, LAMINATING AND BRACING. REFER TO 3631-3-63 (BUILDING CONCRETE SAFETY INFORMATION), PUBLISHED BY THE CONCRETE RESEARCH INSTITUTE, 581 DOWD ROAD, SUITE 200, MALDEN, VA 53745 AND VITA (VIBRO) TRUSS COMPANY OF AMERICA, 6300 ENTERPRISE DRIVE, SUITE 100, FARMERSVILLE, VA 53745 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED ROOF CEILING.

**JULIUS LEE'S
CONS. ENGINEERS P.A.**
1465 GT 4th AVENUE
DELRAY BEACH, FL 33444-2161

1456 6th AVE. N.
DELRAY BEACH, FL. 33444-2161

REF	ASCE7-02-CABI301E
DATE	11/26/03
DRWG	MTX STD CABLE 16 E H
-ENG	

—ENG

REVIEWED

By Julius Lee at 12:00 pm, Jun 11, 2008

No: 34869
STATE OF FLORIDA

MAX. TOT. LD. 60 PSF
MAX. SPACING 24.0"

CABLE TRUSS DETAIL NOTES:

LIVE LOAD DEPLETION CRITERIA IS L/240.

PROVIDE UPLIFT CONNECTIONS FOR 136 PLF OVER CONTINUOUS BEARING (6 PSF WC DEAD LOAD)

CABLE END SUPPORTS LOAD FROM 4' 0"

PLYWOOD OVERHANG

ATTACH EACH "L" BRACE WITH 10d NAILS.
* FOR (1) "L" BRACE, SPACE NAILS AT 2" O.C.

IN 18° END ZONES AND 4° O.C. BETWEEN ZONES

IN 18° EWD ZONES AND 6° O.C. BETWEEN ZONES

1. BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

CABLE VERTICAL PLATE SIZES

VERTICAL LENGTH	NO SPLICE
-----------------	-----------

LESS THAN 4' 0"	1X1 OR 2X2
GREATER THAN 4' 0" BUT	

LESS THAN 11' 0"	2X4
------------------	-----

GREATER THAN 11' 0"	2.5X4
---------------------	-------

REFLECT TO COMMON THOUGHTS DESIGN FOR
PRAY, RESOLVE AND HEAL PIETERS

© 2000 Blackwell Science Ltd, *Journal of Internal Medicine* 247: 395–401

--	--

REF ASCB7-02-GAL

DATE 11/26/03

DDW

מחלקת המבחנים

-ENG

111

50 PSI


24.0"

--	--

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ " from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.



* Plate location details available in MiTek 20/20 software or upon request.

PLATE SIZE

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.


4 x 4

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T, I or Eliminator bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSII: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ER-5243, 9604B, 9730, 95-43, 96-31, 9667A
NER-487, NER-561
95110, 84-32, 96-67, ER-3907, 9432A

© 2006 MiTek® All Rights Reserved

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSII.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T, I, or Eliminator bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.

Job	Truss	Truss Type	GABLE	Qty	1	Ply	TROY LAND RES.	14395726
327354	T21G			1			Job Reference (optional)	

Builders FirstSource, Lake City, FL 32055

7,140 S Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:22 2010 Page 2

NOTES (14-15)

- (13) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- (14) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
- (15) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

Uniform Loads (plf)
1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Vert: 1-13=-87(F=-33), 13-22=-87(F=-33), 22-23=-87(F=-33), 2-24=-10




July 12, 2010

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE.
Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Application of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the fabricator. Additional permanent bracing of the overall structure is the responsibility of the building designer, for general guidance regarding the fabricator, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and ECSI1 Building Component Safety Information** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	327354	T19	COMMON	Qty	4	Ply	TROY LAND RES.	Job Reference (optional)	7.1405 Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:19 2010 Page 1
-----	--------	-----	--------	-----	---	-----	----------------	--------------------------	---

1-6-0	6-9-14	12-1-6	17-8-0	23-2-10	28-6-2	35-4-0	36-10-0	1-6-0
0-4-3	0-4-3	0-4-3	0-4-3	0-4-3	0-4-3	0-4-3	0-4-3	0-4-3



LOADING (psf)	SPACING	CSI	DEFL	in (loc)	L/d	L/d	PLATES	GRIP	Weight: 184 lb
TCLL 20.0	Plates Increase 1.25	TC 0.42	Ver(TL) -0.15	2-12	>99	360	MT20	244/190	
TCCL 7.0	Lumber Increase 1.25	BC 0.46	Ver(TL) -0.29	2-12	>99	240			
BCCL 0.0	Rep Stress Incr YES	WB 0.32	Horz(TL) 0.03	10	n/a	240			
BCDL 5.0	Code FBC2007/TP12002	(Matrix)	Wind(L) 0.43	8-10	>255	240			

LUMBER	TOP CHORD	2 X 4 SYP No.2	TOP CHORD	2 X 4 SYP No.2	WEBS	2 X 4 SYP No.3
BRACING	TOP CHORD	WEBS	TOP CHORD	WEBS	TOP CHORD	WEBS

Structural wood sheathing directly applied or 4-11-0 oc purfins.
Rigid ceiling directly applied or 6-0-0 oc bracing.
1 Row at midpt 6-10, 4-11
Mittek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS	(lb/size)	2=92/10-5-8, 10=156/9-0-5-8, 8=161/0-3-8
Max Horiz 2=131(LC 7)		
Max Uplift 2=250(LC 6), 10=385(LC 7), 8=228(LC 7)		
Max Grav 2=92(LC 1), 10=156/9(LC 1), 8=243(LC 11)		
FORCES	(lb) - Max. Comp/Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-1448/704, 3-4=-1240/677, 4-5=-612/418, 5-6=-612/417, 6-7=-123/524,	
BOT CHORD	2-12=-468/1215, 12-13=-205/860, 11-14=-205/860, 8-10=-279/201	
WEBS	6-11=-107/532, 6-10=-1258/596, 7-10=-321/345, 4-11=-566/422, 4-12=-210/438,	
3-12=-280/290		

- NOTES (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-05; 110mph (3-second gust); TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 5.0psf.
 - All bearings are assumed to be SYP No.2.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 250 lb uplift at joint 2, 385 lb uplift at joint 8, and 228 lb uplift at joint 11.
 - "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 - This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 - Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard

July 12, 2010




WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE M17-7473 BEFORE USE.

Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Application of design parameters and proper incorporation of component is responsibility of building designer. Bracing of the truss, erection and bracing, delivery, erection and bracing, consult ANSI/TPI 1 Quality Criteria, D58-87 and BCS11 Building Component Safety Information available from Truss Plate Institute, 583 D'Oroffo Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.
327354	T186	GABLE	2		
14395721			1		Job Reference (optional)

Builders FirstSource, Lake City, FL 32055 7,140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:18 2010 Page 1



LOADING (psf)	SPACING	DEFL	in (loc)	W/def	L/D
TCLL 20.0	Plates Increase 1.25	Ver(TL) -0.17	16-17	>999	360
TCCL 7.0	Lumber Increase 1.25	Ver(TL) -0.24	16-17	>999	240
BCLL 0.0 *	Rep Stress Incr NO	Horz(TL) 0.01	14	n/a	240
BCDL 5.0	Code FBC2007/TP12002	Wind(TL) 0.24	11-13	>542	240

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2	Structural wood sheathing directly applied or 5-4-3 oc purlins.
BOT CHORD 2 X 4 SYP No.2	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2 X 4 SYP No.3	1 Row at midpt 6-16, 8-14
OTHERS 2 X 4 SYP No.3	Mitek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.

REACTIONS All bearings 0-3-8 except (if=length) 14=0-5-8, 20=0-5-8.
 (b) - Max Horz 2=-176(LC 7)
 Max Uplift All uplift 100 lb or less at joint(s) except 2=-271(LC 6), 14=-887(LC 7), 20=-993(LC 6), 11=-286(LC 7)
 Max Gray All reactions 250 lb or less at joint(s) except 2=390(LC 10), 14=1819(LC 1), 20=1856(LC 1), 11=268(LC 11)


FORCES (lb) - Max. Comp/Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 3-4=-207/250, 4-5=-504/175, 5-6=-965/585, 6-7=-596/452, 7-8=-714/451, 8-9=-213/493.
 BOT CHORD 17-18=-155/726, 19-20=-898/722, 19-47=-155/726, 47-48=-155/726, 48-49=-24/616, 49-50=-24/616, 15-16=0/309, 15-51=0/309, 51-52=0/309, 14-52=0/309, 8-16=-93/517, 8-14=-1615/896, 10-14=-411/694, 10-13=-315/236, 6-17=-143/331, 5-19=-957/592, 4-19=-683/1531, 4-20=-1934/1130

NOTES (1) Unbalanced roof live loads have been considered for this design.
 (2) Wind: ASCE 7-05; 10mph (3-second gust); TCCL=4.2psf; BCDL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate gird DOL=1.60
 (3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1-2002.
 (4) All plates are 2x4 MTT20 unless otherwise indicated.
 (5) Gable studs spaced at 2-0-0 oc.
 (6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 (7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 5.0psf.
 (8) All bearings are assumed to be SYP No.2.
 (9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 271 lb uplift at joint 2, 887 lb uplift at joint 14, 993 lb uplift at joint 20 and 286 lb uplift at joint 11.
 (10) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 (11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 (12) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 (13) Truss Designer Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MTT-7473 BEFORE USE.
 Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Application of design parameters and proper incorporation of component is the responsibility of the building designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the fabricator. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding erection, delivery, storage, erection and bracing, consult ANSI/TPI 1 Quality Criteria, D58-89 and BCS1 Building Component Safety Information available from Truss Plate Institute, 583 D'Oncchio Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

Job	Truss	T18	COMMON	Qty	9	Ply	TROY LAND RES.	1	Job Reference (optional)	7.140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:17 2010 Page 1
327354										14395720



LOADING (psf)	SPACING	Plates Increase	Rep Stress Incr	Code FBC2007/TP2002	CSI	DEFL	Wind(LL)	Horz(TL)	Vert(TL)	in (loc)	L/dell	L/d
20.0	2.0-0	1.25	1.25	2.0-0	0.95	0.02	0.02	0.02	0.23	13.14	>999	240
TCLL												360
TCDL												240
BCLL												n/a
BCDL												240

LUMBER	TOP CHORD	2 X 4 SYP No. 2	Except	TOP CHORD	2 X 4 SYP No. 1D	BOT CHORD	2 X 4 SYP No. 2	WEBS	2 X 4 SYP No. 3
RECTIONS									
(b) - Max Horiz 2 = -155(LC 7)									
All bearings 0-3-8 except (if length) 11=0-5-8, 17=0-5-8.									
(b) - Max Horiz 2 = -155(LC 7)									
Max Grav All reactions 250 lb or less at joint(s) except 2 = -266(LC 6), 11 = -465(LC 7), 17 = -787(LC 6), 8 = -252(LC 7)									
Max Grav All reactions 250 lb or less at joint(s) except 2 = -266(LC 6), 11 = -465(LC 7), 17 = -787(LC 6), 8 = -252(LC 7)									

FORCES	(b) - Max. Comp/Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-18 = -506/310, 3-19 = -721/390, 4-19 = -270/201, 4-5 = -830/543, 5-6 = -613/418, 6-7 = -132/360
BOT CHORD	2-17 = -139/354, 16-17 = -499/382, 16-20 = -81/687, 20-21 = -81/687, 15-21 = -81/687, 14-15 = -81/687, 14-22 = -20/511, 22-23 = -20/511, 12-24 = -20/271, 24-25 = -20/271, 11-25 = -20/271
WEBS	6-13 = -27/436, 6-11 = -1279/643, 7-10 = -458/737, 7-10 = -310/234, 5-14 = -228/426, 4-14 = -151/278, 4-16 = -749/402, 3-16 = -366/1150, 3-17 = -2232/1315
NOTES	(10-11)
1) Unbalanced roof live loads have been considered for this design.	
2) Wind: ASCE 7-05, 11 mph (3-second gust); TCDDL = 4.2psf; BCDDL = 3.0psf; h = 18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) and C-C	
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDDL = 5.0psf.	
5) All bearings are assumed to be SYP No. 2.	
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 266 lb uplift at joint 2, 465 lb uplift at joint 11	
7) Semi-rigid pitchbrakes including heels* Member end fixity model was used in the analysis and design of this truss.	
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 138 lb down and 102 lb up at 4-0-0 on top chord. The design/selection of such connection device(s) is the responsibility of others.	
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).	
10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.	
11) Truss Design Engineer: Julius Lee, PE; License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435	




LOAD CASE(S) Standard
 11) Truss Design Engineer: Julius Lee, PE; License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

Job	Truss	T16	327354
Truss Type	SPECIAL	1	
Qty	Ply	1	
	TROY LAND RES.		14395718

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)

7,140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:16 2010 Page 1



LOADING (psf)	SPACING	DEFL	BRACING	LUMBER
TCLL 20.0	Plates Increase 1.25	Ver(TL) -0.10	Structural wood sheathing directly applied or 4-4-6 oc purlins, except end verticals.	TOP CHORD 2 X 4 SYP No. 2
TCCL 7.0	Lumber Increase YES	Horz(TL) 0.09	Rigid ceiling directly applied or 5-10-15 oc bracing.	BOT CHORD 2 X 4 SYP No. 3
BCCL 0.0	Rep Stress Incr YES	Wind(LL) 0.14	Fasten T and I braces to narrow edge of web with 10d Common wire nails, 9in o.c. with 4in minimum end distance.	WEBS 2 X 4 SYP No. 3
BCDL 5.0	Code FBC2007/TP2002	Ver(TL) -0.20	Brace must cover 90% of web length.	WEBS 2 X 4 SYP No. 3

REACTIONS	FORCES	NOTES
Max Horiz 2=290(LC 6)	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	(1) Unbalanced roof live loads have been considered for this design.
Max Uplift 9=221(LC 5), 2=259(LC 6)	TOP CHORD 2-3=1651/763, 3-4=1950/1122, 4-5=1193/710, 5-6=1124/730, 6-7=748/452	(2) Wind: ASCE 7-05: 11 mph (3-second gust): TCCL=4.2psf, BCCL=3.0psf, h=18ft, Cat. II: Exp B: enclosed; MWFRS (low-rise) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate gnp DOL=1.60
	BOT CHORD 2-14=981/1401, 4-12=399/640, 11-12=1158/1685, 10-11=681/1063, 9-10=452/748	(3) Provide adequate drainage to prevent water ponding.
	WEBS 3-14=470/422, 12-14=1042/1476, 3-12=171/275, 4-11=891/670, 5-11=506/834, 6-11=329/164, 6-10=457/333, 7-10=198/420, 7-9=1041/631	(4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.

6) All bearings are assumed to be SYP No. 2.

7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 9=221, 2=259.

8) "Semi-rigid pitchbreaks including heels" Member and fixity model was used in the analysis and design of this truss.

9) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required for any particular building is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TP1 1 as referenced by the building code.


11) Truss Design Engineer: Julius Lee, P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

LOAD CASE(S) Standard

DESIGN INFORMATION - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Application of design parameters and proper incorporation of component is the responsibility of the building designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erection, quality control, storage, delivery, erection and bracing. Consult ANSI/TP1 Quality Criteria, D58-87 and BCS1 Building Component Safety Information available from Truss Piche Institute, 583 D'Oroville Drive, Madison, WI 53719.

July 12, 2010



Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435


(2) Wind: ASCE 7 roof live load (3-second gust): TC1D1=4.2psf, BC1D1=3.0psf, Cat. II, Exp B; enclosed: MWFRS (low-rise) and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
(3) Provide adequate drainage to prevent water ponding.
(4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
(5) * This truss has been designed for a live load of 20 psf on the bottom chord in all areas where a reangle 3-6-0 fall by 2-0-0 wide will fall between the bottom chord and any other members.
(6) All bearings are assumed to be SYP No. 2.
(7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (f=b) 10=209/2=69.
(8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
(9) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
(10) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

TOP CHORD
- Max Comp/Max. Ten. - 18217/107.4, 4.5- = 1759/1116, 5.6- = 1706/1137, 6.7- = 1806/1096.
TOP CHORDS (lb) - 2.3-Max Comp/Max. Ten. - 18217/107.4, 4.5- = 1759/1116, 5.6- = 1706/1137, 6.7- = 1806/1096.
BOT CHORD
2.1-18=938/540, 8.9-9=911/528, 9.10-8=878/517
7.8-9=939/540, 8.9-9=911/528, 9.10-8=878/517
2.1-18=938/540, 8.9-9=911/528, 9.10-8=878/517
3.18-8=405/341, 16.18-8=979/1453, 14.1-16=1106/1556, 6.1-14=558/830, 6.1-13=324/606,
7.1-13=569/396, 7.1-12=1123/707, 9.1-12=707/1219
WEBS


REACTIONS (lb/size) 10=902/0-5-8, 2=1002/0-5-8
Max Horz 2=249(LC 6)
Max Uplift 10=-200(LC 7), 2=-269(LC 6)

Structural wood sheathing directly applied or 4-5-13 oc purlins, except end verticals,
Rigid ceiling directly applied or 5-1-4 oc bracing,
MilTek recommends that Stabilizers and required cross bracing

LOADING (psi)	20.0	TC/L	1.25	Plates increase	2.0-0	CSi	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP	244/190	Weight: 185 lb
	7.0	TC/L	1.25	Lumber increase		BC	Vent(TL)	-0.24	13-14	>99				
	0.0	BCLL	YES	Rep Stress incr		WB	Horz(TL)	0.14	10	n/a				
	5.0	BC/L		Code FBC2007/TP12002		(Matrix)	Wind(LL)	0.17	13-14	>99				



Job	327354	T12	SPECIAL	Qty	1	Ply	TROY LAND RES.	Job Reference (optional)	7.140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:14 2010 Page 1
									14395714



LOADING (psf)	SPACING	CS	DEF	Ver(TL)	Horz(TL)	Wind(TL)	DEFL	L/D	PLATES	GRIP	Weight: 173 lb
20.0	2.0-0	0.93	0.23	-0.44	0.36	0.28	0.28	9-12	MT20	244/190	
TCL	Plates Increase	TC	in (loc)	Ver(TL)	Horz(TL)	Wind(TL)		>999			
TCDL	Lumber Increase	BC		-0.44	0.36	0.28		10			
BCLL	Rep Stress Incr	WB		0.36	0.36	0.28		n/a			
BCDL	Code FBC2007/TFP2002	CSI		0.28	0.28	0.28		240			

LUMBER	TOP CHORD	BOT CHORD	WEBS	REACTIONS	FORCES	TOP CHORD	BOT CHORD	WEBS
2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 3	10 = 893/0-5-8, 2 = 263/LC 6	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2 X 4 SYP No. 3
2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 3	Max Horiz 2 = 154/LC 6	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2 X 4 SYP No. 3
2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 2	2 X 4 SYP No. 3	Max Uplift 10 = 157/LC 7, 2 = 263/LC 6	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2-3 = 1631/855, 3-4 = 1786/1005, 4-5 = 1768/1128, 5-6 = 1828/1081, 6-7 = 1854/1092, 7-8 = 1838/1029, 8-9 = 2439/1316, 9-10 = 699/398	2 X 4 SYP No. 3

NOTES (10-11)

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-05: 11 mph (3-second gust); TCDF=4.2psf; BCDF=3.0psf; h=18ft; Cat. III; Exp B; enclosed; MWFRS (low-rise) and C-C

3) Provide adequate drainage to prevent water ponding.

4) This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.

5) * All bearings are assumed to be SYP No. 2.

6) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.

7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (if=lb) 10=15.

8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.

9) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.

10) Trust Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

11) Standard

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erection. Quality control, delivery, erection and bracing: consult ANSI/TPI1 Quality Criteria, D58-87 and BCS11 Building Component Safety Information available from Truss Plate Institute, 583 D'Oncio Drive, Madison, WI 53719.

LOAD CASE(S) Standard

FLORIDA PROFESSIONAL ENGINEER


STATE OF FLORIDA

JULIUS S.K. LEE

License No. 34869

Boynton, FL 33435

Job	Truss	T10	327354	14395712
Truss Type	SPECIAL	1	Ply	TROY LAND RES.
Qty	1			
Job Reference (optional)	7.140 S Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:13 2010 Page 1			



LOADING (psf)	SPACING	CSI	DEFL	in (loc)	L/d	PLATES	GRIP	Weight: 168 lb
TCLL 20.0	Plates Increase 1.25	TC 0.54	Vert(TL) -0.44	14	>756	360		
TCDL 7.0	Lumber Increase 1.25	BC 0.76	Vert(TL) -0.85	13-14	>395	240		
BCLL 0.0	Rep Stress Incr YES	WB 0.78	Horz(TL) 0.47	10	n/a	n/a		
BCDL 5.0	Code FBC2007/TP12002	(Mainx)	Wind(LL) 0.53	14	>636	240		

LUMBER	BRACING	TOP CHORD	BOT CHORD
2 X 4 SYP No. 2 *Except*	Structural wood sheathing directly applied or 2-8-3 oc purlins.		
T3: 2 X 6 SYP No. 1D	Rigid ceiling directly applied or 4-6-0 oc bracing.		
2 X 4 SYP No. 2 *Except*	Mitek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.		
B2, B4: 2 X 4 SYP No. 3, B6: 2 X 6 SYP No. 1D			
2 X 4 SYP No. 3			
OTHERS 2 X 6 SYP No. 1D			
LBR SCAB 8-10 2 X 6 SYP No. 1D one side			

REACTIONS	FORCES	TOP CHORD	BOT CHORD	WEBS
(lb/size) 10=892/0-5-8, 2=899/0-5-8	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	2-3=-1629/874, 3-4=-1381/740, 4-5=-2341/1309, 5-6=-4316/2296, 6-7=-4436/2358, 7-8=-2545/1339, 8-19=-2496/1295, 9-19=-2534/1287, 9-20=-406/262, 10-20=-452/257	2-18=-801/1388, 5-16=-1186/627, 13-14=-1955/3942, 12-13=-1955/3942, 9-12=-1191/2499	3-18=-238/256, 4-18=-638/349, 16-18=-685/1412, 4-16=-825/1586, 14-16=-1216/2418, 5-14=-1103/2207, 7-14=-285/563, 7-12=-1520/780, 8-12=-185/448
Max Horz 2=130(LC 6)	Max Uplift 10=-174(LC 4), 2=-239(LC 6)			

NOTES (11-12)

1) Attached 5-8-15 scab 8 to 10, front face(s) 2 X 6 SYP No. 1D with 2 row(s) of 10d (0.131"x3") nails spaced 9" o.c. except: starting at 0-0-5 from end at joint 8, nail 2 row(s) at 4" o.c. for 5-1-1.

2) Unbalanced roof live loads have been considered for this design.

3) Wind: ASCE 7-05; 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior (2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grp DOL=1.60

4) Provide adequate drainage to prevent water ponding.

5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.

7) All bearings are assumed to be SYP No. 2.

8) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TFP 1 angle to grain formula. Building designer should verify capacity of bearing surface.

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (if lb) 10=174, 2=239.


10) *Pin all pitchbreaks* Member end fixity model was used in the analysis and design of this truss.

11) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TFP 1 as referenced by the building code.


12) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard

July 12, 2010



Job	Truss	327354	Builder's FirstSource, Lake City, FL 32055
Truss Type	SPECIAL	1	Job Reference (optional)
Qty	Ply	1	TROY LAND RES.
			7.140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:12 2010 Page 1




LOADING (psf)	SPACING	Plates Increase	Lumber Increase	Rep Stress Incr	Code FBC2007/FP12002	CSI	DEFL	in (loc)	L/d	GRIP	PLATES	Weight: 151 lb
TCLL 20.0	2'-0-0	1.25	1.25	NO	2'-0-0	0.57	Vert(L) -0.42	12-13	>803	360	MT20	
TCDL 7.0						0.88	Vert(TL) -0.85	12-13	>401	240		
BCLL 0.0						0.85	Horz(TL) 0.24	8	n/a	240		
BCDL 5.0						(Mainx)	Wind(LL) 0.55	12-13	>610	240		

LUMBER	TOP CHORD	BOT CHORD	WEBS
2 X 4 SYP No.2	2 X 4 SYP No.2	B1: 2 X 6 SYP No.1D, B2: 2 X 4 SYP No.3	2 X 4 SYP No.3
Max Horiz 2=110(LC 5)	Max Horiz 2=552(LC 5), 8=436(LC 6)		
Max Uplift 2=1078(LC 9), 8=995(LC 1)	Max Gray 2=1078(LC 9), 8=995(LC 1)		

REACTIONS (lb/size) 2=1077/0-5-8, 8=995/0-5-8
 Max Horiz 2=110(LC 5)
 Max Uplift 2=552(LC 5), 8=436(LC 6)
 Max Gray 2=1078(LC 9), 8=995(LC 1)

FORCES (lb) - Max. Comp/Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1801/991, 3-17=-4015/2432, 17-18=-4015/2432, 4-19=-4150/2488, 19-20=-4150/2488, 5-20=-4150/2488, 5-21=-3233/1616, 21-22=-3233/1616, 6-22=-3233/1616, 6-23=-3233/1616, 23-24=-3233/1616, 7-24=-3234/1616, 7-8=-1688/794, 2-16=-872/1523, 13-27=-2161/4111, 12-28=-2161/4111, 12-29=-2161/4111, 29-30=-2161/4111, 11-31=-656/1453, 31-32=-656/1453, 10-32=-656/1453, 8-10=-659/1447, 3-16=-382/217, 13-17=-1617/2648, 5-13=-338/43, 5-11=-927/614, 7-11=-970/1872


NOTES (11-12)
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-05, 10 mph (3-second gust), TCDDL=4.2psf, BCDDL=3.0psf, h=18ft, Cal. II, Exp B, enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate gyp DOL=1.60
 3) Provide adequate drainage to prevent water ponding.
 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 6) All bearings are assumed to be SYP No.2.
 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (l=lb) 2=552, 8=436
 8) *Semi-rigid pitchbreaks including heels: Member end fixity model was used in the analysis and design of this truss.
 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 18 lb up at 7-7-4, 1 lb down and 75 lb up at 9-7-4, 1 lb down and 75 lb up at 11-7-4, 22 lb up at 13-7-4, 22 lb up at 15-7-4, 22 lb up at 17-7-4, 22 lb up at 19-7-4, 22 lb up at 21-7-4, and 22 lb up at 23-7-4, 8 lb down and 59 lb up at 25-8-0 on top chord, and 146 lb down and 146 lb up at 7-7-4, 8 lb down at 9-7-4, 11 lb down at 11-7-4, 11 lb down at 13-7-4, 11 lb down at 15-7-4, 11 lb down at 17-7-4, 11 lb down at 19-7-4, 11 lb down at 21-7-4, 11 lb down at 23-7-4, and 29 lb down at 25-7-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 Continued on page 2



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MUI 7473 BEFORE USE.
 Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component stability during construction is the responsibility of the erector. Additional support of individual web members only. Additional temporary bracing to insure stability of building design - not truss designer. Bracing shown for erection, quality control, storage, delivery, erection and bracing. consult ANS/TP1 Quality Criteria, D58-89 and ECSI1 Building Component Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435


Job	Truss	108	SPECIAL	Qty	1	Ply	TROY LAND RES.	1	Job Reference (optional)	7,140 S Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:12 2010 Page 1
327354										



LOADING (psf)	SPACING	Code FBC2007/TP12002	CSI	DEFL	in (loc)	L/d	PLATES	GRIP	Weight: 194 lb
TCLL 20.0	Plates Increase 1.25	2-0-0	TC 0.71	Vert(TL) -0.25	13-14	>999	MT20	244/190	
TCDL 7.0	Lumber Increase 1.25		BC 0.83	Vert(TL) -0.38	13-14	>702			
BCLL 0.0	Rep Stress Incr NO		WB 0.88	Horz(TL) 0.03	11	n/a			
BCLD 5.0				Wind(TL) 0.16	13-14	>999			

LUMBER	TOP CHORD	2 X 4 SYP No.2	TOP CHORD	2 X 4 SYP No.3	WEBS	2 X 4 SYP No.3
REACTIONS (lb/size)	2-961/0-5-8, 11=1895/0-3-8					
Max Horiz 2=333(C 6)						
Max Uplift 2=-236(C 6), 11=-343(C 5)						
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.						
TOP CHORD	2-3=1597/530, 3-4=1448/543, 4-5=701/272, 5-6=-92/280, 6-7=-102/308					
BOT CHORD	2-14=-849/1347, 14-16=-581/901, 16-17=-581/901, 13-17=-581/901, 9-11=-800/354,					
WEBS	4-14=-285/635, 4-13=-667/495, 5-13=-512/1141, 5-11=-1090/588, 7-9=-446/147					
NOTES	(10-11)					
1) Wind: ASCE 7-05, 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) and C-C						
Exterior(2) zone-C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60						
2) Provide adequate drainage to prevent water ponding.						
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.						
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will						
5) All bearings are assumed to be SYP No.2.						
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (l=lb) 2=236.						
7) *Semi-rigid pitchbreaks including heels* Member and fixity model was used in the analysis and design of this truss.						
8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.						
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).						
10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.						
11) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435						

LOAD CASE(S) Standard	Continued on page 2
July 12, 2010	




WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MUI-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Application of design parameters and proper incorporation of component is the responsibility of the building designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erection, delivery, erection and bracing, consult ANSI/TPI1 Quality Criteria, 058-87 and BCS11 Building Component Safety Information available from Truss Piece Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395709
3277354	T07	SPECIAL	1		Job Reference (optional)	
Builders FirstSource, Lake City, FL 32055						7.1405 Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 1



LOADING (psf)	SPACING	Code FBC2007/TP12002	CSI	DEFL	Wind (LL)	Horiz (TL)	Vert (TL)	in (loc)	L/d	PLATES	GRIP	Weight: 188 lb
20.0	2.0-0	Plates Increase 1.25	TC 0.79	-0.25	0.03	-0.38	-0.38	13-14	>999	MT20	244/190	
7.0		Lumber Increase 1.25	BC 0.86	0.03	0.03	0.03	0.03	13-14	>999			
5.0		Rep Stress Incr NO	WB 0.69	0.16	0.16	0.16	0.16	13-14	>999			

LUMBER	TOP CHORD	2 X 4 SYP No.2	TOP CHORD	2 X 4 SYP No.2	WEBS	2 X 4 SYP No.3	WEBS	2 X 4 SYP No.3	WEBS	2 X 4 SYP No.3	WEBS	2 X 4 SYP No.3
11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382	11-18=237/382
12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382	12-18=237/382
13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895	13-17=550/895
14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895	14-16=550/895
15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339	15-15=339
16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895	16-17=550/895
17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382	17-18=237/382
18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382	18-19=237/382
19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382	19-20=237/382


REACTIONS	(lb/size)	2=968/0-5-8	11=1839/0-3-8	Max Horiz 2=300(LC 6)	Max Uplift 2=243(LC 6), 11=348(LC 5)	FORCES	(lb) - Max Comp/Max Ten	- All forces 250 (lb) or less except when shown	TOP CHORD	2-3=1617/577	3-4=1468/589	4-5=701/295	5-6=99/298	6-7=115/339	BOT CHORD	2-3=1617/577	3-4=1468/589	4-5=701/295	5-6=99/298	6-7=115/339	WEBS	3-14=231/255	4-14=308/662	4-13=610/436	5-13=436/1037	5-11=1179/583	7-9=461/156	NOTES	(10-11)	1) Wind: ASCE 7-05: 110mph (3-second gust); TCCL=4.2psf; BCCL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior (2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	2) Provide adequate drainage to prevent water ponding	3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads	4) This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCCL = 5.0psf.	5) All bearings are assumed to be SYP No. 2.	6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (if=lb) 2=243, 11=348	7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.	8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.	9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).	10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.	11) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435	LOAD CASE(S) Standard	Continued on page 2
-----------	-----------	-------------	---------------	-----------------------	--------------------------------------	--------	-------------------------	---	-----------	--------------	--------------	-------------	------------	-------------	-----------	--------------	--------------	-------------	------------	-------------	------	--------------	--------------	--------------	---------------	---------------	-------------	-------	---------	---	---	---	---	--	---	--	---	--	--	--	-----------------------	---------------------

INSTALLATION GUIDE	MITTEK RECOMMENDS THAT STABILIZERS AND REQUIRED CROSS BRACING BE INSTALLED DURING TRUSS ERECTION, IN ACCORDANCE WITH STABILIZER	PROFESSIONAL ENGINEER	FLORIDA	STATE OF	JULIUS S.K. LEE	NO 34869	1109 Coastal Bay Blvd, Boynton, FL 33435	July 12, 2010
--------------------	---	-----------------------	---------	----------	-----------------	----------	--	---------------

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE M17-743 BEFORE USE.	Design valid for use only with Mitek connections. This design is based only upon parameters shown, and is for an individual building component.	Applicability of design parameters and proper incorporation of component - not truss designer, bracing shown is for joined support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the fabricator. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding erection, delivery, erection and bracing, refer to the Mitek Quality Control Manual.	Safety information available from Mitek Plate Institute, 583 D'Oroff Drive, Madison, WI 53719.	ANSI/TPI 1 Quality Control Manual, B58-87 and B581 Building Component	Julius Lee	1109 Coastal Bay Blvd, Boynton, FL 33435
--	---	--	--	---	------------	--

Job	327354	Truss	T06	SPECIAL	Qty	1	Ply	TROY LAND RES.	14395708
-----	--------	-------	-----	---------	-----	---	-----	----------------	----------

Builders FirstSource, Lake City, FL 32055 7.140 S Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 1




LOADING (psf)	SPACING	Plates Increase	Plates Increase	Rep Stress Incr	Code FBC2007/TP12002	CSI	DEFL	in (loc)	L/d	GRIP	PLATES	Weight: 183 lb
TCLL 20.0	2.0-0	1.25	1.25	NO	2.0-0	0.68	Vert(LL)	-0.29	13-14	360	MT20	
TCDL 7.0		1.25	1.25			0.82	Vert(TL)	-0.42	13-14	240		
BCLL 0.0						0.85	Horz(TL)	0.04	11	n/a		
BDDL 5.0							Wind(LL)	0.16	13-14	>999		


LUMBER	TOP CHORD	2 X 4 SYP No.2	TOP CHORD	2 X 4 SYP No.3	WEBS	2 X 4 SYP No.3 - 5-11, 7-9	Fasten T and l braces to narrow edge of web with 10d Common wire	Brace must cover 90% of web length.	Mittek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.
FORCES (lb) - Max Comp/Max Ten. - All forces 250 (lb) or less except when shown.	2-3=-1648/617, 3-4=-1495/624, 4-5=-710/319, 5-6=-103/306, 6-7=-131/349	2-3=-346/676, 11-18=-864/433, 6-9=-499/358	7-9=-454/167	3-14=-244/268, 4-14=-318/687, 4-13=-548/374, 5-13=-376/961, 5-11=-1339/612					

REACTIONS	(lb/size) 2=977/0-5-8, 11=1871/0-3-8 Max Horiz 2=268(LC 6) Max Uplift 2=-247(LC 6), 11=-353(LC 5)
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown:	
TOP CHORD	2-3=-1648/617, 3-4=-1495/624, 4-5=-710/319, 5-6=-103/306, 6-7=-131/349
BOT CHORD	2-14=-828/1396, 14-16=-521/900, 16-17=-521/900, 13-17=-521/900, 12-13=-346/676, 12-18=-346/676, 11-18=-346/676, 9-11=-864/433, 6-9=-499/358
WEBS	3-14=-244/268, 4-14=-318/687, 4-13=-548/374, 5-13=-376/961, 5-11=-1339/612, 7-9=-454/167
NOTES (10-11)	
1) Wind: ASCE 7-05, 110mph (3-second gust); TCDD=4.2psf; BCDD=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior (2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	

NOTES	(10-11)								
1) Wind: ASCE 7-05; 10 mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cal. I; Exp B; enclosed; MWFRS (low-rise) and C-C									
2) Provide adequate drainage to prevent water ponding.									
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.									
4) * Fit between the bottom chord and any other members, with BCDL = 5.0psf.									
5) All bearings are assumed to be SYP No.2.									
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (l=lb) 2=247.									
7) "Semi-rigid pitchbreaks including heels" Member and fixity model was used in the analysis and design of this truss.									
8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.									
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).									
10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TP1 1 as referenced by the building code.									
11) Truss Design Engineer: Julius Lee, P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435									



Job	327354	Truss	T05	SPECIAL	Qty	1	Ply	TROY LAND RES.	Job Reference (optional)	1	7.140 S Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:11 2010 Page 1
-----	--------	-------	-----	---------	-----	---	-----	----------------	--------------------------	---	--



LOADING (psf)	SPACING	CSI	DEFL	in (loc)	L/d	PLATES	GRIP	Weight: 182 lb
TCLL 20.0	Plates Increase 1.25	TC 0.36	Vert(TL) -0.33	14-15	>943	360		
TCDL 7.0	Lumber Increase 1.25	BC 0.89	Vert(TL) -0.48	14-15	>639	240		
BCLL 0.0	Rep Stress Incr NO	WB 0.86	Horz(TL) 0.05	11	n/a			
BCLD 5.0	Code FBC2007/TP12002	(Mainx)	Wind(LL) 0.20	14-15	>999	240		

LUMBER	TOP CHORD	BOT CHORD	WEBS
2 X 4 SYP No.2	2 X 4 SYP No.2	2 X 4 SYP No.3	2 X 4 SYP No.3
2 X 4 SYP No.2	2 X 4 SYP No.2	2 X 4 SYP No.3	2 X 4 SYP No.3
2 X 4 SYP No.2	2 X 4 SYP No.2	2 X 4 SYP No.3	2 X 4 SYP No.3

Structural wood sheathing directly applied or 4-0-10 oc purlins, except end verticals.
Rigid ceiling directly applied or 6-0-0 oc bracing.
T-Brace:
2 X 4 SYP No.3 - 6-11
Fasten T and l braces to narrow edge of web with 10d Common wire nails, 9in o.c. with 4in minimum end distance.
Brace must cover 90% of web length.
Mittek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.

REACTIONS (lb/size) 2=137/0-5-8, 11=139/10-3-8
Max Horiz 2=236(LC 6)
Max Uplift 2=277(LC 6), 11=327(LC 5)
FORCES (lb) - Max Comp/Max, Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=2215/893, 3-4=2063/907, 4-5=1297/586, 5-6=541/248
BOT CHORD 2-15=1024/1900, 15-16=645/1310, 14-17=645/1310, 13-14=479/1010, 12-18=479/1010, 11-12=248/541, 10-11=385/221, 7-10=260/183
WEBS 3-15=268/304, 4-15=381/754, 5-14=219/588, 5-12=934/461, 6-12=347/847, 6-11=1162/535

NOTES (10-11)
(1) Wind: ASCE 7-05; 10mph (3-second gust); TCDL=4.2psf; BCLD=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
(2) Provide adequate drainage to prevent water ponding.
(3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
(4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 5.0psf.
(5) All bearings are assumed to be SYP No.2.
(6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (if=lb) 2=277, 11=327.
(7) "Semi-rigid pitchbreaks including heels" Member and fixity model was used in the analysis and design of this truss.
(8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.
(9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
(10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
(11) Truss Design Engineer: Julius Lee, PE; License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard
Continued on page 2



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 BEFORE USE.
Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component or building designer - not truss designer, bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding location, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 Quality Criteria, D58-87 and BCS1 Building Component Safety Information available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITER REFERENCE PAGE III-7473 BEFORE USE.

Design valid for use only with Mitek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erection. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding erection, quality control, storage, delivery, erection and bracing consult **ANSI/TPI1 Quality Criteria, D58-87 and BCS11 Building Component** available from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Julius Lee
1109 Coastal Bay Blvd.
Boynton, FL 33435

July 12, 2010



LOAD CASE(S) Standard
Uniform Loads (plf)

Vert: 1-4=-54, 4-5=-54, 5-8=-54, 2-15=-10, 14-15=-70(F=-60), 12-14=-10, 11-12=-10, 9-10=-10

Builders FirstSource, Lake City, FL 32055


7:140 5 Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:10 2010 Page 2

Job	Truss	TROY LAND RES.	14395705
Truss Type	Qty	Ply	Job Reference (optional)
SPECIAL	1	1	1
T03			
327354			

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE M11-7473 BEFORE USE.
 Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component.
 Application of design parameters and proper incorporation of component is responsibility of building designer. Brocting shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the fabricator. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI1 Quality Criteria, D58-89 and ECSI1 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oroville Drive, Madison, WI 53719.

Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

July 12, 2010



LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-4=-54, 4-5=-54, 5-8=-54, 8-11=-54, 11-14=-54, 14-21=-70(F=-60), 21-24=-70(F=-60), 24-25=-20(F)
 Concentrated Loads (lb)
 Vert: 16=-97(F) 17=-97(F) 18=-97(F) 19=-97(F) 20=-20(F) 21=-20(F) 22=-20(F) 23=-20(F) 24=-20(F) 25=-20(F)

Job	Truss	Truss Type	Qty	Ply	TROY LAND RES.	14395704
327354	T02	SPECIAL	1	1	Job Reference (optional)	



Vertical Loads (plf)

LOAD CASE(S) Standard

1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

NOTES (13-14)

(1) Unbalanced roof live loads have been considered for this design.

(2) Wind: ASCE 7-05: 11 mph (3-second gust); TCDFL=4 zpsf; BCDL=3 dpsf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60 zone and C-C exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1-2002.

(4) All plates are 2x4 MT20 unless otherwise indicated.

(5) Gable requires continuous bottom chord bearing.

(6) Gable studs spaced at 2'-0"-oc.

(7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

(8) * This truss has been designed for a live load of 20 dpsf on the bottom chord in all areas where a rectangle 3'-6"-0" tall by 2'-0"-0" wide will fit between the bottom chord and any other members.

(9) All bearings are assumed to be SYP No.2.

(10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13 except (if=b) 11 "Semi-rigid pitchbraces including heels". Member end and fixity model was used in the analysis and design of this truss.

(12) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

(13) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.

(14) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435

REACTIONS

IONS All bearings 22-6-0.

OTHERS	2 X 4 SYP No.3
--------	----------------

BOT CHORD 2 X 4 SYP No.2

TOP CHORD 2 X 4 SYP No.2

BRACING
TOP CHORD
BOT CHORD


Structural wood sheathing directly applied or 6-0-0 oc purlins.

Mitek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer

installation guide.


[illegible]

Plate Offsets (X,Y): [2:0-3-8,Edge],[2:0-2-8,Edge]



Scale = 1:40.8

Job	Truss	Truss Type	JACK	Qty	1	Ply	1	TRUSS LAND RES.	14395701
327354	H44							Job Reference (optional)	
								7.140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:08 2010 Page 1	



LOADING (psf)	SPACING	DEFL	DEFL	in (loc)	W/dell	L/d	PLATES	GRIP	Weight: 16 lb
TCDL 20.0	Plates Increase 1.25	TC 0.35	Ver(TL) -0.01	2-4	>999	360	MT20	244/190	
TCDL 7.0	Lumber Increase 1.25	BC 0.08	Horz(TL) -0.00	3	n/a	240			
BCLL 0.0	Rep Stress Incr NO	WB 0.00	Wind(TL) 0.00	2	***	240			
BCDL 5.0	Code FBC2007/TP12002								

LUMBER	TOP CHORD	2 X 4 SYP No.2	BRACING	TOP CHORD	2 X 4 SYP No.2	Bot CHORD	2 X 4 SYP No.2

REACTIONS (lb/size) 3=47/Mechanical, 2=25/0-8-8, 4=16/Mechanical
 Max Horiz 2=116(LC 3)
 Max Uplift 3=49(LC 6), 2=259(LC 3)
 Max Grav 3=47(LC 1), 2=255(LC 1), 4=48(LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (10-11)
 1) Wind: ASCE 7-05: 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end
 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 4) All bearings are assumed to be SYP No. 2.
 5) Refer to girder(s) for truss to truss connections.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (if=lb) 2=259.
 7) Semi-rigid pitchbreaks including heels' Member end fixity model was used in the analysis and design of this truss.
 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 25 lb up at 1-5-12, and 25 lb up at 1-5-12, and 16 lb up at 1-5-12, and 16 lb up at 1-5-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 11) Truss Design Engineer: Julius Lee, PE: Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435.


LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-3=-5.4, 2-4=-10
 Concentrated Loads (lb)
 Vert: 5=50(F=25, B=25) 6=11(F=5, B=5)



July 12, 2010

Job	327354	Truss	EJ7	MONO HIP	Qty	1	Ply	TROY LAND RES.	Job Reference (optional)	1
-----	--------	-------	-----	----------	-----	---	-----	----------------	--------------------------	---

Builders FirstSource, Lake City, FL 32055 7/14/5 Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:07 2010 Page 1



LOADING (psf)	SPACING	CSI	DEFL	in (loc)	L/d	PLATES	GRIP	Weight: 35 lb
TCLL 20.0	Plates Increase 1.25	TC 0.24	Vert(LL) -0.08	2-5	>999	MIT20	244/190	
TCCL 7.0	Lumber Increase 1.25	BC 0.19	Vert(TL) -0.16	2-5	>555			
BCCL 0.0	Rep Stress Incr YES	WB 0.07	Horz(TL) -0.00	5	n/a			
BCDL 5.0	Code FBC2007/TP12002	(Matrix)	Wind(LL) 0.03	2-5	>999			

LUMBER	BRACING	TOP CHORD	BOT CHORD
TOP CHORD 2 X 4 SYP No. 2	Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.		
BOT CHORD 2 X 4 SYP No. 2	Rigid ceiling directly applied or 10'-0" oc bracing.		
WEBS 2 X 4 SYP No. 3			

REACTIONS (lb/size) 5'-218/Mechanical, 2'-334/0-5-8
 Max Horz 2=134(LC 6)
 Max Uplift 5=-59(LC 6), 2=-124(LC 6)
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 3-5=-215/279
NOTES (9-11)
 1) Wind: ASCE 7-05: 110mph (3-second gust); TCCL=4.2psf; BCCL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) and C-C
 Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 2) Provide adequate drainage to prevent water ponding.
 3) This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
 5) All bearings are assumed to be SYP No. 2.
 6) Refer to girder(s) for truss to truss connections.
 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 59 lb uplift at joint 5 and 124 lb uplift at joint 2.
 8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 9) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 10) Truss Design Engineer: Julius Lee, P.E. License No. 34869; Address: 1109 Coastal Bay Blvd. Boynton Beach, FL 33435
 11) Use Simpson HTU26 to attach Truss to Carrying member


LOAD CASE(S) Standard
 Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer, for general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI Quality Criteria, D58-89 and BC511 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oroffo Drive, Madison, WI 53719.



July 12, 2010
 Julius Lee
 1109 Coastal Bay Blvd.
 Boynton, FL 33435

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE M17-73 BEFORE USE.
 Design valid for use only with Mittek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer, for general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult **ANSI/TPI Quality Criteria, D58-89 and BC511 Building Component Safety Information** available from Truss Plate Institute, 583 D'Oroffo Drive, Madison, WI 53719.

Job	Truss	EJ38	JACK	Qty	1	Ply	1	TROY LAND RES.	14395697
327354								Job Reference (optional)	
								7:140 s Oct 1 2009 Mittek Industries, Inc. Mon Jul 12 09:46:07 2010 Page 1	



LOADING (psf)	20.0	TCLL	2.00	SPACING	2.0-0	CSI	0.17	DEFL	in (loc)	5-6	>999	360	L/d
	7.0	TCDL	1.25	Plates Increase	1.25	BC	0.10	Vert(TL)	-0.00	5-6	>999	240	L/d
	0.0	BCLL	NO	Rep Stress Incr	NO	WB	0.05	Horz(TL)	-0.00	3	n/a	240	n/a
	5.0	BCDL	NO	Code FBC2007/TFP12002		(Matrix)		Wind(LL)	0.00	5-6	>999	240	n/a

LUMBER	2 X 4 SYP No.2	BRACING	Structural wood sheathing directly applied or 2-1-8 oc purlins, except end verticals.	MITTEK recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.
WEBS	2 X 4 SYP No.3	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	

REACTIONS (lb/size) 6=342/0-5-0, 3=46/Mechanical, 4=156/Mechanical
 Max Horiz 6=165(LC 5)
 Max Uplift 6=108(LC 5), 3=31(LC 6), 4=14(LC 5)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES (10-11)
 1) Wind: ASCE 7-05: 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MVFRS (low-rise) gable end
 Zone: end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 3) This truss has been designed for a live load of 20 Dpsf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 4) All bearings are assumed to be SYP No.2.
 5) Refer to girder(s) for truss to truss connections.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 108 lb uplift at joint 6, 31 lb uplift at joint 3 and 141 lb uplift at joint 4.
 7) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 68 lb down and 32 lb up at 0-1-12, and 208 lb down and 65 lb up at 2-0-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 10) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TFP 1 as referenced by the building code.
 11) Truss Design Engineer: Julius Lee, P.E.; Florida P.E. License No. 34669; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (psf)
 Vert: 1-2=-54, 2-3=-54, 4-6=-10
 Concentrated Loads (lb)
 Vert: 6=-68 7=-208(F)
 July 12, 2010



Job	Truss	EJ3	JACK	Qty	7	Ply	TROY LAND RES.	1	Job Reference (optional)	7,140 s Oct 1 2009 Mitek Industries, Inc. Mon Jul 12 09:46:06 2010 Page 1	14395695
-----	-------	-----	------	-----	---	-----	----------------	---	--------------------------	---	----------



LOADING (psf)	SPACING	CSI	DEFL	in (loc)	L/dell	L/d	PLATES	GRIP	Weight: 12 lb
TCLL 20.0	Plates Increase 1.25	TC 0.18	Vert(LL) -0.00	2-4	>999	360	MT20	244/190	
TCDL 7.0	Lumber Increase 1.25	BC 0.05	Vert(TL) -0.00	2-4	>999	240			
BCLL 0.0	Rep Stress Incr YES	WB 0.00	Horz(TL) -0.00	3	n/a	240			
BCDL 5.0	Code FBC2007/TPI2002	(Matrix)	Wind(LL) 0.00	2	****	240			

LUMBER	BRACING	TOP CHORD	BOT CHORD
2 X 4 SYP No. 2	Structural wood sheathing directly applied or 3'-0\"		

Mitek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer installation guide.

REACTIONS (lb/size) 3=43/Mechanical, 2=210/0-5-8, 4=14/Mechanical
 Max Horiz 2=115(LC 6)
 Max Uplift 3=34(LC 7), 2=158(LC 6)
 Max Grav 3=43(LC 1), 2=210(LC 1), 4=41(LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
NOTES (8-9)
 1) Wind: ASCE 7-05: 110mph (3-second gust); TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cal. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Extentior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate gnp DOL=1.60
 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0\"

4) All bearings are assumed to be SYP No. 2.
 5) Refer to girder(s) for truss to truss connections.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 34 lb uplift at joint 3 and 158 lb uplift at joint 2.
 7) *Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.
 8) This manufactured product is designed as an individual building component. The suitability and use of this component for any particular building is the responsibility of the building designer per ANSI TPI 1 as referenced by the building code.
 9) Truss Design Engineer: Julius Lee, PE; Florida P.E. License No. 34869; Address: 1109 Coastal Bay Blvd, Boynton Beach, FL 33435



RE: 327354 - TROY LAND RES.

Site Information:

Project Customer: SKYLINE HOMES Project Name: 327354 Model: TROY LAND RES.
Lot/Block:
Address: 100 NW LOWER SPRINGS RD
City: COLUMBIA CTY State: FL

BEARING HEIGHT SCHEDULE

	10' 1-1/8"
	8' 1-1/8"

NOTES:

- 1) REFER TO HB-9 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V05 FOR ALTERNATE BRACING REQUIREMENTS.
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
- 4) ALL TRUSSES ARE DESIGNED FOR 2" e.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
- 5) ALL WALLS SHOWN ON THIS AGENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
- 6) 5/42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
- 7) ALL ROOF TRUSSES HANGERS TO BE SAME-SON H106 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSSES HANGERS TO BE SAME-SON TH442 UNLESS OTHERWISE NOTED.
- 8) BEARING/CEILING/INTEL (B/C/I) TO BE FURNISHED BY BUILDER.

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND V005 ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS, REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.



Accepted By: _____ Date: _____



Jacksonville
Bunnell
PHONE: 904-437-5349 FAX: 904-437-5494
Lake City
PHONE: 904-772-6100 FAX: 904-772-1973
Sanford
PHONE: 386-755-6894 FAX: 386-755-7973
PHONE: 407-322-0054 FAX: 407-322-9553

BUILDER:
SKYLINE HOMES
TROY LAND RES.

DATE: 6-16-10 DRAWN BY: K.L.H. 327354
SCALE: NTS
REVISION:



6/12 PITCH
18" 0/H

MASTER BEDROOM TRAY
MAXIMUM 14" DEEP