

Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 3235275 - IC CONST. - HAMRICK RES.

MiTek USA, Inc.

16023 Swingley Ridge Rd
Chesterfield, MO 63017

Site Information:

Customer Info: IC CONSTRUCTION Project Name: Hamrick Res. Model: Custom
Lot/Block: 57 Subdivision: The Oaks
Address: TBD, TBD
City: Columbia Cty State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.

Name: License #:
Address:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2020/TPI2014 Design Program: MiTek 20/20 8.5
Wind Code: ASCE 7-16 Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 45 individual, Truss Design Drawings and 0 Additional Drawings.

With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T28327328	CJ01	7/22/22	15	T28327342	T02	7/22/22
2	T28327329	CJ03	7/22/22	16	T28327343	T03	7/22/22
3	T28327330	CJ05	7/22/22	17	T28327344	T04	7/22/22
4	T28327331	EJ01	7/22/22	18	T28327345	T04G	7/22/22
5	T28327332	HJ10	7/22/22	19	T28327346	T05	7/22/22
6	T28327333	PB01	7/22/22	20	T28327347	T05G	7/22/22
7	T28327334	PB01G	7/22/22	21	T28327348	T06	7/22/22
8	T28327335	PB02	7/22/22	22	T28327349	T07	7/22/22
9	T28327336	PB02G	7/22/22	23	T28327350	T08	7/22/22
10	T28327337	PB03	7/22/22	24	T28327351	T09	7/22/22
11	T28327338	PB03G	7/22/22	25	T28327352	T10	7/22/22
12	T28327339	T01	7/22/22	26	T28327353	T10G	7/22/22
13	T28327340	T01G	7/22/22	27	T28327354	T11	7/22/22
14	T28327341	T01GG	7/22/22	28	T28327355	T11G	7/22/22




This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision based on the parameters
provided by Builders FirstSource-Lake City, FL.

Truss Design Engineer's Name: Lee, Julius

My license renewal date for the state of Florida is February 28, 2023.




Julius Lee PE No. 34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

July 22, 2022

Lee, Julius

1 of 2



RE: 3235275 - IC CONST. - HAMRICK RES.

MiTek USA, Inc.

16023 Swingley Ridge Rd
Chesterfield, MO 63017

Site Information:

Customer Info: IC CONSTRUCTION Project Name: Hamrick Res. Model: Custom
Lot/Block: 57 Subdivision: The Oaks
Address: TBD, TBD
City: Columbia Cty State: FL

No.	Seal#	Truss Name	Date
29	T28327356	T12	7/22/22
30	T28327357	T12G	7/22/22
31	T28327358	T13	7/22/22
32	T28327359	T14	7/22/22
33	T28327360	T14G	7/22/22
34	T28327361	T15	7/22/22
35	T28327362	T15G	7/22/22
36	T28327363	T16	7/22/22
37	T28327364	T17	7/22/22
38	T28327365	V01	7/22/22
39	T28327366	V02	7/22/22
40	T28327367	V03	7/22/22
41	T28327368	V04	7/22/22
42	T28327369	V05	7/22/22
43	T28327370	V06	7/22/22
44	T28327371	V07	7/22/22
45	T28327372	V08	7/22/22




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327329
3235275	CJ03	Jack-Open	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:30 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-hgZJsXXIDWh_4o?Lq9NpqKiRTO08cAP0jQQXp2yvosR



Scale = 1:17.3

Plate Offsets (X,Y)--		[2:0-1-13,0-1-0]									
LOADING	(psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.25	TC 0.16	Vert(LL)	-0.00	4-7	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC 0.08	Vert(CT)	-0.01	4-7	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MP						Weight: 13 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=97(LC 12)
Max Uplift 3=-44(LC 12), 2=-49(LC 12)
Max Grav 3=65(LC 19), 2=210(LC 1), 4=51(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 2-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 44 lb uplift at joint 3 and 49 lb uplift at joint 2.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.
3235275	CJ05	Jack-Open	2	1	T28327330

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:31 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-9s7i4tXw_qpriyaYOtu2MXFaJoKILcf9y4A5LUyvosQ



Scale: 1/2"=1'

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.28	Vert(LL)	0.03	4-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.24	Vert(CT)	-0.06	4-7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 19 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=143(LC 12)
Max Uplift 3=-81(LC 12), 2=-49(LC 12), 4=-1(LC 12)
Max Grav 3=120(LC 19), 2=276(LC 1), 4=89(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 4-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 81 lb uplift at joint 3, 49 lb uplift at joint 2 and 1 lb uplift at joint 4.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.
3235275	EJ01	Jack-Partial	12	1	T28327331

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:31 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-9s7i4tXw_qpriyaY0tu2MXFZHoHhLbS9y4A5LUyvosQ



Scale = 1:30.2

Plate Offsets (X,Y)--		[2:0-1-9,0-2-5]	
LOADING (psf)		SPACING-	2-0-0
TCLL 20.0		Plate Grip DOL	1.25
TCDL 7.0		Lumber DOL	1.25
BCLL 0.0 *		Rep Stress Incr	YES
BCDL 10.0		Code	FBC2020/TPI2014
		CSI.	
		TC 0.35	
		BC 0.44	
		WB 0.08	
		Matrix-MS	
		DEFL.	
		in (loc)	I/defl L/d
		Vert(LL) -0.08 6-9 >999	240
		Vert(CT) -0.16 6-9 >529	180
		Horz(CT) 0.00 2 n/a	n/a
		PLATES	GRIP
		MT20	244/190
		Weight: 32 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=182(LC 12)
Max Uplift 4=-48(LC 12), 2=-55(LC 12), 5=-58(LC 12)
Max Grav 4=77(LC 19), 2=346(LC 1), 5=184(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 6-11-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 4, 55 lb uplift at joint 2 and 58 lb uplift at joint 5.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327332
3235275	HJ10	Diagonal Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:32 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-d3h4HDYYI7xiJ68kxAPHvlogTCah4_9JBkveuwvyosP



Scale = 1:29.6

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.58	Vert(LL) -0.05	6-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.58	Vert(CT) -0.11	6-7	>999	180		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.37	Horz(CT) 0.01	5	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 45 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=182(LC 8)
Max Uplift 4=-93(LC 8), 2=-191(LC 8), 5=-114(LC 8)
Max Grav 4=148(LC 1), 2=526(LC 1), 5=300(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-667/208
BOT CHORD 2-7=-285/553, 6-7=-285/553
WEBS 3-7=0/285, 3-6=-604/312

NOTES-

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 4, 191 lb uplift at joint 2 and 114 lb uplift at joint 5.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 62 lb down and 73 lb up at 1-6-1, 62 lb down and 73 lb up at 1-6-1, 80 lb down and 46 lb up at 4-4-0, 80 lb down and 46 lb up at 4-4-0, and 109 lb down and 92 lb up at 7-1-15, and 109 lb down and 92 lb up at 7-1-15 on top chord, and 21 lb down and 45 lb up at 1-6-1, 21 lb down and 45 lb up at 1-6-1, 25 lb down at 4-4-0, 25 lb down at 4-4-0, and 47 lb down and 16 lb up at 7-1-15, and 47 lb down and 16 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 7=-4(F=-2, B=-2) 12=-73(F=-36, B=-36) 15=-59(F=-29, B=-29)

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327333
3235275	PB01	Piggyback	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:33 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-5FFSVZZAWR3ZxGjwVlwWSyK_zc3gpW9SPOfBQNYvosO




Plate Offsets (X,Y)--		[3:0-3-0,Edge]									
LOADING	(psf)	SPACING-		CSL		DEFL.	in	(loc)	I/defl	L/d	PLATES
TCLL	20.0	Plate Grip DOL	1.25	TC	0.02	Vert(LL)	-0.00	4	n/r	120	MT20
TCDL	7.0	Lumber DOL	1.25	BC	0.02	Vert(CT)	-0.00	4	n/r	120	GRIP
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a	n/a	244/190
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-P							Weight: 7 lb
											FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=1-5-12, 4=1-5-12
Max Horz 2=18(LC 11)
Max Uplift 2=-22(LC 12), 4=-22(LC 13)
Max Grav 2=81(LC 1), 4=81(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 2 and 22 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327334
3235275	PB01G	PIGGYBACK	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:34 2022 Page 1
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-ZRppqivaoHIBQZPI73?RI_At9c0OGYzPce1OlypyvosN



Scale = 1:6.0

										1-11-6			
Plate Offsets (X,Y)-- [2:0-3-7,Edge]										1-11-6			
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP			
TCLL	20.0	Plate Grip DOL 1.25		TC	0.02	Vert(LL) n/a - n/a		999		MT20	244/190		
TCDL	7.0	Lumber DOL 1.25		BC	0.00	Vert(CT) n/a - n/a		999					
BCLL	0.0 *	Rep Stress Incr YES		WB	0.00	Horz(CT) 0.00 3 n/a		n/a					
BCDL	10.0	Code FBC2020/TPI2014		Matrix-P						Weight: 3 lb	FT = 20%		

LUMBER-

TOP CHORD 2x4 SP No.2

REACTIONS.

(size) 1=1-11-6, 3=1-11-6
Max Horz 1=10(LC 9)
Max Uplift 1=-14(LC 12), 3=-14(LC 13)
Max Grav 1=38(LC 1), 3=38(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 1 and 14 lb uplift at joint 3.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327335
3235275	PB02	Piggyback	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:35 2022 Page 1
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-1eNCwFbQ22JHAZtJdiy_XNQIkPjH9th8IUfYvosM



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.13	Vert(LL) 0.00	5	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.12	Vert(CT) 0.01	5	n/r	120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 29 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS.

(size) 2=6-11-13, 4=6-11-13, 6=6-11-13
Max Horz 2=58(LC 11)
Max Uplift 2=44(LC 12), 4=52(LC 13), 6=34(LC 12)
Max Grav 2=154(LC 1), 4=154(LC 1), 6=260(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-5 to 3-3-5, Interior(1) 3-3-5 to 4-3-0, Exterior(2R) 4-3-0 to 7-3-0, Interior(1) 7-3-0 to 8-2-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 44 lb uplift at joint 2, 52 lb uplift at joint 4 and 34 lb uplift at joint 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327336
3235275	PB02G	GABLE	1	1	Job Reference (optional)	


Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:36 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-Wqxb7bb3pMR8ojSVAQUD3byTNp3M0tXv5Ltr1hyvosL



Scale = 1:16.8



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.14	Vert(LL) 0.00	5	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.09	Vert(CT) 0.01	5	n/r	120		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.02	Horz(CT) 0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-P					Weight: 25 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=5-11-3, 4=5-11-3, 6=5-11-3
Max Horz 2=-51(LC 10)
Max Uplift 2=-46(LC 12), 4=-53(LC 13), 6=-15(LC 12)
Max Grav 2=146(LC 1), 4=146(LC 1), 6=200(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-5 to 3-3-5, Interior(1) 3-3-5 to 3-8-12, Exterior(2R) 3-8-12 to 6-8-5, Interior(1) 6-8-5 to 7-2-2 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 46 lb uplift at joint 2, 53 lb uplift at joint 4 and 15 lb uplift at joint 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327337
3235275	PB03	GABLE	18	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:15:37 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-_0VzKwchagZ?Qt1hk7?ScoVeaDP_IJq2K?dPZ8yvosK




Plate Offsets (X,Y)-- [2:0-3-9,0-1-8], [3:0-0-0,0-0-0], [6:0-3-9,0-1-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.17	Vert(LL)	0.00	6	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.13	Vert(CT)	0.00	7	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S						Weight: 65 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS.

All bearings 14-11-12.
(lb) - Max Horz 2=-117(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 6 except 8=-161(LC 13), 10=-161(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 2, 6 except 9=255(LC 1), 8=338(LC 20), 10=339(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 5-8=-252/181, 3-10=-253/182

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-5 to 3-3-5, Interior(1) 3-3-5 to 8-3-0, Exterior(2R) 8-3-0 to 11-3-0, Interior(1) 11-3-0 to 16-2-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4'-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6 except (jt=lb) 8=161, 10=161.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327338
3235275	PB03G	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:15:38 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-SD2LYGdJLzhs11culrWh902qqdmEUnmbZfMy5ayvosJ



4x4 =

Scale = 1:30.8




Plate Offsets (X,Y)-- [2:0-3-9,0-1-8], [8:0-3-9,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.07	Vert(LL)	0.00	9	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.06	Vert(CT)	0.00	9	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 69 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

- All bearings 13-11-3.
(lb) - Max Horz 2=-109(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 8, 13, 11 except 14=-107(LC 12), 10=-107(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 2, 8, 12, 13, 14, 11, 10

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-5 to 3-3-5, Interior(1) 3-3-5 to 7-8-11, Exterior(2R) 7-8-11 to 10-8-11, Interior(1) 10-8-11 to 15-2-2 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8, 13, 11 except (jt=lb) 14=107, 10=107.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327339
3235275	T01	Common	17	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:39 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-wPcjicex6HqjfBB4sY1whDatm1yvD81LoJ6Wd0yvosl



4x6 ||

Scale = 1:51.5




Plate Offsets (X,Y)-- [3:0-3-0,0-3-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.64	Vert(LL)	-0.14	7-9	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.67	Vert(CT)	-0.25	7-9	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.42	Horz(CT)	0.04	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 146 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-6-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 6=0-3-8, 2=0-3-8
Max Horz 2=198(LC 11)
Max Uplift 6=-249(LC 13), 2=-283(LC 12)
Max Grav 6=1303(LC 20), 2=1381(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1994/403, 3-4=-1874/440, 4-5=-1883/446, 5-6=-2004/410
BOT CHORD 2-9=-382/1737, 7-9=-149/1120, 6-7=-267/1609
WEBS 4-7=-259/1020, 5-7=-328/232, 4-9=-251/1007, 3-9=-324/230

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 25-0-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=249, 2=283.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 4-6=-54, 2-9=-20, 7-9=-80(F=-60), 6-7=-20

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see


ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders FirstSource (Lake City, FL) Lake City, FL - 32055, 8530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:40 2022 Page 1
ID:e1QvOht7s?_4_S?OvDtno3RzFGI6-ObA5zyeZtbyaHKmGPGY9ER74KQNLybkU0zr3ATyvosh
-1-6-0 6-0-0 12-6-0 19-0-0 25-0-0
1-6-0 6-0-0 6-6-0 6-6-0 6-0-0



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except:
WEBS	2x4 SP No.3		10-0-0 oc bracing: 8-9.
OTHERS	2x4 SP No.3	WEBS	1 Row at midbt 5-13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-4=-138/346, 4-5=-116/542, 5-7=-537/199, 7-8=-679/177
BOT CHORD	2-16=-281/165, 15-16=-281/165, 14-15=-281/165, 13-14=-93/566
WEBS	5-9=-185/655, 7-9=-402/261, 5-13=-921/257, 4-13=-304/224

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

July 22, 2022




Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327341
3235275	T01GG	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:41 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-sokUAlfBeu4RuUKTzz3OmeqKpqnBh8ceFdbciyvovsG



Scale = 1:29.3




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [10:0-3-8,Edge]

LOADING (psf)	SPACING-		CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25		TC 0.15	Vert(LL)	-0.01	11	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL 1.25		BC 0.05	Vert(CT)	-0.01	11	n/r	120		
BCLL 0.0 *	Rep Stress Incr YES		WB 0.03	Horz(CT)	0.00	10	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 72 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 13-4-0.
(lb) - Max Horz 2=-112(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 10, 15, 16, 13, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 10, 14, 15, 16, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) 1-6-0 to 1-6-0, Exterior(2N) 1-6-0 to 6-8-0, Corner(3R) 6-8-0 to 9-8-0, Exterior(2N) 9-8-0 to 14-10-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 10, 15, 16, 13, 12.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327343
3235275	T03	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:44 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-HNQcoKi4wpS?ly32e5d5OHImV2aZuMI4xbpHJEYvosD



Scale = 1:52.1




Plate Offsets (X,Y)-- [3:0-3-0,0-3-0], [7:0-6-0,0-0-7], [10:0-2-4,0-3-4]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.45	Vert(LL)	-0.19	8	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.96	Vert(CT)	-0.38	9-10	>797	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.61	Horz(CT)	0.27	7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 147 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2 *Except*
 4-11,5-8: 2x4 SP No.3
 WEBS 2x4 SP No.3 *Except*
 6-9: 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-15 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 9-7-1 oc bracing.
 WEBS 1 Row at midpt 5-10

REACTIONS.

(size) 7=0-3-8, 2=0-3-8
 Max Horz 2=198(LC 9)
 Max Uplift 7=182(LC 13), 2=216(LC 12)
 Max Grav 7=923(LC 1), 2=1008(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1385/262, 3-4=-1407/265, 4-5=-1391/294, 5-6=-3342/547, 6-7=-1401/289
 BOT CHORD 2-12=-267/1099, 4-10=-186/1127, 9-10=-381/2849, 8-9=-122/870, 5-9=-165/1383,
 7-8=-191/1141
 WEBS 3-12=-356/158, 10-12=-293/1193, 5-10=-1833/410, 6-9=-357/2716, 6-8=-1348/230

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 25-0-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=182, 2=216.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
 MiTek Inc. DBA MiTek USA FL Cert 6634
 16023 Swingley Ridge Rd. Chesterfield, MO 63017
 Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327344
3235275	T04	Roof Special	7	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:45 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-lZz_Ogiih7asN6eECp8KxUqxMR?tdjsDAFZqrgyvosc




Plate Offsets (X,Y)-- [1:0-8-0,0-0-7], [6:0-3-0,0-0-3-0], [7:0-2-14,0-1-8], [12:0-5-8,0-2-8]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.44	Vert(LL)	-0.17	12-15	>999	240	MT20 244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.70	Vert(CT)	-0.37	12-15	>817	180	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.22	7	n/a	n/a	
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 139 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-3-6 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=Mechanical, 7=0-3-8
Max Horz 1=-198(LC 10)
Max Uplift 1=-182(LC 12), 7=-216(LC 13)
Max Grav 1=923(LC 1), 7=1008(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1361/288, 2-3=-1165/264, 3-4=-1069/263, 4-5=-1065/268, 5-6=-2395/385,
6-7=-2698/408
BOT CHORD 1-12=-288/1129, 11-12=-179/992, 10-11=-213/2008, 9-10=-273/2323, 7-9=-276/2317
WEBS 2-12=-255/152, 4-11=-208/898, 5-11=-1504/224, 5-10=-174/1669, 6-10=-265/167

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 26-6-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=182, 7=216.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327345
3235275	T04G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:46 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-DIXND?JKSRij?FDQmWfZTIN7irN1MGiNPvINN6yv0sB



Scale = 1:57.5




Plate Offsets (X,Y)-- [1:0-2-9,Edge], [9:0-3-8,0-0-2], [9:1-6-6,Edge], [14:0-5-8,0-2-8]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.34	Vert(LL)	-0.06 11-36	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.45	Vert(CT)	-0.12 11-36	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.62	Horz(CT)	0.04 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 167 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-10-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

All bearings 8-8-0 except (jt=length) 1=0-3-8, 1=0-3-8, 9=0-3-8.
(lb) - Max Horz 1=-190(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 17 except 1=-301(LC 24), 1=-198(LC 1), 9=-148(LC 13), 14=-272(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 15, 16, 17 except 9=464(LC 1), 14=1507(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-3=-41/698, 3-4=-82/843, 6-7=-353/40, 7-9=-814/149
BOT CHORD 1-17=-571/174, 16-17=-571/174, 15-16=-571/174, 14-15=-571/174, 13-14=-738/262, 12-13=0/293, 11-12=-17/698, 9-11=-30/734
WEBS 4-14=-1087/175, 4-13=-22/741, 5-13=-407/19, 6-13=-524/88, 6-12=0/481, 7-12=-444/189

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 26-6-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17 except (jt=lb) 1=301, 9=148, 14=272.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327346
3235275	T05	Common	2	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:47 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-hx5IRLkyDkqacPocKEAo0vD6Fh65qWWdZ2xvZyvosA




Plate Offsets (X,Y)-- [4:0-2-3,Edge]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d
TCLL 20.0		Plate Grip DOL	1.25	TC 0.68		Vert(LL)	-0.10 6-9	>999	240
TCDL 7.0		Lumber DOL	1.25	BC 0.59		Vert(CT)	-0.18 6-9	>995	180
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.14		Horz(CT)	0.01 2	n/a	n/a
BCDL 10.0		Code	FBC2020/TPI2014	Matrix-MS					
					PLATES	GRIP			
					MT20	244/190			
					Weight: 63 lb		FT = 20%		

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.

(size) 2=0-3-8, 4=0-3-8
Max Horz 2=-135(LC 10)
Max Uplift 2=-145(LC 12), 4=-145(LC 13)
Max Grav 2=648(LC 1), 4=648(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-682/162, 3-4=-682/162
BOT CHORD 2-6=-42/479, 4-6=-42/479
WEBS 3-6=0/357

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 7-8-0, Exterior(2R) 7-8-0 to 10-8-0, Interior(1) 10-8-0 to 16-10-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=145, 4=145.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327347
3235275	T05G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:48 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-98f7ehla_2yREZNptxh1Y7SWBf9CqJ?gsDnUS?yvos9



Scale = 1:32.7




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [10:0-3-8,Edge]

LOADING (psf)	SPACING-		CSL.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.15	Vert(LL)	-0.00	11	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.09	Vert(CT)	-0.00	11	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	10	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S						Weight: 83 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

- All bearings 15-4-0.
(lb) - Max Horz 2=-127(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 10, 15, 16, 13, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 10, 14, 15, 16, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-6-0 to 1-6-0, Exterior(2N) 1-6-0 to 7-8-0, Corner(3R) 7-8-0 to 10-8-0, Exterior(2N) 10-8-0 to 16-10-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 10, 15, 16, 13, 12.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327348
3235275	T06	Common Girder	1	2	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:50 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-5Wnt3NmrWfC9TtWB?MkVeYXrOSpB11QyJXGbWtyvos7



Scale: 3/8"=1'




Plate Offsets (X,Y)-- [1:0-4-0,0-1-9], [5:0-4-0,0-1-9], [7:0-4-0,0-3-12]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.23	Vert(LL) -0.06	7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.25	Vert(CT) -0.10	7-8	>999	180		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.76	Horz(CT) 0.02	5	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 201 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x8 SP 2400F 2.0E
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-2-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=0-3-8, 5=0-3-8
Max Horz 1=-113(LC 25)
Max Uplift 1=-736(LC 8), 5=-806(LC 9)
Max Grav 1=3558(LC 1), 5=3894(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-5454/1132, 2-3=-3856/833, 3-4=-3857/835, 4-5=-5521/1144
BOT CHORD 1-8=-959/4512, 7-8=-959/4512, 6-7=-901/4570, 5-6=-901/4570
WEBS 3-7=-844/4016, 4-7=-1767/450, 4-6=-354/1805, 2-7=-1694/435, 2-8=-339/1730

NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-8-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=736, 5=806.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 903 lb down and 202 lb up at 2-0-12, 903 lb down and 202 lb up at 4-0-12, 903 lb down and 202 lb up at 6-0-12, 903 lb down and 202 lb up at 8-0-12, 903 lb down and 202 lb up at 10-0-12, and 903 lb down and 202 lb up at 12-0-12, and 903 lb down and 202 lb up at 14-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327348
3235275	T06	Common Girder	1	2	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,
8.530 s Dec 6 2021 MiTek Industries, Inc.
Thu Jul 21 15:15:50 2022
Page 2
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-5Wnt3NmrWfC9TtWB?MkVeYXrOSpBI1QyJXGbWtyvos7

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-3=-54, 3-5=-54, 1-5=-20

Concentrated Loads (lb)

Vert: 8=-903(B) 13=-903(B) 14=-903(B) 15=-903(B) 16=-903(B) 17=-903(B) 18=-903(B)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327349
3235275	T07	Half Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc.
Thu Jul 21 15:15:51 2022
Page 1

1-6-0
3-9-11
7-0-0
13-0-14
19-0-0
24-11-2
31-0-0

1-6-0
3-9-11
3-2-5
6-0-14
5-11-2
5-11-2
6-0-14

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-ZjLFGjnTHzK0515OZ3FkAl4tds_?1Si6YB083Kyvos6

Scale = 1:54.7




Plate Offsets (X,Y)--		[2:0-4-5,0-1-8], [4:0-3-12,0-2-0], [10:Edge,0-4-4]							
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.77	in (loc)	I/defl	L/d	GRIP
TCDL	7.0	Lumber DOL	1.25	BC	0.91	Vert(LL)	0.22 12-14	>999	240
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.89	Vert(CT)	-0.38 12-14	>963	180
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS		Horz(CT)	0.11 10	n/a	n/a
								Weight: 204 lb FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-6-11 oc purlins, except end verticals.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 5-9-5 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 5-15
			2 Rows at 1/3 pts 8-10

REACTIONS. (size) 10=Mechanical, 2=0-3-8
Max Horz 2=191(LC 27)
Max Uplift 10=-935(LC 5), 2=-834(LC 8)
Max Grav 10=2423(LC 1), 2=2299(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
2-3=-3742/1395, 3-4=-3590/1372, 4-5=-3007/1193, 5-6=-3968/1538, 6-8=-3968/1538
BOT CHORD 2-15=-1262/3068, 14-15=-1610/4130, 12-14=-1610/4130, 11-12=-1031/2654,
10-11=-1031/2654
WEBS 4-15=-603/1700, 5-15=-1476/623, 5-14=-171/655, 6-12=-355/208, 8-12=-669/1675,
8-11=-167/700, 8-10=-3348/1299

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=935, 2=834.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 66 lb down and 51 lb up at 7-0-0, 66 lb down and 49 lb up at 9-0-12, 66 lb down and 49 lb up at 11-0-12, 66 lb down and 49 lb up at 13-0-12, 66 lb down and 49 lb up at 15-0-12, 66 lb down and 49 lb up at 17-0-12, 66 lb down and 42 lb up at 19-0-12, 66 lb down and 49 lb up at 21-0-12, 66 lb down and 49 lb up at 23-0-12, 66 lb down and 49 lb up at 25-0-12, and 66 lb down and 49 lb up at 27-0-12, and 66 lb down and 49 lb up at 29-0-12 on top chord, and 427 lb down and 220 lb up at 7-0-0, 156 lb down and 78 lb up at 9-0-12, 156 lb down and 78 lb up at 11-0-12, 156 lb down and 78 lb up at 13-0-12, 156 lb down and 78 lb up at 15-0-12, 156 lb down and 78 lb up at 17-0-12, 156 lb down and 78 lb up at 19-0-12, 156 lb down and 78 lb up at 21-0-12, 156 lb down and 78 lb up at 23-0-12, 156 lb down and 78 lb up at 25-0-12, and 156 lb down and 78 lb up at 27-0-12, and 156 lb down and 78 lb up at 29-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the Load CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327349
3235275	T07	Half Hip Girder	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,
8.530 s Dec 6 2021 MiTek Industries, Inc.
Thu Jul 21 15:15:51 2022
Page 2
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-ZjLFGjnTHzK0515OZ3FkAl4tds_?1SI6YB083Kyvos6

LOAD CASE(S)
Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)

Vert: 1-4=-54, 4-9=-54, 2-10=-20
- Concentrated Loads (lb)

Vert: 4=-18(B) 7=-18(B) 13=-156(B) 15=-427(B) 5=-18(B) 14=-156(B) 6=-18(B) 12=-156(B) 11=-156(B) 8=-18(B) 18=-18(B) 19=-18(B) 20=-18(B) 21=-18(B) 22=-18(B) 23=-18(B) 24=-18(B) 25=-156(B) 26=-156(B) 27=-156(B) 28=-156(B) 29=-156(B) 30=-156(B) 31=-156(B)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327350
3235275	T08	Half Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City, FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:52 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-2vveU3o52HStjAga6nmzjzd6mGMFmzCFnrIibmyvos5



Scale = 1:54.2




Plate Offsets (X,Y)-- [2:0-8-0,0-0-12], [4:0-3-12,0-2-0]							
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc) l/defl L/d
TCLL 20.0		Plate Grip DOL	1.25	TC 0.56		Vert(LL)	-0.14 13-16 >999 240
TCDL 7.0		Lumber DOL	1.25	BC 0.78		Vert(CT)	-0.30 13-16 >999 180
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.62		Horz(CT)	0.06 9 n/a n/a
BCDL 10.0		Code	FBC2020/TPI2014	Matrix-MS			
						PLATES	GRIP
						MT20	244/190
						Weight: 181 lb FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.

(size) 9=Mechanical, 2=0-3-8
Max Horz 2=237(LC 12)
Max Uplift 9=-301(LC 9), 2=-292(LC 12)
Max Grav 9=1298(LC 2), 2=1326(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1881/416, 3-4=-1705/371, 4-5=-1383/353, 5-7=-1227/286, 7-8=-1227/286,
8-9=-1157/318
BOT CHORD 2-13=-491/1550, 11-13=-387/1687, 10-11=-387/1687
WEBS 3-13=-290/164, 4-13=-61/675, 5-13=-460/188, 5-11=0/361, 5-10=-602/211,
7-10=-416/201, 8-10=-367/1577

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-7-3, Interior(1) 1-7-3 to 9-0-0, Exterior(2R) 9-0-0 to 13-4-10, Interior(1) 13-4-10 to 30-10-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=301, 2=292.

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 8-4-14 oc bracing.
WEBS 1 Row at midpt 8-9, 5-13, 5-10

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327351
3235275	T09	Half Hip	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:53 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-W5S0hPjpjaakKKFmgUHCFA9H9ghjVO_P0VVF7Cyvos4



LOADING (psf)	SPACING-	CSL.	DEFL.	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.52	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.77	Vert(LL) -0.28 9-10 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.71	Vert(CT) -0.47 9-10 >789 180		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS	Horz(CT) 0.06 9 n/a n/a		
				Weight: 186 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-1-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 8-3-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 5-12, 5-10, 7-9

REACTIONS. (size) 9=Mechanical, 2=0-3-8
Max Horz 2=283(LC 12)
Max Uplift 9=297(LC 9), 2=287(LC 12)
Max Grav 9=1311(LC 2), 2=1331(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1948/391, 3-4=-1585/350, 4-5=-1267/341, 5-7=-1238/250
BOT CHORD 2-13=-510/1577, 12-13=-510/1577, 10-12=-323/1335, 9-10=-223/932
WEBS 3-12=-465/199, 4-12=-41/586, 5-10=-328/210, 7-10=-136/777, 7-9=-1367/331

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-7-3, Interior(1) 1-7-3 to 11-0-0, Exterior(2R) 11-0-0 to 15-4-10, Interior(1) 15-4-10 to 30-10-4 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=297, 2=287.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327352
3235275	T10	Piggyback Base	3	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:55 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-SUam64qzLCrRaeP9ovJgLBFWKTLczPLiTp_MC5yvos2




Plate Offsets (X,Y)--		[3:0-3-0,0-3-4], [4:0-5-12,0-2-0], [5:0-3-12,0-2-0], [6:0-3-0,0-3-0], [8:0-8-9,Edge]					
LOADING (psf)		SPACING-		CSI.		DEFL.	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.98	in (loc)	I/defl
TCDL	7.0	Lumber DOL	1.25	BC	0.96	13-16	>999
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.27	13-16	>999
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS		8	n/a
						PLATES	
						GRIP	
						MT20	
						244/190	
						Weight: 192 lb	
						FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
SLIDER Right 2x8 SP 2400F 2.0E 1-11-8

REACTIONS.

(size) 2=0-3-8, 8=Mechanical
Max Horz 2=227(LC 9)
Max Uplift 2=-266(LC 12), 8=-226(LC 13)
Max Grav 2=1363(LC 19), 8=1278(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1850/333, 3-4=-1288/297, 4-5=-997/295, 5-6=-1273/297, 6-8=-1642/309
BOT CHORD 2-13=-330/1606, 12-13=-330/1600, 10-12=-123/1052, 9-10=-164/1287, 8-9=-164/1291
WEBS 3-13=0/369, 3-12=-712/268, 4-12=-130/552, 5-10=-109/484, 6-10=-480/231, 6-9=0/266

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-7-3, Interior(1) 1-7-3 to 14-6-0, Exterior(2E) 14-6-0 to 17-6-0, Exterior(2R) 17-6-0 to 21-10-10, Interior(1) 21-10-10 to 31-0-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=266, 8=226.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327353
3235275	T10G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:56 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGl6-wg88KQrb6VzIBo_LLdrvtpnmttfisyriTjvkXyvos1




Plate Offsets (X,Y)--		[3:0-3-0,Edge], [5:0-5-12,0-2-0], [6:0-3-12,0-2-0], [10:0-8-9,Edge]					
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc) l/defl L/d
TCLL 20.0		Plate Grip DOL	1.25	TC 0.68		Vert(LL)	-0.14 15-22 >999 240
TCDL 7.0		Lumber DOL	1.25	BC 0.88		Vert(CT)	-0.27 11-12 >999 180
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.31		Horz(CT)	0.11 10 n/a n/a
BCDL 10.0		Code	FBC2020/TPI2014	Matrix-MS			
						PLATES	GRIP
						MT20	244/190
						Weight: 232 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP M 31 *Except*
5-6,3-4,1-3: 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3
SLIDER Right 2x8 SP 2400F 2.0E 1-9-2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-2 oc purlins, except 2-0-0 oc purlins (5-7-6 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 9-8-9 oc bracing.
WEBS 1 Row at midpt 3-14, 5-12, 8-12

REACTIONS.

(size) 2=0-3-8, 10=Mechanical
Max Horz 2=227(LC 9)
Max Uplift 2=-266(LC 12), 10=-226(LC 13)
Max Grav 2=1373(LC 19), 10=1288(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1910/339, 3-5=-1284/297, 5-6=-1008/291, 6-8=-1239/293, 8-10=-1665/309
BOT CHORD 2-15=-341/1675, 14-15=-343/1660, 12-14=-118/1067, 11-12=-166/1286, 10-11=-166/1286
WEBS 3-15=0/374, 3-14=-748/282, 5-14=-127/530, 6-12=-102/435, 8-12=-453/229, 8-11=0/284

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-7-3, Interior(1) 1-7-3 to 15-0-5, Exterior(2E) 15-0-5 to 16-11-11, Exterior(2R) 16-11-11 to 21-4-5, Interior(1) 21-4-5 to 31-0-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=266, 10=226.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327354
3235275	T11	Piggyback Base	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:15:57 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-OtiXXmsEsp59pyZXvKM8Q0KxyH5KR9V_w7TTG_yvos0

1-6-0	6-0-0	10-1-12	15-7-5	19-8-0	24-3-15	28-7-0	32-10-0	39-6-0	46-4-0
1-6-0	6-0-0	4-1-12	5-5-9	4-0-11	4-7-15	4-3-0	4-3-0	6-8-0	6-10-0

Scale = 1:83.5




Plate Offsets (X,Y)--										[2:0-3-6,0-0-1], [3:0-2-8,0-3-0], [7:0-4-4,0-2-4], [9:0-4-4,0-2-4], [10:0-3-0,0-3-0], [12:0-8-9,Edge]												
LOADING (psf)		SPACING-			2-0-0		CSI.		DEFL.				in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL			1.25		TC	0.66	Vert(LL)	-0.13	16-17	>999		240				MT20		244/190		
TCDL	7.0	Lumber DOL			1.25		BC	0.66	Vert(CT)	-0.22	16-17	>999		180								
BCLL	0.0 *	Rep Stress Incr			YES		WB	0.93	Horz(CT)	0.05	12	n/a		n/a								
BCDL	10.0	Code FBC2020/TPI2014					Matrix-MS												Weight: 316 lb		FT = 20%	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-1-2 oc purlins, except
BOT CHORD 2x6 SP No.2	2-0-0 oc purlins (5-2-7 max.): 7-9.
WEBS 2x4 SP No.3	Rigid ceiling directly applied or 6-0-0 oc bracing.
SLIDER Right 2x6 SP No.2 1-11-8	1 Row at midpt 8-16, 8-14, 10-14

REACTIONS. (size) 2=0-3-8, 19=0-3-8, 12=Mechanical
Max Horz 2=230(LC 9)
Max Uplift 2=-201(LC 8), 19=-436(LC 12), 12=-233(LC 13)
Max Grav 2=231(LC 23), 19=2256(LC 2), 12=1400(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-99/512, 3-4=-498/1080, 4-5=-1267/183, 5-6=-1508/295, 6-7=-1516/459,
7-8=-1216/430, 8-9=-1242/461, 9-10=-1569/478, 10-12=-1866/487
BOT CHORD 2-20=-480/147, 19-20=-475/148, 17-19=-1023/529, 16-17=-197/1321, 14-16=-164/1268,
13-14=-309/1489, 12-13=-308/1491
WEBS 3-20=-297/222, 3-19=-728/750, 4-19=-1844/571, 4-17=-661/2454, 5-17=-688/214,
7-16=-130/626, 8-16=-276/155, 9-14=-114/590, 10-14=-431/234

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-1-10, Interior(1) 3-1-10 to 24-3-15, Exterior(2R) 24-3-15 to 28-11-9, Interior(1) 28-11-9 to 32-10-0, Exterior(2R) 32-10-0 to 37-5-10, Interior(1) 37-5-10 to 46-4-0 zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=201, 19=436, 12=233.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601	MiTek 16023 Swingley Ridge Rd Chesterfield, MO 63017
--	--



16023 Swingley Ridge Rd
Chesterfield MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327356
3235275	T12	Piggyback Base	12	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),		Lake City, FL - 32055,		8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:01 2022 Page 1						
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-Hex1N8vkw2bblZsJ8AQ4asVe8uVBnzfarkRgOlyvory										
1-6-0	6-0-0	10-1-12	15-7-5	19-8-0	24-3-15	29-5-2	35-8-13	40-10-0	46-3-8	47-10-0
1-6-0	6-0-0	4-1-12	5-5-9	4-0-11	4-7-15	5-1-3	6-3-11	5-1-3	5-5-8	1-6-8



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.51	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.47	Vert(LL) -0.12 18-19 >999 240		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.92	Vert(CT) -0.21 18-19 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.03 14 n/a n/a		
	Code FBC2020/TPI2014			Weight: 348 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-7-4 oc purlins, except end verticals, and 2-0-0 oc purlins (4-11-14 max.): 7-11.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 12-14: 2x6 SP No.2	WEBS 1 Row at midpt 8-18, 8-16, 10-15

REACTIONS.	(size) 2=0-3-8, 21=0-3-8, 14=0-3-0
	Max Horz 2=311(LC 11)
	Max Uplift 2=-198(LC 8), 21=-433(LC 12), 14=-193(LC 13)
	Max Grav 2=235(LC 23), 21=2236(LC 2), 14=1526(LC 2)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-90/428, 3-4=-562/998, 4-5=-1323/184, 5-6=-1574/296, 6-7=-1541/447, 7-8=-1237/411, 8-10=-1257/429, 10-11=-702/334, 11-12=-912/338, 12-14=-1461/446
BOT CHORD	2-22=-420/0, 21-22=-415/0, 19-21=-943/524, 18-19=-343/1331, 16-18=-318/1302, 15-16=-271/1094
WEBS	3-22=-297/222, 3-21=-725/751, 4-21=-1826/565, 4-19=-651/2426, 5-19=-711/214, 7-18=-120/635, 8-18=-256/188, 10-16=-51/536, 10-15=-879/240, 11-15=-53/319, 12-15=-187/1044

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-1-9, Interior(1) 3-1-9 to 24-3-15, Exterior(2R) 24-3-15 to 28-11-8, Interior(1) 28-11-8 to 40-10-0, Exterior(2R) 40-10-0 to 45-5-8, Interior(1) 45-5-8 to 47-10-0 zone; end vertical right exposed; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 198 lb uplift at joint 2, 433 lb uplift at joint 21 and 193 lb uplift at joint 14.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601	MiTek 16023 Swingley Ridge Rd Chesterfield, MO 63017
--	---

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327357
3235275	T12G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),		Lake City, FL - 32055,		8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:03 2022 Page 1						
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-D03oopw_SfrJxt0hGbTYfHazUi0dr9tJZwnTdyvorw										
1-6-0	6-0-0	10-1-12	15-7-5	19-8-0	24-3-15	29-5-2	35-8-13	40-3-11	46-3-8	47-10-0
1-6-0	6-0-0	4-1-12	5-5-9	4-0-11	4-7-15	5-1-3	6-3-11	4-6-14	5-11-13	1-6-8

Scale = 1:86.9




Plate Offsets (X,Y)--	[2:0-3-6,0-0-1], [3:0-2-8,0-3-0], [7:0-4-4,0-2-4], [9:0-3-0,0-3-0], [11:0-4-4,0-2-4], [13:0-4-12,0-1-8]
-----------------------	---

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.48	Vert(LL) -0.12 19-20 >999 240		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.92	Vert(CT) -0.21 19-20 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.02 15 n/a n/a		
	Code FBC2020/TPI2014			Weight: 408 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-7-5 oc purlins, except end verticals, and 2-0-0 oc purlins (4-11-12 max.): 7-11.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except*	WEBS 1 Row at midpt 8-19, 8-17, 10-16
13-15: 2x6 SP No.2	
OTHERS 2x4 SP No.3	

REACTIONS. (size) 2=0-3-8, 22=0-3-8, 15=0-3-0
Max Horz 2=308(LC 11)
Max Uplift 2=198(LC 8), 22=433(LC 12), 15=199(LC 13)
Max Grav 2=235(LC 23), 22=2236(LC 2), 15=1522(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-92/429, 3-4=-567/1000, 4-5=-1320/180, 5-6=-1570/292, 6-7=-1539/446,
7-8=-1235/410, 8-10=-1251/429, 10-11=-752/344, 11-13=-964/345, 13-15=-1437/447
BOT CHORD 2-23=-423/0, 22-23=-417/0, 20-22=-946/525, 19-20=-344/1329, 17-19=-313/1299,
16-17=-270/1091
WEBS 3-23=-297/221, 3-22=-724/751, 4-22=-1825/566, 4-20=-653/2425, 5-20=-709/213,
7-19=-119/635, 8-19=-257/188, 10-17=-57/528, 10-16=-835/234, 11-16=-56/346,
13-16=-184/1014

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-1-9, Interior(1) 3-1-9 to 24-3-15, Exterior(2R) 24-3-15 to 28-11-8, Interior(1) 28-11-8 to 40-3-11, Exterior(2R) 40-3-11 to 44-11-4, Interior(1) 44-11-4 to 47-10-0 zone; end vertical right exposed; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 198 lb uplift at joint 2, 433 lb uplift at joint 22 and 199 lb uplift at joint 15.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327358
3235275	T13	Piggyback Base	6	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055, 8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:05 2022 Page 1

ID:e1QvOH7s? 4_S?OvDtno3RzFGI6-9PBVCyF_G51nAA4NOv0lifJRVt7JnhAmMPuXWYvoru

1-6-0	6-0-0	10-1-12	15-7-5	19-8-0	24-3-15	29-5-2	35-8-13	40-10-0	46-3-8
1-6-0	6-0-0	4-1-12	5-5-9	4-0-11	4-7-15	5-1-3	6-3-11	5-1-3	5-5-8



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.62	Vert(LL)	-0.12 17-18 >999 240	MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.47	Vert(CT)	-0.21 17-18 >999 180				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03 13 n/a n/a				
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 348 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-7-5 oc purlins, except end verticals, and 2-0-0 oc purlins (5-0-2 max.): 7-11.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except*	WEBS	1 Row at midpt 8-17, 8-15, 10-14
	12-13: 2x6 SP No.2		
OTHERS	2x4 SP No.2		

REACTIONS.	
(size)	2=0-3-8, 20=0-3-8, 13=0-3-0
Max Horz	2=305(LC 9)
Max Uplift	2=-197(LC 8), 20=-432(LC 12), 13=-166(LC 8)
Max Grav	2=236(LC 23), 20=2231(LC 2), 13=1434(LC 2)

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-97/418, 3-4=-587/993, 4-5=-1321/169, 5-6=-1571/279, 6-7=-1535/435, 7-8=-1232/401, 8-10=-1247/415, 10-11=-690/316, 11-12=-889/313, 12-13=-1379/366
BOT CHORD	2-21=-414/0, 20-21=-408/0, 18-20=-939/502, 17-18=-395/1318, 15-17=-361/1294, 14-15=-315/1084
WEBS	3-21=-297/222, 3-20=-725/751, 4-20=-1820/562, 4-18=-647/2418, 5-18=-709/209, 7-17=-113/632, 8-17=-253/185, 10-15=-53/539, 10-14=-883/243, 11-14=-34/310, 12-14=-232/1033

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 3-1-9, Interior(1) 3-1-9 to 24-3-15, Exterior(2R) 24-3-15 to 28-11-8, Interior(1) 28-11-8 to 40-10-0, Exterior(2R) 40-10-0 to 45-5-8, Interior(1) 45-5-8 to 45-9-4 zone; end vertical right exposed; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 2, 432 lb uplift at joint 20 and 166 lb uplift at joint 13.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601	MiTek 16023 Swingley Ridge Rd Chesterfield, MO 63017
--	---

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327359
3235275	T14	Common	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:06 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-dblwQrztladOKIGxj0FHwCX_vDN2RbJ?08R3yyvort




Plate Offsets (X,Y)--		[4:0-2-3,Edge]									
LOADING	(psf)	SPACING-		CSL		DEFL.	in	(loc)	I/defl	L/d	PLATES
TCLL	20.0	Plate Grip DOL	1.25	TC	0.44	Vert(LL)	-0.06	5-8	>999	240	MT20
TCDL	7.0	Lumber DOL	1.25	BC	0.41	Vert(CT)	-0.10	5-8	>999	180	GRIP
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	4	n/a	n/a	244/190
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS							Weight: 51 lb
											FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=0-3-8, 2=0-3-8
Max Horz 2=108(LC 9)
Max Uplift 4=91(LC 13), 2=127(LC 12)
Max Grav 4=464(LC 1), 2=554(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-565/163, 3-4=-563/166
BOT CHORD 2-5=-50/397, 4-5=-50/397
WEBS 3-5=-8/294

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 6-4-0, Exterior(2R) 6-4-0 to 9-4-0, Interior(1) 9-4-0 to 12-8-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 91 lb uplift at joint 4 and 127 lb uplift at joint 2.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327360
3235275	T14G	Common Supported Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:16:07 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-6oJJdBzVWuLk0UKSVRXUq7kmCJfPnv1TEgu_cOyvors



Scale = 1:28.1




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [10:0-3-8,Edge]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.16	Vert(LL)	-0.01	11	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.04	Vert(CT)	-0.01	11	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	10	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S						Weight: 68 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

- All bearings 12-8-0.
(lb) - Max Horz 2=107(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 10, 15, 16, 13, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 10, 14, 15, 16, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Corner(3E) 1-6-0 to 1-6-0, Exterior(2N) 1-6-0 to 6-4-0, Corner(3R) 6-4-0 to 9-4-0, Exterior(2N) 9-4-0 to 14-2-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 10, 15, 16, 13, 12.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327361
3235275	T15	Common	2	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:08 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-a_shrX_7HBTbeevf282jMLHs_jqfWHXcSKdY8ryvorr




Plate Offsets (X,Y)-- [2:0-6-0,0-0-8], [3:0-3-0,0-3-0], [6:0-6-0,0-0-7]

LOADING (psf)	SPACING-	CSL	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.48	Vert(LL)	-0.13	9-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.74	Vert(CT)	-0.28	7-12	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.28	Horz(CT)	0.04	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS						Weight: 125 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

REACTIONS.

(size) 6=0-3-8, 2=0-3-8
Max Horz 2=198(LC 9)
Max Uplift 6=-182(LC 13), 2=-216(LC 12)
Max Grav 6=1059(LC 20), 2=1137(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1475/271, 3-4=-1345/297, 4-5=-1353/304, 5-6=-1484/278
BOT CHORD 2-9=-274/1323, 7-9=-74/846, 6-7=-170/1196
WEBS 4-7=-168/686, 5-7=-358/239, 4-9=-161/674, 3-9=-351/235

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 25-0-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=182, 2=216.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327362
3235275	T15G	Common Structural Gable	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:09 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-2AQ32t?I2VbSFoTrrcrayvYq1f6E3FkVlh_N5gHyvorq



4x6 ||

Scale = 1:57.3




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [5:0-2-0,0-0-0], [8:Edge,0-3-0]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.48	Vert(LL)	-0.09	9-35	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.47	Vert(CT)	-0.19	9-35	>786	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.29	Horz(CT)	0.00	8	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 192 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 5-13

REACTIONS.

All bearings 12-7-8 except (jt=length) 8=0-3-8, 10=0-3-8, 10=0-3-8.
(lb) - Max Horz 2=190(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 2, 16 except 8=118(LC 13), 13=288(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 12, 14, 15, 16, 10, 10, 2 except 2=251(LC 23), 8=625(LC 20), 13=916(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-44/273, 5-7=-585/194, 7-8=-748/185
BOT CHORD 8-9=-98/618
WEBS 5-9=-176/635, 7-9=-416/257, 5-13=-688/162, 4-13=-324/230

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 12-6-0, Exterior(2R) 12-6-0 to 15-6-0, Interior(1) 15-6-0 to 24-10-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 16, 2 except (jt=lb) 8=118, 13=288.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327363
3235275	T16	Common Girder	1	3	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:11 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-_ZYpTZ00Z6sAV5dEkGcQ_zvNEwyTjYx29IsCIayvoro



4x6 ||

Scale = 1:51.8




Plate Offsets (X,Y)-- [2:0-4-0,0-1-9], [9:0-4-0,0-1-9], [11:0-4-0,0-4-8], [12:0-6-0,0-6-0], [13:0-4-0,0-4-8]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.48	Vert(LL)	-0.14	11	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.35	Vert(CT)	-0.25	11	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.68	Horz(CT)	0.06	9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 576 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x8 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except*
6-12: 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-6-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 9=0-3-8, 2=0-3-8
Max Horz 2=198(LC 5)
Max Uplift 9=1858(LC 9), 2=1716(LC 8)
Max Grav 9=8835(LC 2), 2=6378(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-11270/3034, 3-5=-10509/2738, 5-6=-8380/2051, 6-7=-8380/2050, 7-8=-11183/2518,
8-9=-14376/3073
BOT CHORD 2-14=-2579/9336, 13-14=-2579/9336, 12-13=-2246/8711, 11-12=-1992/9272,
10-11=-2491/11943, 9-10=-2491/11943
WEBS 6-12=-2177/9041, 7-12=-4027/861, 7-11=-868/4688, 8-11=-3340/692, 8-10=-619/3591,
5-12=-3203/1181, 5-13=-1251/3651, 3-13=-948/416, 3-14=-316/875

NOTES-

- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 3 rows staggered at 0-5-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=1858, 2=1716.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 2403 lb down and 955 lb up at 7-0-12, 1278 lb down and 321 lb up at 9-0-12, 1291 lb down and 317 lb up at 11-0-12, 1237 lb down and 246 lb up at 12-6-12, 1237 lb down and 246 lb up at 14-6-12, 1237 lb down and 246 lb up at 16-6-12, 1237 lb down and 246 lb up at 18-6-12, 1189 lb down and 233 lb up at 19-0-12, and 1380 lb down and 253 lb up at 21-0-12, and 1380 lb down and 253 lb up at 23-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327363
3235275	T16	Common Girder	1	3	Job Reference (optional)	

Builders FirstSource (Lake City,FL),
Lake City, FL - 32055,
8.530 s Dec 6 2021 MiTek Industries, Inc.
Thu Jul 21 15:16:11 2022
Page 2
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-_ZYpTZ00Z6sAV5dEkGcQ_zvNEwyTjYx29IsCIAyvor0

LOAD CASE(S)
Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)

Vert: 1-6=-54, 6-9=-54, 2-9=-20
- Concentrated Loads (lb)

Vert: 12=-1125(F) 11=-1125(F) 19=-2403(F) 20=-1120(F) 21=-1120(F) 22=-1125(F) 23=-1125(F) 24=-1090(F) 25=-1249(F) 26=-1249(F)

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327364
3235275	T17	MONO TRUSS	18	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:12 2022 Page 1
ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-Sl6Chu1eKQ_16FCQH_7fXBSXIKF1S7zCNyblHcyvorn



Scale = 1:18.1




Plate Offsets (X,Y)-- [2:0-2-6,Edge]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	2-0-0	TC 0.55	Vert(LL)	0.17	5-9	>571	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.46	Vert(CT)	0.14	5-9	>657	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.18	Horz(CT)	0.00	10	n/a	n/a		
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS						Weight: 36 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-9-7 oc bracing.

REACTIONS.

(size) 2=0-3-8, 10=0-2-0
Max Horz 2=82(LC 8)
Max Uplift 2=-197(LC 8), 10=-134(LC 8)
Max Grav 2=381(LC 1), 10=260(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-524/656, 5-6=-397/210, 4-6=-397/210
BOT CHORD 2-5=-734/503
WEBS 3-5=-442/613, 4-10=-268/422

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-6-0 to 1-6-0, Interior(1) 1-6-0 to 7-6-12 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 10.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=197, 10=134.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327365
3235275	V01	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL),	Lake City, FL - 32055,	8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:14 2022 Page 1
14-1-11	14-1-11	ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-O8Ey5a3us1EIMZMpPP97ccXy172rw13UrG4sMUyvorl
		30-1-6
		15-11-11
		36-1-4
		5-11-14
		37-7-12
		1-6-8




Plate Offsets (X,Y)--		[9:0-4-4,0-2-4], [17:0-4-4,0-2-4], [20:0-0-9,0-1-0], [21:0-4-12,0-1-8], [24:0-1-0,0-2-0], [31:0-3-0,0-3-0], [33:0-3-0,0-3-0]										
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	20.0	Plate Grip DOL	1.25	TC	0.18	Vert(LL)	-0.01	22	n/r	120	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.05	Vert(CT)	-0.02	22	n/r	120		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.14	Horz(CT)	-0.01	23	n/a	n/a		
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-S							Weight: 316 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 9-17.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x6 SP No.2 *Except*	WEBS	1 Row at midpt
OTHERS	21-41: 2x4 SP No.3		17-26, 16-27, 15-28, 14-29, 13-30, 12-31, 11-32, 10-33, 9-34
	2x4 SP No.3		

REACTIONS.		TRUSS DESIGNED FOR WIND LOADS IN THE PLANE OF THE TRUSS ONLY. FOR STUDS EXPOSED TO WIND (NORMAL TO THE FACE), SEE STANDARD INDUSTRY GABLE END DETAILS AS APPLICABLE, OR CONSULT QUALIFIED BUILDING DESIGNER AS PER ANSI/TPI 1.	
(lb) -	Max Horz	1=271(LC 11)	
	Max Uplift	All uplift 100 lb or less at joint(s) 23, 1, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40 except 24=131(LC 13)	
	Max Grav	All reactions 250 lb or less at joint(s) 23, 1, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
----------------	--

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 4-1-4, Interior(1) 4-1-4 to 14-1-11, Exterior(2R) 14-1-11 to 19-2-15, Interior(1) 19-2-15 to 30-1-6, Exterior(2R) 30-1-6 to 35-2-9, Interior(1) 35-2-9 to 37-7-12 zone; end vertical right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 23, 1, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40 except (jt=lb) 24=131.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601	ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component 16023 Swingley Ridge Rd Chesterfield, MO 63017
--	--

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327366
3235275	V02	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:15 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-tKnKJw4WdLMczjx?z6gM9p49xXOQfW5e3wqQuxyvork



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.05	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.03	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 47 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 12-4-7.
(lb) - Max Horz 1=-76(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 7, 11, 12, 9, 8
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 10, 11, 12, 9, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 1-0-1 to 4-2-4, Interior(1) 4-2-4 to 6-2-4, Exterior(2R) 6-2-4 to 9-2-4, Interior(1) 9-2-4 to 11-4-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7, 11, 12, 9, 8.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327367
3235275	V03	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:16:16 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-LXLiWG48OfUTbsWBWpCbh1cIWxjCOyZnlaZzQNYvorj



Scale = 1:34.8

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.18	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.12	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.08	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 66 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 16-3-11.
(lb) - Max Horz 1=-113(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 9=-165(LC 12), 6=-165(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 9=352(LC 19), 6=352(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-9=-260/185, 4-6=-260/185

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 8-2-4, Exterior(2R) 8-2-4 to 11-2-4, Interior(1) 11-2-4 to 15-10-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 9=165, 6=165.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327368
3235275	V04	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,



8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:16:17 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-pjv5kc5m9ycKD05N4XjqEE9TVL2f7P6xXEJWypvori



4x4 =

Scale = 1:43.1



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.17	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.17	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.12	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 87 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 20-3-11.

(lb) - Max Horz 1=-143(LC 8)

Max Uplift All uplift 100 lb or less at joint(s) 1, 7 except 12=-158(LC 12), 13=-114(LC 12), 9=-158(LC 13), 8=-114(LC 13)

Max Grav All reactions 250 lb or less at joint(s) 1, 7 except 10=353(LC 22), 12=429(LC 19), 13=298(LC 19), 9=429(LC 20), 8=298(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-12=-255/183, 5-9=-254/183

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 10-2-4, Exterior(2R) 10-2-4 to 13-2-4, Interior(1) 13-2-4 to 19-10-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7 except (jt=lb) 12=158, 13=114, 9=158, 8=114.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327369
3235275	V05	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,



8.530 s Dec 6 2021 MITek Industries, Inc. Thu Jul 21 15:16:19 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-I51r9I7Ihas1SKEmCylJfEpC8j1blZE_Yod1iyvorg



4x4 =

Scale = 1:51.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.16	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.18	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.19	Horz(CT)	0.00	7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 110 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 24-3-11.

(lb) - Max Horz 1=-172(LC 8)

Max Uplift All uplift 100 lb or less at joint(s) 1 except 12=-151(LC 12), 13=-150(LC 12), 9=-150(LC 13), 8=-150(LC 13)

Max Grav All reactions 250 lb or less at joint(s) 1, 7 except 10=375(LC 22), 12=408(LC 19), 13=392(LC 19), 9=408(LC 20), 8=392(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 12-2-4, Exterior(2R) 12-2-4 to 15-2-4, Interior(1) 15-2-4 to 23-10-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 12=151, 13=150, 9=150, 8=150.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MITek Inc. DBA MITek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327370
3235275	V06	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:20 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-DIbDMd7fSt_u4UylyfGXrtn_pY3RkklNDCXAZ8yvorf



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.17	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.17	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.20	Horz(CT)	0.01	11	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S					Weight: 136 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 6-15

REACTIONS.

All bearings 28-3-11.
(lb) - Max Horz 1=201(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 1, 11 except 17=-152(LC 12), 18=-143(LC 12), 19=-119(LC 12), 14=-152(LC 13), 13=-143(LC 13), 12=-119(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 11 except 15=379(LC 22), 17=448(LC 19), 18=407(LC 19), 19=305(LC 19), 14=448(LC 20), 13=407(LC 20), 12=305(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 14-2-4, Exterior(2R) 14-2-4 to 17-2-4, Interior(1) 17-2-4 to 27-10-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 11 except (jt=lb) 17=152, 18=143, 19=119, 14=152, 13=143, 12=119.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327371
3235275	V07	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,


8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:21 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-hU9bZz8HDB6lHeO9JNnmO4K9dyPd3AZWSrHk5ayvove



4x4 =

Scale = 1:64.7



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.16	in (loc)	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.17	Vert(LL) n/a		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.29	Vert(CT) n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.01		
	Code FBC2020/TPI2014			Weight: 163 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 6-16

REACTIONS.

All bearings 32-3-11.
(lb) - Max Horz 1=-231(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 11 except 17=-153(LC 12), 19=-136(LC 12), 20=-153(LC 12), 15=-153(LC 13), 13=-136(LC 13), 12=-153(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 11 except 16=393(LC 22), 17=453(LC 19), 19=388(LC 19), 20=397(LC 19), 15=453(LC 20), 13=388(LC 20), 12=397(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-8-9, Interior(1) 3-8-9 to 16-2-4, Exterior(2R) 16-2-4 to 19-5-0, Interior(1) 19-5-0 to 31-10-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 11 except (jt=lb) 17=153, 19=136, 20=153, 15=153, 13=136, 12=153.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	IC CONST. - HAMRICK RES.	T28327372
3235275	V08	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,


8.530 s Dec 6 2021 MiTek Industries, Inc. Thu Jul 21 15:16:23 2022 Page 1

ID:e1QvOH7s?_4_S?OvDtno3RzFGI6-etGM_fAXIoMTxxYXRqETVPV8m58X6lpv9mrATyvorc



5x8 =

Scale = 1:73.7



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.16	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 7.0	Plate Grip DOL 1.25	BC 0.17	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.18	Horz(CT)	0.01	13	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 192 lb	FT = 20%
	Code FBC2020/TPI2014							

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 7-19, 6-20, 8-18

REACTIONS.

All bearings 36-3-11.

(lb) - Max Horz 1=-260(LC 8)

Max Uplift All uplift 100 lb or less at joint(s) 1, 13 except 20=-152(LC 12), 22=-138(LC 12), 23=-146(LC 12), 24=-118(LC 12), 18=-152(LC 13), 16=-138(LC 13), 15=-146(LC 13), 14=-118(LC 13)

Max Grav All reactions 250 lb or less at joint(s) 1, 13 except 19=411(LC 22), 20=447(LC 19), 22=426(LC 19), 23=413(LC 19), 24=303(LC 19), 18=446(LC 20), 16=427(LC 20), 15=413(LC 20), 14=303(LC 20)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-282/210

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCCL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 4-1-6, Interior(1) 4-1-6 to 18-2-4, Exterior(2R) 18-2-4 to 21-9-13, Interior(1) 21-9-13 to 35-10-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 13 except (jt=lb) 20=152, 22=138, 23=146, 24=118, 18=152, 16=138, 15=146, 14=118.

This item has been electronically signed and sealed by Lee, Julius, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Julius Lee PE No.34869
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:

July 22,2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless X, Y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{3}{16}$ " from outside edge of truss.

— This symbol indicates the required direction of slots in connector plates.


*** Plate location details available in MiTek 2012 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.