


-CONCRETE SLAB

- 16" W X 12" D THICKENED SLAB FOOTING w/ (2) #5 CONTINUOUS

F3 INTERIOR BEARING STEP FOOTING
S-2 SCALE: 1/2" = 1'-0"



S-2 SCALE: 1/2" = 1'-0"


footing and toward the t side of the v vertically or	ssumes 40 ksi for bent 24" into the ension side of the vall). If the wall is a horizontal bon	e reinforce ne CMU w s over 8' h nd beam w	ed slab at th rall (away fr nigh, add Do rith 1#5 con	e top. The voom the soil urowall lado	ertical stee pressure, w ler reinforce nid height.	l is to be pla within 2" of the ment at 16 For higher p	aced ne exterio "OC
STEMWALL HEIGHT (FEET)	UNBALANCED BACKFILL HEIGHT	sed with reinforcement as shown VERTICAL REINFORCEMENT FOR 8" CMU STEMWALL (INCHES O.C.)		VERTICAL REINFORCEMENT FOR 12" CMU STEMWALL (INCHES O.C.)			
		#5	#7	#8	#5	#7	#8
3.3	3.0	96	96	96	96	96	96
4.0	3.7	96	96	96	96	96	96
4.7	4.3	88	96	96	96	96	96
5.3	5.0	56	96	96	96	96	96
6.0	5.7	40	80	96	80	96	96
6.7	6.3	32	56	80	56	96	96
7.3	7.0	24	40	56	40	80	96
8.0	7.7	16	32	48	32	64	80
8.7	8.3	8	24	32	24	48	64


9.3 9.0 8 16 24 16 40 48

TALL STEM WALL TABLE:


MASO		MATERIALS FOR THIS PROJECT JIREMENTS OF "SPECIFICATION"
THE C PROC BETW ANY E	ONTRACTOR AND MASON EEDING, NOTIFY THE ENG EEN ACI 530.1-02 AND THI	(ACI 530.1/ASCE 6/TMS 602). N MUST IMMEDIATELY, BEFORE GINEER OF ANY CONFLICTS ESE DESIGN DRAWINGS. -02 MUST BE APPROVED BY
	ACI530.1-02 Section	Specific Requirements
1.4A	Compressive strength	8" block bearing walls F'm = 1500 psi
2.1	Mortar	ASTM C 270, Type N, UNO
2.2	Grout	ASTM C 476, admixtures require approval
2.3	CMU standard	ASTM C 90-02, Normal weight, Hollow, medium surface finish, 8"x8"x16" running bond and 12"x12" or 16"x16" column block
2.3	Clay brick standard	ASTM C 216-02, Grade SW, Type FBS, 5.5"x2.75"x11.5"
2.4	Reinforcing bars, #3 - #11	ASTM 615, Grade 40, Fy = 40 ksi, Lap splices min 40 bar dia. (25" for #5)
2.4F	Coating for corrosion protection	Anchors, sheet metal ties completely embedded in mortar or grout, ASTM A525, Class G60, 0.60 oz/ft2 or 304SS
2.4F	Coating for corrosion protection	Joint reinforcement in walls exposed to moisture or wire ties, anchors, sheet metal ties not completely embedded in mortar or grout, ASTM A153, Class B2, 1.50 oz/ft2 or 304SS
3.3.E.2	Pipes, conduits, and accessories	Any not shown on the project drawings require engineering approval.
3.3.E.7	Movement joints	Contractor assumes responsibility for type and location of movement joints if not detailed on project drawings.


MASONRY NOTE:





ALTERNATE IF TRUSSES ARE PERPENDICULAR TO SHEARWALL





STRUCTURAL PLAN SCALE: 1/4" = 1'-0"

STRUCTURAL PLAN NOTES

ALL LOAD BEARING FRAME WALL & PORCH HEADERS SHALL BE A MINIMUM OF (2) 2X6 SP #2 (U.N.O.)

SN-2 ALL LOAD BEARING FRAME WALL HEADERS SHALL HAVE (1) JACK STUD & (1) KING STUD

EACH SIDE (U.N.O.)


ALL HEADERS w/ UPLIFT TO BE STRAPPED DOWN @ EACH SIDE WITH (1) LSTA24, 14-10d @ TOP & BOTTOM OF WALL SN-3 WRAP UNDER BOTTOM PLATE & OVER TOP PLATE 1/2" X 10" ANCHOR BOLT w/ 3" X 3" X 1/4" WASHER MUST BE LOCATED WITHIN 6" OF KING STUD @ ALL DOOR LOCATIONS (U.N.O.)

SN-4 USE ONE JACK STUD GIRDER SUPPORT PER 2500 LB LOAD

DIMENSIONS ON STRUCTURAL SHEETS SN-5 ARE NOT EXACT. REFER TO ARCHITECTURAL FLOOR PLAN FOR ACTUAL DIMENSIONS

PERMANENT TRUSS BRACING IS TO BE INSTALLED AT LOCATIONS AS SHOWN ON THE SEALED TRUSS DRAWINGS. LATERAL BRACING IS TO BE RESTRAINED PER BCSI1-03, BCSI-B1, BCSI-B2, & BCSI-B3, BCSI-B1, BCSI-B2, & BCSI-B3 ARE FURNISHED BY THE TRUSS SUPPLIER, WITH THE SEALED TRUSS PACKAGE

HEADER LEGEND



ACTUAL VS REQUIRED SHEARWALL

	TRANSVERSE	LONGITUDUNAL
ACTUAL	17078 LBF	20793 LBF
REQUIRED	15323 LBF	9769 LBF

DIMENSIONS: Stated dimensions supercede scaled dimensions. Refer all questions to Mark Disosway, P.E. for resolution. Do not proceed without clarification.

COPYRIGHTS AND PROPERTY RIGHTS: Mark Disosway, P.E. hereby expressly reserves its common law copyrights and property right in these instruments of service. This document is not to be reproduced, altered or copied in any form or manner without first the express written permission and consent of Mark Disosway.

CERTIFICATION: I hereby certify that I have examined this plan, and that the applicable portions of the plan, relating to wind engineering comply with the 6th Edition Florida Building Code Residential (2017) to the best of my knowledge.

LIMITATION: This design is valid for one building, at specified location.

MARK DISOSWAY P.E. 53915

THIS PDF HAS DIGITAL SIGNATURE AND ELECTRONIC SEAL. PRINTED **COPIES ARE NOT CONSIDERED** SIGNED OR SEALED. YOU MUST



Monday, August 3, 2020

Mark Disosway P.E. 163 SW Midtown Place Suite 103 Lake City, Florida 32025 386.754.5419 disoswaydesign@gmail.com

> JOB NUMBER: 200831 **S-3**

> > OF 3 SHEETS

CONNECTIONS, WALL, & HEADER DESIGN IS BASED ON REACTIONS & UPLIFTS FROM TRUSS ENGINEERING FURNISHED BY BUILDER. BUILDERS FIRST SOURCE JOB #2365612