

SOFTPIAN
APCHECTUPAL DESIGN CONTRACT

EXTERIOR ELEVATIONS
SCALE: 1/4" = 1'-0"

POTTS JOAN S. S. A CUSTOM RESIDENCE

STUARY

PROJECT ADDRESS: 176 N


©NILIAM MYERS
DESIGN, INC.
1.0. BOX 1513
LAE CITY, FL 32056
(386) 758-8406
wli@willmyers.net



JCB NUMBER 090604

SHEET NUMBER A.1





SCALE: 1/4" = 1'-0"

RIGHT ELEVATION
SCALE: 1"= 1'-0"

SOFTPIXN

USTOM RESIDENCE FOR: $TUJRT \ll JOJN POTTS$ Wect address: 176 nW cambridge HILL Way, Lake City, Florida 32055

©VILLIAM MYER.5


DE.SIGN. INC.

P.O. BOX 1513

LAKE CITY, FL 32056

(386) 758-8406

will@willmyers.net




JOB NUMBER 090604

SHEET NUMBER

A.2

OF 4 SHEETS

Will C-Arg



SCTPIXN

FLOOR PLAN SCALE: 1/4" = 1'-0"

JOANPC S S A CUSTOM RESIDENCE F STUART

©NILIAM MYERS

PLSIGN INC.

FO. BOX 1513

LAK: CITY, FL 32056 (38) 758-8406 wi@willmyers.net



JO3 NUMBER 090604

SHEET NUMBER

A.3

2645 S.F. 150 S.F.

482 S.F.


3,277 S.F.



ELECTRICAL SCALE:

B ART STU


OWILLIAM MYERS **DESIGN, INC.** P.(. BOX 1513 LAKECITY, FL 32056 (386) 758-8406 will@willmyers.net



JOBNUMBER 090604

SHEET NUMBER

OF4 SHEETS



ELECTRICAL PLAN

ELECTRICAL LEGEND (PRE-WIRE FOR LIGHT KIT) DOUBLE SECURITY RECESSED CAN LIGHT BATH EXHAUST FAN LIGHT FIXTURE DUPLEX OUTLET 220v OUTLET GFI DUPLEX OUTLET TELEVISION JACK TELEPHONE JACK SMOKE DETECTOR (see note below) WALL SWITCH 3 WAY WALL SWITCH WATER PROOF GFI OUTLET

NOTE: ALL BEDROOM RECEPTACLES SHALL BE AFCI (ARC FAULT CIRCUIT INTERRUPT)

ALL SMOKE DETECTORS SHALL HAVE BATTERY BACKUP POWER AND ALL WIRED TOGETHER SO IF ANY ONE UNIT IS ACTUATED THEY ALL ACTIVATE.

2 OR 4 TUB FLUORESCENT FIXTURE

THE ELECTRICAL SERVICE OVERCURRENT PROTECTION DEVICE SHALL BE INSTALLED ON THE EXTERIOR OF STRUCTURES TO SERVE AS A DISCONNECT MEANS. CONDUCTORS USED FROM THE EXTERIOR DISCONNECTING MEANS TO A PANEL OR SUB PANEL SHALL HAVE FOUR-WIRE CONDUCTORS, OF WHICH ONE CONDUCTOR SHALL BE USED AS AN EQUIPMENT GROUND.

THE CONTRACTOR SHALL COORDINATE THE TRUSS TO TRUSS ANCHOR REQUIREMENTS WITH THE TRUSS ENGINEERING SHOP DRAWINGS, SOME OF THE TRUSS TO TRUSS CONNECTIONS WILL REQUIRE ANCHOR STRAPS IN ADDITION TO TYPICAL NAILING. ANCHOR DEVICES SHALL BE REQUIRED FOR ALL JOINTS WITH AN UPLIFT OR GRAVITY LOAD OF 100 LBS OR GREATER.

TRUSSES BEARING ON INTERIOR PARTITIONS WHERE UPLIFT LOADS ARE PRESENT SHALL REQUIRE ANCHORS OF EQUAL OR GREATER LOAD CAPACITY THAN THAT INDICATED BY THE TRUSS SHOP DRAWINGS. THE UPLIFT ANCHOR SYSTEM SHALL BE CONTINUOUS TO THE FOUNDATION.

SHOP DWG COORDINATION: THE TRUSS ANCHOR STRAPS AS INDICATED IN THE CONSTRUCTION DOCUMENTS ARE SUGGESTED STRAPS AND THAT THE TRUSS ENGINEERED SHOP DRAWING LOADS TAKE PRECEDENCE OVER THAT INDICATED IN THE CONSTRUCTION DOCUMENTS. THE UPLIFT LOADS INDICATED FOR EACH TRUSS IN THE ENGINEERED TRUSS SHOP DRAWINGS MAY BE MATCHED TO STANDARD PRODUCT UPLIFT RATINGS FOR COMPARABLE UPLIFT CONNECTORS, AND THAT THE PRODUCTS THAT PROVIDE EQUAL OR GREATER UPLIFT RESISTANCE FOR THE LISTED LOADS MAY BE USED IN LIEU OF THOSE INDICATED IN THE CONSTRUCTION DOCUMENTS OR AS APPROVED BY THE BUILDING OFFICIAL.

Roof Framing PLAN

SCALE: 1/4" = 1'-0"

ANCHOR GIRDER TRUSS(ES) TO HEADER WITH 2 "SIMPSON" LGT(2, 3 OR 4), ANCHOR HEADER TO KING STUDS W/ 2 "SIMPSON" ST22 EA. END - TYP., T.O.

REFER TO THE WINDOW/DOOR HEADER SCHEDULE ON SHEET SD.4 FOR ALL MINIMUM SIZE HEADERS AND ALTERNATES MINIMUM SIZE ALLOWABLE IS 2-2×10.

GENERAL TRUSS NOTES:

1. TRUSSES SHALL BE DESIGNED | BY A LICENSED ENGINEER, AND IN ACCORDANCE WITH THE REQUIREMENTS OF THINE "NATIONAL FOREST PRODUCTS ASSOCIATION" MANUAL FOR "STRESS RATED L LUMBER AND IT'S CONNECTIONS", LATEST Ed., ALONG W/ THE "TRUSS PLATE INSTITUTE"E" SUGGESTED GUIDELINES FOR TEMPORARY AND PERMANENT BRACING, AND HALANDLING OF TRUSSES. TRUSS SHOP DRAWINGS SHALL INCLUDE TRUSS DESIGN, PLACE; EMENT PLANS, DETS, & TRUSS TO TRUSS CONNECTIONS.

ROOF PLAN NOTES

- SEE EXTERIOR ELEVATIONS FOR ROOF PITCH
- ALL OVERHANG 18" UNLESS OTHERWISE NOTED
- PROVIDE ATTIC YENTILATION IN AC-
- SEE EXTERIOR ELEVATIONS AND FLOOR PLANS TO VERIFY PLATE AND HEEL HEIGHTS

CORDANCE WITH SCHEDULE ON SD.3

- MOVE ALL VENTS AND OTHER
- ROOF PENETRATIONS TO REAR

SHEATH ROOF W/ 1/2" CDX PLYWOOD PLACED

W/ LONG DIMENSION PERPENDICULAR TO THE ROOF TRUSSES, SECURE TO FRAMING W/ 8d NAILS - AS PER DETAIL ON SHEET SD.4

NOTE

THE DESIGN WIND SPEED FOR THIS PROJECT IS 110 MPH PER 2007 FBC 1609 AND LOCAL JURISDICTION REQUIREMENTS

ALL PENETRATIONS OF THE TOP PLATE OF ALL LOAD BEARING WALLS SHALL BE SEALED WITH FIRE RETARDANT CAULKING, INCLUDING WIRING, PLUMBING OR OTHER SUCH PENETRATIONS. WALLS OVER 8'-0" TALL SHALL HAVE CONTINUOUS BLOCKING TO LIMIT CAVITY HEIGHT TO 8'-O". PENETRATIONS THROUGH SUCH BLOCKING SHALL BE TREATED IN THE SAME MANNER AS TOP PLATES, NOTED ABOVE


WOOD STRUCTURAL NOTES

- I. TEMPORARY BRACING OF THE STRUCTURE DURING ERECTION, REQUIRED FOR SAFE AND STABLE CONSTRUCTION, SHALL BE THE SOLE RESPON-SIBILITY OF THE CONTRACTOR SO ENGAGED, TEMPORARY & PERMANENT BRACING OF ROOF TRUSSES SHALL BE AS PER THE STANDARD GUIDE-LINES OF THE "TRUSS PLATE INSTITUTE".
- 2. ALL TRUSSES SHALL BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER & SHALL BE SIGNED AND SEALED BY SAME, TRUSS DESIGN SHALL INCLUDE PLACEMENT PLANS, TRUSS DETAILS, TRUSS TO TRUSS CONNECTIONS & THE STANDARD SPECIFICATIONS & RECOMMENDATIONS OF INSTALLATION OF THE "TRUSS PLATE INSTITUTE",
- 3. WOOD STUDS IN EXTERIOR WALLS & INTERIOR BEARING WALLS SHALL BE NOT LESS THAN Nr.2 HEM-FIR OR BETTER.
- 4. CONNECTORS FOR WOOD FRAMING SHALL BE GALVANIZED METAL OR BLACK METAL AS MANUFACTURED OR AS CALLED FOR IN THE PLANS AND BE OF A DESIGN SUITABLE FOR THE LOADS AND USE INTENDED. REFER TO THE JOINT REINFORCEMENT SCHEDULE FOR PRINCIPLE CON-NECTIONS.

AREA OF ATTIC	REQ'D L.F. OF YENT	NET FREE AREA OF INTAKE
1600 SF	20 LF	410 SQ.IN.
1900 SF	24 LF	490 SQ.IN.
2200 SF	28 LF	570 SQ.IN.
2500 SF	32 LF	650 SQ.IN.
2800 SF	36 LF	730 SQ.IN.
3100 SF	40 LF	820 SQ.IN.
3600 SF	44 LF	900 SQ.IN.


SOTTPIXN

AND



MIAMI/DADE PRODUCT APPROVAL REPORT: *98-0713,05

Ridge Vent DETAIL



VALLEY FLASHING

	TALS for FLASI	HING/ROOF	NG
MATERIAL	MINIMUM THICKNESS (in)	GAGE	WEIGHT
COPPER			16
ALUMINUM	0.024		
STAINLESS STEEL		28	
GALVANIZED STEEL	er10.0	26 (ZINC COATED G90)	
ZINC ALLOY LEAD PAINTED TERNE	0.027		40 20




SHEET NUMBER

JOE NUMBER

090604

OLAS PAUL SLER ITECT

OF6 SHEETS



EAVE DRIP


		TALS FOR FLAS	FLASHING/ROOFING EMENTS		
1	MATERIAL	MINIMUM THICKNESS (in)	GAGE	WEIGHT	
cc	PPER			16	
AL	uminum	0.024			
ST	AINLESS STEEL		28		
G/	LYANIZED STEEL	er10.0	26 (ZINC COATED G90)		
LE	IC ALLOY AD JINTED TERNE	0.027		40 20	


Roofing/Flashing DETS.

SCALE: NONE




NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS




























H2.5










SCALE: NONE







PENETRATIONS

SOFFIT/DROPFD CLG.

FIREBLOCKING NOTES:

FIREBLOCKING SHALL BE INSTALLED IN WOOD FRAME CONSTRUCTIONN THE FOLLOWING LOCATIONS:

- I, IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS INCLUDING FURRED SPACES AT CEILING AND FLOOR LEVELS.
- 2. AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL ANIHORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, DROP CEILINGS, COVE CEINGS, ETC.
- 3. AT OPENINGS AROUND VENTS, PIPES, DUCTS, CHIMNEYS AND FIRPLACES AT CEILING AND FLOOR LEVELS WITH "PYROPANEL MULTIFLEX SEALAT"
- 4. AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL STUIWALL OR PARTITION SPACES AND CONCEALED SPACES CREATED BY AN 3SEMBLY OF FLOOR JOISTS, FIREBLOCKING SHALL BE PROVIDED FOR THEULL DEPTH OF THE JOISTS AT THE ENDS AND OVER THE SUPPORTS.

Fire Stopping DETAILS

: NONE



GENERAL NOTES:

- I. THE CONTRACTOR SHALL INDEMNIFY THE OWNER AGAINST ALI_{LL} CLAIMS, WHETHER FROM PERSONAL INJURY OR PROPERTY DAMAGE, ARISING FROM EVENTS ASSOCIATED WITH THE WORK, PERFORMED UNDER THE CONTRACT FOR THIS PROJECT.
- 2. THE CONTRACTOR AND/OR SUB-CONTRACTORS SHALL WAR-.
 RANT ALL WORK FOR A PERIOD OF ONE YEAR FOLLOWING TITHE
 DATE OF FINAL COMPLETION AND ACCEPTANCE BY THE OWNEJER.
 DEFECTS IN MATERIALS, EQUIPMENT, COMPONENTS AND WORKKMANSHIP SHALL BE CORRECTED AT NO FURTHER COST TO THHE
 OWNER DURING THE ONE YEAR WARRANTY PERIOD.
- 3. AT THE OWNER'S OPTION, A WARRANTY INSPECTION SHALL BE PERFORMED DURING THE ELEVENTH MONTH FOLLOWING THE COMMENCEMENT OF THE WARRANTY PERIOD, FOR THE PURE-POSE OF DETERMINING ANY WARRANTY WORK THAT MAY BE REQUIRED. THE CONTRACTOR SHALL BE PRESENT DURING THINIS INSPECTION IF REQUESTED BY THE OWNER.
- 4. THE CONTRACTOR SHALL PAY FOR ALL PERMITS, LICENSES, TESTS AND THE LIKE THAT MAY BE REQUIRED BY THE VARIOUS AUTHORITIES HAVING JURISDICTION OVER THIS PROJECT BE THEY CITY, COUNTY, STATE OR FEDERAL.
- 5. THE OWNER SHALL FILE A "NOTICE OF COMMENCEMENT" PRIOR TO THE BEGINNING THE THE PROJECT AND THE CONTRACTOR((g(S)) SHALL FILE "NOTICE TO OWNER" AND PROVIDE "RELEASE OF LIEN" FOR ALL PAYMENT REQUESTS PRIOR TO DISBURSEMENT TO OF ANY FUNDS.
- 6. ANY AND ALL DISPUTES ARISING FROM EVENTS ASSOCIATED WITH THE CONSTRUCTION OF THIS PROJECT BETWEEN THE OWNER, CONTRACTOR(S) AND SUPPLIERS SHALL BE RESOLVELED THROUGH BINDING ARBITRATION.
- ALL WORK SHALL BE IN ACCORDANCE W/ APPLICABLE CODE'S
 AND LOCAL REGULATIONS, INCLUDING APPLICABLE ENERGY
 CODES. ALL COMPONENTS OF THE BUILDING SHALL MEET WITH A
 THE MINIMUM ENERGY REQUIREMENTS OF THE BUILDING CODE.
 ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITEC'S
 IN WRITING PRIOR TO THE COMMENCEMENT OF THE WORK.
- 8. ALL INSULATION SHALL BE LEFT EXPOSED AND ALL LABLES LEFT INTACT ON THE WINDOWS AND DOORS UNTIL INSPECTED BY THE BUILDING OFFICIAL.
- 9. ALL WOOD IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE TREATED.
- 10. INTERIOR BEARING WALLS SHALL BE CONSTRUCTED IN COM-PLIANCE WITH "UL Design U333", BATT INSULATION SHALL BE INCLUDED WHERE UNCONDITIONED AREA IS BEING SEPARATED DEPORTED OF TROM HEATED / COOLED AREA.
- II. INTERIOR STUD WALLS SEPARATING LIVING AREA FROM GARAGE AREAS SHALL BE CONSTRUCTED IN COMPLIANCE WITH "UL Design U333", INCLUDING R-II BATT INSULATION,
- 12. CEILINGS OVER ATTACHED GARAGES OR GARAGES W/ LIVING;
 AREA ABOVE SHALL BE 5/8" FIRECODE "C" GWB ON IX3 WOODD
 FURRING AT 16" O.C., ATTACHED W/ I 1/4" BUGLEHEAD SCREWS;

 6 6" O.C. ALONG EACH POINT OF BEARING.

PROJECT INFORMATION / NOTES:

DESIGN VALUES/LOADS & CODES

WIND DESIGN SPEED: 110 MPH, UNLESS NOTED OTHERWISE

SOIL DESIGN STATEMENT:

FOOTING DESIGN IS BASED UPON 1000PSF SOIL BEARING PRESSURIRE PROVIDED BY CLEAN SAND, GRAVEL OR STONE. OTHER SOIL CONDITICIONS IS: CLAY, HIGH LEVEL OF ORGANICS OR OTHER UNDESIRABLE SOILS SHALL REQUIRE FOUNDATION MODIFACATIONS.

LIVE LOADS: 1st FLOOR: 40PSF, 2nd FLOOR: 40PSF, ROOF: AS DETITERMINED BY SHAPE FACTORS APPLIED TO THE WIND FORCE GENERATED BYY THE DESIGN WIND SPEED.

BUILDING CODE: 2001 FLORIDA BUILDING CODE

ELECTRICAL CODE: NATIONAL ELECTRICAL CODE - LATEST LIFE SAFETY: NFPA-IOI - LATEST

CONSTRUCTION DOCUMENTS

THE CUSTOMER IS RESPONSIBLE FOR DELIVERING THE REQUIRED SETS OF CONSTRUCTION DOCUMENTS TO THE PERMIT ISSUING AUTHORITIES, FOOR THE ISSUANCE OF CONSTRUCTION PERMITS. THE CONTRACTOR SHALL REVIEW THE CONSTRUCTION DOCUMENTS AND VERIFY ALL DIMENSIONS. ANNY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF ANY WORK OR FABRACATION OF ANY MATERIALS.

DO NOT SCALE OFF THESE PLANS

AMPLE DIMENSIONS ARE SHOWN ON THE PLANS TO LOCATE ALL ITETEMS. SIMPLE ARITHMETIC MAY BE USED TO DETERMINE THE LOCATIONS O'DE THOSE ITEMS NOT DIMENSIONED.

CHANGES TO FINAL PLAN SETS

PLEASE DO NOT MAKE ANY STRUCTURAL CHANGES TO THESE PLANS WITHOUT CONSULTING WITH THE ARCHITECT. THE OWNER SHALL ASSUME ANY , AND ALL LIABILITY FOR STRUCTURAL DAMAGE RESULTING FROM CHANGES MAADE TO THE PLANS OR BY SUBSTITUTION OF MATERIALS DIFFERENT FROM SPECIFICATION ON THE PLANS.

INORGANIC ARSENICAL PRESSURE TREATED WOGOD SOME FRAMING MATERIALS SPECIFIED FOR THE CONSTRUCTION OF YYOUR PROJECT SUCH AS SILLS OR EXTERIOR FRAMING ARE PRESSURE TRREATED. EACH PIECE IS CLEARLY MARKED FOR EASY IDENTIFICATION AND ISIS USUALLY GREENISH IN COLOR.

THIS WOOD HAS BEEN PRESERVED BY PRESSURE-TREATMENT WITH AN EPAREGISTERED PESTICIDE CONTAINING INORGANIC ARSENIC TO PROTEECT IT FROM INSECT ATTACK AND DECAY. EXPOSURE TO TREATED WOOD I MAY PRESENT CERTAIN HAZARDS, THEREFORE, PRECAUTIONS SHOULD BEE TAKEN BOTH WHEN HANDLING THE TREATED WOOD AND IN DETERMINING WHELERE TO USE OR DISPOSE OF THE TREATED WOOD.

FOR FURTHER INFORMATION ON THE USE OF AND DISPOSAL OF INORRGANIC ARSENIC PRESSURE TREATED WOOD, PLEASE REFER TO THE EPA MAATERIAL SAFETY SHEET DEALING WITH THIS PRODUCT.

HARDWARE RETIGHTENING REQUIREMENTS

ALL LAG SCREW AND BOLT CONNECTIONS ON COMPOUND BEAMS, POOSTS, GIRDERS, TIMBER TRUSSES AND OTHER STRUCTURAL MEMBERS TO BBE INSPECTED PERIODICALLY AND RETIGHTENED AS NECESSARY.

FLORIDA BUILDING CODE

Compliance Summary

TYPE OF CONSTRUCTION

Roof: Hip Construction, Wood Trusses © 24" O.C. Walls: 2x4 Wood Studs © 16" O.C.

Floor: 4" Thk. Concrete Slab W/ Fibermesh Concrete Additive Foundation: Continuous Footer/Stem Wall

ROOF DECKING

Material: 1/2" CD Plywood or 7/16" O.S.B.

Sheet Size:48"x96" Sheets Perpendicular to Roof Framing Fasteners: 8d Common Nails per schedule on sheet 5D.2

SHEARWALLS

Material: 7/16" O.S.B. "WindSTORM": 48" \times 97", 109", 121" OR 145" Sheet Size:48"x97" (109", 121" OR 145") Sheets Placed Vertical Fasteners: 8d Common Nails @ 4" O.C. Edges & 8" O.C. Interior Dragstrut: Double Top Plate (S,Y,P.) W/16d Nails @ 12" O.C. Wall Studs: 2x4 SPF Studs @ 16" O.C.

HURRICANE UPLIFT CONNECTORS

Truss Anchors:Simpson H2.5a @ Ea. Truss End (Typ. U.O.N.)

Wall Tension: Wall Sheathing Nailing is Adequate - 8d @ 4" O.C. Top & Bot. Anchor Bolts: 1/2" A30T THRU-BOLTS @ 64" O.C. - 1st Bolt 8" from corner Corner Hold-down Device(1) Anchor THRU-BOLT

Porch Column Base ConnectoSimpson ABU44/ABU66 @ each column

Porch Column to Beam Connectobimpson EPC44/PC44 @ each column

FOOTINGS AND FOUNDATIONS

Footing: 20"x12" Cont. W/2-*5 Bars Cont. \$ 1-*3 Transverse \$ 24" O.C. Stemmall: 8" C.M.U. W/1-*5 Vertical Dowel \$ 48" O.C.

ALL WIND LOADS ARE IN ACCORDAN FLORIDA BUILDING CODE, 20	CE WITH SECTION 1609, POT EDITION.
BASIC WIND SPEED:	110 MPH
WIND IMPORTANCE FACTOR (I):	l = 1.00
BUILDING CATAGORY:	CATAGORY II
WIND EXPOSURE:	"B"
INTERNAL PRESSURE COEFFICIENT:	+/- 0.18
MWFRS PER TABLE 1609.2A (FBC 2001) DESIGN WIND PRESSURES:	ROOF: - 23.1 PSF WALLS: + 26.6 PSF EAVES: - 32.3 PSF
COMPONENTS & CLADING PER TABLES 1609.2B & 1609.2C (FBC 2007) DESIGN WIND PRESSURES:	OP'NGS: + 21.8 / - 29.1 PSF EAVES: - 68.3 PSF ROOF: + 19.9 / - 25.5 PSF

TERMITE PROTECTION NOTES:

SOIL CHEMICAL BARRIER METHOD:

- 1. A PERMANENT SIGN WHICH IDENTIFIES THE TERMITE TREATMENT PROVIDER AND NEED FOR REINSPECTION AND TREATMENT CONTRACT RENEWAL SHALL BE PROVIDED, THE SIGN SHALL BE POSTED NEAR THE WATER HEATER OR ELECTRIC PANEL, FBC 104.2.6
- 2. CONDENSATE AND ROOF DOWNSPOUTS SHALL DISCHARGE AT LEAST 1'-O"
 AWAY FROM BUILDING SIDE WALLS. FBC 1503.4.4
- 3. IRRIGATION/SPRINKLER SYSTEMS INCLUDING ALL RISERS AND SPRAY HEADS SHALL NOT BE INSTALLED WITHIN 1'-O" FROM BUILDING SIDE WALLS, FBC 1503.4.4
- 4. TO PROVIDE FOR INSPECTION FOR TERMITE INFESTATION, BETWEEN WALL COVERINGS AND FINAL EARTH GRADE SHALL NOT BE LESS THAN 6".

 EXCEPTION: PAINT AND DECORATIVE CEMENTIOUS FINISH LESS THAN 5/8"
 THICK ADHERED DIRECTLY TO THE FOUNDATION WALL. FBC 1403,1.6
- 5. INITIAL TREATMENT SHALL BE DONE AFTER ALL EXCAVATION AND BACKFILL IS COMPLETE, FBC 1816.1.1
- 6. SOIL DISTURBED AFTER THE INITIAL TREATMENT SHALL BE RETREATED INCLUDING SPACES BOXED OR FORMED. FBC 1816.1.2
- 7. BOXED AREAS IN CONCRETE FLOOR FOR SUBSEQUENT INSTALLATION OF TRAPS, ETC., SHALL BE MADE WITH PERMANENT METAL OR PLASTIC FORMS. PERMANENT FORMS MUST BE OF A SIZE AND DEPTH THAT WILL ELIMINATE THE DISTURBANCE OF SOIL AFTER THE INITIAL TREATMENT, FBC 1816.1.3
- 8. MINIMUM 6 MIL VAPOR RETARDER MUST BE INSTALLED TO PROTECT AGAINST RAINFALL DILUTION, IF RAINFALL OCCURS BEFORE VAPOR RETARDER PLACEMENT, RETREATMENT IS REQUIRED. FBC 1816,1,4
- 9. CONCRETE OVERPOUR AND MORTAR ALONG THE FOUNDATION PERIMETER MUST BE REMOVED BEFORE EXTERIOR SOIL TREATMENT. FBC 1816.1.5

 10. SOIL TREATMENT MUST BE APPLIED UNDER ALL EXTERIOR CONCRETE OR GRADE WITHIN 1'-0" OF THE STRUCTURE SIDEWALLS. FBC 1816.1.6
- II. AN EXTERIOR VERTICAL CHEMICAL BARRIER MUST BE INSTALLED AFTER CONSTRUCTION IS COMPLETE INCLUDING LANDSCAPING AND IRRIGATION. ANY SOIL DISTURBED AFTER THE VERTICAL BARRIER IS APPLIED, SHALL BE RETREATED. FBC 1816.1.6
- 12. ALL BUILDINGS ARE REQUIRED TO HAVE PER-CONSTRUCTION TREATMENT. FBC 1816.1.7
- 13. A CERTIFICATE OF COMPLIANCE MUST BE ISSUED TO THE BUILDING DEPARTMENT BY * LICENSED PEST CONTROL COMPANY BEFORE A CERTIFICATE OF OCCUPANCY WILL BE ISSUED. THE CERTIFICATE OF COMPLIANCE SHALL STATE: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. THE TREATMENT IS IN ACCORDANCE WITH THE RULES AND LAWS OF THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES". FBC 1816.1.7
- 14. AFTER ALL WORK IS COMPLETED, LOOSE WOOD AND FILL MUST BE REMOVED FROM BELOW AND WITHIN 1'-O" OF THE BUILDING. THIS INCLUDES ALL GRADE STAKES, TUB TRAP BOXES, FORMS, SHORING OR OTHER CELLULOSE CONTAINING MATERIAL. FBC 2303.1.3

15. NO WOOD, VEGETATION, STUMPS, CARDBOARD, TRASH, ETC., SHALL BE BURIED WITHIN 15'-O" OF ANY BUILDING OR PROPOSED BUILDING. FBC 2303.1.4

FRAMING ANCHOR SCHEDULE

APPLICATION	MANUF'R/MODEL	CAP.
TRUSS TO WALL: GIRDER TRUSS TO POST/HEAD! HEADER TO KING STUD(S): PLATE TO FOUNDATION: PORCH BEAM TO POST: PORCH POST TO FND.: MISC. JOINTS	SIMPSON H2.5a ERGIMPSON LGT, W/ 28 - 16d NAI SIMPSON ST22 5/8"~ THRU-BOLT SIMPSON PC44/EPC44 SIMPSON ABU44 SIMPSON A34	535# L8 785# 13 70# 3340# 1700# 2200# 3 5#/240

NOTE:

NOTE:

ALL ANCHORS SHALL BE SECURED W/ NAILS AS PRESCRIBED BY THE MANUFACTURER FOR MAXIMUM JOINT STRENGTH, UNLESS NOTED OTHERWISE, NOTE:

REFER TO THE INCLUDED STRUCTURAL DETAILS FOR ADDITIONAL ANCHORS/ JOINT REINFORCEMENT AND FASTENERS. NOTE:

ALL UNLISTED JOINTS IN THE LOAD PATH SHALL BE REINFORCED WITH SIMPSON A34 FRAMING ANCHORS, TYPICAL T.O. NOTE:

"SEMCO" PRODUCT APPROVAL:
MIAMI/DADE COUNTY REPORT *95-0818.15


"SIMPSON" PRODUCT APPROVALS:
MIAMI/DADE COUNTY REPORT *97-0107.05, *96-1126.11, *99-0623.04
SBCCI NER-443, NER-393

GENERAL NAILING SCHEDULE:

CONNECTION	COMMON NAILS	Nr. / SPACING
BRIDGING TO JOIST, TOE NAIL 2" SUBFLOOR TO JOIST,	16d	2 EA, END
BLIND & FACE NAILING BOLE PLATE TO JOIST OR BLOCKING	16d	2
FACE NAILED TOP OR SOLE PLATE TO STUD	16d	16" O.C.
END NAILED	16d	2
STUD TO SOLE PLATE, TOE NAILED	8d	3 OR 2 16d
DOUBLE STUDS, FACE NAILED	16d	24" O.C.
DOUBLE TOP PLATES, FACE NAILED FOR PLATES - LAPS & INTERSECTIONS	16d	16" O.C.
FACE NAILED X 6 SHEATHING TO EACH POINT	16d	2
OF BEARING, FACE NAILED BUILT-UP CORNER STUDS, FACE	8d	2
NAILED	16d	30" O.C.
BUILT-UP GIRDERS & BEAMS	20d	32" O.C. @ TOP & BOTTOM & STAGGERED - 2 @ EA. END & @ SPLICES
3/4" PLYWOOD SUBFLOORING	8d	6" O.C. @ EDGES
OSB SHEATHING, 7/16" THICK	8d	INTERMEDIATE 6" O.C. @ EDGES 10" O.C. @ INTERMEDIATE
'8" FIBERBOARD SHEATHING	6d	3" O.C. @ EDGES 6" O.C. @ INTERMEDIATE

- A. NAILS, BOLTS AND OTHER METAL CONNECTORS WHICH ARE USED IN LOCATIONS EXPOSED TO THE WEATHER SHALL BE GALVANIZED OR OTHERWISE CORROSION RESISTANT.
- B. IN GENERAL, NAILS SHALL PENETRATE THE SECOND MEMBER A DIS-TANCE EQUAL TO THE THICKNESS OF THE MEMBER BEING NAILED THERETO, OR GREATER.
- C. THERE SHALL BE NOT LESS THAN 2 NAILS PER CONNECTION.
- D. GLUING SHALL NOT BE CONSIDERED AN ACCEPTABLE CONNECTOR IN LIEU OF THOSE SPECIFIED HEREIN.
- E. FORMED METAL CONNECTORS, AS PER THE SCHEDULE HEREIN, SHALL HAVE THE NUMBER OF NAILS INSTALLED AS REQUIRED BY THE MANUFACTURER, OR AS DIRECTED BY THE PLANS.
- F. NAILS PROJECTING BEYOND THE LAST WOOD MEMBER SHALL BE CLINCHED, WHEREVER POSSIBLE.









A CUSTOM RESIDENCE FOR: STUJARTJMM JOJMPOTPROJECT ADDRESS: 176 NW CAMBRIDGE HILL WAY, LAKE CITY, FLORID







JOB NUMBER 090604

SHEET NUMBER


OF 6 SHEETS

NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEN [DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS
















SEE PLANS FOR ANCHOR VARIATIONS

Post/Beam DETAIL SCALE: 1" - 1'-0"



PLYWOOD FLITCH BEAM DETAIL NOT TO SCALE



MULTIPLE GANG LAM, DETALIL NOT TO SCALE


B/U Beam DETAILS

ROOF SHEATHING FASTENINGS

SCALE: NONE


NAILING ZONE	SHEATHING TYPE	FASTENER	SPACIFING	
1.		8d COMMON OR	6 In. o.c. s. EDGE 12 In. o.c. s. FIELD	
2	7/16 " O.S.B. OR 15/32 CDX	8d HOT DIPPED GALVANIZED	6 in. o.c. ; EDGE 6 in. o.c. ; FIELD	
3		BOX NAILS	4 in. o.c. © GAEABLE ENDWALL OR GABLE E TRUSS 6 in. o.c. EDGE 6 in. o.c. FIELD	
4'-1	ROOF EDGE	: [4' 5'	ROOF EDGE
P. GH2		2 200	3	1
11	-4 2	/ 2 /		

ROOF SHEATHING NAILING ZONES ROOF SHEATHING NAILING ZONES (HIP ROOF)




(GABLE ROOF)

Roof Nail Pattern DET. SCALE: NONE




Gable End DETAILS SCALE: NONE



GABLE END GYPSUM DIAPHRAGM HOLDOWN CONNECTOR SCALE: NONE


K



END WALL BRACING FOR CEILING DIAPHRAGM

(ALTERNATIVE TO BALLOON FRAMING)

NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE



Truss Bracing DETAILS

SCALE: AS NOTED



SHOLAS PAUL EISLER SHITECT

SOFIPIAN

AN LAKE

AND AND

SIDENCE

COM


A CUST ST PROJEC

JOB NUMBER 09)604

SHEETNUMBER S.6

OF 63HEETS

NOTE: ALL DRAWINGS NOT TO BE SCALED, WRITTEIN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS



CONCRETE / MASONRY / **METALS GENERAL NOTES:**

- DESIGN SOIL BEARING PRESSURE: 1000 PSF.
- 2. EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PREFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
- CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING GD. SHALL BE PLACED IN 12" LIFTS. BOTH SUB-SOIL AND FILL COMPAC-TION SHALL BE NOT LESS THAN 98% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 1500 SF OF BUILDING PAD AREA, OR FRACTION THEREOF, FOR EACH 12" LIFT.
- 4. REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIRE-MENTS OF ASTM A615, ALL BENDS SHALL BE MADE COLD.
- 5. WELDED WIRE MESH SLAB REINFORCING SHALL MEET THE REQUIRE-MENTS OF ASTM A185 - MIN. YEILD STRESS = 85 KSI.
- CONCRETE SHALL BE STANDARD MIX F'c = 3000 PSI FOR ALL FTGS, SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX F'c = 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACE-MENT. MIXING, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
- CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH -F'm = 1500 PSI.
- MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
- 9. STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH, BOLTS SHALL BE ASTM A307 / GRADE 1 OR A325, AS PER PLAN REQUIREMENTS.
- 10. WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.
- 11. 2X4 P/T WOOD SILL, CONT., ALL AROUND, W/ 5/8"~ A.B. W/ 3" SQ. X 1/4" PLATE WASHERS WITHIN 6" FROM EACH CORNER, EA. WAY, & WITHIN 6" FROM ALL WALL OPENINGS / ENDS - 1/2"~ A.B. W/ 2" SQ. WASHERS ALONG EACH RUN @ 48" O.C., MAX. - ALL ANCHOR BOLTS SHALL HAVE A MINIMUM OF 8" EMBEDMENT INTO THE CONCRETE.

THE DESIGN WIND SPEED FOR THIS

PROJECT IS 110 MPH PER 2007 FBC 1609 AND LOCAL JURISDICTION REQUIREMENTS

ADDED FILL SHALL BE APPLIED IN 8" LIFTS -EA. LIFT SHALL BE CONPACTED TO 98% DRY COMPACTION PER THE "MODIFIED PROCTOR" METHOD.

NOTE:

PLUMBING CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL PLUMBING WORK, INCLUDING ALL PLUMBING LINE LOCATIONS AND RISER DIAGRAM - CONT'R SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER AND 1 COPY TO THE PERMIT ISSUING AUTHORITY.

H.V.A.C. CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL H.V.A.C. WORK, INCLUDING ALL DUCTWORK LOC., SIZES, LINES, EQUIPMENT SCH. & BALANCING REPORT - CONT'R SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER & 1 COPY TO THE PERMIT ISSUING AUTHORITY.

N22 SITE / FOUNDATION NOTES

CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS, F'c = 3000 PSI. WHERE EXCESS WATER IS ADDED TO THE CONCRETE SO THAT ITS SERVICABILITY IS DEGRADED, THE ATTAINMENT OF REQUIRED STRENGTHSHALL NOT RELEASE THE CONTRACTOR FROM PROVIDING SUCH MODIFCATIONS AS MAY BE REQUIRED BY THE ENGINNEER TO PROVIDE A SERVICEABLE MEMBER OR SURFACE. ALL CONCRETE SHALL BE VIBRATER. NO REPAIR OR RUBBING OF CONCRETE SURFACES SHALL BE MADE PRIOR TO INSPECTION BY AND APPROVAL OF ENGINEER, OWNER OR HIS REPRESENTATIVE.

WELDED WIRE REINFORCED SLAB; 6° × 6° W1.4 × W1.4, FB = 85KSI, WELDED WIRE REINFORCEMENT FABRIC (W.W.M.) CONFORMING TO ASTM A185; LOCATED IN MIDDLE OF THE SLAB; SUPPORTED WITH APPROVED MATERIALS OR SUPPORTS AT SPACINGS NOT TO EXCEED 3'.

FIBER CONCRETE SLAB: CONCRETE SLABS ON GROUND CONTAINING SYNTHETIC FIBER REINFORCEMENT. FIBER LENGTH 1/2 INCH TO 2 INCHES. DOSAGE AMOUNTS FROM 0.75 TO 1.5 POUNDS PER CUBIC YARD PER THE MANUFACTURER'S RECOMMENDATIONS. FIBERS TO COMPLY WITH ASTM C 1116. SUPPLIER TO PROVIDE ASTM C 1116 CERTIFICATION OF COMPLIANCE WHEN REQUESTED BY BUILDING OFFICIAL.

REBAR: ASTM A 615, GRADE 60, DEFORMED BARS, FY = 60 KSI. ALL LAP SPLICES 40 * DB (25" FOR #5 BARS); UNO. ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI 315-96, U.N.O. ALL TENSION DEVELOPMENT LENGTHS SHALL BE 23".

CONTROL JOINTS: WHERE SPECIFIED, SAWN CONTROL JOINTS IN SLAB-ON-GRADE SHALL BE CUT IN ACCORDANCE WITH ACI 302. JOINTS SHALL BE CUT WITHIN 12 HOURS OF SLAB PLACEMENT. THE LENGTH / WIDTH RATIOS OF SLAB AREAS SHALL NOT EXCEED 1.5 AND TYPICAL SPACING OF CUTS TO BE 12FT. DO NOT CUT WWM OR REINFORCING STEEL. (RECOMMENDED LOCATION OF CONTROL JOINTS IS SUBJECT TO OWNER AND CONTRACTOR'S APPROVAL. THE CONTROL JOINTS ARE NOT INTENDED TO PREVENT CRACKS BUT RATHER TO ENCOURAGE THE SLAB TO CRACK ON A GIVEN LINE.)

CONCREAT BLOCK: ASTM C-90 WITH MEDIUM SURFACE FINISH, F'm = 1500 PSI. MORTAR: TYPE M OR N FOR ALL MASONRY UNITS.

ANCHOR BOLTS: A-307 ANCHOR BOLTS WITH MINIMUM EMBEDMENT AS SPECIFIED IN DRAWINGS BUT NO LESS THAN 7" IN CONCRETE OR REINFORCED BOND BEAM OR 15" IN GROUTED CMU.


WASHERS: WASHERS USED WITH 1/2" BOLTS TO BE 2" \times 2" \times 9/64"; WITH 5/8" BOLTS TO BE 3" \times 3" \times 9/64"; WITH 3/4" BOLTS TO BE 3" \times 3" \times 9/64"; WITH 7/8" BOLTS TO BE 3" \times 3" \times 5/16"; UNO.

SOFTPIAN

PLAN 1/4" = 1'-0"

FOUNDATION

TLOJ. AN 30 AND AND



LAC ECA \Box \Box \Box \Box ARI N.C.A.

JOB NUMBER 09)604

SHEETNUMBER OF 63HEETS