

76 North Meadowbrook Drive Alpine, UT 84004 office (201) 874-3483 swyssling@wysslingconsulting.com

Lumio Solar 12600 Challenger Parkway, Suite 200 Orlando, FL 32826



Digitally signed by Scott Wyssling, PE DN: C=US, S=Utah, L=Alpine, O=Wyssling Consulting, OU=Engineering, CN="Scott Wyssling, PE", E=swyssling@wysslingconsulting.com Reason: I am the author of this document Location: your signing location here Date: 2022.06.28 16:50:31-06'00' Foxit PDF Editor Version: 11.2.2

Re: Engineering Services Osorio Residence 380 Southeast Melrose Way, Lake City FL 6.000 kW System

To Whom It May Concern:

We have received information regarding solar panel installation on the roof of the above referenced structure. Our evaluation of the structure is to verify the existing capacity of the roof system and its ability to support the additional loads imposed by the proposed solar system.

A. Site Assessment Information

- 1. Site visit documentation identifying attic information including size and spacing of framing for the existing roof structure.
- 2. Design drawings of the proposed system including a site plan, roof plan and connection details for the solar panels. This information will be utilized for approval and construction of the proposed system.

B. Description of Structure:

Roof Framing: Prefabricated wood trusses at 24" on center. All truss members are constructed of 2 x 4 dimensional lumber.
 Roof Material: Metal Roofing
 Roof Slopes: 27 +/- degrees
 Attic Access: Accessible

Foundation: Permanent

C. Loading Criteria Used

- Dead Load
 - Existing Roofing and framing = 7 psf
 - New Solar Panels and Racking = 3 psf
 - TOTAL = 10 PSF
- Live Load = 20 psf (reducible) 0 psf at locations of solar panels
- Ground Snow Load = 0 psf
- Wind Load based on ASCE 7-16
 - Ultimate Wind Speed = 120 mph (based on Risk Category II)
 - Exposure Category B

Analysis performed of the existing roof structure utilizing the above loading criteria is in accordance with the FBC 2020 7th Edition, including provisions allowing existing structures to not require strengthening if the new loads do not exceed existing design loads by 105% for gravity elements and 110% for seismic elements. This analysis indicates that the existing framing will support the additional panel loading without damage, if installed correctly.

D. Solar Panel Anchorage

- 1. The solar panels shall be mounted in accordance with the most recent "S-5 Installation Manual". If during solar panel installation, the roof framing members appear unstable or deflect non-uniformly, our office should be notified before proceeding with the installation.
- 2. System will be attached to the metal roofing material utilizing the patented S-5 connection. Installation of the connections shall be in accordance with the manufacturer's recommendations.
- 3. Considering the wind speed, roof slopes, size and spacing of framing members, and condition of the roof, the panel supports shall be placed no greater than 48" on center.
- 4. Panel supports connections shall be staggered to distribute load to adjacent framing members.

Based on the above evaluation, this office certifies that with the racking and mounting specified, the existing roof system will adequately support the additional loading imposed by the solar system. This evaluation is in conformance with the *FBC 2020* 7th *Edition*, current industry standards and practice, and is based on information supplied to us at the time of this report.

Should you have any questions regarding the above or if you require further information do not hesitate to contact me.

ulv vours


Scott E. Wyssling, PE Florida License No. 8





		ARRAY	DESCRIPT	ION		DESIGN SPECIF	ICATION
ROOF	# OF	AZIMUTH	TRUSS SIZE	TRUSS	ROOF	RISK CATEGORY	II
ROOI	MODULES	AZIWOTT	TRUSS SIZE	SPACING	MATERIAL	CONSTRUCTION	SFD
#1	15	278°	2X4	24" O.C.	METAL	ZONING	RESIDENTIAL
						SNOW LOAD (ASCE 7-16)	0 PSF
						EXPOSURE CATEGORY	В

LE	GEND
(E)	- EXISTING
(N)	- NEW



THIS PLAN HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY SCOTT WYSSLING, PE USING A DIGITAL SIGNATURE AND DATE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES



Wyssling Consulting, PLLC 36 h Meadowbrock Drive Alpine UT 84004 Rerida License # R734712 Date Signed 6/28/2022

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY SCOTT WYSSLING ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEAL, AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

OINOCAUSTIC STATES STAT	ATLANTIC KEY ENERGY LLC TODE STAPOINT CT STE B WINTER PARK, FL 32792 +1 (407) 988-0273 PROJECT NAME & ADDRESS
Scott E. Wyssling Florida License No. 81558 76 North Meadowbrook Drive Alpine, UT 84004 SIGNATURE WITH SEAL DESCRIPTION DATE REVISIONS DESCRIPTION DATE REVISIONS DESCRIPTION DATE DESCRIPTION DATE DESCRIPTION DATE DESCRIPTION DATE DESCRIPTION DATE NR Checked by: SHEET NAME ROOF PLAN AND MODULES	IEL MENDO RESIDE SE MELR AKE CITY,
DESCRIPTION DATE REV	Scott E. Wyssling Florida License No. 81558 76 North Meadowbrook Drive Alpine, UT 84004
Checked by: S.W. Date: 6/22/22 SHEET NAME ROOF PLAN AND MODULES	
SHEET NUMBER	Checked by: S.W. Date: 6/22/22 SHEET NAME ROOF PLAN AND MODULES SHEET NUMBER

ROOF PLAN AND MODULES

SCALE: NTS

S-0

The Right Way!®

S-5-U Clamp

The S-5-U clamp is by far our most popular and most versatile clamp. It fits about 85% of the standing seam profiles manufactured in North America—including most structural and architectural profiles. It can be used on vertically oriented seams and, by rotating the clamp 90 degrees, it can also be used on most horizontal 2" seam profiles.

Its simple design, generous dimensioning, and multiple hole orientations are what make the S-5-U clamp so versatile for use with the S-5!* snow retention products, such as ColorGard®, as well as with other heavy-duty applications.

Installation is as simple as setting the specially patented round-point setscrews into the clamp, placing the clamp on the seam, and tightening them to the specified tension. Then, affix ancillary items using the bolt provided with the product. Go to www.S-5.com/tools for information and tools available for properly attaching and tensioning S-5!

S-5-U Mini Clamp

The S-5-U Mini is a bit shorter than the S-5-U and has one setscrew rather than two. The mini is the choice for attaching all kinds of rooftop accessories: signs, walkways, satellite dishes, antennas, rooftop lighting, lightning protection systems, solar arrays, exhaust stack bracing, conduit, condensate lines, mechanical equipment—just about anything!

*S-5! mini clamps are not compatible with, and should not be used with S-5! SnoRail¹⁹/SnoFence¹¹ or ColorGard[®] snow

S-5-U Mini and -5-U

com 5 www.S-888-825-3432 |

The S-5-U clamp is our

in North America.

most popular and versatile

clamp, fitting about 85% of

the standing seam profiles


The Right Way!*


The strength of the S-5-U clamp is in its simple design. The patented setscrews will slightly dimple the metal seam material but not pierce itleaving the roof manufacturer's warranty intact.

The S-5-U and S-5-U Mini clamps are each furnished with the hardware shown to the right. Each box also includes a bit tip for tightening setscrews using an electric screw gun. A structural aluminum attachment clamp, the S-5-U is compatible with most common metal roofing materials excluding copper. All included hardware is stainless steel. Please visit www.S-5.com for more information including CAD details, metallurgical compatibilities and specifications.

The S-5-U clamp has been tested for load-to-failure results on most major brands and profiles of standing seam roofing. The independent lab test data found at www.S-5.com can be used for load-critical designs and applications. S-5!® holding strength is unmatched in the industry.


Example Profiles






For horizontal seams under 0.65", do not use this clamp. Visit www.S-5.com for more detailed information and proper clamp usage

S-5-U Clamp



S-5-U Mini Clamp



S-5!® Warning! Please use this product responsibly!

Products are protected by multiple U.S. and foreign patents. Visit the website at www.S-5.com for Products are protected by multiple U.S. and foreign patents. Visit the website at www.S-S.com for complete information on patents and trademarks. For maximum holding strength, setscrews should be tensioned and re-tensioned as the seam material compresses. Clamp setscrew tension should be verified using a calibrated torque wrench between 160 and 180 inch pounds when used on 22ga steel, and between 130 and 150 inch pounds for all other metals and thinner gauges of steel. Consult the S-S! website at www.S-S.com for published data regarding holding strength.

Copyright 2021, Metal Roof Innovations, Ltd. S-51 products are patent protected. S-51 aggressively protects its patents, trademarks, and copyrights. Version 08172

ofs!

2

SOLARMOUNT

SOLARMOUNT defined the standard in solar racking. Features are designed to get installers off the roof faster. Our grounding & bonding process eliminates copper wire and grounding straps to reduce costs. Systems can be configured with standard or light rail to meet your design requirements at the lowest cost possible. The superior aesthetics package provides a streamlined clean edge for enhanced curb appeal, with no special brackets required for installation.





LOSE ALL OF THE COPPER & LUGS SMALL IS THE NEXT NEW BIG THING ENHANCED DESIGN & LAYOUT TOOLS System grounding through Enphase microinverters and trunk cables Light Rail is Fully Compatible with all SM Components



Featuring Google Map Capabilities within U-Builder

FAST INSTALLATION. SUPERIOR AESTHETICS

OPTIMIZED COMPONENTS • VERSATILITY • DESIGN TOOLS • QUALITY PROVIDER

SOLARMOUNT



OPTIMIZED COMPONENTS INTEGRATED BONDING & PRE-ASSEMBLED PARTS

Components are pre-assembled and optimized to reduce installation steps and save straps or bonding jumpers to reduce costs. Utilize the microinverter mount with a wire

VERSATILITY **ONE PRODUCT - MANY APPLICATIONS**

Quickly set modules flush to the roof or at a desired tilt angle. Change module

AUTOMATED DESIGN TOOI DESIGN PLATFORM AT YOUR SERVICE

when you log in. You will enjoy the ability to share projects with customers: there's no need to print results and send to a distributor, just click and share



INTEGRATED BONDING



INTEGRATED BONDING MICROINVERTER MOUNT w/ WIRE MANAGEMENT



UNIRAC CUSTOMER SERVICE MEANS THE HIGHEST LEVEL OF PRODUCT SUPPORT










TECHNICAL SUPPORT


Unirac's technical support team is dedicated to answering nuestions & addressing issues in real time. An online including engineering reports stamped letters and technical data sheets greatly

CERTIFIED QUALITY PROVIDER

Unirac is the only PV mounting vendor with ISO certifications highest standards for fit form and function. These certifications demonstrate our

PROTECT YOUR REPUTATION WITH OUALITY RACKING SOLUTIONS BACKED BY ENGINEERING EXCELLENCE AND A SUPERIOR SUPPLY CHAIN





SCOPE OF WORK:

TO INSTALL A ROOF MOUNTED SOLAR PHOTOVOLTAIC SYSTEM AT THE OWNER RESIDENCE LOCATED AT 380 SE MELROSE WAY, LAKE CITY, FL 32025.

SYSTEM DC RATING: 6.00 KWDC SYSTEM AC RATING: 4.36 KWAC

GENERAL NOTES:

- THESE CONSTRUCTION DOCUMENTS HAVE BEEN BASED ON FIELD INSPECTIONS AND OTHER INFORMATION AVAILABLE AT THE TIME. ACTUAL FIELD CONDITIONS MAY REQUIRE MODIFICATIONS IN CONSTRUCTION DETAILS.
- ARCHITECT HAS NOT BEEN RETAINED TO SUPERVISE ANY CONSTRUCTION OR INSTALLATION OF ANY EQUIPMENT AT SITE.
- CONTRACTOR HAS THE FULL RESPONSIBILITY TO CHECK AND VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS. ANY DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK. ANY WORK STARTED BEFORE CONSULTATION AND ACCEPTANCE BY THE ENGINEER SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE SUBJECT TO CORRECTION BY THEM WITHOUT ADDITIONAL COMPENSATION.
- THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE PROPER INSTALLATION AND COMPLETION OF THE WORK WITH APPROVED MATERIALS.
- THE CONTRACTOR SHALL PERFORM THE WORK IN STRICT CONFORMANCE WITH THE LOCAL LAWS, REGULATIONS AND THE NATIONAL ELECTRIC CODE.

ELECTRICAL NOTES:

- THE EQUIPMENT AND ALL ASSOCIATED WIRING AND INTERCONNECTION SHALL BE INSTALLED ONLY BY QUALIFIED PEOPLE. A QUALIFIED PERSON IS ONE WHO HAS SKILLS AND KNOWLEDGE RELATED TO THE CONSTRUCTION AND OPERATION OF THE ELECTRICAL EQUIPMENT AND INSTALLATIONS AND HAS RECEIVED SAFETY TRAINING TO RECOGNIZE AND AVOID THE HAZARDS INVOLVED. (NEC 690.4(C), NEC 2017).
- NEW CONDUIT ROUTING SHOWN IS ESSENTIALLY SCHEMATIC. SUBCONTRACTOR SHALL LAY OUT RUNS TO SUIT FIELD CONDITIONS AND THE COORDINATION REQUIREMENTS OF OTHER TRADES.
- ARRAY WIRING SHOULD NOT BE READILY ACCESSIBLE EXCEPT TO QUALIFIED PERSONNEL
- ALL CONDUCTORS AND WIRE TIES EXPOSED TO SUNLIGHT ARE LISTED AS UV RESISTANT.
- ALL CONDUIT SIZES AND TYPES, SHALL BE LISTED FOR ITS PURPOSE AND APPROVED FOR THE SITE APPLICATIONS.

	Plans Reviewed	Depa
Columbia	for Code Compliance	ines,
5	ate of Florid	and a start of the

	SHEET
CS-0	COVER SHEET & BOM
E-1	STRING LAYOUT & SIGNAGE
E-2	ELECTRICAL DIAGRAM & CAL
E-3+	EQUIPMENT SPECIFICATIONS

GOVERNING CODES

2018 NFPA 1 (FIRE CODE) 2017 NATIONAL ELECTRICAL CODE 2020 FLORIDA BUILDING CODE (7TH EDITION)

AUTHORITY HAVING JURISDICTION (AHJ): COLUMBIA COUNTY

		BILL OF M
EQUIPMENT	QTY	
SOLAR PV MODULE	15	Q.PEAK DUO BLK ML
MICROINVERTER	15	ENPHASE IQ8PLUS-7
JUNCTION BOX	1	JUNCTION BOX, NEM
COMBINER BOX	1	ENPHASE IQ COMBIN
AC DISCONNECT	1	FUSED AC DISCONN

INDEX

LCS.

ATERIALS

DESCRIPTION

L-G10+ 400W

-72-2-US


MA 3R, UL LISTED

NER 4/4C W/ IQ ENVOY (X-IQ-AM1-240-4)


STATE OF

SIONAL E LORIO

IECT, 240V, NEMA 3R, UL LISTED



SOLAR





Ν

04'00' STATE OF SIONAL ENO 0 14080000 THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY OMAR TIRADO ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT

LEGEND

- NEW (N)

(E) - EXISTING

- MODULE STRING ID

- UTILITY METER

- AC DISCONNECT

- COMBINER BOX

RN RAPID SHUTDOW WITCH TO THE "OFF" POSITION TO SHUT

WN THE ENTIRE P\ SYSTEM


CONSIDERED SIGNED AND SEAL, AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES


ATLANTIC KEY ENERGY LLC TO06 STAPOINT CT STE B WINTER PARK, FL 32792 +1 (407) 988-0273 PROJECT NAME & ADDRESS
GRABIEL MENDOZA OSORIO RESIDENCE 380 SE MELROSE WAY LAKE CITY, FL 32025
ENGINEER CONTACT INFORMATION OMAR TIRADO LICENSE# 89380 12600 CHALLENGER PKWY, STE 200 ORLANDO, FL 32826 SIGNATURE WITH SEAL
REVISIONS DESCRIPTION DATE REV Image: Colspan="2">Image: Colspan="2" Image: Colspan=""Colspan="2" Image: Colspa
Drawn by: N.R. Checked by: O.T. Date: 6/22/22
STRING LAYOUT & SIGNAGE
SHEET NUMBER

1	ROOF PLAN WITH STRING LAYOUT
E-1	SCALE: NTS

ID	INITIAL CONDUCTOR LOCATION	FINAL CONDUCTOR LOCATION	MIN	I. CONDUCTOR SIZE (AWG)	MIN. DIA CONDUIT SIZE (IN.)	# OF PARALLEL CIRCUITS	CURRENT-CARRYING CONDUCTORS IN CONDUIT	OCPD (A)		MIN. EGC SIZE (AWG)	TEMP. COR	R. FACTOR	CONDUIT FILL FACTOR	CONT. CURRENT (A)	MAX. CURRENT (A)	BASE AMP. (A)	D
1	STRING A	JUNCTION BOX	12	Q CABLE	N/A	1	2	N/A	6	BARE COPPER	0.76	55°C	N/A	8.47	10.59	30	
2	STRING B	JUNCTION BOX	12	Q CABLE	N/A	1	2	N/A	6	BARE COPPER	0.76	55°C	N/A	9.68	12.10	30	
3	JUNCTION BOX	IQ COMBINER	10	THWN-2 COPPER	0.75 LTNM	2	4	20	10	THWN-2 COPPER	0.76	55°C	0.8	9.68	12.10	40	
4	IQ COMBINER	AC DISCONNECT	10	THWN-2 COPPER	0.75 LTNM	1	3	30	10	THWN-2 COPPER	0.96	34°C	1	18.15	22.69	40	
5	AC DISCONNECT	MSP	6	THWN-2 COPPER	0.75 LTNM	1	3	N/A	-	-	0.96	34°C	1	18.15	22.69	75	

NOTE: LTNM OR EQUIVALENT TYPE CONDUIT






BASE	DERATED	TERM. AMP.				
AMP. (A)	AMP. (A)	RATING (A)	LENGTH (F	,	ROP (%)	AVC.
30	N/A	N/A	40.00		0.56	ANC SOLAR
30	N/A	N/A	30.00	(0.48	
40	24.3	35	40.00	(0.40	ATLANTIC KEY ENERGY LLC 7006 STAPOINT CT
40	38.4	35	5.00	(0.09	STE B WINTER PARK, FL 32792
75	72.0	65	5.00		0.04	+1 (407) 988-0273
(E) BI-DI UTILITY I	RECTIONAL					GRABIEL MENDOZA OSORIO RESIDENCE 380 SE MELROSE WAY LAKE CITY, FL 32025
	 (E) MAIN BREAK TO HOUSE, 200 					ENGINEER CONTACT INFORMATION OMAR TIRADO LICENSE# 89380 12600 CHALLENGER PKWY, STE 200 ORLANDO, FL 32826
] +					SIGNATURE WITH SEAL
	ROUND					REVISIONS
	UCTOR					DESCRIPTION DATE REV
						Drawn by: N.R.
			Г	LEGE	ND	Checked by: 0.T.
					ISTING	Date: 6/22/22
				(N) - NE		
	DESIGN TE	MPERATUR	E SPECIF	ICATIO		ELECTRICAL LINE
	CORD LOW T				1°C	DIAGRAM & CALCS.
AN	IBIENT TEMP	(HIGH TEMP 2%	b)		34°C	SHEET NUMBER
	NDUIT HEIGH				1.0"	E-2
CC	NDUCTOR TE	MPERATURE R	ATE (ROO	F)	55°C	

- 6AWG BARE COPPER

MECHANICAL SPECIFICATION


Format	74.0 in × 41.1 in × 1.26 in (including frame) (1879 mm × 1045 mm × 32 mm)
Weight	48.5lbs (22.0 kg)
Front Cover	0.13 in (3.2mm) thermally pre-stressed glass with anti-reflection technology
Back Cover	Composite film
Frame	Black anodized aluminum
Cell	6 × 22 monocrystalline Q.ANTUM solar half cells
Junction Box	2.09-3.98 in × 1.26-2.36 in × 0.59-0.71 in (53-101 mm × 32-60 mm × 15-18 mm), IP67, with bypass diodes
Cable	4 mm² Solar cable; (+) ≥49.2 in (1250 mm), (-) ≥49.2 in (1250 mm)
Connector	Staubli MC4; IP68




ELECTRICAL CHARACTERISTICS

PO	WER CLASS			385	390	395	400	405
1ENJ	IIMUM PERFORMANCE AT STANDA	RD TEST CONDITIC	NS, STCI (PO	WER TOLERANCE +	5W/-0W)			
-	Power at MPP ¹	PMP	[W]	385	390	395	400	405
	Short Circuit Current ¹	Isc	[A]	11.04	11.07	11.10	11.14	11.17
Minimun	Open Circuit Voltage ⁴	Voc	[V]	45.19	45.23	45.27	45.30	45.34
	Current at MPP	IMPP	[A]	10.59	10.65	10.71	10.77	10.83
	Voltage at MPP	V _{MPP}	[V]	36.36	36.62	36.88	37.13	37,39
	Efficiency!	η	[%]	≥19.6	≥19.9	≥20.1	≥20.4	≥20.6
MIR	IMUM PERFORMANCE AT NORMA	LOPERATING CON	DITIONS, NMC	∑T [±]				
mumi	Power at MPP	PMEP	[W]	288.8	292.6	296.3	300.1	303.8
	Short Circuit Current	lec	[A]	8.90	8.92	8.95	8.97	9.00
	Open Circuit Voltage	Vac	[V]	42.62	42.65	42.69	42.72	42.76
Min	Current at MPP	IMPP	[A]	8.35	8.41	8,46	8.51	8.57
	Voltage at MPP	VMP	[V]	34,59	34,81	35.03	35.25	35.46

Q CELLS PERFORMANCE WARRANTY





Typical module performance under low irradiance conditions in comparison to STC conditions (25°C, $1000\,W/m^2$)

2

24

pallets

24

pallets modules

32

48.0 in 1656lbs 1220mm 751 kg


C

Temperature Coefficient of Isc	a	[%/K]	+0.04	Temperature Coefficient of Voc	β	[%/K]	-0.27
Temperature Coefficient of P _{MPP}	Y	[%/K]	-0.34	Nominal Module Operating Temperature	NMOT	[*F]	109±5.4 (43±3°C)

Maximum System Voltage Vers	0.0	1000/501/1000/101	PV module classification	Class II	
Maximum SASIAILI ADILBÃO (202	141	1000(EOU 1000(0C)	F 4 Induite classification	101030-1	
Maximum Series Fuse Rating	[A DC]	20	Fire Rating based on ANSI/UL 61730	TYPE 2	
Max. Design Loed, Push / Pull ^a	[lbs/ft2]	75 (3600 Pa) /55 (2660 Pa)	Permitted Module Temperature	-40°F up to +185°F	
Max. Test Load, Push/PulP	[lbs/ft²]	113 (5400Pa)/84 (4000Pa)	en Continuous Duty	(-40 °C up to +85 °C	
² See Installation Manual					

QUALIFICATIONS AND CERTIFICATES

UL-61730, CE-compliant, Gueiny Controlled PV - TÜV Rheinland, IEC 612152018, IEC 647302016, U.S. Patient No. 9,898,215 (solar cells), QCPV Centification angoing.



Note: Installation instructions must be followed. See the Installation and operating manual or contact our technical service department for further information on approved installation and use of this product.

Hanwha Q CELLS America Inc. 400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 748 59 96 | EMAIL inquiry@us.q-cells.com | WEB www.q-cells.us

NPUT DATA (DC)		108-60-2-US	108PLUS-72-2-US	WINTER PAR	RK, FL 327
Commonly used module pairings ¹	w	235 - 350	235 - 440	+1 (407) 9	,
Aodule compatibility		60-cell/120 half-cell	60-cell/120 half-cell and 72-cell/144 half-cell	PROJECT NAM	IE & ADDF
IPPT voltage range	v	27-37	29-45		
Operating range	v	25-48	25 - 58		
/in/max start voltage	٧	30 / 48	30/58		
lax input DC voltage	v	50	60		
lax DC current ² [module lsc]	A		15	OSORIC	
vervoltage class DC port			1	II Б	γ μ
C port backfeed current	mA		0	US I	STORE
V array configuration		txl Ungrounded array; No additional DC side protection req	uired; AC side protection requires max 20A per branch circuit		OSE WAY
UTPUT DATA IACI		108-60-2-US	108PLUS-72-2-US	DOZA	S S
eak output power	VA	245	300		Ц
lax continuous output power	VA	240	290	GRABIEL MENDOZA RESIDENCE	MEL
ominal (L-L) voltage/range ³	v	240 / 2	211 - 264	II E SI	<u>∃</u> 5
lax continuous output current	A	1.0	1.21		SE
lominal frequency	Hz		60		
xtended frequency range	Hz	50	- 68	AB	380
ax units per 20 A (L-L) branch circuit		16	13		(.)
otal harmonic distortion		<	5%	0	
vervoltage class AC port					
C port backfeed current	mA		30		
ower factor setting			1.0		
rid-tied power factor (adjustable)		0.85 leading	- 0.85 lagging	ENGINEER CONTA	
eak efficiency	%	97.5	97.6	OMAR T	
EC weighted efficiency	%	97	97	LICENSE	E# 89380
ight-time power consumption	m\¥		60	12600 CHALLENGE ORLANDO	
ECHANICAL DATA				SIGNATURE	WITH SE
mbient temperature range		-40°C to +60°C	(-40°F to +140°F)		
elative humidity range		4% to 100%	(condensing)		
C Connector type		M	104		
Nimensions (HxWxD)		212 mm (8.3") x 175 mr	m (6.9") x 30.2 mm (1.2")		
Veight		1.08 kg	(2.38 lbs)		
cooling		Natural conve	ection - no fans		
pproved for wet locations		,	fes		
coustic noise at 1 m		<60	0 dBA		
collution degree			03	DESCRIPTION	DATE
inclosure		Class II double-insulated, corros	sion resistant polymeric enclosure		
nviron. category / UV exposure rating	_	NEMA Type	e 6 / outdoor		
OMPLIANCE					
		CA Rule 21 (UL 1741-SA), UL 62109-1, UL1741/IEEE1547, FCC Part	15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01		
ertifications		This product is UL Listed as PV Rapid Shut Down Equipment and 690.12 and C22.1-2018 Rule 64-218 Rapid Shutdown of PV Systemeters and C22.1-2018 Rule 64-218 Rapid Shutdown of PV Systemete			
		manufacturer's instructions.		Drawn by:	
No enforced DC /AC ratio See the cor	matib	lity calculator at https://link.enphase.com/		Checked by:	
dule-compatibility (2) Maximum conti	nuous	input DC current is 10.6A (3) Nominal voltage		Date: SHEET	
ige can be extended beyond nominal i al requirements to define the number		red by the utility. (4) Limits may vary. Refer to oinverters per branch in your area.	IQ8SP-DS-0002-01-EN-US-2021-10-19	EQUIP	
		n ann an Ann an Ann a' ann an ann ann an			
				SPECIFIC	JAHC

Enphase IQ Combiner 4/4C

MODEL NUMBER					
IQ Combiner 4 (X-IQ-AM1-240-4)	IQ Combiner 4 with Enphase IQ Gateway printed circuit boa C12.20 +/- 0.5%) and consumption monitoring (+/- 2.5%). In IQ System Controller 2 and to deflect heat.				
IQ Combiner 4C (X-IQ-AM1-240-4C)	IQ Combiner 4C with Enphase IQ Gateway printed circuit b (ANSI C12.20 +/-0.5%) and consumption monitoring (4/-2 (CELLMODEM-M1-06-SP-05), a plug-and-play industrial-g (Available in the US, Canada, Mexico, Puerto Rico, and the the installation area.) includes a silver solar shield to matcl				
ACCESSORIES AND REPLACEMENT PARTS	(not included, order separately)				
Ensemble Communications Kit COM MS-CELLMODEM-M1-06 CELLMODEM-M1-06-SP-05 CELLMODEM-M1-06-AT-05	 Includes COMMS-KIT-01 and CELLMODEM-M1-06-SP-05 Ensemble sites 46 based LTE-M1 cellular modem with 5-year Sprint data 46 based LTE-M1 cellular modem with 5-year AT&T data 				
Circuit Breakers BRK-10A-2:240V BRK-15A-2:240V BRK-20A-2P-240V BRK-5A-2P-240V-B BRK-5A-2P-240V-B BRK-20A-2P-240V-B	Supports Eaton BR210, BR215, BR220, BR230, BR240, BR Circuit breaker, 2 pole, 10A, Eaton BR210 Circuit breaker, 2 pole, 15A, Eaton BR215 Circuit breaker, 2 pole, 20A, Eaton BR220 Circuit breaker, 2 pole, 15A, Eaton BR215B with hold dow Circuit breaker, 2 pole, 20A, Eaton BR220B with hold dow				
EPLC-01	Power line carrier (communication bridge pair), quantity -				
XA-SOLARSHIELD-ES	Replacement solar shield for IQ Combiner 4/4C				
XA-PLUG-120-3	Accessory receptacle for Power Line Carrier in IQ Combine				
XA-ENV-PCBA-3	Replacement IQ Gateway printed circuit board (PCB) for (
X-IQ-NA-HD-125A	Hold down kit for Eaton circuit breaker with screws.				
ELECTRICAL SPECIFICATIONS					
Rating	Continuous duty				
System voltage	120/240 VAC, 60 Hz				
Eaton BR series busbar rating	125 A				
Max. continuous current rating	65 A				
Max. continuous current rating (input from PV/storage)	64 A				
Max. fuse/circuit rating (output)	90 A				
Branch circuits (solar and/or storage)	Up to four 2-pole Eaton BR series Distributed Generation				
Max. total branch circuit breaker rating (input)	80A of distributed generation / 95A with IQ Gateway brea				
Production metering CT	200 A solid core pre-installed and wired to IQ Gateway				
Consumption monitoring CT (CT-200-SPLIT)	A pair of 200 A split core current transformers				
MECHANICAL DATA					
Dimensions (WxHxD)	37.5 x 49.5 x 16.8 cm (14.75" x 19.5" x 6.63"). Height is 21.				
Weight	7.5 kg (16.5 lbs)				
Ambient temperature range	-40° C to +46° C (-40° to 115° F)				
Cooling	Natural convection, plus heat shield				
Enclosure environmental rating	Outdoor, NRTL-certified, NEMA type 3R, polycarbonate co				
Wire sizes	 20 A to 50 A breaker inputs: 14 to 4 AWG copper conduct 60 A breaker branch input: 4 to 1/0 AWG copper conduct Main lug combined output: 10 to 2/0 AWG copper conduct Neutral and ground: 14 to 1/0 copper conductors Always follow local code requirements for conductor sizi 				
Altitude	To 2000 meters (6,560 feet)				
INTERNET CONNECTION OPTIONS					
Integrated Wi-Fi	802.11b/g/n				
Cellular	CELLMODEM-M1-06-SP-05, CELLMODEM-M1-06-AT-05 (4 Mobile Connect cellular modem is required for all Ensemble i				
Ethernet	Optional, 802.3, Cat5E (or Cat 6) UTP Ethernet cable (not				
COMPLIANCE	U 1741 041/004 000 04 4011 11 000 0				
Compliance, IQ Combiner	UL 1741, CAN/CSA C22.2 No. 107.1, 47 CFR, Part 15, Clas Production metering: ANSI C12.20 accuracy class 0.5 (PV Consumption metering: accuracy class 2.5				
Compliance, IQ Gateway	UL 60601-1/CANCSA 22.2 No. 61010-1				

To learn more about Enphase offerings, visit enphase.com

© 2021 Enphase Energy, All rights reserved. Enphase, the Enphase logo, IQ Combiner 4/4C, and other names are trademarks of Enphase Energy, Inc. Data subject to change. 10-21-2021

