

ARRAY DESCRIPTION						
ROOF	# OF MODULES	AZIMUTH	TRUSS SIZE	TRUSS SPACING	ROOF MATERIAL	
#1	22	178	2X4	24"O.C.	METAL	

	DESIGN SPECIFICATION				
	RISK CATEGORY	II			
	CONSTRUCTION	SFD			
	ZONING	RESIDENTIAL			
J	SNOW LOAD (ASCE 7-16)	0 PSF			
	EXPOSURE CATEGORY	В			
	WIND SPEED (ASCE 7-16)	150 MPH			





THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY OMAR TIRADO ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT VCONSIDERED SIGNED AND SEAL, AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

LEGEND
(E) - EXISTING
(N) - NEW

(N) - NEW

ROOF PLAN AND MODULES

SCALE: NTS

ATLANTIC KEY ENERGY LLC
12600 CHALLENGER PARKWAY
SUITE 200
ORLANDO, FL 32826
1 (407) 988-0273

Lumio X

ASHLEY DULL
RESIDENCE
PROJECT # P-0065449
1108 NORTHWEST ASHLEY ST
LAKE CITY, FL 32055

SIGNATURE WITH SEAL

REVISIONS

DESCRIPTION DATE REV

Drawn by: N.R

late: SHEET NAME

ROOF PLAN AND MODULES

1/10/2023

SHEET NUMBER

S-0

ProteaBracket[™]

A versatile bracket for mounting solar PV to trapezoidal roof profiles

profiles!

roof

trapezoidal

2

2

solar

attach

ProteaBracket™ is now made in aluminum. Still the most versatile trapezoidal metal roof attachment solution on the market, the S-5! ProteaBracket just got better!

The bracket features an adjustable attachment base and module attachment options to accommodate different roof profile dimensions and mounting options.

Our pre-applied EPDM gasket with peel and stick adhesive makes installation a snap, ensuring accurate and secure placement the first time.

With no messy sealants, faster installation, and a weather-proof fit, ProteaBracket offers you the most versatile solar attachment solution available.

ProteaBracket* can be used for rail mounting or "direct-attach" with S-5! PVKIT™

*When ProteaBracket is used in conjunction with the S-5! PVKIT, an additional nut is required during installation.

NEW

www.S-5.com

888-825-3432

NOW AVAILABLE IN ALUMINUM



Features and Benefits

- 34% lighter saves on shipping
- Stronger L-Foot™
- Load-tested for engineered application
- Corrosion-resistant materials
- Adjustable Fits rib profiles up to 3"
- Peel-and-Stick prevents accidental shifting during installation
- Fully pre-assembled
- 25-year warranty*

*See www.S-S.com for details



ProteaBracket™ is the perfect solar attachment solution for most trapezoidal rib, exposed-fastened metal roof profiles!

ProteaBracket™ is compatible with common metal roofing materials and comes with a pre-applied EPDM gasket on

Note: All four pre-punched holes must be used to achieve tested strength. Fasteners are provided.


For design assistance, ask your distributor, or visit www.S-5.com for the independent lab test data that can be used for load-critical designs and applications. Also, please visit our website for more information including metallurgical compatibilities and specifications.

S-5!" holding strength is unmatched in the industry.


Multiple Attachment Options:



Side Mount Rail



Bottom Mount Rail



S-51* Warning! Please use this product responsibly!

Copyright 2019, Metal Roof Innovations, ibd. 5-51 products are patent protected. 5-51 aggressively protects its patents, trademarks, and copyrights. Version 07060

Products are protected by multiple U.S. and foreign patents. For published data regarding holding strength, bolt torque, patents, and trademarks, visit the S-Si website at www.S-S.com.

w/S-5! PVKIT™ (rail-less)

ProteaBracket 0.35" x 1,00" Slotted Hole-

Protea Bracket fits profiles up to 3 inches

No surface preparation needed. (1) Wipe away excess oil and debris. (2) Peel off adhesive release paper. (3) Align and mount bracket directly onto crown of panel. (4) Secure ProteaBracket through pre-punched holes, using piercing-point S-5! screws.



Distributed by

ATLANTIC KEY ENERGY LLC

12600 CHALLENGER PARKWAY SUITE 200 ORLANDO, FL 32826 1 (407) 988-0273

PROJECT # P-0065449 1108 NORTHWEST ASHLEY S ASHLEY DULL RESIDENCE

S

SIGNATURE WITH SEAL

REVISIONS DESCRIPTION DATE REV

SHEET NAME

1/10/2023

EQUIPMENT SPECIFICATIONS SHEET NUMBER

S-1

SOLARMOUNT



SOLARMOUNT defined the standard in solar racking. Features are designed to get installers off the roof faster. Our grounding & bonding process eliminates copper wire and grounding straps to reduce costs. Systems can be configured with standard or light rail to meet your design requirements at the lowest cost possible. The superior aesthetics package provides a streamlined clean edge for enhanced curb appeal, with no special brackets required for installation.









System grounding through Enphase microinverters and trunk cables Light Rail is Fully Compatible with all SM Components



FAST INSTALLATION. SUPERIOR AESTHETICS

OPTIMIZED COMPONENTS . VERSATILITY . DESIGN TOOLS . QUALITY PROVIDER

SOLARMOUNT

#UNIRAC

OPTIMIZED COMPONENTS


INTEGRATED BONDING & PRE-ASSEMBLED PARTS

Components are pre-assembled and optimized to reduce installation steps and save straps or bonding jumpers to reduce costs. Utilize the microinverter mount with a wire

ONE PRODUCT - MANY APPLICATIONS

Quickly set modules flush to the roof or at a desired tilt angle. Change module

when you log in. You will enjoy the ability to share projects with customers; there's no need to print results and send to a distributor, just click and share





UNIRAC CUSTOMER SERVICE MEANS THE HIGHEST LEVEL OF PRODUCT SUPPORT













TECHNICAL SUPPORT

CERTIFIED QUALITY PROVIDER

BANKABLE WARRANTY

quality. SOLARMOUNT is covered by a twenty five (25) year

PROTECT YOUR REPUTATION WITH QUALITY RACKING SOLUTIONS BACKED BY ENGINEERING EXCELLENCE AND A SUPERIOR SUPPLY CHAIN



ATLANTIC KEY ENERGY LLC 12600 CHALLENGER PARKWAY

SUITE 200 ORLANDO, FL 32826

PROJECT # P-0065449 1108 NORTHWEST ASHLEY S RESIDENCE

SIGNATURE WITH SEAL

REVISIONS DESCRIPTION DATE

1/10/2023 SHEET NAME

EQUIPMENT SPECIFICATIONS

SHEET NUMBER

S-2