


| BEARING WOOD INTERIOR WALL SCHEDULE | | | | | |
|-------------------------------------|--------------|-------------------------------|-------------------------------|----------------|------------------|
| MARK | STUD SPACING | CONNECTION & FASTENERS | | LUMBER SPECIES | UPLIFT CAP (LBS) |
| | | TOP | BOTTOM | | |
| BW1 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW2 | 16" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SPF | 402 |
| BW3 | 16" | SP4 W/ (6) 10d X 1 1/2" NAILS | SP4 W/ (6) 10d X 1 1/2" NAILS | SPF | 571 |
| BW4 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW5 | 16" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SYP | 439 |
| BW6 | 16" | SP4 W/ (6) 10d X 1 1/2" NAILS | SP4 W/ (6) 10d X 1 1/2" NAILS | SYP | 665 |
| BW7 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW8 | 12" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SPF | 535 |
| BW9 | 12" | SP4 W/ (6) 10d X 1 1/2" NAILS | SP4 W/ (6) 10d X 1 1/2" NAILS | SPF | 760 |
| BW10 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW11 | 12" | SP2 W/ (6) 10d NAILS | SP1 W/ (6) 10d NAILS | SYP | 585 |
| BW12 | 12" | SP4 W/ (6) 10d X 1 1/2" NAILS | SP4 W/ (6) 10d X 1 1/2" NAILS | SYP | 885 |

NOTE: 2 x 4 WALLS ARE ASSUMED U.N.O. ON FLOOR PLANS
 * ALL LUMBER TO BE GRADE #2
 ** CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED
 *** SP2'S & SP4'S CAN BE SUB. FOR SP4'S W/ RESPECT TO STUD SIZE



BEARING INTERIOR WALL DETAIL

- GENERAL NOTES**
- SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED UNO.
 - ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.
 - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 - CONTACT E.O.R. IF SPA S, SP1 S OR SP2 S CONNECTORS ARE SUBSTITUTED. TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
 - IF "B" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE WRO6/S3.1 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2nd FLOOR TO 1ST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY.)
 - IF "S" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 7/16" OSB PLYWOOD W/ 8d NAILS AT 4" O.C. IN FIELD AND EDGE TO (1) SIDE OF WALL & 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE AND AS SHEARWALLS. SEE PLAN AND WALLS SECTION FOR STUD SPACING AND GRADE.
 - IF THE BEARING WALL IS INDICATED WITH THE BWL BW4, BW7, BW10 THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT. THE STUDS ARE TOE NAILED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (8d NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

| COLUMN SCHEDULE | | | | |
|-----------------|---|---|-----------------------|--|
| MARK | COLUMN SIZE | (BASE) CONN. & FASTENER | UPLIFT(LBS) | |
| C1 | (3) 2 x 4 #2 SPF | (4) - 16d TOENAILS | 0 | |
| C2 | (3) 2 x 4 #2 SPF | DT122 W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS | 2145 | |
| C3 | (3) 2 x 4 SYP #1 OR- | (4) - 16d TOENAILS | 0 | |
| C4 | (4) 2 x 4 SPF #2 | | 2145 | |
| C5 | 4 x 4 P.T. #2 SYP POST | AQUA W/ 5/8" ATR** & (12) - 16d NAILS | G = 6665 U = 2200 | |
| C6 | 6 x 6 P.T. #2 SYP POST | ABUG6 W/ 5/8" ATR** & (12) - 16d NAILS | G = 12000 U = 2300 | |
| C7 | 8 x 8 P.T. #2 SYP POST | ABUG8 W/ (2) - 5/8" ATR** & (18) - 16d NAILS | G = 21335 U = 2320 | |
| C8 | 3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C9 | 3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (14) 1/4" X 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C10 | 3.5 x 3.5 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 6970 | |
| C11 | 5.25 x 5.25 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C12 | 7 x 7 F.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C13 | 5.25 x 7 x 7 P.L. 1.8E Rb-2400 PSI (WOLMANIZED IF EXT.) | HOURSDS2 S W/ (20) 1/4" X 2 1/2" SDS WS & 7/8" EPOXY ANCHOR, OR ATR** | 7870 | |

- GENERAL COLUMN NOTES**
- SEE FLOOR PLAN FOR WALL WIDTH. STUD PACKS TO MATCH WALL WIDTH UNO.
 - ALL STRUCTURAL LUMBER TO BE SYP #1 OR SPF #2 UNO ON PLAN.
 - NAIL BUILT UP STUDS PER DETAIL WF37.
 - MINIMUM BOLT EMBEDMENT:
5" EMBEDMENT FOR 1/2" ATR
6" EMBEDMENT FOR 5/8" ATR
8" EMBEDMENT FOR 1" ATR
 - IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL-OUT ON PLAN FOR ATTACHMENT)
 - SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
 - SAME NOMINAL SIZE PARALLEL COLUMNS (1.8E) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS**

| COMMON NAIL vs. PNEUMATIC GUN NAILS: | | | |
|--------------------------------------|-----------------|--------------------|------------------------------|
| COMMON NAIL | DIA. / LENGTH | PNEUMATIC GUN NAIL | APPLICATION |
| 8d | 0.131" X 2 1/4" | 0.131" X 2 1/4" | SEE PLAN RING SHEATH ON ROOF |
| 10d OR 12d | 0.148" X 3" | 0.131" X 3" | SEE PLAN |
| 12d | 0.148" X 3 1/4" | 0.131" X 3 1/4" | STUD WALL CORNERS |
| 10d | 0.148" X 3" | 0.131" X 3" | STUD PACK COLUMNS |
| 16d | 0.162" X 3 1/4" | 0.131" X 3 1/4" | SEE PLAN |


| BEAM SCHEDULE | | |
|---------------|--|---|
| MARK | BEAM SIZE | CONNECTIONS |
| BM1 | (2) - 2 x 8 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA18 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM2 | (2) - 2 x 10 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM3 | (2) - 2 x 12 #2 SYP W/ 7/16" OSB FLITCH PLATE. NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM4 | (2) - 1 3/4" X 11 1/4" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA14 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM5 | (2) - 1 3/4" X 11 7/8" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA14 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM6 | (2) - 1 3/4" X 16" LVL 2.0E Rb=2600 PSI. NAIL BEAM TOGETHER USING (2) ROWS 1/4" X 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |

- GENERAL BEAM NOTES**
- VERIFY W/ PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END)
 - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
 - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.

| HEADER SCHEDULE | | |
|-----------------|---|---|
| MARK | HEADER SIZE | REMARKS |
| H1 | (2) - 2X6 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H2 | (2) - 2X8 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H3 | (2) - 2X10 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H4 | (2) - 2X12 #2 SYP W/ 1/2" FLITCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H5 | (2) - 1 3/4" X 11 1/4" LVL 2.0E Rb=2600 PSI | ATTACH TOGETHER W/ (2) ROWS 1/4" X 1 1/2" SDS MD SCREWS @ 16" O.C. TYP. EACH SIDE |
| H6 | (2) - 1 3/4" X 9 1/4" LVL 2.0E Rb=2600 PSI | ATTACH TOGETHER W/ (2) ROWS 1/4" X 1 1/2" SDS MD SCREWS @ 16" O.C. TYP. EACH SIDE |

| HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS | | | |
|--|----------|-----------------|-----|
| OPENING SIZE | 2x4 WALL | 2x6 OR 2x8 WALL | |
| 1'-0" - 3'-11" | (1) | (1) | (2) |
| 4'-0" - 9'-11" | (2) | (3) | (2) |
| 10'-0" - 16'-0" | (3) | (4) | (3) |


- GENERAL HEADER NOTES**
- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
 - IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CONNECTIONS UNO ON PLAN
 - IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.
 - ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF37.
 - FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" o.c. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
 - FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
 - IF HEADER IS NOT SPECIFIED CONTACT E.O.R.



- Any accessible space under a stairway shall be protected with 1/2" gypsum board.
- Maximum Stair Riser height not to exceed 7 3/4"
- Minimum Stair Tread depth shall be not less than 10" (exclusive of nosing).

STAIR DETAIL (STRAIGHT)

SCALE: 1/4" = 1'-0"



1ST FLOOR PLAN

SCALE: 1/4" = 1'-0"
(ALL ELEVATIONS)

NOTE:
 INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
- Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length
 The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
 M1502.3 Duct termination
 Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
 Option 1: Gypsum
 1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
 The gypsum board shall be attached w/ Type "W" 1x4 drywall screws at 8" O.C. in field and edges.
 Option 2: Plyster Base
 7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path. Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

| | |
|-----------------------|-----------|
| 1st FLOOR | 1020 S.F. |
| 2nd FLOOR | 1385 S.F. |
| TOTAL LIVING (AC) | 2405 S.F. |
| GARAGE | 416 S.F. |
| LANAI | 118 S.F. |
| COVERED ENTRY | 52 S.F. |
| TOTAL AREA UNDER ROOF | 2991 S.F. |

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is for the structural engineering portions of the drawing pages bearing engineer's signature and seal.
 CA No. 9161 AA26003115

TOTAL SOLUTIONS GROUP
 258 Southhall Lane, Suite 200
 Maitland, Florida, 32751
 (407) 880 2333

100% Employee Owned
 myTSGhome.com


DAMS HOMES
 FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY
 LOT: 117
 BLK:
 SEC:
 SUB: PRESERVE AT LAUREL LAKE
 120 SW BELFLOWER DR
 LAKE CITY

Model Name / Number:
2405
 Plan/Issue Date:
 Wednesday, March 19, 2025
 KA PROJECT NUMBER:
25-02688
 Sheet: **2** Of:
FLOOR PLAN

| BEARING WOOD INTERIOR WALL SCHEDULE | | | | | |
|-------------------------------------|--------------|-------------------------------|-------------------------------|-----------------|-----|
| MARK | STUD SPACING | CONNECTION & FASTENERS | LUMBER SPECIES | UPLIFT CAP (lb) | |
| | | TOP | BOTTOM | | |
| BW1 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW2 | 16" | SP2 W/ (6)10d NAILS | SP1 W/ (6)10d NAILS | SPF | 402 |
| BW3 | 16" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SPF | 574 |
| BW4 | 16" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW5 | 16" | SP2 W/ (6)10d NAILS | SP1 W/ (6)10d NAILS | SYP | 439 |
| BW6 | 16" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SYP | 665 |
| BW7 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SPF | 0 |
| BW8 | 12" | SP2 W/ (6)10d NAILS | SP1 W/ (6)10d NAILS | SPF | 535 |
| BW9 | 12" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SPF | 760 |
| BW10 | 12" | (2) 16d TOENAILS | (2) 16d TOENAILS | SYP | 0 |
| BW11 | 12" | SP2 W/ (6)10d NAILS | SP1 W/ (6)10d NAILS | SYP | 585 |
| BW12 | 12" | SP4 W/ (6) 10d x 1 1/2" NAILS | SP4 W/ (6) 10d x 1 1/2" NAILS | SYP | 885 |



- ### GENERAL NOTES
- SEE FLOOR PLAN FOR WALL SIZE, ASSUME 2x4 STUDS USED UNO.
 - ALL STRUCTURAL LUMBER TO BE SP#1 #1 OR SP#2 UNO ON PLAN.
 - CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 - CONTACT E.O.R. IF SP#4 S, SP#5 OR SP#6'S CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
 - IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED, SEE W/09.3.1 OR INDICATED DETAIL FOR PROPER CONNECTIONS FOR 2ND FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 3 STORY PROJECTS ONLY)
 - IF "BW" IS INDICATED THE WALL IS CONSIDERED A SHEARWALL AND REQUIRES MIN. 7" MIN. OSB FLUTCH PLATE AND ANCHORS AT 4" O.C. IN FIELD AND ETC. TO (1) SIDE OF WALL.
 - ALL 2x EXTERIOR WALLS W/ EXTERIOR SHEATHING ATTACHED PER NAILING SCHEDULE ACT AS SHEARWALLS. SEE PLAN AND WALL SECTIONS FOR STUD SPACING AND GRADE.
 - IF THE BEARING WALL IS INDICATED WITH THE BOLD, BWA, BWT, BWD THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT, THE STUDS ARE TOE NAIL TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HAND CAPPED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

| COLUMN SCHEDULE | | | | |
|-----------------|--|--|-----------------------|--|
| MARK | COLUMN SIZE | (BASE) CONN. & FASTENER | UPLIFT(LB) | |
| C1 | (3) 2 x 4 #2 SPF | (4) - 16d TOENAILS | 0 | |
| C2 | (3) 2 x 4 #2 SPF | DT22 W/ 1/2" WEDGE ANCHOR & (6) 1/4" x 1 1/2" SDS SCREWS | 2145 | |
| C3 | (3) 2 x 4 SYP #1 OR | (4) - 16d TOENAILS | 0 | |
| C4 | (4) 2 x 4 SPF #2 | DT22 W/ 1/2" WEDGE ANCHOR & (6) 1/4" x 1 1/2" SDS SCREWS | 2145 | |
| C5 | 4 x 4 P.T. #2 SYP POST | ABU4 W/ 5/8" ATR** & (2) - 16d NAILS | G = 6065 U = 2200 | |
| C6 | 6 x 6 P.T. #2 SYP POST | ABU6 W/ 5/8" ATR** & (2) - 16d NAILS | G = 12000 U = 2300 | |
| C7 | 8 x 8 P.T. #2 SYP POST | ABU8 W/ (2) - 5/8" ATR** & (3) - 16d NAILS | G = 24335 U = 2320 | |
| C8 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C9 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ (14) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 5645 | |
| C10 | 3.5 x 3.5 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 6970 | |
| C11 | 5.25 x 5.25 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C12 | 7 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ (20) 1/4" x 2 1/2" SDS WS & 5/8" EPOXY ANCHOR, OR ATR** | 7870 | |
| C13 | 5.25 x 7 P.L. 1.8E Rb=2400 PSI (WOLMANIZED IF EXT.) | H0US-SDS2.5 W/ 7/8" ATR AND (20) 1/4" x 2" SDS WOOD SCREWS | 7870 | |

- ### GENERAL COLUMN NOTES
- SEE FLOOR PLAN FOR WALL WIDTH, STUD PAKS TO MATCH WALL WIDTH UNO.
 - ALL STRUCTURAL LUMBER TO BE SP#1 #1 OR SP#2 UNO ON PLAN.
 - NAIL BUILT UP STUDS PER DETAIL W/37
 - MINIMUM BOLT EMBEDMENT:
5" EMBEDMENT FOR 1/2" ATR
6" EMBEDMENT FOR 5/8" ATR
8" EMBEDMENT FOR 7/8" ATR
 - IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS NOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT)
 - SEE WOOD CONSTRUCTION NOTE #4 ON COVER SHEET FOR CORROSION INFORMATION
 - SAME NOMINAL SIZE PARALLAM COLUMNS (L8E) MAY BE SUBSTITUTED FOR ANY P.T. SYP POST NOTED IN THE PLANS**

| COMMON NAIL VS. PNEUMATIC GUN NAILS: | | | | |
|--------------------------------------|--------------------------------|--------------------------------|-----------------------------|----------------------------------|
| COMMON NAIL | DIA. / LENGTH | PNEUMATIC GUN NAIL | COMMON VS. GUN NAIL | APPLICATION |
| 8d | 0.131" x 2 1/4" | 0.131" x 2 1/4" | SEE PLAN RING SHANK ON ROOF | SHEATHING ROOF & WALLS |
| 10d OR 12d | 0.148" x 3" 0.148" x 3 1/4" | 0.131" x 3" 0.131" x 3 1/4" | SEE PLAN | BLOCKING & TOE NAILS & TOP PLATE |
| 12d | 0.148" x 3 1/4" | 0.131" x 3 1/4" | 8" O.C. (COMMON) | STUD WALL CORNERS |
| 10d | 0.148" x 3" | 0.131" x 3" | 8" O.C. (COMMON) | STUD PACK COLUMNS |
| 16d | 0.162" x 3 3/4" | 0.131" x 3 3/4" | (2) 16d (COMMON) | SEE PLAN |

| BEAM SCHEDULE | | |
|---------------|--|---|
| MARK | BEAM SIZE | CONNECTIONS |
| BM1 | (2) - 2 x 8 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM2 | (2) - 2 x 10 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM3 | (2) - 2 x 12 #2 SYP W/ 7/16" OSB FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 12d NAILS @ 12" O.C. TYP EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM4 | (2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM5 | (2) - 1 3/4" x 11 7/8" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |
| BM6 | (2) - 1 3/4" x 16" LVL 2.0E Fb=2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE | CONNECTION: PROVIDE (2) SIMPSON LSTA24 OR (2) SIMPSON HTS20 TO WOOD POST OR (2) SIMPSON HETA16 TO CMU COL. U.N.O. ON ROOF PLAN. |

- ### GENERAL BEAM NOTES
- VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEYOND EACH END)
 - SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
 - BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.

| HEADER SCHEDULE | | |
|-----------------|---|---|
| MARK | HEADER SIZE | REMARKS |
| H1 | (2) - 2x6 #2 SYP W/ 1/2" FLUTCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H2 | (2) - 2x6 #2 SYP W/ 1/2" FLUTCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H3 | (2) - 2x10 #2 SYP W/ 1/2" FLUTCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H4 | (2) - 2X12 #2 SYP W/ 1/2" FLUTCH PLATE | SEE GENERAL HEADER NOTE #5 THIS SHEET |
| H5 | (2) - 1 3/4" x 11 1/4" LVL 2.0E Fb=2600 PSI | ATTACH TOGETHER W/ (2) ROWS 1/4" x 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE |
| H6 | (2) - 1 3/4" x 9 1/4" LVL 2.0E Fb=2600 PSI | ATTACH TOGETHER W/ (3) ROWS 1/4" x 3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EACH SIDE |

| HEADER SUPPORT NO. OF JACKS & STUDS REQ. AT OPENINGS | | | | | |
|--|----------|---------------|---------------|---------------|---------------|
| OPENING SIZE | 2x4 WALL | JACKS EA. END | KINGS EA. END | JACKS EA. END | KINGS EA. END |
| 1'-0" - 3'-11" | (1) | (2) | (1) | (2) | (2) |
| 4'-0" - 9'-11" | (2) | (3) | (2) | (2) | (2) |
| 10'-0" - 16'-0" | (3) | (4) | (3) | (4) | (4) |

- ### GENERAL HEADER NOTES
- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
 - IF HEADER IS ON THE 1st FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS UNO ON PLAN
 - IF HEADER IS ON THE 2nd FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.
 - ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL W/37
 - FASTEN ALL MULT-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" O.C. ALONG EACH EDGE OR (3) ROWS IF 2x10 OR LARGER.
 - FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d TOENAILS PER SIDE
 - IF HEADER IS NOT SPECIFIED CONTACT E.O.R.

| EXTERIOR 2ND FLOOR BEARING WALL SCHEDULE | | | | |
|--|------|---------|----------|--|
| HEIGHT | STUD | SPECIES | SPACING | |
| 8'-0" | 2x4 | SYP #2 | 16" O.C. | |
| 9'-0" | 2x4 | SYP #2 | 16" O.C. | |
| >9'-0" | 2x6 | SYP #2 | 16" O.C. | |

* WHEN THE TOP OF WALL IS GREATER THAN 9'-0", THEN AT EACH EXTERIOR CORNER WITHIN THE 4'-0" END ZONE, THE STUDS WILL BE DOUBLE STUDS @ 16" O.C. OR SINGLE STUDS @ 12" O.C.



THIS IS ONLY USED WITH PLASTER OR STUCCO EXTERIOR FINISH

** WALL SHEATHING 15/32" EXPOSURE 1 OR EQUIVALENT, REFER TO SHEATHING SCHEDULE FOR ATTACHMENTS. **

| | | |
|---|---|---|
| Y | N | MASTER BA. OPTIONS |
| | | 4030 (1) PG. FIBERGLASS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. DISC LT. |

OPT. MASTER BATH

SCALE: 1/4" = 1'-0"



2ND FLOOR PLAN

SCALE: 1/4" = 1'-0"

(ALL ELEVATIONS)

NOTE:
○ INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

WALL LEGEND

- FRAMED WALL
- BEARING FRAME WALL
- FRAMED WALL W/ BRICK VENEER
- FRAMED WALL W/ SIDING OR STUCCO

GENERAL NOTES

- R302.6 (table 302.6) If water based ceiling texture material is used, Provide 1/2" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. Note 1/2" sag-resistant gypsum board may be used I.L.O. 5/8" gypsum board. 5/8" type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/8" solid wood door, solid or honeycomb core steel door, or 20 Minute fire rated door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surfaces and any soffits protected on the enclosed side with 1/2" gypsum board.
- Outdoor swimming pools shall be provided with a barrier complying with R4501.1.7.1.1 through R4501.1.7.1.4.
- Bathroom exhaust fans must vent to the exterior of the building. Exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.
- R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than 5/8 inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below or the exterior of the building, the operable window shall comply with one of the following:
 - Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its retracted position.
 - Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
 - Operable windows that are provided with window opening control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
- EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces.
- M1502.4.5 Duct length
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3
M1502.3 Duct termination
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
- Porch Ceilings: (See plan for the following options)
Option 1: Gypsum:
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
The gypsum board shall be attached W/ Type "W" 1x4" drywall screws at 8" O.C. in field and edges.
Option 2: Plaster Base:
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.
- Energy Code Compliance Path is Performance Based Path Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING FURRING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

COUNTY SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:
2405

Plan/Issue Date:
Wednesday, March 19, 2025

KA PROJECT NUMBER:
25-02688

Sheet: **2.1** Of:

2nd FLOOR PLAN

COUNTY
SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 3333

100% Employee Owned
myTSGhome.com



FLORIDA CONTRACTORS' LICENSE NO. CRC1330146

100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 117

BLK:

SEC:

SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:

25-02688

Sheet:


5

Of:

ELEVATION - A

VENTILATION CALCULATION

| | |
|---|-----------------------|
| Soffit product provides | 4.12 net sq in / sf |
| Ridge vent provides | 18.00 net sq in / lf |
| Off ridge vent provides | 138.00 net sq in / sf |
| Overhang distance | 1.33 ft |
| S.F. of Area to be vented (SF) | 1335 s.f. |
| Total needed for exhaust for upper 1/3 | 320 net sq inches |
| Total needed for intake (soffit area, lower) | 320 net sq inches |
| Number of Off Ridge Vents for upper 1/3 needed | 2 |
| L.F. of Ridge Vent needed (can be used in combo with ORV) | 18 |
| Lineal Feet of Soffit needed to meet required | 58 |
| Lineal S.F. provided by plan | 191 |




LEFT ELEVATION "A"

SCALE: 1/4" = 1'-0"



REAR ELEVATION

SCALE: 1/4" = 1'-0"



RIGHT ELEVATION "A"

SCALE: 1/4" = 1'-0"



FRONT ELEVATION "A"

SCALE: 1/4" = 1'-0"



| | | |
|-------------|---|-----|
| TB05 | REQUIRED MINIMUM PERMANENT TRUSS BRACING PLAN | NTS |
|-------------|---|-----|

| | | | | |
|-------------------|---|---------|--|--|
| WIND | ENGINEERED ROOF PER ASCE 7-22 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft | | | |
| | WIND SPEED (ULTIMATE) | 130 MPH | | |
| | WIND SPEED (ALLOWABLE) | 101 MPH | | |
| EXPOSURE CATEGORY | | B | | |

| | | | | |
|-------------------------------|---------------------------------|--------|--------|--------|
| EFFECTIVE WIND AREA (SQ FEET) | WIND PRESSURE AND SUCTION (PSF) | | | |
| | (-) VALUE DENOTES SUCTION | | | |
| AREA | ROOF | 1 | 2 | 3 |
| 10 | HIP | -22.94 | -31.68 | -31.68 |
| | GABLE | -24.44 | -38.92 | -46.25 |

ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):


ZONE 1: ASTM F1667 RRSR-01 (8d) NAILS @ 6" O.C. ON EDGE & 6" O.C IN FIELD
ZONE 2: ASTM F1667 RRSR-01 (8d) NAILS @ 4" O.C. ON EDGE & 4" O.C IN FIELD
ZONE 3: ASTM F1667 RRSR-01 (8d) NAILS @ 4" O.C. ON EDGE & 4" O.C IN FIELD

ROOF SHEATHING:
SHINGLE: 7/16" EXP. 1 (²/₁₆) or 15/32" EXP. 1 (³/₁₆)
TILE: 15/32" EXP. 1 (³/₁₆)

NOTE:

- PER CODE ASTM F1667 RRSR-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS
- WHERE THE SHEATHING THICKNESS IS GREATER THAN 15/32", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RRSR-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RRSR-04 (3" x .120") NAILS
- GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C FIRST 4 BAYS WITH (2) 12d NAILS EA. END, ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE


HIP ROOF > 20 TO 27 DEG.
a=4ft [4:12] b=12ft [12:12]
GABLE ROOF > 20 TO 27 DEG.
[4:12] b=12ft [12:12]




WALL SHEATHING MAY BE INSTALLED VERTICALLY OR HORIZONTALLY, ATTACH PER RAILING SCHEDULE. PANEL EDGES WILL NEED TO BE ATTACHED TO STUD AND OR BLOCKING AT ALL EDGES. A MINIMUM SPACE IS RECOMMENDED BETWEEN PANELS AT EDGES AND END JOINTS TO ALLOW FOR EXPANSION. FASTENERS SHALL NOT PENETRATE SURFACE MORE THAN $\frac{1}{4}"$.

- | | |
|---|--|
| A | NAIL AT BASE 2 ROWS @ 4" O.C. w/ 8d COMMON NAIL. |
| B | NAIL AT TOP PLATE TWO ROWS @ 4" O.C. w/ 8d COMMON NAIL. |
| C | NAIL OPENING PERIMETER @ 2" ROWS @ 4" O.C. w/ 8d COMMON NAIL. |
| D | NAIL INTERIOR AT 12" O.C. w/ 8d COMMON NAIL. |
| E | STAGGER ALL VERTICAL JOINTS & NAIL @ 4" O.C. w/ 8d COMMON NAIL. |
| F | PLYWOOD SPLICES @ HEADER - NAIL SHEATHING TO HEADER w/ 8d COMMON NAILS @ 3" O.C. (2) ROWS @ TOP & BOTTOM. |
| G | (3) 8d NAILS @ 4" O.C. TO EACH TRUSS END OR VERTICAL MEMBER END. |
| H | FLOOR SHEATHING @ 12" PLYWOOD DECKING GLUED AND NAIL w/ 8d COMMON NAILS @ 4" O.C. AT EDGES OVERPRIOR NAIL FASTENERS. |


NOTE: 8d NAILS FOR WALL SHEATHING MUST BE MIN. .131" X 2 1/2".
DO NOT OVERDRIVE NAILS; FASTENERS SHALL NOT PENETRATE
SURFACE MORE THAN 1/8"




LOCAL HORIZONTAL WALL ELEVATION DIAGRAM



SINGLE NAIL EDGE SPACING




DOUBLE NAIL EDGE SPACING



SECTION X-X

AT ALL PANEL BLOCKING
LOCATIONS MIN 2 X 4 #2 SPF
TURNED VERTICAL W/ 7/16"
FLITCH PLATE TO W/ (2) 12d
TOENAILS EA. END, NAIL FLITCH
PLATE TO VERTICAL W/ (4) 8d
NAILS

(2) 8d NAILS @ 3" O.C.



ROOF PLAN "A" & "CR"

SCALE: 1/4" = 1'-0"

| SIMPSON - CONNECTOR SCHEDULE | | | | SYP - CONNECTOR SCHEDULE | | | |
|------------------------------|-----------------|---|------|--------------------------|---|------|------|
| MARK | TYPE | CONNECTOR & FASTENERS | SYP | SYP | CONNECTOR & FASTENERS | SYP | SYP |
| (A) | FRAME TO FRAME | HETATA or (9) 9d x 1 1/2" OR HETAD or (10) 9d x 1 1/2" | 1810 | 1810 | HTATA or (10) 9d x 1 1/2" OR HTAD or (10) 9d x 1 1/2" | 1585 | 1870 |
| (B) | FRAME TO FRAME | H2 x 5d x (10) 9d NALS | 615 | 700 | RTTA or (10) 9d NALS | 515 | 585 |
| (C) | FRAME TO FRAME | HT2 x 5d x (10) 9d x 1 1/2" OR HT2 x 5d x (10) 9d x 1 1/2" TRUSSES | 1065 | 1049 | RTT2 x 5d x (10) 9d x 1 1/2" OR RTT2 x 5d x (10) 9d x 1 1/2" TRUSSES | 865 | 1020 |
| (D) | FRAME TO FRAME | MT12 x 5d x (10) 1 1/2" x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 990 | 1080 | MT12 x 5d x (10) 1 1/2" x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 845 | 1165 |
| (E) | FRAME TO MASSWY | MT12 x 5d x (10) 1 1/2" x 1 1/2" EMBEDDED W/ SIMPSON "SET-30" EPOXY | 1330 | 1655 | MT12 x 5d x (10) 1 1/2" x 1 1/2" EMBEDDED W/ SIMPSON "SET-30" EPOXY | 1030 | 1485 |
| (F) | FRAME TO MASSWY | HT250 x 5d x (10) 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1215 | 1415 | HT250 x 5d x (10) 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1285 | 1535 |
| (G) | FRAME TO MASSWY | (2) HT250 x 5d x (10) 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 2430 | 2880 | (2) HT250 x 5d x (10) 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 2570 | 3030 |
| (H) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (I) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (J) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (K) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (L) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (M) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (N) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (O) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (P) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (Q) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (R) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (S) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (T) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (U) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (V) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (W) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (X) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (Y) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |
| (Z) | FRAME TO MASSWY | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 1075 | 1175 | HT2 x 5d x (10) 9d x 1 1/2" (AT EXTERIOR LOCATION) INCLUDE (4) 10d TENSILS | 930 | 1030 |

NOT USED

GENERAL CONNECTOR NOTES:

1. CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALLS / BEAMS w/ (2) 1x2 TOENAILS.
2. ALL TRUSS TO TRUSS CONNECTIONS ARE PROVIDED BY TRUSS MANUFACTURER, U.N.O. ON PLAN.
3. G.C. MAY USE EITHER SIMPSON OR USP CONNECTIONS. SEE FRAMING PLAN FOR CONNECTOR CALL OUT.
4. FOR SINGLE PLY TRUSSES, SCAB ON FULL HEIGHT SYP #1 2"x4" TO TRUSS VERTICAL WEB (2) ROIS OF 10d NAILS @ 3" O.C. STAGGERED.
5. 12" MIN. A.T.R. EMBEDMENT @ CMU BOND BEAM U.N.O.
6. SCAB TRUSS CHOHQ W/ 4" O" 2" SYP #2 (MATCH CHOHQ LUMBER SIZE) w/ (2) ROWS 10d @ 4" FROM END & 4" O.C. STAGGERED. CENTER AT CONNECTOR LOCATION AS MUCH AS POSSIBLE.

A MINIMAL CONNECTOR UNO ON FRAMING PLAN

1. CONNECTION FOR ALL ROOF / FLOOR TRUSSES TO MASONRY WALLS/LINTELS/ICF WALLS UNO ON PLAN
2. CONNECTION AT 24" OR 32" O.C. PENDING VERTICALS FOR ALL FLOOR TRUSSES PARALLEL TO MASONRY WALLS
3. CONNECTION FOR ALL HIP JACK (CORNER JACK) TO MASONRY WALLS/ICF WALLS/LINTELS
4. CONNECTION FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C. MAX. w/ (2) AT EACH CORNER. G.C. TO VERIFY LOCATION DOES NOT CONFLICT W/IT (IF APPLICABLE) LAYOUT
5. CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALLS/BEAMS w/ (2) 12d TONAILS

B MINIMAL CONNECTOR UNO ON FRAMING PLAN

- | | |
|---|---|
| 1. | CONNECTION FOR JACK TRUSS TO WOOD WALL OR BEAM |
| | MINIMAL CONNECTOR UNO ON FRAMING PLAN |
| 1. | CONNECTION FOR ALL TRUSSES TO INTERIOR/EXTERIOR BEARING WOOD WALLS AND/OR BEAMS |

ROOF FRAMING NOTES

1. SINGLE OR METAL ROOFING SYSTEM (SEE ARCH.) SHEATHING - SEE [RSH] SCHEDULE THIS SHT. FOR SHT-G FASTENERS ON PRE. ENGINEERED WOOD TRUSSES AT 2'-0" O.C. MAX. OR CONVENTIONAL FRAME ROOF (SEE PLAN FOR SIZE AND SPACING. SEE ARCHITECTURAL PLAN FOR TYPICAL ROOF SLOPE AND OTHER INFORMATION)
TILE ROOFING SYSTEM (SEE ARCH.) SEE [RSH] SCHEDULE THIS SHEET
2. THE EXTERIOR CEILING FOR THE ENTRIES AND PORCHES SHALL HAVE EITHER 7/16" OSB EXPOSURE 1 SHEATHING OR 1/2" GLASS. THE UNDERSIDE OF THE ROOF TRUSSES, ALL PANEL JOINTS ARE TO BE BLOCKED. BOLD WITH 2x4 #2 SP WITH (3) 2x4 TOWALS EACH END. THE SHEATHING IS TO BE NAILED WITH 8d NAILS AT 4" ON CENTER AT ALL EDGES AND THEN 8" ON CENTER IN FIELD
3. FOR UNDERLAYMENT REQUIREMENTS SEE R905.1.1.1


--- NOTE TO FRAMER ---

IF ROOF TRUSS LAYOUT SHOWS TRUSS I.D.'S, THIS LAYOUT HAS BEEN PROVIDED BY THE CLIENT/ DESIGNER OR ARCHITECT TO USE FOR THE DESIGN OF THIS PROJECT. OTHERWISE A GENERIC LAYOUT HAS BEEN DETERMINED. BUT PRIOR TO CONSTRUCTION OR TRUSS FABRICATION, FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS ARE TO BE SUBMITTED TO ENGINEER OF RECORD (E.O.R.) FOR REVIEW AND APPROVAL. AT THIS TIME THE E.O.R. IS RESPONSIBLE FOR THE REVIEW OF THE LAYOUT AND THE APPROVAL OF THE FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS. ADDITIONAL FEE'S MAY APPLY. STARTING CONSTRUCTION OR TRUSS FABRICATION PRIOR TO THIS REVIEW IS NOT ADVISED, AND THE E.O.R. IS NOT RESPONSIBLE FOR ADDITIONAL COSTS DUE TO REVISIONS OF THE PLAN. IF CONVENTIONAL FRAMING IS SHOWN, NO TRUSS APPROVAL IS REQUIRED, UNLESS LAYOUT IS REVISED W/OUT WRITTEN APPROVAL FROM FDS.

**SEE PLAN SET FOR TRUSS BRACING AND
ADDITIONAL ROOF INFORMATION**

| | | |
|-------------|---|--------|
| TB13 | WALL SHEATHING INSTALLATION AND NAILING SCHEDULES | N.T.S. |
|-------------|---|--------|


| | |
|--|------------|
| COUNTY SEAL | |
| To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal. | |
| CA No. 9161 | AA26003115 |
|  <p>TSG TOTAL SOLUTIONS GROUP 258 Southhall Lane, Suite 200 Maitland, Florida, 32751 (407) 880 2333</p> <p>100% Employee Owned myTSGhome.com</p> <p>DAMS HOMES</p> <p>FLORIDA CONTRACTORS LICENSE NO. CRC1330146</p> <p>100 WEST GARDEN STREET PENSACOLA FL 32502</p> <p>DIVISION LOCATION: GAINESVILLE</p> <p>INVENTORY</p> <p>LOT: 117 BLK: SEC: SUB: PRESERVE AT LAUREL LAKE 120 SW BELLFLOWER DR LAKE CITY</p> <p>Model Name / Number: 2405</p> <p>Plan Issue Date: Wednesday, March 19, 2025</p> <p>KA PROJECT NUMBER: 25-02688</p> <p>Sheet: S-1</p> <p>of:</p> <p>ROOF PLAN "A" & "CR"</p> | |
| Wednesday, March 19, 2025 | |




**SEE PLAN SET FOR TRUSS BRACING AND
ADDITIONAL ROOF INFORMATION**

CA No. 9161 AA26003115







TB15 EXTERIOR NON-BEARING WALL DETAIL N.T.S.




WC04 GARAGE HEADER ANCHOR 3/4" = 1'-0"




WC05 SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.



FB06 SECTION @ CORNER FRAMING 3/4" = 1'-0" STANDARD CORNER A-A




WC03 WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




CD11 COMMON BEAM ATTACHMENT N.T.S.

NOTE: @ ALL EXT. CONDITIONS ATTACH 2x STUDS TO TOP PLATE W/ (4) 16d TONAILS (2) ON EA. SIDE TYP. TOE NAILS MAY BE SUBSTITUTED W/ (1) SIMPSON H2.5A CONNECTOR @ EA. STUD TO TOP PLATE W/ 8d 2 1/2" x 0.131 NAILS




CD25 BEAM TO WALL CONNECTION N.T.S.




| CONNECTOR LEGEND | | WINDOW & DOOR JACK TABLE | |
|------------------|--|--|--|
| (A) | SIMPSON SPH4 W/ 12-10d x 1/2 | PROVIDE JACKS @ EACH END AS FOLLOWS | |
| (B) | (1) SIMPSON SDWC15600 @ 16" O.C. | (2) WHEN OPN'GS ARE GREATER THEN 4'-0" | |
| (C) | (2) SIMPSON SDWC15600 @ EACH SIDE OF HEADER FROM KING STUDS TO TOP PLATE & (2) SDWC15600 FROM JACK STUD TO HEADER. | (3) WHEN OPN'GS ARE GREATER THEN 10'-0" BUT LESS THAN 16'-0" | |
| (D) | SIMPSON SPH4 W/ 12-10d x 1 1/2" | NOTE: FOR EXTERIOR OR SHEAR WALL SEE SHEET S1 FOR WALL & ROOF SHEATHING INSTALLATION & NAILING SCHEDULES | |
| (E) | 1/2"x10" J-BOLT W/ 2"x2"x1/8" WASHER @ 32" O.C. PLUS (2) WITHIN 6" EACH SIDE OF JACK STUDS @ HEADER | | |


WF66 TYPICAL BEARING WALL N.T.S.




WC06 EXTERIOR FRAME CORNER 3/4" = 1'-0"



RD01 VALLEY FLASHING DETAIL N.T.S.




CD26 GIRDER BASE CONNECTION 1/2" = 1'-0"



WF68 CORNER CONNECTION N.T.S.

NOTE: @ ALL EXT. CONDITIONS ATTACH 2x STUDS TO TOP PLATE W/ (4) 16d TONAILS (2) ON EA. SIDE TYP. TOE NAILS MAY BE SUBSTITUTED W/ (1) SIMPSON H2.5A CONNECTOR @ EA. STUD TO TOP PLATE W/ 8d 2 1/2" x 0.131 NAILS



CD25 BEAM TO WALL CONNECTION N.T.S.

COUNTY SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELLFLOWER DR
LAKE CITY

Model Name / Number:


2405

Plan Issue Date:
Wednesday, March 19, 2025


KA PROJECT NUMBER:
25-02688

Sheet: **S-2** of:


TYPICAL FRAMING DETAILS




WF03 WALL SPLICE DETAIL 3/4" = 1'-0"




SG07 2 STORY COLUMN @ GIRDER N.T.S.




TB18 NON-BRG. EXT CMU WALL (FLOOR TRUSS) 3/4" = 1'-0"



WF39 TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



WF67 WALL FRAMING 3/4" = 1'-0"



WF09 WALL HEADER DETAIL N.T.S.

STAIR NOTES
STAIRWAY CONSTRUCTION SHALL CONFORM TO THE FBC-R (CURRENT EDITION) SECTIONS R311.7, R312 AND R302.7.

RISER HEIGHT:
THE RISER HEIGHT SHALL BE NOT MORE THAN 7 3/4 INCHES. THE RISER HEIGHT SHALL BE MEASURED VERTICALLY BETWEEN LEADING EDGES OF THE ADJACENT TREADS. THE GREATEST RISER HEIGHT WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH. RISERS SHALL BE VERTICAL OR SLOPED FROM THE UNDERSIDE OF THE NOSING OF THE TREAD ABOVE. OPEN RISERS ARE PERMITTED PROVIDED THAT THE OPENINGS LOCATED MORE THAN 30 INCHES, AS MEASURED VERTICALLY, TO THE FLOOR OR GRADE BELOW DO NOT PERMIT THE PASSAGE OF A 4-INCH DIAMETER SPHERE.

TREAD DEPTH:
THE TREAD DEPTH SHALL BE NOT LESS THAN 10 INCHES. THE TREAD DEPTH SHALL BE MEASURED HORIZONTALLY BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AND AT A RIGHT ANGLE TO THE TREAD'S LEADING EDGE. THE GREATEST TREAD DEPTH WITHIN ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH.

WINDERS:
WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 10 INCHES MEASURED BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AT THE INTERSECTIONS WITH THE WALKLINE. WINDER TREADS SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 6 INCHES AT ANY POINT WITHIN THE CLEAR WIDTH OF THE STAIR.


NOSINGS:
NOSINGS AT TREADS, LANDINGS AND FLOORS OF STAIRWAYS SHALL HAVE A RADIUS OF CURVATURE AT THE NOSING NOT GREATER THAN 9/16 INCH OR A BEVEL NOT EXCEEDING 1/2 INCH. A NOSING PROJECTION NOT LESS THAN 3/4 INCH AND NOT MORE THAN 1 1/4 INCHES SHALL BE PROVIDED ON STAIRWAYS. THE GREATEST NOSING PROJECTION SHALL NOT EXCEED THE SMALLEST NOSING PROJECTION BY MORE THAN 3/8 INCH WITHIN A STAIRWAY.

HANDRAILS:
HANDRAILS SHALL BE PROVIDED ON NOT LESS THAN ONE SIDE OF EACH FLIGHT WITH FOUR OR MORE RISERS. HANDRAIL HEIGHT MEASURED VERTICALLY FROM THE SLOPED PLANE ADJOINING THE TREAD NOSING, OR FINISH SURFACE OF RAMP SLOPE, SHALL BE NOT LESS THAN 34 INCHES AND NOT MORE THAN 38 INCHES. HANDRAILS FOR STAIRWAYS SHALL BE CONTINUOUS FOR THE FULL LENGTH OF THE FLIGHT, FROM A POINT DIRECTLY ABOVE THE TOP RISER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOWEST RISER OF THE FLIGHT. HANDRAIL ENDS SHALL BE RETURNED OR SHALL TERMINATE IN NEWEL POSTS OR SAFETY TERMINALS. HANDRAILS ADJACENT TO A WALL SHALL HAVE A SPACE OF NOT LESS THAN 1 1/2 INCHES BETWEEN THE WALL AND THE HANDRAILS.

GRIP-SIZE:
HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF NOT LESS THAN 1 1/4 INCHES AND NOT GREATER THAN 2 INCHES OR PROVIDE EQUIVALENT GRASPABILITY IN COMPLIANCE WITH SECTION R311.7.B.3.


GUARDS:
GUARDS SHALL BE PROVIDED FOR THOSE PORTIONS OF OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, RAMPS AND LANDINGS, THAT ARE LOCATED MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW AT ANY POINT WITHIN 24 INCHES HORIZONTALLY TO THE EDGE OF THE OPEN SIDE. REQUIRED GUARDS AT OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, PORCHES, BALCONIES OR LANDINGS, SHALL BE NOT LESS THAN 36 INCHES IN HEIGHT AS MEASURED VERTICALLY ABOVE THE ADJACENT WALKING SURFACE OR THE LINE CONNECTING THE LEADING EDGES OF THE TREADS. REQUIRED GUARDS SHALL NOT HAVE OPENINGS FROM THE WALKING SURFACE TO THE REQUIRED GUARD HEIGHT THAT ALLOW PASSAGE OF A SPHERE 4 INCHES IN DIAMETER.

UNDER-STAIR PROTECTION:
ENCLOSED SPACE UNDER STAIRS THAT IS ACCESSED BY A DOOR OR ACCESS PANEL SHALL HAVE WALLS, UNDER-STAIR SURFACE AND ANY SOFFITS PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH GYPSUM BOARD.



INTERIOR STAIR SECTION

N.T.S.



SD04 GENERAL LANDING FRAMING INFO. N.T.S.

COUNTY
SEAL

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com



FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY
LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELLFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:


25-02688

Sheet: S-2.1 of:


TYPICAL FRAMING
DETAILS

Wednesday, March 19, 2025


SG01 GIRDER/COLUMN @ 2ND FLR w/HIGH BM N.T.S.




SH05 HEADER CONNECTION @ 2ND FLOOR w/ HIGH BEAM




WF69 WALL @ 2ND FLOOR N.T.S.




18 FLOOR CONNECTION N.T.S.




FB12 BLOCKING DETAIL 3/4\" = 1'-0"




WS06 FLOOR ATTACHMENT DETAIL 3/4\" = 1'-0"




WF70 CANTELIVER FLOOR SECTION N.T.S.




WF65 LOW ROOF TO SECOND FLOOR CONN. N.T.S.




WF71 KNEEWALL AT DORMER N.T.S.




SH07 ALTERNATE HEADER CONDITIONS N.T.S.



WF06 2 STORY INTERIOR BEARING WALL N.T.S.



WS04 TYPICAL TWO STORY WALL SECTION 3/4\" = 1'-0"



COUNTY SEAL

CA No. 9161

AA26003115

TOTAL SOLUTIONS GROUP

258 Southhall Lane, Suite 200

Maitland, Florida, 32751

(407) 880 2333

100% Employee Owned

myISGhome.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET

PENSACOLA FL 32502

DIVISION LOCATION:

GAINESVILLE

Job Information:

INVENTORY

LOT: 117

BLK: SEC:

SUB: PRESERVE AT LAUREL LAKE

120 SW BELFLOWER DR

LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:

25-02688


Sheet:

S-3.1


Of:

TYPICAL WALL DETAILS

Wednesday, March 19, 2025




TB01 TYPICAL CROSS BRACING DETAIL N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL N.T.S.

THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.




CH01 TYPICAL CHIMNEY FRAME DETAIL 3/4" = 1'-0"


| RAFTER SIZE | |
|----------------|----------------------------------|
| 0'-8" SPAN - | 2"x6" W/4-12d EACH END |
| 8'-12" SPAN - | 2"x8" W/4-12d EACH END |
| 12'-15" SPAN - | 2"x10" W/ SIMPSON A 34 @ EA. END |
| 15'-18" SPAN - | 2"x12" W/ SIMPSON A 34 @ EA. END |




TB17 CONV. FRAMING & VALLEY FRAMING N.T.S.




TB03 HIP / RIDGE BLOCKING DETAIL N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP) N.T.S.






GE04 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING 3/4" = 1'-0"





WF05 DORMER FRAMING DETAIL N.T.S.

TRUSS NOTES:

1. WOOD TRUSS ERECTOR SHALL PROVIDE BRACING ACCORDING TO ANSI/TPI-2014 (TRUSS PLATE INSTITUTE) NOTE THAT THE COMBINED WIND AREA IS GREATER BEFORE THE ROOF SHEATHING IS APPLIED, AND BRACING SHALL THEREFORE BE INSTALLED AS THE TRUSSES ARE ERECTED. INADEQUATE BRACING IS THE MOST COMMON CAUSE OF ACCIDENT IN WOOD TRUSS CONSTRUCTION. FULL BUNDLES OF SHEATHING SHALL NOT BE PLACED ON TRUSSES. THIS CONSTRUCTION LOAD SHOULD BE LIMITED TO 8 SHEETS OF SHEATHING ON ANY PAIR OF TRUSSES & SHALL BE LOCATED ADJACENT TO THE SUPPORTS. NO EXCESS CONCENTRATION OF ANY CONSTRUCTION MATERIAL (SUCH AS GRAVEL OR SHINGLES) SHALL BE PLACED ON THE TRUSSES IN ANY ONE AREA THEY SHALL BE SPREAD OUT EVENLY OVER A LARGE AREA SO AS TO AVOID OVERLOADING ANY ONE TRUSS.
2. ALL BRACING (DB,CB,BB) SHOWN ABOVE SHALL BE IN ADDITION TO CONTINUOUS LATERAL BRACING SPECIFIED BY THE TRUSS MANUFACTURER. ALL LATERAL BRACING SPECIFIED BY TRUSS MANUF. SHALL HAVE ADDITIONAL DIAGONAL BRACES AT 20'-0" O.C. MAXIMUM.
3. ALL BRACES SHALL BE 2x4 NOMINAL DIMENSION LUMBER & SHALL BE ATTACHED W/ (3) 12d NAILS AT EACH TRUSS INTERSECTION.
4. ADDITIONAL BOTTOM CHORD BRACING SHALL BE INSTALLED AS REQUIRED BY TRUSS DESIGN WHEREVER ADEQUATE STRUCTURAL CEILING ARE NOT ATTACHED DIRECTLY TO THE BOTTOM CHORD OF THE TRUSS.
5. PROVIDE TRUSS BLOCKING AT ALL TRUSS BEARING SUPPORTS WHERE TRUSS DEPTH EXCEEDS STANDARD HEEL HEIGHT. SEE TYP. TRUSS BLOCKING DETAILS.




SECTION B-B



A-A ALTERNATE BLOCKING DETAIL @ INTERIOR BEARING


TYP. WOOD TRUSS BLOCKING @ RAISED HEEL DETAIL

TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS 3/4" = 1'-0"



GENERAL NOTES
1. SEE SH07/D4 FOR ALT. CONDITION

SH00 HEADER CONNECTION @ 2ND FLOOR 3/4" = 1'-0"



WF05 WALL SPICE DETAIL 3/4" = 1'-0"

COUNTY
SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.
CA No. 9161 AA26003115



TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 880 2333

100% Employee Owned
myTSGhome.com

DAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330148
100 WEST GARDEN STREET
PENSACOLA FL 32502

DIVISION LOCATION:
GAINESVILLE

Job Information:

INVENTORY

LOT: 117
BLK:
SEC:
SUB: PRESERVE AT LAUREL LAKE
120 SW BELFLOWER DR
LAKE CITY

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:


25-02688

Sheet:


S-4

Of:


ROOF FRAMING
AND BRACING DETAILS




GE05 GABLE END BRACING - FRAME WALL N.T.S.




GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




GE24 GABLE @ VAULT N.T.S.




WF72 LEDGER N.T.S.




WF73 KNEEWALL @ DORMER N.T.S.




GE21 SECTION @ DUTCH GABLE 3/4"=1'-0"




LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.




GE23.1 GABLE END OVERHANG 1/2"=1'-0"



SR01 SECTION AT SHED ROOF 3/4"=1'-0"



GE16 SECTION @ HIP GABLE SCALE: 3/4"=1'-0"



COUNTY SEAL

Wednesday, March 19, 2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

CA No. 9161 AA26003115

TS&G

CA No. 9161 AA26003115

Making Dreams Come True

TOTAL SOLUTIONS GROUP

258 Southhall Lane, Suite 200

Maitland, Florida, 32751

(407) 880 2333

100% Employee Owned

myTS&Ghome.com

DAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET

PENSACOLA FL 32502

DIVISION LOCATION:

GAINESVILLE

Job Information:

Model Name / Number:

2405

Plan Issue Date:

Wednesday, March 19, 2025

KA PROJECT NUMBER:

25-02688

Sheet: S-4.1 Of:

INVENTORY

LOT: 117

BLK: SEC:

SUB: PRESERVE AT LAUREL LAKE

120 SW BELFLOWER DR

LAKE CITY

ROOF FRAMING AND BRACING DETAILS

