

## Columbia County, FL. Building & Zoning **Culvert Permit** #000038764



**OWNER: JOHN & ELIZABETH HARRISON** ADDRESS:

**PHONE:** 386.365.9220 DATE ISSUED: October 17, 2019 809 NW MILO TER LAKE CITY, FL32055

PARCEL ID: 08-3S-16-02032-107 **ACRES: 5.01** 

SUBDIVISION: HILLS OF HUNTSVILLE LOT: 7 BLK: PHASE:

**ZONING**: AGRICULTURE - 3 A-3 FLOOD ZONE: X Latitude: 30.238839 Longitude: -82.727415

CONTRACTOR

**PHONE:** 386.365.8685 NAME: SARA E GRESHAM

336 NW CORWIN GLN BUSINESS: JOHN NORRIS LAKE CITY, FL 32055 LICENSE: CRC1331978 -

PROJECT DETAILS

**BUILDING PERMIT #:** 

38763

STANDARDS:

Shall conform to Public Works Determinations as stated below

REQUIREMENTS:

Install min, 32 ' × 18 " corr metal culvert w / concrete mitred ends, w / 6 " × 6 " welded wire, rebar or culvert bolts in mitred ends, concrete mitred ends W -3ft × L -4ft, with 4"of limerock on top cover.

Notice: in addition to the requirements of this permit, there may be additional restrictions applicable to this property that may be found in the public records of this county. The issuance of this permit does not waive compliance by permittee with deed restrictions. Notice: all other applicable state or federal permits shall be obtained before commencement of this permitted development.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

Every permit issued shall become invalid unless the work authorized by such permit is commenced within 180 days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time the work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous inspection.