









Floor Plan  
SCALE: 1/4" = 1'-0"

| EXISTING AREA SCHEDULE |             |
|------------------------|-------------|
| NAME                   | AREA        |
| Conditioned Space      | 960 sq ft.  |
| Total                  | 1658 sq ft. |

| ADDITION AREA SCHEDULE |            |
|------------------------|------------|
| NAME                   | AREA       |
| Conditioned Space      | 531 sq ft. |
| Porch                  | 234 sq ft. |
| Total                  | 765 sq ft. |

| NEW TOTAL AREA SCHEDULE |             |
|-------------------------|-------------|
| NAME                    | AREA        |
| Conditioned Space       | 1491 sq ft. |
| Total                   | 2423 sq ft. |




CONCRETE / MASONRY / METALS GENERAL NOTES:


1. DESIGN SOIL BEARING PRESSURE: 1000 P&F.
2. EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PERFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
3. CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING GD. SHALL BE PLACED IN 12" LIFTS. BOTH SUB-SOIL AND FILL COMPACTION SHALL BE NOT LESS THAN 98% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 1500 SF OF BUILDING PAD AREA, OR FRACTION THEREOF, FOR EACH 12" LIFT.
4. REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIREMENTS OF ASTM A615, ALL BENDS SHALL BE MADE COLD.
5. WELDED WIRE MESH SLAB REINFORCING SHALL MEET THE REQUIREMENTS OF ASTM A185 - MIN. YIELD STRESS = 85 KSI.
6. CONCRETE SHALL BE STANDARD MIX F'c = 3000 PSI FOR ALL FTG, SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX F'c = 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACEMENT. MIXING, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
7. CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH - F'm = 1500 PSI.
8. MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
9. STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH, BOLTS SHALL BE ASTM A307 / GRADE I OR A325, AS PER PLAN REQUIREMENTS.
10. WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.

EXTERIOR WALL SHEATHING:  
APPLY VERTICALLY, "Windstorm" 7/16" OSB 48" X 91", 109", 121" OR 145" SHEATHING. FASTEN TO THE TOP PLATE AND THE SILL PLATE WITH EITHER 6d RING SHANK NAILS @ 3" O.C. OR 8d RING SHANK NAILS @ 4" O.C. FASTEN TO EACH STUD WITH EITHER 6d RING SHANK NAILS @ 6" O.C. OR 8d R.S. NAILS @ 8" O.C.


NOTE:  
ADDED FILL SHALL BE APPLIED IN 8" LIFTS - EA. LIFT SHALL BE COMPACTED TO 98% DRY COMPACTION PER THE "MODIFIED PROCTOR" METHOD.



SECTION A  
SCALE: NONE



SECTION B  
SCALE: NONE




4" SMOOTH STEELED TROWLED CONC. SLAB, W/ FIBERMESH REINFORCING, OVER 6 MIL PLASTIC SHEETING, ON CLEAN, WELL COMPACTED SAND FILL, TERMITE TREATED  
NOTE:  
LAP EDGES OF 6 MIL VAPOR BARRIER MIN. 6" - SEAL ALL JOINTS, TEARS AND PIPING PENETRATIONS WITH DUCT TAPE

2X4 P/T WOOD SILL, CONT., ALL AROUND, W/ 1/2" A.B. W/ 2" SQ. X 1/4" PLATE WASHERS WITHIN 8" FROM EACH CORNER, EA. WAY, 4" WITHIN 8" FROM ALL WALL OPENINGS / ENDS - 1/2" A.B. W/ 2" SQ. WASHERS ALONG EACH RUN @ 48" O.C., MAX. - ALL ANCHOR BOLTS SHALL HAVE A MINIMUM OF 1" EMBEDMENT INTO THE CONCRETE. (1/2" THREADED ROD MAY BE USED IN PLACE OF ANCHOR BOLTS)

NOTE:  
PRIOR TO THE CONSTRUCTION OF THE FOUNDATION, THE CONTRACTOR SHALL COORDINATE ANY INTERIOR BEARING LOCATION CONDITIONS PER THE TRUSS ENGINEERED SHOP DRAWINGS WITH THE FOUNDATION PLAN. ANY INTERIOR BEARING LOCATIONS OR ANY POINT LOADS OF 4.0 K OR GREATER SHALL BE SUPPORTED VIA A MODIFIED FOUNDATION PLAN TAKING THESE LOADS INTO CONSIDERATION. THE CONTRACTOR SHALL MAKE THE ENGINEERED TRUSS SHOP DRAWINGS AVAILABLE TO THE ARCHITECT FOR THE PURPOSE OF RENDERING SUCH MODIFICATIONS PRIOR TO FORMING ANY CONCRETE.

ONE KING STUD UP TO 50" OF OPENING WIDTH, OVER 50", MIN. TWO KING STUDS  
ONE JACK STUD UP TO 40" OF OPENING WIDTH, OVER 40", MIN. TWO JACK STUDS



PROVIDE A 10"x20" CONT. CONCRETE FOOTING W/ 2 #5 REBAR, BOTTOM 4 WIRE CHAIRS @ 48" O.C. - UNDER ALL PORCH PERIMETER OR SEE OPTIONAL MONOLITHIC DETAIL

CONSTRUCTION NOTES

1. FIELD VERIFY ALL DIMENSIONS AND MATERIALS. ALL OUTSIDE DIMENSIONS ARE TO FACE OF FOUNDATION.
2. ALL NAILING CONSTRUCTION MATERIALS SHALL BE AS PER 2001 FBC - SEE A.6
3. PROVIDE EXTERIOR COMBUSTION AIR TO GAS FIRED H.V.A.C. EQUIPMENT, WOOD BURNING STOVES, AND FIREPLACES.
4. VENT CLOTHES DRYER, BATH, AND COOKING FANS TO EXTERIOR AS REQUIRED.
5. CONTRACTOR SHALL CALL ATTENTION TO THE DESIGNER, ANY DISCREPANCIES IN DRAWINGS AND/OR SPECIFICATIONS AND SHALL RECEIVE INSTRUCTIONS OR CLARIFICATIONS BEFORE PROCEEDING WITH THE PORTION OF THE WORK IN QUESTION.
6. ROOF 1 FLOOR TRUSS FRAMING PLANS ARE FOR GENERAL INFORMATION ONLY. THE TRUSS MANUFACTURER SHALL PROVIDE A DETAILED LAYOUT FOR TRUSS AND FRAMING MEMBERS.
7. SHOULD CONDITIONS AT THE SITE BE FOUND MATERIALLY DIFFERENT FROM THOSE INDICATED BY THE DRAWINGS AND/OR SPECIFICATIONS, AND THE CONDITIONS USUALLY INHERENT IN THE WORK OF THE CHARACTER SHOWN AND SPECIFIED BE DIFFERENT FROM THE DESIGNER'S RECOMMENDED BUILDING PROCEDURES, CALL IMMEDIATE ATTENTION TO SUCH CONDITIONS BEFORE PROCEEDING.
8. LP GAS-BURNING APPLIANCES ARE NOT PERMITTED IN BASEMENTS OR CRAWLSPACES.
9. DO NOT SCALE DRAWINGS. USE PRINTED DIMENSIONS ONLY.

CUSTOM RESIDENTIAL DESIGN for:

FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

DRAWN BY:

DATE: Monday, March 8, 2021

SECTION LETTER

PAGE NUMBERS

APPROVED:

CHECKED BY:

PAGE:

3/7

A3

Bradley Franks Construction, LLC  
PHONE: 386-755-2455  
FAX: info@bradleyfranks.com  
257 SW Hudson in Lake City, FL 32025

SOFTPLAN  
ARCHITECTURAL DESIGN SOFTWARE

Tompkins Addition  
PHONE: FAX:

REVISION: 26 SEP 2016

Copyright 2016 N.P. Geisler, Architect

DRAWN: npg

Celebrating 48 Years of Service  
1972 - 2020  
N.P. Geisler, Architect  
AR0001005

NICHOLAS GEISLER ARCHITECT  
NCA&S, Certified  
199 W. Brown Rd. Lake City, FL 32025  
813-523-4335

DATE: 21 DEC 2016

COM: 2K1693

SHEET: A.6

6 OF 9

NOTE:  
PLUMBING CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL PLUMBING WORK, INCLUDING ALL PLUMBING LINE LOCATIONS AND RISER DIAGRAM - CONTR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER AND 1 COPY TO THE PERMIT ISSUING AUTHORITY.

NOTE:  
H.V.A.C. CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL H.V.A.C. WORK, INCLUDING ALL DUCTWORK LOC., SIZES, LINES, EQUIPMENT SCH. 4 BALANCING REPORT - CONTR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER 4 1 COPY TO THE PERMIT ISSUING AUTHORITY.

SHEAR WALL SEGMENTS, SEE A.6 (ALL EXT. WALLS, LESS DOOR OPENINGS)

NOTE:  
THE DESIGN WIND SPEED FOR THIS PROJECT IS 130 MPH PER 2011 FBC 1603 AND LOCAL JURISDICTION REQUIREMENTS

16 Mar 2021  
AR0001005



| AFFILIATION                  | MANUF/R/MODEL                  | CAP.      |
|------------------------------|--------------------------------|-----------|
| TRUSS TO WALL:               | SIMPFON H2.5a                  | 750*      |
| GIRDER TRUSS TO POST/HEADER: | SIMPFON LGT, W/ 28 - 16d NAILS | 1185*     |
| HEADER TO KING STUD(S):      | SIMPFON S722                   | 1370*     |
| PLATE TO STUD:               | SIMPFON SP2                    | 1065*     |
| STUD TO BILL:                | SIMPFON SP1                    | 585*      |
| POST TO KING BEAM TO POST:   | BOLT THRU W/ 2-5/8" BOLTS      | 1700*     |
| PORCH POST TO FND.:          | SIMPFON AB666                  | 2300*     |
| MISC. JOINTS                 | SIMPFON A34                    | 315*/240* |


NOTE:  
"SIMPSON" PRODUCT APPROVALS:  
MIAMI/DADE COUNTY REPORT #97-0107.05, #96-1126.11, #99-0623.04  
SBCCI NER-443, NER-393

1. TEMPORARY BRACING OF THE STRUCTURE DURING ERECTION, REQUIRED FOR SAFE AND STABLE CONSTRUCTION, SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR SO ENGAGED. TEMPORARY & PERMANENT BRACING OF ROOF TRUSSES SHALL BE AS PER THE STANDARD GUIDELINES OF THE "TRUSS PLATE INSTITUTE".
2. ALL TRUSSES SHALL BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER & SHALL BE SIGNED AND SEALED BY SAME. TRUSS DESIGN SHALL INCLUDE PLACEMENT PLANS, TRUSS DETAILS, TRUSS TO TRUSS CONNECTIONS & THE STANDARD SPECIFICATIONS & RECOMMENDATIONS OF INSTALLATION OF THE "TRUSS PLATE INSTITUTE".
3. WOOD STUDS IN EXTERIOR WALLS & INTERIOR BEARING WALLS SHALL BE NOT LESS THAN №2 HEM-FIR OR BETTER.
4. CONNECTORS FOR WOOD FRAMING SHALL BE GALVANIZED METAL OR BLACK METAL AS MANUFACTURED OR AS CALLED FOR IN THE PLANS AND BE OF A DESIGN SUITABLE FOR THE LOADS AND USE INTENDED. REFER TO THE JOINT REINFORCEMENT SCHEDULE FOR PRINCIPLE CONNECTIONS.

1. TRUSSES SHALL BE DESIGNED BY A LICENSED ENGINEER, AND IN ACCORDANCE WITH THE REQUIREMENTS OF THE "NATIONAL FOREST PRODUCTS ASSOCIATION" MANUAL FOR "STRESS RATED LUMBER AND ITS CONNECTIONS", LATEST Ed., ALONG W/ THE "TRUSS PLATE INSTITUTE" SUGGESTED GUIDELINES FOR TEMPORARY AND PERMANENT BRACING, AND HANDLING OF TRUSSES. TRUSS SHOP DRAWINGS SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, DETS, & TRUSS TO TRUSS CONNECTIONS.
2. TRUSS SHOP DRAWINGS SHALL BE SIGNED & SEALED BY THE DESIGNING ENGINEER.


**NOTE:**  
ALL PENETRATIONS OF THE TOP PLATE OF ALL LOAD BEARING WALLS SHALL BE SEALED WITH FIRE RETARDANT CAULKING, INCLUDING WIRING, PLUMBING OR OTHER SUCH PENETRATIONS. WALLS OVER 8'-0" TALL SHALL HAVE CONTINUOUS BLOCKING TO LIMIT CAVITY HEIGHT TO 8'-0". PENETRATIONS THROUGH SUCH BLOCKING SHALL BE TREATED IN THE SAME MANNER AS TOP PLATES, NOTED ABOVE

**NOTE:**  
ALL UPLIFT CONNECTORS SHALL BE FIELD ADJUSTED TO MATCH  
OR EXCEED THE DEVELOPED LOADS PER ENGINEERED TRUSS  
SHOP DRAWINGS



## SCALE: NONE

D



SCALE: 1/4" = 1'-0"

DBL. 2X12 SYP Nr. 2 BEAM, w/ 1/2" PLYWOOD  
FLITCH PLATE - ASSEMBLE AS PER DETAIL -  
ON SHEET A.8 - EA. PORCH (2 LOCATIONS)  
or Bolt-Thru w/ 2- 5/8 Carriage Bolts

SHOP DRUG COORDINATION THE TRUSS ANCHOR STRAPS AS INDICATED IN THE CONSTRUCTION DOCUMENTS ARE SUGGESTED. STRAPS AND THE TRUSS ENGINEERED SHOP DRAWING LOADS TAKE PRECEDENCE OVER THAT INDICATED IN THE CONSTRUCTION DOCUMENTS.

THE UPLIFT LOADS INDICATED FOR EACH TRUSS IN THE ENGINEERED TRUSS SHOP DRAWINGS MAY BE MATCHED TO STANDARD PRODUCT UPLIFT RATINGS FOR COMPARABLE UPLIFT CONNECTORS, AND THAT THE PRODUCTS THAT PROVIDE EQUAL OR GREATER UPLIFT RESISTANCE FOR THE LISTED LOADS MAY BE USED IN LIEU OF THOSE INDICATED IN THE CONSTRUCTION DOCUMENTS OR AS APPROVED BY THE BUILDING OFFICIAL.

THE CONTRACTOR SHALL COORDINATE THE TRUSS TO TRUSS ANCHOR REQUIREMENTS WITH THE TRUSS ENGINEERING SHOP DRAWINGS. SOME OF THE TRUSS TO TRUSS CONNECTIONS WILL REQUIRE ANCHOR STRAPS IN ADDITION TO TYPICAL NAILING. ANCHOR DEVICES SHALL BE REQUIRED FOR ALL JOINTS WITH AN UPLIFT OR GRAVITY LOAD OF 100 LBS OR GREATER.

TRUSSES BEARING ON INTERIOR PARTITIONS WHERE UPLIFT LOADS ARE PRESENT SHALL REQUIRE ANCHORS OF EQUAL OR GREATER LOAD CAPACITY THAN THAT INDICATED BY THE TRUSS SHOP DRAWINGS. THE UPLIFT ANCHOR SYSTEM SHALL BE CONTINUOUS TO THE FOUNDATION.

**NOTE:**  
SHEATH ROOF W/ 1/2" CDX PLYWOOD PLACED  
W/ LONG DIMENSION PERPENDICULAR TO THE  
ROOF TRUSSES, SECURE TO FRAMING W/ 8d RING  
SHANK NAILS - AS PER DETAIL N ON SHEET A.7

**NOTE:**  
THE DESIGN WIND SPEED FOR THIS  
PROJECT IS 130 MPH PER 2011 FBC 1609  
AND LOCAL JURISDICTION REQUIREMENTS

**NOTE!**  
REFER TO THE WINDOW/DOOR HEADER  
SCHEDULE ON SHEET A.1 FOR ALL  
MINIMUM SIZE HEADERS AND ALTERNATES  
MINIMUM SIZE ALLOWABLE IS 2-2X12

R-1 ALL ROOF PITCH 7 / 12, U.N.O.

R-2 ALL OVERHANG 20"  
UNLESS OTHERWISE NOTED

R-3 PROVIDE ATTIC VENTILATION IN ACCORDANCE WITH SCHEDULE ON A.6

R-4 MOVE ALL VENTS AND OTHER ROOF PENETRATIONS TO REAR

DRAWN: 

CUSTOM RESIDENTIAL DESIGN for:

ROOF PLAN

SCALE: 1/4" = 1'-0"

Bradley Franks Construction, LLC

COMM: 2K1699

SHEE

A.8  
8 OF 9

**Tompkins**  
**Addition**

ONE:  
EAY:

A circular logo is shown. The left half of the circle contains the letter 'A', and the right half contains the number '11'. An arrow points from the text 'SECTION LETTER' to the 'A'. Another arrow points from the text 'PAGE NUMBERS' to the '11'.

## CONCLUSION


GE  
MPC

PAGE:

A.4


A.4






Floor Plan - ELECTRICAL  
SCALE: 1/4" = 1'-0"






**Girder Truss Column DET.**  
SCALE: 1/2" = 1'-0"



**TYP. PERMANENT TRUSS BRACING DIA.**  
NTS  
NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

**Truss Bracing DETAILS**  
SCALE: AS NOTED




**Shear Wall DETAILS**  
SCALE: NONE


- SHEARWALL NOTES:**
1. ALL SHEARWALLS SHALL BE TYPE 2 SHEARWALLS AS DERIVED BY STD 10-91 SBCG 305-4.3.
  2. THE WALL SHALL BE ENTIRELY SHEATHED WITH 1/16" O.S.B. INCLUDING AREAS ABOVE AND BELOW OPENINGS.
  3. ALL SHEATHING SHALL BE ATTACHED TO FRAMING ALONG ALL FOUR EDGES WITH JOINTS FOR ADJACENT PANELS OCCURRING OVER COMMON FRAMING MEMBERS OR ALONG BLOCKING.
  4. NAIL SPACING SHALL BE 4" O.C. EDGES AND 8" O.C. IN THE FIELD.
  5. TYPE 2 SHEARWALLS ARE DESIGNED FOR THE OPENING IT CONTAINS. MAXIMUM HEIGHT OF OPENING SHALL BE 8/16 TIMES THE WALL HEIGHT. THE MINIMUM DISTANCE BETWEEN OPENINGS SHALL BE THE WALL HEIGHT/3.5 FOR 8'-0" WALLS (2'-3").
  6. ALL THREAD ROD MAY BE DELETED WHEN HEADER PLAT STRAPS USED- M6TA24.

| OPENING WIDTH  | SILL PLATES        | 16d TOE NAILS EACH END |
|----------------|--------------------|------------------------|
| UP TO 6'-0"    | (1) 2x4 OR (1) 2x6 | 1                      |
| > 6' TO 8'-0"  | (3) 2x4 OR (1) 2x6 | 2                      |
| > 8' TO 12'-0" | (8) 2x4 OR (2) 2x6 | 3                      |

| NAILING ZONE | SHEATHING TYPE | FASTENER                                        | SPACING                                                                        |
|--------------|----------------|-------------------------------------------------|--------------------------------------------------------------------------------|
| 1            | 1/16" O.S.B.   | 8d COMMON OR 8d HOT DIPPED GALVANIZED BOX NAILS | 6 in. o.c. EDGE<br>12 in. o.c. FIELD                                           |
| 2            | OR 15/32 CDX   |                                                 | 6 in. o.c. EDGE<br>6 in. o.c. FIELD                                            |
| 3            |                |                                                 | 4 in. o.c. GABLE TRUSS OR GABLE ENDWALL<br>6 in. o.c. EDGE<br>6 in. o.c. FIELD |



**ROOF SHEATHING NAILING ZONES (GABLE ROOF)**





**ROOF SHEATHING NAILING ZONES (HIP ROOF)**


**Roof Nail Pattern DET.**

SCALE: NONE


| HEADER SPANS FOR EXTERIOR BEARING WALLS |             |                     |     |        |   |
|-----------------------------------------|-------------|---------------------|-----|--------|---|
| HEADERS SUPPORTING:                     | HEADER SIZE | BUILDING WIDTH (FT) |     |        |   |
|                                         |             | 20'                 | 28' | 36'    |   |
| ROOF, CEILING                           | 2-2x4       | 3'-6"               | 1   | 3'-2"  | 1 |
|                                         | 2-2x6       | 5'-5"               | 1   | 4'-8"  | 1 |
|                                         | 2-2x8       | 6'-10"              | 1   | 5'-11" | 1 |
|                                         | 2-2x10      | 8'-5"               | 2   | 7'-3"  | 2 |
|                                         | 2-2x12      | 9'-9"               | 2   | 8'-5"  | 2 |
|                                         | 3-2x8       | 8'-4"               | 1   | 7'-5"  | 1 |
|                                         | 3-2x10      | 10'-6"              | 1   | 9'-1"  | 1 |
|                                         | 3-2x12      | 12'-2"              | 2   | 10'-1" | 2 |
|                                         | 4-2x8       | 9'-2"               | 1   | 8'-4"  | 1 |
|                                         | 4-2x10      | 11'-8"              | 1   | 10'-6" | 1 |
|                                         | 4-2x12      | 14'-1"              | 1   | 12'-2" | 2 |



**TYPICAL WINDOW HEADER**




**NON-BEARING WALL HEADER**



**BEARING WALL HEADER**

**Wall Framing/ Header DET's**


SCALE: NONE



**Typical Wall SECTION**


SCALE: 3/4" = 1'-0"

EXTERIOR WALL SHEATHING:  
APPLY VERTICALLY, "Windstorm" 1/16" O.S.B 48" X 91", 109", 121" OR 145" SHEATHING. FASTEN TO THE TOP PLATE AND THE SILL PLATE WITH EITHER 6d RING SHANK NAILS @ 3" O.C. OR 8d R.S. NAILS @ 4" O.C. ALONG INTERMEDIATE SUPPORTS, TYPICAL, T.O.  
NAILS @ 8" O.C.



**GABLE END GYPSUM DIAPHRAGM HOLDOWN CONNECTOR**

SCALE: NONE



**END WALL BRACING FOR CEILING DIAPHRAGM**

NTS

(ALTERNATIVE TO BALLOON FRAMING)

NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

REVISION:  
Copyright 2018  
N.P. Geisler, Architect  
DRAWN:  
rpg

CUSTOM RESIDENTIAL DESIGN for:  
EDWARD AND HELEN ROLING

STRUCTURAL DETAILS

APPROVED: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_  
SECTION LETTER: A PAGE NUMBERS: 11  
SCALE: 1/4" = 1'-0"  
DRAWN BY: \_\_\_\_\_ DATE: Monday, March 8, 2021  
Bradley Franks Construction, LLC  
PHONE: 386-755-2455  
FAX: info@bradleyfranks.com  
257 SW Hudson in Lake City, FL 32025  
NICHOLAS GEISLER ARCHITECT  
1912 - 2020  
48 Years of Celebrating Service  
N.P. Geisler, Architect  
NCAAB Certified  
TOMPKINS ADDITION  
ARCHITECTURAL DESIGN SOFTWARE  
PHONE: \_\_\_\_\_ FAX: \_\_\_\_\_



