


















Revision Schedule		
Revision Number	Revision Description	Revision Date
0	ISSUED FOR PERMITTING	5/15/22

DOOR SCHEDULE				
Mark	Width	Height	Finish	Description
1	2' - 8"	6' - 8"		
2	3' - 0"	6' - 8"		
3	3' - 0"	6' - 8"		
4	3' - 0"	6' - 8"		
5	3' - 0"	6' - 8"		
6	3' - 0"	6' - 8"		
7	3' - 0"	6' - 8"		
8	3' - 0"	6' - 8"		
9	3' - 0"	6' - 8"		

WINDOW SCHEDULE			
MARK	ROUGH WIDTH	ROUGH HEIGHT	DESCRIPTION
1	3' - 1 3/4"	4' - 11 3/4"	Vent Window
2	3' - 1 3/4"	4' - 11 3/4"	Vent Window
3	3' - 1 3/4"	4' - 11 3/4"	Vent Window

	FLOOR OUTLET
	OUTLET DUPLEX
	OUTLET DUPLEX - GFI
	OUTLET DUPLEX - 220
	SINGLE SWITCH
	THREE WAY SWITCH
	FAN / LIGHT COMBO
	CEILING LIGHT
	6" RECESS CAN LIGHT
	FLOOD LIGHT
	VANITY LIGHT
	CEILING LIGHT
	PENDANT LIGHT
	3 LIGHT CHANDELIER
	200 AMP PANEL
	SMOKE DETECTOR
	CARBON MONOXIDE ALARMS


○ ELECTRICAL LEGEND  
1/4" = 1'-0"

ELECTRICAL PLAN NOTES:


1. WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUFACTURER'S SPECIFICATIONS.
2. CONSULT THE OWNER FOR THE NUMBER OF SEPERATE TELEPHONE LINES TO BE INSTALLED.
3. INSTALLATION SHALL BE PER NATIONAL ELECTRIC CODE.
4. ALL SMOKE DETECTORS SHALL BE 120V WITH BATTERY BACKUP OF THE PHOTOELECTRIC TYPE AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS.
5. TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER OWNER'S DIRECTIONS, & IN ACCORDANCE WITH APPLICABLE SECTIONS OF NEC - LATEST ADDITION.
6. ELECTRICAL CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL ELECTRICAL WORK, INCLUDING ANY CHANGES TO THE ELECTRICAL PLAN, ADDITIONS TO THE ELCTRICAL PLAN, RISER DIAGRAM, AS-BUILT PANEL SCHEDULE WITH ALL CIRCUITS IDENTIFIED WITH CIRCUIT NUMBER, DESCRIPTION, AND BREAKER SERVICE ENT. AND ALL UNDERGROUND WIRE LOCATIONS/ROUTING/DEPTH. RISER DIAGRAM SHALL INCLUDE WIRE SIZES/TYPE AND EQUIPMENT TYPE WITH RATINGS AND LOADS. CONTRACTOR SHALL PROVIDE 1 COPY OF "AS-BUILT" DRWINGS TO OWNER AND 1 COPY TO PERMITTING AUTHORITY.
7. ALL BEDROOM RECEPTACLES SHALL BE ON AFCI PROTECTED CIRCUITS.
8. ALL BATHROOM RECEPTICALS SHALL BE GFIC.

③ ELECTRICAL NOTES  
1/4" = 1'-0"

SHEET SCHEDULE				
SHEET NUMBER	SHEET NAME	REVISION	REVISION DATE	DESCRIPTION
A-001	FLOOR PLAN AND ELECTRICAL PLAN	0	5/15/22	ISSUED FOR PERMITTING
A-002	ELEVATIONS	0	5/15/22	ISSUED FOR PERMITTING
S-001	STRUCTURAL NOTES	0	5/15/22	ISSUED FOR PERMITTING
S-002	FOUNDATION PLAN AND FLOOR FRAMING	0	5/15/22	ISSUED FOR PERMITTING
S-003	ROOF FRAMING PLAN	0	5/15/22	ISSUED FOR PERMITTING
S-004	SECTION VIEWS	0	5/15/22	ISSUED FOR PERMITTING



TOTAL HEATED AREA: 917 S.F.



② ELECTRICAL PLAN  
1/4" = 1'-0"

5/15/2022 3:19:56 PM  
email: ggil@gillengineering.com



Gary Gill  
2022.05.15 15:24:48  
-04'00"  
2022.001.20117

MORRISON ADDITION


COLUMBIA COUNTY, FL

MIKE MORRISON				GILL ENGINEERING SERVICES, INC AUTH # 30824 GARY GILL PE #51942 426 SW COMMERCE DR 130-M LAKE CITY, FL 32025 386-590-1242
DRAWN BY:	GG			
CHKD BY:	GG			
APPRD BY:	GG			


FLOOR PLAN AND ELECTRICAL PLAN

PROJECT #: 2216-022	DWG #: A-001	REV #: 0
------------------------	-----------------	-------------


Revision Schedule		
Revision Number	Revision Description	Revision Date
0	ISSUED FOR PERMITTING	5/15/22



① EAST  
1/4" = 1'-0"



② NORTH  
1/4" = 1'-0"



③ SOUTH  
1/4" = 1'-0"

5/15/2022 3:19:57 PM

email: ggil@gillengineeringervices.com



MORRISON ADDITION

COLUMBIA COUNTY, FL

MIKE MORRISON

DRAWN BY: GG  
CHKD BY: GG  
APPRD BY: GG

GILL ENGINEERING SERVICES, INC  
AUTH # 30824  
GARY GILL PE #51942  
426 SW COMMERCE DR 130-M  
LAKE CITY, FL 32025 386-590-1242

ELEVATIONS

PROJECT #: 2216-022

DWG #: A-002

REV #: 0

GENERAL NOTES:

1. ALL CONSTRUCTION AND DESIGN SHALL CONFORM TO THE 2020 FBC (7TH ED)
2. THE STRUCTURAL DRAWINGS SHALL BE UTILIZED IN CONJUNCTION WITH OTHER CONSULTANTS' DRAWINGS.
3. THE STRUCTURAL DRAWINGS ARE INTENDED FOR THE STRUCTURE TO ACT AS WHOLE ONCE CONSTRUCTION IS COMPLETE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE SAFETY AND STABILITY (I.E, TEMPORARY BRACING IF REQUIRED) DURING CONSTRUCTION AS A RESULT OF CONSTRUCTIONS METHODS AND SEQUENCES.
4. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING STRUCTURES. THE ENGINEER SHALL BE NOTIFIED ON ANY DISCREPANCY BETWEEN THE EXISTING CONDITIONS AND CONSTRUCTION DOCUMENTS.
5. DESIGN CRITERIA

A. CODE: 2020 FBC (7TH ED)

B. LOADS AND DESIGN CRITERIA: THE FOLLOWING LOADS AND CRITERIA WERE USED IN ADDITION T THE DEAD LOAD OF THE STRUCTURE.

LIVE LOADS:

ROOF20 PSF

SOIL CRITERIA:  
ALLOWABLE SOIL BEARING1500 PSF  
PASSIVE PRESSURE150 PCF  
FRICTION COEFFICIENT0.35

WIND CRITERIA:  
WIND SPEED:130 MPH (3-SECOND GUST)  
CATEGORY:II  
EXPOSUREC  
INTERNAL PRESSURES:=-/ 0.18  
COMPONENTS AND CLADDING:

ZONE 1: 18.52 / -33.26 PSF  
ZONE 2: 18.52 / -45.89 PSF  
ZONE 3: 18.52 / -45.89 PSF  
ZONE 4: 24.84 / -26.95 PSF  
ZONE 5: 24.84 / -33.26 PSF

REINFORCING STEEL:

1. ALL BAR REINFORCEMENT SHALL BE CONFORM TO ASTM 615 GRADE 60.
2. WELD WIRE FABRIC REINFORCEMENT SHALL CONFORM TO ASTM A185
3. CLEARANCE OF MAIN REINFORCEMENT FROM ADJACENT SHALL BE CONFORM TO THE FOLLOWING (UNLESS OTHERWISE SHOWN IN DETAIL).

A. UNFORMED SURFACES IN CONTACT WITH GROUND (FOOTING OR WALL BOTTOM).....3"

B. SLAB ON GRADE .....2 1/2"

C. FORMED SURFACE IN CONTACT WITH GROUND OR EXPOSED TO WEATHER (WALLS, PIERS).....2 1/2"

D. IN ALL CASES, CLEARANCE NOT LESS THAN DIAMETER OF BARS.

NOTE: MAXIMUM DEVIATION FROM THESE REQUIREMENTS SHALL BE + 1/4" FOR SECTIONS 10" OR LESS AND +1/2" FOR SECTIONS OVER 10" THICK.
4. REINFORCEMENT SHALL BE CONTINUOUS THROUGH ALL CONSTRUCTION JOINTS UNLESS OTHERWISE INDICATED ON DRAWS
5. WHERE REINFORCEMENT IS NOT SHOWN ON DRAWINGS, PROVIDE REINFORCEMENT IN ACCORDANCE WITH APPLICABLE TYPICAL DETAILS OR SIMILAR TO THAT SHOWN FOR MOST NEARLY SIMILAR SITUATION, AS DETERMINED BY THE ARCHITECT / ENGINEER. IN NO CASE SHALL REINFORCEMENT BE LESS THAN MINIMUM PERMITTED BY APPLICABLE CODES.
6. ALL WORKMANSHIP AND MATERIAL SHALL BE CONFORMED TO THE MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES" (ACI-315)
7. ALL REINFORCEMENT SHALL BE INSPECTED AND APPROVED BY THE ARCHITECT/ENGINEER OR OWNER TESTING AGENCY BEFORE CONCRETE IS PLACED.
8. WHERE CONTINUOUS BARS ARE CALLED FOR THEY SHALL BE CONTINUOUSLY AROUND CORNERS, LAPPED AT NECESSARY SPLICES AND HOOKED AT CONTINUOUS ENDS.
9. WELDED WIRE FABRIC SHALL BE LAPPED ONE FULL MESH PANEL OR 6" MIN.
10. ALL REINFORCING SPLICES SHALL CONFORM TO THE TABLE(S) PROVIDED IN THE GENERAL NOTES FOR STRENGTH OF CONCRETE BUT IN NO CASE LESS THAN THE REQUIREMENTS OF THE LATEST EDITION OF A318
11. SLABS AND WALLS SHALL NOT BE SLEEVED OR BOXED OUT OR HAVE THEIR REINFORCEMENT INTERRUPTED EXCEPT SPECIFICALLY NOTED ON THE DRAWINGS. PROVIDE ADDITIONAL REINFORCEMENT AROUND OPENINGS AS SHOWN IN THE DETAILS.
12. SUBMIT CHECKED SHOP DRAWINGS TO THE ARCHITECT / ENGINEER FOR REVIEW PRIOR TO FABRICATION OF REINFORCEMENT.
13. BAR SUPPORTS SHALL BE ALL STAINLESS STELL OR SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION OR PLASTIC-TIPPED IN SUCH A MANNER AS TO PROVIDE A MINIMUM 2 1/2 INCHES OF PROTECTION FROM THE SUBGRADE.

ADDITION CONCRETE ITEMS:

SLAB AND WALL REINFORCING LAP SPLICE LENGTHS

LAP SLICE LENGTHS FOR REINFORCING IN 4000 PSI CONCRETE AS FOLLOWS

BAR SIZE	TENSION SPLICE		DEVELOPMENT LENGTH
	TOP	OTHER	
#3	21"	15"	13"
#4	29"	20"	17"
#5	35"	25"	21"
#6	43"	31"	25"
#7	54"	39"	32"
#8	71"	51"	42"

- NOTES:
1. LAPPED SPLICE LENGTHS BASED ON ASTM A-615, GRADE 60, REBAR
2. REINFORCING BARS CLASSIFIED AS TOP BARS WHEN MORE THAN 12" ON CONCRETE IS CAST BENEATH RESPECTIVE REINFORCING BAR.
3. COMPRESSION SPLICES SHALL PERMISSIBLE ONLY WHERE SPECIFICALLY NOTED ON THE DRAWINGS
4. TENSION SPLICES SHALL BE USED IN ALL BEAMS, SLABS, AND WALLS UNLESS OTHERWISE NOTED.
5. WHEN LAPPING LARGER BARS WITH SMALLER BARS, LAP LENGTH FOR SMALLER BAR SHALL GOVERN RESPECTIVE SPLICE.
6. SPLICE CONTINUOUS TOP REINFORCING BARS AT CENTER OF CLEAR SPAN WITH COMPRESSION SPLICES
7. SPLICE CONTINUOUS REINFORCING BARS AT CENTER OF SUPPORTING ELEMENT WITH COMPRESSION SPLICES.

CONCRETE AND REINFORCING STEEL:

1. ALL CONCRETE DESIGNED PER CURRENT EDITION OF AC1 318
2. CONCRETE SHALL HAVE THE FOLLOWING MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS:

A. FOUNDATION WALLS, PIERS, AND FOOTINGS4000 PSI

B. SLAB ON CARE:4000 PSI

C. ALL OTHER CONCRETE4000 PSI
3. ALL CONCRETE SHALL BE NORMAL WEIGHT CONCRETE WITH A NORMAL AIR DENSITY OF 145 PSF.
4. PROVIDE CONSTRUCTION JOINTS WHERE SHOWN, OMIT NONE AND ADD NONE WITHOUT WRITTEN APPROVAL FROM THE ARCHITECT / ENGINEER.SUBMIT DRAWINGS SHOWING ALL PROPOSED CONSTRUCTION JOINT LOCATIONS FOR APPROVAL PRIOR TO PREPARATIONS OF AFFECTED REINFORCEMENT SHOP DRAWINGS
5. MINIMUM ELAPSED TIME BETWEEN ADJACENT CONCRETE PLACEMENTS SHALL BE 48 HOURS
6. CONCRETE MIX DESIGN FOR EACH TYPE AND STRENGTH OF CONCRETE SPECIFIED SHALL BE SUBMITTED FOR ARCHITECT / ENGINEER REVIEW 30 DAYS PRIOR TO PLACEMENT OF CONCRETE
7. ALL REINFORCING STEEL ASTM A615 GRADE 60, ALL WELDED WIRE FABRIC ASTM A185

CONCRETE TESTING:

1. OBTAIN AT LEAST ONE COMPOSITE SAMPLE FOR EACH 50 CUBIC YARDS / TRUCK, OR FRACTION THEREOF, OF EACH DESIGN MIXTURE OF CONCRETE PLACED IN ANY ONE DAY. COMPOSITE SAMPLES ARE OBTAINED IN ACCORDANCE WITH "STANDARD PRACTICE FOR SAMPLING FRESHLY MIXED CONCRETE," ASTM C 172. SLUMP TESTS ARE REQUIRED FOR EACH COMPOSITE SAMPLE AND WHENEVER CONSISTENCY OF THE CONCRETE APPEARS TO VARY.

FLOOR SLABS:

1. STRUCTURAL FILL SHALL BE PLACED IN THIN LOOSE LIFTS NOT EXCEEDING 12" IN THICKNESS AND COMPACTED WITH A HEAVY ROLLER. EACH LIFT SHALL BE THOROUGHLY COMPACTED WITH THE LABORATORY ROLLER TO PROVIDE DENSITIES TO AT LEAST 95% OF THE PROCTOR MAXIMUM DRY DENSITY. STRUCTURAL FILL SHALL CONSIST OF AN INORGANIC NON-PLASTIC, GRANULAR SOIL CONTAINING LESS THAN 10% MATERIAL PASSING THE 200 MESH SIEVE.
2. CONCRETE SLAB SHALL HAVE A BROOM FINISH. SLAB TO HAVE A FLAT TOLERANCE OF 1/8" OVER 10 FT.

COMPACTION REQUIREMENTS

1. SUBGRADE SOILS AND STRUCTURAL FILL MATERIALS SHALL BE COMPACTED TO THE FOLLOWING PERCENTAGES OF THE ASTM D1557 MAXIMUM DRY DENSITY AT +/- 2% OPTIMUM MOISTURE CONTENT:

MATERIAL	MINIMUM PERCENT COMPACTION
STRUCTURAL FILL,IN THE BUILDING AREA	95
SUBBASE FOR SLAB SUPPORT	95
SUBGRADE BELOW STRUCTURAL FILL	95
MISCELLANEOUS BACKFILL	90

FOUNDATION FIELD OBSERVATION AND TESTS:

THE OWNER SHALL EMPLOY THE SERVICES OF A REGISTERED, LICENSED GEOTECHNICAL ENGINEER TO OBSERVE ALL CONTROLIID EARTHWORK. THE GEOTECHNICAL ENGINEER SHALL PROVIDE CONTINUOUS ON-SITE OBSERVATION BY EXPERIENCED PERSONNEL DURING CONSTRUCTION OF CONTROLLED EARTHWORK. THE CONTRACTOR SHALL NOTIFY THE GEOTECHNICAL ENGINEER AT LEAST TWO WORKING DAYS IN ADVANCE OF ANY FIELD OPERATIONS OF THE CONTROLIID EARTHWORK. TESTS OF MATERIALS SHALL BE MADE AT THE FOLLOWING RATES:

ONE FIELD DENSITY TEST PER EACH 500 SQUARE YARDS OF COMPACTED SUBGRADE PRIOR TO PLACING STRUCTURAL FILL OR FLOOR SLAB CONSTRUCTION WITH A MINIMUM OF 3 TESTS.

ONE FIELD DENSITY TEST PER EACH 300 CUBIC YARDS OF STRUCTURAL FILL PLACED OR EACH HORIZONTAL LAYER OF STRUCTURAL FILL. WHICHEVER IS GREATER.

ONE MOISTURE-DENSITY CURVE FOR EACH TYPE OF MATERIAL USED, AS INDICATED BY SIEVE ANALYSIS AND PLASTICITY INDEX.

GENERAL WOOD NOTES:

DIMENSIONAL LUMBER

1. DIMENSIONAL LUMBER USED AS STRUCTURAL FRAMING (i.e. JOISTS, RAFTERS,HEADERS) SHALL BE SOUTHERN YELLOW PINE NO.2 OR EQUAL.
2. DIMENSIONAL LUMBER USED FOR STUDS WALLS SHALL BE STUD GRADE UNLESS NOTED OTHERWISE. STUDS SHALL HAVE BE SPACES AT 16" MIN WITH A DOUBLE TOP PLATE. SPLICES IN THE DOUBLE TOP WALLS SHALL BE ALTERNATE TOP AND BOTTOM. IN NO CASE SHALL 2x4 BEARING WALLS SUPPORT MORE THAN TWO FLOORS OF FRAMING IN ADDITION TO ROOF AND CEILING
3. ROUGH CUT TIMBER USED AS STRUCTURAL FRAMING SHALL BE AS SPECIFIED IN THE CONSTRUCTION DOCUMENTS
4. ALL LUMBER IN CONTACT WITH THE GROUND, CONCRETE SHALL BE PRESSURED-TREATED. CONTRACTOR MAY SUBMIT FOR APPROVAL A MOISTURE BARRIER IN-LIEU OF THE PRESSURE TREATED WOOD.
5. FASTENERS FOR PRESERVATIVE-TREATED AND FIRE-RETARDANT TREATED WOOD SHALL BE OF HOT-DIPPED ZINC COATED GALVANIZED STEEL OR STAINLESS STEEL AND SHALL FOLLOW CURRENT SIMPSON GUIDELINES BASED ON WEATHER EXPOSURE WHERE STAINLESS STEEL CONNECTORS OR HOT DIPPED CONNECTORS ARE SPECIFIED IN THE DRAWINGS, STAINLESS STEEL OR HOT DIPPED GALVANIZED FASTENERS SHALL BE USED TO MATCH THE CONNECTORS TYPE.
6. ALL NAILS FOR STRUCTURAL WORK SHALL BE COMMON WIRE NAILS UNLESS NOTED OR DETAILED OTHERWISE MEETING ASTM F1667. HOLES SHALL BE PRE-DRILLED WHERE NECESSARY TO PREVENT SPLITTING. NAILS SHALL HAVE THE MINIMUM PROPERTIES SPECIFIED IN THE TABLE BELOW:

NAIL TYPE	SHANK DIAMETER- INCHES	MINIMUM PENETRATION - INCHES
6d	0.113	1.13
8d	0.131	1.31
10d	0.148	1.48
12d	0.148	1.48
16d	0.162	1.63
20d	0.192	1.92

NAILING NOT SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE PER THE NAILING SCHEDULE BELOW:

- A. JOIST SITTING ON SILL OR GIRDER(3) 8d TOENAILS, EA. SIDE
- B. BLOCKING BETWEEN JOIST/RAFTERS(2) 10d TOENAILS EA. SIDE, EA. END
- RIM BLOCKING BETWEEN JOIST/RAFTERS(3) 10d TOENAILS EA. END
- C. TOP PLATE TO STUD(2) 16d END NAILS
- D. STUD TO SILL PLATE(2) 16d END NAILS OR (4) 8d TOENAILS
- E. DOUBLE STUDS(2) 10d @ 12" O.C.
- F. DOUBLE TOP STUDS - BETWEEN SPLICE NAILING16d @ 16" O.C. FACE NAILS
- G. DOUBLE TOP STUDS - EACH SIDE OF SPLICE PLATE(8) 16d
- H. BLOCKING TO TOP PLATE(2) 10d TOENAILS EACH SIDE
- BLOCKING TO FLOOR/ROOF SHEATHING(4) 10d NAILS
- I. RIM JOIST OR BLK TO TOP PLATE OR SILL PLATE8d TOENAILS @ 6" O.C.
- J. CONTINUOUS (2) AND (3) PIECE HEADERS16d @ 16" O.C. ALONG EACH EDGE
- K. CEILING JOIST LAPS OVER PARTITIONS(3) 16d FACE NAILS, MINIMUM
- L. RAFTER TO TOP PLATE OR SILL PLATE(3) 8d TOENAILS EACH SIDE
- M. BUILT-UP CORNER STUDS16d @ 24" O.C.
- N. TONGUE AND GROOVE DECKING(2) 16d AT EACH BEARING
- P. CROSS BRIDGING(2) 10d EACH END
- R. HORIZONTAL BLOCKING BETWEEN WALL STUDS(2) 10d TOENAILS EACH END
- S. I-JOISTS SITTING ON TOP PLATE OR BEAM(2) 10d NAILS THROUGH JOIST FLANGE

NAILING SCHEDULE NOTES:

1. ALL OTHER NAILING REQUIREMENTS NOTE SHOWN ON DRAWINGS OR IN SCHEDULE ABOVE SHALL BE IN ACCORDANCE WITH 2012 FBC.
2. POWER DRIVEN OR PNEUMATIC NAILS OTHER THAN COMMON NAILS MAY BE USED IF DATA IS SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO USE.
3. MINIMUM NAIL LENGTHS SHALL BE SUFFICIENT TO ACHIEVE MINIMUM PENETRATION INTO MAIN MEMBER AS NOTED IN SCHEDULE ON NOTE ABOVE.

WOOD STRUCTURAL PANELS

1. STRUCTURAL WOOD PANELS SHALL CONFORM TO THE REQUIREMENTS ON ONE OF THE FOLLOWING STANDARDS AND PUBLICATIONS:

A. U.S. PRODUCT STANDARD PS-1 FOR CONSTRUCTION AND INDUSTRIAL PLYWOOD

B. U.S. PRODUCT STANDARD PS-2 PERFORMANCE STANDARD FOR WOOD BASED STRUCTURAL USE PANELS

C. APA PRP-108 PERFORMANCE STANDARDS
2. ROOF AND WALL PANELS SHALL BE APA RATED, EXPOSURE 1, 1/2" OR 5/8" (AS NOTED ON DRAWINGS), 5 PLY PLYWOOD WITH A MIN. 32/16 SPAN RATING UNLESS NOTE OTHERWISE ON THE DRAWINGS. SHEATHING SHALL BE EXTERIOR GRADE WHERE EITHER SIDE OF SHEATHING IS PERMANENTLY EXPOSED TO WEATHER.
3. FLOOR SHEATHING SHALL BE TONGUE AND GROOVE APA RATED 5-PLY 3/4" PLYWOOD OR OSB SHEATHING (MIN APA RATED 48/24 SPAN RATING) PROVIDE A-C GRADE PLYWOOD AT ALL DECK SHEATHING LOCATIONS.
4. ALL FLOOR AND ROOF SHEATHING SHALL BE INSTALLED WITH THE FACE GRAIN PERPENDICULAR TO THE SUPPORTS AND A 1/8" GAP AT ALL PANEL EDGES UNLESS RECOMMENDED OTHERWISE BY THE PANEL MANUFACTURER.
5. ALL SHEATHING PANELS SHALL BE INSTALLED WITH END JOINTS STAGGERED UNLESS NOTED OTHERWISE ON THE DRAWINGS.
6. WHERE BLOCKING IS NOT SPECIFICALLY REQUIRED FOR THE ROOF SHEATHING, PLY CLIPS ON OR TONGUE AND GROOVE PLYWOOD SHALL BE USED.
7. SUB-FLOORING SHEATHING SHALL BE UNBLOCKED UNLESS NOTED OTHERWISE ON THE STRUCTURAL DRAWINGS, SUB-FLOOR SHEATHING SHALL BE GLUED DOWN TO THE SUPPORTING MEMBERS AND GLUED AT THE TONGUE AND GROOVE JOINTS.
8. ALL NAILS SHALL BE COMMON NAILS. ROOF SHEATHING SHALL UTILIZE RING SHANK NAILS.. STAINLESS STEEL (TYPE 316) NAILS SHALL BE USED AT PERMANENTLY EXPOSED EXTERIOR AREAS. ALL NAILS THAT ARE NOT EXPOSED TO THE ELEMENTS BUT IN CONTACT WITH PRESERVATIVE TREATED LUMBER SHALL BE MINIMUM HOT DIPPED GALVANIZED MEETING ASTM A153.

MASONRY:

1. ALL MASONRY UNITS SHALL COMPLY WITH ASTM C 90 WITH A COMPRESSION STRENGTH OF 1900 PSI (NET AREA).
2. F'm = 1500 PSI
3. MORTAR SHALL BE TYPE S.
4. GROUT : F'c = 2000 PSI
5. CELLS CONTAINING REBAR SHALL BE GROUTED SOLID FROM BOTTOM TO THE TOP OF WALL IN ACCORDANCE WITH THE FLORIDA BUILDING CODE.
6. ALL CELLS BELOW GRADE SHALL BE GROUTED SOLID.
7. ALL VERTICAL REBAR SHALL BE IN PLACE AND SECURED WITH REBAR POSITIONERS PRIOR TO GROUTING.
8. CELLS CONTAINING EXPANSION ANCHORS SHALL BE GROUTED SOLID. UNLESS OTHERWISE NOTES MASONRY CELLS SHALL BE GROUTED IN ACCORDANCE WITH FBC (MAXIMUM 5 FOOT GROUT LIFTS).
9. LAP REBAR 48 BAR DIAMETERS (12" MIN) UNLESS NOTED OTHERWISE. ALL HORIZONTAL REINFORCING IN BOND BEAMS SHALL BE CONTENTIOUS AROUND CORNERS OR HAVE BENT (CORNER) BARS OF THE SAME SIZE AND A LAP AS NOTED ABOVE. VERTICAL STEEL SHALL CONTINUE THROUGH BOND BEAMS. PROVIDE STANDARD TRUSS TYPE JOINT REINFORCING AT 16" O.C. USE PREFABRICATED CORNERS AND TEES AT ALL WALL CORNERS AND INTERSECTIONS RESPECTIVELY
10. ALL MASONRY WALL CONFIGURATIONS INCLUDING WALL OPENINGS SHALL BE COORDINATED WITH CIVIL, MECHANICAL.PLUMBING, ELECTRICAL, AND DRAWING FROM ALL OTHER DISCIPLINES.

MORRISON ADDITION

COLUMBIA COUNTY, FL

MIKE MORRISON				GILL ENGINEERING SERVICES, INC AUTH # 30824 GARY GILL PE #51942 426 SW COMMERCE DR 130-M LAKE CITY, FL 32025 386-590-1242
DRAWN BY:	GG			
CHKD BY:	GG			
APPRD BY:	GG			

STRUCTURAL NOTES


PROJECT #:	DWG #:	REV #:
2216-022	S-001	0

5/15/2022 3:19:57 PM  
email: ggil@gillengineeringervices.com







Revision Schedule		
Revision Number	Revision Description	Revision Date
0	ISSUED FOR PERMITTING	5/15/22




1 ROOF FRAMING  
1/4" = 1'-0"



2 DETAIL - LEAN TOO LEDGER  
3/4" = 1'-0"




3 DETAIL - TRUSS CONNECTION  
3/4" = 1'-0"




- NOTES:
1. ACTUAL BRACING REQUIREMENTS WILL VARY DUE TO WIND LOAD, CODE CRITERIA BUILDING HEIGHT, TRUSS SPAN, WEB LUMBER (GRADE AND SPECIES), ON CENTER SPACING, AND OTHER VARIABLES. BRACING AND ATTACHEMENT REQUIREMENTS SHOULD BE DESIGNED FOR EACH SPECIFIC JOB.
  2. CONNECTION BETWEEN BOTTOM CHORD OF GABLE END TRUSS AND WALL, AS WELL AS THE DESIGN AND SPECIFICATION OF TEMPORARY AND PERMANENT BRACING OF THE ROOF SYSTEM IS THE RESPONSIBILITY OF THE BUILDING DESIGNER.


4 BRACING  
1/4" = 1'-0"



6 ROOF SHEATHING  
1/2" = 1'-0"



5 GABLE END BRACING  
1/2" = 1'-0"



7 TRUSS BLOCKING - LOW HEEL  
1" = 1'-0"

MORRISON ADDITION  
COLUMBIA COUNTY, FL

MIKE MORRISON

DRAWN BY: GG  
CHKD BY: GG  
APPRD BY: GG

GILL ENGINEERING SERVICES, INC  
AUTH # 30824  
GARY GILL PE #51942  
426 SW COMMERCE DR 130-M  
LAKE CITY, FL 32025 386-590-1242

ROOF FRAMING PLAN

PROJECT #:  
2216-022





DWG #:  
S-003

REV #:  
0

5/15/2022 3:19:59 PM

email: ggil@gillengineering.com

Gill  
Engineering Services, Inc.



Revision Schedule		
Revision Number	Revision Description	Revision Date
0	ISSUED FOR PERMITTING	5/15/22

5/15/2022 3:20:00 PM  
email: ggil@gillengineering.com



MORRISON ADDITION  
COLUMBIA COUNTY, FL

MIKE MORRISON

DRAWN BY: GG  
CHKD BY: GG  
APPRD BY: GG

GILL ENGINEERING SERVICES, INC  
AUTH # 30824  
GARY GILL PE #51942  
426 SW COMMERCE DR 130-M  
LAKE CITY, FL 32025 386-590-1242

SECTION VIEWS

PROJECT #: 2216-022

DWG #: S-004

REV #: 0