	SHC	OCK ARRESTOR S	CHEDULE		
FIXTURE UNITS	P.D.I. UNITS	ZURN	JOSAM	SMITH	WADE
1-11	A	Z-1700-100	75001	5005	W-5
12-32	В	Z-1700-200	75002	5010	W-10
33-60	С	Z-1700-300	75003	5020	W-20
61-113	D	Z-1700-400	75004	5030	W-50
114-154	E	Z-1700-500	75005	5040	W-75
155-330	F	Z-1700-600	75006	5050	W-100

				FLOOR D	RAIN SCHEDULE
ITEM	ZURN	JOSAM	SMITH	WADE	DESCRIPTION
FD-1	Z-415-6S	30000-6S	2006-B	W-1103-G6	6" SQUARE WITH SATIN NICKLE FINISH - 1/2" TRAP PRIMER
FD-2	Z-505-Y	32200-74	2131-C	W-1214-TD	12" ROUND, SEDIMENT BUCKET WITH SATIN BRONZE FINISH - 1/2" TRAP PRIMER
FS-1	ZN-1910-KC	49000	3100-C	W-9114-24	8" SQUARE WITH SATIN NICKLE FINISH - 1/2" TRAP PRIMER
AD-1	Z-415-8S	-	-	-	8" SQUARE WITH SATIN NICKLE FINISH
HD	-	_	-	120	SEE DETAIL

4.1 ALL ABOVE GROUND WATER PIPING - FIBERGLASS, 1" THICKNESS, ASJ JACKET, DOUBLE

SEALING LAP JOINT, 0.24 K AT 75°F. INSULATION AND ADHESIVES INSTALLED IN RETURN

AIR PLENUMS SHALL HAVE A MAXIMUM FLAME SPREAD RATING OF 25 AND A MAXIMUM

4.2 ABOVEGROUND CONDENSATE PIPING SHALL BE 1/2" FLEXIBLE UNICELLULAR POLYOLEFIN FOAM AND SHALL HAVE A MAXIMUM FLAME SPREAD RATING OF 25 AND A MAXIMUM SMOKE

5.1 VALVES 2" AND SMALLER SHALL BE BALL VALVES, 150 PSI SWP, 400 PSI WOG. STANDARD

5.2 CHECK VALVES, ROUGH BRASS, REGRINDING BRONZE DISC - STOCKHAM B-345; B-309 OR

TIGHT SHUT-OFF - STOCKHAM S214-BR-T-T, STOCKHAM S216-BR-T-S OR EQUAL.

6.1 DOMESTIC WATER PIPING SHALL BE THOROUGHLY FLUSHED OUT AND STERILIZED IN

PORT BALL, BRONZE TRIM, CAST BRONZE BODY, CHROMIUM-PLATED BRASS BALL, BRONZE

HANDLE WITH PLASTIC COATED HAND GRIP, 90 DEGREE OPERATION FROM FULL OPEN TO

NON-BLOWOUT STEM, TEFLON SEAT, DOUBLE O-RING STEM SEALS, ZINC-COATED STEEL

1. ALL VERTICAL PLUMBING SHALL BE PLUMB TO WITHIN 1/8" PER 4'.

SMOKE DEVELOPED RATING OF 50.

DEVELOPED RATING OF 50 - IMCOA "IMCOLOCK"

ACCORDANCE WITH THE STANDARD PLUMBING CODE.

2. ALL PLUMBING INSTALLATIONS AND MATERIALS SHALL BE IN STRICT ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL CODES AND

PIPING ROUTING IS SCHEMATIC AND IS NOT INTENDED TO INDICATE EXACT

ROUTING AND ALL ADDITIONAL OFFSETS AND FITTINGS REQUIRED FOR

OBSTRUCTIONS AND ROUTE PIPING TO AVOID ANY AND ALL CONFLICTS.

PROPER INSTALLATION AND TO MAINTAIN CLEARANCES. CONTRACTOR TO

VERIFY STRUCTURAL, MECHANICAL, AND ELECTRICAL INSTALLATIONS, AND

REGULATIONS AND AUTHORITIES HAVING JURISDICTION OVER THIS PROJECT.

3. ROUTE ALL PIPING CONCEALED ABOVE CEILING, WITHIN WALLS, OR IN CHASES

4. SEE ARCHITECTURAL DRAWINGS FOR FIXTURE LOCATIONS AND MOUNTING

5. SLEEVE AND FIRESTOP ALL PENETRATIONS OF RATED WALLS, CEILINGS, FLOORS, ETC. INCLUDING ROOF, FLASH AND COUNTERFLASH ALL ROOF

6. PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL WHEN REQUIRED BY

7. ALL SANITARY WASTE LINES ARE UNDER FLOOR/FLOOR SLAB. ALL VENT LINES

8. SEE WASTE AND VENT RISER SCHEMATIC DIAGRAM FOR WASTE AND VENT PIPE

AND WATER LINES ARE ABOVE CEILING UNLESS OTHERWISE NOTED.

9. SEE WATER RISER SCHEMATICS DIAGRAM FOR WATER PIPING SIZING.

11. PLUMBING CONTRACTOR TO PROVIDE SANITARY WASTE VENT, DOMESTIC

FURNISHED BY THIS CONTRACTOR OR FURNISHED BY OTHERS.

12. SIZE AND LOCATION OF CLEANOUTS SHALL BE IN ACCORDANCE WITH STANDARD PLUMBING CODE AND ALL JURISDICTIONAL REGULATIONS.

THE SATISFACTION OF THE OWNER REPRESENTATIVE.

WATER, ETC. ROUGH-IN AND MAKE FINAL CONNECTIONS (INCLUDING

13. PATCH ALL DISTURBED SURFACES TO MATCH ADJACENT SURFACES. WORK

14. COOPERATION WITH OTHER TRADES IN ROUTING AND/OR BURIAL DEPTHS, AS DETERMINED DURING CONSTRUCTION, AND AS DIRECTED BY THE

ARCHITECT/ENGINEER WILL BE NECESSARY. IT IS INTENDED TO BE

15. VENT PIPES THROUGH ROOF SHALL TERMINATE AT LEAST 10' FROM HVAC

SHALL BE SIZED AND LOCATED ACCORDING TO MANUFACTURER'S

16. USE MECHANICAL SHOCKSTOPS TO CONTROL WATER HAMMER. SHOCKSTOPS

PRIOR TO BID, AND INCLUDE ANY DEVIATIONS IN THIS PROJECT.

SHALL BE DONE ONLY BY WORKERS SKILLED IN THE TRADE INVOLVED AND TO

UNDERSTOOD THAT THE PLANS MAY NOT BE DRAWN COMPLETELY TO SCALE.

THE CONTRACTOR IS TO FIELD VERIFY DIMENSIONS OF ALL UTILITIES, ETC.,

SUPPLYING AND/OR INSTALLING ALL NECESSARY RELATED STOPS, VALVES,

TRAPS, ETC.. AND MAKING READY FOR USE) TO ALL EQUIPMENT WHETHER

10. MOUNT HOSE BIBBS 24" ABOVE FINISHED GRADE.

CODE AN AIR GAP SERVING INDIVIDUAL FIXTURES, DEVICES, APPLIANCES, OR

EXCEPT AS SPECIFICALLY NOTED, OR IN MECHANICAL EQUIPMENT ROOMS.

DRAWINGS FOR SLOPE.

5.00 - VALVES AND COCKS

6.00 - STERILIZATION

PLUMBING NOTES

PENETRATIONS.

ROOFTOP INTAKES.

RECOMMENDATIONS.

2. ALL WATER CLOSET BENDS SHALL HAVE A STAINLESS STEEL TOP FLANGE.

3. RESTROOMS SHALL BE SLOPED TO THE FLOOR DRAINS. SEE ARCHITECTURAL

1.1 PROVIDE ALL LABOR, MATERIAL AND EQUIPMENT FOR A COMPLETE AND PROPERLY OPERATING PLUMBING SYSTEM.

1.2 CODES AND STANDARDS: ALL PLUMBING WORK SHALL BE IN STRICT COMPLIANCE WITH

1.5 CONTRACTIOR SHALL COORDINATE HIS WORK WITH ALL OTHER TRADES BEFORE FABRICATION OR INSTALLATION. OFFSETS AND/OR TRANSITIONS REQUIRED SHALL BE

1.7 PROVIDE ALL MATERIALS REQUIRED TO PROPERLY SUPPORT ALL PIPING AND EQUIPMENT. PIPE HANGERS SHALL BE ADJUSTABLE TYPE AND BE SPACED IN ACCORDANCE WITH THE STANDARD PLUMBING CODE. PROVIDE PLASTIC COATED RING ON HANGERS FOR COPPER

1.8 PROVIDE DIELECTRIC UNIONS OR FLANGES BETWEEN COPPER AND STEEL PIPING AND BETWEEN BRASSWARE AND STEEL, DO NOT USE STEEL AND COPPER PIPING IN THE SAME

1.9 PROVIDE RIEDUCING FITTINGS (REDUCING BUSHINGS SHALL NOT BE USED) WHERE

1.10 THE CONTRACTOR SHALL SUPPLY AND INSTALL ALL SERVICES THROUGHOUT THE BUILDING AND MAKE CONNECTION TO SITE UTILITIES APPROXIMATELY 5'-0" OUTSIDE THE

1.11 SEE ARCHITECTURAL DRAWINGS FOR FIXTURE LOCATIONS AND MOUNTING HEIGHTS.

2.00 - BASIC MATERIALS AND METHODS

2.1 ABOVEGROUND WATER PIPE AND FITTINGS - TYPE "L" COPPER.

AND IN ACCORDANCE WITH PDI STANDARD WH-201. PRODUCTS SHALL BE EQUAL TO THOSE MANUFACTURED BY PRECISION PLUMBING PRODUCTS OR SIOUX CHIEF.

EQUIPMENT.

2.5 NOT USED.

2.6 PROVIDE INLINE WATER FILTER AT COFFEE MAKER AND ICE MAKER TO REMOVE MATERIALS, TASTE AND ODOR - "EVERPURE" OR "SYSTEMS IV".

COUPLINGS OR DWY COPPER.

2.9 INSTALL GRAVITY LINES SLOPED AT 1/8" PER FOOT FOR PIPE 3" AND LARGER AND 1/4" PER FOOT FOR PIPE SMALLER THAN 3". VERIFY INVERT ELEVATION WITH SITE PIPING PRIOR TO

3.00 - PLUMBING FIXTURES ANDTRIM

3.1 ALL PLUMBING FIXTURES SHALL BE "FIRST QUALITY" AS DEFINED AND SET FORTH IN COMMERCIAL STANDARD CS77-28 AS PROMULGATED BY THE U.S. DEPARTMENT OF

3.3 FIXTURES AND FITTINGS PROPOSED SHALL BE FROM ONE MANUFACTURER AND OF SIMILAR CHARACTER IN ANY ROOM OR LOCATION. ESCUTCHEONS, HANDLES, ETC. ON THE DIFFERENT FIXTURES SHALL BE OF THE SAME DESIGN.

3.4 PROVIDE FIXTURE ¢ARRIERS AS RECOMMENDED BY FIXTURE MANUFACTURER AND/OR CONSTRUCTION METHOD.

3,5 PROVIDE ACCESS PANELS TO ALL VALVES WITHIN CHASES OR ABOVE NON-ACCESSIBLE

CEILINGS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES. 3.6 FLOOR DRAIN TRAP SEALS SHALL HAVE AN APPROVED GRAVITY FED TRAP PRIMER. SIOUX

1.00 - GENERAL PROVISIONS

BI-LEVEL ELECTRICAL WATER COOLER (H.C.)

TAILPIECE. WALL MOUNTED REFRIGERANT CHILLER UNIT CAPABLE

TENPERATURE OF 90°F. ELECTRICAL CHARACTERISTICS - 120V AC,

60HZ, SINGLE PHASE WITH APRON EXTENSION KIT. FOUNTAIN TO

CHROME PLATED 17 GAUGE 1-1/4" x 1-1/2" BRASS P-TRAP WITH

3/8" I.P.S. CHROME PLATED ANGLE SUPPLY, LOOSE KEY STOP,

FOUNTAIN: HALSEY TAYLOR - HTV8BL - Q

REDUCER, WROUGHT BRASS DEEP BELL FLANGE ESCUTCHEON

······

WALL HYDRANT SHALL BE CONCEALED TYPE, AUTOMATIC DRAINING TYPE WITH ANTI - SIPHON VACUUM BREAKER, 3/4" HOSE THREAD

NOZZLE, ONE PIECE VALVE PLUNGER TO CONTROL BOTH FLOW AND

DRAIN FUNCTIONS, HARDENED STAINLESS STEEL OPERATING STEM,

POLISHED BRASS FINISH ON BRASS FINISH ON BRASS CASTINGS.

LOOSE TEE KEY TO BE FURNISHED WITH EACH HYDRANT.

CHECK ARCHITECTURAL DRAWINGS FOR WALL THICKNESS.

AND 1/2" CHROME PLATED COOPER EXTENSION TUBE WITH SWEAT

18 GAUGE STAINLESS STEEL WATER COOLER POLISHED TO A #4

SATIN FINISH WITH DUAL RECEPTOR, SELF CLOSING FRONT

OF 8 GPH OF 50°F DRINKING WATER AT AN AMBIENT ROOM

HAVE FLEXIBLE BUBBLER.

CLEANOUT.

CONNECTION.

WH-1 WALL HYDRANT

TRAP: MCGUIRE - 8902

SUPPLY: MCGUIRE - 158LK

MOUNTED PUSH BUTTON TYPE BUBBLER, STRAINER AND

1.3 ALL PLUMBING WORK SHALL BE DONE IN A NEAT AND WORKMANLIKE MANNER.

1.4 CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND FEES, ETC. REQUIRED FOR

PROVIDED WITHOUT ADDITIONAL COST, CONTRACTOR SHALL COORDINATE AND INSTALL

1.6 CONTRACTOR SHALL BE RESPONSIBLE TO REPAIR OR REPLACE DAMAGED

BUILDING. CONTRACTOR SHALL SUPPLY AND INSTALL FIXTURES, FITTINGS, VALVING AND TRIM AND MAKE READY FOR USE ALL FIXTURES, EQUIPMENT, ETC.

2.2 PROVIDE UNIONS ORFLANGES IN ALL DOMESTIC WATER SERVICE LINES AT EACH PIECE OF EQUIPMENT, SPECIALTY VALVES OR AT OTHER LOCATIONS REQUIRED FOR READY

FOAM CORE PIPE ISNOT ACCEPTABLE.

2.8 ABOVE GROUND SANITARY WASTE ARMS - SERVICE WEIGHT CAST IRON WITH NO-HUB

3.2 ALL FIXTURES ARE TOBE WHITE VITREOUS CHINA UNLESS OTHERWISE SPECIFICALLY

SHALL BE PROVIDED WITH AN ACCESS PANEL.

PLUMBING SPECIFICATIONS

THE STANDARD PLUMBING CODE AND ALL LOCAL CODES HAVING JURISDICTION.

THE EXECUTION OF THIS WORK.

HIS WORK IN A TIMELY MANNER TO PREVENT DELAYS IN THE CONSTRUCTION.

EQUIPMENTAND/OR MATERIAL.

PIPING TO PROVIDE DIELECTRIC ISOLATION.

SYSTEM WITHOUT SUCH ISOLATION.

CHANGES IIN PIPE SIZES OCCUR.

2.3 WATER HAIMMER ARRESTORS SHALL BE INSTALLED AT THE LOCATIONS ON THE PLANS

2.4 VALVES: PROVIDE VALVES TO ISOLATE EACH RISER, BRANCH LINE AND PIECE OF

2.7 ABOVE GROUND SANITARY WASTE, SANITARY VENT AND PIPING - SCHEDULE 40 PVC.

ANY PIPE BEING INSTALLED.

CHIEF MODEL 200 OR APPROVED EQUAL.

3.7 ALL CONCEALED TRAPS, PRIMERS, VALVES, CLEANOUTS, ETC. LOCATED IN TILED AREAS

L-1 LAVATORY

VITREOUS CHINA LAVATORY, 21-1/4" x 18-1/8" WITH FRONT OVERFLOW, SELF DRAINING DECK AREA, PROVIDE FIXTURE PUNCHED FOR SINGLE HOLE.

SINGLE LEVER, DECK MOUNTED FAUCET, 0.5 GPH, VANDAL RESISTANT SPRAY HEAD.

CHROME PLATED CAST BRASS GRID STRAINER WITH 1-1/4" O.D. OFFSET TAILPIECE, CHROME PLATED 17 GAUGE 1-1/4" x 1-1/2" BRASS P-TRAP WITH C.O. PLUG AND SLIP NUTS. PROVIDE P-TRAP AND TAILPIECE WITH PREWRAPPED SEAMLESS MOLDED CLOSED CELL VINYL INSULATION WITH FLEXIBLE COLLARS TO ALLOW PIPE CONNECTION. PREWRAPPED DRAIN INSULATION KIT SHALL INCLUDE HOT AND COLD ANGLE STOP AND WATER SUPPLY COVER OF SAME

TWO 3/8" I.P.S. CHROME PLATED ANGLE SUPPLY, LOOSE KEY STOP, REDUCER, WROUGHT BRASS DEEP BELL FLANGE ESCUTCHEON AND 1/2" CHROME PLATED COPPER EXTENSION TUBE.

MOUNT LAVATORY 34" FROM RIM TO FINISHED FLOOR.

CHINA: KOHLER - 2196-1N FAUCET: CHICAGO - 2200 STRAINER / TRAP: MCGUIRE - 155WC / PW 2150 WC SUPPLIES: MCGUIRE - H170LK

WALL HUNG LAVATORY (H.C.)

VITREOUS CHINA LAVATORY, 21-1/4" x 18-1/8", WITH FRONT OVERFLOW, SELF DRAINING DECK AREA AND CONTOURED BACK AND SIDE SPLASH PANELS, PROVIDE FIXTURE PUNCHED FOR SINGLE HOLE AND CONCEALED ARM CARRIER SUPPORT.

SINGLE LEVER, DECK MOUNTED, HANDWASHING FAUCET, 0.5 GPM, VANDAL RESISTANT SPRAY HEAD.

CHROME PLATED CAST BRASS GRID STRAINER WITH 1-1/4" O.D. OFFSET TAILPIECE, CHROME PLATED 17 GAUGE 1-1/4" x 1-1/2" BRASS P-TRAP WITH C.O. PLUG AND SLIP NUTS. PROVIDE P-TRAP AND TAILPIECE WITH PRE-WRAPPED SEAMLESS MOLDED CLOSED CELL VINYL INSULATION WITH FLEXIBLE COLLARS TO ALLOW PIPE CONNECTION. PRE-WRAPPED DRAIN INSULATION KIT SHALL INCLUDE HOT COLD ANGLE STOP AND WATER SUPPLY COVERS OF

TWO 3/8" I.PS. CHROME PLATED ANGLE SUPPLY, LOOSE KEY STOP, REDUCER, WROUGHT BRASS DEEP BELL FLANGE ESCUTCHEON AND 1/2" CHROME PLATED COPPER EXTENSION TUBE.

LAVATORY SUPPORT SYSTEM WITH CONCEALED ARMS: COATED STEEL UPRIGHTS WITH WELDED FEET, CAST IRON ADJUSTABLE HEADERS, STEEL SLEEVES, ALIGNMENT TRUSS AND FASTENERS.

CHINA: KOHLER - K-2005

CARRIER: J.R. SMITH - NO. 700

SAME MATERIAL.

FAUCET: CHICAGO - 2200 STRAINER / TRAP: MCGUIRE - 155 WC / PW 2150 WC SUPPLIES: MCGUIRE - H170LK

SINGLE COMPARTMENT SELF - RIMMING SINK CONSTRUCTED OF TYPE 304 18-8 STAINLESS STEEL, 22" x 19" x 7-1/2" DEEP. INTERIOR AND TOP SURFACES SHALL BE POLISHED TO A HIGH LUSTER FINISH. PROVIDE SINK WITH STAINLESS STEEL CRUMB CUP STRAINERS. PROVIDE FIXTURE PUNCHED FOR 2 - HOLE FAUCET INSTALLATION ON 4" CENTERS.

SWING SPOUT AND 2.0 GPM LAMINAR FLOW REGULATOR, SINGLE

3/8" I.P.S. CHROME PLATED ANGLE SUPPLY, LOOSE KEY STOP, REDUCER, WROUGHT BRASS DEEP BELL FLANGE ESCUTCHEON AND 1/2" CHROME PLATED COPPER EXTENSION TUBE WITH SWEAT CONNECTION.

CHROME PLATED 17 GAUGE 1-1/2" x 1-1/2" P-TRAP WITH CLEANOUT.

SINK: ELKAY - LR2219 FAUCET: CHICAGO - 2302-CP SUPPLIES: MCGUIRE - H170LK TRAP: MCGUIRE - 8902

WC-1 WATER CLOSET

BARRIER FREE, VITREOUS CHINA, FLOOR MOUNTED, SIPHON JET. ELONGATED CLOSET BOWL WITH 1" TOP SPUD, 14-3/4" HIGH BOWL.

EXPOSED CLOSET FLUSH VALVE, CHROME PLATED, METAL OSILLATING NON HOLD OPEN HANDLE, 1" I.PS. SCREW DRIVER ANGLE STOP WITH PROTECTIVE CAP, ADJUSTABLE TAILPIECE, VACUUM BREAKER FLUSH CONNECTION AND SPUD COUPLING FOR 1" TOP SPUD, WALL AND SPUD FLANGES, SOLID RING PIPE SUPPORT, AND 2" OFFSET TO AVOID GRAB BAR, MOUNT FLUSH VALVE HANDLE MAX 44" AFF. VALVE HANDLE SHALL BE INSTALLED

CONTOURED SEAT SHALL BE EXTRA HEAVY SOLID PLASTIC WITH OPEN FRONT LESS COVER. SEAT SHALL INCLUDE STAINLESS STEEL SELF SUSTAINING CHECK HINGE FEATURE.

BASIS OF DESIGN CHINA: KOHLER - K-4406 FLUSH VALVE: SLOAN ROYAL - 111

SEAT: CHURCH - NO. 295-SSC

ON "WIDE" SIDE OF SEAT.

NC-2 WATER CLOSET (H.C.)

BARRIER FREE, VITREOUS CHINA, FLOOR MOUNTED, SIPHON JET, ELONGATED CLOSET BOWL WITH 1" TOP SPUD, 17-1/2" HIGH BOWL.

EXPOSED CLOSET FLUSH VALVE, CHROME PLATED, METAL OSILLATING NON HOLD OPEN HANDLE, 1" I.PS. SCREW DRIVER ANGLE STOP WITH PROTECTIVE CAP. ADJUSTABLE TAILPIECE, VACUUM BREAKER FLUSH CONNECTION AND SPUD COUPLING FOR 1" TOP SPUD, WALL AND SPUD FLANGES, SOLID RING PIPE SUPPORT, AND 2" OFFSET TO AVOID GRAB BAR, MOUNT FLUSH VALVE HANDLE MAX 44" AFF. VALVE HANDLE SHALL BE INSTALLED

CONTOURED SEAT SHALL BE EXTRA HEAVY SOLID PLASTIC WITH OPEN FRONT LESS COVER. SEAT SHALL INCLUDE STAINLESS

STEEL SELF SUSTAINING CHECK HINGE FEATURE. BASIS OF DESIGN CHINA: KOHLER - K-4405 FLUSH VALVE: SLOAN ROYAL - 111

SEAT: CHURCH - NO. 295-SSC

ON "WIDE" SIDE OF SEAT.

URINAL WITH 1.0 GALLON FLUSH VALVE (H.C.)

VITREOUS CHINA, WALL HUNG, SIPHON JET, URINAL WITH 3/4" TOP SPUD, AND HANGER.

EXPOSED FLUSH VALVE, CHROME PLATED, SENSOR OPERATED, HARD WIRED, LESS HANDLE OPENING, 3/4" I.PS. SCREW DRIVER ANGLE STOP WITH PROTECTIVE CAP, ADJUSTABLE TAILPIECE, VACUUM BREAKER FLUSH CONNECTION AND SPUD COUPLING FOR 3/4" TOP SPUD, WALL AND SPUD FLANGES.

MOUNT 17" ABOVE FINISHED FLOOR TO RIM.

CHINA: KOHLER - K-4989-T FLUSH VALVE: SLOAN ROYAL - 186 FLOOR CARRIER: J.R. SMITH NO. 637

MS-1 MOP SINK

PRECAST TERRAZZO WITH STAINLESS STEEL CAP, 24" x 24" x 12", TERRAZZO SHALL BE MADE OF GREY MARBLE CHIPS CAST IN WHITE PORTLAND CEMENT TO PRODUCE A COMPRESSIVE STRENGTH OF NOT LESS THAN 3,000 P.S.I. TERRAZZO SURFACE SHALL BE GROUND AND POLISHED WITH ALL AIR HOLES AND / OR PITS TO BE GROUTED AND EXCESS REMOVED. DRAIN BODY SHALL BE STAINLESS STEEL CAST INTEGRAL, AND SHALL PROVIDE FOR A CAULKED LEAD CONNECTION AND NOT LESS THAN 1" DEEP TO A 3"


TYPE 304, 20-GAUGE STAINLESS STEEL SPLASH PANELS, 12" HEIGHT SECURED TO WALL ON 2 SIDES.

SERVICE FAUCET SHALL BE CHROME PLATED WITH RENEWABLE SEATS IN MONEL, VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACE, PAIL HOOK, AND 3/4" HOSE THREAD ON

PROVIDE MOP HANGER.

BASIS OF DESIGN SINK: WILLIAMS - SBC-1700 FAUCET: WILLIAMS - T-10VB MOP HANGER: WILLIAMS - T-40

PLUMBING SYMBOL LEGEND							
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION				
	DOMESTIC COLD WATER SUPPLY LINE		BOTTOM OF PIPING DROP				
	DOMESTIC HOT WATER SUPPLY LINE	IÓI	BALL VALVE				
	DOMESTIC WASTE WATER DRAIN LINE		1-WAY CLEANOUT				
	TURN IN PIPING		2-WAY CLEANOUT				









AKIN & ASSOCIATES

ARCHITECTS, INC.

RELEASED

FOR CONSTRUCTION

JOB NO.: 0906

CHECKED: THG

REVISIONS :

DATE: 03/10/10

3/22/10 ADDENDUM #1

CLIENT:

COLUMBIA COUNT **BOARD OF** COUNTY COMMISSIONER

PROJ. PHASE: 100% CONSTRUCTION

DOCUMENTS SHEET TITLE: **PLUMBING**

SHEET NO .:

AS SHOWN