

DATE 11/07/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023831

APPLICANT MELANIE RODER PHONE 752-2281
ADDRESS 387 SW KEMP CT LAKE CITY FL 32025
OWNER MATTHEW ERKINGER PHONE 754-5555
ADDRESS 563 SW HEATHRIDE DR LAKE CITY FL 32025
CONTRACTOR MATTHEW ERKINGER PHONE 754-5555
LOCATION OF PROPERTY 90 WEST, L INTO EMERALD COVE, 1/2 MILE ON HEATHRIDGE DR
TO TEEND AT THE CUL-DE-SAC

TYPE DEVELOPMENT SFD,UTILITY ESTIMATED COST OF CONSTRUCTION 104650.00
HEATED FLOOR AREA 2093.00 TOTAL AREA 2853.00 HEIGHT 23.00 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 7/12 FLOOR SLAB
LAND USE & ZONING RSF-2 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 0 FLOOD ZONE XPP DEVELOPMENT PERMIT NO.

PARCEL ID 33-3S-16-02438-116 SUBDIVISION EMERALD COVE
LOT 16 BLOCK PHASE 1 UNIT TOTAL ACRES .50

000000883 RR067135
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
CURB & GUTTER 05-1085-N BK JH N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: FLOOR 1 FOOT ABOVE THE ROAD, NOC ON FILE
WAIVER PERMIT DONE DUE TO CURB AND GUTTER-WAITING ON INFO FROM ROAD

DEPARTMENT Check # or Cash 15091

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 525.00 CERTIFICATION FEE \$ 14.27 SURCHARGE FEE \$ 14.27
MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 628.54
INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

Revised 9-23-04

For Office Use Only Application # 0510-80 Date Received 10-27-05 By LH Permit # 883/23831
 Application Approved by - Zoning Official BLK Date 01.11.05 Plans Examiner OK JTH Date 11-1-05
 Flood Zone X Per Plat Development Permit N/A Zoning RSF-2 Land Use Plan Map Category Res. Low Density
 Comments _____

Applicants Name Linda or Melanie Roder Phone 752-2281
 Address 387 S.W. Kemp Ct. Lake City FL 32024
 Owners Name Erkinger Home Builders Phone 754-5555
 911 Address 563 SW Heatheridge Dr. Lake City FL 32024
 Contractors Name Matthew Erkinger Phone 754-5555
 Address 248 S.E. Nassau St. Lake City FL 32025
 Fee Simple Owner Name & Address NA
 Bonding Co. Name & Address NA
 Architect/Engineer Name & Address Matthew Erkinger / Mark Disosway
 Mortgage Lenders Name & Address 1st Federal
 Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
 Property ID Number 33-35-16-02438-116 Estimated Cost of Construction 140,000
 Subdivision Name Emerald Cove Lot 16 Block _____ Unit _____ Phase 1
 Driving Directions 90 West 3/4 mi past Brown Rd go left on Emerald Cove Entrance, go 1/2 mile on Heatheridge Dr., go to end of road, lot is at end, in Cul de Sac
 Type of Construction SPD Number of Existing Dwellings on Property 0
 Total Acreage _____ Lot Size .5 Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 35' Side 39' Side 31' Rear 107'
 Total Building Height 23' Number of Stories 1 Heated Floor Area 2093 Roof Pitch 7-12
Porches 218 GARAGE 542 TOTAL 2853

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Owner Builder or Agent (Including Contractor) Linda R. Roder
 Commission #DD303275
 STATE OF FLORIDA
 COUNTY OF COLUMBIA
 Expires: Mar 24, 2008
 Bonded Thru
 Atlantic Bonding Co., Inc.

Contractor Signature Matthew Erkinger
 Contractors License Number RR-067135
 Competency Card Number _____
 NOTARY STAMP/SEAL

Sworn to (or affirmed) and subscribed before me
 this 1 day of September 2005
 Personally known ✓ or Produced Identification _____

Notary Signature

BUILDING SET BACKS:
FRONT: 25 FEET
SIDE: 10 FEET

CORPORATION
ZONE: A-3

CYPRESS LAKE PHASE



REGISTERED FLORIDA ENGINEER


COUNTY, FLORIDA

THIS IS TO CERTIFY THAT ON THIS 29 OF JULY 2005, GARY GILL, REGISTERED FLORIDA ENGINEER, AS SPECIFIED WITHIN CHAPTER 471, FLORIDA STATUTES, LICENSE NO. 51942, DOES HEREBY CERTIFY THAT ALL REQUIRED IMPROVEMENTS HAVE BEEN INSTALLED IN COMPLIANCE WITH THE APPROVED CONSTRUCTION PLANS AND IFF APPLICABLE, ANY SUBMITTED "AS-BUILT" BLUEPRINTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE BOARD OF COUNTY COMMISSIONERS OF COLUMBIA

CERTIFICATE OF SUBDIVIDER'S ENGINEER

UTILITIES SHALL ALSO BE EASEMENTS FOR THE CONSTRUCTION, INSTALLATION, MAINTENANCE AND OPERATION OF CABLE TELEVISION SERVICES.

ROAD RIGHT-OF-WAY



UTILITY EASEMENT DETAIL:

THE PROPERTY AS SURVEYED FALLS WITHIN ZONE "X" AS PER THE FLOOD INSURANCE RATE MAP OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY PANEL NO. 120070 0175B

FLOOD ZONE INFORMATION:

4	10°31'51"	350.00	64.33	32.25	54.27	59.24
5	5°11'01"	600.00	54.28	27.16	54.27	59.24
6	4°16'36"	600.00	44.79	22.40	44.77	54.27
7	16°37'03"	600.00	174.02	87.62	173.41	54.27
8	23°21'07"	600.00	244.54	123.99	242.85	54.27
10	31°48'42"	600.00	333.13	170.98	328.85	54.27
12	28°56'00"	420.00	212.09	108.36	209.85	54.27
13	90°00'00"	320.00	502.65	320.00	452.55	54.27
14	41°24'35"	30.00	21.68	11.34	21.21	54.27
15	172°49'09"	50.00	150.81	79.86	99.80	54.27
16	41°24'35"	30.00	21.68	11.34	21.21	54.27
17	5°11'01"	630.00	57.00	28.52	56.98	54.27
24	5°11'01"	570.00	51.57	25.80	51.55	54.27
25	16°37'03"	630.00	182.72	92.01	182.08	54.27
26	22°51'19"	570.00	227.37	115.22	225.87	54.27
33	23°48'03"	630.00	261.70	132.77	259.83	54.27
34	16°37'03"	570.00	165.32	83.24	164.74	54.27
35	31°48'42"	570.00	316.47	162.43	312.43	54.27
42	31°48'42"	630.00	349.79	179.53	345.31	54.27
43	70°25'00"	380.00	467.02	268.14	438.18	54.27
44	28°40'11"	480.00	240.18	122.66	237.88	54.27
45	17°55'35"	420.00	131.41	66.24	130.87	54.27
46	11°00'25"	420.00	80.69	40.47	80.56	54.27
47	16°05'49"	320.00	89.90	45.25	89.61	54.27
48	44°51'20"	320.00	250.52	132.08	244.17	54.27
49	3°40'27"	320.00	20.52	10.26	20.52	54.27
50	23°47'23"	320.00	132.87	67.40	131.91	54.27
51	1°35'01"	320.00	8.84	4.42	8.84	54.27
52	53°27'47"	50.00	46.66	25.18	44.98	54.27
53	73°44'23"	50.00	64.35	37.50	60.00	54.27
54	45°36'59"	50.00	39.81	21.03	38.76	54.27
62	11°04'28"	630.00	121.77	61.08	121.58	54.27
63	5°32'35"	630.00	60.95	30.50	60.93	54.27
64	4°45'03"	570.00	87.06	43.61	86.97	54.27
65	14°06'15"	570.00	140.31	70.51	139.96	54.27
81	9°54'02"	630.00	108.86	54.57	108.73	54.27
82	12°53'04"	630.00	141.67	71.14	141.37	54.27
83	7°16'50"	630.00	80.05	40.08	80.00	54.27
84	3°38'09"	630.00	39.98	20.00	39.97	54.27
85	4°01'28"	570.00	40.04	20.03	40.03	54.27
86	12°35'35"	570.00	125.28	62.89	125.03	54.27
87	8°53'27"	570.00	88.45	44.31	88.36	54.27
88	17°29'56"	570.00	174.09	87.73	173.41	54.27
89	5°25'20"	570.00	53.94	26.99	53.92	54.27
90	4°16'36"	630.00	47.02	23.52	47.01	54.27
100	4°16'36"	570.00	42.55	21.28	42.54	54.27
101	12°32'25"	630.00	137.89	69.22	137.61	54.27
102	11°41'56"	630.00	128.64	64.54	128.41	54.27
103	7°34'21"	630.00	83.26	41.69	83.20	54.27
104	37°46'47"	380.00	250.56	130.03	246.05	54.27
105	32°38'13"	380.00	216.46	111.25	213.54	54.27

PREPARED BY AND RETURN TO:

TERRY McDAVID
POST OFFICE BOX 1328
LAKE CITY, FL 32056-1328

Property Appraiser's Identification Number 02438-560 02421-000 Inst:2005023270 Date:09/21/2005 Time:14:55 Doc Stamp-Deed : 245.00 MK DC, P. DeWitt Cason, Columbia County B:1059 P:344

TM File No: 05-789

WARRANTY DEED

This Warranty Deed, made this 16th day of September, 2005, BETWEEN D D P CORPORATION, a Florida corporation, whose post office address is 4158 US Highway 90 West, Lake City, Florida 32055, of the County of Columbia, State of Florida, grantor, and ERKINGER HOME BUILDERS, INC., a Florida Corporation, whose post office address is 248 SE Nassau St., Lake City, Florida 32025, grantee.

(Whenever used herein the terms "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives and assigns of individuals, and the successors and assigns of corporations, trusts and trustees)

Witnesseth: that said grantor, for and in consideration of the sum of Ten Dollars (\$10.00), and other good and valuable considerations to said grantor in hand paid by said grantee, the receipt whereof is hereby acknowledged, has granted, bargained and sold to the said grantee, and grantee's heirs and assigns forever, the following described land, situate, lying and being in Columbia County, Florida, to-wit:

Lot 16, Emerald Cove, Phase 1, a subdivision according to the plat thereof recorded in Plat Book 8, Pages 35-36, public records, Columbia County, Florida.

Together with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.


To Have and to Hold, the same in fee simple forever.

And subject to taxes for the current year and later years and all valid easements and restrictions of record, if any, which are not hereby reimposed; and also subject to any claim, right, title or interest arising from any recorded instrument reserving, conveying, leasing, or otherwise alienating any interest in the oil, gas and other minerals. And grantor does warrant the title to said land and will defend the same against the lawful claims of all persons whomsoever, subject only to the exceptions set forth herein.

**Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan**
Permit Application Number: 05-1085N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

BRKINGER/CR 05-3148



1 inch = 50 feet

Site Plan Submitted By Paul L. L... Date 10/24/05
Plan Approved ☒ Not Approved ☐ Date 10/25/05

By Mrs. D. L... Columbia CPHU

Notes: _____

PREPARED BY AND RETURN TO:

TERRY McDAVID
POST OFFICE BOX 1328
LAKE CITY, FL 32056-1328
File No. 05-789

Inst:2005023272 Date:09/21/2005 Time:14:57

YMK DC, P. DeWitt Cason, Columbia County B:1059 P:354

PERMIT NO. _____

TAX FOLIO NO.: 02438-000 & 02421-000

NOTICE OF COMMENCEMENT

STATE OF FLORIDA
COUNTY OF COLUMBIA

The undersigned hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

1. Description of property:

Lot 16, Emerald Cove, Phase 1, a subdivision according to the plat thereof recorded in Plat Book 8, Pages 35-36, public records, Columbia County, Florida.

2. General description of improvement: Construction of dwelling

3. Owner information:

a. Name and address: Erkinger Home Builders, Inc., 248 SE Nassau St., Lake City, Florida 32025.

b. Interest in property: Fee Simple

c. Name and address of fee simple title holder (if other than Owner):

4. Contractor: Erkinger Home Builders, Inc., 248 SE Nassau St., Lake City, Florida 32025.

5. Surety

a. Name and address: None

b. Amount of bond:

6. Lender: FIRST FEDERAL SAVINGS BANK OF FLORIDA, 4705 West US Highway 90, Lake City, Florida 32055.


7. Persons within the State of Florida designated by Owner upon whom notices or other documents may be served as provided by Section 713.13(1)(a)7., Florida Statutes: None

8. In addition to himself, Owner designates Attn: Teresa Davis, FIRST FEDERAL SAVINGS BANK OF FLORIDA, 4705 West US Highway 90, Lake City, Florida 32055, to receive a copy of the Lienor's Notice as provided in Section 713.13(1)(b), Florida Statutes.

9. Expiration date of notice of commencement (the expiration date is 1 year from the date of recording unless a different date is specified). September 16, 2006.

STATE OF FLORIDA, COUNTY OF COLUMBIA
I HEREBY CERTIFY that the above and foregoing
is a true copy of the original filed in this office.
P. DeWITT CASON, CLERK OF COURTS


By Manuel Kuen
Deputy Clerk
Date Sept 21, 2005



ERKINGER HOME BUILDERS, INC.


By: Matthew A. Erkinger, Sr.
President

The foregoing instrument was acknowledged before me this 16th day of September, 2005, by Matthew A. Erkinger, Sr., President of Erkinger Home Builders, Inc., a Florida corporation, on behalf of the corporation. He is personally known to me and did not take an oath.



Karen M. Wright
Notary Public
My commission expires: _____

Er. Kinger Lot 16 Emerald Cove
Site Plan





Phone (386) 755-3611
Fax (386) 752-5381

Notice of Intent for Preventative Treatment for Termites

(As required by Florida Building Code (FBC) 104.2.6)

Aspen Pest Control, Inc.
(386) 755-3611
State License # - JB109476
State Certification # - JF104376

Lot # 16 Emerald Cove - Lake City, FL 32055

Address of Treatment or Lot/Block of Treatment

Bora-Care Wood Treatment - 23% Disodium Octaborate Tetrahydrate

Method of Termite Prevention Treatment - Soil Barrier, Wood Treatment, Bait System, Other

Application onto Structural Wood

Description of Treatment

The above named structure will receive a complete treatment for the prevention of subterranean termites at the dried-in stage of construction. Treatment is done in accordance with the rules and laws established by the Florida Department of Agriculture and Consumer Services and according to EPA registered label directions as stated in Florida Building Code Section 1861.1.8.


Authorized Signature

9-12-05
Date



Commercial - Residential
301 NW Cole Terrace / Lake City, Florida 32015



CLYATT WELL DRILLING, INC.

Established in 1971
Post Office Box 180
Worthington Springs, Florida 32697
Phone (386)496-2488 FAX (386)496-4640

INVOICE DATE

3/31/2003

INVOICE NUMBER

WELL SPECS

DUE AND PAYABLE UPON RECEIPT

CUSTOMER NAME AND ADDRESS

Erkinger Home Builders
Attn.: Matthew A. Erkinger
248 Southeast Nassau Street
Lake City, Florida 32025

DESCRIPTION OF WORK

4" Well and Pump

QTY	DESCRIPTION	PRICE	SUB-TOTAL
	Feet 4" Well 1 HP Submersible Pump 1-1/4" Galvanized Pipe 14/3 Submersible Pump Wire With Ground WF255 (220 Gallon Equivalent) Tank 4 X 1-1/4 Well Seal Pressure Relief Valve Controls & Fittings		

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

0510-80

Reference to: Build permit application Number:

**Erkinger Home Builders Owner Erkinger Home Builders lot 16 of
Emerald Cove Subdivision**


On the date of November 2, 2005 application 0510-80 and plans for construction of a single family dwelling were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

**Please include application number 0510-81 when making
reference to this application.**

- ✓ 1. Application 0510-80 which was filed with the building department on the date of October 27, 2005 will be reviewed under the Florida Building Code 2004. The Wind Load design by Mr. Mark Disosway was design under the Florida Building Code 2001. The wind Load design should reflect the code sections of the Florida Building Code 2004 that relate to wind Load design code requirements.
2. Please show compliance with sections R309 of the FRC-2004 R309.1 Opening protection. Openings from a private garage directly into a room used for sleeping purposes shall not be permitted. Other openings between the garage and residence shall be equipped with solid wood doors not less than 13/8 inches (35 mm) in thickness, solid or honeycomb core steel doors not less than 13/8 inches (35 mm) thick, or 20-minute fire-rated doors. R309.1.1 Duct penetration: Ducts in the garage and ducts penetrating the

walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel or other approved material and shall have no openings into the garage. R309.2 Separation required: The garage shall be separated from the residence and its attic area by not less than ½-inch (12.7 mm) gypsum board applied to the garage side. Garages beneath habitable rooms shall be separated from all habitable rooms above by not less than 5/8-inch (15.9 mm) Type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than ½-inch (12.7 mm) gypsum board or equivalent.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	Lt 16 Phase 1 Emerald Cove	Builder:	Erkinger Homes
Address:		Permitting Office:	Columbia County
City, State:	Lake City, FL	Permit Number:	23831
Owner:	Erkinger Homes	Jurisdiction Number:	221000
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 42.0 kBtu/hr SEER: 10.00
3. Number of units, if multi-family	1	b. N/A	
4. Number of Bedrooms	3	c. N/A	
5. Is this a worst case?	No	13. Heating systems	
6. Conditioned floor area (ft²)	2093 ft²	a. Electric Heat Pump	Cap: 42.0 kBtu/hr HSPF: 7.00
7. Glass area & type	Single Pane Double Pane	b. N/A	
a. Clear glass, default U-factor	0.0 ft² 307.0 ft²	c. N/A	
b. Default tint, default U-factor	0.0 ft² 0.0 ft²	14. Hot water systems	
c. Labeled U-factor or SHGC	0.0 ft² 0.0 ft²	a. Electric Resistance	Cap: 50.0 gallons EF: 0.91
8. Floor types		b. N/A	
a. Slab-On-Grade Edge Insulation	R=0.0, 194.0(p) ft	c. N/A	
b. N/A		15. HVAC credits	
c. N/A		(CF-Ceiling fan, CV-Cross ventilation, HF-Whole house fan, PT-Programmable Thermostat, MZ-C-Multizone cooling, MZ-H-Multizone heating)	
9. Wall types			
a. Frame, Wood, Exterior	R=11.0, 1433.0 ft²		
b. Frame, Wood, Adjacent	R=11.0, 155.0 ft²		
c. N/A			
d. N/A			
e. N/A			
10. Ceiling types			
a. Under Attic	R=30.0, 2093.0 ft²		
b. N/A			
c. N/A			
11. Ducts			
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 190.0 ft		
b. N/A			

Glass/Floor Area: 0.15

Total as-built points: 29278

Total base points: 30005

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: [Signature]DATE: 9-26-05

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.

OWNER/AGENT: [Signature]DATE: 10-30-05

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.



BUILDING OFFICIAL: _____

DATE: _____

SUMMER CALCULATIONS
Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, Fl,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt			Area X SPM X SOF = Points			
.18	2093.0	20.04	7549.9	Double, Clear	N	1.5	8.0	99.0	19.20	0.97	1838.6
				Double, Clear	E	1.5	8.0	6.0	42.06	0.96	241.7
				Double, Clear	S	1.5	8.0	198.0	35.87	0.92	6556.8
				Double, Clear	W	1.5	8.0	4.0	38.52	0.96	147.6
				As-Built Total:			307.0			8784.7	
WALL TYPES Area X BSPM = Points				Type	R-Value			Area X SPM = Points			
Adjacent	155.0	0.70	108.5	Frame, Wood, Exterior	11.0			1433.0	1.70	2436.1	
Exterior	1433.0	1.70	2436.1	Frame, Wood, Adjacent	11.0			155.0	0.70	108.5	
Base Total:		1588.0	2544.6	As-Built Total:			1588.0			2544.6	
DOOR TYPES Area X BSPM = Points				Type	Area X SPM = Points						
Adjacent	21.0	2.40	50.4	Adjacent Wood				21.0	2.40	50.4	
Exterior	0.0	0.00	0.0								
Base Total:		21.0	50.4	As-Built Total:			21.0			50.4	
CEILING TYPES Area X BSPM = Points				Type	R-Value			Area X SPM X SCM = Points			
Under Attic	2093.0	1.73	3620.9	Under Attic	30.0			2093.0	1.73 X 1.00	3620.9	
Base Total:		2093.0	3620.9	As-Built Total:			2093.0			3620.9	
FLOOR TYPES Area X BSPM = Points				Type	R-Value			Area X SPM = Points			
Slab	194.0(p)	-37.0	-7178.0	Slab-On-Grade Edge Insulation	0.0			194.0(p)	-41.20	-7992.8	
Raised	0.0	0.00	0.0								
Base Total:			-7178.0	As-Built Total:			194.0			-7992.8	
INFILTRATION Area X BSPM = Points				Area X SPM = Points							
		2093.0	10.21			2093.0			10.21	21369.5	

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, Fl,

PERMIT #:

BASE				AS-BUILT							
Summer Base Points: 27957.3				Summer As-Built Points: 28377.3							
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
27957.3		0.4266	11926.6	28377.3		1.00	1.138	0.341	1.000	11018.9	

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt			Area X WPM X WOF = Points			
.18	2093.0	12.74	4799.7	Double, Clear	N	1.5	8.0	99.0	24.58	1.00	2435.3
				Double, Clear	E	1.5	8.0	6.0	18.79	1.02	115.0
				Double, Clear	S	1.5	8.0	198.0	13.30	1.04	2741.0
				Double, Clear	W	1.5	8.0	4.0	20.73	1.01	83.8
				As-Built Total:							307.0
WALL TYPES Area X BWPM = Points				Type	R-Value			Area X WPM = Points			
Adjacent	155.0	3.60	558.0	Frame, Wood, Exterior			11.0	1433.0	3.70		5302.1
Exterior	1433.0	3.70	5302.1	Frame, Wood, Adjacent			11.0	155.0	3.60		558.0
Base Total:		1588.0	5860.1	As-Built Total:				1588.0			5860.1
DOOR TYPES Area X BWPM = Points				Type	Area X WPM = Points						
Adjacent	21.0	11.50	241.5	Adjacent Wood				21.0	11.50		241.5
Exterior	0.0	0.00	0.0								
Base Total:		21.0	241.5	As-Built Total:				21.0			241.5
CEILING TYPES Area X BWPM = Points				Type	R-Value			Area X WPM X WCM = Points			
Under Attic	2093.0	2.05	4290.6	Under Attic			30.0	2093.0	2.05 X 1.00		4290.6
Base Total:		2093.0	4290.6	As-Built Total:				2093.0			4290.6
FLOOR TYPES Area X BWPM = Points				Type	R-Value			Area X WPM = Points			
Slab	194.0(p)	8.9	1726.6	Slab-On-Grade Edge Insulation			0.0	194.0(p)	18.80		3647.2
Raised	0.0	0.00	0.0								
Base Total:			1726.6	As-Built Total:				194.0			3647.2
INFILTRATION Area X BWPM = Points				Area X WPM = Points							
		2093.0	-0.59	-1234.9				2093.0	-0.59		-1234.9

WINTER CALCULATIONS
Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT						
Winter Base Points:		15683.6		Winter As-Built Points:		18179.7				
Total Winter Points	X	System Multiplier	= Heating Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points
15683.6		0.6274	9839.9	18179.7	1.000	1.000	(1.069 x 1.169 x 0.93)	0.487	1.000	10292.5
				18179.7	1.00	1.162		0.487	1.000	10292.5

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, Fl,

PERMIT #:

BASE					AS-BUILT					
WATER HEATING										
Number of Bedrooms	X	Multiplier	=	Total	Tank Volume	EF	Number of Bedrooms	X	Tank X Ratio	Credit X Multiplier = Total
3		2746.00		8238.0	50.0	0.91	3		1.002655.47	1.007966.4
					As-Built Total:					7966.4

CODE COMPLIANCE STATUS							
BASE				AS-BUILT			
Cooling Points	+	Heating Points	= Total Points	Cooling Points	+	Heating Points	= Total Points
11927		9840	30005	11019		10292	29278
		8238				7966	

PASS



Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

New Construction Subterranean Termite Soil Treatment Record

OMB Approval No. 2502-0525
(exp. 10/31/2005)

This form is completed by the licensed Pest Control Company.

Public reporting burden for this collection of information is estimated to average 15 minutes per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. This information is mandatory and is required to obtain benefits. HUD may not collect this information, and you are not required to complete this form, unless it displays a currently valid OMB control number.

Section 24 CFR 200.926d(b)(3) requires that the sites for HUD insured structures must be free of termite hazards. This information collection requires the builder to certify that an authorized Pest Control company performed all required treatment for termites, and that the builder guarantees the treated area against infestation for one year. Builders, pest control companies, mortgage lenders, homebuyers, and HUD as a record of treatment for specific homes will use the information collected. The information is not considered confidential.

This report is submitted for informational purposes to the builder on proposed (new) construction cases when soil treatment for prevention of subterranean termite infestation is specified by the builder, architect, or required by the lender, architect, FHA, or VA.

All contracts for services are between the Pest Control Operator and builder, unless stated otherwise.

23831

Section 1: General Information (Treating Company Information)

Company Name: Aspen Pest Control, Inc.
Company Address: 301 NW Cole Terrace City Lake City State FL Zip 32055
Company Business License No. JB109476 Company Phone No. 386-755-3611
FHAVA Case No. (if any) _____

Section 2: Builder Information

Company Name: Erkinge Home Builders Company Phone No. _____

Section 3: Property Information

Location of Structure(s) Treated (Street Address or Legal Description, City, State and Zip) 563 Heatherdale Drive
Lake City, FL

Type of Construction (More than one box may be checked) ☒ Slab ☐ Basement ☐ Crawl ☐ Other _____
Approximate Depth of Footing: Outside 0 Inside 0 Type of Fill 0

Section 4: Treatment Information

Date(s) of Treatment(s) 2-15-06
Brand Name of Product(s) Used Boro-Eco
EPA Registration No. 64405-1
Approximate Final Mix Solution % 73%
Approximate Size of Treatment Area: Sq. ft. 2453 Linear ft. 0 Linear ft. of Masonry Voids 0
Approximate Total Gallons of Solution Applied 3
Was treatment completed on exterior? ☒ Yes ☒ No
Service Agreement Available? ☒ Yes ☐ No

Note: Some state laws require service agreements to be issued. This form does not preempt state law.

Attachments (List) _____

Comments _____

Name of Applicator(s) Steve Brannon Certification No. (if required by State law) JB104376

The applicator has used a product in accordance with the product label and state requirements. All treatment materials and methods used comply with state and federal regulations.

Authorized Signature Steve Brannon Date 2-15-06

Warning: HUD will prosecute false claims and statements. Conviction may result in criminal and/or civil penalties. (18 U.S.C. 1001, 1010, 1012; 31 U.S.C. 3729, 3802)

Form NPCA-99-B may still be used

form HUD-NPCA-99-B (04/2003)

Reorder Product #2581 • from CROWNMAX • 1-800-252-4011

COLUMBIA COUNTY FLORIDA DEPARTMENT OF BUILDING AND ZONING

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 33-3S-16-02438-116

Building permit No. 000023831

Use Classification SFD, UTILITY

Fire: 17.76

Permit Holder MATTHEW ERKINGER

Waste: 36.75

Owner of Building MATTHEW ERKINGER

Total: 54.51

Location: 563 SW HEATHRIDGE DR(EMERALD COVE, LOT 16)

Date: 07/07/2006



Harry Dickel

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)


This unit is A.C.A. certified as a heater with 99% heat efficiency.

No chimney or flue system required.

With selection of factory installed optional extras.



VF-4000

- 19,000 - 23,000 Btu/hr with manual control valve
- 19,500 - 25,000 Btu/hr with millivolt control valve
- Fully assembled and ready to install
- Attractive wood surrounds available
- 15" x 30" fixed or operable screen opening



VF-5000


- 25,000 Btu/hr millivolt variable heat output
- 15" X 30" glass or screen viewing area
- Clean burning, safe and easy to install
- Realistic charred oak logs with glowing embers




VF-6000

- 52,000 Btu/hr millivolt variable heat output
- Beautiful 20" X 34" glass or screen viewing area
- Will operate during a power failure
- Designed for large rooms

SUPERIOR



7-5000



1. **THE**
 2. **THE**
 3. **THE**
 4. **THE**
 5. **THE**
 6. **THE**
 7. **THE**
 8. **THE**
 9. **THE**
 10. **THE**
 11. **THE**
 12. **THE**
 13. **THE**
 14. **THE**
 15. **THE**
 16. **THE**
 17. **THE**
 18. **THE**
 19. **THE**
 20. **THE**
 21. **THE**
 22. **THE**
 23. **THE**
 24. **THE**
 25. **THE**
 26. **THE**
 27. **THE**
 28. **THE**
 29. **THE**
 30. **THE**
 31. **THE**
 32. **THE**
 33. **THE**
 34. **THE**
 35. **THE**
 36. **THE**
 37. **THE**
 38. **THE**
 39. **THE**
 40. **THE**
 41. **THE**
 42. **THE**
 43. **THE**
 44. **THE**
 45. **THE**
 46. **THE**
 47. **THE**
 48. **THE**
 49. **THE**
 50. **THE**
 51. **THE**
 52. **THE**
 53. **THE**
 54. **THE**
 55. **THE**
 56. **THE**
 57. **THE**
 58. **THE**
 59. **THE**
 60. **THE**
 61. **THE**
 62. **THE**
 63. **THE**
 64. **THE**
 65. **THE**
 66. **THE**
 67. **THE**
 68. **THE**
 69. **THE**
 70. **THE**
 71. **THE**
 72. **THE**
 73. **THE**
 74. **THE**
 75. **THE**
 76. **THE**
 77. **THE**
 78. **THE**
 79. **THE**
 80. **THE**
 81. **THE**
 82. **THE**
 83. **THE**
 84. **THE**
 85. **THE**
 86. **THE**
 87. **THE**
 88. **THE**
 89. **THE**
 90. **THE**
 91. **THE**
 92. **THE**
 93. **THE**
 94. **THE**
 95. **THE**
 96. **THE**
 97. **THE**
 98. **THE**
 99. **THE**
 100. **THE**

Original
FD-302 (Rev. 1-25-60)

THE

Control shown in new development

THE

WALLACE STEVENS
THE NEW YORK PUBLIC
LIBRARY
ASTEN LENOX TILDEN FOUNDATION
100 N. 5TH ST.
NEW YORK, N.Y.

Bring Leaves in
(For VZ-4 only)

Archives
Per. 10-5-1965

CLASS OF 2000
WAS 17-5 IN 1998


EXTRA BOLD,
FOR VP-5 & VP-6 ONLY

THE NEW YORK
PUBLIC LIBRARY
ASTOR LENOX TILDEN FOUNDATION
125 WEST 47TH STREET
NEW YORK 19

Wall thickness
12-14mm, 15-18mm

SURROGATES

The **Champion Paper Survival** is hand-crafted using a combination of solid **Poplar** and **Pine**, which being the strongest type of Paper allows you the option to **save** against the **majority** financial downturn. The survival is **hand-crafted** using **only** a **select** **own** **tree** **and** **plant** **and** **water** **and** **land**.



Distributed by


Working Product Development

Big Change

	Normal	Stressed
Very good	24,000 - 25,000	14,000 - 15,000
Good	19,500 - 23,000	13,500 - 18,000
Fair	25,000 - 32,000	23,000 - 37,000

[illegible]

These features and functions are not new. Plastic design
has been around for decades. The only difference is that
now it's more than just a design. It's a way of life. It's
a way of thinking. It's a way of doing things. It's a way
of being. It's a way of living. It's a way of...
© 1994 by A.G.A. Design & Development



www.CambridgeIslandProducts.com


DATE FORWARDED MAY 19 1971

Printed in U.S.A. ©2001 American Electric Products • 1118 West 2nd Ave., Ontario, CA 92303-4130
 American Electric Products Corp. may have filed for copyright notice in U.S. Patent #5,980,000.

22 1475:40 0002 10 FRY

FOR NO. 1-386 BCL BCL 4735

FROM LAKE CITY INDUSTRIES

[illegible]

DATE	TIME	LOCATION	STATUS	REMARKS
16	7	23	3	5 2 IN

	
GALCO BASELINE ROAD HARTFORD, CT 06105	
ORDER NO.	ORDERING BY
DATE	QUANTITY
UNIT	PRICE
TOTAL	TOTAL
NAME	ADDRESS
CITY	STATE
ZIP	COUNTRY
PHONE	FAX
E-MAIL	COMMENTS
ORDER NO.	ORDERING BY
DATE	QUANTITY
UNIT	PRICE
TOTAL	TOTAL
NAME	ADDRESS
CITY	STATE
ZIP	COUNTRY
PHONE	FAX
E-MAIL	COMMENTS

WEST 6274183 ON FILE **WASH 10/19/68** 64-2030

DESIGN LOAD +200 PSF & -200 PSF
TEST LOAD +300 PSF & -300 PSF
STERN APPLIED MTR COMPANY

INSIDE ELEVATION

16'-0" MAX. WIDTH

LE CA. AND BENTONITE. THE TOP OF THE
UNSATURATED ZONE IS AT THE BOTTOM SECTION,
AND THE BOTTOM OF THE SATURATED ZONE IS AT THE TOP OF THE BOTTOM SECTION.

SEC 6-1

VERTICAL
TRACK, 06 GAZ

7-0
MAX.
HEIGHT

(A) SECTION FOUR

100

NOT PART OF THIS CASE
EXCLUDED FROM DISCLOSURE
TERMINAL PENDING APPLICATION

A. a. used by time or occasion of speaking.


RESULTS:
1. REACTED TO POSITIVE AND NEGATIVE IN PPS REACT
2. AND POSITIVE AND NEGATIVE IN PPS WITH COMMENTS
FOR ASTA E-150

3. INDEPENDENT LITIGATION OF OTHER SIDE IS NOT ALLOWED.
4. THE STAFF ACCOUNT BY THEM MUST BE COORDINATE WITH THE STATE TREASURY.
7. FINANCIAL RECORDS AT ALL APPOINTMENT POINT

Jun. 28 2004 07:38AM P3

FIG. NO. 1:385-754-9993


FROM: Columbia Door Company




FASTENER ATTACHMENT



This seal is to be used only on the door. The sealant is a special compound that will fill the gap between the door and the frame. It is not to be used on any other part of the door.




SEC. D-D



SEC. E-E



SEC. F-F



SEC. A-A

COLUMBIA DOOR COMPANY
1000 N. 10th St., Milwaukee, Wis. 53233
Tel. 414-385-7544
Fax 414-385-7545
E-Mail: sales@cdco.com
Web: www.cdco.com

SEE PAGE 1 FOR MATERIALS LIST
SEE PAGE 2 FOR FINISHES
SEE PAGE 3 FOR OPTIONS
SEE PAGE 4 FOR ACCESSORIES
SEE PAGE 5 FOR INSTALLATION
SEE PAGE 6 FOR MAINTENANCE

FIG. NO. 1:385-754-9993



March 6, 2002

Subject: Elk Product Approval Information

All Prestique® and Capstone® products manufactured in Tuscaloosa, AL are certified under the Miami - Dade County Building Code Office (BCCO). These products also meet the requirements for the Florida Building Code since they are MD approved. The following test protocols must be passed by each of the products in order for MD product certification:

ASTM D3462

PA 100 (110 mph uplift and wind driven rain resistance)

PA 107 (Modified ASTM D3161 - 110 mph wind uplift resistance)

The nailing patterns that were used during the PA 100 and PA 107 wind test protocols for the Prestique and Capstone products are listed below. Also listed below are the Miami - Dade Notice of Acceptance Numbers (NOA).

Raised Profile, Prestique High Definition, Prestique 25, or Prestique 30 -

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.04

Prestique I 35 or Prestique I* -

PA 100 = 4 nails

PA 107 = 5 nails

MD NOA# = 01-1226.05

Prestique Plus or Prestique Gallery Collection* -

PA 100 = 4 nails

PA 107 = 4 nails

MD NOA# = 01-1226.03

Capstone*

PA 100 = 4 Nails

PA 107 = 4 Nails

MD NOA# = 01-0523.01

* As per the Elk Limited Warranty, six nails are required for the Elk high wind warranty.


If there are any questions please contact:

Mike Reed - Technical Manager:
(205) 342-0287

or

Daniel DeJarnette - QA Engineer
(205) 342-0298

1997



Web Content

30-year lifetime warranty covering non-approved coverage for strokes and subsequent labor for the entire 5 years. Once an owner for transference, provides coverage for subsequent labor and strokes for balance of limited warranty period. 5-year limited warranty period. 5-year limited warranty period.

30-year limited warranty period
non-extended coverage for
drivings and maintenance labor for
the initial 5 years, plus an option
for "transferability" - extended
coverage for application labor and
drivings for lifetime of vehicle
warranty period 5-year drivings
with warranty.

Last Estimate

40-year limited warranty protects
ret-rofitted coverage for
shingles and application labor for
the entire 5 years, plus an option
for "permanency": provided
coverage for corrosion, mold and
shingles for balance of lifetime
warranty period 5-year limited
and permanent

HIP AND RIDGE SHINGLES

Size: 12"x 12"
Emboss: 24"
Pieces/Bundle: 48
Coverage: 4 Bundles = 100 Linear Feet

High Definition

30-year lifetime warranty period, comprehensive coverage for shingles and replacement labor for the next 5 years, plus an option for "Third-Party": increased coverage for replacement labor and shingles for balance of lifetime warranty period; 5-year limited wind warranty.

32 Bureaus/Parcel
12 Salaries/Truck
638 Bureaus/Truck
10 Pieces/Bureau
1 Bureau = 120.32 (per '90)

ALL PROBLEMS, RAINBOW PRINCE AND SUNNY HILLS are registered trademarks owned by C.H. Wirthsmeier® company. Wirthsmeier® designs work with the main hand, because attention must be paid to the main hand. A word can be considered registered under the main hand and the main hand.

Check for availability with *Stat-in-Situ*™ treatment to reveal the decoloration of roofing granules caused by the growth of certain types of algae. Not available in Scandinavia.

ASTM Specifications D 3012, Type-C; D 3101, Type-I; E 168 and the requirements of ASTM D 3482.

All Pratique and Raised Profile shingles meet the latest Metric Code building code requirements.

© 1994 by The McGraw-Hill Companies, Inc.

SPECIFIC ATLAS

Save Work Includes Arranging all labor, materials and equipment necessary to complete remainder of (1990) design specified plans. Color shall be (white or color).
 100 and 1000 gpa to be (100 and 1000 gpa) used.

All exposed metal surfaces (flashing, vent, etc.) to be painted with matching E.P. roof accessory paint.

Partitions or Roof Deck, Roof Joist to one dry, well-ventilated 1" x 2" (24mm x 12.7mm) board; exterior-grade plywood (exposed 1" rated sheathing is about 1/2" (12.7mm) thick conforming to the specifications of the American Plywood Association, 718 (194mm) stored horizontally or vertically. Most fire retardant plywood decks are NOT approved substitutes for 1" (25mm) sheathing. Consult the Field Service for application specifications over other cases or other system.

Minimum Underlayment for shingle roof slopes. 4" or less: 157.5/204 sq. ft. or greater: 100 sq. ft. or greater. No. 15 or 30 asphalt shingles for underlayment, 1 sq. ft. or less: 4 sq. ft. or less (157.5/204 sq. ft. to a minimum of 2 sq. ft. (157.5/204 sq. ft.)). 100-150 sq. ft. of underlayment overlapped a minimum of 10". Fasteners shall be of sufficient length and loading power to support several sq. ft. of the shingles. The shingles shall be secured as required by the applicable manufacturer's instructions or as shown on the drawing.

For cross-wire signs is a standard, shingles shall be laminated with Star-Guard treatment, as manufactured by the E.I. du Pont de Nemours and Company, Inc., or its subsidiaries, and shall be applied to the back of the sign.

Complete application instructions are supplied by ERI and printed on the back of every sample packet. A

Manufacturers are cautioned against the correct interpretation of the instructions. These instructions are the minimum required to meet the equipment requirements. In some areas, building codes may require different application techniques or methods beyond our instructions. In these cases, the user code must be followed under no circumstances will EIC accept liability on requirements less than those contained in its application instructions.

For specifications or CSI 'online call 800.354.SPEC (7753)
or e-mail 130275@csiconsult.com

**SOUTHEAST &
ATLANTIC OFFICE:
800.945.5551**

CORPORATE HEADQUARTERS:
800.354.7732

PLANT LOCATION:
ECO.945.5545

ELK
www.elkcorp.com

Architectural Testing

AAMA/NWWDA 101/LS.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/LS.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high


Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen N. Rumm
1 APRIL 2002



Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.


Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen H. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max


Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002



Test Specimen Description: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry


Optional Performance

4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"	0.26" max.
	@ 47.2 psf (negative)	0.46"	0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*


Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"

Allen N. Reeves
1 APRIL 2002



Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:



Mark A. Hess
Technician

MAH:nib
01-41134.01




Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



FIBERGLASS DOORS

APPROVED ARRANGEMENT:



Test Data Review Certificate #3026447A: #3026447B;
#3026447C and COP/Test Report Validation Matrix
#3026447A-001, 002, 003; #3026447B-001, 002, 003;
#3026447C-001, 002, 003 provides additional
information - available from the ITS/WH website
(www.itssemko.com), the Masonite website
(www.masonite.com) or the Masonite technical center.

Note:

Units of other sizes are covered by this
report as long as the panels used do not
exceed 3'0" x 6'8".

Double Door with 2 Sidelites
Maximum unit size = 8'4" x 6'8"

Design Pressure
+55.0/-55.0

limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national,
state or local building codes specify the edition required.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0005-02 or
MAD-WL-MA0008-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0005-02.

APPROVED DOOR STYLES:



Flush



6-panel



New England 4-panel



Eyebrow 4-panel



9-panel



Eyebrow 5-panel with scroll

Oakcraft
Wood-grain textured
FIBERGLASS ENTRY DOORS

June 17, 2002

Our continuing program of product improvements makes specifications, design and product
detail subject to change without notice.

ARTEK
Non-textured Fiberglass Entry Doors

PREMDOR Collection
Premium Quality Doors



Exclusively from:

Masonite
Masonite International Corporation

FIBERGLASS DOORS

APPROVED SIDELITE STYLES:



129 Series



200 Series



12R, 12L, 23R, 23L, 24R, 24L
Series



450 Series



152 Series



149 Series

CERTIFIED TEST REPORTS:

CTLA-772W-2

Certifying Engineer and License Number: Ramesh Patel, P.E./20224

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Door panels constructed from 0.075" minimum thick fiberglass skins. Both stiles constructed of 1-5/8" laminated lumber. Top end rails constructed of 31/32" wood. Bottom end rails constructed of 31/32" wood composite. Interior cavity of slab filled with rigid polyurethane foam core.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533




Test Data Review Certificate #3026447A;
#3026447B; #3026447C and COP/Test
Report Validation Matrix #3026447A-
001, 002, 003; #3026447B-001, 002,
003; #3026447C-001, 002, 003
provides additional information -
available from the ITS/WH website
(www.itswh.com), the Masonite
website (www.masonite.com) or the
Masonite technical center.

X

Glazed Inswing Unit

COP-WL-JH4141-02

WOOD-EDGE STEEL DOORS**APPROVED ARRANGEMENT:****Note:**

Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".

Single Door
Maximum unit size = 3'0" x 6'8"

Design Pressure
+40.5/-40.5

Limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itsmko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0001-02 and MAD-WL-MA0041-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0001-02.

APPROVED DOOR STYLES:**1/4 GLASS:**

100 Series



133, 135 Series



136 Series



680 Series



822 Series

1/2 GLASS:

105 Series*



106, 160 Series*



129 Series*



200 Series*



12 R/L, 23 R/L, 24 R/L Series*



107 Series*



108 Series



304 Series

*This glass kit may also be used in the following door styles: 5-panel; 5-panel with scroll; Eyebrow 5-panel; Eyebrow 5-panel with scroll.

1

Johnson
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite
Masonite International Corporation

X

Glazed Inswing Unit

COP-WL-JH4141-02

WOOD-EDGE STEEL DOORS**APPROVED DOOR STYLES:
3/4 GLASS:**

404 Series




410 Series




450 Series

FULL GLASS:

109 Series

114, 120, 122
Series

152 Series



149 Series



300 Series

CERTIFIED TEST REPORTS:

NCTL 210-1897-7, 8, 9, 10, 11, 12; NCTL 210-1861-4, 5, 6, 10, 11, 12; NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA202.

Evaluation report NCTL-210-2794-1

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core. Slab glazed with insulated glass mounted in a rigid plastic lip lite surround.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:TESTED IN
ACCORDANCE WITH
MIAMI-DADE BCCO PA202COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

State of Florida, Professional Engineer
Kurt Balthazor, P.E. - License Number 56533

Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itswh.com), the Masonite website (www.masonite.com) or the Masonite technical center.

Johnson
EntrySystems

June 17, 2002

Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite International Corporation

Residential System Sizing Calculation

Summary

Erkinger Homes
Lake City, FL

Project Title:
Lt 16 Phase 1 Emerald Cove

Code Only
Professional Version
Climate: North


9/26/2005

Location for weather data: Jacksonville - User customized: Latitude(30) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (78F) Humidity difference(49gr.)			
Winter design temperature	32 F	Summer design temperature	99 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	38 F	Summer temperature difference	24 F
Total heating load calculation	34165 Btuh	Total cooling load calculation	32789 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	122.9 42000	Sensible (SHR = 1)	175.0 42000
Heat Pump + Auxiliary(0.0kW)	122.9 42000	Latent	0.0 0
		Total (Electric Heat Pump)	128.1 42000

WINTER CALCULATIONS

Winter Heating Load (for 2093 sqft)


Load component		Load	
Window total	307 sqft	8473	Btuh
Wall total	1588 sqft	5151	Btuh
Door total	21 sqft	193	Btuh
Ceiling total	2093 sqft	2721	Btuh
Floor total	194 ft	5975	Btuh
Infiltration	240 cfm	10024	Btuh
Subtotal		32538	Btuh
Duct loss		1627	Btuh
TOTAL HEAT LOSS		34165	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 2093 sqft)

Load component		Load	
Window total	307 sqft	5529	Btuh
Wall total	1588 sqft	3846	Btuh
Door total	21 sqft	268	Btuh
Ceiling total	2093 sqft	3307	Btuh
Floor total		0	Btuh
Infiltration	222 cfm	5870	Btuh
Internal gain		3000	Btuh
Subtotal(sensible)		21819	Btuh
Duct gain		2182	Btuh
Total sensible gain		24001	Btuh
Latent gain(infiltration)		7408	Btuh
Latent gain(internal)		1380	Btuh
Total latent gain		8788	Btuh
TOTAL HEAT GAIN		32789	Btuh



EnergyGauge® System Sizing based on ACCA Manual J.

PREPARED BY: *R. O. O'Leary*

DATE: *9-26-05*

EnergyGauge® FLRCPB v3.4

System Sizing Calculations - Winter

Residential Load - Component Details

Erkinger Homes

Project Title:
Lt 16 Phase 1 Emerald Cove

Code Only
Professional Version
Climate: North

Lake City, FL

Reference City: Jacksonville (User customized) Winter Temperature Difference: 38.0 F

9/26/2005

Window	Panes/SHGC/Frame/U	Orientation	Area X	HTM=	Load
1	2, Clear, Metal, DEF	N	99.0	27.6	2732 Btuh
2	2, Clear, Metal, DEF	E	6.0	27.6	166 Btuh
3	2, Clear, Metal, DEF	S	198.0	27.6	5465 Btuh
4	2, Clear, Metal, DEF	W	4.0	27.6	110 Btuh
Window Total			307		8473 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Frame - Exterior	11.0	1433	3.4	4872 Btuh
2	Frame - Adjacent	11.0	155	1.8	279 Btuh
Wall Total			1588		5151 Btuh
Doors	Type		Area X	HTM=	Load
1	Wood - Adjac		21	9.2	193 Btuh
Door Total			21		193Btuh
Ceilings	Type	R-Value	Area X	HTM=	Load
1	Under Attic	30.0	2093	1.3	2721 Btuh
Ceiling Total			2093		2721Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab-On-Grade Edge Insul	0	194.0 ft(p)	30.8	5975 Btuh
Floor Total			194		5975 Btuh
Infiltration	Type	ACH X	Building Volume	CFM=	Load
	Natural	0.40	20930(sqft)	140	5844 Btuh
	Mechanical			100	4180 Btuh
Infiltration Total				240	10024 Btuh

Totals for Heating	Subtotal	32538 Btuh
	Duct Loss(using duct multiplier of 0.05)	1627 Btuh
	Total Btuh Loss	34165 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)

(Frame types - metal, wood or insulated metal)

(U - Window U-Factor or 'DEF' for default)

(HTM - ManualJ Heat Transfer Multiplier)

Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

System Sizing Calculations - Summer

Residential Load - Component Details

Erkinger Homes

Project Title:

Code Only

Lt 16 Phase 1 Emerald Cove

Professional Version

Lake City, FL

Climate: North

Reference City: Jacksonville (User customized) Summer Temperature Difference: 24.0 F 9/26/2005

Window	Type	Panes/SHGC/U/InSh/ExSh Omt	Overhang		Window Area(sqft)			HTM		Load		
			Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded			
1	2, Clear, DEF, B, N	N	1.5	8	99.0	0.0	99.0	17	17	1683	Btuh	
2	2, Clear, DEF, B, N	E	1.5	8	6.0	0.0	6.0	17	48	288	Btuh	
3	2, Clear, DEF, B, N	S	1.5	8	198.0	198.0	0.0	17	26	3366	Btuh	
4	2, Clear, DEF, B, N	W	1.5	8	4.0	0.0	4.0	17	48	192	Btuh	
Window Total					307					5529	Btuh	
Walls	Type	R-Value			Area			HTM		Load		
	1	Frame - Exterior	11.0			1433.0			2.5		3582	Btuh
	2	Frame - Adjacent	11.0			155.0			1.7		264	Btuh
Wall Total					1588.0					3846	Btuh	
Doors	Type				Area			HTM		Load		
	1	Wood - Adjac				21.0			12.7		268	Btuh
	Door Total					21.0					268	Btuh
Ceilings	Type/Color	R-Value			Area			HTM		Load		
	1	Under Attic/Dark	30.0			2093.0			1.6		3307	Btuh
	Ceiling Total					2093.0					3307	Btuh
Floors	Type	R-Value			Size			HTM		Load		
	1	Slab-On-Grade Edge Insulation	0.0			194.0 ft(p)			0.0		0	Btuh
	Floor Total					194.0					0	Btuh
Infiltration	Type	ACH			Volume			CFM=		Load		
	Natural	0.35			20930			122.3		3230	Btuh	
	Mechanical							100		2640	Btuh	
	Infiltration Total								222		5870	Btuh

Internal gain	Occupants		Btuh/occupant		Appliance	Load
	6		X 300 +			
					1200	3000 Btuh

Totals for Cooling	Subtotal	21819 Btuh
	Duct gain(using duct multiplier of 0.10)	2182 Btuh
	Total sensible gain	24001 Btuh
	Latent infiltration gain (for 49 gr. humidity difference)	7408 Btuh
	Latent occupant gain (6 people @ 230 Btuh per person)	1380 Btuh
	Latent other gain	0 Btuh
	TOTAL GAIN	32789 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds/Daperies(B) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(Omt - compass orientation)

EnergyGauge® FLRCPB v3.4

Emerald
Cove
Box 16

EFFECTIVE MARCH 1, 2002

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

- APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL**

Applicant

Plans Examiner

- All drawings must be clear, concise and drawn to scale ("Optional" details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
- Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.
- Site Plan including:**
- Dimensions of lot
 - Dimensions of building set backs
 - Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.
 - Provide a full legal description of property.
- Wind-load Engineering Summary, calculations and any details required**
- Plans or specifications must state compliance with FBC Section 1606
 - The following information must be shown as per section 1606.1.7 FBC
 - Basic wind speed (MPH)
 - Wind importance factor (I) and building category
 - Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated
 - The applicable internal pressure coefficient
 - Components and Cladding. The design wind pressure in terms of psf (kN/m^2), to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional
- Elevations including:**
- All sides
 - Roof pitch
 - Overhang dimensions and detail with attic ventilation
 - Location, size and height above roof of chimneys
 - Location and size of skylights
 - Building height
 - Number of stories

☒	☒
☒	☒
☒	☒

☐	☒
☐	☒

☒	☒
☒	☒

☒	☒
☒	☒

☒	☒
-------------------------------------	-------------------------------------

☒	☐
-------------------------------------	--------------------------

☐	☐
--------------------------	--------------------------

Floor Plan including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessable bathroom)

Foundation Plan including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
 1. Truss layout and truss details signed and sealed by Fl. Pro. Eng.
 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
 1. Rafter size, species and spacing
 2. Attachment to wall and uplift
 3. Ridge beam sized and valley framing and support details
 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- a) Masonry wall
 1. All materials making up wall
 2. Block size and mortar type with size and spacing of reinforcement
 3. Lintel, tie-beam sizes and reinforcement
 4. Gable ends with rake beams showing reinforcement or gable truss and wall bracing details
 5. All required connectors with uplift rating and required number and size of fasteners for continuous tie from roof to foundation
 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 7. Fire resistant construction (if required)
 8. Fireproofing requirements
 9. Shoe type of termite treatment (termiteicide or alternative method)
 10. Slab on grade
 - a. Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 11. Indicate where pressure treated wood will be placed
 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐ ☐ b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐ ☐ c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

Notice Of Commencement

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

Mark Disosway, P.E.

POB 868, Lake City, FL 32056, Ph (386) 754-5419, Fax (386) 269-4871

November 3, 2005

Building Department

Re: Permit 0510-80, Erkinger Builders, Spec House, Lot #16, Phase I, Emerald Cove S/D, Columbia County, Florida

Dear Building Official:

Please accept this letter as addendum to the plans for the above referenced house to change all references to FBC 2001 to FBC 2004.

- The plan was drawn prior to the effective date for FBC 2004, 01 October 2005.
- Since the wind load requirements of FBC 2004 remain basically unchanged from FBC 2001 there are no structural changes required to this plan.

Mark Disosway
03 NOV 05

Mark Disosway, PE
Florida Registered Professional Engineer

Cc Erkinger Builders

Project Information for:		L130833					
Builder:	ERKINGER HOMES	Date:	9/21/2005				
Lot:	LOT 16 EMERALD COVE	Start Number:	546				
Subdivision:	N/A						
County or City:	COLUMBIA COUNTY						
Truss Page Count:	107						
Truss Design Load Information (UNO)		Design Program: MiTek 5.2 / 6.2					
Gravity	Wind	Building Code:	FBC2001				
Roof (psf): 42	Wind Standard: ASCE 7-98						
Floor (psf): 55	Wind Speed (mph): 110						
Note: See individual truss drawings for special loading conditions							
Building Designer, responsible for Structural Engineering: (See attached)							
ERKINGER, MATTHEW ANTHONY RR0067135							
Address:	248 SE NASSAU STREET	Designer:	24				
	LAKE CITY, FL 32025						
Truss Design Engineer: Thomas, E. Miller, P.E., 56877 - Byron K. Anderson, PE FL 60987							
Company:	Structural Engineering and Inspections, Inc. EB 9196						
Address	16105 N. Florida Ave, Ste B, Lutz, FL 33549						
Notes:							
1. Truss Design Engineer is responsible for the individual trusses as components only.							
2. Determination as to the suitability and use of these truss components for the structure is the responsibility of the Building Designer of Record, as defined in ANSI/TPI 1-1995 Section 2.2							
3. The seal date shown on the individual truss component drawings must match the seal date on this index sheet.							
#	Truss ID	Dwg. #	Seal Date	#	Truss ID	Dwg. #	Seal Date
1	CJ1	092105546	9/21/2005	41	T22	092105586	9/21/2005
2	CJ1V	092105547	9/21/2005	42	T23	092105587	9/21/2005
3	CJ3	092105548	9/21/2005	43	T24	092105588	9/21/2005
4	CJ3V	092105549	9/21/2005	44	T25	092105589	9/21/2005
5	CJ5	092105550	9/21/2005	45	T26	092105590	9/21/2005
6	EJ5	092105551	9/21/2005	46	T27	092105591	9/21/2005
7	EJ5V	092105552	9/21/2005	47	T28	092105592	9/21/2005
8	EJ5X	092105553	9/21/2005	48	T29	092105593	9/21/2005
9	EJ5Z	092105554	9/21/2005	49	T30	092105594	9/21/2005
10	EJ7	092105555	9/21/2005	50	T31	092105595	9/21/2005
11	EJ7A	092105556	9/21/2005	51	T32	092105596	9/21/2005
12	EJ7B	092105557	9/21/2005	52	T33	092105597	9/21/2005
13	EJ7C	092105558	9/21/2005	53	T33G	092105598	9/21/2005
14	HJ5	092105559	9/21/2005	54	T34	092105599	9/21/2005
15	HJ5V	092105560	9/21/2005	55	CJ1V	092105600	9/21/2005
16	HJ7	092105561	9/21/2005	56	CJ3	092105601	9/21/2005
17	T01	092105562	9/21/2005	57	CJ3V	092105602	9/21/2005
18	T01G	092105563	9/21/2005	58	CJ5	092105603	9/21/2005
19	T02	092105564	9/21/2005	59	EJ5	092105604	9/21/2005
20	T02G	092105565	9/21/2005	60	EJ5V	092105605	9/21/2005
21	T03	092105566	9/21/2005	61	EJ5X	092105606	9/21/2005
22	T04	092105567	9/21/2005	62	EJ5Z	092105607	9/21/2005
23	T04G	092105568	9/21/2005	63	EJ7	092105608	9/21/2005
24	T05	092105569	9/21/2005	64	EJ7A	092105609	9/21/2005
25	T06	092105570	9/21/2005	65	EJ7B	092105610	9/21/2005
26	T07	092105571	9/21/2005	66	EJ7C	092105611	9/21/2005
27	T08	092105572	9/21/2005	67	HJ5	092105612	9/21/2005
28	T09	092105573	9/21/2005	68	HJ5V	092105613	9/21/2005
29	T10	092105574	9/21/2005	69	HJ7	092105614	9/21/2005
30	T11	092105575	9/21/2005	70	T01	092105615	9/21/2005
31	T12	092105576	9/21/2005	71	T01G	092105616	9/21/2005
32	T13	092105577	9/21/2005	72	T02	092105617	9/21/2005
33	T14	092105578	9/21/2005	73	T02G	092105618	9/21/2005
34	T15	092105579	9/21/2005	74	T03	092105619	9/21/2005
35	T16	092105580	9/21/2005	75	T04	092105620	9/21/2005
36	T17	092105581	9/21/2005	76	T04G	092105621	9/21/2005
37	T18	092105582	9/21/2005	77	T05	092105622	9/21/2005
38	T19	092105583	9/21/2005	78	T06	092105623	9/21/2005
39	T20	092105584	9/21/2005	79	T07	092105624	9/21/2005
40	T21	092105585	9/21/2005	80	T08	092105625	9/21/2005

SEP 21 2005

[Log On](#)**Public Services**

[Search for a Licensee](#)
[Apply for a License](#)
[View Application Status](#)
[Apply to Retake Exam](#)
[Find Exam Information](#)
[File a Complaint](#)
[AB&T Delinquent Invoice
& Activity List Search](#)

User Services

[Renew a License](#)
[Change License Status](#)
[Maintain Account](#)
[Change My Address](#)
[View Messages](#)
[Change My PIN](#)
[View Continuing Ed](#)

[Term Glossary](#)[Online Help](#)[DBPR Home](#) | [Online Services Home](#) | [Help](#) | [Site Map](#)

3:26:17 PM

Licensee Details**Licensee Information**

Name: **ERKINGER, MATTHEW ANTHONY (Primary N
INDIVIDUAL (DBA Name)**
Main Address: **248 SE NASSAU ST
LAKE CITY Florida 32025**
County: **COLUMBIA**


License Mailing:

LicenseLocation:

License Information

License Type: **Registered Residential Contractor**
Rank: **Reg Residential**
License Number: **RR0067135**
Status: **Current,Active**
Licensure Date: **12/02/1997**
Expires: **08/31/2007**

**Special
Qualifications****Bldg Code Core
Course Credit****No Qualified****Business License Required** **02/20/2004****Qualification Effective**[View Related License Information](#)[View License Complaint](#)[Terms of Use](#) | [Privacy Statement](#)




SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:

THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987

STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196

16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105549
L130833	CJ3V	MONO SCISSOR	2	1	

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Miltek Industries, Inc. Tue Sep 20 17:50:40 2005 Page 1

[illegible]

Weight: 14 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 3=31/Mechanical, 2=278/0-3-8, 4=42/Mechanical
Max Horz 2=153(load case 5)
Max Uplift 3=27(load case 4), 2=-198(load case 5)
Max Grav 3=31(load case 3), 2=278(load case 1), 4=42(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/52, 2-3=-65/15
BOT CHORD 2-4=-8/8

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDF=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate gird DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 3 and 198 lb uplift at joint 2.

LOAD CASE(S) Standard

SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




Plate Offsets (X,Y): [2;0-3-3;0-1-8]									
LOADING (psf)		SPACING		CSI		DEFL		PLATES	GRIP
TCLL	20.0	Plates Increase	2-0-0	TC	0.25	in (loc)	l/def	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.14	Vert(LL)	2-4 >999		
BCLL	10.0	Rep Stress Incr	YES	WB	0.00	Vert(TL)	2-4 >999		
BCDL	5.0	Code FBC2001/TPI2002		(Matrix)		Horz(TL)	3 n/a n/a		
								Weight: 20 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D

BOT CHORD 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 5'-0'-0" oc purlins.

BOT CHORD Rigid ceiling directly applied or 10'-0'-0" oc bracing.

REACTIONS (lb/size) 3=101/Mechanical, 2=340/0-3-8, 4=71/Mechanical
Max Horz 2=205(load case 5)
Max Uplift 3=93(load case 5), 2=191(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=80/39
BOT CHORD 2-4=0/0


NOTES
1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 3 and 191 lb uplift at joint 2.

LOAD CASE(S) Standard

SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job L130833	Truss EJ5V	Truss Type SPECIAL	Qty 2	Ply 1	Dwg.#092105552	
Builders FirstSource, Lake City, FL 32055			6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:42 2005 Page 1			
LOADING (psf) TCLL 20.0 TCDL 7.0 BCLL 10.0 BCDL 5.0		SPACING 2'-0"-0" Plates Increase 1.25 Lumber Increase 1.25 Rep Stress Incr YES Code FBC2001/TPI2002	CSI TC 0.24 BC 0.14 WB 0.00 (Matrix)	DEFL in (loc) Vert(LL) -0.03 1-3 >999 240 Vert(TL) -0.04 1-3 >999 180 Horz(TL) -0.00 2 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 17 lb	
LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D		BRACING TOP CHORD Structural wood sheathing directly applied or 5'-0"-0" oc purlins. BOT CHORD Rigid ceiling directly applied or 10'-0"-0" oc bracing.				
REACTIONS (lb/size) 1=198/Mechanical, 2=127/Mechanical, 3=71/Mechanical Max Horz 1=134(load case 5) Max Uplift1=-33(load case 5), 2=-130(load case 5)						
FORCES (lb) - Maximum Compression/Maximum Tension TOP CHORD 1-2=-95/53 BOT CHORD 1-3=-14/14						
NOTES 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified. 2) Refer to girder(s) for truss to truss connections. 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 1 and 130 lb uplift at joint 2.						
LOAD CASE(S) Standard						

SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105555	
L130833	EJ7	MONO TRUSS	19	1	Job Reference (optional)	
Builders FirstSource, Lake City, FL 32055			6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:43 2005 Page 1			

Truss diagram showing a mono truss structure. The top chord is 7'-0" long, and the bottom chord is 7'-0" long. The height is 4'-6". The vertical offsets are 2'-0" and 2'-0". A 3x6 plate is shown at joint 2. The scale is 1/2" = 1'-0".

Plate Offsets (X,Y): [2'-0"-3'-3, 0'-1'-8]											
LOADING (psf)		SPACING		CSI		DEFL		PLATES		GRIP	
TCLL	20.0	Plates Increase	2'-0'-0	TC	0.38	in	(loc)	l/defl	L/d	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.30	Vert(LL)	-0.11	2'-4	>728	240	
BCLL	10.0	Rep Stress Incr	YES	WB	0.00	Vert(TL)	-0.18	2'-4	>436	180	
BCDL	5.0	Code FBC2001/TPI2002		(Matrix)		Horz(TL)	-0.00	3	n/a	n/a	
Weight: 26 lb											
LUMBER						BRACING					
TOP CHORD 2 X 4 SYP No.2D						TOP CHORD Structural wood sheathing directly applied or 6'-0'-0 oc purlins.					
BOT CHORD 2 X 4 SYP No.2D						BOT CHORD Rigid ceiling directly applied or 10'-0'-0 oc bracing.					
REACTIONS (lb/size) 3=160/Mechanical, 2=416/0'-3'-8, 4=103/Mechanical											
Max Horz 2=259(load case 5)											
Max Uplift 3=144(load case 5), 2=196(load case 5)											
FORCES (lb) - Maximum Compression/Maximum Tension											
TOP CHORD 1-2=0/54, 2-3=-109/64											
BOT CHORD 2-4=0/0											
NOTES											
1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.											
2) Refer to girder(s) for truss to truss connections.											
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 3 and 196 lb uplift at joint 2.											
LOAD CASE(S) Standard											

SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




Plate Offsets (X,Y): [2:0-4-0-0-3-5], [10:0-1-14,0-1-0]

LOADING (psf)		SPACING		CSI	DEFL				PLATES	GRIP
						in	(loc)	I/defl		
TCLL	20.0	Plates Increase	1.25	TC	0.22	-0.03	1-2	n/r	90	MT20
TCOL	7.0	Lumber Increase	1.25	BC	0.17	-0.05	1-2	n/r	80	244/190
BCLL	10.0	Rep Stress Incr	YES	WB	0.21	0.00	6	n/a	n/a	
BCDL	5.0	Code FBC2001/TPI2002		(Matrix)						
										Weight: 39 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3
OTHERS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

* Uplift in gravity load case.

REACTIONS (lb/size) 6=-192/3-6-0, 8=850/3-6-0, 7=26/3-6-0
Max Horz 8=152(load case 5)
Max Uplift 6=-192(load case 1), 8=-602(load case 5)
Max Grav 6=223(load case 5), 8=850(load case 1), 7=36(load case 3)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=-702/537, 3-4=-695/614, 4-5=-10/24, 5-6=-83/92
BOT CHORD 2-8=510/748, 7-8=-572/650, 6-7=-572/650
WEBS 4-8=-740/817, 4-6=-740/651


NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- 3) Provide adequate drainage to prevent water ponding.
- 4) Gable studs spaced at 2'-0" oc.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 192 lb uplift at joint 6 and 602 lb uplift at joint 6.
- 6) Non Standard bearing condition. Review required.


LOAD CASE(S) Standard


SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549







SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549











SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549












SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:
THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987
STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196
16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549



Job	Truss	Truss Type	Qty	Ply	Dwg.#092105577
L130833	T13	SPECIAL	1	1	

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:03 2005 Page 1




Plate Offsets (X,Y): [1:Edge,0-0-1], [3:0-6-8,Edge], [5:0-7-0,0-0-5], [8:0-3-8,Edge]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.49	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.72	Vert(LL) -0.24 3-11 >999 240	MT18H	244/190
BCLL 10.0	Lumber Increase 1.25	WB 0.78	Vert(TL) -0.39 3-11 >684 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.35 15 n/a n/a		
	Code FBC2001/TPI2002			Weight: 154 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D *Except*	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
T1 2 X 8 SYP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied or 7-6-2 oc bracing.
BOT CHORD 2 X 4 SYP No.2D *Except*	
B3 2 X 4 SYP No.3, B3 2 X 4 SYP No.3	
WEBS 2 X 4 SYP No.3 *Except*	
W5 2 X 4 SYP No.2D	
SLIDER Left 2 X 6 SYP No.1D 1-8-10	

REACTIONS (lb/size) 1=954/0-3-8, 15=941/Mechanical
Max Horz 1=305(load case 5)
Max Uplift 1=270(load case 5), 15=269(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-811/183, 2-3=-531/114, 3-4=-1627/599, 4-5=-937/417, 5-6=-709/412, 6-7=-709/412, 7-8=-929/382, 9-15=-941/348, 8-9=-814/366
BOT CHORD 1-12=-711/115, 3-12=-9/62, 3-11=-683/1498, 10-11=-683/1497, 9-10=-84/155
WEBS 8-10=-189/586, 6-10=-181/548, 4-11=0/195, 4-10=-954/553

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- The following joint(s) require plate inspection per the Tooth Count Method when this truss is chosen for quality assurance inspection: 5.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 270 lb uplift at joint 1 and 269 lb uplift at joint 15.

LOAD CASE(S) Standard




Plate Offsets (X,Y): [1:0-3-8,Edge], [3:0-1-8,0-2-0], [6:0-3-8,Edge]															
LOADING (psf)		SPACING		2-0-0		CSI		DEFL		in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0		Plates Increase		1.25		TC 0.55		Vert(LL)		-0.31	10	>864	240	MT20	244/190
TCDL 7.0		Lumber Increase		1.25		BC 0.53		Vert(TL)		-0.50	10	>533	180		
BCLL 10.0		Rep Stress Incr		YES		WB 0.78		Horz(TL)		0.36	13	n/a	n/a		
BCDL 5.0		Code FBC2001/TPI2002				(Matrix)									
														Weight: 155 lb	


LUMBER	BRACING
TOP CHORD 2 X 8 SYP 2400F 2.0E *Except*	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
T2 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 7-6-6 oc bracing.
BOT CHORD 2 X 4 SYP No.2D *Except*	
B3 2 X 4 SYP No.3, B3 2 X 4 SYP No.3	
WEBS 2 X 4 SYP No.3 *Except*	
W5 2 X 4 SYP No.2D	
SLIDER Left 2 X 6 SYP No.1D 1-8-10	


REACTIONS (lb/size) 1=954/0-3-8, 13=941/Mechanical
 Max Horz 1=307(load case 5)
 Max Uplift1=-272(load case 5), 13=-275(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-662/136, 2-3=-290/133, 3-4=-1616/587, 4-5=-928/416, 5-6=-932/381, 7-13=-941/347, 6-7=-816/364
 BOT CHORD 1-10=0/0, 3-9=-676/1479, 8-9=-676/1479, 7-8=-81/152
 WEBS 5-8=-179/550, 6-8=-200/599, 4-9=0/228, 4-8=-945/543


- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed: MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 272 lb uplift at joint 1 and 275 lb uplift at joint 13.


LOAD CASE(S) Standard











SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:

THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987

STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196

16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549




Plate Offsets (X,Y): [2-0-3-3-0-1-8], [10-0-8-1-0-0-10], [15-0-4-0-0-3-0]							
LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d
TCLL 20.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.31 14-15	>999	240
TCDL 7.0	Lumber Increase	1.25	BC 0.54	Vert(TL)	-0.51 14-15	>797	180
BCLL 10.0	Rep Stress Incr	YES	WB 0.82	Horz(TL)	0.15 10	n/a	n/a
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)				
				PLATES		GRIP	
				MT20		244/190	
				Weight: 229 lb			

LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D *Except* B4 2 X 4 SYP No.3 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD Structural wood sheathing directly applied or 3-2-0 oc purlins. BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
--	--


REACTIONS (lb/size) 10=1463/0-3-8, 18=1770/0-4-15
 Max Horz 18=-318(load case 3)
 Max Uplift 10=-425(load case 6), 18=-625(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-435/356, 3-4=-1699/532, 4-5=-1647/643, 5-6=-1570/680, 6-7=-1860/730, 7-8=-3786/1281, 8-9=-3743/1179, 9-10=-2515/823
 BOT CHORD 2-18=-262/462, 17-18=-262/475, 16-17=-361/1401, 15-16=-289/1361, 14-15=-490/2102, 12-14=0/108, 8-14=-165/155, 12-13=0/0,
 11-12=-42/0, 10-11=-625/2092
 WEBS 3-18=-1633/813, 3-17=-728/1708, 4-17=-240/218, 4-16=-180/142, 5-16=-59/215, 5-15=-197/444, 6-15=-177/633, 7-15=-865/408,
 11-14=-712/2569, 9-14=-217/1182, 9-11=-1335/422, 7-14=-546/1806

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; Lumber DOL=1.60 plate gnp DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- 4) Provide adequate drainage to prevent water ponding.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 425 lb uplift at joint 10 and 625 lb uplift at joint 18.

LOAD CASE(S) Standard




LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D *Except* B4 2 X 4 SYP No.3 WEBS 2 X 4 SYP No.3	BRACING TOP CHORD BOT CHORD WEBS	Structural wood sheathing directly applied or 2-10-11 cc purlins, Rigid ceiling directly applied or 6-0-0 cc bracing. 1 Row at midpt 3-16, 6-15
--	--	--

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-2520/833, 3-4=-1883/733, 4-5=-1545/711, 5-6=-1868/758, 6-7=-4199/1419, 7-8=-4037/1296, 8-9=-4103/1285, 9-10=-2713/894
BOT CHORD 2-17=-552/2071, 16-17=-553/2067, 15-16=-226/1545, 14-15=-525/2184, 12-14=0/103, 7-14=-191/186, 12-13=0/0, 11-12=-73/0, 10-11=-685/2261
WEBS 3-17=0/274, 3-16=-671/398, 4-16=-155/487, 5-15=-302/901, 6-15=-980/484, 6-14=-622/2089, 9-11=-1477/458, 11-14=-770/2824, 9-14=-264/1335

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCFL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 556 lb uplift at joint 2 and 460 lb uplift at joint 10.

LOAD CASE(S) Standard




SEPTEMBER 21, 2005 TRUSS DESIGN ENGINEER:

THOMAS E. MILLER PE 56877, BYRON K. ANDERSON PE 60987

STRUCTURAL ENGINEERING AND INSPECTIONS, INC. EB 9196

16105 N. FLORIDA AVE. STE B, LUTZ, FL 33549






Plate Offsets (X,Y): [1:0-4-10 Edge], [3:0-3-0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.40	Vert(LL)	-0.19	8-10	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.55	Vert(TL)	-0.33	8-10	>994	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.51	Horz(TL)	0.04	8	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)							
										Weight: 174 lb

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3 "Except"
 W7 2 X 4 SYP No.2D
 SLIDER Left 2 X 4 SYP No.2D 3-5-7

BRACING
 TOP CHORD Structural wood sheathing directly applied or 5-1-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 7-10-5 oc bracing.
 WEBS 1 Row at midpt 4-10, 6-8

REACTIONS (lb/size) 1=1158/0-4-15, 8=1158/Mechanical
 Max Horz 1=349(load case 4)
 Max Uplift 1=349(load case 5), 8=324(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-1718/584, 2-3=-1567/602, 3-4=-1506/581, 4-5=-929/452, 5-6=-915/458, 6-7=-153/88, 7-8=-182/123
 BOT CHORD 1-11=-674/1391, 10-11=-453/1094, 9-10=-223/616, 8-9=-223/616
 WEBS 3-11=-241/260, 4-11=-158/456, 4-10=-594/386, 5-10=-259/561, 6-10=-118/286, 6-8=-990/393

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Refer to girder(s) for truss to truss connections.
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 349 lb uplift at joint 1 and 324 lb uplift at joint 8.

LOAD CASE(S) Standard




Plate Offsets (X,Y): [1:Edge,0-1-12]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.37	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.46	Vert(LL) -0.13 7-9 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.34	Vert(TL) -0.23 7-9 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.02 7 n/a n/a		
	Code FBC2001/TPI2002			Weight: 192 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3 "Except"
 W1 2 X 4 SYP No.2D, W9 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 9-8-9 oc bracing.
 WEBS 1 Row at midpt 2-10, 3-9, 5-7


REACTIONS (lb/size) 12=1067/0-4-3, 7=1067/Mechanical
 Max Horz 12=280(load case 4)
 Max Uplift 12=307(load case 5), 7=301(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-1259/438, 2-3=-892/419, 3-4=-653/409, 4-5=-819/419, 5-6=-128/78, 1-12=-959/373, 6-7=-158/110
 BOT CHORD 11-12=-357/241, 10-11=-450/1004, 9-10=-211/685, 8-9=-200/539, 7-8=-200/539
 WEBS 2-11=0/108, 2-10=-441/310, 3-10=-181/312, 3-9=-275/252, 4-9=-189/330, 5-9=-114/237, 1-11=-175/815, 5-7=-912/370

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 307 lb uplift at joint 12 and 301 lb uplift at joint 7.

LOAD CASE(S) Standard



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.38	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.34	Vert(LL) -0.14 11-12 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.85	Vert(TL) -0.25 11-12 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.02 8 n/a n/a		
	Code FBC2001/TP12002			Weight: 182 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2 X 4 SYP No.3 *Except*	WEBS 1 Row at midpt 4-11, 4-10
W1 2 X 4 SYP No.2D, W9 2 X 4 SYP No.2D	

REACTIONS (lb/size) 12=933/0-3-8, 8=933/Mechanical
 Max Horz 12=197(load case 4)
 Max Uplift 12=-284(load case 5), 8=-261(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-165/82, 2-3=-747/362, 3-4=-594/362, 4-5=-589/361, 5-6=-672/353, 6-7=-119/66, 1-12=-180/114, 7-8=-147/95
 BOT CHORD 11-12=-298/536, 10-11=-176/570, 9-10=-158/423, 8-9=-158/423
 WEBS 2-11=-112/130, 3-11=-28/140, 4-11=-130/124, 4-10=-401/260, 5-10=-194/376, 6-10=-96/255, 2-12=-756/300, 6-8=-751/316

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 284 lb uplift at joint 12 and 261 lb uplift at joint 8.

LOAD CASE(S) Standard




Plate Offsets (X,Y): [1.0-8-1.0-0-6]									
LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP				
TCLL 20.0	Plates Increase 2-0-0 1.25	TC 0.42	in (loc) l/defl L/d	MT20	244/190				
TCDL 7.0	Lumber Increase 1.25	BC 0.45	Vert(LL) 0.09 8-9 >999 240						
BCLL 10.0	Rep Stress Incr NO	WB 0.48	Vert(TL) -0.13 8-9 >999 180						
BCDL 5.0	Code FBC2001/TPI2002	(Matrix)	Horz(TL) 0.03 6 n/a n/a						
Weight: 88 lb									

LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D WEBS 2 X 4 SYP No.3 "Except" W4 2 X 4 SYP No.2D	BRACING TOP CHORD Structural wood sheathing directly applied or 4-4-7 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 5-10-3 oc bracing.
---	---

REACTIONS (lb/size) 1=1194/0-3-8, 6=1438/0-4-15
 Max Horz 1=102(load case 4)
 Max Uplift 1=804(load case 3), 6=-955(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2026/1388, 2-3=-2037/1487, 3-4=-2037/1487, 4-5=-1309/874, 5-6=-1424/933
 BOT CHORD 1-9=-1239/1694, 8-9=-1253/1717, 7-8=-758/1117, 6-7=-11/11
 WEBS 2-9=-289/463, 2-8=-399/456, 3-8=-486/496, 4-8=-850/1079, 4-7=-219/245, 5-7=-943/1353

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
- 3) Provide adequate drainage to prevent water ponding.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 804 lb uplift at joint 1 and 955 lb uplift at joint 6.
- 5) Girder carries hip end with 2-4-15 right side setback, 5-0-0 left side setback, and 5-0-0 end setback.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 363 lb down and 198 lb up at 15-2-0, and 245 lb down and 170 lb up at 5-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54, 2-4=-91(F=-37), 4-5=-54, 1-9=-30, 7-9=-50(F=-20), 6-7=-30
 Concentrated Loads (lb)
 Vert: 9=-245(F) 7=-363(F)




Plate Offsets (X,Y): [1.0-3-3.0-1-8]							
LOADING (psf)	SPACING	CSI	DEFL		PLATES	GRIP	
TCLL 20.0	2-0-0	TC 0.37	in (loc) l/defl L/d		MT20	244/190	
TCDL 7.0	Plates Increase 1.25	BC 0.36	Vert(LL) 0.22 1-7 >930 240				
BCLL 10.0	Lumber Increase 1.25	WB 0.30	Vert(TL) 0.18 1-7 >999 180				
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.02 5 n/a n/a				
	Code FBC2001/TPI2002						Weight: 84 lb

LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D WEBS 2 X 4 SYP No.3 "Except" W4 2 X 4 SYP No.2D	BRACING TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 6-5-2 oc bracing.
---	--

REACTIONS (lb/size) 1=705/0-3-8, 5=705/0-3-8
 Max Horz 1=136(load case 4)
 Max Uplift 1=413(load case 4), 5=408(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-996/983, 2-3=-543/661, 3-4=-670/708, 4-5=-648/665
 BOT CHORD 1-7=-837/783, 6-7=-851/792, 5-6=-54/40
 WEBS 2-7=-407/242, 2-6=-338/348, 3-6=-190/93, 4-6=-561/559

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 413 lb uplift at joint 1 and 408 lb uplift at joint 5.

LOAD CASE(S) Standard

Job L130833	Truss T29	Truss Type SPECIAL	Qty 1	Ply 1	Dwg.#092105593
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:16 2005 Page 1		




Plate Offsets (X,Y): [8-0-4-0-0-0-8]					
LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.66	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.43	Vert(LL) 0.08 7-8 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.55	Vert(TL) -0.12 7-8 >999 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) 0.08 6 n/a n/a		
	Code FBC2001/TPI2002			Weight: 65 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 4-5-1 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 6-9-13 oc bracing.
WEBS 2 X 4 SYP No.3	

REACTIONS (lb/size) 6=939/0-3-8, 2=956/0-3-8
Max Horz 2=210(load case 4)
Max Uplift 6=484(load case 2), 2=475(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=-2060/961, 3-4=-1758/876, 4-5=-1723/874, 5-6=-821/507
BOT CHORD 2-8=-875/1756, 7-8=-903/1754, 6-7=-56/128
WEBS 3-8=-408/806, 4-8=-62/183, 4-7=-372/348, 5-7=-874/1724

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) Provide adequate drainage to prevent water ponding.
- 3) Bearing at joint(s) 6, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 484 lb uplift at joint 6 and 475 lb uplift at joint 2.
- 5) Girder carries hip end with 0-0-0 right side setback, 5-0-0 left side setback, and 5-0-0 end setback.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 245 lb down and 170 lb up at 5-1-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-5=-91(F=-37), 2-8=-30, 7-8=-50(F=-20), 6-7=-50(F=-20)
Concentrated Loads (lb)
Vert: 8=-245(F)

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105594
L130833	T30	SPECIAL	1	1	
Builders FirstSource, Lake City, FL 32055					
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:16 2005 Page 1					




Plate Offsets (X,Y): [3-0-3-1,Edge]									
LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES
TCLL 20.0	Plates Increase	1.25	TC 0.37	Vert(LL)	-0.07	2-6	>999	240	MT20
TCDL 7.0	Lumber Increase	1.25	BC 0.34	Vert(TL)	-0.11	2-6	>999	180	GRIP
BCLL 10.0	Rep Stress Incr	YES	WB 0.35	Horz(TL)	0.04	5	n/a	n/a	244/190
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)						Weight: 64 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 5-11-8 oc purlins, except end
BOT CHORD 2 X 4 SYP No.2D	verticals.
WEBS 2 X 4 SYP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=531/0-3-8, 2=666/0-3-8
Max Horz 2=263(load case 5)
Max Uplift 5=183(load case 4), 2=278(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=-1069/363, 3-4=-816/407, 4-5=-451/270
BOT CHORD 2-6=-408/890, 5-6=-33/68
WEBS 3-6=0/129, 4-6=-421/833

NOTES


- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Provide adequate drainage to prevent water ponding.
- 3) Bearing at joint(s) 5, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 183 lb uplift at joint 5 and 278 lb uplift at joint 2.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105595
L130833	T31	SPECIAL	1	1	Job Reference (optional)

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:17 2005 Page 1



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.29	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.25	Vert(LL) -0.06 2-8 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.22	Vert(TL) -0.10 2-8 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.04 6 n/a n/a		
	Code FBC2001/TPI2002			Weight: 77 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3


BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 9-0-6 oc bracing.

REACTIONS (lb/size) 6=531/0-3-8, 2=666/0-3-8
 Max Horz 2=317(load case 5)
 Max Uplift 6=-175(load case 5), 2=-274(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-1132/394, 3-4=-908/324, 4-5=-347/181, 5-6=-473/274
 BOT CHORD 2-8=-513/962, 7-8=-193/384, 6-7=-9/27
 WEBS 3-8=-210/210, 4-8=-261/686, 4-7=-386/251, 5-7=-266/503

NOTES
 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 2) Provide adequate drainage to prevent water ponding.
 3) Bearing at joint(s) 6, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 175 lb uplift at joint 6 and 274 lb uplift at joint 2.

LOAD CASE(S) Standard



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.22	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.27	Vert(LL) -0.08 2-8 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.76	Vert(TL) -0.14 2-8 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.07 6 n/a n/a		
	Code FBC2001/TPI2002			Weight: 84 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 8-4-14 oc bracing.
WEBS 2 X 4 SYP No.3	WEBS 1 Row at midpt 5-6


REACTIONS (lb/size) 6=531/0-3-8, 2=666/0-3-8
 Max Horz 2=371(load case 5)
 Max Uplift 6=230(load case 5), 2=259(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-1093/316, 3-4=-264/38, 4-5=-160/88, 5-6=-516/279
 BOT CHORD 2-8=-494/920, 7-8=-594/1242, 6-7=-1/12
 WEBS 3-8=-235/758, 3-7=-1168/559, 4-7=-140/172, 5-7=-294/530

- NOTES**
- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 2) Provide adequate drainage to prevent water ponding.
 - 3) Bearing at joint(s) 6, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 230 lb uplift at joint 6 and 259 lb uplift at joint 2.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105597
L130833	T33	COMMON	1	1	
Builders FirstSource, Lake City, FL 32055			Job Reference (optional)		
			6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:18 2005 Page 1		



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.27	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.05	Vert(LL) -0.00 6-7 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.03	Vert(TL) -0.00 6-7 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 6 n/a n/a		
	Code FBC2001/TPI2002				Weight: 42 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3 "Except"
W1 2 X 4 SYP No.2D, W1 2 X 4 SYP No.2D

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS (lb/size) 8=363/0-3-8, 6=363/0-3-8
Max Horz 8=123(load case 4)
Max Uplift 8=200(load case 5), 6=200(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/58, 2-3=-170/90, 3-4=-170/90, 4-5=0/58, 2-8=-328/250, 4-6=-328/250
BOT CHORD 7-8=-107/111, 6-7=-13/26
WEBS 3-7=-68/47, 2-7=-5/126, 4-7=-5/126

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 200 lb uplift at joint 8 and 200 lb uplift at joint 6.

LOAD CASE(S) Standard



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.26	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.05	Vert(LL) -0.03 7 n/r 90		
BCLL 10.0	Lumber Increase 1.25	WB 0.04	Vert(TL) -0.05 7 n/r 80		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 6 n/a n/a		
	Code FBC2001/TPI2002				
				Weight: 38 lb	


LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 6-2-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2 X 4 SYP No.2D	
OTHERS 2 X 4 SYP No.3	

REACTIONS (lb/size) 12=164/6-2-0, 8=164/6-2-0, 10=254/6-2-0, 11=72/6-2-0, 9=72/6-2-0
 Max Horz 12=90(load case 5)
 Max Uplift 12=173(load case 5), 8=183(load case 6), 10=24(load case 5), 11=75(load case 4), 9=70(load case 3)
 Max Grav 12=206(load case 7), 8=206(load case 8), 10=254(load case 1), 11=98(load case 3), 9=93(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/58, 2-3=-30/58, 3-4=-1/100, 4-5=0/100, 5-6=-25/53, 6-7=0/58, 2-12=-196/255, 6-8=-196/255
 BOT CHORD 11-12=-60/120, 10-11=-60/120, 9-10=-60/120, 8-9=-60/120
 WEBS 4-10=-193/78, 3-11=-73/50, 5-9=-70/48

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 173 lb uplift at joint 12, 183 lb uplift at joint 8, 24 lb uplift at joint 10, 75 lb uplift at joint 11 and 70 lb uplift at joint 9.

LOAD CASE(S) Standard



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.28	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.08	Vert(LL) -0.00 7 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.09	Vert(TL) -0.01 6-7 >999 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) -0.00 6 n/a n/a		
	Code FBC2001/TPI2002			Weight: 46 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 6 SYP No.1D
 WEBS 2 X 4 SYP No.3 *Except*
 W1 2 X 4 SYP No.2D, W1 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 8=653/0-3-8, 6=653/0-3-8
 Max Horz 8=90(load case 4)
 Max Uplift 8=315(load case 4), 6=315(load case 5)

FORCES


(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/58, 2-3=-383/136, 3-4=-383/136, 4-5=0/58, 2-8=-498/276, 4-6=-498/276
 BOT CHORD 7-8=-90/90, 6-7=0/0
 WEBS 3-7=-105/261, 2-7=-67/295, 4-7=-67/295

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 315 lb uplift at joint 8 and 315 lb uplift at joint 6.
- Girder carries tie-in span(s): 7-0-0 from 0-0-0 to 6-2-0
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54, 2-3=-54, 3-4=-54, 4-5=-54, 6-8=-129(F=-99)



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.23	in (loc) l/defl L/d	MT20	244/190
TCCL 7.0	Plates Increase 1.25	BC 0.02	Vert(LL) -0.01 4 >857 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.01 4 >947 180		
BCCL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 3 n/a n/a		
	Code FBC2001/TPI2002				
					Weight: 7 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 2=266/0-3-8, 3=-75/Mechanical
 Max Horz 2=100(load case 5)
 Max Uplift 2=-277(load case 5), 3=-75(load case 1)
 Max Grav 2=266(load case 1), 3=132(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/51, 2-3=-74/89
 BOT CHORD 2-4=-7/0

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 277 lb uplift at joint 2 and 75 lb uplift at joint 3.

LOAD CASE(S) Standard

Job L130833	Truss CJ3	Truss Type MONO TRUSS	Qty 8	Ply 1	Dwg.#092105601
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:40 2005 Page 1		




Plate Offsets (X,Y): [2-0-3-4,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.25	Vert(LL)	-0.00	2-4	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.05	Vert(TL)	-0.01	2-4	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)							
										Weight: 13 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=31/Mechanical, 2=278/0-3-8, 4=42/Mechanical
Max Horz 2=154(load case 5)
Max Uplift 3=-26(load case 4), 2=-200(load case 5)
Max Grav 3=31(load case 3), 2=278(load case 1), 4=42(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-64/15
BOT CHORD 2-4=0/0

NOTES


- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 3 and 200 lb uplift at joint 2.

LOAD CASE(S) Standard

Job L130833	Truss CJ3V	Truss Type MONO SCISSOR	Qty 2	Ply 1	Dwg.#092105602
----------------	---------------	----------------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:40 2005 Page 1



Scale = 1:12.8

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.24	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.05	Vert(LL) -0.00 2-4 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.01 2-4 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.00 3 n/a n/a		
	Code FBC2001/TP1/2002				
				Weight: 14 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 3=31/Mechanical, 2=278/0-3-8, 4=42/Mechanical
Max Horz 2=153(load case 5)
Max Uplift 3=-27(load case 4), 2=-198(load case 5)
Max Grav 3=31(load case 3), 2=278(load case 1), 4=42(load case 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/52, 2-3=-65/15
BOT CHORD 2-4=-8/8

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone: Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TP1 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 3 and 198 lb uplift at joint 2.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Dwg.#092105603
L130833	CJ5	MONO TRUSS	4	1	

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:41 2005 Page 1




Plate Offsets (X,Y): [2:0-3-4,0-1-8]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.25	Vert(LL)	-0.03	2-4	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.14	Vert(TL)	-0.05	2-4	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)							
									Weight: 20 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=103/Mechanical, 2=343/0-3-8, 4=72/Mechanical
Max Horz 2=207(load case 5)
Max Uplift 3=96(load case 5), 2=191(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/54, 2-3=81/40
BOT CHORD 2-4=0/0


NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 96 lb uplift at joint 3 and 191 lb uplift at joint 2.

LOAD CASE(S) Standard



Job L130833	Truss EJ5V	Truss Type SPECIAL	Qty 2	Ply 1	Dwg.#092105605
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mittek Industries, Inc. Tue Sep 20 17:50:42 2005 Page 1		



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.24	in (loc) l/def L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.14	Vert(LL) -0.03 1-3 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.00	Vert(TL) -0.04 1-3 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.00 2 n/a n/a		
	Code FBC2001/TPI2002				Weight: 17 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 5'-0-0 oc purlins.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS (lb/size) 1=198/Mechanical, 2=127/Mechanical, 3=71/Mechanical
Max Horz 1=134(load case 5)
Max Uplift1=-33(load case 5), 2=-130(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-95/53
BOT CHORD 1-3=-14/14

NOTES
1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 1 and 130 lb uplift at joint 2.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:42 2005 Page 1




Plate Offsets (X,Y): [5:0-3-0-0-1-12]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.29	Vert(LL)	0.06	5	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.10	Vert(TL)	-0.06	1-5	>877	180		
BCLL 10.0	Rep Stress Incr YES	WB 0.02	Horz(TL)	0.02	4	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002	(Matrix)							
									Weight: 18 lb

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 5'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6'-0-0 oc bracing.

REACTIONS

(lb/size) 1=198/Mechanical, 3=187/Mechanical, 4=10/Mechanical
Max Horz 1=134(load case 5)
Max Uplift 1=33(load case 5), 3=118(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-95/34, 2-3=-71/92
BOT CHORD 1-5=-19/4, 4-5=-0/0
WEBS 2-5=0/69

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 1 and 118 lb uplift at joint 3.

LOAD CASE(S) Standard

Job L130833	Truss EJ7A	Truss Type SPECIAL	Qty 6	Ply 1	Dwg.#092105609
----------------	---------------	-----------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:44 2005 Page 1




Plate Offsets (X,Y): [2-0-3-3-0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.24	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.61	Vert(LL) -0.04 6-7 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.32	Vert(TL) -0.07 6-7 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.03 5 n/a n/a		
	Code FBC2001/TPI2002			Weight: 34 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D *Except*
WEBS B2 2 X 4 SYP No.3
2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 4=111/Mechanical, 2=419/0-3-8, 5=156/Mechanical
Max Horz 2=261(load case 5)
Max Uplift 4=104(load case 5), 2=196(load case 5), 5=35(load case 5)


FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=343/0, 3-4=77/43
BOT CHORD 2-8=88/233, 7-8=0/55, 3-7=0/107, 6-7=391/768, 5-6=0/0
WEBS 3-6=774/393

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Refer to girder(s) for truss to truss connections.
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 104 lb uplift at joint 4, 196 lb uplift at joint 2 and 35 lb uplift at joint 5.

LOAD CASE(S) Standard



Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:45 2005 Page 1




Plate Offsets (X,Y): [2:0-4-0,0-3-5], [10:0-1-14,0-1-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.22	Vert(LL)	-0.03	1-2	n/r	90	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.17	Vert(TL)	-0.05	1-2	n/r	80		
BCDL 10.0	Rep Stress Incr	YES	WB 0.21	Horz(TL)	0.00	6	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)							
									Weight: 39 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3
 OTHERS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 6=-192/3-6-0, 8=850/3-6-0, 7=26/3-6-0
 Max Horz 8=152(load case 5)
 Max Uplift 6=-192(load case 1), 8=-602(load case 5)
 Max Grav 6=223(load case 5), 8=850(load case 1), 7=36(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-702/537, 3-4=-695/614, 4-5=-10/24, 5-6=-83/92
 BOT CHORD 2-8=-510/748, 7-8=-572/650, 6-7=-572/650
 WEBS 4-8=-740/817, 4-6=-740/651


NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II: Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- 3) Provide adequate drainage to prevent water ponding.
- 4) Gable studs spaced at 2-0-0 oc.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 192 lb uplift at joint 6 and 602 lb uplift at joint 8.
- 6) Non Standard bearing condition. Review required.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mitex Industries, Inc. Tue Sep 20 17:50:46 2005 Page 1



LOADING (psf)		SPACING		CSI		DEFL				PLATES		GRIP	
TCLL	20.0	Plates Increase	1.25	TC	0.47	in	(loc)	l/defl	L/d	MT20		244/190	
TCDL	7.0	Lumber Increase	1.25	BC	0.24	Vert(LL)	-0.07	2-5	>999				
BCLL	10.0	Rep Stress Incr	NO	WB	0.00	Vert(TL)	-0.12	2-5	>678				
BCDL	5.0	Code FBC2001/TPI2002		(Matrix)		Horz(TL)	-0.00	3	n/a				
												Weight: 27 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING
TOP CHORD Structural wood sheathing directly applied or 7-0-14 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 3=191/Mechanical, 2=373/0-4-15, 5=117/Mechanical
Max Horz 2=194(load case 4)
Max Uplift 3=-155(load case 4), 2=-237(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/57, 2-3=-82/51
BOT CHORD 2-5=-0/0, 4-5=-0/0

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 155 lb uplift at joint 3 and 237 lb uplift at joint 2.
- 5) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)


Vert: 1-2=-54

Trapezoidal Loads (plf)

Vert: 2=-3(F=26, B=26)-to-3=-95(F=-21, B=-21), 2=-0(F=15, B=15)-to-4=-53(F=-12, B=-12)

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:46 2005 Page 1



LOADING (psf)		SPACING		CSI		DEFL		PLATES		GRIP	
TCLL	20.0	2-0-0		TC	0.45	in	(loc)	l/def	L/d	MT20	244/190
TCDL	7.0	Plates Increase	1.25	BC	0.24	Vert(LL)	-0.07	2-5	>999		
BCLL	10.0	Lumber Increase	1.25	WB	0.00	Vert(TL)	-0.13	2-5	>633		
BCDL	5.0	Rep Stress Incr	NO	(Matrix)		Horz(TL)	-0.00	3	n/a		
		Code FBC2001/TPI2002								Weight: 27 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D

BRACING
TOP CHORD Structural wood sheathing directly applied or 7-0-14 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 3=193/Mechanical, 2=368/0-3-8, 5=119/Mechanical
Max Horz 2=192(load case 4)
Max Uplift 3=-156(load case 4), 2=-230(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/56, 2-3=-82/52
BOT CHORD 2-5=-12/13, 4-5=-2/0

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 156 lb uplift at joint 3 and 230 lb uplift at joint 2.
- 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard


1) Regular: Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54

Trapezoidal Loads (plf)

Vert: 2=-2(F=26, B=26)-to-3=-95(F=-21, B=-21), 2=0(F=15, B=15)-to-4=-53(F=-12, B=-12)



Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:48 2005 Page 1




Plate Offsets (X,Y): [2:0-3-3,0-1-8], [6:0-3-3,0-1-8], [8:0-4-0,0-3-0]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.26	Vert(LL)	-0.18	8-9	>999	240	MT20	244/190
TCCL 7.0	Lumber Increase 1.25	BC 0.71	Vert(TL)	-0.29	8-9	>885	180		
BCCL 10.0	Rep Stress Incr NO	WB 0.24	Horz(TL)	0.04	6	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002	(Matrix)							
Weight: 108 lb									

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-10-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-8-9 oc bracing.

REACTIONS (lb/size) 2=1186/0-3-8, 6=1186/0-3-8
Max Horz 2=227(load case 4)
Max Uplift 2=459(load case 5), 6=459(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-1713/567, 3-4=-1569/597, 4-5=-1569/597, 5-6=-1713/567, 6-7=0/54
BOT CHORD 2-9=438/1401, 8-9=-203/962, 6-8=-322/1401
WEBS 3-9=-239/232, 4-9=-259/710, 4-8=-259/710, 5-8=-239/232

NOTES


- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 459 lb uplift at joint 2 and 459 lb uplift at joint 6.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 4-7=-54, 2-9=-30, 8-9=-80(F=50), 6-8=-30

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:49 2005 Page 1



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.64	in (loc) l/def L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.55	Vert(LL) -0.14 8-10 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.28	Vert(TL) -0.23 8-10 >999 180		
BCDL 5.0	Rep Stress Incr NO	(Matrix)	Horz(TL) 0.06 8 n/a n/a		
	Code FBC2001/TPI2002			Weight: 152 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 3-3-15 oc purlins.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 7-9-6 oc bracing.
WEBS 2 X 4 SYP No.3	
OTHERS 2 X 4 SYP No.3	

REACTIONS (lb/size) 2=1784/0-3-8, 8=1784/0-3-8
 Max Horiz 2=215(load case 4)
 Max Uplift 2=686(load case 5), 8=686(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-14/113, 2-3=-2534/824, 3-4=-2425/814, 4-5=-2230/789, 5-6=-2230/789, 6-7=-2425/814, 7-8=-2534/824, 8-9=-14/113
 BOT CHORD 2-11=-693/2112, 10-11=-350/1353, 8-10=-570/2112
 WEBS 4-11=-625/362, 5-11=-310/879, 5-10=-310/879, 6-10=-625/362

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) Gable studs spaced at 2-0-0 oc.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 686 lb uplift at joint 2 and 686 lb uplift at joint 8.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-5=-114(F=-60), 5-9=-114(F=-60), 2-8=-30

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:50 2005 Page 1




Plate Offsets (X,Y): [2-0-3-3,0-1-8], [4-0-3-3,0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.23	Vert(LL)	-0.03	4-6	>999	240	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.16	Vert(TL)	-0.04	4-6	>999	180		
BCLL 10.0	Lumber Increase 1.25	WB 0.06	Horz(TL)	0.01	4	n/a	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)							
	Code FBC2001/TP12002								
								Weight: 49 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 2=587/0-3-8, 4=587/0-3-8
Max Horiz 2=-124(load case 3)
Max Uplift 2=-272(load case 5), 4=-272(load case 6)


FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/54, 2-3=-572/156, 3-4=-572/156, 4-5=0/54
BOT CHORD 2-6=-45/427, 4-6=-45/427
WEBS 3-6=0/192

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 272 lb uplift at joint 2 and 272 lb uplift at joint 4.

LOAD CASE(S) Standard





6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:52 2005 Page 1



LOADING	(psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL	20.0	Plates Increase	1.25	TC	0.34	Vert(LL)	0.48	13-14	>522	240	MT20	244/190
TCDL	7.0	Lumber Increase	1.25	BC	0.66	Vert(TL)	0.40	13-14	>630	180		
BCLL	10.0	Rep Stress Incr	YES	WB	0.47	Horz(TL)	0.03	9	n/a	n/a		
BCDL	5.0	Code FBC2001/TPI2002		(Matrix)								
										Weight: 159 lb		

BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purfins, except end verticals
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing. Except:
	1 Row at midpt 5-13


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=-250/232, 3-4=-928/845, 4-5=-850/939, 5-6=-989/927, 6-7=-882/843, 7-8=0/58, 7-9=-920/832
BOT CHORD 2-14=141/349, 13-14=-554/760, 11-13=-65/127, 5-13=-148/152, 11-12=0/0, 10-11=-104/190, 9-10=-11/52
WEBS 3-13=-117/161, 6-10=-422/186, 3-14=-1192/861, 7-10=-513/684, 4-13=-651/633, 10-13=-103/862, 6-13=-79/203

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); $h=20ft$; $TCDD=4.2psf$; $BCDL=3.0psf$; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; and vertical right exposed; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 449 lb uplift at joint 9 and 729 lb uplift at joint 14.

LOAD CASE(S) Standard

Job Reference (optional)

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:50:54 2005 Page 1



Weight: 209 lb


TOP CHORD	Structural wood sheathing directly applied or 4-2-4 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 5-0-3 oc bracing.

REACTIONS (lb/size) 11=1749/0-3-8, 16=2025/0-3-8
Max Horz 16=269(load case 4)
Max Uplift 11=-947(load case 5), 16=-1311(load case 5)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-49/112, 2-3=-509/486, 3-4=-574/725, 4-5=-1633/1504, 5-6=-1413/1486, 6-7=-1730/1626, 7-8=-1424/1415, 8-9=-1569/1477, 9-10=-49/110, 9-11=-1653/1542
BOT CHORD 2-16=526/611, 15-16=-1353/1456, 13-15=-71/134, 6-15=-164/214, 13-14=0/0, 12-13=-86/220, 11-12=-130/176
WEBS 4-15=-238/235, 7-12=-787/569, 4-16=-2494/2078, 9-12=-928/1115, 5-15=-861/850, 12-15=-1336/1426, 7-15=-86/192

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); $h=20ft$; $TCDF=4.2psf$; $BCDF=3.0psf$; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed ; end vertical right exposed; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- 4) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- 5) All plates are MT20 plates unless otherwise indicated.
- 6) All plates are 2x4 MT20 unless otherwise indicated.
- 7) The following joint(s) require plate inspection per the Tooth Count Method when this truss is chosen for quality assurance inspection: 5.
- 8) Gable studs spaced at 2-0-0 oc.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 947 lb uplift at joint 11 and 1311 lb uplift at joint 16.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-5=114(F=60), 5-9=114(F=60), 9-10=114(F=60), 2-15=30, 13-14=30, 11-13=30



Job L130833	Truss T06	Truss Type COMMON	Qty 1	Ply 2	Dwg.#092105623
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:56 2005 Page 1		



Job L130833	Truss T07	Truss Type MONO HIP	Qty 1	Ply 1	Dwg.#092105624
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:50:57 2005 Page 1		




Plate Offsets (X,Y): [2:0-3:15,Edge]

LOADING (psf)	SPACING	2:0-0	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.73	Vert(LL)	-0.22 11-12	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.79	Vert(TL)	-0.36 11-12	>886	180	MT20H	187/143
BCLL 10.0	Rep Stress Incr	NO	WB 0.99	Horz(TL)	0.11 8	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)						
Weight: 149 lb									

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3
WEDGE
Left: 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 4-5-15 oc bracing.
WEBS 1 Row at midpt 7-8, 5-9, 7-9

REACTIONS

(lb/size) 8=2449/0-3-8, 2=2323/0-3-8
Max Horz 2=265(load case 4)
Max Uplift 8=1408(load case 2), 2=1152(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/54, 2-3=3863/2000, 3-4=4004/2235, 4-5=4004/2236, 5-6=2410/1378, 6-7=2410/1378, 7-8=2287/1420
BOT CHORD 2-13=1760/3234, 12-13=1772/3263, 11-12=2097/3716, 10-11=2097/3716, 9-10=2097/3716, 8-9=4170
WEBS 3-13=323/822, 3-12=747/965, 4-12=558/653, 5-12=233/380, 5-11=0/316, 5-9=1725/950, 6-9=583/620, 7-9=1765/3089


NOTES


- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) Provide adequate drainage to prevent water ponding.
- 3) All plates are MT20 plates unless otherwise indicated.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1408 lb uplift at joint 8 and 1152 lb uplift at joint 2.
- 5) Girder carries hip end with 0-0-0 right side setback, 7-0-0 left side setback, and 7-0-0 end setback.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 539 lb down and 374 lb up at 7-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard


- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-3=-54, 3-7=-118(F=-64), 2-13=-30, 8-13=-65(F=-35)
Concentrated Loads (lb)
Vert: 13=539(F)







Job L130833	Truss T11	Truss Type HIP	Qty 1	Ply 1	Dwg.#092105628
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:00 2005 Page 1		



LOADING (psf)		SPACING 2-0-0	CSI	DEFL	PLATES	GRIP
TCCL	20.0	Plates Increase 1.25	TC 0.41	in (loc) l/def L/d	MT20	244/190
TCCL	7.0	Lumber Increase 1.25	BC 0.44	Vert(LL) -0.14 10-11 >999 240		
BCCL	10.0	Rep Stress Incr YES	WB 0.55	Vert(TL) -0.24 10-11 >999 180		
BCCL	5.0	Code FBC2001/TPI2002	(Matrix)	Horz(TL) 0.02 7 n/a n/a		
						Weight: 147 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3 *Except*
W1 2 X 4 SYP No.2D, W7 2 X 4 SYP No.2D

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 9-7-12 oc bracing.

REACTIONS (lb/size) 11=933/0-3-8, 7=933/Mechanical
Max Horz 11=210(load case 5)
Max Uplift 11=251(load case 5), 7=232(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-478/130, 2-3=-989/397, 3-4=-800/397, 4-5=-454/253, 5-6=-567/243, 1-11=-343/147, 6-7=-904/366
BOT CHORD 10-11=-453/902, 9-10=-291/697, 8-9=-9/9, 7-8=-9/9
WEBS 2-10=-137/228, 3-10=-17/213, 4-10=-101/206, 4-9=-483/274, 5-9=-5/92, 2-11=-702/321, 6-9=-246/711

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 251 lb uplift at joint 11 and 232 lb uplift at joint 7.

LOAD CASE(S) Standard

Job L130833	Truss T12	Truss Type SPECIAL	Qty 1	Ply 1	Dwg.#092105629
----------------	--------------	-----------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:00 2005 Page 1




Plate Offsets (X,Y): [1:0-3-6,Edge], [3:0-1-8,0-2-0]

LOADING (psf)	SPACING	CSI	DEFL	in (loc)	l/def	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	Vert(LL)	-0.35	3-10	>760	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.51	Vert(TL)	-0.58	3-10	>459		
BCLL 10.0	Lumber Increase 1.25	WB 0.46	Horz(TL)	0.33	14	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)						
	Code FBC2001/TPI2002							
							Weight: 157 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D *Except*
T1 2 X 8 SYP 2400F 2.0E
BOT CHORD 2 X 4 SYP No.2D *Except*
B3 2 X 4 SYP No.3, B3 2 X 4 SYP No.3
WEBS 2 X 4 SYP No.3 *Except*
W5 2 X 4 SYP No.2D
SLIDER Left 2 X 6 SYP No.1D 1-8-10

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-11-8 oc bracing: 3-10.

REACTIONS

(lb/size) 1=954/0-3-8, 14=941/Mechanical
Max Horz 1=282(load case 5)
Max Uplift 1=-296(load case 5), 14=-298(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-662/131, 2-3=-290/108, 3-4=-1713/700, 4-5=-1191/495, 5-6=-700/380, 6-7=-880/370, 8-14=-941/358, 7-8=-842/370
BOT CHORD 1-11=0/0, 3-10=-820/1649, 9-10=-364/940, 8-9=-44/84
WEBS 4-10=-848/540, 5-10=-249/700, 5-9=-451/203, 6-9=-50/198, 7-9=-243/677

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 296 lb uplift at joint 1 and 298 lb uplift at joint 14.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:03 2005 Page 1




Plate Offsets (X,Y): [1:Edge,0-0-1], [3:0-6-8,Edge], [5:0-7-0-0-5], [8:0-3-8,Edge]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.49	in (loc) l/defl L/d	MT20	244/190
TCCL 7.0	Plates Increase 1.25	BC 0.72	Vert(LL) -0.24 3-11 >999 240	MT18H	244/190
BCCL 10.0	Lumber Increase 1.25	WB 0.78	Vert(TL) -0.39 3-11 >684 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.35 15 n/a n/a		
	Code FBC2001/TPI2002			Weight: 154 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D *Except*
T1 2 X 8 SYP 2400F 2.0E
BOT CHORD 2 X 4 SYP No.2D *Except*
B3 2 X 4 SYP No.3, B3 2 X 4 SYP No.3
WEBS 2 X 4 SYP No.3 *Except*
W5 2 X 4 SYP No.2D
SLIDER Left 2 X 6 SYP No.1D 1-8-10

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-6-2 oc bracing.

REACTIONS

(lb/size) 1=954/0-3-8, 15=941/Mechanical
Max Horz 1=305(load case 5)
Max Uplift 1=270(load case 5), 15=269(load case 5)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-811/183, 2-3=-531/114, 3-4=-1627/599, 4-5=-937/417, 5-6=-709/412, 6-7=-709/412, 7-8=-929/382, 9-15=-941/346, 8-9=-814/366
BOT CHORD 1-12=-71/115, 3-12=-9/62, 3-11=-683/1498, 10-11=-683/1497, 9-10=-84/155
WEBS 8-10=-189/586, 6-10=-181/548, 4-11=0/195, 4-10=-954/553

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) The following joint(s) require plate inspection per the Tooth Count Method when this truss is chosen for quality assurance inspection: 5.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 270 lb uplift at joint 1 and 269 lb uplift at joint 15.

LOAD CASE(S) Standard

Job L130833	Truss T14	Truss Type SPECIAL	Qty 4	Ply 1	Dwg.#092105631
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:04 2005 Page 1		




Plate Offsets (X,Y): [1:0-3-8 Edge], [3:0-1-8,0-2-0], [6:0-3-8 Edge]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.55	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.53	Vert(LL) -0.31 10 >864 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.76	Vert(TL) -0.50 10 >533 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.36 13 n/a n/a		
	Code FBC2001/TPI2002			Weight: 155 lb	

LUMBER

TOP CHORD 2 X 8 SYP 2400F 2.0E *Except*
T2 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D *Except*
B3 2 X 4 SYP No.3, B3 2 X 4 SYP No.3
WEBS 2 X 4 SYP No.3 *Except*
W5 2 X 4 SYP No.2D
SLIDER Left 2 X 6 SYP No.1D 1-8-10

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-6-6 oc bracing.

REACTIONS

(lb/size) 1=954/0-3-8, 13=941/Mechanical
Max Horz 1=307(load case 5)
Max Uplift 1=-272(load case 5), 13=-275(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-662/136, 2-3=-290/133, 3-4=-1616/587, 4-5=-928/416, 5-6=-932/381, 7-13=-941/347, 6-7=-816/364
BOT CHORD 1-10=0/0, 3-9=-676/1479, 8-9=-676/1479, 7-8=-81/152
WEBS 5-8=-179/550, 6-8=-200/599, 4-9=0/228, 4-8=-945/543

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98: 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 272 lb uplift at joint 1 and 275 lb uplift at joint 13.

LOAD CASE(S) Standard

Job L130833	Truss T15	Truss Type SPECIAL	Qty 1	Ply 3	Dwg.#092105632
Builders FirstSource, Lake City, FL 32055			6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:05 2005 Page 1		

-2-0-0	3-6-14	6-0-15	11-1-8	16-2-0	20-8-4	25-0-12	29-7-0	32-10-3	36-7-0
2-0-0	3-6-14	2-6-1	5-0-8	5-0-8	4-6-4	4-4-8	4-6-4	3-3-3	3-8-13

Scale = 1:65.7

3-6-14	6-0-15	11-1-8	16-2-0	20-8-4	25-0-12	29-7-0	32-10-3	36-7-0
3-6-14	2-6-1	5-0-8	5-0-8	4-6-4	4-4-8	4-6-4	3-3-3	3-8-13

Plate Offsets (X,Y): [2-0-2-14,0-2-0], [12-0-1-2,0-0-7], [13-0-3-0,0-3-0], [16-0-3-8,0-3-0]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.31	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.56	Vert(LL) 0.28 18-19 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.72	Vert(TL) -0.44 18-19 >998 180		
BCDL 5.0	Rep Stress incr NO	(Matrix)	Horz(TL) 0.14 12 n/a n/a		
	Code FBC2001/TPI2002			Weight: 682 lb	

LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.1D WEBS 2 X 4 SYP No.3 "Except" W1 2 X 4 SYP No.2D	BRACING TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
---	---

REACTIONS (lb/size) 12=3160/0-3-8, 23=3733/0-3-8
 Max Horz 23=168(load case 3)
 Max Uplift 12=1698(load case 2), 23=2014(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/58, 2-3=3290/1898, 3-4=5292/3130, 4-5=7901/4620, 5-6=7901/4620, 6-7=9411/5487, 7-8=6604/3876, 8-9=6604/3876, 9-10=6605/3875, 10-11=5582/3210, 11-12=5714/3142, 2-23=3487/1930
 BOT CHORD 22-23=-175/110, 21-22=-269/314, 20-21=-171, 4-20=-2045/1454, 19-20=-3238/5447, 18-19=-5570/9579, 17-18=-15/210, 6-18=-86/562, 16-17=-533/909, 15-16=-4295/7464, 14-15=-2699/4837, 13-14=-2624/4817, 12-13=-2624/4817
 WEBS 3-22=-2081/1254, 20-22=-1478/2607, 3-20=-2551/4337, 4-19=-1771/2954, 5-19=-608/640, 6-19=-2003/1192, 16-18=-3844/6698, 7-18=-1473/2424, 7-16=-1170/897, 7-15=-1221/753, 9-15=-507/549, 10-15=-1495/2441, 10-14=-369/776, 11-14=-252/135, 11-13=0/54, 2-22=-1793/3150

NOTES
 1) 3-ply truss to be connected together with 0.131"x3" Nails as follows:
 Top chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 Webs connected as follows: 2 X 4 - 1 row at 0-9-0 oc.
 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 3) Unbalanced roof live loads have been considered for this design.
 4) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60.
 5) Provide adequate drainage to prevent water ponding.
 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1698 lb uplift at joint 12 and 2014 lb uplift at joint 23.
 7) Girder carries tie-in span(s): 7-0-0 from 0-0-0 to 3-6-14
 8) Girder carries hip end with 7-0-0 right side setback, 3-6-14 left side setback, and 7-0-0 end setback.
 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 539 lb down and 374 lb up at 29-7-0, and 275 lb down and 191 lb up at 3-6-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54, 2-3=-54, 3-10=-118(F=-64), 10-12=-54, 22-23=-129(F=-99), 21-22=-65(F=-35), 18-20=-65(F=-35), 14-17=-65(F=-35), 12-14=-30
 Concentrated Loads (lb)
 Vert: 22=-275(F) 14=-539(F)

Job L130833	Truss T16	Truss Type SPECIAL	Qty 1	Ply 1	Dwg.#092105633
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:06 2005 Page 1		

-2-0-0	5-6-14	6-0-15	11-0-3	16-2-0	21-10-8	27-7-0	31-10-3	36-7-0
2-0-0	5-6-14	0-6-1	4-11-4	5-1-13	5-8-8	5-8-8	4-3-3	4-8-13

Scale = 1/8" = 1'-0"




Plate Offsets (X,Y): [2-0-2-9-0-2-8], [10-0-0-0-0-0-4], [11-0-4-0-0-3-0], [12-0-3-8-0-3-0], [15-0-2-8-0-2-4]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.31	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.92	Vert(LL) -0.49 14-15 >891 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.83	Vert(TL) -0.82 14-15 >529 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.14 10 n/a n/a		
	Code FBC2001/TPI2002				
				Weight: 221 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D *Except*
B3 2 X 4 SYP No.3
WEBS 2 X 4 SYP No.3 *Except*
W1 2 X 4 SYP No.2D, W4 2 X 4 SYP No.1D

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-7-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 4-15


REACTIONS (lb/size) 10=1522/0-3-8, 18=1649/0-3-8
Max Horz 18=208(load case 4)
Max Uplift 10=503(load case 3), 18=559(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/58, 2-3=-1894/765, 3-4=-1614/721, 4-5=-3081/1240, 5-6=-3031/1237, 6-7=-1987/860, 7-8=-1988/860, 8-9=-2341/931,
9-10=-2557/1003, 2-18=-1549/717
BOT CHORD 17-18=-1848, 16-17=0/0, 14-15=-1121/2497, 13-14=0/108, 5-14=-287/240, 12-13=-177/21, 11-12=-972/2525, 10-11=-789/2157
WEBS 4-15=-1219/656, 4-14=-255/786, 12-14=-802/2526, 6-14=-324/684, 6-12=-223/146, 6-11=-817/491, 8-11=-274/881, 9-11=-220/234,
15-17=0/84, 3-15=-227/674, 15-18=-164/219, 2-15=-605/1548

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 503 lb uplift at joint 10 and 559 lb uplift at joint 18.

LOAD CASE(S) Standard



Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:07 2005 Page 1




Plate Offsets (X,Y): [2-0-2-14,0-2-0], [11-0-8-1,0-0-10], [12-0-3-8,0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.25	Vert(LL)	-0.34	21	>999	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.74	Vert(TL)	-0.58	21	>719		
BCLL 10.0	Lumber Increase 1.25	WB 0.71	Horz(TL)	0.17	11	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)						
	Code FBC2001/TP12002						Weight: 260 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D "Except"
 B3 2 X 4 SYP No.3, B5 2 X 4 SYP No.3, B7 2 X 4 SYP No.3
 WEBS 2 X 4 SYP No.3 "Except"
 W1 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-7-4 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 4-20

REACTIONS

(lb/size) 11=1470/0-3-8, 22=1834/0-4-15
 Max Horz 22=-235(load case 3)
 Max Uplift 11=-394(load case 6), 22=-477(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/58, 2-3=-92/7, 3-4=-166/127, 4-5=-1635/662, 5-6=-1852/817, 6-7=-2226/915, 7-8=-2234/913, 8-9=-3063/1214, 9-10=-3096/1117,
 10-11=-2536/903, 2-23=-291/0
 BOT CHORD 22-23=-74/56, 21-22=0/0, 19-20=-498/1198, 18-19=-504/1383, 17-18=-504/1383, 16-17=-25/106, 15-16=0/90, 7-15=-183/175,
 14-15=-542/2114, 13-14=0/73, 9-14=-189/194, 12-13=-14/59, 11-12=-696/2113
 WEBS 4-19=-241/365, 5-19=-26/244, 2-22=0/257, 20-22=-1541/809, 3-20=-238/151, 4-20=-1667/676, 10-12=-677/303, 12-14=-738/2221,
 10-14=-259/512, 8-15=-312/474, 8-14=-464/1160, 6-17=-752/404, 5-17=-392/724, 15-17=-602/1790, 6-15=-141/552

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
- Provide adequate drainage to prevent water ponding.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 394 lb uplift at joint 11 and 477 lb uplift at joint 22.

LOAD CASE(S) Standard

Job L130833	Truss T19	Truss Type SPECIAL	Qty 1	Ply 1	Dwg.#092105636
----------------	--------------	-----------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:08 2005 Page 1




Plate Offsets (X,Y): [2-0-3-0-0-1-8], [11-0-8-1-0-0-10], [12-0-3-8-0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.48	in (loc) l/def L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.55	Vert(LL) 0.35 15-16 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.71	Vert(TL) -0.37 15-16 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.16 11 n/a n/a		
	Code FBC2001/TP12002				
					Weight: 273 lb

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD
BOT CHORD 2 X 4 SYP No.2D "Except"	BOT CHORD
B3 2 X 4 SYP No.3, B6 2 X 4 SYP No.3	Structural wood sheathing directly applied or 3-5-9 oc purlins, except end verticals.
WEBS 2 X 4 SYP No.3 "Except"	Rigid ceiling directly applied or 4-11-15 oc bracing. Except:
W1 2 X 4 SYP No.2D	1 Row at midpt 7-16
	WEBS 1 Row at midpt 6-20, 16-20, 4-21, 8-15

REACTIONS (lb/size) 11=1400/0-3-8, 21=1833/0-4-15
Max Horz 21=309(load case 5)
Max Uplift 11=-769(load case 3), 21=-1050(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/58, 2-3=-142/258, 3-4=-34/263, 4-5=-1149/1079, 5-6=-958/988, 6-7=-1680/1562, 7-8=-1693/1573, 8-9=-3219/2794, 9-10=-3167/2617, 10-11=-2395/1948, 2-22=-5/6
BOT CHORD 21-22=-47/70, 20-21=-739/657, 19-20=-186/69, 18-19=-186/69, 17-18=0/0, 16-18=-147/164, 7-16=-95/141, 15-16=-1315/1689, 13-15=-47/90, 9-15=-252/251, 13-14=0/0, 12-13=-28/38, 11-12=-1592/1990
WEBS 5-20=-363/336, 6-20=-897/684, 6-16=-484/603, 16-20=-1121/1340, 10-12=-858/645, 12-15=-1836/2205, 10-15=-486/726, 3-21=-217/190, 2-21=-161/213, 4-20=-409/534, 4-21=-1552/1190, 8-15=-1423/1604, 8-16=-276/265

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 769 lb uplift at joint 11 and 1050 lb uplift at joint 21.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)

6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:09 2005 Page 1






Plate Offsets (X,Y): [2-0-3-3,0-1-8], [10-0-8-1,0-0-10], [15-0-4-0,0-3-0]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.27	Vert(LL)	-0.31 14-15	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.54	Vert(TL)	-0.51 14-15	>797	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.82	Horz(TL)	0.15 10	n/a	n/a		
BCDL 5.0	Code FBC2001/TPI2002		(Matrix)						
								Weight: 229 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D *Except*
 B4 2 X 4 SYP No.3
 WEBS 2 X 4 SYP No.3


BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-2-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 10=1463/0-3-8, 18=1770/0-4-15
 Max Horz 18=-318(load case 3)
 Max Uplift 10=-425(load case 6), 18=-625(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-435/356, 3-4=-1699/532, 4-5=-1647/643, 5-6=-1570/680, 6-7=-1860/730, 7-8=-3786/1281, 8-9=-3743/1179, 9-10=-2515/823
 BOT CHORD 2-18=-262/462, 17-18=-262/475, 16-17=-361/1401, 15-16=-289/1361, 14-15=-490/2102, 12-14=0/108, 8-14=-165/155, 12-13=0/0,
 11-12=-42/0, 10-11=-625/2092
 WEBS 3-18=-1633/813, 3-17=-728/1708, 4-17=-240/218, 4-16=-180/142, 5-16=-59/215, 5-15=-197/444, 6-15=-177/633, 7-15=-865/408,
 11-14=-712/2569, 9-14=-217/1182, 9-11=-1335/422, 7-14=-546/1806

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; cantilever left exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 - 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 425 lb uplift at joint 10 and 625 lb uplift at joint 18.

LOAD CASE(S) Standard



Job L130833	Truss T22	Truss Type SPECIAL	Qty 1	Ply 1	Dwg.#092105639
----------------	--------------	-----------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mittek Industries, Inc. Tue Sep 20 17:51:11 2005 Page 1




Plate Offsets (X,Y): [2:0-2-6,0-0-11], [3:0-3-0,0-3-0], [10:0-1-3,Edge], [11:0-3-8,0-2-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.40	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.75	Vert(LL) -0.57 14-16 >761 240		
BCLL 10.0	Rep Stress Incr YES	WB 0.91	Vert(TL) -0.96 14-16 >454 180		
BCDL 5.0	Code FBC2001/TPI2002	(Matrix)	Horz(TL) 0.22 10 n/a n/a		
				Weight: 214 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D "Except"
B4 2 X 4 SYP No.3
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-11-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 4-16, 6-16

REACTIONS

(lb/size) 2=1650/0-3-8, 10=1569/0-3-8
Max Horz 2=-381(load case 3)
Max Uplift 2=-552(load case 5), 10=-468(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension:

TOP CHORD 1-2=0/49, 2-3=-2540/872, 3-4=-2341/845, 4-5=-1779/732, 5-6=-1791/729, 6-7=-4247/1426, 7-8=-4057/1290, 8-9=-4120/1279,
9-10=-2719/891
BOT CHORD 2-17=-642/2131, 16-17=-433/1815, 15-16=-499/2122, 14-15=-499/2122, 12-14=0/102, 7-14=-228/206, 12-13=0/0, 11-12=-89/0,
10-11=-682/2266
WEBS 3-17=-261/242, 4-17=-133/446, 4-16=-553/349, 5-16=-528/1415, 6-16=-949/485, 6-14=-648/2184, 9-11=-1483/453, 11-14=-760/2837,
9-14=-264/1349


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 552 lb uplift at joint 2 and 468 lb uplift at joint 10.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mittek Industries, Inc. Tue Sep 20 17:51:12 2005 Page 1



Job L130833	Truss T24	Truss Type COMMON	Qty 1	Ply 1	Dwg.#092105641
----------------	--------------	----------------------	----------	----------	----------------

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:12 2005 Page 1




Plate Offsets (X,Y): [1:0-4-10,Edge], [3:0-3-0-0-3-0]

LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.40	Vert(LL) -0.19 8-10 >999 240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.55	Vert(TL) -0.33 8-10 >994 180		
BCLL 10.0	Rep Stress Incr YES	WB 0.51	Horz(TL) 0.04 8 n/a n/a		
BCDL 5.0	Code FBC2001/TPI2002	(Matrix)			Weight: 174 lb

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3 *Except*
W7 2 X 4 SYP No.2D
SLIDER Left 2 X 4 SYP No.2D 3-5-7

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-1-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-10-5 oc bracing.
WEBS 1 Row at midpt 4-10, 6-8

REACTIONS (lb/size) 1=1158/0-4-15, 8=1158/Mechanical
Max Horz 1=349(load case 4)
Max Uplift 1=349(load case 5), 8=324(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-1718/584, 2-3=-1567/602, 3-4=-1506/581, 4-5=-929/452, 5-6=-915/458, 6-7=-153/88, 7-8=-182/123
BOT CHORD 1-11=-674/1391, 10-11=-453/1094, 9-10=-223/616, 8-9=-223/616
WEBS 3-11=-241/260, 4-11=-158/456, 4-10=-594/386, 5-10=-259/561, 6-10=-118/286, 6-8=-990/393

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 349 lb uplift at joint 1 and 324 lb uplift at joint 8.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:13 2005 Page 1




Plate Offsets (X,Y): [1:Edge,0-1-12]

LOADING (psf)	SPACING	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase	1.25	TC 0.37	Vert(LL)	-0.13	7-9	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase	1.25	BC 0.46	Vert(TL)	-0.23	7-9	>999	180		
BCLL 10.0	Rep Stress Incr	YES	WB 0.34	Horz(TL)	0.02	7	n/a	n/a		
BCDL 5.0	Code FBC2001/TP12002		(Matrix)							
										Weight: 192 lb

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3 "Except"
 W1 2 X 4 SYP No.2D, W9 2 X 4 SYP No.2D

BRACING
 TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 9-8-9 oc bracing.
 WEBS 1 Row at midpt 2-10, 3-9, 5-7

REACTIONS (lb/size) 12=1067/0-4-3, 7=1067/Mechanical
 Max Horz 12=280(load case 4)
 Max Uplift 12=307(load case 5), 7=301(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-1259/438, 2-3=-892/419, 3-4=-653/409, 4-5=-819/419, 5-6=-128/78, 1-12=-959/373, 6-7=-158/110
 BOT CHORD 11-12=-357/241, 10-11=-450/1004, 9-10=-211/685, 8-9=-200/539, 7-8=-200/539
 WEBS 2-11=0/108, 2-10=-441/310, 3-10=-181/312, 3-9=-275/252, 4-9=-189/330, 5-9=-114/237, 1-11=-175/815, 5-7=-912/370


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCCL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 307 lb uplift at joint 12 and 301 lb uplift at joint 7.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

Job Reference (optional)
6.200 s Jul 13 2005 Mitek Industries, Inc. Tue Sep 20 17:51:14 2005 Page 1



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.38	in (loc) l/defl L/d	MT20	244/190
TCCL 7.0	Plates Increase 1.25	BC 0.34	Vert(LL) -0.14 11-12 >999 240		
BCCL 10.0	Lumber Increase 1.25	WB 0.85	Vert(TL) -0.25 11-12 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.02 8 n/a n/a		
	Code FBC2001/TPI2002			Weight: 182 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3 *Except*
W1 2 X 4 SYP No.2D, W9 2 X 4 SYP No.2D

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-11, 4-10

REACTIONS (lb/size) 12=933/0-3-8, 8=933/Mechanical
Max Horz 12=197(load case 4)
Max Uplift 12=284(load case 5), 8=261(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-165/82, 2-3=-747/362, 3-4=-594/362, 4-5=-589/361, 5-6=-672/353, 6-7=-119/66, 1-12=-180/114, 7-8=-147/95
BOT CHORD 11-12=-298/536, 10-11=-176/570, 9-10=-158/423, 8-9=-158/423
WEBS 2-11=-112/130, 3-11=-28/140, 4-11=-130/124, 4-10=-401/260, 5-10=-194/376, 6-10=-96/255, 2-12=-756/300, 6-8=-751/316

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98: 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate gnp DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 284 lb uplift at joint 12 and 261 lb uplift at joint 8.

LOAD CASE(S) Standard




Plate Offsets (X,Y): [1:0-8-1,0-0-6]

LOADING (psf)		SPACING		CSI		DEFL				PLATES		GRIP	
TCLL	20.0	2-0-0		TC	0.42	in	(loc)	I/defl	L/d	MT20		244/190	
TCDL	7.0	Plates Increase	1.25	BC	0.45	Vert(LL)	0.09	8-9	>999				
BCLL	10.0	Lumber Increase	1.25	WB	0.48	Vert(TL)	-0.13	8-9	>999				
BCDL	5.0	Rep Stress Incr	NO	(Matrix)		Horz(TL)	0.03	6	n/a				
											Weight: 88 lb		

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3 *Except*
 W4 2 X 4 SYP No.2D

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-4-7 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-10-3 oc bracing.

REACTIONS (lb/size) 1=1194/0-3-8, 6=1438/0-4-15
 Max Horz 1=102(load case 4)
 Max Uplift 1=804(load case 3), 6=955(load case 2)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2026/1388, 2-3=-2037/1487, 3-4=-2037/1487, 4-5=-1309/874, 5-6=-1424/933
 BOT CHORD 1-9=-1239/1694, 8-9=-1253/1717, 7-8=-758/1117, 6-7=-11/11
 WEBS 2-9=-289/463, 2-8=-399/456, 3-8=-486/496, 4-8=-850/1079, 4-7=-219/245, 5-7=-943/1353

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60.
- Provide adequate drainage to prevent water ponding.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 804 lb uplift at joint 1 and 955 lb uplift at joint 6.
- Girder carries hip end with 2-4-15 right side setback, 5-0-0 left side setback, and 5-0-0 end setback.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 363 lb down and 198 lb up at 15-2-0, and 245 lb down and 170 lb up at 5-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54, 2-4=-91(F=-37), 4-5=-54, 1-9=-30, 7-9=-50(F=-20), 6-7=-30
 Concentrated Loads (lb)
 Vert: 9=-245(F) 7=-363(F)




Plate Offsets (X,Y): [1:0-3,3:0-1-8]

LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.37	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.38	Vert(LL) 0.22 1-7 >930 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.30	Vert(TL) 0.18 1-7 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) -0.02 5 n/a n/a		
	Code FBC2001/TPI2002				
				Weight: 84 lb	

LUMBER	BRACING
TOP CHORD 2 X 4 SYP No.2D	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2 X 4 SYP No.2D	BOT CHORD Rigid ceiling directly applied or 6-5-2 oc bracing.
WEBS 2 X 4 SYP No.3 *Except*	
W4 2 X 4 SYP No.2D	

REACTIONS (lb/size) 1=705/0-3-8, 5=705/0-3-8
 Max Horz 1=136(load case 4)
 Max Uplift 1=-413(load case 4), 5=-408(load case 3)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-996/983, 2-3=-543/661, 3-4=-670/708, 4-5=-648/665
 BOT CHORD 1-7=-837/783, 6-7=-851/792, 5-6=-54/40
 WEBS 2-7=-407/242, 2-6=-338/348, 3-6=-190/93, 4-6=-561/559

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 413 lb uplift at joint 1 and 408 lb uplift at joint 5.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 Mittek Industries, Inc. Tue Sep 20 17:51:16 2005 Page 1




Plate Offsets (X,Y): [8-0-4-0,0-0-8]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.66	Vert(LL)	0.08	7-8	>999	240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.43	Vert(TL)	-0.12	7-8	>999	180		
BCLL 10.0	Rep Stress Incr NO	WB 0.55	Horz(TL)	0.08	6	n/a	n/a		
BCDL 5.0	Code FBC2001/TP12002	(Matrix)							
									Weight: 65 lb

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 4 SYP No.2D
 WEBS 2 X 4 SYP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-5-1 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-9-13 oc bracing.

REACTIONS (lb/size) 6=939/0-3-8, 2=956/0-3-8
 Max Horz 2=210(load case 4)
 Max Uplift 6=-484(load case 2), 2=-475(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/53, 2-3=-2060/961, 3-4=-1758/876, 4-5=-1723/874, 5-6=-821/507
 BOT CHORD 2-8=-875/1756, 7-8=-903/1754, 6-7=-56/128
 WEBS 3-8=-408/808, 4-8=-62/183, 4-7=-372/348, 5-7=-874/1724

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- 2) Provide adequate drainage to prevent water ponding.
- 3) Bearing at joint(s) 6, 2 considers parallel to grain value using ANSI/TP1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 484 lb uplift at joint 6 and 475 lb uplift at joint 2.
- 5) Girder carries hip end with 0-0-0 right side setback, 5-0-0 left side setback, and 5-0-0 end setback.
- 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 245 lb down and 170 lb up at 5-1-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-3=-54, 3-5=-91(F=-37), 2-8=-30, 7-8=-50(F=-20), 6-7=-50(F=-20)
 Concentrated Loads (lb)
 Vert: 6=-245(F)

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:16 2005 Page 1




Plate Offsets (X,Y): [3:0-3-1,Edge]

LOADING (psf)	SPACING	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.37	Vert(LL)	-0.07	2-6	>999	240	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.34	Vert(TL)	-0.11	2-6	>999	180		
BCLL 10.0	Lumber Increase 1.25	WB 0.35	Horz(TL)	0.04	5	n/a	n/a		
BCDL 5.0	Rep Stress Incr YES	(Matrix)							
	Code FBC2001/TPI2002								
								Weight: 64 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-11-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(lb/size) 5=531/0-3-8, 2=666/0-3-8
Max Horiz 2=263(load case 5)
Max Uplift 5=-183(load case 4), 2=-278(load case 5)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=-1069/363, 3-4=-816/407, 4-5=-451/270
BOT CHORD 2-6=-408/890, 5-6=-33/68
WEBS 3-6=0/129, 4-6=-421/833


NOTES

- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Provide adequate drainage to prevent water ponding.
- Bearing at joint(s) 5, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 183 lb uplift at joint 5 and 278 lb uplift at joint 2.

LOAD CASE(S) Standard

Builders FirstSource, Lake City, FL 32055

6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:17 2005 Page 1



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.29	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.25	Vert(LL) -0.06 2-8 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.22	Vert(TL) -0.10 2-8 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.04 6 n/a n/a		
	Code FBC2001/TPI2002				
				Weight: 77 lb	

LUMBER

TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 9-0-6 oc bracing.

REACTIONS

(lb/size) 6=531/0-3-8, 2=666/0-3-8
Max Horz 2=317(load case 5)
Max Uplift 6=175(load case 5), 2=274(load case 5)


FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/53, 2-3=1132/394, 3-4=908/324, 4-5=347/181, 5-6=473/274
BOT CHORD 2-8=513/962, 7-8=193/384, 6-7=9/27
WEBS 3-8=210/210, 4-8=261/686, 4-7=386/251, 5-7=266/503

NOTES

- 1) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- 2) Provide adequate drainage to prevent water ponding.
- 3) Bearing at joint(s) 6, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 175 lb uplift at joint 6 and 274 lb uplift at joint 2.

LOAD CASE(S) Standard





LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2'-0"	TC 0.27	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.05	Vert(LL) -0.00 6-7 >999 240		
BCLL 10.0	Lumber Increase 1.25	WB 0.03	Vert(TL) -0.00 6-7 >999 180		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 6 n/a n/a		
	Code FBC2001/TPI2002				
				Weight: 42 lb	

LUMBER TOP CHORD 2 X 4 SYP No.2D BOT CHORD 2 X 4 SYP No.2D WEBS 2 X 4 SYP No.3 *Except* W1 2 X 4 SYP No.2D, W1 2 X 4 SYP No.2D	BRACING TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.
---	---


REACTIONS (lb/size) 8=363/0-3-8, 6=363/0-3-8
 Max Horz 8=123(load case 4)
 Max Uplift 8=200(load case 5), 6=200(load case 6)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/58, 2-3=-170/90, 3-4=-170/90, 4-5=0/58, 2-8=-328/250, 4-6=-328/250
 BOT CHORD 7-8=-107/111, 6-7=-13/26
 WEBS 3-7=-68/47, 2-7=-5/126, 4-7=-5/126

NOTES
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; end vertical left and right exposed; Lumber DOL=1.60 plate gnp DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 200 lb uplift at joint 8 and 200 lb uplift at joint 6.

LOAD CASE(S) Standard

Job L130833	Truss T33G	Truss Type COMMON	Qty 1	Ply 1	Dwg.#092105651
Builders FirstSource, Lake City, FL 32055			Job Reference (optional) 6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:19 2005 Page 1		



LOADING (psf)	SPACING	CSI	DEFL	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.26	in (loc) l/defl L/d	MT20	244/190
TCDL 7.0	Plates Increase 1.25	BC 0.05	Vert(LL) -0.03 7 n/r 90		
BCLL 10.0	Lumber Increase 1.25	WB 0.04	Vert(TL) -0.05 7 n/r 80		
BCDL 5.0	Rep Stress Incr YES	(Matrix)	Horz(TL) 0.00 8 n/a n/a		
	Code FBC2001/TPI2002			Weight: 38 lb	

LUMBER
TOP CHORD 2 X 4 SYP No.2D
BOT CHORD 2 X 4 SYP No.2D
WEBS 2 X 4 SYP No.2D
OTHERS 2 X 4 SYP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 12=164/6-2-0, 8=164/6-2-0, 10=254/6-2-0, 11=72/6-2-0, 9=72/6-2-0
Max Horz 12=90(load case 5)
Max Uplift 12=173(load case 5), 8=183(load case 6), 10=24(load case 5), 11=75(load case 4), 9=70(load case 3)
Max Grav 12=206(load case 7), 8=206(load case 8), 10=254(load case 1), 11=98(load case 3), 9=93(load case 4)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/58, 2-3=-30/58, 3-4=-1/100, 4-5=0/100, 5-6=-25/53, 6-7=0/58, 2-12=-196/255, 6-8=-196/255
BOT CHORD 11-12=-60/120, 10-11=-60/120, 9-10=-60/120, 8-9=-60/120
WEBS 4-10=-193/78, 3-11=-73/50, 5-9=-70/48


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98; 110mph (3-second gust); h=20ft; TCCL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone and C-C Exterior(2) zone; Lumber DOL=1.60 plate grip DOL=1.60. This truss is designed for C-C for members and forces, and for MWFRS for reactions specified.
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see MiTek "Standard Gable End Detail"
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 173 lb uplift at joint 12, 183 lb uplift at joint 8, 24 lb uplift at joint 10, 75 lb uplift at joint 11 and 70 lb uplift at joint 9.

LOAD CASE(S) Standard

Job L130833	Truss T34	Truss Type COMMON	Qty 1	Ply 1	Job Reference (optional)
Builders FirstSource, Lake City, FL 32055					6.200 s Jul 13 2005 MiTek Industries, Inc. Tue Sep 20 17:51:20 2005 Page 1

Dwg.#092105652



LOADING (psf)	SPACING 2-0-0	CSI	DEFL in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plates Increase 1.25	TC 0.28	Vert(LL) -0.00 7 >999 240	MT20	244/190
TCDL 7.0	Lumber Increase 1.25	BC 0.08	Vert(TL) -0.01 6-7 >999 180		
BCLL 10.0	Rep Stress Incr NO	WB 0.09	Horz(TL) -0.00 6 n/a n/a		
BCDL 5.0	Code FBC2001/TP12002	(Matrix)			
				Weight: 46 lb	

LUMBER
 TOP CHORD 2 X 4 SYP No.2D
 BOT CHORD 2 X 6 SYP No.1D
 WEBS 2 X 4 SYP No.3 *Except*
 W1 2 X 4 SYP No.2D, W1 2 X 4 SYP No.2D

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=653/0-3-8, 6=653/0-3-8
 Max Horz 8=90(load case 4)
 Max Uplift 8=315(load case 4), 6=315(load case 5)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/58, 2-3=383/136, 3-4=383/136, 4-5=0/58, 2-8=-498/276, 4-6=-498/276
 BOT CHORD 7-8=-90/90, 6-7=0/0
 WEBS 3-7=-105/261, 2-7=-67/295, 4-7=-67/295

NOTES


- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-98: 110mph (3-second gust); h=20ft; TCDL=4.2psf; BCDL=3.0psf; Category II; Exp B; enclosed; MWFRS gable end zone; Lumber DOL=1.60 plate grip DOL=1.60.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 315 lb uplift at joint 8 and 315 lb uplift at joint 6.
- Girder carries tie-in span(s): 7-0-0 from 0-0-0 to 6-2-0
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard


- Regular: Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-2=-54, 2-3=-54, 3-4=-54, 4-5=-54, 6-8=-129(F=-99)

Symbols

PLATE LOCATION AND ORIENTATION



* Center plate on joint unless dimensions indicate otherwise. Dimensions are in inches. Apply plates to both sides of truss and securely seal.



* For 4 x 2 orientation, locate plates 1/8" from outside edge of truss and vertical web.



* This symbol indicates the required direction of slots in connector plates.

PLATE SIZE

4 X 4


The first dimension is the width perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING




Indicates location of required continuous lateral bracing.

BEARING



Indicates location of joints at which bearings (supports) occur.

Numbering System



JOINTS AND CHORDS ARE NUMBERED CLOCKWISE AROUND THE TRUSS STARTING AT THE LOWEST JOINT FARTHEST TO THE LEFT.

WEBS ARE NUMBERED FROM LEFT TO RIGHT

CONNECTOR PLATE CODE APPROVALS

BOCA	96-31, 96-67
ICBO	3907, 4922
SBCCI	9667, 9432A
WISC/DILLHR	960022-W, 970036-N
NER	561



MITek Engineering Reference Sheet: MIT-7473

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
2. Cut members to bear tightly against each other.
3. Place plates on each face of truss at each joint and embed fully. Avoid knots and wane at joint locations.
4. Unless otherwise noted, locate chord splices at 1/4 panel length (± 6" from adjacent joint.)
5. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
6. Unless expressly noted, this design is not applicable for use with fire retardant or preservative treated lumber.
7. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
8. Plate type, size and location dimensions shown indicate minimum plating requirements.
9. Lumber shall be of the species and size, and in all respects, equal to or better than the grade specified.
10. Top chords must be sheathed or purlins provided at spacing shown on design.
11. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
12. Anchorage and / or load transferring connections to trusses are the responsibility of others unless shown.
13. Do not overload roof or floor trusses with stacks of construction materials.
14. Do not cut or alter truss member or plate without prior approval of a professional engineer.
15. Care should be exercised in handling, erection and installation of trusses.

© 1993 MITek® Holdings, Inc.

