

NEW

PANEL SCHEDULE: HVAC										MOUNTING: SURFACE										LOCATION: RM. 117									
SERVICE: 120/208, 3ø, 4W										MAIN: 600A M.L.O.										RATING: 22,000 A.I.C									
CKT NO.	DESCRIPTION	C. BKR.			LOAD KVA./ø					C. BKR.			DESCRIPTION					CKT NO.											
		A	P		A	B	C			A	P		A	B	C														
1	PANEL HVAC	*	200	3	11.35					2.3		30	3	*				RTU-2	2										
3								11.35			2.3								4										
5	↓		↓	↓				11.35				2.3	↓	↓	↓		↓		6										
7	RTU-3	*	50	3	3.91					3.91		60	3	*				RTU-4	8										
9								3.91			3.91								10										
11	↓		↓	↓				3.91				3.91	↓	↓	↓		↓		12										
13	RTU-5	*	50	3	3.91					3.60		40	3	*				AHU-1	14										
15								3.91			3.60								16										
17	↓		↓	↓				3.91			3.60	↓	↓	↓		↓			18										
19	AHU-2	*	40	3	3.60					3.60		40	3	*				AHU-3	20										
21								3.60			3.60								22										
23	↓		↓	↓				3.60			3.60	↓	↓	↓		↓			24										
25	SPACE		-	-	-					-		-	-				SPACE	26											
27	SPACE		-	-	-					-		-	-				SPACE	28											
29	SPACE		-	-	-					-		-	-				SPACE	30											
31	SPACE		-	-	-					-		-	-				SPACE	32											
33	SPACE		-	-	-					-		-	-				SPACE	34											
35	SPACE		-	-	-			-		-		-	-				SPACE	36											
37	SPACE		-	-	-					-		-	-				SPACE	38											
39	SPACE		-	-	-					-		-	-				SPACE	40											
41	SPACE		-	-	-					-		-	-				SPACE	42											
					22.77	22.77	22.77			13.41	13.41	13.41	* HACR RATED CIR. BKR.																
TOTAL CONNECTED LOAD: 108.54 KVA										301.5 AMPS																			
TOTAL DEMAND LOAD: 108.54 KVA										301.5 AMPS																			

NEW

PANEL SCHEDULE: HVAC										MOUNTING: SURFACE										LOCATION: EXTERIOR									
SERVICE: 120/208, 3ø, 4W										MAIN: 225 M.L.O.										RATING: 22,000 A.I.C									
CKT NO.	DESCRIPTION	C. BKR.			LOAD KVA./ø					C. BKR.			DESCRIPTION	CKT NO.															
		A	P		A	B	C			A	P																		
1	HP-1	*	50	3	2.95					2.4		50	3	*	HP-2	2													
3								2.95			2.4					4													
5	↓		↓	↓				2.95			2.4	↓	↓	↓	↓	6													
7	HP-3	*	40	3	2.4					3.6		80	3	*	HP-4	8													
9								2.4			3.6					10													
11	↓		↓	↓				2.4			3.6	↓	↓	↓	↓	12													
13	SPACE		-	-	-					-	-	-	-	-	SPACE	14													
15	SPACE		-	-	-					-	-	-	-	-	SPACE	16													
17	SPACE		-	-	-					-	-	-	-	-	SPACE	18													
19	SPACE		-	-	-					-	-	-	-	-	SPACE	20													
21	SPACE		-	-	-					-	-	-	-	-	SPACE	22													
23	SPACE		-	-	-					-	-	-	-	-	SPACE	24													
25	SPACE		-	-	-					-	-	-	-	-	SPACE	26													
27	SPACE		-	-	-					-	-	-	-	-	SPACE	28													
29	SPACE		-	-	-					-	-	-	-	-	SPACE	30													
31	SPACE		-	-	-					-	-	-	-	-	SPACE	32													
33	SPACE		-	-	-					-	-	-	-	-	SPACE	34													
35	SPACE		-	-	-					-	-	-	-	-	SPACE	36													
37	SPACE		-	-	-					-	-	-	-	-	SPACE	38													
39	SPACE		-	-	-					-	-	-	-	-	SPACE	40													
41	SPACE		-	-	-					-	-	-	-	-	SPACE	42													
					5.35	5.35	5.35		6.0	6.0	6.0	PROVIDE NEMA 3R LOCKABLE ENCLOSURE																	
TOTAL CONNECTED LOAD: 34.05 KVA										94.6 AMPS																			
TOTAL DEMAND LOAD: 34.05 KVA										A AMPS																			

CNB OPERATIONS
CENTER

PROPOSED
ADDITION &
RENOVATIONS

U.S. HIGHWAY 90 EAST
LAKE CITY, FLORIDA



Clemons, Rutherford
& Associates Inc.

Architects
Planners
Interior Designers
Construction Managers

2027 Thomasville Road
Tallahassee, Florida 32312

(904) 385-6153
Fax (904) 386-8420

The drawings, specifications and other documents prepared by Clemons, Rutherford & Associates, Inc. (CRA) for this project are herewith provided to you for use only with respect to this project and shall not be used for any other project without the written consent of CRA. The drawings, specifications and other documents are provided to you for information only and shall not be used for any other project without the written consent of CRA. The drawings, specifications and other documents are provided to you for information only and shall not be used for any other project without the written consent of CRA.

PHASE	DATE	DRAWN	CHECK
PHASE REVIEW	10/26/99	J. SCOTT	K. FOLLMAR
CON. DOCS.	12/03/99	J. SCOTT	K. FOLLMAR

REVISIONS
DATE COMMENTS
2/2/00 V.E. ITEMS

CRA PROJ#: 96103
PHASE: 100% CONSTRUCTION
DOCUMENTS

SHEET TITLE
PANEL SCHEDULES
E-9 10 of 39

"HVAC"	"HVACA"	

