FBC 2020(7TH EDITION)

ALL CONCRETE STRUCTURAL CONCRETE BUILDINGS' WORK SHALL CONFORM 10 H REQUIREMENTS OF ACT 318, BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE, AND ACT 301, SPECIFICATION FOR

CONCRETE MATERIAL SHALL COMPLY WITH:

A.CEMENT-ASTM C150 TYPE

B.AGGREGATE-ASTM C33 MAXIMUM AGGREGATE SIZE C.WATER- POTABLE D.AIR ENTRAINING ADMIXTURE-ASTM C260

E.WATER-REDUCING ADMIXTURE-ASTM C494, INCLUDING SUPER PLASTICIZERS F. FLY ASH- ASTMC618, CLASS C

CONCRETE SHALL A.FOOTINGS,FOUNDATIONS,WALLS CONSTRUCTION DEVELOP THE MAXIMUM 28 DAY COMPRESSIVE STRENGTH(fc),(EXCEPT AS NOTED ON DRAWINGS) COMPRESSIVE STRENGTH(fc)

EXTERIOR SLABS, WALLS AND CURBS(AIR ENTRAINED CONCRETE)

B.INTERIOR SLABS

3000PSI

CONCRETE PROPERTIES SHALL BE ESTABLISHS ON THE BASIS OF FIELD EXPERIENCE AND/OR TO WHEN FLY ASH UTILIZED IN THE MIX. MIX SHALL CONTAIN A WATER REDUCER, FLY ASH SHALL YARD AND CEMENT SHALL BE REDUCED BY NOT MORE THAN 15 PERCENT BY WEIGHT. AND/OR TRIALMIXTURE ASH SHALL BE ADDED A E IN ACCORDANCE AT THE RATE OF NOT WITH ACI-318-11 MORE THAN 100 POUNDS SECTIONS PER

- PRORPORTION AND DESIGN MIXES TO RESULT IN CONCRETE SLUMP AT POINT OF PLACEMENT OF NOT MORE THAN
- 무 AIR ENTRAINING ADMIXTURE IN EXTERIOR EXPOSED CONCRETE TO 7 PERCENT ENTRAINED AIR.
- READY MIX CONCRETE SHALL COMPLY WITH THE REQUIREMENTS OF ASTM C94
- COMMERCIAL TESTING LABORATOTY. THE TESTING DOES NOT RELIEVE CONTRACTOR A.SAMPLING-ASTM C172
 B.SLUMP-ASTM C143, ONE TEST FOR EACH SET OF COMPRESSIVE STRENGTH TEST! SAMPLINGSS & TESTING FOR QUALITY CONTROL DURING THE PLACEMENT OF CONCRETE SHALL INCLUDE THE FOLLOWING, WITH ALL SAMPLING AND TESTING BEING DONE AT A RESPONSIBILITY OF PROVIDING CONCRETE IN COMPLIANCE WITH SPECIFICATIONS:

C.COMPRESSIVE TEST SPECIMEN-ASTM C31, PLACEMENT SET OF COMPRESSIVE STRENGTH TEST SPECIMENS.

ONE SET OF 4 CYLINDERS FOR EACH 50 CUBIC YARD OR FRACTION THEREOF WITH A MINIMUM OF ONE SET FOR EACH DAYS

D.AIR CONTENT- ASTM C231,ONE TEST FOR EACH SET OF COMPRESSIVE STRENGTH SPECIMEN.

E. COMPRESSIVE STRENGTH TEST-ASTM C39, TEST ONE SPECIMEN AT 7 DAYS AND TWO SPECIMENS AT 28 DAYS AND ONE SPECIMEN RETAINED IN RESERVE
TESTING IF REQUIRED. TEST RESULTS SHALL BE REPORTED IN WRITING TO ARCHITECT,ENGINEER,CONTRACTOR AND CONCRETE PRODUCER ON THE SAME DAY DAY Y TEST ARE MADE.

NO ALUMINIUM ITEMS SHALL BE EMBEDED IN ANY CONCRETE CHLORIDES IN ANY FORM OR CONCENTRATION SHALL NOT BE ADDED To ANY CONCRETE,

- REINFORCING STEEL: A. REINFORCING BARS-ASTM A615 GRADE 60, EXCEPT TIES & STIRRUPS MAY BE GRADE 40 DEFORMED. B. WELDED WIRE FABRIC-ASTM A 185
- 9099 ACCESSORIES AND SUPPORTS FOR REINFORCEMENT- COMPLY WITH CRSI RECOMMENDATIONS.

 BARS MARKED CONTINOUS AND ALL VERTICAL STEEL SHALL BE LAPPED OR EMBEDDED TO DEVELOP THE FULL UNLESS SHOWN OTHERWISE SPLICE TOP BARS NEAR MIDSPAN AND SPLICE BOTTOM BARS OVER SUPPORTS. TENSILE CAPACITY 무 THE BAR, LAPS

SHALL BE CLASS'B'

CONCRETE WORK EXECUTION:
A.CONSTRUCT FORM TO CORRECT S
B.POSITION, SUPPORT AND SECURE I
MINIMUM CONCRETE COVER FOR
CAST AGAINST & EXPOSED EART CORRECT SIZE,SHAPE, ALIGNMENT,ELEVATION AND POSITION, AND SUPPORT VERTICAL AND SUPPORT FOR REINFORCEMENT SHALL BE UNLESS NOTED OTHERWISE ON THE DRAWINGS POSED EARTH LATERAL LOADS

TO EARTH OR WATER

INCHES

NOT EXPOSED TO WEATHER OR IN CONTACT WITH EARTH 1/2 INCHES

C.PLACE CONCRETE IN COMPLIANCE WITH ACI 304'RECOMMEND PRACTICE FOR MEASURING, MIXING, TRANSPORTING AND PLACING CONCRETE'

D.CONSOLIDATE PLACED CONCRETE USING MECHANICAL VIBRATING EQUIPMENT SO THAT CONCRETE IS WORKED AROUND REINFORCEMENTS, EMBEDE ITEMS AND IN TO FORMS.

E.ALL CONCRETE IS REINFORCED UNLESS SPECIFICALLY NOTED AS UNREINFORCED. REINFORCED CONCRETE NOT OTHERWISE INDICATED WITH THE SAME REINFORCEMENT A SIMILAR SECTIONS. CONCRETE WORK FROM PHYSICAL DAMAGE OR REDUCED STRENGTH DUE TO WEATHER EXTREMES, IN COLD WEATHER. COMPLY WITH ACI 306; IN HOT WEATHER COMPLY AS OTHER

GIN CONCERNS OF GRADE BEAMS AND WALLS, PROVIDE CORNER REINFORCEMENT (LAP TWO FEET EACH DIRECTION) IN COURSE FACE, MATCHING SIZE AND SPACING HORIZONTAL REINFORCEMENT. PROVIDE THREE # 4 SUPORT BARS WHERE REQUIRED FOR SUPPORT OR CORNER BARS.

H. AT OPENINGS IN WALLS ADD ONE #5 BAR(OPENING DIMENSION PLUS 60 BAR DIAMETERS) FOR EACH FACE AND EACH SIDE OF OPENING AND ONE #5 BAR BY 5'-0' DIAGONALLY FOR EACH FACE AND EACH CORNER OF OPENING.

I.PROVIDE ONE #5 BAR DIAGONALLY AT EACH FACE OF ALL STEPS IN GRADE BEAMS AND FOUNDATION WALLS.

JLAP REINFORCEMENTS AS FOLLOWS, EXCEPT AS NOTED OTHERWISE ON THE DRAWING: #4 BARS-12',#5 BARS-19',#6 BARS-26'.

K.PROVIDE CONSTRUCTION JOINTS IN FOOTINGS, GRADE BEAMS AND WALLS AS SHOWN ON DVG'S. WITH ACI 305


BROOM FINISH ALL EXTERIOR CONCRETE SLABS

STEEL TROWEL FINISH ALL INTERIOR CONCRETE SLABS,


M. REMOVE FINS AND PROJECTIONS, REPAIR AND PATCH DEFECTIVE AREAS WITH CEMENT GROUT IMMEDIATELY AFTER REMOVAL


FOUNDATION GENERAL NOTES:


- COMPACTED BACKFIL SHALL THE ALLOWABLE SOIL BEARING CAPACITY IS ASSUMED TO BE A MINIMUM OF 1500 PSF, THE DESIGN ENGINEER
 SHALL BE NOTIFIED IMMEDIATELY IF ANY CONDITIONS ARE DIFFERENT THAN THESE ASSUMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY
 THE SOIL CONDITIONS BEFORE CONSTRUCTION, AND IF UNUSUAL CONDITIONS ARE ENCOUNTERED, NOTIFY THE ENGINEER BEFORE CONSTRUCTION BEGINEER IM
 SHALL NOT PROCEED WITH THE WORK IF GROUNDWATER IS ENCOUNTERED DURING EXCAVATION, AND SHALL NOTIFY THE GEOTECHNICAL ENGINEER IM BEFORE CONSTRUCTION BEGINS, THE CONTRACTOR GEOTECHNICAL ENGINEER IMMEDIATELY.
- REFER TO BOLTS AT COLUMNS FIL SHALL BE USED IN THE EXCAVATION AFTER THE CONCRETE IS SET. BUILDING MANUFATURER'S ANCHOR BOLT PLAN FOR ANCHOR BOLTSIZES AND PLACEMENT. NS SHALL BE HEADED BOLTS OR THREADED RODS WITH DOUBLE NUTS ATTACHED AT THE END.
- CONCRETE MONOLITHIC POUR IS ACCEPTABLE.
- DUE TO LACK OF SPECIFIC GEO-TECHNICAL INFORMATION, SLAB HAS BEEN DESIGNED SEALING ENGINEER IS NOT RESPONSIBLE FOR DIFFERENTIAL SETTLEMENT, CRACKING, RESULTING FROM UNREPORTED CONDITIONS MITIGATING THE ABOVE ASSUMPTIONS OR OTHER FUTURE DEFECTS 120 and LIVE LOAD OF 250 PSF




₹P. SECTION THRU EXTERIOR ENDWALL/ SIDEWALL COL. FOOTING











FOUNDATION PLAN-2	HIGH SPRINGS, FL 32643	8065	CUSTOMER: GIBRALTAR CONSTRUCTION	BUILDINGS AND MORE	ISSUE
		DATE:			DET
		5/ 18/23			웃
		/23			DATE





*NOTE: REFER ANCHOR BOLT DRAWINGS FOR BOLT PLACEMENT AND COLUMN LOCATION

NOTE: ALL BASE PLATES @ 100.00' (U.N.) FINISH FLOOR @ 100.00' (U.N.)

1/8"x 1 1/2" SAWCUT FOR 4" SLAB WET CUT NOT LATER THAN 2 HRS. AFTER FINAL TROWEL FINISH

4XW1.4 -

Δ

À

Δ

CONCRETE SLAB

TYP.

CONTROL JOINT DETAIL

Ashokbhai A Patel Valdosta el (229)402-2640 2023 05 18 15:27:36-04'00'

SPECTRAL RESPONSE

SITE CLASS

Endwall Rafter (Live)


Wall Girt Endwall Rafter (Wind) OCCUPANCY/BISK CATEGORY


JI.TIMATE.


Length (ft) = Width (ft)

Length (ft) =

60







RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Line Frame mw lines: Anc. 44 _Bott 0.750 N 6.000 Base_Plate (in) Width Length Thick W 12.00 0.375 Grout (in)

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm mш Anc._Bolt Oty Dia 44 0.750 6.000 Base_Plate (in) Width Length Thick 10.00 0.375 Grout (in)

Base_Plate (in) Width Length Thick ANCHOR BOLTS & BASE PLATES 0.375 0.250 0.250 0.250 Grout (in) 0.0 $\oplus \oplus \boxtimes$ 24 24 Jamb Endwall Frame 3/4

Frm

Anc._Bolt Qty Dia COLUMN:

CEDB

8.000

8.000 8.000

8.000 8.000

8.000

ENDWALL

BUILDING

BRACING REACTIONS

Loc Line

Reactions(k)
Wind — — Seismic —
Z Vert Horz Vert

Panel_Shear (lb/ft) Wind Seis

Note

3

(h)Rigid frame at endwall

⊕4m→

B,D 2,3

6.3

1.50 1.50 2.50

ANCHOR BOLT SUMMARY

GENERAL NOTES

FOUNDATION DESIGN AND CONSTRUCTION ARE NOT THE RESPONSIBILITY OF METAL BUILDING MANUFACTURER.

THE WIND REACTION.

Building reactions are the following building

e based data:

ht (ft)
se (Rise/12)
ad (psf)
al Load (psf)
Live Load(psf)
Live Load

40.0 = 60.0 = 18.0/1 = 2.0/2.0 = 1.0 20.0

18.0

NOTES

FOR REACTIONS

Frm

COLUMN:

COLUMN

REACTIONS

Vert 0.0 0.0 0.0

BASIC COLUMN REACTIONS

Collat Vert 0.2 0.1 0.1

Live Vert 3.7 4.9 0.0

Wind Right1 Vert -2.3 -4.3

Wind Vert -3.0 -2.5 -0.5

Vert 0.0 0.0 0.0

ALL REACTIONS ARE UNFACTORED.

4. ANCHOR BOLTS SHALL BE ACCURATELY SET TO A TOLLERANCE OF +/- 1/8" IN BOTH ELEVATION AND LOCATION.

S

COLUMN BASE PLATES ARE DESIGNED NOT TO EXCEED A BEARING PRESSURE OF 1050 POUNDS PER SQUARE INCH.

By Richard T Smith at 10:30 am, May 08, 2023 REVIEWED

BUILDING A BUILDINGS AND MORE HIGH SPRINGS, FL 32643 GIBRALTAR CONSTRUCTION ISSUE DET CHK 2/23 DATE

ANCHOR BOLT REACTIONS
NO. DEWAY BY:
PAGE 1.2 JRD

SPW 91:

BNONE


Frame Live Load
Min(psf
Max(psf
)
Wind Speed (mph
)
Wind Code Enclosed/Open/Partial Importance Wind Importance Seismic Zone Coeff (Fa*Ss) 12.0 16.0 122.0 FBC 20 Enclosed 20 (7th Edition)

> Richard T. Smith PE#43547 Ph-706-888-4874

Salem AL, 36874 510 Lee Rd 281

ACHORD TSMI

NOTE: THE FRAMING AT BOTH ENDWALLS IS NOT DESIGNED TO ACCOMMODATE FUTURE ADDITIONS. REACTIONS CORRESPONDING TO THESE FRAME LINES REFLECT LOADINGS FOR ACTUAL TRIBUTARY AREA AND ARE NOT INTENDED TO INCLUDE ANY FUTURE MODIFICATIONS UNLESS NOTED OTHERWISE.



RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Col A Anc._Bolt Oty Dia 4 0.750 6.000 Base_Plate (in) Width Length Thick 8.000 0.375 Grout (in) 0.0

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm D Anc._Bolt Oty Dia 4 0.750 6.000 8.000 0.375 Base_Plate (in) Width Length Thick Grout (in) 0.0

Frame lines: N S

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Anc._Bolt Qty Dia 4 0.750 6.000 Base_Plate (in) Width Length Thick 8.000 0.375 Grout (in)

ANCHOR BOLT SUMMARY (in) e Projection

GENERAL NOTES

Qty

Frame

3/4"

GR36 Type

2.50

- FOUNDATION DESIGN AND CONSTRUCTION ARE NOT THE RESPONSIBILITY OF METAL BUILDING MANUFACTURER.
- ALL REACTIONS ARE UNFACTORED.
- ULTIMATE WIND LOADS ARE USED TO DERIVE THE WIND REACTION.
- ANCHOR BOLTS SHALL BE ACCURATELY SET TO A TOLLERANCE OF +/- 1/8" IN BOTH ELEVATION AND LOCATION.
- COLUMN BASE PLATES ARE DESIGNED NOT TO EXCEED A BEARING PRESSURE OF 1050 POUNDS PER SQUARE INCH.

Frame RIGID FRAME: Frame Column Line Line lines: -Wind_Right2-Horiz Vert 0.4 -0.9 0.5 -1.2 0.4 -0.9 Horiz 0.0 0.0 BASIC COLUMN REACTIONS (k) -Dead-Vert 0.5 0.7 Horiz 0.0 0.0 -Collateral -- Vert 0.0 0.1 0.2 0.2 0.1 0.2 0.1 Horiz -0.6 -0.6 -Wind_Right1-loriz Vert 0.9 -1.9 1.5 -3.1 0.9 -1.9 --Wind_Left2-Horiz Vert -1.2 -1.6 -2.0 -2.1 -1.2 -1.6

NOTES Building reactions are based on the following building data: Raof Slope (Rise/12)
Roof Slope (Rise/12)
Dead Load (psf)
Collateral Load (psf)
Roof Live Load(psf)
Frame Live Load
Min(psf FOR REACTIONS ed (mph) = 16.0 = 122.0 = 122.0 = FBC 20 = FBC 20 = Enclosed = 1.00 = 1.00 = 0.12 2.0 2.0 1.0 20.0 18.0

BUILDING BRACING REACTIONS Exposure
Enclosed/Open/Partial
Importance Wind
Importance Seismic
Seismic Zone
Seismic Coeff (Fa*Ss)

20 (7th Edition)

Loc -Wall — Col # Reactions(k)
Wind — Seismic —
Horz Vert Horz Vert Panel_Shear (lb/ft) Wind Seis Note

(e)Bracing loads are applied to supporting building (h)Rigid frame at endwall

Torsional Bracing Used

R SW R SW R SW

FOE

PE # 43547 Ph-706-888-4874 Richard T. Smith

Salem AL, 36874 10 Lee Rd 281

ACHARD TSMI REVIEWED

By Richard T Smith at 10:30 am, May 08, 2023


BUILDING BUILDINGS AND MORE HIGH SPRINGS, 8065 GIBRALTAR CONSTRUCTION W FL 32643 DET 至 2/23 DATE


ANCHOR BOLT REACTIONS
NO.
PAGE 1.3 PROMINED

SPW en

NONE

NOTE: THE FRAMING AT BOTH ENDWALLS IS NOT DESIGNED TO ACCOMMODATE FUTURE ADDITIONS. REACTIONS CORRESPONDING TO THESE FRAME LINES REFLECT LOADINGS FOR ACTUAL TRIBUTARY AREA AND ARE NOT INTENDED TO INCLUDE ANY FUTURE MODIFICATIONS UNLESS NOTED OTHERWISE.





P-100 8x25Z16 P-101 8x25Z16	CB-6 1/4 CBL	CB-5 1/4 CBL	E-1 8LE14@2	P-2 8x25Z16	P-1 8x25Z16	BLDG. A	MARK PART	F PL	MEMBER TABLE
23'-11 1/2 19'-11 1/2 22'-2"	22'-8"		19'-11 1/2		21'-11 1/2		LENGTH		

SPLICE BOLT TABLE

MARK Top Bot Int TYPE DIA Length
SP-1 4 0 0 A325 5/8" 2"

BASE PLATE TABLE
COL PLATE SIZE
MARK Width THICK Length
BP-1 6" 3/8" 8"

FILANGE BRACES: (1) One Side; (2) Two Sides
F8×X(1): xx=length(in)
A - L2x2x14

MARK MEMBER LENGTH

RF1-100 W8X10 14'-1 1/4"

RF1-101 W8X10 18'-11"

WEIGHT 156 208

MEMBER SIZE TABLE

A A A - 9 13/16"

FB160/(1)

FB16

Richard T. Smith

PE#43547 Ph-706-888-4874

510 Lee Rd 281

Salem AL, 36874

NO 143547

NO 143547

STATE OF

STATE OF

STATE OF

BY Richard T Smith at 10:30 am, May 08, 2023

RIGID FRAME CROSS SECTION	HIGH SPRINGS, FL 32643	8065	GIBRALTAR CONSTRUCTION	BUILDINGS AND MORE	ISSUE
		DATE			DET
		s/ 2/23			CHK
		23			DATE

PAGE


2.1


JRD JRD


SPW SCAE NONE


NOTE: THE FRAMING AS DEPICTED ABOVE IS NOT DESIGNED TO ACCOMMODATE ANY FUTURE EXPANSION.


RIGID FRAME ELEVATION: FRAME LINE 1


















	FRAME ORD ORD ORD ORD ORD ORD ORD OR
MEMBER FRAME MARK DJ-2 DH-1 G-19 G-19	ME LINE E PART PART BASE TRM GUTTER EAVE TRM GUTEND L CORBOX L GUTEND R CORBOX R CORBOX R AMB R JAMB R HEAD WCT-2
N TABLE LINE E PART 8X25C16 8X25C16 8X25C16 8X25C16 8X25Z16 8X25Z16	LENGTH 20"-3" 20"-3" 1"-0" 1"-0" 7"-5" 7"-5" 3'-7"
LENGTH 12'-4" 3'-4" 20'-11 1/2" 21'-11 1/2"	DETAIL TRIM_16 TRIM_1 TRIM_2 TRIM_2 TRIM_2 TRIM_2 TRIM_2 TRIM_6 TRIM_61 TRIM_20







	65432DRA
MEMBER FRAME _ MARK G-9 G-10 CB-4	FRAME LINE B PART DID PART BASE TRM BASE TRM FRAME LINE B REND LH REND RH MUCT-2
R TABLE LINE B PART 8x25Z16 8x25Z16 8x25Z16 6x25Z16	LENGTH 20'-3" 20'-3" 6" 20'-3"
LENGTH 20'-11 1/2" 21'-11 1/2" 26'-8"	DETAIL TRIM_16 ETD TRIM_13 TRIM_13 TRIM_20



TRIM TABLE
FRAME LINE A
OID PART
I GUTTER
2 GUTEND L
3 CORBOX L
4 GUTEND R
5 CORBOX R DETAIL TRIM 2

Richard T. Smith

510 Lee Rd 281 PE#43547 Ph-706-888-4874

PICHARD T SMITTER OF STATE OF


DET CH. DATE


BUILDINGS AND MORE HIGH SPRINGS, FL 32643
HIGH SPRINGS, FL 32643


DEVANUE 1994
FRAMING & SHEETING LAYOUT


DEVANUE 1994
PAGE 4.2

JRD SPW NONE GIBRALTAR CONSTRUCTION 8065 2/23











BUILDINGS AND MORE	GIBRALTAR CONSTRUCTION	308 HD; 8065	HIGH SPRINGS, FL 32643	FRAMING DETAILS	THE WAY HAVE
		Barwa S			DHEUXED BIT
		5/ 2/23	Ì		65
		23			SME





CONNNECTIONS STRUCTURAL BOLTED

A325 AND A490 CONNECTION BOLTS. REFER TO COVER PAGE "GENERAL NOTES" INSTRUCTIONS ON TIGHTENING ALL PARAGRAPH "C", SECTION "9" FOR

TRIM NOTES:

- \square SECURE GUTTER SPLICES AND END SEAL TRIM SPLICES WITH TUBE CAULK.
- PLUGS WITH RIVETS.
- [3] SECURE ALL OTHER ROOF TRIM SPLICES WITH TRIM SCREWS UNLESS
- [4] 5 NOTED OTHERWISE.
 TRIM SCREWS ARE LOCATED 24" ON
 CENTER UNLESS NOTED OTHERWISE.
 STD. TRIM SPLICES ARE 3" TOTAL UNLESS NOTED OTHERWISE.

PERSONNEL DOORS MORTISE PREPPED

ALL MORTISE PREPPED PERSONNEL DOORS COME AS RIGHTHAND REVERSED SWING.

(i.e. STANDING ON THE OUTSIDE OF THE BUILDING FACING THE DOOR, THE LOCK WILL BE ON THE LEFTHAND SIDE OF THE DOOR AND THE DOOR WILL SWING OUTWARD FROM THE BUILDING.

ANY FIELD MODIFICATIONS ARE THE RE-SPONSIBILITY OF THE ERECTOR AND MBM IS NOT LIABLE FOR LABOR CHARGES NOR DAMAGES DUE TO ERROR.

GENERAL SKYLIGHT NOT LIP'S (LIGHT TRANSMITTING PANELS) SHALL LOCATED END-TO-END AND SHALL NOT BE SIDE-TO-SIDE. IT IS RECOMMENDED THAT A OF (3) METAL ROOF PANELS BE INSTALLED EACH LIP SIDELAP.

BUILDINGS WITH LESS THAN $\sim 60^\circ-0^\circ$ OF ROOF PANELS IN A SINGLE "RUN" TYPICALLY ARE ONLY ALLOWED (1) LTP PER "RUN".

4

3

ANY INSTALLATIONS FOR LIP'S OUTSIDE OF THESE GUIDLINES AND THE DETAILS PROVIDED BY THE M.B.M. REMOVE SAID M.B.M. FROM ANY LIABILITIES OR FAULTS DESPITE CLAIMS AGAINST M.B.M.

5

DO NOT STEP ON LTP'S ONCE THEY HAVE BEEN INSTALLED! STEPPING ON LPT'S AFTER INSTALLATION MAY RESULT IN INJURY OR DEATH! FOR ALL LTP'S PROVIDED BY M.B.M., LIGHT STONE FASTENERS WILL BE PROVIDED FOR A CLOSE MATCH TO LTP COLOR. THIS INCLUDES WALL & ROOF LTP'S.

5

2

METAL ROOF PANELS ARE NOT TO BE INSTALLED USING A SIMPLE-SPAN CONDITION. IT IS RECOMMENDED THAT A MIN. OF (3) ROOF FRAMING MEMBERS, PREFERABLY (4), SUPPORT ALL METAL ROOF PANELS WHERE ROOF PANELS HAVE BEEN CUT (FACTORY OR FIELD) TO ALLOW FOR LTP INSTALLATION.

LTP'S SHALL NOT BE INSTALLED EAVE—TO—PEAK OR EAVE—TO—EAVE (ONE LTP PER SINGLE "RUN" OF SHEETING).

B= BUILT-UP

08=

10 12 12 13

41208

5,6,8,10 OR 12 (INCHES)

MEASURED IN 16ths. (4= 1/4", 5= 5/16" ETC.) 1= 10ga 3= 3/16" ETC.

ETC.

1=

ALLED ECOMMENDED ERS, TORY OR	NOT BE LOCATED A MINIMUM BETWEEN
BEAM TYPE	
BEAM DEPTH	MEMBER
FLANGE WIDTH	T-U
FLANGE THK.	GEN
WEB THK.	

DET CHK DATE

By Richard T Smith at 10:30 am, May 08, 2023

REVIEWED

ACTICENS NO 143547


Salem AL, 36874 510 Lee Rd 281 PE#43547 Ph-706-888-4874 Richard T. Smith


BUILDINGS HIGH SPRINGS, FL 3 8065 GIBRALTAR CONSTRUCTION AND MORE 32643 5/ 2/23

JRD BD


SPW the

NONE





REVIEWED By Richard T Smit	STATE C		MANA PE	Salem A	510 Lee Rd 281	PE#43547 Ph-706-888-4874	Richard T. Smith
REVIEWED By Richard T Smith at 10:30 am, May 08, 2023	STATE OF SEA	143547 Minit	ACCENSO A	L, 36874	Rd 281	706-888-4874	Smith



PURLIN Flange C-Clamp is not C-CLAMP roof purlin. All other material M.B.M. only provides (BY M.B.M.) PURLIN ATTACHMENT BY OTHERS IN NOT DRILL HOLES IN FLANGES HOLES INTO

an acceptable connection

hardware is by others.


Recommended Connection Detail


MANY FACTORS BEYOND THE CONTROL OF THE METAL BUILDING SUPPLIER AFFECT THE ABILITY OF A PURLIN TO SAFELY SUPPORT HANGING LOADS COMBINED WITH OTHER REQUIRED ROOF LOADS. DUE TO THE VARIABLES INVOLVED IN HANGING LOADS AND THEIR ATTACHMENTS TO THE PURLINS, THE METAL BUILDING SUPPLIER CANNOT ASSURE THAT THE PURLINS FOR A PARTICULAR BUILDING PROJECT CAN SAFELY SUPPORT THE MAXIMUM ALLOWABLE HANGING LOADS IN COMBINATION WITH OTHER ROOF LOADS.

IT IS THE RESPONSIBILITY OF THE HANGER SYSTEM INSTALLER TO COORDINATE WITH THE ENGINEER OF RECORD FOR THE OVERALL PROJECT TO ENSURE A SAFE HANGING LOAD INSTALLATION. THE METAL BUILDING ENGINEER IS NOT THE ENGINEER OF RECORD FOR THE OVERALL PROJECT. WITHOUT SPECIFIC CERTIFICATION FOR INDIVIDUAL HANGING LOADS, THE NET EFFECTS OF APPLIED HANGER LOADS INSTALLED ON A PARTICULAR PURLIN SHALL NOT EXCEED THE NET EFFECTS OF THE CERTIFIED UNIFORMLY APPLIED DESIGN COLLATERAL LOAD.

HANGING LOADS SHOULD NOT BE APPLIED TO THE PURLIN LIP, WHERE PERMISSIBLE, THE BEST PRACTICE FOR HANGING LOADS IS TO ATTACH TO THE PURLIN WEB USING A BOLT AND NUT, OR SELF-DRILLING SCREWS.

HANGING UNIFORM LOADS SUCH AS SPRINKLER MAINS OR HVAC EQUIPMENT SHOULD BE DISTRIBUTED OVER SEVERAL PURLINS, AND SHOULD NEVER EXCEED THE COLLATERAL LOAD ALLOWANCE OVER SEVERAL PURLINS, AND SHOULD NEVER EXCEED THE COLLATERAL LOAD ALLOWANCE FOR THE ROOF SYSTEM. FOR UNIFORM LOADS THAT RUN PARALLEL TO THE PURLINS, IT MAY BE NECESSARY TO USE TRANSVERSE SUPPORT CHANNELS (A.KA. TRAPEZE BEAMS) ATTACHED TO THE WEBS OR FLANGES OF ADJACENT PURLINS TO SPREAD THE LOAD BETWEEN TWO OR MORE PURLINS. SUCH CASES, CONTACT THE BUILDING MANUFACTURER OR A LOCAL PROFESSIONAL ENGINEER PRIOR TATTEMPTING TO HANG LOADS FROM THE PURLINS





BUILDINGS AND MORE 792 SW BASCOM NORRIS DR. LAKE CITY, FL 32025

5/ 2/23 DATE: GIBRALTAR CONSTRUCTION JOB NO: 8065

BUILDING A SIZE:

BUILDING B SIZE: WIDTH : 40 ft. LENGTH : 60 ft. WIDTH : 20 ft. LENGTH : 60 ft. EAVE HT : 18 ft. H/S EAVE HT: 18 ft.

JOB SITE: HIGH SPRINGS, FL 32643

To Whom It May Concern:

This Letter of Design Certification ensures that primary and secondary framing furnished by Metal Building Manufacturer are designed in accordance with information specified to Metal Building Manufacturer on the order documents and summarized by loading information below.

DESIGN LOAD CRITERIA:

Building Code: FBC 20/7th Edition

Roof Dead Load(D): 2.000 $\,$ psf plus wt. of metal bldg structure Roof Live Load(Lr): 20.00 $\,$ psf

Tributary Live Load Reduction: Yes

Collateral Load(C) : 1 psf Seismic Use Group : II - Normal

Building Risk Category : II - Normal Seismic Site Class : d Ultimate : 122 mph Wind Speed Mapped Response (Ss) : 0.0782 Nominal: 94.50 mph Mapped Response (S1) : 0.0471

Wind Exp. Cat : B

Design Response (Sds) : 0.0832 Serviceability Wind : 10 -year MRI Design Response (Sdl) : 0.0752 Enclosure Type : Enclosed Rigid Frame (Cs) : 0.0277

: -0.18/0.18 Internal Wind Coef. Design Category (SDC) : B Seismic Importance : 1.00 Res Mod Factor (OMF)R : 3.00** Res Mod Factor (Brc)R : 3.00**

**STEEL SYSTEM NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE.

BLDG. A COMPONENTS & CLADDING (unfactored)

Wall Field Values : 20.944 psf / -22.689 psf Wall Edge Values : 20.944 psf / -27.925 psf

BLDG. B COMPONENTS & CLADDING (unfactored)

Wall Field Values : 19.897 psf / -21.555 psf Wall Edge Values : 19.897 psf / -26.529 psf

REFERENCE DESIGN STANDARDS:

- *AISC Specification for Structural Steel Buildings-Allowable stress design, 360-16. *AISI North-American Specification for the Design of Cold-Formed Steel Structural Members, 2016 Edition.
- *MBMA Low Rise Building Systems Manual, Latest Edition.
- *AISC Design Guide 3, "Serviceability Design Consideration for
- Steel Buildings, Second Edition"
- *AWS Latest Edition of Structural Welding Code-Steel.
- * FBC 20/7th Edition are using the ASCE7-16.


This certification is limited to the structural design of the frames, secondary, and roof/wall covering manufactured or supplied by Metal Building Manufacturer only and excludes Accessory items such as doors, windows, louver manufacturer only and excludes accessory items such as doors, windows, louver Richard T. Smith translucent panels, and ventilators. This certification specifically excludes Richard T. Smith any foundation, masonry, erection of building and general contract work.

The undersigned is not the engineer of record for the overall project.

Sincerely,

Richard T. Smith, P.E.

PE#43547 Ph-706-888-4874 510 Lee Rd 281 Salem AL, 36874



REVIEWED

By Richard T Smith at 10:29 am, May 08, 2023

BUILDINGS AND MORE 792 SW BASCOM NORRIS DR. LAKE CITY, FL 32025

DATE: 5/ 2/23

GIBRALTAR CONSTRUCTION JOB NO: 8065

BUILDING A SIZE: WIDTH : 40 ft.

LENGTH : 60 ft.

BUILDING B SIZE:

WIDTH : 20 ft. LENGTH : 60 ft.

EAVE HT : 18 ft. EAVE HT : JOB SITE: HIGH SPRINGS, FL 32643 EAVE HT : 18 ft. H/S

To Whom It May Concern:

This Letter of Design Certification ensures that primary and secondary framing furnished by Metal Building Manufacturer are designed in accordance with information specified to Metal Building Manufacturer on the order documents and summarized by loading information below.

DESIGN LOAD CRITERIA:

Wind Exp. Cat

Building Code: FBC 20/7th Edition

Roof Dead Load(D): 2.000 $\,$ psf plus wt. of metal bldg structure Roof Live Load(Lr): 20.00 $\,$ psf

Tributary Live Load Reduction: Yes

Collateral Load(C) : 1 psf Building Risk Category : II - Normal Wind Speed

Ultimate: 122 mph Nominal: 94.50 mph

: B : 10 -year MRI

Serviceability Wind Enclosure Type : Enclosed Internal Wind Coef. : -0.18/0.18 Seismic Use Group : II - Normal Seismic Site Class : d

Mapped Response (Ss) : 0.0782 Mapped Response (S1) : 0.0471

Design Response (Sds) Design Response (Sdl) : 0.0752 Rigid Frame (Cs) : 0.0277

Design Category (SDC) : B Seismic Importance : 1.00 Res Mod Factor (OMF)R : 3.00** Res Mod Factor (Brc)R : 3.00**

**STEEL SYSTEM NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE.

BLDG. A COMPONENTS & CLADDING (unfactored)

Wall Field Values : 20.944 psf / -22.689 psf Wall Edge Values : 20.944 psf / -27.925 psf

BLDG. B COMPONENTS & CLADDING (unfactored)

: 19.897 psf / -21.555 psf : 19.897 psf / -26.529 psf Wall Field Values Wall Edge Values

REFERENCE DESIGN STANDARDS:

- *AISC Specification for Structural Steel Buildings-Allowable stress design, 360-16. *AISI North-American Specification for the Design of Cold-Formed Steel Structural Members, 2016 Edition.
- *MBMA Low Rise Building Systems Manual, Latest Edition.
- *AISC Design Guide 3, "Serviceability Design Consideration for

Steel Buildings, Second Edition"

- *AWS Latest Edition of Structural Welding Code-Steel.
- * FBC 20/7th Edition are using the ASCE7-16.

This certification is limited to the structural design of the frames, secondary, and roof/wall covering manufactured or supplied by Metal Building Manufacturer only and excludes Accessory items such as doors, windows, louver translucent panels, and ventilators. This certification specifically excludes Richard T. Smith any foundation, masonry, erection of building and general contract work.


The undersigned is not the engineer of record for the overall project.

Sincerely,

Richard T. Smith, P.E.

PE#43547 Ph-706-888-4874

510 Lee Rd 281 Salem AL, 36874



REVIEWED

By Richard T Smith at 10:29 am. May 08, 2023