PAT LYNCH LYNCH DRILLING CORP P O Box 934 Branford, FL 32008 (386)935-1076

DATE April 25, 2022

CUSTOMER Betty T Sauls and Perry R Sauls 10640 SW CR 240, Lake City, FL 32024

LOCATION

WE WILL CONSTRUCT A 4" WATER WELL COMPLETE WITH 4" WATER WELL STEEL CASING, 1 HP SUBMERSIBLE PUMP (20 GPM) WITH 1 1/4" DROP PIPE, AND AN 86 GALLON CAPTIVE AIR TANK (21.9 GALLON DRAWDOWN).

WELL WILL BE COMPLETE AT THE WELL SITE, WE DO NOT INCLUDE ELECTRICAL NOR PLUMBING CONNECTIONS FROM THE WELL TO THE HOME AND/OR POWER POLE.

ANY VARIATIONS OF THE ABOVE ARE SUBJECT TO APPROVAL FROM THE CUSTOMER AND.OR CONTRACTOR PRIOR TO COMMENSMENT OF THE INDIVIDUAL JOB.

THANK YOU

NOT RESPONSIBLE FOR THE QUALITY OF WATER