

DATE 11/12/2010

Columbia County Building Permit

This Permit Must Be Prominently Posted on Premises During Construction

PERMIT

000029001

APPLICANT DOUGLAS BAGGETT PHONE 407-482-8282
ADDRESS PO BOX 781766 ORLANDO FL 32878
OWNER DONALD BAGGETT PHONE 863-467-4885
ADDRESS 415 SW CIRBUS DRIVE LAKE CITY FL 32025
CONTRACTOR DOUG BAGGETT PHONE 407-235-4515
LOCATION OF PROPERTY 441 SOUTH, R AVIATION DR, SOUTH ON CIRBUS BLVD, GO
STRAIGHT AT 90 DEGREE CURVE INTO DRIVE

TYPE DEVELOPMENT HANGAR ESTIMATED COST OF CONSTRUCTION 63250.00
HEATED FLOOR AREA TOTAL AREA 5225.00 HEIGHT 14.00 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 1/12 FLOOR SLAB

LAND USE & ZONING AG-3 MAX. HEIGHT 35

Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 22-5S-17-09322-004 SUBDIVISION LAKE CITY AIRPARK
LOT 4 BLOCK PHASE UNIT TOTAL ACRES 4.01

CGC1508506
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING X10-415 HD BK N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ACCESSORY USE, NOC ON FILE

Check # or Cash 1787

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Insulation date/app. by
Rough-in plumbing above slab and below wood floor date/app. by Electrical rough-in date/app. by
Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by Pool date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
Pump pole date/app. by Utility Pole date/app. by M/H tie downs, blocking, electricity and plumbing date/app. by
Reconnection date/app. by RV date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 320.00 CERTIFICATION FEE \$ 26.13 SURCHARGE FEE \$ 26.13
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ 0.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ CULVERT FEE \$ TOTAL FEE 422.26

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

DATE 12/28/2010

Columbia County Building Permit
This Permit Must Be Prominently Posted on Premises During Construction**PERMIT**
000029099

APPLICANT DOUGLAS BAGGETT PHONE 407-482-8282
ADDRESS PO BOX 781766 ORLANDO FL 32878
OWNER DONALD BAGGETT PHONE 863-467-4885
ADDRESS 415 SW CIRRUS DRIVE LAKE CITY FL 32025
CONTRACTOR DOUG BAGGETT PHONE 407-235-4515
LOCATION OF PROPERTY 441 SOUTH, R AVIATION DR, SOUTH ON CIRRUS BLVD, GO
STRAIGHT AT 90 DEGREE CURVE INTO DRIVE
TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 263300.00
HEATED FLOOR AREA 2467.00 TOTAL AREA 5266.00 HEIGHT 16.00 STORIES 1
FOUNDATION CONCRETE WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB
LAND USE & ZONING AG-3 MAX. HEIGHT 35
Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO. _____

PARCEL ID 22-5S-17-09322-004 SUBDIVISION LAKE CITY AIRPARK
LOT 4 BLOCK _____ PHASE _____ UNIT _____ TOTAL ACRES 4.00

CGC1508506
Culvert Permit No. _____ Culvert Waiver _____ Contractor's License Number _____ Applicant/Owner/Contractor _____
EXISTING 10-0514-N BK TC N
Driveway Connection _____ Septic Tank Number _____ LU & Zoning checked by _____ Approved for Issuance _____ New Resident _____

COMMENTS: FLOOR ONE FOOT ABOVE THE ROAD

NOC ON FILE

Check # or Cash 1863**FOR BUILDING & ZONING DEPARTMENT ONLY**

(footer/Slab)

Temporary Power _____ Foundation _____ Monolithic _____
date/app. by _____ date/app. by _____ date/app. by _____
Under slab rough-in plumbing _____ Slab _____ Sheathing/Nailing _____
date/app. by _____ date/app. by _____ date/app. by _____
Framing _____ Insulation _____
date/app. by _____ date/app. by _____
Rough-in plumbing above slab and below wood floor _____ Electrical rough-in _____
date/app. by _____ date/app. by _____
Heat & Air Duct _____ Peri. beam (Lintel) _____ Pool _____
date/app. by _____ date/app. by _____ date/app. by _____
Permanent power _____ C.O. Final _____ Culvert _____
date/app. by _____ date/app. by _____ date/app. by _____
Pump pole _____ Utility Pole _____ M/H tie downs, blocking, electricity and plumbing _____
date/app. by _____ date/app. by _____ date/app. by _____
Reconnection _____ RV _____ Re-roof _____
date/app. by _____ date/app. by _____ date/app. by _____

BUILDING PERMIT FEE \$ 1320.00 CERTIFICATION FEE \$ 26.33 SURCHARGE FEE \$ 26.33
MISC. FEES \$ 0.00 ZONING CERT. FEE \$ _____ FIRE FEE \$ 0.00 WASTE FEE \$ _____
FLOOD DEVELOPMENT FEE \$ _____ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ _____ **TOTAL FEE** 1397.66
INSPECTORS OFFICE Ljh CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

EVERY PERMIT ISSUED SHALL BECOME INVALID UNLESS THE WORK AUTHORIZED BY SUCH PERMIT IS COMMENCED WITHIN 180 DAYS AFTER ITS ISSUANCE, OR IF THE WORK AUTHORIZED BY SUCH PERMIT IS SUSPENDED OR ABANDONED FOR A PERIOD OF 180 DAYS AFTER THE TIME THE WORK IS COMMENCED. A VALID PERMIT RECIEVES AN APPROVED INSPECTION EVERY 180 DAYS. WORK SHALL BE CONSIDERED NOT SUSPENDED, ABANDONED OR INVALID WHEN THE PERMIT HAS RECIEVED AN APPROVED INSPECTION WITHIN 180 DAYS OT THE PREVIOUS INSPECTION.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

BE SEE ATTACHED COPY OF PERMIT.

2.C.

Columbia County Building Permit Application

ENERGY CODE ☒

For Office Use Only	Application # <u>1011-27-A</u>	Date Received <u>11/18</u>	By <u>JW</u>	Permit # <u>29099</u>
Zoning Official <u>BLK</u>	Date <u>23.11.10</u>	Flood Zone <u>X</u>	Land Use <u>A-3</u>	Zoning <u>A-3</u>
FEMA Map # <u>N/A</u>	Elevation <u>N/A</u>	MFE <u>1' above RL</u>	River <u>N/A</u>	Plans Examiner <u>T.C.</u>
Date <u>11-22-10</u>				
Comments _____				
☒ NOC ☒ EH ☒ Deed or PA ☒ Site Plan ☐ State Road Info ☐ Parent Parcel # _____				
☐ Dev Permit # _____ ☐ In Floodway ☐ Letter of Auth. from Contractor ☐ F W Comp. letter _____				
IMPACT FEES: EMS _____ Fire _____ Corr _____ Road/Code _____				
School _____ = TOTAL <u>Suspended</u> <u>VF</u>				

Septic Permit No. 10-0514-N

Fax 407-482-8283
407-235-4515
Phone 407-482-8282

Name Authorized Person Signing Permit DOUG BAGGETT

Address 481 CAREY WAY, ORLANDO, FL 32825

Owners Name DONALD BAGGETT Phone 863-467-4885

911 Address 415 S.W. CIRRUS DRIVE, LAKE CITY, FL

Contractors Name DOUG BAGGETT (PBA BUILDING CORP.) Phone 407-482-8282

Address 481 CAREY WAY, ORLANDO, FL 32825

Fee Simple Owner Name & Address DONALD W. BAGGETT 10151 SE 126th BLVD
ORLANDO, FL 32824

Bonding Co. Name & Address N/A

Architect/Engineer Name & Address RTR WORLD SERVICES

Mortgage Lenders Name & Address N/A

Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progress Energy

Property ID Number 22-55-17-09322-004 Estimated Cost of Construction \$236,000

Subdivision Name LAKE CITY AIRPARK Lot 4 Block _____ Unit _____ Phase _____

Driving Directions US 441/41, EAST ON AVIATION WAY, SOUTH ON
CIRRUS DRIVE - GO STRAIGHT TO 90 DEGREE CURVE INTO DRIVE.

Number of Existing Dwellings on Property 0

Construction of SINGLE FAMILY RESIDENCE Total Acreage 4 Lot Size _____

Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive Total Building Height 16'

Actual Distance of Structure from Property Lines - Front SEE SITE PLAN Side 107'8" Side 83' Side 181'10" Rear 324'9"

Number of Stories _____ Heated Floor Area 2467 Total Floor Area 5266 Roof Pitch _____

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction. **CODE:** Florida Building Code 2007 with 2009 Supplements and the 2008 National Electrical Code.

\$1447.66

* MINUS ZONING FEE:

"JW SPOKE w/ DAW" - 11.23.10



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM
APPLICATION FOR CONSTRUCTION PERMIT

SSO 322104477
SIBC 11/22
10-0514-N.
PERMIT NO. AP985020
DATE PAID: 11/18/10
FEE PAID: 425.00
RECEIPT #: 12-PID-1536247

APPLICATION FOR:

☒ New System ☐ Existing System ☐ Holding Tank ☐ Innovative
☐ Repair ☐ Abandonment ☐ Temporary ☐

APPLICANT: DONALD BAGGETT

AGENT: DUG BAGGETT TELEPHONE: 407-235-4515

MAILING ADDRESS: P.O. Box 781766, ORLANDO, FL 32878

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105(3)(m) OR 489.552, FLORIDA STATUTES. IT IS THE APPLICANT'S RESPONSIBILITY TO PROVIDE DOCUMENTATION OF THE DATE THE LOT WAS CREATED OR PLATTED (MM/DD/YY) IF REQUESTING CONSIDERATION OF STATUTORY GRANDFATHER PROVISIONS.

PROPERTY INFORMATION

LOT: 4 BLOCK: SUBDIVISION: LC Airport PLATTED: 1980

PROPERTY ID #: 22-55-17-09322-004 ZONING: I/M OR EQUIVALENT: ☒ Y ☐ N

PROPERTY SIZE: 4 ACRES WATER SUPPLY: ☒ PRIVATE PUBLIC ☐ ≤ 2000 GPD ☐ > 2000 GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? ☒ Y ☐ N DISTANCE TO SEWER: FT

PROPERTY ADDRESS: 415 SW CIRROS DRIVE, LAKE CITY, FL

DIRECTIONS TO PROPERTY: LAKE CITY AIRPORT - FROM 41/441 GO EAST ON AVIATION DRIVE, THEN SOUTH ON CIRROS.

BUILDING INFORMATION

☒ RESIDENTIAL ☐ COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-6, FAC
1	<u>SINGLE FAMILY RESIDENCE</u>	<u>3</u>	<u>2467</u>	
2				
3				
4				

☐ Floor/Equipment Drains ☐ Other (Specify)

SIGNATURE: [Signature] DATE: 11/17/2010

ENTERED
EKF

RECEIVED
11/18/10



STATE OF FLORIDA
DEPARTMENT OF HEALTH

APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number 10-0514-N

PART II - SITE PLAN

Scale: Each block represents 5 feet and 1 inch = 50 feet.

SEE ATTACHED
SITE PLAN

Notes:

Site Plan submitted by: DOUG BIGGETT, PBA BUILDING. PRES.

Signature

Title

Plan Approved y

Not Approved _____

Date 11/18/2010

By _____ County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT

LOCATION OF
PROPOSED SEPT
TANK & DRAIN PIP
RESIDENCE

1:30

התאחדות המורים

Columbia County Building Permit Application

TIME LIMITATIONS OF APPLICATION : An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

TIME LIMITATIONS OF PERMITS: Every permit issued shall become invalid unless the work authorized by such permit is commenced within 180 days after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of 180 days after the time work is commenced. A valid permit receives an approved inspection every 180 days. Work shall be considered not suspended, abandoned or invalid when the permit has received an approved inspection within 180 days of the previous approved inspection.

FLORIDA'S CONSTRUCTION LIEN LAW: Protect Yourself and Your Investment: According to Florida Law, those who work on your property or provide materials, and are not paid-in-full, have a right to enforce their claim for payment against your property. This claim is known as a construction lien. If your contractor fails to pay subcontractors or material suppliers or neglects to make other legally required payments, the people who are owed money may look to your property for payment, even if you have paid your contractor in full. This means if a lien is filed against your property, it could be sold against your will to pay for labor, materials or other services which your contractor may have failed to pay.

NOTICE OF RESPONSIBILITY TO BUILDING PERMITEE: **YOU ARE HEREBY NOTIFIED** as the recipient of a building permit from Columbia County, Florida, you will be held responsible to the County for any damage to sidewalks and/or road curbs and gutters, concrete features and structures, together with damage to drainage facilities, removal of sod, major changes to lot grades that result in ponding of water, or other damage to roadway and other public infrastructure facilities caused by you or your contractor, subcontractors, agents or representatives in the construction and/or improvement of the building and lot for which this permit is issued. No certificate of occupancy will be issued until all corrective work to these public infrastructures and facilities has been corrected.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

OWNERS CERTIFICATION: I CERTIFY THAT ALL THE FOREGOING INFORMATION IS ACCURATE AND THAT ALL WORK WILL BE DONE IN COMPLIANCE WITH ALL APPLICABLE LAWS REGULATING CONSTRUCTION AND ZONING.

NOTICE TO OWNER: There are some properties that may have deed restrictions recorded upon them. These restrictions may limit or prohibit the work applied for in your building permit. It may be to your advantage to check and see if your property is encumbered by any restrictions.

(Owners Must Sign All Applications Before Permit Issuance.)

Owners Signature

****OWNER BUILDERS MUST PERSONALLY APPEAR AND SIGN THE BUILDING PERMIT.**

CONTRACTORS AFFIDAVIT: By my signature I understand and agree that I have informed and provided this written statement to the owner of all the above written responsibilities in Columbia County for obtaining this Building Permit including all application and permit time limitations.

Contractor's Signature (Permitee)


Contractor's License Number CG-C 1508506
Columbia County
Competency Card Number _____

Affirmed under penalty of perjury to by the Contractor and subscribed before me this 18th day of November 2010.

Personally known _____ or Produced Identification FL DL

State of Florida Notary Signature (For the Contractor)

SEAL:



Prepared by:
Michael H. Harrell
Abstract & Title Services, Inc.
283 NW Cole Terrace
Lake City, Florida 32055

Warranty Deed

Individual to Individual

THIS WARRANTY DEED made the 24th day of March, 2006 by

Nicholas D. Carnevale, and his wife, Irene O. Carnevale

hereinafter called the grantor, to

Inst:2006007704 Date:03/29/2006 Time:08:45

Doc Stamp-Deed : 735.00

S.F. DC, P. DeWitt Cason, Columbia County B:1078 P:2365

Donald W. Baggett, and his wife, Julia Elaine Baggett

whose post office address is: 10151 SE 126th Blvd, Okeechobee, FL 34974

hereinafter called the grantee:

(Wherever used herein the terms "grantor" and "grantee" include all the parties to this instrument and the heirs, legal representatives and assigns of individuals, and the successors and assigns of corporation)

Witnesseth: That the grantor, for and in consideration of the sum of \$10.00 and other valuable considerations, receipt whereof is hereby acknowledged, hereby grants, bargains, sells, aliens, remises, releases, conveys, and confirms unto the grantee, all that certain land situate in COLUMBIA County, FLORIDA, viz: Parcel ID# R09322-004

Lot 4, of Lake City Airpark, a subdivision according to the plat thereof as recorded in Plat Book 5, Page 10, of the Public Records of Columbia County, Florida; and also, the North Half (N ½) of Oak Street (vacated) as lies South and contiguous to Lot 4.

TOGETHER with all tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining.

TO HAVE AND TO HOLD, the same in fee simple forever.

AND the grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land; that the grantor hereby fully warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2005.

IN WITNESS WHEREOF, the said grantor has signed and sealed these presents the day and year first above written.

Signed, sealed and delivered in our presence:

Traci Landry
Witness

Traci Landry
Printed Name

Jessica Newsome
Witness

Jessica Newsome
Printed Name

Nicholas D. Carnevale
Nicholas D. Carnevale

Irene O. Carnevale
Irene O. Carnevale

STATE OF FLORIDA
COUNTY OF COLUMBIA

The foregoing instrument was acknowledged before me this 24th day of March, 2006 by Nicholas D. Carnevale, and his wife, Irene O. Carnevale, personally known to me or, if not personally known to me, who produced drivers license for identification and who did not take an oath.

(SEAL)



Notary Public

My Commission Expires:

Inst. 201012018597 Date: 11/18/2010 Time: 11:23 AM
 DC.P.DeWitt Cason, Columbia County Page 1 of 1 B:1205 P:291

NOTICE OF COMMENCEMENT

County Clerk's Office Stamp or Seal

Tax Parcel Identification Number _____

THE UNDERSIGNED hereby gives notice that improvements will be made to certain real property, and in accordance with Section 713.13 of the Florida Statutes, the following information is provided in this NOTICE OF COMMENCEMENT.

1. Description of property (legal description):
 a) Street (job) Address: 415 SW CIRROS DRIVE, BOKE CITY, FL
2. General description of improvements: SINGLE FAMILY RESIDENCE
3. Owner Information
 a) Name and address: DONALD BAGGETT, 10151 SE 126TH BLVD, ORECHORD, FL
 b) Name and address of fee simple titleholder (if other than owner) _____
 c) Interest in property: FEESIMPLE
4. Contractor Information
 a) Name and address: DOUG BAGGETT, FBA BUILDING CORP, 481 CARRY WAY, ORLANDO, FL
 b) Telephone No.: 407-482-8282 Fax No. (Opt.): 32825
5. Surety Information
 a) Name and address: N/A
 b) Amount of Bond: _____
 c) Telephone No.: _____ Fax No. (Opt.): _____
6. Lender
 a) Name and address: N/A
 b) Phone No.: _____
7. Identity of person within the State of Florida designated by owner upon whom notices or other documents may be served:
 a) Name and address: DOUG BAGGETT, 481 CARRY WAY, ORLANDO, FL 32825
 b) Telephone No.: 407-482-8282 Fax No. (Opt.): _____
8. In addition to himself, owner designates the following person to receive a copy of the Lienor's Notice as provided in Section 713.13(l)(b), Florida Statutes:
 a) Name and address: _____
 b) Telephone No.: _____ Fax No. (Opt.): _____
9. Expiration date of Notice of Commencement (the expiration date is one year from the date of recording unless a different date is specified): _____

WARNING TO OWNER: ANY PAYMENTS MADE BY THE OWNER AFTER THE EXPIRATION OF THE NOTICE OF COMMENCEMENT ARE CONSIDERED IMPROPER PAYMENTS UNDER CHAPTER 713, PART I, SECTION 713.13, FLORIDA STATUTES, AND CAN RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY; A NOTICE OF COMMENCEMENT MUST BE RECORDED AND POSTED ON THE JOB SITE BEFORE THE FIRST INSPECTION. IF YOU INTEND TO OBTAIN FINANCING, CONSULT YOUR LENDER OR AN ATTORNEY BEFORE COMMENCING WORK OR RECORDING YOUR NOTICE OF COMMENCEMENT.

STATE OF FLORIDA
 COUNTY OF COLUMBIA


10. [Signature]
 Signature of Owner or Owner's Authorized Office/Director/Partner/Manager

DOUGLAS J. BAGGETT
 Print Name

The foregoing instrument was acknowledged before me, a Florida Notary, this 18th day of November, 2010, by:
Doug B. Andrew Walther as officer / notary (type of authority, e.g. officer, trustee, attorney
 fact) for Doug Baggett (name of party on behalf of whom instrument was executed).

Personally Known _____ OR Produced Identification X Type FL DL

Notary Signature [Signature] Notary Stamp or Seal:



11. Verification pursuant to Section 92.525, Florida Statutes. Under penalties of perjury, I declare that I have read the foregoing and that the facts stated in it are true to the best of my knowledge and belief.

[Signature]
 Signature of Natural Person Signing (in line #10 above).



**COLUMBIA COUNTY BUILDING DEPARTMENT
RESIDENTIAL CHECK LIST REQUIREMENTS**

6-25-09

**MINIMUM PLAN REQUIREMENTS FOR THE
FLORIDA BUILDING CODE RESIDENTIAL 2007 EFFECTIVE 1 MARCH 2009 & 2009
SUPPLEMENTS EFFECTIVE 1 MARCH 2009, ONE (1) AND TWO (2) FAMILY DWELLINGS
with Supplements and Revision, OF THE NATIONAL ELECTRICAL 2008**

ALL REQUIREMENTS ARE SUBJECT TO CHANGE

**ALL BUILDING PLANS MUST INDICATE COMPLIANCE with the Current 2007
FLORIDA BUILDING CODES RESIDENTIAL EFFECTIVE 1 MARCH 2009 & 2009
SUPPLEMENTS EFFECTIVE 1 MARCH 2009. ALL PLANS OR DRAWINGS SHALL
PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND
SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE
STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE
STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY
DWELLINGS.**

**FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER
FIGURE R301.2(4) of the FLORIDA BUILDING CODES RESIDENTIAL (Florida Wind
speed map) SHALL BE USED.**

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE -----110 MPH
NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

**GENERAL REQUIREMENTS:
APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL**

Items to Include-
Each Box shall be
Circled as
Applicable

Yes No N/A

1	Two (2) complete sets of plans containing the following:			
2	All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void			
3	Condition space (Sq. Ft.) 2407	Total (Sq. Ft.) under roof 5266	IIIIIIII	IIIIIIII IIII

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL R101.2.1

Site Plan information including:

4	Dimensions of lot or parcel of land	✓		
5	Dimensions of all building set backs	✓		
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed well and septic tank and all utility easements.	✓		
7	Provide a full legal description of property. SEE WARRANTY DEED	ASA		

Wind-load Engineering Summary, calculations and any details required

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
8	Plans or specifications must show compliance with FBCR Chapter 3	IIIII	IIII	IIIII
		YES	NO	N/A
9	Basic wind speed (3-second gust), miles per hour	✓		
10	(Wind exposure – if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated)	✓		
11	Wind importance factor and nature of occupancy	✓		
12	The applicable internal pressure coefficient, Components and Cladding	✓		
13	The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component, cladding materials not specifically designed by the registered design professional.	✓		

Elevations Drawing including:

14	All side views of the structure	✓		
15	Roof pitch	✓		
16	Overhang dimensions and detail with attic ventilation	✓		
17	Location, size and height above roof of chimneys	✓		
18	Location and size of skylights with Florida Product Approval	N/A		
18	Number of stories	✓		
20A	Building height from the established grade to the roofs highest peak	✓		

Floor Plan including:

20	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches, deck, balconies	✓		
21	Raised floor surfaces located more than 30 inches above the floor or grade	✓		
22	All exterior and interior shear walls indicated	✓		
23	Shear wall opening shown (Windows, Doors and Garage doors)	✓		
24	Show compliance with Section FBCR 310 Emergency escape and rescue opening shown in each bedroom (net clear opening shown) and Show compliance with Section FBCR 613.2 where the opening of an operable window is located more than 72 inches above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches above the finished floor of the room in which the window is located. Glazing between the floor and 24 inches shall be fixed or have openings through which a 4-inch-diameter sphere cannot pass.	✓		
25	Safety glazing of glass where needed	N/A		
26	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 of FBCR)			
27	Show stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails	✓		
28	Identify accessibility of bathroom (see FBCR SECTION 322)			

All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plans (see Florida product approval form)

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable
--	---

FBCR 403: Foundation Plans

		YES	NO	N/A
29	Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	✓		
30	All posts and/or column footing including size and reinforcing	✓		
31	Any special support required by soil analysis such as piling.	✓		
32	Assumed load-bearing value of soil <u>2,000</u> Pound Per Square Foot	✓		
33	Location of horizontal and vertical steel, for foundation or walls (include # size and type) For structures with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an grounding electrode system. Per the National Electrical Code article 250.52.3	✓		

FBCR 506: CONCRETE SLAB ON GRADE

34	Show Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)	✓		
35	Show control joints, synthetic fiber reinforcement or welded fire fabric reinforcement and Supports	✓		

FBCR 320: PROTECTION AGAINST TERMITES

36	Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or Sub mit other approved termite protection methods. Protection shall be provided by registered termiticides	✓		
----	--	---	--	--

FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)

37	Show all materials making up walls, wall height, and Block size, mortar type	✓		
38	Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement			

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect

Floor Framing System: First and/or second story

39	Floor truss package shall including layout and details, signed and sealed by Florida Registered Professional Engineer	✓		
40	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls, stem walls and/or piers	N/A		
41	Girder type, size and spacing to load bearing walls, stem wall and/or piers	N/A		
42	Attachment of joist to girder	N/A		
43	Wind load requirements where applicable	✓		
44	Show required under-floor crawl space	✓		

45	Show required amount of ventilation opening for under-floor spaces	✓		
46	Show required covering of ventilation opening	✓		
47	Show the required access opening to access to under-floor spaces	✓		
48	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges & interior of the areas structural panel sheathing	N/A		
49	Show Draftstopping, Fire caulking and Fire blocking			
50	Show fireproofing requirements for garages attached to living spaces, per FBCR section 309	N/A		
51	Provide live and dead load rating of floor framing systems (psf).	N/A		

FBCR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
52	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls	N/A		
53	Fastener schedule for structural members per table FBCR 602.3 are to be shown			
54	Show Wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural members, showing fastener schedule attachment on the edges & intermediate of the areas structural panel sheathing			
55	Show all required connectors with a max uplift rating and required number of connectors and oc spacing for continuous connection of structural walls to foundation and roof trusses or rafter systems			
56	Show sizes, type, span lengths and required number of support jack studs, king studs for shear wall opening and girder or header per FBCR Table 502.5 (1)			
57	Indicate where pressure treated wood will be placed			
58	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural panel sheathing edges & intermediate areas			
59	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail			

FBCR :ROOF SYSTEMS:

60	Truss design drawing shall meet section FBCR 802.10 Wood trusses	✓		
61	Include a layout and truss details, signed and sealed by Florida Professional Engineer	✓		
62	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters	✓		
63	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details	✓		
64	Provide dead load rating of trusses	✓		

FBCR 802:Conventional Roof Framing Layout

65	Rafter and ridge beams sizes, span, species and spacing	✓		
66	Connectors to wall assemblies' include assemblies' resistance to uplift rating	✓		
67	Valley framing and support details	N/A		
68	Provide dead load rating of rafter system	✓		

FBCR Table 602.3(2) & FBCR 803 ROOF SHEATHING

69	Include all materials which will make up the roof decking, identification of structural panel sheathing, grade, thickness	✓		
70	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas	✓		

FBCR ROOF ASSEMBLIES FRC Chapter 9

71	Include all materials which will make up the roof assemblies covering	✓		
72	Submit Florida Product Approval numbers for each component of the roof assemblies covering	PBA		

TBD

FBCR Chapter 11 Energy Efficiency Code for residential building

Residential construction shall comply with this code by using the following compliance methods in the FBCR chapter 11 Residential buildings compliance methods. **Two of the required forms are to be submitted, N1100.1.1.1 As an alternative to the computerized Compliance Method A, the Alternate Residential Point System Method hand calculation, Alternate Form 600A, may be used. All requirements specific to this calculation are located in Sub appendix C to Appendix G. Buildings complying by this alternative shall meet all mandatory requirements of this chapter. Computerized versions of the Alternate Residential Point System Method shall not be acceptable for code compliance.**

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable		
		YES	NO	N/A
73	Show the insulation R value for the following areas of the structure	✓		
74	Attic space	✓		
75	Exterior wall cavity	✓		
76	Crawl space	N/A		

HVAC information

77	Submit two copies of a Manual J sizing equipment or equivalent computation study	PBA		
78	Exhaust fans shown in bathrooms Mechanical exhaust capacity of 50 cfm intermittent or 20 cfm continuous required	✓		
79	Show clothes dryer route and total run of exhaust duct	✓		

Plumbing Fixture layout shown

80	All fixtures waste water lines shall be shown on the foundation plan	✓		
81	Show the location of water heater	✓		

Private Potable Water

82	Pump motor horse power	PBA		
83	Reservoir pressure tank gallon capacity	PBA		
84	Rating of cycle stop valve if used	PBA		

Electrical layout shown including

85	Show Switches, receptacles outlets, lighting fixtures and Ceiling fans	✓		
86	Show all 120-volt, single phase, 15- and 20-ampere branch circuits outlets required to be protected by Ground-Fault Circuit Interrupter (GFCI) Article 210.8 A	✓		
87	Show the location of smoke detectors & Carbon monoxide detectors	✓		
88	Show service panel, sub-panel, location(s) and total ampere ratings	✓		
89	On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a disconnecting means for the utility company electrical service. Conductors used from the exterior disconnecting means to a panel or sub panel shall have four-wire conductors, of which one conductor shall be used as an equipment ground. Indicate if the utility company service entrance cable will be of the overhead or underground type. For structures with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an Grounding electrode system. Per the National Electrical Code article 250.52.3	✓ SAT		
90	Appliances and HVAC equipment and disconnects			
91	Show all 120-volt, single phase, 15- and 20-ampere branch circuits supplying outlets installed in dwelling unit family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreation rooms, closets, hallways, or similar rooms or areas shall be protected by a listed Combination arc-fault circuit interrupter , Protection device.	✓		

Disclosure Statement for Owner Builders *If you as the applicant will be acting as an owner/builder under section 489.103(7) of the Florida Statutes, submit the required owner builder disclosure statement form.*

Notice Of Commencement

A notice of commencement form **recorded** in the Columbia County Clerk Office is required to be filed with the building department Before Any Inspections can be preformed.

GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Items to Include- Each Box shall be Circled as Applicable
--	--

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

		YES	NO	N/A
92	Building Permit Application A current Building Permit Application form is to be completed and submitted for all residential projects	IBA	✓	
93	Parcel Number The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested	IBA	✓	
94	Environmental Health Permit or Sewer Tap Approval A copy of a approved Columbia County Environmental Health (386) 758-1058	PBA		
95	City of Lake City A permit showing an approved waste water sewer tap	IBA		✓
96	Toilet facilities shall be provided for all construction sites	PBA	✓	
97	Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White an approval land use development letter issued by the Town of Fort is required to be submitted with the application for a building permit.	N/A		✓

98	Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations	N/A	✓	
99	CERTIFIED FINISHED FLOOR ELEVATIONS will be required on any project where the base flood elevation (100 year flood) has been established	N/A		
100	A development permit will also be required. Development permit cost is \$50.00	PBA		
101	Driveway Connection: If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.	PBA		✓
102	911 Address: If the project is located in an area where a 911 address has not been issued, then application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125	PBA	✓	

Section R101.2.1 of the Florida Building Code Residential:

The provisions of Chapter 1, Florida Building Code, Building shall govern the administration and enforcement of the Florida Building Code, Residential.

Section 105 of the Florida Building Code defines the:

Time limitation of application.

An application for a permit for any proposed work shall be deemed to have been abandoned 180 days after the date of filing, unless such application has been pursued in good faith or a permit has been issued; except that the building official is authorized to grant one or more extensions of time for additional periods not exceeding 90 days each. The extension shall be requested in writing and justifiable cause demonstrated.

Single-family residential dwelling.

Section 105.3.4 A building permit for a single-family residential dwelling must be issued within 30 working days of application therefor unless unusual circumstances require a longer time for processing the application or unless the permit application fails to satisfy the Florida Building Code or the enforcing agency's laws or ordinances.

Permit intent.

Section 105.4.1: A permit issued shall be constructed to be a license to proceed with the work and not as authority to violate, cancel, alter or set aside any of the provisions of the technical codes, nor shall issuance of a permit prevent the building official from thereafter requiring a correction of errors in plans, construction or violations of this code. Every permit issued shall become invalid unless the work authorized by such permit is commenced within six months after its issuance, or if the work authorized by such permit is suspended or abandoned for a period of six months after the time the work is commenced.

PRODUCT APPROVAL SPECIFICATION

Location: SHEET

Project Name: BAGGETT RESIDENCE

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit on or after April 1, 2004. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS		<i>SEE DRAWINGS</i>	
1. Swinging			
2. Sliding			
3. Sectional (GARAGE)	WAYNE DATION	SERIES 8000 GARAGE DOOR	FL8248-R1(8248.16)
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS		<i>SEE DRAWINGS</i>	
1. Single hung			
2. Horizontal Slider			
3. Casement			
4. Double Hung			
5. Fixed			
6. Awning			
7. Pass-through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11 Dual Action			
12. Other			
C. PANEL WALL		<i>WILL FORWARD</i>	
1. Siding	TOMAS HARDIE	HARDI PLANK LAP SIDING	FL13192-R1
2. Soffits	ALSCO	ALUMINUM SOFFIT PANELS	FL4459-R2
3. EIFS	N/A		
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS		<i>WILL FORWARD</i>	
1. Asphalt Shingles			
2. Underlayments	WRGRACE	ICE & WATER SHIELD	FL298-R2
3. Roofing Fasteners	DAG-11	FL699 SRMCO FASTEN SCHEDULE	FL-10741
4. Non-structural Metal	SOUTHERS THRUWATERS	FL11937 - 5V CRIMP ROOF	FL11937
Rt 5. Built-Up Roofing	N/A		
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs Residential Performance Method A

Project Name: R1110119 Street: City, State, Zip: Lake City, FL, Owner: Doug Baggett Design Location: FL, Gainesville	Builder Name: <i>Doug Baggett</i> Permit Office: Columbia County Permit Number: <i>29099</i> Jurisdiction: 221000
--	--

1. New construction or existing New (From Plans) 2. Single family or multiple family Single-family 3. Number of units, if multiple family 1 4. Number of Bedrooms 3 5. Is this a worst case? No 6. Conditioned floor area (ft²) 2619 7. Windows (551.3 sqft.) Description Area a. U-Factor: Dbl, U=0.35 551.30 ft² SHGC: SHGC=0.27 b. U-Factor: N/A ft² SHGC: c. U-Factor: N/A ft² SHGC: d. U-Factor: N/A ft² SHGC: e. U-Factor: N/A ft² SHGC: 8. Floor Types (2619.0 sqft.) Insulation Area a. Slab-On-Grade Edge Insulation R=0.0 2619.00 ft² b. N/A R= ft² c. N/A R= ft²	9. Wall Types (2155.3 sqft.) Insulation Area a. Concrete Block - Int Insul, Exterior R=4.0 2155.30 ft² b. N/A R= ft² c. N/A R= ft² d. N/A R= ft² 10. Ceiling Types (2619.0 sqft.) Insulation Area a. Cathedral/Single Assembly (Vented) R=19.0 2619.00 ft² b. N/A R= ft² c. N/A R= ft² 11. Ducts a. Sup: Attic Ret: Attic AH: Interior Sup. R= 6, 225 ft² 12. Cooling systems a. Central Unit Cap: 57.0 kBtu/hr SEER: 13 13. Heating systems a. Electric Heat Pump Cap: 57.0 kBtu/hr HSPF: 8 14. Hot water systems a. Propane Cap: 80 gallons EF: 0.59 b. Conservation features None 15. Credits CF, Pstat
--	--

Glass/Floor Area: 0.211	Total As-Built Modified Loads: 35.41 Total Baseline Loads: 51.30	PASS
-------------------------	---	------

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code. <i>Lina M. Reese</i> PREPARED BY: _____ DATE: 11-19-10 I hereby certify that this building, as designed, is in compliance with the Florida Energy Code. OWNER/AGENT: _____ DATE: _____	Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.  BUILDING OFFICIAL: _____ DATE: _____
--	--

- Compliance requires certification by the air handler unit manufacturer that the air handler enclosure qualifies as certified factory-sealed in accordance with N1110.A.3.



PROJECT

Title: R1110119	Bedrooms: 3	Address Type: Street Address
Building Type: FLAsBuilt	Conditioned Area: 2619	Lot #
Owner: Doug Baggett	Total Stories: 1	Block/SubDivision:
# of Units: 1	Worst Case: No	PlatBook:
Builder Name:	Rotate Angle: 0	Street:
Permit Office: Columbia County	Cross Ventilation: No	County: Columbia
Jurisdiction: 221000	Whole House Fan: No	City, State, Zip: Lake City , FL ,
Family Type: Single-family		
New/Existing: New (From Plans)		
Comment:		

CLIMATE

✓	Design Location	TMY Site	IECC Zone	Design Temp 97.5 %	Design Temp 2.5 %	Int Design Temp Winter	Int Design Temp Summer	Heating Degree Days	Design Moisture	Daily Temp Range
_____	FL, Gainesville	FL_GAINESVILLE_REGI	2	32	92	75	70	1305.5	51	Medium

FLOORS

✓	#	Floor Type	Perimeter	R-Value	Area	Tile	Wood	Carpet
_____	1	Slab-On-Grade Edge Insulatio	231.3 ft	0	2619 ft²	0.25	0.5	0.25

ROOF

✓	#	Type	Materials	Roof Area	Gable Area	Roof Color	Solar Absor.	Tested	Deck Insul.	Pitch
_____	1	Hip	Metal	2760 ft²	0 ft²	Medium	0.65	N	0	18.4 deg

ATTIC

✓	#	Type	Ventilation	Vent Ratio (1 in)	Area	RBS	IRCC
_____	1	Partial cathedral cei	Vented	300	2619 ft²	N	N

CEILING

✓	#	Ceiling Type	R-Value	Area	Framing Frac	Truss Type
_____	1	Cathedral/Single Assembly (Vented)	19	2619 ft²	0.1	Wood

WALLS

✓	#	Ornt	Adjacent To	Wall Type	Cavity R-Value	Area	Sheathing R-Value	Framing Fraction	Solar Absor.
_____	1	NE	Exterior	Concrete Block - Int Insul	4	597.3333	0	0	0.03
_____	2	SE	Exterior	Concrete Block - Int Insul	4	480.5 ft²	0	0	0.03
_____	3	SW	Exterior	Concrete Block - Int Insul	4	595.2 ft²	0	0	0.03
_____	4	NW	Exterior	Concrete Block - Int Insul	4	482.2222	0	0	0.03

WINDOWS

Orientation shown is the entered, asBuilt orientation.

✓	#	Ornt	Frame	Panels	NFRC	U-Factor	SHGC	Storms	Area	Overhang		Int Shade	Screening
										Depth	Separation		
✓	1	NE	TIM	Low-E Double	Yes	0.35	0.27	N	80 ft²	10 ft 4 in	0 ft 6 in	HERS 2006	None
✓	2	NE	TIM	Low-E Double	Yes	0.35	0.27	N	80.4 ft²	17 ft 0 in	4 ft 0 in	HERS 2006	None
✓	3	NE	None	Low-E Double	Yes	0.35	0.27	N	12 ft²	2 ft 0 in	2 ft 0 in	HERS 2006	None
✓	4	NE	TIM	Low-E Double	Yes	0.35	0.27	N	15.6 ft²	17 ft 0 in	2 ft 0 in	HERS 2006	None
✓	5	SE	TIM	Low-E Double	Yes	0.35	0.27	N	20.1 ft²	17 ft 4 in	0 ft 6 in	HERS 2006	None
✓	6	SE	None	Low-E Double	Yes	0.35	0.27	N	4 ft²	9 ft 8 in	0 ft 6 in	HERS 2006	None
✓	7	SE	None	Low-E Double	Yes	0.35	0.27	N	8 ft²	0 ft 6 in	2 ft 0 in	HERS 2006	None
✓	8	SE	None	Low-E Double	Yes	0.35	0.27	N	12 ft²	2 ft 0 in	2 ft 0 in	HERS 2006	None
✓	9	SW	TIM	Low-E Double	Yes	0.35	0.27	N	40.2 ft²	13 ft 0 in	0 ft 6 in	HERS 2006	None
✓	10	SW	None	Low-E Double	Yes	0.35	0.27	N	72 ft²	9 ft 8 in	0 ft 6 in	HERS 2006	None
✓	11	SW	None	Low-E Double	Yes	0.35	0.27	N	72 ft²	13 ft 0 in	0 ft 6 in	HERS 2006	None
✓	12	SW	TIM	Low-E Double	Yes	0.35	0.27	N	7.8 ft²	13 ft 0 in	0 ft 6 in	HERS 2006	None
✓	13	NW	TIM	Low-E Double	Yes	0.35	0.27	N	20.1 ft²	9 ft 8 in	0 ft 6 in	HERS 2006	None
✓	14	NW	TIM	Low-E Double	Yes	0.35	0.27	N	20.1 ft²	9 ft 8 in	0 ft 6 in	HERS 2006	None
✓	15	NW	None	Low-E Double	Yes	0.35	0.27	N	9 ft²	4 ft 4 in	0 ft 6 in	HERS 2006	None
✓	16	NW	None	Low-E Double	Yes	0.35	0.27	N	18 ft²	6 ft 0 in	0 ft 6 in	HERS 2006	None
✓	17	NW	None	Low-E Double	Yes	0.35	0.27	N	12 ft²	0 ft 6 in	0 ft 6 in	HERS 2006	None
✓	18	NW	None	Low-E Double	Yes	0.35	0.27	N	12 ft²	12 ft 8 in	0 ft 6 in	HERS 2006	None
✓	19	NW	None	Low-E Double	Yes	0.35	0.27	N	36 ft²	9 ft 8 in	0 ft 6 in	HERS 2006	None

INFILTRATION & VENTING

✓	Method	SLA	CFM 50	ACH 50	ELA	EqLA	--- Forced Ventilation ---		Run Time	Fan
							Supply CFM	Exhaust CFM	Fraction	Watts
✓	Default	0.00036	2473	6.09	135.8	255.3	0 cfm	0 cfm	0	0

COOLING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Air Flow	SHR	Ducts
✓	1	Central Unit	None	SEER: 13	57 kBtu/hr	cfm	0.8	sys#1

HEATING SYSTEM

✓	#	System Type	Subtype	Efficiency	Capacity	Ducts
✓	1	Electric Heat Pump	None	HSPF: 8	57 kBtu/hr	sys#1

HOT WATER SYSTEM

✓	#	System Type	EF	Cap	Use	SetPnt	Conservation
✓	1	Propane	0.59	80 gal	60 gal	120 deg	None

SOLAR HOT WATER SYSTEM

✓	FSEC Cert #	Company Name	System Model #	Collector Model #	Collector Area	Storage Volume	FEF
_____	None	None			ft²		

DUCTS

✓	#	--- Supply --- Location	R-Value	Area	--- Return --- Location	Area	Leakage Type	Air Handler	CFM 25	Percent Leakage	QN	RLF
_____	1	Attic	6	225 ft²	Attic	75 ft²	Default Leakage	Interior	(Default)	(Default) %		

TEMPERATURES

Programable Thermostat: Y

Ceiling Fans:

Cooling	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Heating	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec
Venting	☒ Jan	☒ Feb	☒ Mar	☒ Apr	☒ May	☒ Jun	☒ Jul	☒ Aug	☒ Sep	☒ Oct	☒ Nov	☒ Dec

Thermostat Schedule: HERS 2006 Reference

Hours

Schedule Type		1	2	3	4	5	6	7	8	9	10	11	12
Cooling (WD)	AM PM	78 80	78 80	78 78	78 78	78 78	78 78	78 78	78 78	80 78	80 78	80 78	80 78
Cooling (WEH)	AM PM	78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78
Heating (WD)	AM PM	66 68	66 68	66 68	66 68	66 68	68 68	68 68	68 68	68 68	68 68	68 66	68 66
Heating (WEH)	AM PM	66 68	66 68	66 68	66 68	66 68	68 68	68 68	68 68	68 68	68 68	68 66	68 66

Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS:

Lake City, FL,

PERMIT #:

INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	N1106.AB.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	N1106.AB.1.2	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	N1106.AB.1.2	Penetrations/openings > 1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	N1106.AB.1.2	Between walls & ceilings; penetrations of ceiling plane to top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	N1106.AB.1.2	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	N1106.AB.1.2	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	N1106.AB.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	N1112.AB.3	Comply with efficiency requirements in Table N1112.ABC.3 Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	N1112.AB.2.3	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%. Heat pump pool heaters shall have a minimum COP of 4.0.	
Shower heads	N1112.AB.2.4	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	N1110.AB	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated and installed in accordance with the criteria of Section N1110.AB. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	N1107.AB.2	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	N1104.AB.1 N1102.B.1.1	Ceilings-Min. R-19. Common walls-frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE INDEX* = 69

The lower the Energy Performance Index, the more efficient the home.

, Lake City, FL,

1. New construction or existing	New (From Plans)	9. Wall Types	Insulation	Area
2. Single family or multiple family	Single-family	a. Concrete Block - Int Insul, Exterior	R=4.0	2155.30 ft ²
3. Number of units, if multiple family	1	b. N/A	R=	ft ²
4. Number of Bedrooms	3	c. N/A	R=	ft ²
5. Is this a worst case?	No	d. N/A	R=	ft ²
6. Conditioned floor area (ft ²)	2619	10. Ceiling Types	Insulation	Area
7. Windows**	Description	a. Cathedral/Single Assembly (Vented)	R=19.0	2619.00 ft ²
a. U-Factor:	DbI, U=0.35	b. N/A	R=	ft ²
SHGC:	SHGC=0.27	c. N/A	R=	ft ²
b. U-Factor:	N/A	11. Ducts		
SHGC:		a. Sup: Attic Ret: Attic AH: Interior Sup. R= 6, 225 ft ²		
c. U-Factor:	N/A	12. Cooling systems		
SHGC:		a. Central Unit	Cap: 57.0 kBtu/hr	
d. U-Factor:	N/A		SEER: 13	
SHGC:		13. Heating systems		
e. U-Factor:	N/A	a. Electric Heat Pump	Cap: 57.0 kBtu/hr	
SHGC:			HSPF: 8	
8. Floor Types	Insulation	14. Hot water systems		
a. Slab-On-Grade Edge Insulation	R=0.0	a. Propane	Cap: 80 gallons	
b. N/A	R=	b. Conservation features	EF: 0.59	
c. N/A	R=	None		
		15. Credits		
			CF, Pstat	

I certify that this home has complied with the Florida Energy Efficiency Code for Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: _____ Date: _____

Address of New Home: _____ City/FL Zip: _____



*Note: The home's estimated Energy Performance Index is only available through the EnergyGauge USA - FlaRes2008 computer program. This is not a Building Energy Rating. If your index is below 100, your home may qualify for incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at (321) 638-1492 or see the Energy Gauge web site at energygauge.com for information and a list of certified Raters. For information about Florida's Energy Efficiency Code for Building Construction, contact the Department of Community Affairs at (850) 487-1824.

**Label required by Section 13-104.4.5 of the Florida Building Code, Building, or Section B2.1.1 of Appendix G of the Florida Building Code, Residential, if not DEFAULT.


[DCA HOME](#) | [ABOUT DCA](#) | [DCA PROGRAMS](#) | [CONTACT DCA](#)

[BCIS Home](#) | [Log In](#) | [User Registration](#) | [Hot Topics](#) | [Submit Surcharge](#) | [Stats & Facts](#) | [Publications](#) | [FBC Staff](#) | [BCIS Site Map](#) | [Links](#) | [Search](#)
**Product Approval**

USER: Public User

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > **Application Detail**


FL #	FL10298-R1						
Application Type	Revision						
Code Version	2007						
Application Status	Approved						
Comments							
Archived	☐						
Product Manufacturer	JELD-WEN						
Address/Phone/Email	3737 Lakeport Blvd Klamath Falls, OR 97601 (800) 535-3936 fbc@jeld-wen.com						
Authorized Signature	Janet Gerard fbc@jeld-wen.com						
Technical Representative	Steve Strawn						
Address/Phone/Email	31725 Hwy 97 N. Chiloquin, OR 97624 (541) 783-2057 stevestr@jeld-wen.com						
Quality Assurance Representative							
Address/Phone/Email							
Category	Windows						
Subcategory	Double Hung						
Compliance Method	Certification Mark or Listing						
Certification Agency	Window and Door Manufacturers Association						
Validated By	Window and Door Manufacturers Association						
Referenced Standard and Year (of Standard)	<table border="0"> <thead> <tr> <th><u>Standard</u></th> <th><u>Year</u></th> </tr> </thead> <tbody> <tr> <td>AAMA/WDMA/CSA101/I.S.2A440-05</td> <td>2005</td> </tr> <tr> <td>ASTM E1300</td> <td>2004</td> </tr> </tbody> </table>	<u>Standard</u>	<u>Year</u>	AAMA/WDMA/CSA101/I.S.2A440-05	2005	ASTM E1300	2004
<u>Standard</u>	<u>Year</u>						
AAMA/WDMA/CSA101/I.S.2A440-05	2005						
ASTM E1300	2004						
Equivalence of Product Standards							
Certified By							
Product Approval Method	Method 1 Option A						
Date Submitted	05/09/2008						

Date Validated 06/02/2008
 Date Pending FBC Approval 07/01/2008
 Date Approved 09/15/2008

Summary of Products

FL #	Model, Number or Name	Description
10298.1	Premium Sitrine EX Clad Double Hung 406-H-690	Clad Double Hung 48x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298 R1 C CAC CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298 R1 II Prem Clad SLEX DH Install [45x80] 73597.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.2	Premium Sitrine EX Clad Double Hung 406-H-699	Clad Double Hung 2 Wide
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other: Clad DH 2-Wide Mullion (91x92)		Certification Agency Certificate FL10298 R1 C CAC CCL for Jeld-Wen H 1-23-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298 R1 II Prem Clad SLEX Clad DH 2 Wide Mullion Install [91x92] 76547.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.3	Premium Sitrine EX Clad Double Hung 406-H-706	Clad Double Hung HP 45x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298 R1 C CAC CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298 R1 II Prem Clad SLEX DH Install [45x80HP] 71763.02.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.4	Premium Sitrine EX Clad Double Hung 406-H-709	Clad Double Hung HP 37x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298 R1 C CAC CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298 R1 II Prem Clad SLEX DH Install [37x80HP] 77371.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.5	Premium Sitrine EX Clad Double Hung 406-H-710	Clad Double Hung Triple 3(37x64)
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298 R1 C CAC CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298 R1 II Prem Clad SLEX Clad DH 3 Wide Mullion Install [112x64] 77040.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.6	Premium Sitrine EX Clad Double	Clad Double Hung HP Plus 41x64

	Hung 406-H-716	
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +60/-60 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [41x64HPP] 78306.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.7	Premium Sitrine EX Clad Double Hung 406-H-717	Clad Double Hung HP Plus 37x76
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +60/-60 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [37x76HPP] 78305.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.8	Premium Sitrine EX Clad Double Hung HP 406-H-665	Clad Double Hung 45.375x92
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [45x92HP] 71758.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.9	Premium Sitrine EX Clad Double Hung HP 406-H-687	Clad Double Hung 33x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [33x80HP] 76501.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.10	Premium Sitrine EX Clad Double Hung HP 406-H-691	Clad Double Hung 45x64
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 09/05/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [45x64] 76496.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.11	Premium Sitrine EX Clad Double Hung HP 406-H-700	Clad Double Hung HP 45x92
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 1-23-08.pdf Quality Assurance Contract Expiration Date 03/16/2011 Installation Instructions FL10298_R1_II_Prem Clad SLEX DH Install [45x92] 76547.02.pdf

		Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.12	Premium Sitrine EX Wood Double Hung 406-H-688	Wood Double Hung 45x92
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 09/06/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [45x92] 76502.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.13	Premium Sitrine EX Wood Double Hung 406-H-703	Wood Double Hung 33x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 1-23-08.pdf Quality Assurance Contract Expiration Date 07/06/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [33x80] 71790.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.14	Premium Sitrine EX Wood Double Hung 406-H-718	Wood Double Hung Standard 45x92
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 12/20/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [45x92] 78304.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.15	Premium Sitrine EX Wood Double Hung 406-H-720	Wood Double Hung Twin 2(45x92)
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +25/-25 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 07/06/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Case 2 Wide Mullion Install [91x92] 76722.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.16	Premium Sitrine EX Wood Double Hung HP 406-H-684	Wood Double Hung 45x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +35/-35 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 09/06/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [45x80HP] 76493.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.17	Premium Sitrine EX Wood Double Hung HP 406-H-685	Wood Double Hung 45x60
Limits of Use Approved for use in HVHZ: No		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf

Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Quality Assurance Contract Expiration Date 09/05/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [45x60HP] 76499.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10298.18	Premium Sitrine EX Wood Double Hung HP 406-H-686	Wood Double Hung 33x80
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +50/-50 Other:		Certification Agency Certificate FL10298_R1_C_CAC_CCL for Jeld-Wen H 4-7-08.pdf Quality Assurance Contract Expiration Date 09/17/2011 Installation Instructions FL10298_R1_II_Prem Wood SLEX Double Hung Install [33x80HP] 76500.01.pdf Verified By: Window and Door Manufacturers Association Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:

[Back](#)

[Next](#)

Department of Community Affairs
 Florida Building Code Online
 Codes and Standards
 2555 Shumard Oak Boulevard
 Tallahassee, Florida 32399-2100
 (850) 487-1824, Fax (850) 414-8436
 © 2000-2010 The State of Florida. All rights reserved.

[Privacy Statement](#) |
 [Copyright Statement](#) |
 [Accessibility Statement](#) |
 [Plug-in Software](#) |
 [Customer Service Survey](#) |
 [Contact Us](#)

Product Approval Accepts:




[DCA HOME](#) | [ABOUT DCA](#) | [DCA PROGRAMS](#) | [CONTACT DCA](#)
[BCIS Home](#) | [Log In](#) | [User Registration](#) | [Hot Topics](#) | [Submit Surcharge](#) | [Stats & Facts](#) | [Publications](#) | [FBC Staff](#) | [BCIS Site Map](#) | [Links](#) | [Search](#)
**Product Approval**

USER: Public User

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > **Application Detail**

- COMMUNITY PLANNING
- HOUSING & COMMUNITY DEVELOPMENT
- EMERGENCY MANAGEMENT
- OFFICE OF THE SECRETARY

FL #	FL10784				
Application Type	New				
Code Version	2007				
Application Status	Approved				
Comments					
Archived	☐				
Product Manufacturer	JELD-WEN				
Address/Phone/Email	3737 Lakeport Blvd Klamath Falls, OR 97601 (800) 535-3936 fbc@jeld-wen.com				
Authorized Signature	Janet Gerard fbc@jeld-wen.com				
Technical Representative	Steve Strawn				
Address/Phone/Email	31725 Hwy 97 N. Chiloquin, OR 97624 (541) 783-2057 stevestr@jeld-wen.com				
Quality Assurance Representative					
Address/Phone/Email					
Category	Exterior Doors				
Subcategory	Swinging Exterior Door Assemblies				
Compliance Method	Certification Mark or Listing				
Certification Agency	Miami-Dade BCCO - CER				
Validated By	Miami-Dade BCCO - VAL				
Referenced Standard and Year (of Standard)	<table border="0"> <tr> <td>Standard</td> <td>Year</td> </tr> <tr> <td>TAS 202-94</td> <td>1994</td> </tr> </table>	Standard	Year	TAS 202-94	1994
Standard	Year				
TAS 202-94	1994				
Equivalence of Product Standards Certified By					
Product Approval Method	Method 1 Option A				
Date Submitted	05/21/2008				
Date Validated	06/05/2008				

Date Pending FBC Approval
Date Approved

07/09/2008
09/15/2008

Summary of Products		
FL #	Model, Number or Name	Description
10784.1	Premium Wood Door	6'-0" x 6'-8", Opaque, Single or Double Door, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1022.06.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1022.06.PDF Quality Assurance Contract Expiration Date 12/06/2010 Installation Instructions FL10784_R0_II_04-1022.06.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.2	Premium Wood Door	6'-0" x 6'-8", Opaque, Single or Double Door, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1022.05.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1022.05.PDF Quality Assurance Contract Expiration Date 12/06/2009 Installation Instructions FL10784_R0_II_04-1022.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.3	Premium Wood Door	6'-0" x 6'-8", Opaque, Single Door, with or without Side-lites, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +65/-70 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0714.05.pdf Quality Assurance Contract Expiration Date 08/23/2009 Installation Instructions FL10784_R0_II_04-0714.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.4	Premium Wood Door	6'-0" x 6'-8", Opaque, Single Door, with or without Side-lites, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +60/-70 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0714.04.pdf Quality Assurance Contract Expiration Date 08/23/2009 Installation Instructions FL10784_R0_II_04-0714.04.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.5	Premium Wood Door	6'-0" x 8'-0", Opaque, Single or Double Door, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1022.06.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1022.06.PDF Quality Assurance Contract Expiration Date 12/06/2010 Installation Instructions FL10784_R0_II_04-1022.06.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.6	Premium Wood Door	6'-0" x 8'-0", Opaque, Single or Double Door, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes		Certification Agency Certificate FL10784_R0_C_CAC_04-1022.05.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-

Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		1022.05.PDF Quality Assurance Contract Expiration Date 12/06/2009 Installation Instructions FL10784_R0_II_04-1022.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.7	Premium Wood Door	6'-0" x 8'-0", Opaque, Single Door, with or without Side-lites, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +55/-55 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0714.05.pdf Quality Assurance Contract Expiration Date 08/23/2009 Installation Instructions FL10784_R0_II_04-0714.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.8	Premium Wood Door	6'-0" x 8'-0", Opaque, Single Door, with or without Side-lites, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +55/-55 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0714.04.pdf Quality Assurance Contract Expiration Date 08/23/2009 Installation Instructions FL10784_R0_II_04-0714.04.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.9	Premium Wood Door	6'-0" x 6'-8", Full Lite or Divided Lite, Single or Double Door, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.06.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.06.PDF Quality Assurance Contract Expiration Date 09/20/2010 Installation Instructions FL10784_R0_II_04-1025.06.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.10	Premium Wood Door	6'-0" x 6'-8", Full Lite or Divided Lite, Single or Double Door, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0312.01.pdf Quality Assurance Contract Expiration Date 04/26/2009 Installation Instructions FL10784_R0_II_04-0312.01.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.11	Premium Wood Door	6'-0" x 6'-8", Full Lite or Divided Lite, Single Door, With or Without Side-lites, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +55/-55 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.05.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.05.PDF Quality Assurance Contract Expiration Date 09/20/2010 Installation Instructions FL10784_R0_II_04-1025.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:

10784.12	Premium Wood Door	6'-0" x 6'-8", Full Lite or Divided Lite, Single Door, With or Without Side-lites, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +55/-55 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.07.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.07.PDF Quality Assurance Contract Expiration Date 09/27/2010 Installation Instructions FL10784_R0_II_04-1025.07.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.13	Premium Wood Door	6'-0" x 8'-0", Full Lite or Divided Lite, Single or Double Door, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +32/-32 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.06.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.06.PDF Quality Assurance Contract Expiration Date 09/20/2010 Installation Instructions FL10784_R0_II_04-1025.06.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.14	Premium Wood Door	6'-0" x 8'-0", Full Lite or Divided Lite, Single or Double Door, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +32/-32 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-0312.01.pdf Quality Assurance Contract Expiration Date 04/26/2009 Installation Instructions FL10784_R0_II_04-0312.01.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.15	Premium Wood Door	6'-0" x 8'-0", Full Lite or Divided Lite, Single or Double Door, In-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.05.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.05.PDF Quality Assurance Contract Expiration Date 09/20/2010 Installation Instructions FL10784_R0_II_04-1025.05.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:
10784.16	Premium Wood Door	6'-0" x 8'-0", Full Lite or Divided Lite, Single or Double Door, Out-swing
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +47/-47 Other: Product must be installed per manufacturers instructions as stated in NOA.		Certification Agency Certificate FL10784_R0_C_CAC_04-1025.07.pdf FL10784_R0_C_CAC_2007 Compliance Letter 04-1025.07.PDF Quality Assurance Contract Expiration Date 09/27/2010 Installation Instructions FL10784_R0_II_04-1025.07.pdf Verified By: Miami-Dade BCCO - CER Created by Independent Third Party: Evaluation Reports Created by Independent Third Party:

[Back](#)
[Next](#)


Department of Community Affairs
Florida Building Code Online
Codes and Standards
2555 Shumard Oak Boulevard
Tallahassee, Florida 32399-2100
(850) 487-1824, Fax (850) 414-8436
© 2000-2010 The State of Florida. All rights reserved.

[Privacy Statement](#) | [Copyright Statement](#) | [Accessibility Statement](#) | [Plug-in Software](#) | [Customer Service Survey](#) | [Contact Us](#)

Product Approval Accepts:



Project Information


For: Doug Baggett
Lake City, FL
Phone: 407-235-4515

Notes: Load Calculation was obtained from an electronic copy of CAD drawing.

Design Information

Weather: Gainesville Regional AP, FL, US

Winter Design Conditions

Outside db 33 °F
Inside db 70 °F
Design TD 37 °F

Summer Design Conditions

Outside db 92 °F
Inside db 75 °F
Design TD 17 °F
Daily range M
Relative humidity 50 %
Moisture difference 48 gr/lb

Heating Summary

Structure 35039 Btuh
Ducts 9332 Btuh
Central vent (0 cfm) 0 Btuh
Humidification 0 Btuh
Piping 0 Btuh
Equipment load 44371 Btuh

Sensible Cooling Equipment Load Sizing

Structure 26918 Btuh
Ducts 11014 Btuh
Central vent (0 cfm) 0 Btuh
Blower 3413 Btuh
Use manufacturer's data y
Rate/swing multiplier 1.00
Equipment sensible load 41344 Btuh

Infiltration

Method Simplified
Construction quality Average
Fireplaces 1 (Average)

	Heating	Cooling
Area (ft²)	2619	2619
Volume (ft³)	26354	26354
Air changes/hour	0.37	0.16
Equiv. AVF (cfm)	161	70

Latent Cooling Equipment Load Sizing

Structure 3106 Btuh
Ducts 2929 Btuh
Central vent (0 cfm) 0 Btuh
Equipment latent load 6035 Btuh
Equipment total load 47379 Btuh
Req. total capacity at 0.80 SHR 4.3 ton

Heating Equipment Summary

Make Trane or Equivalent
Trade Split System Heat Pump
Model 4TWR3060A1
ARI ref no. 1106434
Efficiency 8 HSPF
Heating input 58000 Btuh @ 47°F
Heating output 28 °F
Temperature rise 1900 cfm
Actual air flow 0.043 cfm/Btuh
Air flow factor 0 in H2O
Static pressure
Space thermostat

Cooling Equipment Summary

Make Trane or Equivalent
Trade Split System Heat Pump
Cond 4TWR3060A1
Coil 4TEC3F60B1
ARI ref no. 1106434
Efficiency 10.8 EER, 13 SEER
Sensible cooling 45600 Btuh
Latent cooling 11400 Btuh
Total cooling 57000 Btuh
Actual air flow 1900 cfm
Air flow factor 0.050 cfm/Btuh
Static pressure 0 in H2O
Load sensible heat ratio 0.87

Bold/italic values have been manually overridden

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

Project Information

For: Doug Baggett
Lake City, FL
Phone: 407-235-4515

Design Conditions

Location:		Indoor:		Heating	Cooling
Gainesville Regional AP, FL, US		Indoor temperature (°F)		70	75
Elevation:	131 ft	Design TD (°F)		37	17
Latitude:	30°N	Relative humidity (%)		30	50
		Moisture difference (gr/lb)		10.4	48.5
Outdoor:		Infiltration:			
Dry bulb (°F)		Method		Simplified	
Daily range (°F)		Construction quality		Average	
Wet bulb (°F)		Fireplaces		1 (Average)	
Wind speed (mph)					

Construction descriptions

Construction descriptions	Or	Area ft²	U-value Btu/h/ft²·°F	Insul R ft²·°F/Btu/h	Htg HTM Btu/h/ft²	Loss Btu/h	Clg HTM Btu/h/ft²	Gain Btu/h
Walls 13A-4ocs: Blk wall, stucco ext, r-4 ext bd ins, 8" thk, 1/2" gypsum board int fnsh	ne	407	0.143	4.0	5.25	2135	2.60	1059
	se	436	0.143	4.0	5.25	2290	2.60	1136
	sw	403	0.143	4.0	5.25	2116	2.60	1049
	nw	353	0.143	4.0	5.25	1854	2.60	919
	all	1600	0.143	4.0	5.25	8395	2.60	4163

Partitions

(none)

Windows

10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 10.3 ft overhang (6.7 ft window ht, 0.5 ft sep.)	ne	80	0.350	0	12.8	1033	15.0	1208
10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 17 ft overhang (6.7 ft window ht, 4 ft sep.)	ne	80	0.350	0	12.8	1033	15.0	1208
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 2 ft overhang (4 ft window ht, 2 ft sep.)	ne	12	0.350	0	12.8	154	19.3	232
4B5-2fb: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 17 ft overhang (1.3 ft window ht, 2 ft sep.)	se	12	0.350	0	12.8	154	16.8	201
	all	24	0.350	0	12.8	308	18.1	433
10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 17.3 ft overhang (6.7 ft window ht, 0.5 ft sep.)	ne	16	0.350	0	12.8	200	24.2	377
	se	20	0.350	0	12.8	258	7.18	144
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 9.7 ft overhang (2 ft window ht, 0.5 ft sep.)	se	4	0.350	0	12.8	51	9.23	37

2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 0.5 ft overhang (4 ft window ht, 2 ft sep.)	se	8	0.350	0	12.8	103	20.2	162
10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 13 ft overhang (6.7 ft window ht, 0.5 ft sep.)	sw	40	0.350	0	12.8	516	7.18	288
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 9.7 ft overhang (6 ft window ht, 0.5 ft sep.)	sw	72	0.350	0	12.8	925	9.23	664
	nw	36	0.350	0	12.8	462	19.3	696
	all	108	0.350	0	12.8	1387	12.6	1360
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 13 ft overhang (6 ft window ht, 0.5 ft sep.)	sw	72	0.350	0	12.8	925	9.23	664
4B5-2fb: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 13 ft overhang (1.3 ft window ht, 0.5 ft sep.)	sw	8	0.350	0	12.8	100	11.6	91
10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 9.7 ft overhang (6.7 ft window ht, 0.5 ft sep.)	nw	20	0.350	0	12.8	258	15.0	302
10D-b: 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 9.7 ft overhang (6.7 ft window ht, 0.5 ft sep.)	nw	20	0.350	0	12.8	258	13.5	272
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 4.3 ft overhang (3 ft window ht, 0.5 ft sep.)	nw	9	0.350	0	12.8	116	19.3	174
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 6 ft overhang (3 ft window ht, 0.5 ft sep.)	nw	18	0.350	0	12.8	231	19.3	348
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 0.5 ft overhang (4 ft window ht, 0.5 ft sep.)	nw	12	0.350	0	12.8	154	19.3	232
2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; 2 glazing, clr low-e outr, argon gas, mtl /w brk frm mat, clr innr, 1/4" gap, 1/4" thk; NFRC rated (SHGC=0.27); 50% blinds 45°, medium; 50% outdoor insect screen; 12.7 ft overhang (4 ft window ht, 0.5 ft sep.)	nw	12	0.350	0	12.8	154	19.3	232

Doors

(none)

Ceilings

16B-19md: Attic ceiling, mtl roof mat, r-19 ceil ins, 5/8" gypsum board int fnsh	2619	0.049	19.0	1.80	4709	2.59	6788
--	------	-------	------	------	------	------	------

Floors

22A-cpl: Bg floor, light dry soil, carpet fir fnsh	231	0.989	0	36.3	8397	0	0
--	-----	-------	---	------	------	---	---

1	Room name	Entire House				Bonus			
2	Exposed wall	231.3 ft				32.3 ft			
3	Ceiling height	9.3 ft				9.3 ft			
4	Room dimensions	2618.7 ft²				156.7 ft²			
5	Room area					15.7 x 10.0 ft			
	Ty	Construction number	U-value (Btuh/ft²·F)	Or	HTM (Btuh/ft²)	Area (ft²) or perimeter (ft)	Load (Btuh)	Area (ft²) or perimeter (ft)	Load (Btuh)
					Heat Cool	Gross N/P/S	Heat Cool	Gross N/P/S	Heat Cool
6	W	13A-4ocs	0.143	ne	5.25 2.60	595 407	2135 1059	93 81	425 211
	G	10D-b	0.350	ne	12.85 15.03	80 0	1033 1208	0 0	0 0
	G	10D-b	0.350	ne	12.85 15.03	80 0	1033 1208	0 0	0 0
	G	2 glazing, clr low-e	0.350	ne	12.85 19.32	12 0	154 232	12 0	154 232
11	G	4B5-2fb	0.350	ne	12.85 24.16	16 0	200 377	0 0	0 0
	W	13A-4ocs	0.143	se	5.25 2.60	481 436	2290 1136	146 134	702 348
	G	10D-b	0.350	se	12.85 7.18	20 20	258 144	0 0	0 0
	G	2 glazing, clr low-e	0.350	se	12.85 9.23	4 4	51 37	0 0	0 0
	G	2 glazing, clr low-e	0.350	se	12.85 20.25	8 0	103 162	0 0	0 0
	G	2 glazing, clr low-e	0.350	se	12.85 16.78	12 4	154 201	12 4	154 201
	W	13A-4ocs	0.143	sw	5.25 2.60	595 403	2116 1049	62 62	325 161
	G	10D-b	0.350	sw	12.85 7.18	40 40	516 288	0 0	0 0
	G	2 glazing, clr low-e	0.350	sw	12.85 9.23	72 72	925 664	0 0	0 0
	G	2 glazing, clr low-e	0.350	sw	12.85 9.23	72 72	925 664	0 0	0 0
	G	4B5-2fb	0.350	sw	12.85 11.60	8 8	100 91	0 0	0 0
	W	13A-4ocs	0.143	nw	5.25 2.60	481 353	1854 919	0 0	0 0
	G	10D-b	0.350	nw	12.85 15.03	20 0	258 302	0 0	0 0
	G	10D-b	0.350	nw	12.85 15.03	20 0	258 302	0 0	0 0
	G	2 glazing, clr low-e	0.350	nw	12.85 19.32	9 0	116 174	0 0	0 0
	G	2 glazing, clr low-e	0.350	nw	12.85 19.32	18 0	231 348	0 0	0 0
	G	2 glazing, clr low-e	0.350	nw	12.85 19.32	12 0	154 232	0 0	0 0
	G	2 glazing, clr low-e	0.350	nw	12.85 19.32	12 0	154 232	0 0	0 0
	G	2 glazing, clr low-e	0.350	nw	12.85 19.32	36 0	462 696	0 0	0 0
	C	16B-19md	0.049	-	1.80 2.59	2619 2619	4709 6788	157 157	282 406
	F	22A-cpl	0.989	-	36.30 0.00	2619 231	8397 0	157 32	1174 0
6	c) AED excursion						2498		39
	Envelope loss/gain						28588 20982		3216 1598
12	a) Infiltration						6451 1316		902 184
	b) Room ventilation						0 0		0 0
13	Internal gains:	Occupants @ Appliances/other	230		4		920 3700	0	0 500
	Subtotal (lines 6 to 13)						35039 26918		4117 2282
	Less external load						0 0		0 0
	Less transfer						0 0		0 0
	Redistribution						0 0		0 0
14	Subtotal						35039 26918		4117 2282
15	Duct loads				27% 41%		9332 11014	27% 41%	1097 934
	Total room load						44371 37931		5214 3216
	Air required (cfm)						1900 1900		223 161

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1	Room name					Bed2					Bath2				
2	Exposed wall					22.3 ft					0 ft				
3	Ceiling height					9.3 ft					9.3 ft				
4	Room dimensions					1.0 x 228.4 ft					8.3 x 6.7 ft				
5	Room area					228.4 ft²					55.6 ft²				
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)		
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool	
6	W	13A-4ocs	0.143	ne	5.25	2.60	121	81	424	210	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	40	0	516	604	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0	
11	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	se	5.25	2.60	62	54	283	141	0	0	0	0	
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	8	0	103	162	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	sw	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	nw	5.25	2.60	25	25	130	65	0	0	0	0	
	G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	C	16B-19md	0.049	-	1.80	2.59	228	228	411	592	56	56	100	144	
	F	22A-cpl	0.989	-	36.30	0.00	228	22	811	0	56	0	0	0	
6	c) AED excursion														
	Envelope loss/gain														
12	a) Infiltration														
	b) Room ventilation														
13	Internal gains: Occupants @ 230 Appliances/other														
	Subtotal (lines 6 to 13)														
	Less external load														
	Less transfer														
	Redistribution														
14	Subtotal														
15	Duct loads														
	Total room load														
	Air required (cfm)														

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1	Room name					Hall					Bath3				
2	Exposed wall					9.3 ft 8.0 ft					7.3 ft				
3	Ceiling height					heat/cool					heat/cool				
4	Room dimensions					9.3 ft 1.0 x 79.1 ft					9.3 ft 8.0 x 9.0 ft				
5	Room area					79.1 ft²					72.0 ft²				
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)		
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool	
6	W	13A-4ocs	0.143	ne	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0	
11	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	se	5.25	2.60	47	26	139	69	68	64	337	167	
	G	10D-b	0.350	se	12.85	7.18	20	20	258	144	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	4	4	51	37	
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	sw	5.25	2.60	28	28	146	73	0	0	0	0	
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	nw	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	C	16B-19md	0.049	-	1.80	2.59	79	79	142	205	72	72	129	187	
	F	22A-cpl	0.989	-	36.30	0.00	79	8	290	0	72	7	266	0	
6	c) AED excursion									-14				-11	
	Envelope loss/gain									976	477			784	379
12	a) Infiltration									223	45			204	42
	b) Room ventilation									0	0			0	0
13	Internal gains: Occupants @ 230							0			0	0			0
	Appliances/other										0			0	
	Subtotal (lines 6 to 13)									1199	522			988	421
	Less external load									0	0			0	0
	Less transfer									0	0			0	0
	Redistribution									0	0			0	0
14	Subtotal									1199	522			988	421
15	Duct loads							27%	41%	319	214	27%	41%	263	172
	Total room load									1518	736			1252	593
	Air required (cfm)									65	37			54	30

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1	Room name					ah					Bed3					
2	Exposed wall					0 ft					27.7 ft					
3	Ceiling height					9.3 ft					9.3 ft					
4	Room dimensions					3.0 x 4.3 ft					1.0 x 212.8 ft					
5	Room area					13.0 ft²					212.8 ft²					
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)			
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool		
6	W	13A-4ocs	0.143	ne	5.25	2.60	0	0	0	0	0	0	0	0		
11	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0		
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0		
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0		
	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0		
	W	13A-4ocs	0.143	se	5.25	2.60	0	0	0	0	133	133	700	347		
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0		
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0		
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0		
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0		
	W	13A-4ocs	0.143	sw	5.25	2.60	0	0	0	0	124	88	462	229		
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0		
G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	36	36	462	332			
G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0			
G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0			
W	13A-4ocs	0.143	nw	5.25	2.60	0	0	0	0	0	0	0	0			
G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0			
G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0			
G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0			
G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0			
G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0			
G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0			
G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0			
C		16B-19md	0.049	-	1.80	2.59	13	13	23	34	213	213	383	552		
F		22A-cpl	0.989	-	36.30	0.00	13	0	0	0	213	28	1004	0		
6	c) AED excursion									-1				357		
	Envelope loss/gain									23	33			3011	1816	
12	a) Infiltration									0	0			772	157	
	b) Room ventilation									0	0			0	0	
13	Internal gains: Occupants @ 230 Appliances/other							0			0	1			230	0
	Subtotal (lines 6 to 13)									23	33			3782	2204	
	Less external load									0	0			0	0	
	Less transfer									0	0			0	0	
	Redistribution									0	0			0	0	
14	Subtotal									23	33			3782	2204	
15	Duct loads							27%	41%	6	13		27%	41%	1007	902
	Total room load									30	46			4789	3105	
	Air required (cfm)									1	2			205	156	

1	Room name				Living Rm				Kitchen					
2	Exposed wall				22.7 ft				0 ft					
3	Ceiling height				9.3 ft				9.3 ft					
4	Room dimensions				19.0 x 22.7 ft				13.7 x 22.7 ft					
5	Room area				430.7 ft²				309.8 ft²					
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)	
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool
6	W	13A-4ocs	0.143	ne	5.25	2.60	0	0	0	0	0	0	0	0
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0
11	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0
	W	13A-4ocs	0.143	se	5.25	2.60	0	0	0	0	0	0	0	0
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0
	W	13A-4ocs	0.143	sw	5.25	2.60	211	91	477	236	0	0	0	0
	G	10D-b	0.350	sw	12.85	7.18	40	40	516	288	0	0	0	0
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	72	72	925	664	0	0	0	0
	G	4B5-2fb	0.350	sw	12.85	11.60	8	8	100	91	0	0	0	0
	W	13A-4ocs	0.143	nw	5.25	2.60	0	0	0	0	0	0	0	0
	G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	C	16B-19md	0.049	-	1.80	2.59	431	431	774	1116	310	310	557	803
	F	22A-cpl	0.989	-	36.30	0.00	431	23	823	0	310	0	0	0
6	c) AED excursion									868				-68
	Envelope loss/gain								3615	3264			557	735
12	a) Infiltration								632	129			0	0
	b) Room ventilation								0	0			0	0
13	Internal gains:		Occupants @	230			0			0	0			0
			Appliances/other							900				1800
	Subtotal (lines 6 to 13)								4247	4293			557	2535
	Less external load								0	0			0	0
	Less transfer								0	0			0	0
	Redistribution								0	0			0	0
14	Subtotal								4247	4293			557	2535
15	Duct loads						27%	41%	1131	1757	27%	41%	148	1037
	Total room load								5378	6050			705	3573
	Air required (cfm)								230	303			30	179

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1	Room name					Dining 22.0 ft					Master Bed 41.0 ft				
2	Exposed wall					9.3 ft 1.0 x 302.0 ft heat/cool					9.3 ft 1.0 x 356.4 ft heat/cool				
3	Ceiling height					302.0 ft²					356.4 ft²				
4	Room dimensions														
5	Room area														
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)		
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool	
6	W	13A-4ocs	0.143	ne	5.25	2.60	205	109	570	283	161	121	635	315	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	40	0	516	604	
	G	10D-b	0.350	ne	12.85	15.03	80	0	1033	1208	0	0	0	0	
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0	
11	G	4B5-2fb	0.350	ne	12.85	24.16	16	0	200	377	0	0	0	0	
	W	13A-4ocs	0.143	se	5.25	2.60	0	0	0	0	25	25	130	65	
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	sw	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	nw	5.25	2.60	0	0	0	0	195	151	794	394	
	G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	20	0	258	272	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	12	0	154	232	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	12	0	154	232	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	C	16B-19md	0.049	-	1.80	2.59	302	302	543	783	356	356	641	924	
	F	22A-cpl	0.989	-	36.30	0.00	302	22	799	0	356	41	1488	0	
6	c) AED excursion									-72				237	
	Envelope loss/gain									3145	2579			4771	3273
12	a) Infiltration									613	125			1143	233
	b) Room ventilation									0	0			0	0
13	Internal gains: Occupants @ 230 Appliances/other							0		0	0	2		460	0
	Subtotal (lines 6 to 13)									3758	2704			5914	3967
	Less external load									0	0			0	0
	Less transfer									0	0			0	0
	Redistribution									0	0			0	0
14	Subtotal									3758	2704			5914	3967
15	Duct loads							27%	41%	1001	1106	27%	41%	1575	1623
	Total room load									4759	3810			7489	5590
	Air required (cfm)									204	191			321	280

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1	Room name					Wic1 0 ft					Wic2 0 ft				
2	Exposed wall					9.3 ft					9.3 ft				
3	Ceiling height					7.0					7.3				
4	Room dimensions					x 6.0 ft					x 6.0 ft				
5	Room area					42.0 ft²					44.0 ft²				
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)		
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool	
6	W	13A-4ocs	0.143	ne	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0	
11	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	se	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	sw	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0	
	G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0	
	W	13A-4ocs	0.143	nw	5.25	2.60	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	15.03	0	0	0	0	0	0	0	0	
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0	
	C	16B-19md	0.049	-	1.80	2.59	42	42	76	109	44	44	79	114	
	F	22A-cpl	0.989	-	36.30	0.00	42	0	0	0	44	0	0	0	
6	c) AED excursion									-3				-3	
	Envelope loss/gain									76	106			79	111
12	a) Infiltration									0	0			0	0
	b) Room ventilation									0	0			0	0
13	Internal gains: Occupants @ 230							0		0	0	0		0	0
	Appliances/other									0	0			0	0
	Subtotal (lines 6 to 13)									76	106			79	111
	Less external load									0	0			0	0
	Less transfer									0	0			0	0
	Redistribution									0	0			0	0
14	Subtotal									76	106			79	111
15	Duct loads							27%	41%	20	43	27%	41%	21	45
	Total room load									96	149			100	157
	Air required (cfm)									4	7			4	8

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

1 2 3 4 5	Room name Exposed wall Ceiling height Room dimensions Room area						Study 27.3 ft 9.3 ft 14.3 x 13.0 ft 186.3 ft²				MBath 20.7 ft 9.3 ft 1.0 x 129.9 ft 129.9 ft²			
	Ty	Construction number	U-value (Btuh/ft²·°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area (ft²) or perimeter (ft)		Load (Btuh)	
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool
6	W	13A-4ocs	0.143	ne	5.25	2.60	0	0	0	0	16	16	81	40
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0
	G	10D-b	0.350	ne	12.85	15.03	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	ne	12.85	19.32	0	0	0	0	0	0	0	0
11	G	4B5-2fb	0.350	ne	12.85	24.16	0	0	0	0	0	0	0	0
	W	13A-4ocs	0.143	se	5.25	2.60	0	0	0	0	0	0	0	0
	G	10D-b	0.350	se	12.85	7.18	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	9.23	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	20.25	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	se	12.85	16.78	0	0	0	0	0	0	0	0
	W	13A-4ocs	0.143	sw	5.25	2.60	121	85	446	221	50	50	260	129
	G	10D-b	0.350	sw	12.85	7.18	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	36	36	462	332	0	0	0	0
	G	2 glazing, clr low-e	0.350	sw	12.85	9.23	0	0	0	0	0	0	0	0
	G	4B5-2fb	0.350	sw	12.85	11.60	0	0	0	0	0	0	0	0
	W	13A-4ocs	0.143	nw	5.25	2.60	133	77	405	201	127	100	525	261
	G	10D-b	0.350	nw	12.85	15.03	20	0	258	302	0	0	0	0
	G	10D-b	0.350	nw	12.85	13.53	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	9	0	116	174
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	18	0	231	348
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	0	0	0	0	0	0	0	0
	G	2 glazing, clr low-e	0.350	nw	12.85	19.32	36	0	462	696	0	0	0	0
	C	16B-19md	0.049	-	1.80	2.59	186	186	335	483	130	130	234	337
	F	22A-cpl	0.989	-	36.30	0.00	186	27	992	0	130	21	750	0
6	c) AED excursion									930				298
	Envelope loss/gain								3361	3165			2198	1587
12	a) Infiltration								762	155			576	118
	b) Room ventilation								0	0			0	0
13	Internal gains: Occupants @ 230 Appliances/other						0			0	0			0
	Subtotal (lines 6 to 13)								4123	3820			2774	1704
	Less external load								0	0			0	0
	Less transfer								0	0			0	0
	Redistribution								0	0			0	0
14	Subtotal								4123	3820			2774	1704
15	Duct loads						27%	41%	1098	1563	27%	41%	739	697
	Total room load								5221	5383			3513	2402
	Air required (cfm)								224	270			150	120

Printout certified by ACCA to meet all requirements of Manual J 8th Ed.

29099

Richard T. Reep, M. Arch.

20 January 2011

Troy Crews
Building Inspector
Columbia County Building Department
Post Office Box 1529
Lake City, FL 32056-1529

via fax 386-758-2160

Re: Baggett Residence
Interior Footing Alternate

At the main residence, interior footings are to be placed along grid lines R1.3 and R2.3. The footings are shown on sheet S101.

✓
T.C.
1-20-11

The following footing may be used in lieu of the typical footing for this project:

Thickened slab, a minimum of 1' - 0" thick x 1' 4" wide, with tapered (45 degree) sides, containing two #5 rebar continuous along the length of the footing. This footing may be poured monolithically with the floor slab.

If you have any questions please feel free to contact me anytime.

Regards,




Richard T. Reep, AIA

Copy: Douglas J. Baggett, PBA

AR11827

ITW Building Components Group, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 0 278
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID:1U6L2327Z1003152525



Truss Fabricator: **Duley Truss**
Job Identification: **10700-HOUSE ACCT. BAGGETT RES (10700-HOUSE ACCT. BAGGETT RES**
Truss Count: **53**
Model Code: **Florida Building Code 2007 and 2009 Supplement**
Truss Criteria: **FBC2007Res/TPI-2002(STD)**
Engineering Software: **Alpine Software, Versions 9.01, 10.02.**
Structural Engineer of Record: **The identity of the structural EOR did not exist as of**
Address: **the seal date per section 61G15-31.003(5a) of the FAC**
Minimum Design Loads: **Roof - 37.0 PSF @ 1.25 Duration**
Floor - N/A
Wind - 120 MPH ASCE 7-05 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR2327

Douglas M. Fleming
-Truss Design Engineer-

1950 Marley Drive
Haines City, FL 33844

Details: -


#	Ref	Description	Drawing#	Date
1	61373--T1		10307109	11/03/10
2	61374--T2		10307110	11/03/10
3	61375--T3		10307105	11/03/10
4	61376--T3A		10307106	11/03/10
5	61377--T4		10307107	11/03/10
6	61378--T5		10307108	11/03/10
7	61379--T6A		10307141	11/03/10
8	61380--T6B		10307139	11/03/10
9	61381--T6C		10307138	11/03/10
10	61382--T6G		10307106	11/03/10
11	61383--T6		10307137	11/03/10
12	61384--T7		10307104	11/03/10
13	61385--T8		10307105	11/03/10
14	61386--T9		10307153	11/03/10
15	61387--T12		10307131	11/03/10
16	61388--T13		10307148	11/03/10
17	61389--T14		10307103	11/03/10
18	61390--T15		10307120	11/03/10
19	61391--T16		10307119	11/03/10
20	61392--T17		10307118	11/03/10
21	61393--T18		10307117	11/03/10
22	61394--T19		10307116	11/03/10
23	61395--SJ5		10307122	11/03/10
24	61396--EJ7		10307125	11/03/10
25	61397--SJ3		10307123	11/03/10
26	61398--SJ1		10307124	11/03/10
27	61399--EJ7A		10307149	11/03/10
28	61400--EJ7B		10307115	11/03/10
29	61401--EJ7C		10307152	11/03/10
30	61402--SJ5A		10307150	11/03/10
31	61403--SJ3A		10307147	11/03/10
32	61404--SJ1A		10307130	11/03/10
33	61405--SJ5B		10307112	11/03/10
34	61406--SJ3B		10307113	11/03/10
35	61407--SJ1B		10307114	11/03/10
36	61408--SJ6C		10307129	11/03/10

#	Ref	Description	Drawing#	Date
37	61409--SJ5C		10307132	11/03/10
38	61410--SJ4C		10307133	11/03/10
39	61411--SJ3C		10307134	11/03/10
40	61412--SJ2C		10307135	11/03/10
41	61413--SJ1C		10307136	11/03/10
42	61414--SJ5D		10307126	11/03/10
43	61415--SJ3D		10307127	11/03/10
44	61416--SJ1D		10307128	11/03/10
45	61417--EJ11E		10307146	11/03/10
46	61418--SJ10E		10307145	11/03/10
47	61419--SJ9E		10307144	11/03/10
48	61420--SJ8E		10307143	11/03/10
49	61421--SJ7E		10307142	11/03/10
50	61422--CJ7		10307121	11/03/10
51	61423--CJ7A		10307151	11/03/10
52	61424--CJ7B		10307111	11/03/10
53	61425--CJ11C		10307140	11/03/10



ITW Building Components Group, Inc.

1950 Marley Drive Haines City, FL 33844
Page 1 of 1 Document ID:1U6L2327Z1003152525



Truss Fabricator: **Duley Truss**
Job Identification: **10700-HOUSE ACCT. BAGGETT RES (10700-HOUSE ACCT. BAGGETT RES)**
Truss Count: **2**
Model Code: **Florida Building Code 2007 and 2009 Supplement**
Truss Criteria: **FBC2007Res/TPI-2002(STD)**
Engineering Software: **Alpine Software, Versions 9.01, 10.02.**
Structural Engineer of Record:
Address:
Minimum Design Loads: **Roof - 37.0 PSF @ 1.25 Duration**
Floor - N/A
Wind - 120 MPH ASCE 7-05 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR2327

Revised Trusses

#	Ref	Description	Drawing#	Date
1	61375--T3		10307105	11/03/10
2	61418--SJ10E		10307145	11/03/10

Seal Date: 11/03/2010

-Truss Design Engineer-
Douglas M. Fleming

1950 Marley Drive
Haines City, FL 33844

(10700-HOUSE ACCT. BAGGETT RES - T1)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Roof overhang supports 2.00 psf soffit load.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI(+/-)=0.18

Wind reactions based on MWFRS pressures.

#1 hip supports 7-0-0 jacks with no webs.

Left side jacks have 7-0-0 setback with 0-0-0 cant and 2-0-14 overhang. End jacks have 7-0-0 setback with 0-0-0 cant and 2-0-14 overhang. Right side jacks have 7-0-0 setback with 0-0-0 cant and 2-0-14 overhang.



R=1109 U=249 W=4"

Design Crit: FBC2007Res/TP1-2002 (STD)


PLT TYP. Wave	Scale = .375"/Ft.	
	REF	R2327 - 61373
ALPINE ITW Building Components Group Inc. Haines City, FL 33844 FL COA #0 278	DATE	11/03/10
	DRW	HCUSR2327 10307109
ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR THE TRUSS IN CONFORMANCE WITH THE DESIGN, ANY FABRICATING, HANDLING, SHIPPING, INSTALLING, OR ERECTING. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.	HC-ENG	SSB/DF
	SEQN-	338076
FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR THE TRUSS IN CONFORMANCE WITH THE DESIGN, ANY FABRICATING, HANDLING, SHIPPING, INSTALLING, OR ERECTING. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.	DUR.FAC.	1.25
	SPACING	24.0"
JREF - 1U6L2327Z10		

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.

Design Crit: FBC2007Res/TPI -2002(STD)
FT/RT=20%(0%)/10(0)

FL/-/2/-/-/R/-/-

No. 66848

STATE OF

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0 278

44441/03/2010

of this document for any purpose is the responsibility of the

...ING DESIGNER PER ANSI/TPI 1 S

FL COA #0 278

1124

2 COMPLETE TRUSSES REQUIRED

Nail Schedule: 0.128"x3.25", min. nails
Top Chord: 1 Row @ 12.00" o.c.
Bot Chord: 1 Row @ 11.25" o.c.
Webs : 1 Row @ 4" o.c.
Use equal spacing between rows and studs in each row to avoid splitting.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GGpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

End verticals not exposed to wind pressure.

Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



R=5654 U=1195 W=8"

U=1197 W=8"

PLT TYP. 20 Gauge HS Wave

Design Crit: FBC2007Res/TPI-2002(STD)

FL/-/2/-/-/R/-/
Scale = .125"/Ft.

QTY: 01 0923.23

FT/RT=20%(0%)/10(0)

Wave

PLT TYP. 20 Gauge HS

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WTCA (WOOD TRUSS COUNCIL OF AMERICA), 6300 NORTH LEE STREET, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

**** IMPORTANT **** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSSES IN CONFORMANCE WITH THIS DESIGN, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

CONNECTION PLATES ARE MADE TO CONFORM TO THE PROVISIONS OF AISC (NATIONAL DESIGN SPEC. BY AISC) AND TPI. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN.

PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, SHALL BE 1/4" THICK GALVALUME STEEL. ALL CONNECTION PLATES SHALL BE 20" WIDE.

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-1-2002 SEC. 3.

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0 278

Haines City, FL 33844
FL COA #0 278

100

(10700-HOUSE ACCT. BAGGETT RES - T3A)

Top chord 2x4 SP #2 Dense :T2, T3 2x6 SP #2:
Bot chord 2x6 SP #2
Webs 2x4 SP #3

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0
psf. lw=1.00 GCpl(+/-)=0.18

Wind reactions based on MWFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace all
flat TC @ 24" OC, all BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

2 COMPLETE TRUSSES REQUIRED

Nail Schedule: 0.128"x3.25", min. nails
Top Chord: 1 Row @12.00" o.c.
Bot Chord: 1 Row @12.00" o.c.
Webs : 1 Row @ 4" o.c.
Use equal spacing between rows and stagger nails
in each row to avoid splitting.

End verticals not exposed to wind pressure.

#1 hip supports 14-0-0 jacks with no webs.

WARNING: Furnish a copy of this DWG to the installation contractor.
Special care must be taken during handling, shipping and installation
of trusses. See "WARNING" note below.

3X4 ≡

2.5X4 ≡ 6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡


6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡

6X6 ≡ 1.5X4 ≡ 5X6 ≡



14-0-0 21-7-0 14-0-0
49-7-0 Over 2 Supports
R=4168 U=732 W=8"

PLT TYP. Wave

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

Scale = .125"/Ft.

FL/-2/-/-/R/-

TC LL 20.0 PSF

TC DL 7.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 37.0 PSF

DUR.FAC. 1.25

SPACING 24.0"

REF R2327- 61376

DATE 11/03/10


DRW HCUSR2327 10307106

HC-ENG SSB/DF

SEQN- 350764

FROM JRG

JREF- 1U6L2327Z10



Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	Webbs	2x4	SP	#3	

End verticals not exposed to wind pressure.

(B) Continuous lateral bracing equally spaced on member. Or 1x4 #3SRB SPF-S or better "T" brace. 80% length of web member. Attached with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.

120 mph wind, 15.42 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18


Wind reactions based on MWFRS pressures.

(A) Continuous lateral bracing equally spaced on member. Or 2x6 #3 or better "T" brace. 80% length of web member. Attached with 16d Box or Gun (0.135"x3.5", min.) nails @ 6" OC.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

Deflection meets L/360 live and L/240 total load.

MMFRS loads based on trusses located at least 15.42 ft. from roof edge.



PLT TYP. Wave


Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

FL/-/2/-/-/R/-/
Scale = .125"/Ft.

TC LL	20.0	PSF	REF	R2327-	61377
TC DL	7.0	PSF	DATE	11/03/10	
BC DL	10.0	PSF	DRW	HCUSR2327	10307107
BC LL	0.0	PSF	HC-ENG	SSB/DF	
TOT.LD.	37.0	PSF	SEQN-	338119	
DUR.FAC.	1.25		FROM	JRG	
SPACING	24.0"		JREF-	1U6L2327Z10	

*****WARNING***** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST AVAILABLE FABRICATION COMPONENT SAFETY INSTRUCTIONS. TRUSS PLATE INSTITUTION 218 0100 (800) 451-3132, ALEXANDRIA, VA 22314) AND WPCA (WOOD TRUSS COUNCIL OF AMERICA, 2000 ENTERPRISE AVE, MADISON, WISCONSIN 53703) FOR THE LATEST VERSIONS OF THESE INSTRUCTIONS. A PROPERLY INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT-FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR-ITW BCG, INC., SHAWNEE, KS. BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FABRICATING, SHIPPING, INSTALLING OR BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC., PER AFAPAs) AND TPI. ITW BCG HAS NO LIABILITY FOR ANY DAMAGE TO PERSONS OR PROPERTY ARISING OUT OF THE USE OF THESE DRAWINGS. ALL PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-1-2002 SECTION 3. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT OF THIS BUILDING. THE SCOPE OF THIS COMMENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANNEX(TPI 1 SEC. 2).



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

End verticals not exposed to wind pressure.

(A) Continuous lateral bracing equally spaced on member. Or 2x6 #3 or better "T" brace. 80% length of web member. Attached with 16d Box or Gun (0.135"x3.5" min.) nails @ 6" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.

MMFRS loads based on trusses located at least 16.26 ft. from roof edge.


120 mph wind, 16.26 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi(+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



22-0-0 5-7-0 22-0-0 49-7-0 Over 2 Supports

R=2072 U=87 W=8"
RL=233/-233

PLT TYP. Wave


Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

TC LL	20.0 PSF	FL/-/2/-/R/-	Scale = .125"/Ft.
TC DL	7.0 PSF	REF	R2327- 61378
BC DL	10.0 PSF	DATE	11/03/10
BC LL	0.0 PSF	DRW	HCUSR2327 10307108
TOT.LD.	37.0 PSF	HC-ENG	SSB/DF
DUR.FAC.	1.25	SEQN-	338113
SPACING	24.0"	FROM	JRG
		JREF-	1U6L2327Z10



WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND UNLOADING. REFER TO BC31 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INFORMATION), 100 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314 and WTC (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THIS DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE TRUSS COMPONENT DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPECIFICATION), 1000 W. WASHINGTON, CHICAGO, IL 60601 AND TPI (TRUSS PLATE INFORMATION), 100 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314. CONNECTOR PLATES ARE MADE OF 2018/16GA (W.H/SS/K) ASTM A653 GRADE 40/60 (W. K/H/SS) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1607. ANY INSPECTION OF PLATES FOLLOWED BY () SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



(10700-HOUSE ACCT. BAGGETT RES - T6A)

Top chord 2x4 SP #1
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpl(+/-)=0.18

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.

Wind reactions based on MMFRS pressures.

Right end vertical not exposed to wind pressure.

MMFRS loads based on trusses located at least 30.00 ft. from roof edge.



7-4-0 Over 2 Supports
R=271 U=0 W=8"
RL=75/-29
R=276 U=54

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave	Scale = .5"/Ft.	
	REF	R2327- 61379
	DATE	11/03/10
	DRW	HCUSR2327 10307141
	HC-ENG	SSB/DF
	SEQN-	341840
ALPINE ITW Building Components Group Inc. Haines City, FL 33844 FL COA #0 278	DUR.FAC.	1.25
	SPACING	24.0"
JREF- 1U6L2327Z10		



WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA, ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W.H/55/K) ASTM A653 GRADE 40/60 (W. K/H.S5) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-2. ANY INSPECTION OF PLATES FOLLOWED BY (I) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DESIGN INDICATES THE ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN. THE SIGNATURE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

(10700-HOUSE ACCT. BAGGETT RES - T6B)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

120 mph wind, 20.17 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpl(+/-)=0.18

End verticals not exposed to wind pressure.


Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.

MWFRS loads based on trusses located at least 20.17 ft. from roof edge.



8-7-8 10-0-8 17-5-0 Over 2 Supports 8-9-8 7-4-8


R=657 U=61
RL=77/-78

R=657 U=60

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .3125"/Ft.

 ALPINE Haines City, FL 33844 FL COA #0278	Douglas Fleming Professional Engineer No. 66848 State of Florida Professional Engineer 02/02/2010				TC LL	20.0 PSF	REF	R2327- 61380
					TC DL	7.0 PSF	DATE	11/03/10
					BC DL	10.0 PSF	DRW	HCUSR2327 10307139
					BC LL	0.0 PSF	HC-ENG	SSB/DF
					TOT.LD.	37.0 PSF	SEQN-	341835
					DUR.FAC.	1.25	FROM	JRG
					SPACING	24.0"	JREF-	1U6L2327Z10

(10700-HOUSE ACCT. BAGGETT RES - T6C)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #1
Webs 2x4 SP #3
:Rt Wedge 2x4 SP #3:

Left end vertical not exposed to wind pressure.

Bottom chord checked for 10.00 psf non-concurrent live load.

Shim all supports to solid bearing.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 Gcpl(+/-)=0.18

Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

MWFRS loads based on trusses located at least 30.00 ft. from roof edge.



10'-0-0 Over 2 Supports

R=377 U=36
RL=40/-103

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)


PLT TYP. Wave

FL/-2/-/-/R/-	Scale = .5"/Ft.
TC LL	20.0 PSF
TC DL	7.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	37.0 PSF
DUR.FAC.	1.25
SPACING	24.0"
REF	R2327- 61381
DATE	11/03/10
DRW	HCUSR2327 10307138
HC-ENG	SSB/DF
SEQN-	341797
FROM	JRG
JREF-	1U6L2327Z10



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE) 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WICA (WOOD TRUSS COUNCIL OF AMERICA, 6500 WOODHURST DRIVE, SUITE 100, FORT WORTH, TX 76116) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFAPA) AND TPI. CONNECTOR PLATES ARE MADE OF 2018/16GA (W. H/55/K) ASTM A653 GRADE 40/60 (W. K/H.SS) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWING 100A-Z. DISCONNECTOR PLATES SHALL BE PER ANNEALING P11-2002, SEC. 3.1. A SEAL ON THIS DRAWING INDICATES THE SUITABILITY AND USE OF THIS COMPONENT FOR THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



2 COMPLETE TRUSSES REQUIRED

Nail Schedule: 0.128"x3.25", min. nails
Top Chord: 1 Row @12.00" o.c.
Bot Chord: 1 Row @12.00" o.c.
Webs : 1 Row @ 4" o.c.

Use equal spacing between rows and stagger nails in each row to avoid splitting.

120 mph wind, 16.83 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.


Calculated horizontal deflection is 0.26" due to live load and 0.23" due to dead load.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

MWFRS loads based on trusses located at least 16.83 ft. from roof edge.

BUILDING DESIGNER SHALL EVALUATE AND APPROVE LOAD MAGNITUDES and LOCATIONS. THE TRUSS ENGINEER IS NOT RESPONSIBLE FOR LOAD MAGNITUDES AND LOCATIONS.




21-11-8
23-4-8
24-9-8
46-9-0 Over 2 Supports

R=2764 U=627 W=8"
RL=242/-258

Design Crit: $\text{FBC2007Res}/\text{TPI-2002(STD)}$
 $\text{FT}/\text{RT}=20\%(0\%)/10(0)$

PLT TYP. 20 Gauge HS, Wave

Scale = .125"/Ft.



ALPINE

ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0 278

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND ERECTING. REFER TO BC31 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 216 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WTC (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/A) ASTM A653 GRADE 40/80 (W, K/H, SS) GALV. STEEL. ANGLES PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1600. DRAWING INDICATES FACE OF TRUSS AND UNLESS FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THE DESIGN SHOWN. THE SUITABILITY AND PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BUILDING DESIGNER PER ANSII/TPI 1 SEC. 2.

No. 66848

STATE OF FLORIDA

PROFESSIONAL ENGINEER

11/03/2010

TC LL	20.0	PSF	REF	R2327- 61382
TC DL	7.0	PSF	DATE	11/03/10
BC DL	10.0	PSF	DRW	HCUSR2327 10307106
BC LL	0.0	PSF	HC-ENG	SSB/DF
TOT.LD.	37.0	PSF	SEQN-	341849
DUR.FAC.	1.25		FROM	JRG
SPACING	24.0"		JREF-	1U6L2327Z10

(10700-HOUSE ACCT. BAGGETT RES - T6)

Top chord 2x4 SP #2 Dense : T1 2x4 SP #1:
Bot chord 2x4 SP #2 Dense : B4 2x4 SP #1:
Webs 2x4 SP #3 : W2 2x4 SP #2 Dense:
: Rt Wedge 2x4 SP #3:

Calculated horizontal deflection is 0.31" due to live load and 0.27" due to dead load.

Bottom chord checked for 10.00 psf non-concurrent live load.

Calculated vertical deflection is 0.57" due to live load and 0.51" due to dead load at X = 30-11-2.

MMFRS loads based on trusses located at least 16.83 ft. from roof edge.


120 mph wind, 16.83 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 6.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 G_{CFI}(+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

WARNING: Furnish a copy of this DWG to the installation contractor. Special care must be taken during handling, shipping and installation of trusses. See "WARNING" note below.



R=1758 U=82 W=8"
RL=242/-258

PLT TYP. 20 Gauge HS, Wave
Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

Scale = .125"/Ft.

FL/-2/-/-R/-

QTY 5

9.01.02.0210.16

REF R2327- 61383

DATE 11/03/10

DRW HCUSR2327 10307137

HC-ENG SSB/DF

SEQN- 341779

TC LL 20.0 PSF

TC DL 7.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 37.0 PSF

DUR.FAC. 1.25

SPACING 24.0"

FROM JRG

JREF- 1U6L2327Z10

11/03/2010

FLORIDA


PROFESSIONAL ENGINEER

No. 66648

DOUGLAS FLEMING

11/03/2010

11/03/2010



(10700-HOUSE ACCT. BAGGETT RES - T7)

Top chord 2x4 SP #2 Dense
Bot chord 2x6 SP #2 Dense
Webs 2x4 SP #3

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located
anywhere in roof. CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0
psf. $I_w=1.00$ Gcpi (+/-)=0.18


End verticals not exposed to wind pressure.

Wind reactions based on MWFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace all
flat TC @ 24" OC, all BC @ 24" OC.

Girder supports 7-0-0 span to BC one face and 2-0-0 span to TC/BC
split opposite face.

Deflection meets L/360 live and L/240 total load.



R=1711 U=340 W=8"

R=1711 U=340 W=8"

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .375"/Ft.

FL/-2/-/-/R/-

QTY 1

9.07.02.0210.16

REF R2327- 61384

DATE 11/03/10

DRW HCUSR2327 10307104

HC-ENG SSB/DF

SEQN- 338322

TC LL 20.0 PSF

TC DL 7.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 37.0 PSF

DUR.FAC. 1.25

FROM JRG

JREF- 1U6L2327Z10

SPACING 24.0"

FL/RT=20%(0%)/10(0)

QTY 1

9.07.02.0210.16

REF R2327- 61384

DATE 11/03/10

DRW HCUSR2327 10307104

HC-ENG SSB/DF

SEQN- 338322

DUR.FAC. 1.25

FROM JRG

JREF- 1U6L2327Z10

SPACING 24.0"

FL/RT=20%(0%)/10(0)

QTY 1

9.07.02.0210.16

REF R2327- 61384

DATE 11/03/10

DRW HCUSR2327 10307104

HC-ENG SSB/DF

SEQN- 338322

DUR.FAC. 1.25

FROM JRG

JREF- 1U6L2327Z10

SPACING 24.0"

FL/RT=20%(0%)/10(0)

QTY 1

9.07.02.0210.16

REF R2327- 61384

DATE 11/03/10

DRW HCUSR2327 10307104


HC-ENG SSB/DF

SEQN- 338322

DUR.FAC. 1.25

FROM JRG

JREF- 1U6L2327Z10



Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi(+/-)=0.18

End verticals exposed to wind pressure. Deflection meets L/240 criteria for brittle and flexible wall coverings.


Wind reactions based on MWFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.

Roof overhang supports 2.00 psf soffit load.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.

Design Crit: $\text{FBC2007Res}/\text{TPI}-2002(\text{STD})$
 $\text{FT}/\text{RT}=20\%(0\%)/10(0)$

Scale = .3125"/Ft.

FL/-/2/-/-/R/-/-

9.01.02.0210/16 QTY:

FT/RT=20%(0%)/10(0)

Design Critic: R

PLT TYP.: Wave

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844

EL CO. #0 278

No. 66648

STATE OF FLORIDA

PROFESSIONAL ENGINEER

11/03/2010

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RC31 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 ENTERPRISE LANE, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THIS DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF IBC (NATIONAL DESIGN SPEC. BY AISC) AND TPI. ITW BCG, INC. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/K) ASTM A563 GRADE 40/60 (W. K/H/SS) GALV. STEEL. APPL-2 PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI1-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

TC LL	20.0	PSF	REF	R2327-	61385
TC DL	7.0	PSF	DATE	11/03/10	
BC DL	10.0	PSF	DRW	HCUSR2327	10307105
BC LL	0.0	PSF	HC-ENG	SSB/DF	
TOT. LD.	37.0	PSF	SEQN-	350769	
DUR. FAC.	1.25		FROM	JRG	
SPACING	24.0"		JREF-	1U6L2327Z10	

(10700-HOUSE ACCT. BAGGETT RES - T9)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

End verticals not exposed to wind pressure.

Roof overhang supports 2.00 psf soffit load.

#1 hip supports 7-0-0 jacks with no webs.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof. CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.

Left side jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang. End jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang. Right side jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang.



Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)


PLT TYP. Wave

TC LL	20.0 PSF	FL/-/2/-/-/R/-	Scale = .3125"/Ft.
TC DL	7.0 PSF		REF R2327- 61386
BC DL	10.0 PSF		DATE 11/03/10
BC LL	0.0 PSF		DRW HCUSR2327 10307153
TOT.LD.	37.0 PSF		HC-ENG SSB/DF
DUR.FAC.	1.25		SEQN- 338334
SPACING	24.0"		FROM JRG
			JREF- 1U6L2327Z10



WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST BUILDING COMPONENT SAFETY INFORMATION. PUBLISHED BY TPI. (TRUSS PLATE INSTITUTE) 2100 STATE ST., ALBUQUERQUE, NM 87105. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ITW CONNECTOR PLATES ARE MADE OF 2018/16GA (W/H/SS/K) ASTM A653 GRADE 40/60 (F 47/4/SS) GALV. STEEL. APPLICABLE INSPECTION OF PLATES FOLLOWED BY TPI SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. ANY INSPECTION OF PLATES FOLLOWED BY TPI SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



	Top	Bot	Dense
chord	2x4	SP #2	Dense
chord	2x4	SP #2	Dense
Webs	2x4	SP #3	Dense

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, lw=1.00 GCpi(+/-)=0.18


Roof overhang supports 2.00 psf soffit load.

Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.



R=735 U=159 W=4"
RL=113/-113

Design Crit: FBC2007Res/TPI-2002(STD)

FT/RT=20%(0%)/10(0)

Scale = .375"/Ft.

FL/-/2/-/-/R/-/-

✓16/01/01

9.01.02.0210

1010

 $FT/RT=20\%(0\%)/10(0)$

design of the re-

PLT TYP. Wave

WARNING THUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND REMOVING. REITER BESS (BUILDING CONSTRUCTION), INC., 10000 W. ALBERTA AVE., WESTMINSTER, CO. 80030. (303) 440-6300. LICENSEE NAME: WADSWORTH, INC. 53719. FOR THUSS PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

[illegible]

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844

FL COA #0 278

11/03/2010

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ITW Building Components Group Inc.
Haines City, FL 33844

FL COA #0 278

	Top	chord	2x4	SP	#2	Dense
	Bot	chord	2x4	SP	#2	Dense

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 Gcpi (+/-)=0.18


100% overall supply of 2.7 million

Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.



R=307 U=74 W=4"
RL=62/-62

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .5"/Ft.

TC LL	20.0 PSF	REF	R2327-	61388
TC DL	7.0 PSF	DATE	11/03/10	
BC DL	10.0 PSF	DRW	HCUSR2327	10307148
BC LL	0.0 PSF	HC-ENG	SSB/DF	
TOT. LD.	37.0 PSF	SEQN-	337932	
DUR. FAC.	1.25	FROM	JRG	
SPACING	24.0"	JREF-	1U6L2327Z10	

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO RCSTI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314, AND WTCA WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF THE TRUSS, AFTERNOON, 11/03/2010
DESIGNER'S OFFICE: 11/03/2010
CONTRACTOR PLATES ARE MADE OF 20/18/16GA (W/H/VSS/A) ASTM A953 GRADE 40/60 (W. K/H SS) GALV. STEEL, APPROXIMATELY 1600' LONG. ALL DIMENSIONS ARE IN FEET AND INCHES. SEE DRAWINGS FOR DETAILS. A SEAL ON THIS PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1600'. AN INSPECTION OF PLATES FOLLOWED BY (1.) SHALL BE PER ANNEX A3 OF TP11-2002 SEC 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

No. 66648

STATE OF FLORIDA
PROFESSIONAL ENGINEER

11/03/2010

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0 278

Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	Webbs	2x4	SP	#3	

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Roof overhang supports 2.00 psf soffit load.


Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.

MWFRS loads based on trusses located at least 7.50 ft. from roof edge.



R=177 U=28 W=4.186"
RL=50/-35

R=385 U=99 W=4.619"

Design Crit: FBC2007Res/TPI-2002(STD)
 $FT/RT=20\%(0\%)/10(0)$

PLT TYP. Wave

FL/-/2/-/-/R/-
Scale = .5"/Ft.

TC LL	20.0 PSF	REF R2327- 61389
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCUSR2327 10307103
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT.LD.	37.0 PSF	SEQN- 337935
DUR.FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

[illegible]


IMPORTANT - FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & ACTING OF TRUSSES.

CONNECTOR PLATES ARE MADE OF 20/18/18GA (W 1/2"X3/4" ASTM A653 GRADE 40/60 (W. K.H.S.S) GALV. STEEL APPL. PER DRAWINGS 160A-2.

PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2.

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3.

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT OF THIS CONSTRUCTION. THE REMAINING PORTION OF THIS CONTRACT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANNEX/TPI 1 SEC. 2.



ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0 278

Top chord	2x4	SP #2	Dense
Bot chord	2x4	SP #2	Dense
Webbs	2x4	SP #3	

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Roof overhang supports 2.00 psf soffit load.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 15.00 ft. from roof edge.

Wind reactions based on MWFRS pressures.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

Deflection meets L/360 live and L/240 total load.



R=1173 U=64 W=8"
RL=160/-160

R=1173 U=64 W=8"

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .25"/Ft.

WARNING THUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND REMOVAL. REFER TO THE BUILDING COMPONENTS HANDBOOK, PUBLISHED BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 530 N. DEARBORN AVE., CHICAGO, ILL. 60610, FOR THE LATEST RECOMMENDATIONS OF AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC. FOR THE PROPER USE OF THUSSES. THE THUSSES OF AMERICAN ENTERPRISE LANE, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. IF THE THUSSES ARE NOT USED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., THE USER SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE THUSSES OR OTHERS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID BEAMING.

TC 11	20.0 PSF
-------	----------

RFF R2327- 61390

**** IMPORTANT ****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TP1 - OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC. BY AISC) AND TPI. CONNECTOR PLATES ARE MADE OF 20X18X6GA (#14/SS/SA) ASTM A563 GRADE 40/60 (M. K/H.SS) GALV. STEEL PLATES. ALL DIMENSIONS ARE APPROXIMATE. DIMENSIONS OF TRUSS PER SECTION 1.0 SHALL BE AS SHOWN ON DRAWING. INSPECTION OF PLATES FOLLOWED BY (C) SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. A SEAL OF THE PROFESSIONAL ENGINEER MUST BE AFFIXED TO EACH SET OF DRAWINGS. THE PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPLETION SHALL BE ASSIGNED TO THE DESIGNER. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

TC	NI	7	0	DCE
1	1	1	1	1
2	2	2	2	2
3	3	3	3	3
4	4	4	4	4
5	5	5	5	5
6	6	6	6	6
7	7	7	7	7
8	8	8	8	8
9	9	9	9	9
10	10	10	10	10
11	11	11	11	11
12	12	12	12	12
13	13	13	13	13
14	14	14	14	14
15	15	15	15	15
16	16	16	16	16
17	17	17	17	17
18	18	18	18	18
19	19	19	19	19
20	20	20	20	20
21	21	21	21	21
22	22	22	22	22
23	23	23	23	23
24	24	24	24	24
25	25	25	25	25
26	26	26	26	26
27	27	27	27	27
28	28	28	28	28
29	29	29	29	29
30	30	30	30	30
31	31	31	31	31
32	32	32	32	32
33	33	33	33	33
34	34	34	34	34
35	35	35	35	35
36	36	36	36	36
37	37	37	37	37
38	38	38	38	38
39	39	39	39	39
40	40	40	40	40
41	41	41	41	41
42	42	42	42	42
43	43	43	43	43
44	44	44	44	44
45	45	45	45	45
46	46	46	46	46
47	47	47	47	47
48	48	48	48	48
49	49	49	49	49
50	50	50	50	50
51	51	51	51	51
52	52	52	52	52
53	53	53	53	53
54	54	54	54	54
55	55	55	55	55
56	56	56	56	56
57	57	57	57	57
58	58	58	58	58
59	59	59	59	59
60	60	60	60	60
61	61	61	61	61
62	62	62	62	62
63	63	63	63	63
64	64	64	64	64
65	65	65	65	65
66	66	66	66	66
67	67	67	67	67
68	68	68	68	68
69	69	69	69	69
70	70	70	70	70
71	71	71	71	71
72	72	72	72	72
73	73	73	73	73
74	74	74	74	74
75	75	75	75	75
76	76	76	76	76
77	77	77	77	77
78	78	78	78	78
79	79	79	79	79
80	80	80	80	80
81	81	81	81	81
82	82	82	82	82
83	83	83	83	83
84	84	84	84	84
85	85	85	85	85
86	86	86	86	86
87	87	87	87	87

DATE 11/03/10

IMPORTANT **FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BCG, INC. SO THAT THEY ARE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE TRUSS CONTRACTOR. THE TRUSS CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRUSS DESIGN, THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

10 DL 7.0 F3F

DATE 11/03/10

**** IMPORTANT ****FURNISH A COPY OF THE INSTALLATION CONTRACTOR, ITW BCG, INC., SPECIFICATIONS TO BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (ASTM DESIGN 40760 (W. K/FH.SS) AND TPI). CONNECTOR PLATES ARE MADE OF 20X18X1/16GA (W.H/S&S/A) ASTM A593 GRADE 50/60 (W. K/FH.SS) STEEL. PLATES TO EACH FACE OF THISS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS INDICATE. DRILLING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY FOR THE TRUSS COMBINATION SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SECT. 2.

BC DL 10.0 PSF

DRW HCUSR2327 103

[illegible]

BC LL 0.0 PSF

HC-ENG SSB/DF

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC NATIONAL DESIGN SPEC. BY AISC AND TPI. CONNECTOR PLATES ARE MADE OF 2010/146A (W.H./SS/A) ASTM A563 GRADE 40/60 (W. K.H./SS) GALV. STEEL. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS. A SEAL OF ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS CONSTRUCTION. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE DESIGNER PER ANSI/TPI 1 SEC. 2.

TOT.LD. 37.0 PSF

SEON- 337877

PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS. AN INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC. 3. A SEAL OR DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

DUPLICATE 1 OF

1000

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

DUR., FAC., 1.25


- ROM JRG

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, lw=1.00 GCpi(+/-)=0.18

Wind reactions based on MWFRS pressures.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

Deflection meets L/360 live and L/240 total load.



R=1154 U=61 W=8"
RL=157/-157

Design Crit: FBC2007Res/TPI-2002(STD)
 $FT/RT=20\%(0\%)/10(0)$

Scale = .25"/Ft.

FL/-/2/-/-/R/-/-

0/16 QTY:

10(0)

 $FT/RT=2$

11

PLOT TYP. Wave

WARNING THUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BGCI'S THUSSES (COMPONENT SAFETY INFORMATION), PUBLISHED BY THE THUSSA PULP INSTITUTION, 210 ENTERPRISE LANE, SUITE 312, ALEXANDRIA, VIRGINIA 22304, FOR THUSSES CONSTRUCTION, COMPLETION, AND MAINTENANCE. THUSSES MUST BE PROPERLY ATTACHED TO THE CHORDS. OTHERWISE, INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR WITH THE EGG. INCE. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. BY AFAPA) AND TPI, IT IS UNDERSTOOD THAT THIS DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISC (NATIONAL DESIGN SPEC.) STEEL TRUSS CONNECTIONS, PER TPI DRAWINGS 160A, 160B, 160C, 160D, 160E, 160F, 160G, 160H, 160I, 160J, 160K, 160L, 160M, 160N, 160O, 160P, 160Q, 160R, 160S, 160T, 160U, 160V, 160W, 160X, 160Y, 160Z, 160AA, 160AB, 160AC, 160AD, 160AE, 160AF, 160AG, 160AH, 160AI, 160AJ, 160AK, 160AL, 160AM, 160AN, 160AO, 160AP, 160AQ, 160AR, 160AS, 160AT, 160AU, 160AV, 160AW, 160AX, 160AY, 160AZ, 160BA, 160BB, 160BC, 160BD, 160BE, 160BF, 160BG, 160BH, 160BI, 160BJ, 160BK, 160BL, 160BM, 160BN, 160BO, 160BP, 160BQ, 160BR, 160BS, 160BT, 160BU, 160BV, 160BW, 160BX, 160BY, 160BZ, 160CA, 160CB, 160CC, 160CD, 160CE, 160CF, 160CG, 160CH, 160CI, 160CJ, 160CK, 160CL, 160CM, 160CN, 160CO, 160CP, 160CQ, 160CR, 160CS, 160CT, 160CU, 160CV, 160CW, 160CX, 160CY, 160CZ, 160DA, 160DB, 160DC, 160DD, 160DE, 160DF, 160DG, 160DH, 160DI, 160DJ, 160DK, 160DL, 160DM, 160DN, 160DO, 160DP, 160DQ, 160DR, 160DS, 160DT, 160DU, 160DV, 160DW, 160DX, 160DY, 160DZ, 160EA, 160EB, 160EC, 160ED, 160EE, 160EF, 160EG, 160EH, 160EI, 160EJ, 160EK, 160EL, 160EM, 160EN, 160EO, 160EP, 160EQ, 160ER, 160ES, 160ET, 160EU, 160EV, 160EW, 160EX, 160EY, 160EZ, 160FA, 160FB, 160FC, 160FD, 160FE, 160FF, 160FG, 160FH, 160FI, 160FJ, 160FK, 160FL, 160FM, 160FN, 160FO, 160FP, 160FQ, 160FR, 160FS, 160FT, 160FU, 160FV, 160FW, 160FX, 160FY, 160FZ, 160GA, 160GB, 160GC, 160GD, 160GE, 160GF, 160GG, 160GH, 160GI, 160GJ, 160GK, 160GL, 160GM, 160GN, 160GO, 160GP, 160GQ, 160GR, 160GS, 160GT, 160GU, 160GV, 160GW, 160GX, 160GY, 160GZ, 160HA, 160HB, 160HC, 160HD, 160HE, 160HF, 160HG, 160HH, 160HI, 160HJ, 160HK, 160HL, 160HM, 160HN, 160HO, 160HP, 160HQ, 160HR, 160HS, 160HT, 160HU, 160HV, 160HW, 160HX, 160HY, 160HZ, 160IA, 160IB, 160IC, 160ID, 160IE, 160IF, 160IG, 160IH, 160II, 160IJ, 160IK, 160IL, 160IM, 160IN, 160IO, 160IP, 160IQ, 160IR, 160IS, 160IT, 160IU, 160IV, 160IW, 160IX, 160IY, 160IZ, 160JA, 160JB, 160JC, 160JD, 160JE, 160JF, 160JG, 160JH, 160JI, 160JJ, 160JK, 160JL, 160JM, 160JN, 160JO, 160JP, 160JQ, 160JR, 160JS, 160JT, 160JU, 160JV, 160JW, 160JX, 160JY, 160JZ, 160KA, 160KB, 160KC, 160KD, 160KE, 160KF, 160KG, 160KH, 160KI, 160KJ, 160KK, 160KL, 160KM, 160KN, 160KO, 160KP, 160KQ, 160KR, 160KS, 160KT, 160KU, 160KV, 160KW, 160KX, 160KY, 160KZ, 160LA, 160LB, 160LC, 160LD, 160LE, 160LF, 160LG, 160LH, 160LI, 160LJ, 160LK, 160LL, 160LM, 160LN, 160LO, 160LP, 160LQ, 160LR, 160LS, 160LT, 160LU, 160LV, 160LW, 160LX, 160LY, 160LZ, 160MA, 160MB, 160MC, 160MD, 160ME, 160MF, 160MG, 160MH, 160MI, 160MJ, 160MK, 160ML, 160MM, 160MN, 160MO, 160MP, 160MQ, 160MR, 160MS, 160MT, 160MU, 160MV, 160MW, 160MX, 160MY, 160MZ, 160NA, 160NB, 160NC, 160ND, 160NE, 160NF, 160NG, 160NH, 160NI, 160NJ, 160NK, 160NL, 160NM, 160NN, 160NO, 160NP, 160NQ, 160NR, 160NS, 160NT, 160NU, 160NV, 160NW, 160NX, 160NY, 160NZ, 160OA, 160OB, 160OC, 160OD, 160OE, 160OF, 160OG, 160OH, 160OI, 160OJ, 160OK, 160OL, 160OM, 160ON, 160OO, 160OP, 160OQ, 160OR, 160OS, 160OT, 160OU, 160OV, 160OW, 160OX, 160OY, 160OZ, 160PA, 160PB, 160PC, 160PD, 160PE, 160PF, 160PG, 160PH, 160PI, 160PJ, 160PK, 160PL, 160PM, 160PN, 160PO, 160PP, 160PQ, 160PR, 160PS, 160PT, 160PU, 160PV, 160PW, 160PX, 160PY, 160PZ, 160QA, 160QB, 160QC, 160QD, 160QE, 160QF, 160QG, 160QH, 160QI, 160QJ, 160QK, 160QL, 160QM, 160QN, 160QO, 160QP, 160QQ, 160QR, 160QS, 160QT, 160QU, 160QV, 160QW, 160QX, 160QY, 160QZ, 160RA, 160RB, 160RC, 160RD, 160RE, 160RF, 160RG, 160RH, 160RI, 160RJ, 160RK, 160RL, 160RM, 160RN, 160RO, 160RP, 160RQ, 160RR, 160RS, 160RT, 160RU, 160RV, 160RW, 160RX, 160RY, 160RZ, 160SA, 160SB, 160SC, 160SD, 160SE, 160SF, 160SG, 160SH, 160SI, 160SJ, 160SK, 160SL, 160SM, 160SN, 160SO, 160SP, 160SQ, 160SR, 160SS, 160ST, 160SU, 160SV, 160SW, 160SX, 160SY, 160SZ, 160TA, 160TB, 160TC, 160TD, 160TE, 160TF, 160TG, 160TH, 160TI, 160TJ, 160TK, 160TL, 160TM, 160TN, 160TO, 160TP, 160TQ, 160TR, 160TS, 160TT, 160TU, 160TV, 160TW, 160TX, 160TY, 160TZ, 160UA, 160UB, 160UC, 160UD, 160UE, 160UF, 160UG, 160UH, 160UI, 160UJ, 160UK, 160UL, 160UM, 160UN, 160UO, 160UP, 160UQ, 160UR, 160US, 160UT, 160UU, 160UV, 160UW, 160UX, 160UY, 160UZ, 160VA, 160VB, 160VC, 160VD, 160VE, 160VF, 160VG, 160VH, 160VI, 160VJ, 160VK, 160VL, 160VM, 160VN, 160VO, 160VP, 160VQ, 160VR, 160VS, 160VT, 160VU, 160VV, 160VW, 160VX, 160VY, 160VZ, 160WA, 160WB, 160WC, 160WD, 160WE, 160WF, 160WG, 160WH, 160WI, 160WJ, 160WK, 160WL, 160WM, 160WN, 160WO, 160WP, 160WQ, 160WR, 160WS, 160WT, 160WU, 160WV, 160WW, 160WX, 160WY, 160WZ, 160XA, 160XB, 160XC, 160XD, 160XE, 160XF, 160XG, 160XH, 160XI, 160XJ, 160XK, 160XL, 160XM, 160XN, 160XO, 160XP, 160XQ, 160XR, 160XS, 160XT, 160XU, 160XV, 160XW, 1

REF	R2327-	61391
DATE	11/03/10	
IRW	HCUSR2327	10307119
IC-ENG	SSB/DF	
EQN-	337883	
FROM	JRG	
REF-	1U6L2327Z10	

C LL	20.0 P
C DL	7.0 P
C DL	10.0 P
C LL	0.0 P
OT.LD.	37.0 P
UR.FAC.	1.25
PACING	24.0"

66648
STATE OF FLORIDA
NAT ENGINEER
03/03/2010

INSTALLING AND BRACING.
SS PLATE INSTITUTE, 218
L OF AMERICA, 6300
THESE FUNCTIONS. UNLESS
BOTTOM CHORD SHALL HAVE

ITW BCG, INC. SHALL NOT
IN CONFORMANCE WITH
) AND TPI.
ITW BCG
STEEL. APPLIC
DRAWINGS 160A-
A SEAL ON THIS
FOR THE TRUSS COMPONENT
E RESPONSIBILITY OF THE

MAN, HANDLING, PUBLISHED IN WTCFA (WOOD TECHNIQUES PRIOR TO THE STRUCTURAL INSTALLATION C FAILURE TO BUILDING OF TRACING OF TRACIAL DESIGN S A653 GRADE 41 ON THIS L ANNEX A3 OF TP RESPONSIBILITY FOR ANY BUILDING

THE EXTREME CARE COMPONENT SAFETY ALEXANDRIA, V (1 53719) FOR DED SHALL HAVE P CEILING.

..WARNING.. TO
REFER TO BGCI
NORTH LEE STREET
ENTERPRISE LAW
OTHERWISE INDIC
A PROPERLY ATT
..IMPORTANT
BE RESPONSIBLE
TPI, OR FABRICA
DESIGN CONFORM
CONNECTOR PLATE
PLATES TO EACH
ANY INSPECTION
DRAWING INDICA
DESIGN SHOWN.
BUILDING DESIGN


ALPINE
ITW Building Components
Haines City, FL 33894
F1 COA #0 2000

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MWFRS loads based on trusses located at least 7.50 ft. from roof edge.




R=1125 U=238 W=8"
RL=139/-139

R=1125 U=238 W=8"

PLT TYP. Wave

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

Scale = .25"/Ft.



ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0 278

WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 619 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA 22314, AND WTCA (WOOD TRUSS COUNCIL OF AMERICA), ENTERPRISE LANE, MADISON, WI 53719, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THIS TPI; OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AF&PA) AND TPI.

CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/K) ASTM A653 GRADE 40/60 (W/ K/H/SS) GALV. STEEL. ALL PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1002-1007.

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC 3. A SEAL ON THE DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

No. 66848

STATE OF FLORIDA

PROFESSIONAL ENGINEER

DATE OF EXPIRATION: 03/20/10

REF	R2327- 61392	TC LL	20.0 PSF	TC LL	20.0 PSF
DATE	11/03/10	TC DL	7.0 PSF	TC DL	7.0 PSF
DRW	HCUSR2327 10307118	BC DL	10.0 PSF	BC DL	10.0 PSF
HC-ENG	SSB/DF	BC LL	0.0 PSF	BC LL	0.0 PSF
SEQN-	337892	TOT.LD.	37.0 PSF	TOT.LD.	37.0 PSF
FROM	JRG	DUR.FAC.	1.25	DUR.FAC.	1.25
JREF-	1U6L2327Z10	SPACING	24.0"	SPACING	24.0"

	Top	Bot	Dense
chord	2x4	SP #2	Dense
chord	2x4	SP #2	Dense
Webs	2x4	SP #3	Dense

Roof overhang supports 2.00 psf soffit load.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.


MMWFRS loads based on trusses located at least 7.50 ft. from roof edge.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, 'CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.




Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

FL/-/2/-/-/R/-		Scale = .25"/Ft.
TC LL	20.0 PSF	REF R2327- 61393
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCUSR2327 10307117
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT. LD.	37.0 PSF	SEQN- 337899
DUR. FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST AVAILABLE BUILDING COMPONENT SAFETY INFORMATION. PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 S. STATE ST., STE. 100, CHICAGO, IL 60606. (312) 467-1000. FOR THE NATIONAL TRUSS ASSOCIATION, 1000 N. WILSON AVE., ENTERPRISE, ALA. 36035. (205) 337-1919. FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS, UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BOG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. BY APAPA) AND TPI. NO DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., 1989), AISC STEEL EDITION 1989, AISC PLATES TO EACH FACE OF FLOORS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWING INDICATES. ACCEPTANCE OF TPI-2002 SEC. 3. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC. 3. DRIVING INDICATES. PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENTS OF THIS CONSENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANNEX/TPI 1 SEC. 2.



	Top	chord	2x4	SP	#2	Dense	:T2	2x6	SP	#2	Dense:
Bot		chord	2x4	SP	#1						
		Web	2x4	SP	#3						

Roof overhang supports 2.00 psf soffit load.

In lieu of structural panels or rigid ceiling use purlins to brace all flat TC @ 24" OC, all BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpl (+/-)=0.18

Wind reactions based on MWFRS pressures.

#1 hip supports 7-0-0 jacks with no webs.

Left side jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang. End jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang. Right side jacks have 7-0-0 setback with 0-0-0 cant and 2-1-6 overhang.



PLT TYP. 20 Gauge HS, Wave

Design Crit: FBC2007Res/TPI-2002(STD)

FT=20%(0%)/10(0) 9.01.02.0210.16 QTY 2

Scale = .25"/Ft.

ALPINE

ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0 278

FLORIDA PROFESSIONAL ENGINEER
STATE OF
No. 66648

*****WARNING***** TRUSSES REQUIRE EXTREME CARE IN FABRICATION. HANDLING, SHIPPING, INSTALLING AND UNLOADING REFER TO BCST (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314) AND WTCA (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, WAUWATON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

*****IMPORTANT***** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THIS DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THIS DESIGN CONFORMS TO THE REQUIREMENTS OF THE DESIGN SPECIFICATIONS BY ATAPA AND TPI. ITW BCG, INC. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NOS (NATIONAL DESIGN SPEC.) AND THE REQUIREMENTS OF THE CONNECTOR PLATES MADE OF 20/18/16GA. (W.I./SS/CA) ASTM A653 GRADE 40/60 (W. K/H/SS) GALV. STEEL. APPROXIMATELY 1/8" THICK. PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1800. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX 43 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

(10700-HOUSE ACCT. BAGGETT RES - SJ5)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.


In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpl(+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.



Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave	Scale = .5" /Ft.
TC LL	20.0 PSF
TC DL	7.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	37.0 PSF
DUR.FAC.	1.25
SPACING	24.0"
REF	R2327- 61395
DATE	11/03/10
DRW	HCUSR2327 10307122
HC-ENG	SSB/DF
SEQN-	338040
FROM	JRG
JREF-	1U6L2327210

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WTCA (WOOD TRUSS COUNCIL OF AMERICA), 6200 EXETER AVE, SUITE 100, WILSON, NC 27157 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TRUSSES SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/K) ASTM A653 GRADE 40/60 (W. K/H/SS) GALV. STEEL. ALL PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100% INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PERFORMED AS REQUIRED BY THE DESIGN. THE TRUSS COMPONENT SHALL BE MANUFACTURED TO THE DESIGNER'S REQUIREMENTS. THE DESIGNER SHALL BE RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0278

(10700-HOUSE ACCT. BAGGETT RES - EJ7)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MWFRS loads based on trusses located at least 7.50 ft. from roof edge.



2'-0'-0" → 7'-0'-0" Over 3 Supports →
R=412 U=78 W=8"
RL=123/-52

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .5" / Ft.



WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND DETECTING. REFER TO BEST PRACTICES (BPP) FOR TRUSS MANUFACTURING AND INSTALLATION. TRUSS PLATE INSTALLATION SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. TRUSSES SHALL BE DESIGNED TO MEET THE REQUIREMENTS OF THE DESIGN CRITERIA. TRUSSES SHALL BE DESIGNED TO MEET THE REQUIREMENTS OF THE DESIGN CRITERIA. TRUSSES SHALL BE DESIGNED TO MEET THE REQUIREMENTS OF THE DESIGN CRITERIA.

IMPORTANT: FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN CRITERIA SHALL BE THE RESPONSIBILITY OF THE INSTALLATION CONTRACTOR. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

nW Building Components Group Inc.
Haines City, FL 33844
FL COA #0278

TC LL	20.0 PSF	REF	R2327 - 61396
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307125
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT.LD.	37.0 PSF	SEQN-	338037
DUR.FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

(10700-HOUSE ACCT. BAGGETT RES - SJ3)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.


In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCpl(+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.



R=291 U=73 W=8"
RL=66/-36

Design Crit: FBC2007Res/TPI-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

Scale = .5" / Ft.

FL/-2/-/-R/-

REF R2327- 61397

DATE 11/03/10

DRW HCUSR2327 10307123

HC-ENG SSB/DF

SEQN- 338043


FROM JRG

JREF- 1U6L2327Z10



WARNING** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST PRACTICES FOR TRUSS FABRICATION (TPI) (TRUSS PLATE INSTITUTE) 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.

IMPORTANT** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN; ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. STEEL TRUSSES OR PLATES ARE MADE TO ORDER. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI1-2002 SEC.3. (2) SHALL BE PER ANNEX A3 OF TPI1-2002 SEC.3. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.




120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi (+/-)=0.18

Wind reactions based on MWFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.



2-0-0
1-0-0 over 3 Supports

R=334 U=140 W=8"
RL=38/-28

Design Crit: FBC2007Res/TPI-2002(STD)

PLT TYP: Wave

FI /- /2 /- /- /R /-

Scale = 5"/Ft

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCIS' TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. (1987) FOR MORE INFORMATION. TRUSS PLATE INSTITUTION, 2100
ENTERPRISE LANE, SUITE 312, ALEXANDRIA, VA 22304 AND PCA (WOOD PRESERVATION COUNCIL OF AMERICA), 650
OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED BRIDG CELL.

IMPORTANT PUBLISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BCS, INC., SUMMIT, ILL. BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI-1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI-1. IT IS NOT NECESSARY TO OBTAIN APPROVAL OF THIS DESIGN FROM ANY OTHER AUTHORITY.

PLATES TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN. POSITION PER ANNEC 160A. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT OF THIS BUILDING. SEE NOTE 1 FOR THE LOCATION OF THIS CORNER FOR ANY BUILDING. SEE THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANNEC/TPI-1 SEC. 2.



ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0278

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt. ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCpi(+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.



2-0-0
7-0-0 Over 3 Supports
R=405 U=124 W=4"
RL=75

PLT TYP. Wave

Design Crit: FBC2007Res/TPI-2002(STD)

FT/RT=20%(0%)/10(0)

9.01.02.0210.16

Scale = .5"/Ft.

FL/-/2/-/-/R/-

TC LL 20.0 PSF

TC DL 7.0 PSF

BC DL 10.0 PSF

BC LL 0.0 PSF

TOT.LD. 37.0 PSF

DUR.FAC. 1.25

SPACING 24.0"

REF R2327- 61400

DATE 11/03/10

DRW HCUSR2327 10307115

HC-ENG SSB/DF

SEQN- 337963

FROM JRG

JREF- 1U6L2327Z10

ITW Building Components Group Inc.
Haines City, FL 33844
FL COA #0 278



Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

Calculated horizontal deflection is 0.18" due to live load and 0.10" due to dead load.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $W=1.00$ GCPI (+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

MMFRS loads based on trusses located at least 15.00 ft. from roof edge.



7-0-0 Over 3 Supports
R=338 U=0 W=3.5
RL=143/-99

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC01 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 2108 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA), 6308 ENTERPRISE LANE, JARVISON, MI, 48735 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. ALL TRUSSES MUST BE PROPERLY ATTACHED TO THE BUILDING STRUCTURE AND SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORDS TO A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT: FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN, ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THIS DESIGN, OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/PPI) AND TPI.

ALL TRUSSES ARE MADE OF 20/18/16GA (W/H/S/S) ASTM A653 GRADE 40/60 (W, K/H/S) GALV. STEEL. ALL TRUSSES ARE TO BE INSPECTED BY A QUALIFIED INSPECTOR PRIOR TO INSTALLATION. THE INSPECTOR SHALL BE RESPONSIBLE FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0 278



TC LL	20.0 PSF	REF R2327- 61401
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCURS2327 10307152
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT. LD.	37.0 PSF	SEON- 338362
DUR. FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

Roof overhang supports 2.00 psf soffit load.


Bottom chord checked for 10.00 psf non-concurrent live load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, lw=1.00 GCpl(+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.



1.5X4 III
5'-0-0 Over 3 Supports
R=335 U=32 W=8"
RL=94/-44

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSP (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TP1 (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA), 6108 EXETER STREET, MADISON, WI, 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING REPAIRS OR MODIFICATIONS. ALL TRUSSES AND JOISTS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BCS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THIS DESIGN, OR FABRICATING, HANDLING, SHIPPING, INSTALLING OR BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AF&PA) AND TP1, CONNECTOR PLATES ARE MADE OF 20/18/16GA (N/A/SS) ASTM A653 GRADE 40/60 (N/A/SS) GALV. STEEL. ALL TRUSSES SHALL BE STATIONED PER DESIGN. THE DESIGNER'S ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0278




FL - /2/- /- /R/-		Scale = .5" / Ft.	
TC LL	20.0 PSF	REF	R2327 - 61402
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCSUR2327 10307150
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	338289
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg. Located anywhere in roof, CAT 1, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCP1 (+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.



Scale = .5"/Ft.

••IMPORTANT•• FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC., SHALL NOT BE RESPONSIBLE FOR THE PROPER INSTALLATION OF THE PRODUCT.

Haines City, FL 33844
FL COA #0278



TC LL	20.0 PSF	REF	R2327 - 61404
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCURSR2327 10307130
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	338303
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.


In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=4.2 psf, wind
BC DL=5.0 psf, lw=1.00 GCPI(+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.



2-0-0
5-0-0 Over 3 Supports
R=339 U=121 W=4"
RL=60

Design Crit: FBC2007Res/TP1-2002(STD)

FT/RT=20%(0%)/10(0)

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC&I (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TP1 (TRUSS PLATE INSTITUTE) 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, WAUWATON, WI, 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR, ITW BCG, INC. SHALL BE RESUBMITTED FOR REVIEW AND APPROVAL PRIOR TO BUILDING THE TRUSS IN CONFORMANCE WITH THE TP1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AEP&N) AND TP1. ITW BCG CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/52/K) ASTM A653 GRADE 40/60 (W, K/H/SS) GALV. STEEL. APPL. 2-0-0 PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A, 2-0-0 ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844

FL COA #0 278



FL/-/2/-/-/R/-		Scale = .5" / Ft.	
TC LL	20.0 PSF	REF	R2327 - 61405
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307112
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	337967
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF -	1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Roof overhang supports 2.00 psf soffit load.


In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0
psf. $I_w=1.00$ $GCF(+/-)=0.18$

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.





R=285 U=126 W=4"
RL=46

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND ERECTING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA), 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY MATERIALS OR METHODS NOT SPECIFIED IN THIS DESIGN SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE CONSIDERED A DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY ACPA) AND TPI. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWING 160A15. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



FL/-/2/-/-/R/-		Scale = .5" / Ft.	
TC LL	20.0 PSF	REF	R2327- 61406
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307113
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	337979
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10


THIS DWG PREPARED FROM COMPUTER INPUT (LOADS & DIMENSIONS) SUBMITTED BY TRUSS WFR

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT 11, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, $I_w=1.00$ GCP1 (+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load



R=-64 R_w=57 U=41

R=1 R_w=39 U=23

$$2.5X4(A1) =$$

Diagram of a continuous beam with three supports. The beam is divided into two equal spans of 2-0-0. The total length is 4-0-0. The beam is labeled "Dyer 3 Supports".

R=305 U=179 W=4"
RL=33

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

9.01/02.0210/16 QTY:

FL/-/2/-/-/R/-

Scale = .5"/ft.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0278

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO SC-1 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 OR THE WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES AND WRITERS TO CROSS CHECK THESE DIRECTIONS. THE PROPERTIES INDICATED FOR CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL BE PROPERLY ATTACHED TO THE CHORD CELLS.

FLORIDA
WEEK

STATE OF
NEW YORK

10A
NEE

9

38

040

6/10/20

FL/-/2/-/-/R/-

Scale = .5"/ft.

TC LL	20.0
-------	------

REF R2327- 61

TC DL	7.0
-------	-----

DATE 11/03/

BC	DL	10.0
----	----	------

DRW HCUSR2327 103

BC LL	0.01
-------	------

HC-ENG SSB/DF

TOT 1D	<u>37 0</u>
--------	-------------

SFON- 337976

1 25

EBDM	IBC
------	-----

DOI: 10.1002/

1 NOV 11	200
1 NOV 11	200

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

Calculated horizontal deflection is 0.35" due to live load and 0.23" due to dead load.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT 11, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, lw=1.00 GCpl(+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

MMFRS loads based on trusses located at least 15.00 ft. from roof edge.



← 5-5-11 Over 3 Supports →
R=252 U=0 W=3.5"
RL=111/-77

Design Crit: FBC2007Res/TP1-2002(STD)

FT/RT=20%(0%)/10(0)

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSS (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TP1 (TRUSS PLATE INSTITUTE), 218 W. 10TH STREET, SUITE 312, ALBUQUERQUE, NM 87102, (505) 243-1111, FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TP1: OR FABRICATING, HANDLING, SHIPPING, INSTALLING A BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/PA) AND TP1. CONNECTIONS ARE MADE OF 20/18/1804 (R 1/2S/SK) ASTM A563 GRADE 40/60 (W, K, N, SS) GALV. STEEL. APPROVED FOR THE TRUSS MANUFACTURER: [Signature] DATE: 03/2010. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844

FL COA #0 278



FL/-/2/-/-/R/-		Scale = .375"/Ft.	
TC LL	20.0 PSF	REF	R2327 - 61409
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307132
BC LL	0.0 PSF	HC-ENG SSB/DF	
TOT. LD.	37.0 PSF	SEQN-	338368
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

Calculated horizontal deflection is 0.27" due to live load and 0.18" due to dead load.

Bottom chord checked for 10.00 psf non-concurrent live load.

Deflection meets L/360 live and L/240 total load.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. lw=1.00 GCPI (+/-)=0.18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Truss passed check for 20 psf additional bottom chord live load in areas with 42"-high x 24"-wide clearance.

MMFRS loads based on trusses located at least 15.00 ft. from roof edge.




← 4 5 11 Over 3 Supports →
R=197 U=0 W=3.5"
RL=91/-63

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BUILDING. REFER TO BC&I (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA), 53719 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. LTV BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE TPI OR FABRICATION, HANDLING, SHIPPING, INSTALLING AND BUILDING TRUSSES BY ASPPA) AND TPI. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.




FL/-/2/-/-/R/-		Scale = .375"/Ft.	
TC LL	20.0 PSF	REF	R2327 - 61410
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HOURS2327 10307133
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT.LD.	37.0 PSF	SEQN-	338374
DUR.FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ Gcpl (+/-)=.0, .18

Wind reactions based on MMFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

Bottom chord checked for 10.00 psf non-concurrent live load.
MMFRS loads based on trusses located at least 15.00 ft. from roof edge.



< 3-5-11 Over 3 Supports >

R=136 U=0 W=8'
RL=70/-48

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)

$$FT/RT=20\%(0\%)/10(0)$$

9.01.02.0210/16 QIV:

FL/-/2/-/-/R/-

Scale = .5"/Ft.

ALPINE

ITW Building Components Group Inc

Haines City, FL 33844

FL COA #0278

WARNING: TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO SC-1 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314, AND TRCA (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES AND WORK TO PERFORM IN THESE FUNCTIONS. TRUSSES MUST BE PROPERLY BRACED TO PREVENT BUCKLING. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

••IMPORTANT•• FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE SYSTEM AND SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE SYSTEM AND SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE SYSTEM.

BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN AND FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THE REQUIREMENTS OF THE DESIGN CODE BY METHOD AND TOOL TYPING OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES.

DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AIA/H/AS) AND TP1. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/K) ASTM A653 GRADE 40/60 (W, K/H,SS) GALV. STEEL. APPLICATION OF PLATE STRENGTHENING AND STIFFENING OF BEAMS, JOISTS, AND CONNECTIONS ARE DETAILED ON THIS SECTION.

PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 180A-
ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC.3. A SEAL ON THIS

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TROSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE USER.

BUILDING DESIGNER PER ANSI/TP1 1 SEC. 2.

DOUGLAS FLEMING
LICENSE
No. 66648
9.01.02.0210.16
QTY.

TC LL	20.0
-------	------

REF R2327- 61411

TC DL 7.0 PSF

DATE 11/03/10

BC DL 10.0 PSF

DRW HCUSR2327 10307134

BC: 11 0.0 PSE

HC-ENG SSB/DF

DO EL	3:0	1.01
TOT ID	37 0	PCE

CEOM 220277

101:LD; 37.0 PSI

3

DUR.-FAC. 1.25

FROM JRG


THIS DWG PREPARED FROM COMPUTER INPUT (LOADS & DIMENSIONS) SUBMITTED BY TRUSS MFR.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, located anywhere in roof, CAT 11, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, $I_w=1.00$ GCP1 (+/-)=0.18

Wind reactions based on MWFRS pressures.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.



2+5-11 Over 3 Supports

R=97 U=0 W=8"
RL=68/-34

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

$$FT/RT = 20\%(0\%) / 10(0)$$

9.01:02.0210x16 QTY:2

FL--/2/--/R/-

Scale = .5" / Ft.

WARNING: THESE TRUCKS REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BOLTING. REFER TO GC51 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND WPCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES TO PERFORM THESE FUNCTIONS. OTHERWISE INDICATED FOR CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE PROPERLY ATTACHED RIGID CEILING.

••IMPORTANT•• FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT

IP1: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF CROSSIES.

PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z

DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT

BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

ITW Building Components Group Inc

Haines City, FL 33844

FL COA #0 278



TC LL	20.0 PSF	REF	R2327- 61412
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307135
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	338153
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0
psf. $I_w=1.00$ GCPI (+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.



1-5-1 Over 3 Supports
R=58 Rw=64 U=9 W=8"
RL=39

PLT TYP. Wave

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE TRUSS MANUFACTURER. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE TRUSS MANUFACTURER. THE TRUSS MANUFACTURER SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE THE RESPONSIBILITY OF THE TRUSS MANUFACTURER.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844
FL COA #0278



FL/-/2/-/-/R/-				Scale = .5" / Ft.	
TC LL	20.0 PSF	REF	R2327 - 61413		
TC DL	7.0 PSF	DATE	11/03/10		
BC DL	10.0 PSF	DRW	HGUSR2327 10307136		
BC LL	0.0 PSF	HC-ENG	SSB/DF		
TOT. LD.	37.0 PSF	SEQN-	338159		
DUR. FAC.	1.25	FROM	JRG		
SPACING	24.0"	JREF-	1U6L2327Z10		


THIS DWG PREPARED FROM COMPUTER INPUT (LOADS & DIMENSIONS) SUBMITTED BY TRUSS MFR.

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, not located within 4.50 ft from roof edge, CAT 11, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, lw=1.00 GCPI(+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.



6-0-7 Over 3 Supports

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

9.01.02.0210.16 QTY

4 FL/-/2/-/-/R/-

Scale = .5"/Ft.

WARNING: TRUCKS REQUIRE EXTENSIVE CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND JOINTING. REFER TO BEST (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLASTIC INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND THE (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES AND WORK TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED FOR CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL BE PROPERLY ATTACHED RIGID CEILING.

ALPINE

ITW Building Components Group Inc

Haines City, FL 33844
FL COA #0278

[illegible]

DOUGLAS FLEMING
PUBLIC ENGINEER
02/22/16
No. 66648
STATE OF FLORIDA
PROFESSIONAL ENGINEER

TC LL	20.0 PSF	REF	R2327 - 61415
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307127
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT.LD.	37.0 PSF	SEQN-	338185
DUR.FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF -	1U6L2327Z10

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.


Deflection meets L/360 live and L/240 total load.

120 mph wind, 15.00 ft mean hgt. ASCE 7-05, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf. $I_w=1.00$ GCPI (+/-)=0.18

Wind reactions based on MMFRS pressures.

Bottom chord checked for 10.00 psf non-concurrent live load.

MMFRS loads based on trusses located at least 7.50 ft. from roof edge.




2-0-7 Over 3 Supports

R=77 U=0 W=8"
RL=28

Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

PLT TYP. Wave

ALPINE



Haines City, FL 33844
FL COA #0 278

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC31 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE) 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LANE, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.


IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITR BCG, INC. SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. THE TRUSS IN COMPLIANCE WITH THE DESIGN SHALL BE USED AS SHOWN. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W, H/55/K) ASTM A653 GRADE 40/60 (W, K/H/55) GALV. STEEL. APR. 2010. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUSTAINABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



FL/-/2/-/-/R/-		Scale = .5"/Ft.	
TC LL	20.0 PSF	REF	R2327- 61416
TC DL	7.0 PSF	DATE	11/03/10
BC DL	10.0 PSF	DRW	HCUSR2327 10307128
BC LL	0.0 PSF	HC-ENG	SSB/DF
TOT. LD.	37.0 PSF	SEQN-	338191
DUR. FAC.	1.25	FROM	JRG
SPACING	24.0"	JREF-	1U6L2327Z10

MMFRS loads based on trusses located at least 15.00 ft. from roof edge.

Deflection meets L/360 live and L/240 total load.



Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)

10.02.01.0923.23 QTY

Scale = .3125"/Ft.

ALPINE

ITW Building Components Group Inc.

Haines City, FL 33844

FL COA #0278

WARNING: THESE TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND ERECTING. REFER TO GC-1 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY THE TRUSS PLATE INSTITUTE, 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA. 22314 AND WFOA (WOOD TRUSS COUNCIL OF AMERICA, 6200 ENTERPRISE LANE, MADISON, WI. 53719) FOR SAFETY PRACTICES AND TIPS FOR REFORMING THESE FUNCTIONS. UNLESS PROPERLY INDICATED FOR CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL BE PROPERLY ATTACHED RIGID CELLING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING OR BRACING OF TRUSSES.

[illegible]

No. 66648

STATE OF
ER

FLORIDA
SIGNAL ENGINE


03/2010

FL/-2/-/-/R/-		Scale = .3125"/Ft.
TC LL	20.0 PSF	REF R2327 - 61418
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCU5R2327 10307145
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT. LD.	37.0 PSF	SEQN- 4672 REV
DUR. FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, located anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, $I_w=1.00$ GCPI (+/-)=0.18

Wind reactions based on MMFRS pressures.

Deflection meets L/360 live and L/240 total load



9.01.02.0210x16 QTY:2

FL/-/2/-/-/R/-

Scale = .5"/Ft.

STATE OF
NO. 000040
6300
HAVE
218
ING.

ALPINE

ITW Building Components Group Inc

Haines City, FL 33844
FL COA #0278


FL/-2/-/-R/-		Scale = .5"/Ft.
TC LL	20.0 PSF	REF R2327- 61422
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCUSR327 1030712
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT. LD.	37.0 PSF	SEQN- 338054
DUR. FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

120 mph wind, 15.00 ft mean hgt, ASCE 7-05, *CLOSED bldg, Located anywhere in roof, CAT 11, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0 psf, $I_w=1.00$ GCP1 (+/-)=0.18

Wind reactions based on MWFRS pressures.

Hipjack supports 7-0-0 setback jacks with no webs.

Hipjack supports 7-0-0 setback jacks with no webs.



TC LL	20.0 PSF	REF	R2327- 61423
TC DL	7.0 PSF	DATE	11/03/10
PC DL	10.0 PSF	DRW	HCISB2327 10307151

BC 11	0 0 BCE	HC-ENG-SCB/DE
-------	---------	---------------

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

101.LD:	37.0 PSF	SEQN-	330310
---------	----------	-------	--------

DUR. FAC.	1.25	FROM JR6
-----------	------	----------

SPACING	24 0"	IBEE	41161 3337710
---------	-------	------	---------------


Category	Sub-category	Value
C	1	1
	2	1
D	1	1
	2	1
E	1	1
	2	1
F	1	1
	2	1
G	1	1
	2	1
H	1	1
	2	1
I	1	1
	2	1
J	1	1
	2	1
K	1	1
	2	1
L	1	1
	2	1
M	1	1
	2	1
N	1	1
	2	1
O	1	1
	2	1
P	1	1
	2	1
Q	1	1
	2	1
R	1	1
	2	1
S	1	1
	2	1
T	1	1
	2	1
U	1	1
	2	1
V	1	1
	2	1
W	1	1
	2	1
X	1	1
	2	1
Y	1	1
	2	1
Z	1	1
	2	1

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

In lieu of rigid ceiling use purlins to brace BC @ 24" OC.
Hi/pjack supports 7'-0" setback jacks with no webs.


120 mph wind, 15.00 ft mean hgt, ASCE 7-05, CLOSED bldg, located
anywhere in roof, CAT II, EXP B, wind TC DL=4.2 psf, wind BC DL=5.0
psf. $I_w=1.00$ GCPI(+/-)=0.18

Wind reactions based on MMFRS pressures.
Deflection meets L/360 live and L/240 total load.



R=488 U=131 W=5.657"

PLT TYP. Wave
Design Crit: FBC2007Res/TP1-2002(STD)
FT/RT=20%(0%)/10(0)



WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSI (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 218 NORTH LEE STREET, SUITE 312, ALEXANDRIA, VA, 22314 AND WICA (WOOD TRUSS COUNCIL OF AMERICA), 6308 ENTERPRISE LANE, MADISON, WI 53719 FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL BE A PROPERLY ATTACHED RIGID CEILING.

IMPORTANT FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ITW BCG, INC. SHALL NOT BE RESPONSIBLE FOR ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH THE DESIGN. THE DESIGNER SHALL BE RESPONSIBLE FOR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/SS/K) ASTM A653 GRADE 40/60 (W, K/H/SS) GALV. STEEL. ALL PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWING. DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SIGNED AND SEALED ON THIS DATE. THE SIGNATURE AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

STATE OF FLORIDA
PROFESSIONAL ENGINEER
No. 66648
03/02/2010

TC LL	20.0 PSF	REF R2327- 61424
TC DL	7.0 PSF	DATE 11/03/10
BC DL	10.0 PSF	DRW HCURR2327 10307111
BC LL	0.0 PSF	HC-ENG SSB/DF
TOT. LD.	37.0 PSF	SEQN- 337983
DUR. FAC.	1.25	FROM JRG
SPACING	24.0"	JREF- 1U6L2327Z10

SUBCONTRACTOR VERIFICATION FORM

TBD

25099

APPLICATION NUMBER CONTRACTOR PBA BUILDING CORP PHONE 407-982-8282

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is REQUIRED that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name: Donald Hollingsworth	License #: ER13012377	Phone #: 386-623-6982	Signature:
MECHANICAL/A/C	Print Name: James Bentie	License #: CA058522	Phone #: 352-331-2005	Signature:
PLUMBING/GAS	Print Name: Scott Wolfe	License #: CFC051621	Phone #: 386-935-0616	Signature:
ROOFING	Print Name: OGLES ROOFING	License #: CCC1328699	Phone #: 386-364-4838	Signature:
SHEET METAL	Print Name: OGLES ROOFING	License #: CCC1328699	Phone #: 386-364-4838	Signature:
FIRE SYSTEM/SPRINKLER	Print Name: N/A	License #: N/A	Phone #: N/A	Signature:
SOLAR	Print Name: N/A	License #: N/A	Phone #: N/A	Signature:

MASON	CGC1508506	PBA BUILDING CORP.	Sub-Contractors Printed Name	Sub-Contractors Signature
CONCRETE FINISHER	CGC1508506	PBA BUILDING CORP.		
FRAMING	CGC1508506	PBA BUILDING CORP.		
INSULATION	CGC1508506	PBA BUILDING CORP.		
STUCCO	N/A			
DRYWALL	CGC1508506	PBA BUILDING CORP.		
PLASTER	N/A			
CABINET INSTALLER	CGC1508506	PBA BUILDING CORP.		
PAINTING	CGC1508506	PBA BUILDING CORP.		
ACOUSTICAL CEILING	N/A			
GLASS	N/A			
CERAMIC TILE	CGC1508506	PBA BUILDING CORP.		
FLOOR COVERING	CGC1508506	PBA BUILDING CORP.		
ALUM/VINYL SIDING	N/A			
GARAGE DOOR	CGC1508506	PBA BUILDING CORP.		
METAL BLDG ERECTOR	N/A			

F. S. 440.103 Building permits; Identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

SUBCONTRACTOR VERIFICATION FORM

Permit # 29099

1-13-11

APPLICATION NUMBER

CONTRACTOR

PHONE

THIS FORM MUST BE SUBMITTED PRIOR TO THE ISSUANCE OF A PERMIT

In Columbia County one permit will cover all trades doing work at the permitted site. It is REQUIRED that we have records of the subcontractors who actually did the trade specific work under the permit. Per Florida Statute 440 and Ordinance 89-6, a contractor shall require all subcontractors to provide evidence of workers' compensation or exemption, general liability insurance and a valid Certificate of Competency license in Columbia County.

Any changes, the permitted contractor is responsible for the corrected form being submitted to this office prior to the start of that subcontractor beginning any work. Violations will result in stop work orders and/or fines.

ELECTRICAL	Print Name _____ License #: <u>EC 0001727</u> Signature: <u>Robert Gae (Alliance Integrity LLC)</u> Phone #: <u>407-320-1956</u>
MECHANICAL/A/C	Print Name _____ License #: _____ Signature _____ Phone #: _____
PLUMBING/GAS	Print Name _____ License #: _____ Signature _____ Phone #: _____
ROOFING	Print Name _____ License #: _____ Signature _____ Phone #: _____
SHEET METAL	Print Name _____ License #: _____ Signature _____ Phone #: _____
FIRE SYSTEM/SPRINKLER	Print Name _____ License #: _____ Signature _____ Phone #: _____
SOLAR	Print Name _____ License #: _____ Signature _____ Phone #: _____

Specialty License	License Number	Sub-Contractors Printed Name	Sub-Contractors Signature
MASON			
CONCRETE FINISHER			
FRAMING			
INSULATION			
STUCCO			
DRYWALL			
PLASTER			
CABINET INSTALLER			
PAINTING			
ACOUSTICAL CEILING			
GLASS			
CERAMIC TILE			
FLOOR COVERING			
ALUM/VINYL SIDING			
GARAGE DOOR			
METAL BLDG ERECTOR			

F. S. 440.103 Building permits; identification of minimum premium policy.--Every employer shall, as a condition to applying for and receiving a building permit, show proof and certify to the permit issuer that it has secured compensation for its employees under this chapter as provided in ss. 440.10 and 440.38, and shall be presented each time the employer applies for a building permit.

10:23:40 AM 12/28/2010

1019

Licenses Details

Licenses Information

Name: OGLES, ROBERT LESLEE II (Primary Name)
Main Address: 18523 COUNTY ROAD 136
LIVE OAK Florida 32060
County: SUWANNEE

Licenses Mailing:

Licenses Location:

Licenses Information

Licenses Type: Certified Roofing Contractor
Rank: Cert Roofing
License Number: CCC1328699
Status: Current, Active
Licenses Date: 07/17/2008
Expires: 08/31/2012

Special Qualifications
Qualification Effective
Construction Business 07/17/2008
Fingerprint (Construction Industry Licensing Board) 04/03/2008

View Related License Information

[View License Complaint](#)

[Terms of Use](#) | [Privacy Statement](#) |

CERTIFICATES OF OCCUPANCY

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 22-5S-17-09322-004

Building permit No. 000029099

Use Classification SFD, UTILITY

Fire: 19.26

Permit Holder DOUG BAGGETT

Waste: 50.25

Owner of Building DONALD BAGGETT

Total: 69.51

Location: 415 SW CIRRUS DRIVE, LAKE CITY, F 32025

Date: 07/08/2011

Tracy Crews by H.A.

Building Inspector

POST IN A CONSPICUOUS PLACE
(Business Places Only)

