

DATE 11/04/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023811

APPLICANT MACK ROBINSON PHONE 755-2492
ADDRESS 24262 HIGHWAY 129 O'BRIEN FL 32071
OWNER ROGER LITTLE, JR PHONE 623-1870
ADDRESS 401 SW LITTLE ROAD LAKE CITY FL 32024
CONTRACTOR MACK ROBINSON PHONE 755-2492

LOCATION OF PROPERTY 47S, TL ON 240, TL ON LITTLE ROAD, CURVE RIGHT, 2ND
DRIVE ON RIGHT

TYPE DEVELOPMENT SFD, UTILITY ESTIMATED COST OF CONSTRUCTION 80750.00

HEATED FLOOR AREA 1615.00 TOTAL AREA 2596.00 HEIGHT .00 STORIES 1

FOUNDATION CONC WALLS FRAMED ROOF PITCH 7/12 FLOOR SLAB

LAND USE & ZONING A-3 MAX. HEIGHT 22

Minimum Set Back Requirments: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00

NO. EX.D.U. 0 FLOOD ZONE X DEVELOPMENT PERMIT NO. _____

PARCEL ID 07-5S-17-09151-007 SUBDIVISION _____

LOT _____ BLOCK _____ PHASE _____ UNIT _____ TOTAL ACRES _____

000000876 RB0054287 A Mack Robinson

Culvert Permit No. _____ Culvert Waiver _____ Contractor's License Number _____ Applicant/Owner/Contractor _____
WAIVER 05-1076-N BK JH Y
Driveway Connection _____ Septic Tank Number _____ LU & Zoning checked by _____ Approved for Issuance _____ New Resident _____

COMMENTS: SPECIAL FAMILY LOT PERMIT(GRANDSON)

Check # or Cash 8365

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power _____ Foundation _____ Monolithic _____
date/app. by _____ date/app. by _____ date/app. by _____

Under slab rough-in plumbing _____ Slab _____ Sheathing/Nailing _____
date/app. by _____ date/app. by _____ date/app. by _____

Framing _____ Rough-in plumbing above slab and below wood floor _____
date/app. by _____ date/app. by _____

Electrical rough-in _____ Heat & Air Duct _____ Peri. beam (Lintel) _____
date/app. by _____ date/app. by _____ date/app. by _____

Permanent power _____ C.O. Final _____ Culvert _____
date/app. by _____ date/app. by _____ date/app. by _____

M/H tie downs, blocking, electricity and plumbing _____ Pool _____
date/app. by _____ date/app. by _____

Reconnection _____ Pump pole _____ Utility Pole _____
date/app. by _____ date/app. by _____ date/app. by _____

M/H Pole _____ Travel Trailer _____ Re-roof _____
date/app. by _____ date/app. by _____ date/app. by _____

BUILDING PERMIT FEE \$ 405.00 CERTIFICATION FEE \$ 12.98 SURCHARGE FEE \$ 12.98

MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$ _____

FLOOD DEVELOPMENT FEE \$ _____ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ _____ TOTAL FEE 505.96

INSPECTORS OFFICE [Signature] CLERKS OFFICE CH

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

**Columbia County Building Department
Culvert Waiver**

Weggie
**Culvert Waiver No.
000000876**

DATE: 11/04/2005

BUILDING PERMIT NO. 23811

APPLICANT MACK ROBINSON PHONE 755-2492

ADDRESS 24262 HIGHWAY 129 O'BRIEN FL 32071

OWNER ROGER LITTLE, JR PHONE 623-1870

ADDRESS 401 SW LITTLE ROAD LAKE CITY FL 32024

CONTRACTOR MACK ROBINSON PHONE 755-2492

LOCATION OF PROPERTY 47S, TL ON 240, TL ON LITTLE ROAD, AROUND RIGHT CURVE, 2ND ON RIGHT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT _____

PARCEL ID # 07-5S-17-09151-007

I HEREBY CERTIFY THAT I UNDERSTAND AND WILL FULLY COMPLY WITH THE DECISION OF THE COLUMBIA COUNTY PUBLIC WORKS DEPARTMENT IN CONNECTION WITH THE HEREIN PROPOSED APPLICATION.

SIGNATURE: *Mack Robinson*

A SEPARATE CHECK IS REQUIRED

MAKE CHECKS PAYABLE TO BCC

Amount Paid 50.00

PUBLIC WORKS DEPARTMENT USE ONLY

I HEREBY CERTIFY THAT I HAVE EXAMINED THIS APPLICATION AND DETERMINED THAT THE CULVERT WAIVER IS:

✓ APPROVED _____ NOT APPROVED - NEEDS A CULVERT PERMIT

COMMENTS: _____

SIGNED: *Perry Little* DATE: 11/10/05

ANY QUESTIONS PLEASE CONTACT THE PUBLIC WORKS DEPARTMENT AT 386-752-5955.

COLUMBIA COUNTY

NOV 08 2005

PUBLIC WORKS DEPT.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160



Columbia County Building Permit Application

CK# 8365

Revised 9-23-04

For Office Use Only Application # 0510-79 Date Received 10/27 By TA Permit # 876/23811
Application Approved by - Zoning Official BLK Date 01-11-05 Plans Examiner OK JH Date 11-2-05
Flood Zone X Development Permit N/A Zoning A-3 Land Use Plan Map Category A-3
Comments SEEN 2nd PROPOSED # SECTION 14.9 Special Family Lot Permit + Grand
SITE PLAN ON SHEET 1

Applicants Name Mack Robinson Phone 755 2492
Address 24262 HW 129 OBrien FL 32071
Owners Name Roger Little Jr Phone 623-1870
911 Address 409 SW Little Rd 32024
Contractors Name Mack Robinson Const Phone 755 2492
Address 24262 HW 129 OBrien FL 32071
Fee Simple Owner Name & Address First Federal Savings
Bonding Co. Name & Address _____
Architect/Engineer Name & Address Jim Delbene (Arch) Mark Discoway (eng)
Mortgage Lenders Name & Address First Federal Lake City
Circle the correct power company - FL Power & Light - Clay Elec. - Suwannee Valley Elec. - Progressive Energy
Property ID Number 07-58-17-09151-007 Estimated Cost of Construction \$128,000
Subdivision Name NA Lot _____ Block _____ Unit _____ Phase _____
Driving Directions State Rd 47 south, TL on Co Rd 240 through S curve TL on Little Rd go around RH curve second drive on right follow easement to site
Type of Construction New house - SFD Number of Existing Dwellings on Property 0
Total Acreage 1 Lot Size _____ Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
Actual Distance of Structure from Property Lines - Front 78 - Side 79 - Side 79 - Rear 78
Total Building Height 22' 2" Number of Stories 1 Heated Floor Area 1615 Roof Pitch 7/12
PORCHES 469 GARAGE 512 TOTAL 2596

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA

Sworn to (or affirmed) and subscribed before me

this 27 day of 10

Personally known ✓ or Produced Identification _____



Mack Robinson
Contractor Signature

Contractors License Number RB 0054287

Competency Card Number 5529

NOTARY STAMP/SEAL

[Signature]


Notary Signature

ADVISED MARK ON 11-02-05

**COLUMBIA COUNTY BUILDING DEPARTMENT
CHECKLIST FOR PERMITTING**

Application # 0510-79

✓	Notarized completed Building Permit Application
	Notes:
✓	If an Owner Builder, signed Disclosure Statement
	Notes:
✓	Recorded Deed or a Notarized Affidavit (form from the Building Dept.)
	Notes:
✓	Approved and Signed Site Plan from Environmental Health on the septic
	Notes:
✓	Site plan with actual distances of the structure to each property line
	Notes:
✓	911 Address form, Contact 386.752.8787 for an appointment
	Notes:
✓	Residential or Commercial Checklist completed
	Notes:
✓	Driving directions including all road names
	Notes:
✓	Well information (on plans or letter from the well driller)
	Notes:
7	Before the 1st inspection Recorded Notice of Commencement signed by owner
	Notes: <u>PENDING</u>
✓	2 sets of plans (blueprints)
	Notes:
✓	2 sets of sealed truss engineering
	Notes:
✓	2 sets of energy code & manual J
	Notes:
✓	2 sets of engineering packets including specs on windows, doors, roof and etc.
	Notes:



Columbia County Property Appraiser

J. Doyle Crews, CFA - Lake City, Florida - 386-758-1083

PARCEL: 07-5S-17-09151-000 - TIMBERLAND (005500)

NE1/4 OF NW1/4 OF NW1/4, EX 1 AC DESC ORB 1051-163. ORB 368-269,

Name: LITTLE RALPH E & MARILYN L	LandVal	\$0.00
Site:	BldgVal	\$0.00
Mail: 559 SW LITTLE RD	ApprVal	\$1,980.00
LAKE CITY, FL 32024	JustVal	\$29,160.00
Sales	Assd	\$1,980.00
Info	Exmpt	\$0.00
	Taxable	\$1,980.00

0 0.1 0.2 0.3 mi



This information, GIS Map Updated: 8/3/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

This Instrument Prepared By:
Marilyn Little
559 SW Little Road
Lake City, Florida 32024

PARCEL NO: 07-58-17-09151-000

Inst:2005015958 Date:07/07/2005 Time:10:02
Doc Stamp-Deed : 0.70
MK DC, P. DeWitt Cason, Columbia County B:1051 P:163

WARRANTY DEED

This Warranty Deed, made the 7th day of July 2005, by Ralph Edwin & Marilyn L. Nettles Little, husband and wife, hereinafter called the Grantor, to Roger Edwin Little, Jr. a single man whose post office address is 160 SW Crescent Street, Lake City, Florida 32025 hereinafter called the Grantee.

(Wherever used herein the terms "Grantor" and "Grantee" shall include singular and plural, heirs, legal representatives, and assigns of individuals, and the successors and assigns of corporations, wherever the context so admits or requires.)

WITNESSETH: That the Grantor, for and in consideration of the sum of TEN DOLLARS (\$10.00) and other valuable considerations, receipt whereof is hereby acknowledged, by these presents does grant, bargain, sell, alien, remise, release, convey and confirm unto the Grantee all that certain land situate, lying and being in COLUMBIA County, State of Florida, viz:

SEE SCHEDULE "A" ATTACHED

* Before the above mentioned property can be sold Ralph Edwin Little or Marilyn Nettles Little must be given first right of refusal to purchase said property. Roger Edwin Little Sr. must be given second right of refusal. Teresa Rose Little Metrick must be given third right of refusal

Together, with all the tenements, hereditaments and appurtenances thereto belonging or in anywise appertaining. To Have and to Hold, the same in fee simple forever.

And the Grantor hereby covenants with said grantee that the grantor is lawfully seized of said land in fee simple; that the grantor has good right and lawful authority to sell and convey said land, and hereby warrants the title to said land and will defend the same against the lawful claims of all persons whomsoever; and that said land is free of all encumbrances, except taxes accruing subsequent to December 31, 2004.

In Witness Whereof, the said grantor has signed and sealed these presents the day and year first above written.

Signed, sealed and delivered in the presence of:

Judith M. Conklin
Witness Signature

Judith M. Conklin
Printed Name

Pamlyn Douglas
Witness Signature

Pamlyn Douglas
Printed Name

Ralph Edwin Little
RALPH EDWIN LITTLE

Marilyn L. Nettles Little
MARILYN L. NETTLES LITTLE


STATE OF FLORIDA COUNTY OF COLUMBIA

I hereby certify that on this day, before me, an officer duly authorized to administer oaths and take acknowledgments, personally appeared RALPH EDWIN LITTLE & MARILYN L. NETTLES LITTLE known to me to be the persons one described in and who executed the foregoing instrument, who acknowledged before me that they executed the same, and an oath was not taken. (Check one:)
Said person(s) is personally known to me. ☒ Said person(s) provided the following type of identification: Florida Driver's License (picture ID)

Witness my hand and official seal in the County and State last aforesaid
This 7 day of July, 2005.

Marilyn S. Montgomery
Notary Signature

MARILYN S. MONTGOMERY
Printed Name



SCHEDULE "A"


DESCRIPTION

COMMENCE at the Northeast corner of the Northwest 1/4 of the Northwest 1/4 of Section 7, Township 5 South, Range 17 East, Columbia County, Florida and run South 88°34'37" West along the North line of said Section 7 a distance of 661.15 feet to the Northwest corner of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7; thence South 00°10'02" West along the West line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7 a distance of 453.29 feet to the POINT OF BEGINNING; thence North 88°37'47" East along a line parallel to the South line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7 a distance of 208.71 feet; thence South 00°10'02" West along a line parallel to the West line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7 a distance of 208.71 feet to a point on the South line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7; thence South 88°37'47" West along said South line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7 a distance of 208.71 feet to the Southwest corner of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7; thence North 00°10'02" East along the West line of the Northeast 1/4 of the Northwest 1/4 of the Northwest 1/4 of Section 7 a distance of 208.71 feet to the POINT OF BEGINNING. Containing 1.00 acres, more or less.

Inst:2005015958 Date:07/07/2005 Time:10:02

Doc Stamp-Deed : 0.70

DC, P. DeWitt Cason, Columbia County B:1051 P:164




This information, GIS Map Updated: 8/3/2005, was derived from data which was compiled by the Columbia County Property Appraiser Office solely for the governmental purpose of property assessment. This information should not be relied upon by anyone as a determination of the ownership of property or market value. No warranties, expressed or implied, are provided for the accuracy of the data herein, it's use, or it's interpretation. Although it is periodically updated, this information may not reflect the data currently on file in the Property Appraiser's office. The assessed values are NOT certified values and therefore are subject to change before being finalized for ad valorem assessment purposes.

Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan
Permit Application Number: 05-1076N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

LITTLE JR/CR 05-3151



Site Plan Submitted By Paul Lloyd Date 10/14/05
Plan Approved ☒ Not Approved ☐ Date 10/25/05
By M. J. L. Columbia CPHU

Notes: _____

COLUMBIA COUNTY 9-1-1 ADDRESSING

263 NW Lake City Ave. * P. O. Box 1787 * Lake City, FL 32056-1787
PHONE: (386) 758-1125 * FAX: (386) 758-1365 * Email: ron_croft@columbiacountyfla.com

Addressing Maintenance

To maintain the Countywide Addressing Policy you must make application for a 9-1-1 Address at the time you apply for a building permit. The established standards for assigning and posting numbers to all principal buildings, dwellings, businesses and industries are contained in Columbia County Ordinance 2001-9. The addressing system is to enable Emergency Service Agencies to locate you in an emergency, and to assist the United States Postal Service and the public in the timely and efficient provision of services to residents and businesses of Columbia County.

DATE ISSUED: October 21, 2005

ENHANCED 9-1-1 ADDRESS:

401 SW LITTLE RD (LAKE CITY, FL 32024)

Addressed Location 911 Phone Number: NOT AVAIL.

OCCUPANT NAME: NOT AVAIL.

OCCUPANT CURRENT MAILING ADDRESS: _____

PROPERTY APPRAISER PARCEL NUMBER: 07-SS-17-09151-007

Other Contact Phone Number (If any): _____

Building Permit Number (If known): _____

Remarks: _____

Address Issued By: _____

Columbia County 9-1-1 Addressing / GIS Department

NOTICE: THIS ADDRESS WAS ISSUED BASED ON LOCATION INFORMATION RECEIVED FROM THE REQUESTER. SHOULD, AT A LATER DATE, THE LOCATION INFORMATION BE FOUND TO BE IN ERROR, THIS ADDRESS IS SUBJECT TO CHANGE.

COLUMBIA COUNTY
9-1-1 ADDRESSING
APPROVED

RON E. BIAS

WELL DRILLING

317 SW Brecken Ridge • Fort White, FL 32038
(386) 497-1045 • Mobile: (386) 364-9233 • Fax: (386) 497-1045

No. _____

Date: _____

Name: Mark Robertson

Address: _____

Phone: 704 935-4468

DESCRIPTION:

4" deep well down to 100'
1 hp sub. pump 20 Gpm
80+ Gallon Captives
constant pressure tank
1 1/4" drop system with back
flow preventer
SRWD permit

Total: _____

Deposit: _____

Balance: _____

Date Wanted: _____

Authorized By: Ron E Bias

Received By: _____

Mar. 30 2005 07:57AM PT

FAK NO. : 13864971045

FROM : RON E BIAS WELL DRILLING

FLORIDA ENERGY EFFICIENCY CODE
FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	Roger Little Residence	Builder:	Mack Robinson
Address:	Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E	Permitting Office:	Columbia Co.
City, State:	Lake City, FL 32055-	Permit Number:	
Owner:	Roger Little, Jr.	Jurisdiction Number:	121000 221000
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 35.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 12.00
4. Number of Bedrooms	3	b. N/A	
5. Is this a worst case?	No	c. N/A	
6. Conditioned floor area (ft²)	1615 ft²		
7. Glass area & type	Single Pane Double Pane	13. Heating systems	
a. Clear glass, default U-factor	0.0 ft² 222.0 ft²	a. Electric Heat Pump	Cap: 35.0 kBtu/hr
b. Default tint	0.0 ft² 0.0 ft²		HSPF: 7.90
c. Labeled U or SHGC	0.0 ft² 0.0 ft²	b. N/A	
8. Floor types		c. N/A	
a. Slab-On-Grade Edge Insulation	R=0.0, 193.0(p) ft	14. Hot water systems	
b. N/A		a. Electric Resistance	Cap: 30.0 gallons
c. N/A			EF: 0.90
9. Wall types		b. N/A	
a. Frame, Wood, Exterior	R=13.0, 1261.0 ft²	c. Conservation credits	
b. N/A		(HR-Heat recovery, Solar	
c. N/A		DHP-Dedicated heat pump)	
d. N/A		15. HVAC credits	PT, CF,
e. N/A		(CF-Ceiling fan, CV-Cross ventilation,	
10. Ceiling types		HF-Whole house fan,	
a. Under Attic	R=30.0, 1615.0 ft²	PT-Programmable Thermostat,	
b. N/A		MZ-C-Multizone cooling,	
c. N/A		MZ-H-Multizone heating)	
11. Ducts			
a. Sup: Unc. Ret: Unc. AH: Interior	Sup. R=6.0, 30.0 ft		
b. N/A			

Glass/Floor Area: 0.14

Total as-built points: 21065
Total base points: 25232

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code. PREPARED BY: Tim Delbene DATE: 8/25/05 I hereby certify that this building, as designed, is in compliance with the Florida Energy Code. OWNER/AGENT: DATE:	Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes. BUILDING OFFICIAL: DATE: 
--	--

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055-

BASE				AS-BUILT							
GLASS TYPES											
.18 X Conditioned X BSPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X SPM X SOF = Points				
.18	1615.0	20.04	5825.6	Double, Clear	N	2.0	7.0	30.0	19.20	0.92	531.2
				Double, Clear	N	2.0	3.0	3.0	19.20	0.78	44.8
				Double, Clear	S	2.0	5.0	6.0	35.87	0.72	155.7
				Double, Clear	S	2.0	5.0	9.0	35.87	0.72	233.5
				Double, Clear	E	2.0	7.0	45.0	42.06	0.89	1676.9
				Double, Clear	E	10.0	7.0	30.0	42.06	0.44	557.2
				Double, Clear	E	2.0	5.0	9.0	42.06	0.80	301.7
				Double, Clear	W	10.0	7.0	60.0	38.52	0.46	1056.5
				Double, Clear	W	13.0	7.0	30.0	38.52	0.42	480.7
				As-Built Total:						222.0	
WALL TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Adjacent Exterior	0.0	0.00	0.0	Frame, Wood, Exterior	13.0		1261.0	1.50		1891.5	
Base Total:			1261.0	2143.7		As-Built Total:			1261.0	1891.5	
DOOR TYPES Area X BSPM = Points				Type	Area X SPM = Points						
Adjacent Exterior	21.0	2.40	50.4	Exterior Insulated			21.0	4.10		86.1	
	42.0	6.10	256.2	Exterior Insulated			21.0	4.10		86.1	
				Adjacent Insulated			21.0	1.60		33.6	
Base Total:			63.0	306.6		As-Built Total:			63.0	205.8	
CEILING TYPES Area X BSPM = Points				Type	R-Value		Area X SPM X SCM = Points				
Under Attic	1615.0	1.73	2793.9	Under Attic	30.0		1615.0	1.73 X 1.00		2793.9	
Base Total:			1615.0	2793.9		As-Built Total:			1615.0	2793.9	
FLOOR TYPES Area X BSPM = Points				Type	R-Value		Area X SPM = Points				
Slab	193.0(p)	-37.0	-7141.0	Slab-On-Grade Edge Insulation	0.0		193.0(p)	-41.20		-7951.6	
Raised	0.0	0.00	0.0								
Base Total:			-7141.0	As-Built Total:			193.0	-7951.6			
INFILTRATION Area X BSPM = Points				Area X SPM = Points							
			1615.0	10.21	16489.2		1615.0			10.21	16489.2

SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055

BASE				AS-BUILT							
Summer Base Points: 20418.0				Summer As-Built Points: 18467.0							
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
20418.0		0.4266	8710.3	18467.0		1.000	(1.090 x 1.147 x 0.91)	0.284	0.902	5393.0	
				18467.0		1.00	1.138	0.284	0.902	5393.0	

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055-

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt		Area X WPM X WOF = Points				
.18	1615.0	12.74	3703.5	Double, Clear	N	2.0	7.0	30.0	24.58	1.00	739.8
				Double, Clear	N	2.0	3.0	3.0	24.58	1.01	74.7
				Double, Clear	S	2.0	5.0	6.0	13.30	1.40	111.7
				Double, Clear	S	2.0	5.0	9.0	13.30	1.40	167.6
				Double, Clear	E	2.0	7.0	45.0	18.79	1.05	884.1
				Double, Clear	E	10.0	7.0	30.0	18.79	1.38	776.8
				Double, Clear	E	2.0	5.0	9.0	18.79	1.08	183.2
				Double, Clear	W	10.0	7.0	60.0	20.73	1.20	1492.9
				Double, Clear	W	13.0	7.0	30.0	20.73	1.22	758.2
				As-Built Total:		222.0			5189.1		
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	0.0	0.00	0.0	Frame, Wood, Exterior	13.0		1261.0			3.40	4287.4
Exterior	1261.0	3.70	4665.7								
Base Total: 1261.0 4665.7				As-Built Total:		1261.0			4287.4		
DOOR TYPES Area X BWPM = Points				Type	Area X WPM = Points						
Adjacent	21.0	11.50	241.5	Exterior Insulated				21.0	8.40	176.4	
Exterior	42.0	12.30	516.6	Exterior Insulated				21.0	8.40	176.4	
				Adjacent Insulated				21.0	8.00	168.0	
Base Total: 63.0 758.1				As-Built Total:		63.0			520.8		
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	1615.0	2.05	3310.8	Under Attic	30.0		1615.0	2.05 X 1.00		3310.8	
Base Total: 1615.0 3310.8				As-Built Total:		1615.0			3310.8		
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	193.0(p)	8.9	1717.7	Slab-On-Grade Edge Insulation	0.0		193.0(p)			18.80	3628.4
Raised	0.0	0.00	0.0								
Base Total: 1717.7				As-Built Total:		193.0			3628.4		
INFILTRATION Area X BWPM = Points				Area X WPM = Points							
1615.0 -0.59 -952.8				1615.0 -0.59 -952.8							

WINTER CALCULATIONS
Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055

BASE				AS-BUILT							
Winter Base Points: 13202.9				Winter As-Built Points: 15983.6							
Total Winter Points	X	System Multiplier	= Heating Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points	
13202.9		0.6274	8283.5	15983.6		1.00	(1.069 x 1.169 x 0.93)	0.432	0.950	7617.3	

WATER HEATING & CODE COMPLIANCE STATUS
Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055

BASE					AS-BUILT					
WATER HEATING					Tank	EF	Number of	X	Tank	X
Number of		Multiplier	=	Total	Volume		Bedrooms		Ratio	Multiplier
Bedrooms										Credit = Total
										Multiplier
3		2746.00		8238.0	30.0	0.90	3		1.00	2684.98
										1.00
										8054.9
					As-Built Total:					8054.9

CODE COMPLIANCE STATUS									
BASE					AS-BUILT				
Cooling	+	Heating	+	Hot Water	=	Total	Cooling	+	Heating
Points		Points		Points		Points	Points		Points
8710		8284		8238		25232	5393		7617
									8055
									21065

PASS



Code Compliance Checklist
Residential Whole Building Performance Method A - Details

ADDRESS: Lot: n/a, Sub: NW/4 of NW/4, Plat: SEC 7 T-5-S R-17-E, Lake City, FL 32055-

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum: .3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	✓
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	✓
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	✓
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	✓
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	✓
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	N/A
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	✓

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	✓
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	N/A
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	✓
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	✓
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	✓
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	✓

From: The Columbia County Building Department
Plans Review
135 NE Hernando Av.
P. O Box 1529
Lake City Florida, 32056-1529

0510-79

Reference to: Build permit application Number:

Mack Robinson Owner Roger Little Jr. 401 SW Little Rd.

On the date of November 1, 2005 application 0510-79 and plans for construction of a single family dwelling were reviewed and the following information or alteration to the plans will be required to continue processing this application. If you should have any question please contact the above address, or contact phone number (386) 758-1163 or fax any information to (386) 754-7088.

Please include application number 0510-79 when making reference to this application.

- ✓ 1. Application 0510-79 which was filed with the building department on the date of October 27, 2005 will be reviewed under the Florida Building Code 2004. The Wind Load design by Mr. Mark Disosway was design under the Florida Building Code 2001. The wind Load design should reflect the code sections of the Florida Building Code 2004 that relate to wind Load design code requirements.
- ✓ 2. Please show compliance with sections R308.4 of the FRC-2004 for the window in bath number 2 hazardous locations: Glazing in doors and enclosures for hot tubs, whirlpools, saunas, steam rooms, bathtubs and showers. Glazing in any part of a building wall enclosing these compartments where the bottom exposed edge of the glazing is less than 60 inches (1524 mm) measured vertically above any standing or walking surface.

3. If the elevation of the covered porches finished floor will be 30" above the finished grade please show compliance with sections R312.1 of the FRC-2004 Guards required: Porches, balconies or raised floor surfaces located more than 30 inches (762 mm) above the floor or grade below shall have guards not less than 36 inches (914 mm) in height. Open sides of stairs with a total rise of more than 30 inches (762 mm) above the floor or grade below shall have guards not less than 34 inches (864 mm) in height measured vertically from the nosing of the treads.

R312.2 Guard opening limitations.

Required guards on open sides of stairways, raised floor areas, balconies and porches shall have intermediate rails or ornamental closures which do not allow passage of a sphere 4 inches (102mm) or more in diameter.

Exceptions: The triangular openings formed by the riser, tread and bottom rail of a guard at the open side of a stairway are permitted to be of such a size that a sphere 6 inches (152 mm) cannot pass through.

1607.7.1.1 Concentrated load.

Handrail assemblies and guards shall be able to resist a single concentrated load of 200 pounds (0.89 kN), applied in any direction at any point along the top, and have attachment devices and supporting structure to transfer this loading to appropriate structural elements of the building. Please show on the plans a design detail drawing of both interior and exterior guards to comply with the above code requirement.

4. Please show compliance with sections R309 of the FRC-2004 R309.1 Opening protection. Openings from a private garage directly into a room used for sleeping purposes shall not be permitted. Other openings between the garage and residence shall be equipped with solid wood doors not less than 1 3/8 inches (35 mm) in thickness, solid

or honeycomb core steel doors not less than 13/8 inches (35 mm) thick, or 20-minute fire-rated doors. R309.1.1 Duct penetration: Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel or other approved material and shall have no openings into the garage. R309.2 Separation required: The garage shall be separated from the residence and its attic area by not less than ½-inch (12.7 mm) gypsum board applied to the garage side. Garages beneath habitable rooms shall be separated from all habitable rooms above by not less than 5/8-inch (15.9 mm) Type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than ½-inch (12.7 mm) gypsum board or equivalent.

Thank you,



Joe Haltiwanger
Plan Examiner
Columbia County Building Department

COLUMBIA COUNTY OFFICE OF OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 07-5S-17-09151-007

Building permit No. 000023811

Use Classification SFD, UTILITY

Fire: 35.52

Permit Holder MACK ROBINSON

Waste: 73.50

Owner of Building ROGER LITTLE, JR

Total: 109.02

Location: 401 SW LITTLE ROAD, LAKE CITY, FL

Date: 04/10/2006

Harry Becker

Building Inspector



POST IN A CONSPICUOUS PLACE
(Business Places Only)

23811

McKinze
399 SW CR 138
Ft. White

Notice of Preventative Treatments for Termites
(as required by Florida Building Code (FBC) 104.2.6)

EDWARDS PEST CONTROL, 386 454 3051
241 SE HARDIN COURT, HIGH SPRINGS, FL, 32643

Address of Treatment or Lot/Block of Treatment
6/30/05 4:00 pm Jim Riley
Date Time Applicator
PREMISE Imicloprid 50 GALS
Product Used Chemical used (active ingredient) Number of gallons applied
.05 450 sq ft _____
Percent Concentration Area treated (square feet) Linear feet treated

Stage of treatment (Horizontal, Vertical, Adjoining Slab, retreat of disturbed area)

As per 104.2.6 - If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial and date this line 11/14/06

Notice Of Inspection
and/or Treatment

11/14/06
Date of Inspection

11/14/06
Date of Treatment

PREMISE
Pesticide Used

SUB. TER.
FINAL PREPARATION AND ADDITION
Wood Destroying Organism Treated

Pursuant to Chapter 482, Florida Statutes 482.226(6), this notice is required to be posted. Any licensee who performs control of any wood destroying organism shall post notice of said treatment immediately adjacent to the access to the attic or crawl area or other readily accessible area of the property treated.

Edwards Pest Control
241 SE Hardin Court
High Springs, FL 32643
(386) 454-3051

**RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR
FLORIDA BUILDING CODE 2004 and FLORIDA RESIDENTIAL CODE 2004
WITH AMENDMENTS ONE (1) AND TWO (2) FAMILY DWELLINGS**

ALL REQUIREMENTS ARE SUBJECT TO CHANGE
EFFECTIVE OCTOBER 1, 2005

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 16 OF THE FLORIDA BUILDING CODE 2004 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1609 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE ----- 110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant	Plans Examiner
-----------	----------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

☒	☒
-------------------------------------	-------------------------------------

All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.

Designers name and signature on document (FBC 106.1). If licensed architect or engineer, official seal shall be affixed.

Site Plan including:

- a) Dimensions of lot
- b) Dimensions of building set backs
- c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.
- d) Provide a full legal description of property.

Wind-load Engineering Summary, calculations and any details required

Plans or specifications must state compliance with FBC Section 1609.

The following information must be shown as per section 1603.1.4 FBC

- a. Basic wind speed (3-second gust), miles per hour (km/hr).
- b. Wind importance factor, I_w , and building classification from Table 1604.5 or Table 6-1, ASCE 7 and building classification in Table 1-1, ASCE 7.
- c. Wind exposure, if more than one wind exposure is utilized, the wind exposure and applicable wind direction shall be indicated.
- d. The applicable enclosure classifications and, if designed with ASCE 7, internal pressure coefficient.
- e. Components and Cladding. The design wind pressures in terms of psf (kN/m^2) to be used for the design of exterior component and cladding materials not specifically designed by the registered design professional.

Elevations including:

- a) All sides
- b) Roof pitch
- c) Overhang dimensions and detail with attic ventilation

- 2

c. Crawl space (if applicable)

☐

☒

b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC 106.1.1.2) Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termiticide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

☐

☐

c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment
- g) Arc Fault Circuits (AFCI) in bedrooms
- h) Exhaust fans in bathroom

HVAC information

- a) Energy Calculations (dimensions shall match plans)
- b) Manual J sizing equipment or equivalent computation
- c) Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

*****Notice Of Commencement Required Before Any Inspections Will Be Done**

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

☒

☒

☐

☐

☐

☐

☐

☐

☐

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☒

☐

☐

☐

☐

☐

☐

☐

☒

☐

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

1. **Building Permit Application:** A current Building Permit Application form is to be completed and submitted for all residential projects.
2. **Parcel Number:** The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested.
3. **Environmental Health Permit or Sewer Tap Approval:** A copy of the Environmental Health permit, existing septic approval or sewer tap approval is required before a building permit can be issued. (386) 758-1058 (Toilet facilities shall be provided for construction workers)
4. **City Approval:** If the project is to be located within the city limits of the Town of Fort White, prior approval is required. The Town of Fort White approval letter is required to be submitted by the owner or contractor to this office when applying for a Building Permit. (386) 497-2321
5. **Flood Information:** All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.8 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.7 of the Columbia County Land Development Regulations. **CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.**
A development permit will also be required. Development permit cost is \$50.00
6. **Driveway Connection:** If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial. **If the project is to be located on a F.D.O.T. maintained road, than an F.D.O.T. access permit is required.**
7. **911 Address:** If the project is located in an area where the 911 address has been issued, then the proper paperwork from the 911 Addressing Department must be submitted. (386) 752-8787

ALL REQUIRED INFORMATION IS TO BE SUBMITTED FOR REVIEW. YOU WILL BE NOTIFIED WHEN YOUR APPLICATION AND PLANS ARE APPROVED AND READY TO PERMIT. PLEASE DO NOT EXPECT OR REQUEST THAT PERMIT APPLICATIONS BE REVIEWED OR APPROVED WHILE YOU ARE HERE – TIME WILL NOT ALLOW THIS –PLEASE DO NOT ASK

PRODUCT APPROVAL SPECIFICATION SHEET

Location: _____ Project Name: _____

As required by Florida Statute 553.842 and Florida Administrative Code 9B-72, please provide the information and the product approval number(s) on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit on or after April 1, 2004. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. More information about statewide product approval can be obtained at www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
A. EXTERIOR DOORS			
1. Swinging	<i>Maxxmate</i>	<i>Steel</i>	<i>FL 18</i>
2. Sliding			
3. Sectional			
4. Roll up			
5. Automatic			
6. Other			
B. WINDOWS			
1. Single hung	<i>capital</i>		<i>FL 695</i>
2. Horizontal Slider			
3. Casement			
4. Double Hung			
5. Fixed			
6. Awning			
7. Pass-through			
8. Projected			
9. Mullion			
10. Wind Breaker			
11. Dual Action			
12. Other			
C. PANEL WALL			
1. Siding	<i>James Hardy</i>		<i>FL 889</i>
2. Soffits			
3. EIFS			
4. Storefronts			
5. Curtain walls			
6. Wall louver			
7. Glass block			
8. Membrane			
9. Greenhouse			
10. Other			
D. ROOFING PRODUCTS			
1. Asphalt Shingles			
2. Underlayments			
3. Roofing Fasteners			
4. Non-structural Metal Rf			
5. Built-Up Roofing			
6. Modified Bitumen			
7. Single Ply Roofing Sys			
8. Roofing Tiles			
9. Roofing Insulation			
10. Waterproofing			
11. Wood shingles /shakes			
12. Roofing Slate			

Category/Subcategory (cont.)	Manufacturer	Product Description	Approval Number(s)
13. Liquid Applied Roof Sys			
14. Cements-Adhesives – Coatings			
15. Roof Tile Adhesive			
16. Spray Applied Polyurethane Roof			
17. Other			
E. SHUTTERS			
1. Accordion			
2. Bahama			
3. Storm Panels			
4. Colonial			
5. Roll-up			
6. Equipment			
7. Others			
F. SKYLIGHTS			
1. Skylight			
2. Other			
G. STRUCTURAL COMPONENTS			
1. Wood connector/anchor	Simpson	H16 5xH4	FL 123 123
2. Truss plates			
3. Engineered lumber			
4. Railing			
5. Coolers-freezers			
6. Concrete Admixtures			
7. Material			
8. Insulation Forms			
9. Plastics			
10. Deck-Roof			
11. Wall			
12. Sheds			
13. Other			
H. NEW EXTERIOR ENVELOPE PRODUCTS			
1.			
2.			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) the performance characteristics which the product was tested and certified to comply with, 3) copy of the applicable manufacturers installation requirements.

I understand these products may have to be removed if approval cannot be demonstrated during inspection


Contractor or Contractor's Authorized Agent Signature

Print Name

Date

Location

Permit # (FOR STAFF USE ONLY)



NOTICE:

ADDRESSES BY APPOINTMENT ONLY!

TO OBTAIN A 9-1-1 ADDRESS THE REQUESTER MUST CONTACT THE COLUMBIA COUNTY 9-1-1 ADDRESSING DEPARTMENT AT (386) 752-8787 FOR AN APPOINTMENT TIME AND DATE:


YOU CAN NOT OBTAIN A NEW ADDRESS OVER THE TELEPHONE. MUST MAKE AN APPOINTMENT!

THE ADDRESSING DEPARTMENT IS LOCATED AT 263 NW LAKE CITY AVENUE (OFF OF WEST U.S. HIGHWAY 90 WEST OF INTERSTATE 75 AT THE COLUMBIA COUNTY EMERGENCY OPERATIONS CENTER).

THE REQUESTER WILL NEED THE FOLLOWING:

1. THE PARCEL OR TAX ID NUMBER (SAMPLE: "25-4S-17-12345-123" OR "R12345-123") FOR THE PROPERTY.
2. A PLAT, PLAN, SITE PLAN, OR DRAWING SHOWING THE PROPERTY LINES OF THE PARCEL.
 - a. LOCATION OF PLANNED RESIDENT OR BUSINESS STRUCTURE ON THE PROPERTY WITH DISTANCES FROM TWO OF THE PROPERTY LINES TO THE STRUCTURE (SEE SAMPLE BELOW).
 - b. LOCATION OF THE ACCESS POINT (DRIVEWAY, ETC.) ON THE ROADWAY FROM WHICH LOCATION IS TO BE ADDRESSED WITH A DISTANCE FROM A PARALLEL PROPERTY LINE AND OR PROPERTY CORNER (SEE SAMPLE BELOW).
 - c. TRAVEL OF THE DRIVEWAY FROM THE ACCESS POINT TO THE STRUCTURE (SEE SAMPLE BELOW).


SAMPLE:



NOTE: 5 TO 7 WORKING DAYS MAY BE REQUIRED IF ADDRESSING DEPARTMENT NEEDS TO CONDUCT AN ON SITE SURVEY.



ELK



**PRESTIQUE®
HIGH DEFINITION®**



RAISED PROFILE™

**Prestique Plus *High Definition*
and Prestique Gallery Collection™**

Product size	13⅞" x 39⅞"	50-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.
Exposure	5⅞"	
Pieces/Bundle	16	
Bundles/Square	4/98.5 sq.ft.	
Squares/Pallet	11	

Raised Profile

Product size	13⅞" x 38⅞"	30-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.
Exposure	5⅞"	
Pieces/Bundle	22	
Bundles/Square	3/100 sq.ft.	
Squares/Pallet	16	

Prestique I *High Definition*

Product size	13⅞" x 39⅞"	40-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.
Exposure	5⅞"	
Pieces/Bundle	16	
Bundles/Square	4/98.5 sq.ft.	
Squares/Pallet	14	

HIP AND RIDGE SHINGLES

Seal-A-Ridge® w/FLX™
Size: 12" x 12"
Exposure: 6⅞"
Pieces/Bundle: 45
Coverage: 4 Bundles = 100 linear feet

Prestique *High Definition*

Product size	13⅞" x 38⅞"	30-year limited warranty period: non-prorated coverage for shingles and application labor for the initial 5 years, plus an option for transferability*; prorated coverage for application labor and shingles for balance of limited warranty period; 5-year limited wind warranty*.
Exposure	5⅞"	
Pieces/Bundle	22	
Bundles/Square	3/100 sq.ft.	
Squares/Pallet	16	

Elk Starter Strip

52 Bundles/Pallet
18 Pallets/Truck
936 Bundles/Truck
19 Pieces/Bundle
1 Bundle = 120.33 linear feet

Available Colors: Antique Slate, Weatheredwood, Shakeswood, Sablewood, Hickory, Barkwood**, Forest Green, Wedgewood**, Birchwood**, Sandalwood.
Gallery Collection: Balsam Forest®, Weathered Sage®, Sienna Sunset®.

All Prestique, Raised Profile and Seal-A-Ridge roofing products contain Elk WindGuard® sealant. WindGuard activates with the sun's heat, bonding shingles into a wind and weather resistant cover that resists blow-offs and leaks.

Check for availability with built-in StainGuard® treatment to inhibit the discoloration of roofing granules caused by the growth of certain types of algae. Not available in Sablewood.

All Prestique and Raised Profile shingles meet UL® Wind Resistant (UL 997) and Class "A" Fire Ratings (UL 790); and ASTM Specifications D 3018, Type-I; D 3161, Type-I; E 108 and the requirements of ASTM D 3462.

All Prestique and Raised Profile shingles meet the latest Metro Dade building code requirements.

*See actual limited warranty for conditions and limitations.
**Check for product availability.

SPECIFICATIONS

SCOPE: Work includes furnishing all labor, materials and equipment necessary to complete installation of (name) shingles specified herein. Color shall be (name of color). Hip and ridge type to be Elk Seal-A-Ridge with formula FLX.

All exposed metal surfaces (flashing, vents, etc.) to be painted with matching Elk roof accessory paint.

PREPARATION OF ROOF DECK: Roof deck to be dry, well-seasoned 1" x 6" (25.4mm x 152.4mm) boards; exterior-grade plywood (exposure 1 rated sheathing) at least 3/8" (9.525mm) thick conforming to the specifications of the American Plywood Association; 7/16" (11.074mm) oriented strandboard; or chipboard. Most fire retardant plywood decks are NOT approved substrates for Elk shingles. Consult Elk Field Service for application specifications over other decks and other slopes.

MATERIALS: Underlayment for standard roof slopes, 4" per foot (101.6/304.8mm) or greater: apply non-perforated No. 15 or 30 asphalt-saturated felt underlayment. For low slopes (4" per foot (101.6/304.8mm) to a minimum of 2" per foot (50.8/304.8mm)), use two plies of underlayment overlapped a minimum of 19". Fasteners shall be of sufficient length and holding power for securing material as required by the application instructions printed on shingle wrapper.

For areas where algae is a problem, shingles shall be (name) with StainGuard treatment, as manufactured by the Elk Tuscaloosa plant. Hip and ridge type to be Seal-A-Ridge with formula FLX with StainGuard treatment.

Complete application instructions are published by Elk and printed on the back of every shingle bundle. All

warranties are contingent upon the correct installation as shown on the instructions. These instructions are the minimum required to meet Elk application requirements. In some areas, building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements less than those contained in its application instructions.

For specifications in CSI format, call 800.354.SPEC (7732) or e-mail specinfo@elkcorp.com.

**SOUTHEAST &
ATLANTIC OFFICE:**
800.945.5551

CORPORATE HEADQUARTERS:
800.354.7732


PLANT LOCATION:
800.945.5545

ELK
www.elkcorp.com




SSOOT 01.02

DIRECTIONS FOR APPLICATION

Please read carefully. Failure to follow these instructions may void the product warranty. See specific application instructions for Prestique® Plus and Prestique Gallery Collection™ 110 MPH, and Prestique I 90 MPH limited wind warranty requirements.



VALLEY CONSTRUCTION OPTION (California Open and California Closed are also acceptable) NOTE: For complete ARMA valley installation details, see ARMA Residential Asphalt Roofing Manual.



DIRECTIONS FOR APPLICATION

These application instructions are the minimum required to meet Elk's application requirements. Your failure to follow these instructions may void the product warranty. In some areas, the building codes may require additional application techniques or methods beyond our instructions. In these cases, the local code must be followed. Under no circumstances will Elk accept application requirements that are less than those printed here. Shingles should not be jammed tightly together. All attics should be properly ventilated. Note: It is not necessary to remove tape on back of shingle.

DECK PREPARATION

Roof decks should be dry, well-seasoned 1" x 6" boards or exterior grade plywood minimum 3/8" thick and conform to the specifications of the American Plywood Association or 7/16" oriented strandboard, or 7/16" chipboard.

UNDERLAYMENT

Apply underlayment (Non-Perforated No. 15 or 30 asphalt saturated felt). Cover drip edge at eaves only.

or low slope (2/12 up to 4/12), completely cover the deck with two layers of underlayment overlapping a minimum of 18". Begin by fastening a 19" wide strip of underlayment placed along the eaves. Place a full 36" wide sheet over the starter, horizontally placed along the eaves and completely overlapping the starter strip.

EAVE FLASHING FOR ICE DAMS (ASK A ROOFING CONTRACTOR, REFER TO ARMA MANUAL OR CHECK LOCAL CODES)

or standard slope (4/12 to less than 21/12), use coated roll roofing of no less than 50 pounds over the felt underlayment extending from the eave edge to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

or low slope (2/12 up to 4/12), use a continuous layer of asphalt elastic cement between the two plies of underlayment from the eave edge up roof to a point at least 24" beyond the inside wall of the living space below or one layer of a self-adhered eave and flashing membrane.

Consult the Elk Field Service Department for application specifications over other decks and other slopes.

STARTER SHINGLE COURSE

USE AN ELK STARTER STRIP OR A STRIP SHINGLE INVERTED WITH THE HEADLAP APPLIED AT THE EAVE EDGE. With at least 4" trimmed from the end of the first shingle, start at the rake edge overhanging the eave 1/2" to 3/4". Fasten 2" from the lower edge and 1" from each side.

FIRST COURSE

Start at rake and continue course with full shingles laid flush with the starter course. Shingles may be applied with a course alignment of 45° on the roof.

SECOND COURSE

Start at the rake with the shingle having 10" trimmed off and continue across roof with full shingles.

THIRD COURSE

FOURTH COURSE

Start at the rake and continue with full shingles across roof.

FIFTH AND SUCCEEDING COURSES.

Repeat application as shown for second, third, and fourth courses. Do not rack shingles straight up the roof.

VALLEY CONSTRUCTION

Open, woven and closed cut valleys are acceptable when applied by Asphalt Roofing Manufacturing Association (ARMA) recommended procedures. For metal valleys, use 36" wide vertical underlayment prior to applying 18" metal flashing (secure edge with nails). No nails are to be within 6" of valley center.

RIDGE CONSTRUCTION

For ridge construction use Class "A" Seal-A-Ridge® with formula FLX™ (See ridge package for installation instructions.)

FASTENERS

While nailing is the preferred method for Elk shingles, Elk will accept fastening methods according to the following instructions.

Always nail or staple through the fastener line or on products without fastener lines, nail or staple between and in line with sealant dots.

NAILS: Corrosive resistant, 3/8" head, minimum 12-gauge roofing nails. Elk recommends 1-1/4" for new roofs and 1-1/2" for re-roofs. In cases where you are applying shingles to a roof that has an exposed overhang, for new roofs only, 3/4" ring shank nails are allowed to be used from the eave's edge to a point up the roof that is past the outside wall line. 1" ring shank nails allowed for re-roof.

STAPLES: Corrosive resistant, 16-gauge minimum, crown width minimum of 15/16". Note: An improperly adjusted staple gun can result in raised staples that can cause a fish-mouthed appearance and can prevent sealing.

Fasteners should be long enough to obtain 3/4" deck penetration or penetration through deck, whichever is less.


MANSARD APPLICATIONS

Correct fastening is critical to the performance of the roof. For slopes exceeding 50° (or 21/12) use six fasteners per shingle. Locate fasteners in the fastener area 1" from each side edge with the remaining four fasteners equally spaced along the length of the double thickness (laminated) area. Only fastening methods according to the above instructions are acceptable.

LIMITED WIND WARRANTY

For a Limited Wind Warranty, all Prestique and Raised Profile™ shingles must be applied with 4 properly placed fasteners, or in the case of mansard applications, 6 properly placed fasteners per shingle.

For a Limited Wind Warranty up to 110 MPH for Prestique Gallery Collection or Prestique Plus or 90 MPH for Prestique I, shingles must be applied with 6 properly placed NAILS per shingle. SHINGLES APPLIED WITH STAPLES WILL NOT QUALIFY FOR THIS ENHANCED LIMITED WIND WARRANTY. Also, Elk Starter Strip shingles must be applied at the eaves and rake edges to qualify Prestique Plus, Prestique Gallery Collection and Prestique I shingles for this enhanced Limited Wind Warranty. Under no circumstances should the Elk



HELP STOP BLOW-OFFS AND CALL-BACKS

A minimum of four fasteners must be driven into the DOUBLE THICKNESS (laminated) area of the shingle. Nails or staples must be placed along – and through – the "fastener line" or on products without fastener lines, nail or staple between and in line with sealant dots. CAUTION: Do not use fastener line for shingle alignment.




Refer to local codes which in some areas may require specific application techniques beyond those Elk has specified. All Prestique and Raised Profile shingles have a U.L.® Wind Resistance Rating when applied in accordance with these instructions using nails or staples on re-roofs as well as new construction.

CAUTION TO WHOLESALER: Careless and improper storage or handling can harm fiberglass shingles. Keep these shingles completely covered, dry, reasonably cool, and protected from the weather. Do not store near various sources of heat. Do not store in direct sunlight until applied. DO NOT DOUBLE STACK. Systematically rotate all stock so that the material that has been stored the longest will be the first to be moved out.

© 2002 Elk Corporation of Dallas.

All trademarks, ®, are registered trademarks of Elk Corporation of Dallas, an ELCDOR company. Raised Profile, RidgeCrest, Gallery Collection and FLX are trademarks pending registration of Elk Corporation of Dallas. UL is a registered trademark of Underwriters Laboratories, Inc.

ELK
www.elkcorp.com



STRUCTURAL TEST REPORT SUMMARY

Rendered to:

MI HOME PRODUCTS, INC.


SERIES/MODEL: 650

TYPE: Twin Aluminum Single Hung Window

Title of Test	Results
Overall Design Pressure	35.0 psf
Operating Force	18 lb max.
Air Infiltration	0.29 cfm/ft ²
Water Resistance	5.25 psf
Structural Test Pressure	70.5 psf


Reference should be made to Report No. 01-36060.02 for complete test specimen description and data.


For ARCHITECTURAL TESTING, INC.


Scott D. Kramer, Technician

SDK:nlb/baw




28 MARCH 2002



Architectural Testing

STRUCTURAL TEST REPORT

Rendered to:

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-36060.02
Test Date: 11/04/99
Report Date: 03/26/02
Expiration Date: 11/04/03

Project Summary: Architectural Testing, Inc. (ATI) was contracted to perform tests on a Series/Model 650, twin aluminum single hung window at MI Home Products' test facility in Elizabethville, Pennsylvania. Test specimen description and results are reported herein.

Test Specification The test specimen was evaluated in accordance with the following:

ASTM E 283-91, *Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*

ASTM E 330-97, *Standard Test Method for Structural Performance of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference*

ASTM E 547-96, *Standard Test Method for Water Penetration of Exterior Windows, Curtain Walls, and Doors by Cyclic Static Air Pressure Differential*

Test Specimen Description:

Series/Model: 650

Type: Twin Aluminum Single Hung Window


Overall Size: 5' 10-1/4" wide by 5' 0" high

Active Size (2): 2' 8-3/4" wide by 2' 6-1/4" high


Fixed Daylight Opening Size (2): 2' 6- 1/4" wide by 2' 3" high

Screen Size (2): 2' 7-3/4" wide by 2' 4-1/4" high

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com



Allen H. Reeves
28 MARCH 2002



Test Specimen Description: (Continued)

Finish: All aluminum was painted white.

Glazing Details: Both the active sash and fixed lites utilized 5/8" thick insulating glass fabricated from two sheets of 3/32" thick clear annealed glass and a desiccant filled metal spacer system. The active sash were channel glazed with a flexible wedge gasket. The fixed lites were interior glazed, back bedded with single sided adhesive foam tape and held-in-place with PVC snap-in glazing beads.

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.270" backed by 0.190" high polypile with center fin	1 Row	Fixed meeting stile
3/8" high vinyl wrapped foam bulb	1 Row	Bottom rail
0.187" backed by 0.250" high polypile with center fin	2 Rows	Stiles
1/4" high polypile dust plug	2 Rows	Ends of bottom rail, top of each stile


Frame Construction: Frame was constructed of extruded aluminum members and all corners were coped, butted, sealed, and fastened with two screws per corner. The fixed meeting rail was attached to the jambs with a plastic clip and two screws per end.


Mullion Construction: The mullion was constructed of an extruded aluminum member. It was fastened to the head and sill with four screws per end. All screw heads were sealed as well as the butt joint at the sill.

Sash Construction: The sash were constructed of extruded aluminum members and all corners were coped, butted, and fastened with one screw per corner.

Screen Construction: The screen was constructed of rolled aluminum members and the corners were keyed. The screen mesh was held-in-place with a flexible spline.

Allen M. Reeves
28 MARCH 2002





Test Specimen Description: (Continued)

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Plastic tilt latches	4	Ends of interior meeting rail
Metal pivot bars	4	Ends of the bottom rails
Metal sweep lock	2	Midspan of interior meeting rail
Metal keeper	2	Midspan of fixed meeting rail
Sash stops	4	One per jamb
Block and tackle balance system	4	One per jamb
Spring loaded latch pins	2	6" from ends of screen top rail

Drainage:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Sloped sill		Sill
1/4" wide by 3/16" high weepslot	4	Ends of exterior vertical sill leg

Installation: The test unit was installed into the 2" x 8" nominal Spruce-Pine-Fir #2 wood test buck utilizing the integral nailing fin and 1" roofing nails. Five per top, bottom, and sides of the nail fin were evenly spaced. The nail fin was bedded in a silicone sealant.



Allen N. Reeves
28 MARCH 2002



Test Results

The results are tabulated as follows:


<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
Air Infiltration per ASTM E 283-91		
@ 0.56 psf (15 mph)	0.15 cfm/ft ²	0.30 cfm/ft ²
@ 1.57 psf (25 mph)	0.29 cfm/ft ²	0.30 cfm/ft ²
Water Resistance per ASTM E 547-96 (with and without screen)		
WTP = 5.25 psf	No leakage	No leakage
Uniform Load Structural per ASTM E 330-97 (Measurements reported were taken on the meeting rail) (load held for 33 seconds)		
@ 47.0 psf (exterior)	0.010"	0.24" max.
@ 47.0 psf (interior)	0.015"	0.24" max.

Note: No end measurements were taken on the member measured. The measurements stated above include displacement as well as bending. Only permanent sets were recorded, not deflection measurements. This statement applies to all uniform load tests performed.

Uniform Load Structural per ASTM E 330-97 (Measurements reported were taken on the meeting rail) (load held for 10 seconds)		
@ 70.5 psf (exterior)	0.060"	0.24" max
@ 70.5 psf (interior)	0.040"	0.24" max


Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:



Scott D. Kramer
Technician

SDK:nlb/baw
01-36060.02



Allen N. Reeves, P.E.
Director - Engineering Services
28 MARCH 2002




X

Opaque Inswing Unit

COP-WL-JH4101-02

WOOD-EDGE STEEL DOORS

APPROVED ARRANGEMENT:



Note:
Units of other sizes are covered by this report as long as the panel used does not exceed 3'0" x 6'8".

Single Door
Maximum unit size = 3'0" x 6'8"

Design Pressure
+66.0/-66.0

limited water unless special threshold design is used.

Large Missile Impact Resistance

Hurricane protective system (shutters) is NOT REQUIRED.

Actual design pressure and impact resistant requirements for a specific building design and geographic location is determined by ASCE 7-national, state or local building codes specify the edition required.



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.itssemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

MINIMUM ASSEMBLY DETAIL:

Compliance requires that minimum assembly details have been followed – see MAD-WL-MA0001-02.

MINIMUM INSTALLATION DETAIL:

Compliance requires that minimum installation details have been followed – see MID-WL-MA0001-02.

APPROVED DOOR STYLES:



Flush



Arch Top 3-panel



3-panel



6-panel



New England 4-panel



Eyebrow 4-panel



8-panel



9-panel



15-panel



5-panel



5-panel with scroll



Eyebrow 5-panel



Eyebrow 5-panel with scroll

1

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product detail subject to change without notice.



Exclusively from

Masonite
Masonite International Corporation

X

Opaque Inswing Unit

COP-WL-JH4101-02

WOOD-EDGE STEEL DOORS

CERTIFIED TEST REPORTS:

NCTL 210-2185-1, 2, 3

Certifying Engineer and License Number: Barry D. Portney, P.E. / 16258.

Unit Tested in Accordance with Miami-Dade BCCO PA201, PA202 and PA203.

Door panels constructed from 26-gauge 0.017" thick steel skins. Both stiles constructed from wood. Top end rails constructed of 0.041" steel. Bottom end rails constructed of 0.021" steel. Interior cavity of slab filled with rigid polyurethane foam core.

Frame constructed of wood with an extruded aluminum threshold.

PRODUCT COMPLIANCE LABELING:

TESTED IN ACCORDANCE WITH
MIAMI-DADE BCCO
PA201, PA202 & PA203

COMPANY NAME
CITY, STATE

To the best of my knowledge and ability the above side-hinged exterior door unit conforms to the requirements of the 2001 Florida Building Code, Chapter 17 (Structural Tests and Inspections).

Kurt L Balthaz

State of Florida, Professional Engineer
Kurt Balthazor, P.E. – License Number 56533



Test Data Review Certificate #3026447A and COP/Test Report Validation Matrix #3026447A-001 provides additional information - available from the ITS/WH website (www.etlsemko.com), the Masonite website (www.masonite.com) or the Masonite technical center.

2

Johnson
EntrySystems

June 17, 2002
Our continuing program of product improvement makes specifications, design and product details subject to change without notice.



Exclusively from

Masonite International Corporation



**AAMA/NWWDA 101/I.S.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.

SERIES/MODEL: 650

TYPE: Aluminum Picture Window

Title of Test	Results
Rating	F-R45 60 x 80
Overall Design Pressure	+45.0 psf -47.2 psf
Air Infiltration	0.04 cfm/ft ²
Water Resistance	8.25 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41135.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess, Technician

MAH:nlb



Allen N. Reeves
1 APRIL 2002



AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41135.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650, aluminum picture window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a F-R45 60 x 80 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650

Type: Aluminum Picture Window

Overall Size: 5' 0" wide by 6' 8" high

Daylight Opening Size: 4' 9-1/4" wide by 6' 5-1/4" high

Finish All aluminum was white.

Glazing Details: The test specimen utilized 7/8" thick, sealed insulating glass constructed from two sheets of 3/16" thick, clear annealed glass and a metal reinforced butyl spacer system. The glass was interior glazed against double-sided adhesive foam tape and secured with aluminum snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss.

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck. #8 x 2-1/2" installation screws were utilized 18" on center around the interior perimeter. Polyurethane was utilized to seal the exterior.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.04 cfm/ft ²	0.3 cfm/ft ² max.
<i>Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.</i>			
	Water Resistance (ASTM E 547-00) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.01" 0.01"	0.41" max. 0.41" max.
2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.0" 0.01"	0.29" max. 0.29" max.

Allen H. Reeves
1 APRIL 2002





Test Results: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
	Forced Entry Resistance (ASTM F 588-97)		
	Type: D		
	Grade: 10		
	Hand and Tool Manipulation Test	No entry	No entry
<u>Optional Performance</u>			
4.3	Water Resistance (ASTM E 547-00) WTP = 8.25 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.02"	0.41" max.
	@ 47.2 psf (negative)	0.02"	0.41" max.
	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the jamb) (Loads were held for 10 seconds)		
	@ 67.5 psf (positive)	0.01"	0.29" max.
	@ 70.8 psf (negative)	0.02"	0.29" max.

Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess
Technician

MAH:nlb
01-41135.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002





**AAMA/NWDA 101/I.S.2-97
TEST REPORT SUMMARY**

Rendered to:

MI HOME PRODUCTS, INC.

**SERIES/MODEL: 650 Fin
TYPE: Aluminum Single Hung Window**

Title of Test	Results
Rating	H-R40 52 x 72
Overall Design Pressure	+45.0 psf -47.2 psf
Operating Force	11 lb max.
Air Infiltration	0.13 cfm/ft ²
Water Resistance	6.00 psf
Structural Test Pressure	+67.5 psf -70.8 psf
Deglazing	Passed
Forced Entry Resistance	Grade 10

Reference should be made to Report No. 01-41134.01 dated 03/26/02 for complete test specimen description and data.

For ARCHITECTURAL TESTING, INC.

Mark A. Hess, Technician

MAH:nlb

Allen M. Reeves
1 APRIL 2002





Architectural Testing

AAMA/NWWDA 101/I.S.2-97 TEST REPORT

Rendered to

MI HOME PRODUCTS, INC.
650 West Market Street
P.O. Box 370
Gratz, Pennsylvania 17030-0370

Report No: 01-41134.01
Test Date: 03/07/02
Report Date: 03/26/02
Expiration Date: 03/07/06

Project Summary: Architectural Testing, Inc. (ATI) was contracted by MI Home Products, Inc. to perform tests on Series/Model 650 Fin, aluminum single hung window at their facility located in Elizabethville, Pennsylvania. The samples tested successfully met the performance requirements for a H-R40 52 x 72 rating.

Test Specification: The test specimen was evaluated in accordance with AAMA/NWWDA 101/I.S.2-97, *Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors*.

Test Specimen Description:

Series/Model: 650 Fin

Type: Aluminum Single Hung Window

Overall Size: 4' 4-1/4" wide by 6' 0-3/8" high

Active Sash Size: 4' 1-3/4" wide by 3' 0-5/8" high

Daylight Opening Size: 3' 11-3/8" wide by 2' 9-1/2" high

Screen Size: 4' 0-1/4" wide by 2' 11-1/8" high

Finish: All aluminum was white.

Glazing Details: The active and fixed lites utilized 5/8" thick, sealed insulating glass constructed from two sheets of 1/8" thick, clear annealed glass and a metal reinforced butyl spacer system. The active sash was channel glazed utilizing a flexible vinyl wrap-around gasket. The fixed lite was interior glazed against double-sided adhesive foam tape and secured with PVC snap-in glazing beads.

130 Derry Court
York, PA 17402-9405
phone: 717.764.7700
fax: 717.764.4129
www.archtest.com

Allen N. Reuser
1 APRIL 2002





Test Specimen Description: (Continued)

Weatherstripping:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
0.230" high by 0.270" backed polypile with center fin	1 Row	Fixed meeting rail
0.250" high by 0.187" backed polypile with center fin	2 Rows	Active sash stiles
1/2" x 1/2" dust plug	4 Pieces	Active sash, top and bottom of stiles
1/4" foam-filled vinyl bulb seal	1 Row	Active sash, bottom rail

Frame Construction: The frame was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1" screws through the head and sill into each jamb screw boss. End caps were utilized on the ends of the fixed meeting rail and secured with two 1-1/4" screws per cap. Meeting rail was secured to the frame utilizing two 1-1/4" screws.

Sash Construction: The sash was constructed of extruded aluminum with coped, butted, and sealed corners fastened with two #8 x 1-1/2" screws through the rails into each jamb screw boss.

Screen Construction: The screen was constructed from roll-formed aluminum with keyed corners. The fiberglass mesh was secured with a flexible spline.

Hardware:

<u>Description</u>	<u>Quantity</u>	<u>Location</u>
Metal cam lock with keeper		Midspan, active meeting rail with keeper adjacent on fixed meeting rail
Plastic tilt latch	2	Active sash, meeting rail ends
Metal tilt pin	2	Active sash, bottom rail ends
Balance assembly	2	One in each jamb
Screen plunger	2	4" from rail ends on top rail

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

Drainage: Sloped sill

Reinforcement: No reinforcement was utilized.

Installation: The test specimen was installed into a 2 x 8 #2 Spruce-Pine-Fir wood test buck with #8 x 1-5/8" drywall screws every 8" on center around the nail fin. Polyurethane was used as a sealant under the nail fin and around the exterior perimeter.

Test Results:

The results are tabulated as follows:

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.1	Operating Force	11 lbs	30 lbs max
	Air Infiltration (ASTM E 283-91) @ 1.57 psf (25 mph)	0.13 cfm/ft ²	0.3 cfm/ft ² max

Note #1: The tested specimen meets the performance levels specified in AAMA/NWDA 101/I.S. 2-97 for air infiltration.

	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 2.86 psf	No leakage	No leakage
2.1.4.1	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds) @ 25.9 psf (positive) @ 34.7 psf (negative)	0.42"* 0.43"*	0.26" max. 0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

2.1.4.2	Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds) @ 38.9 psf (positive) @ 52.1 psf (negative)	0.02" 0.02"	0.18" max. 0.18" max.
---------	---	----------------	--------------------------

Allen N. Reeves
1 APRIL 2002





Test Specimen Description: (Continued)

<u>Paragraph</u>	<u>Title of Test - Test Method</u>	<u>Results</u>	<u>Allowed</u>
2.2.1.6.2	Deglazing Test (ASTM E 987) In operating direction at 70 lbs		
	Meeting rail	0.12"/25%	0.50"/100%
	Bottom rail	0.12"/25%	0.50"/100%
	In remaining direction at 50 lbs		
	Left stile	0.06"/12%	0.50"/100%
	Right stile	0.06"/12%	0.50"/100%
	Forced Entry Resistance (ASTM F 588-97)		
	Type: A		
	Grade: 10		
	Lock Manipulation Test	No entry	No entry
	Tests A1 through A5	No entry	No entry
	Test A7	No entry	No entry
	Lock Manipulation Test	No entry	No entry

Optional Performance

4.3	Water Resistance (ASTM E 547-00) (with and without screen) WTP = 6.00 psf	No leakage	No leakage
	Uniform Load Deflection (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 33 seconds)		
	@ 45.0 psf (positive)	0.47"	0.26" max.
	@ 47.2 psf (negative)	0.46"	0.26" max.

**Exceeds L/175 for deflection, but passes all other test requirements.*

Uniform Load Structural (ASTM E 330-97) (Measurements reported were taken on the meeting rail) (Loads were held for 10 seconds)	
@ 67.5 psf (positive)	0.05"
@ 70.8 psf (negative)	0.05"

Allen N. Reeves
1 APRIL 2002





Detailed drawings, representative samples of the test specimen, and a copy of this report will be retained by ATI for a period of four years. The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specification. This report does not constitute certification of this product, which may only be granted by the certification program administrator.

For ARCHITECTURAL TESTING, INC:

Mark A. Hess
Technician

MAH:nlb
01-41134.01

Allen N. Reeves, P.E.
Director - Engineering Services
1 APRIL 2002



LITTLE HVAC LOAD ANALYSIS

for

MACK ROBINSON CONSTRUCTION

Prepared By:

DAVID HALL
DAVID HALL'S INC.
PO BOX 244
LAKE CITY FL. 32056
386-755-9792
10/18/05

Miscellaneous Project Data

Project File Name: MACK ROBINSON, LITTLE

System Input Data

—System 1—	Outdoor Dry Bulb	Outdoor Wet Bulb	Indoor Rel.Hum.	Indoor Dry Bulb	Grains Difference
Winter:	27	N/A	N/A	72	N/A
Summer:	96	78	50%	75	51

External Overhangs

No.	Projection	Offset	No.	Projection	Offset
1	3	1	6	0	0
2	5	0	7	0	0
3	4	0.5	8	0	0
4	0	0	9	0	0
5	0	0	10	0	0

Duct Sizing Inputs

	Runouts	Main Trunk
Duct Material:	Flexible Duct	Fiberglass Duct Board
Roughness Factor:	0.010000	0.003000
Pressure Drop:	0.1000 In.wg/100 Ft.	0.1000 In.wg/100 Ft.
Minimum Velocity:	450.0 Ft./Minute	650.0 Ft./Minute
Maximum Velocity:	750.0 Ft./Minute	900.0 Ft./Minute
Minimum Height:	0 Inches	0 Inches
Maximum Height:	0 Inches	0 Inches

Outside Air Data

	Winter	Summer
Infiltration:	0.900 AC/Hr	0.400 AC/Hr
Volume of Conditioned Space:	X 13304 Cu.Ft.	X 13304 Cu.Ft.
	11,974 Cu.Ft./Hr	5,322 Cu.Ft./Hr
	X 0.0167	X 0.0167
Total Building Infiltration:	199.56 CFM	88.69334 CFM
Total Building Ventilation:	0 CFM	0 CFM
—System 1—		
Infiltration & Ventilation Sensible Gain Multiplier:	23.10 = (1.10 X 21.00 Summer Temp. Difference)	
Infiltration & Ventilation Latent Gain Multiplier:	34.86 = (0.68 X 51.27 Grains Difference)	
Infiltration & Ventilation Sensible Loss Multiplier:	49.50 = (1.10 X 45.00 Winter Temp. Difference)	

Total Building Summary Loads

Component Description	Area Quan	Sen. Loss	Lat. Gain	Sen. Gain	Total Gain
3C Window Double Pane Clear Glass Metal Frame	231	7,537	0	7,863	7,863
9G French Door Double Clear Glass Wood Frame	21	493	0	491	491
10D Door Wood Solid Core	42	870	0	476	476
12C Wall R-11 + 1/2" Gypsum(R-0.5)	1,130	4,577	0	2,502	2,502
16G Ceiling R-30 Insulation	1,612	2,394	0	2,394	2,394
22A Slab on Grade No Edge Insulation	176	6,416	0	0	0
Subtotals for structure:	3,212	22,287	0	13,726	13,726
Active People:	3	0	690	900	1,590
Inactive People:	0	0	0	0	0
Appliances:	0	0	1,200	1,200	2,400
Lighting:	0	0		3,615	
Ductwork:	0	1,608	0	2,149	2,149
Infiltration: Winter CFM: 199.6, Summer CFM: 88.7	294	9,879	3,094	2,049	5,143
Ventilation: Winter CFM: 0.0, Summer CFM: 0.0	0	0	0	0	0
Sensible Gain Total:				23,639	
Temperature Swing Multiplier:				X1.00	
Building Load Totals:		33,774	4,984	23,639	28,623

Check Figures

Total Building Supply CFM:	1074	CFM per square foot:	0.665
Square feet of room area:	1,615	Square feet per ton:	631.281

Building Loads


Total heating required with outside air:	33,774 Btuh	33.774 MBH
Total sensible gain:	23,639 Btuh	83 %
Total latent gain:	4,984 Btuh	17 %
Total cooling required with outside air:	28,623 Btuh	2.385 Tons (based on sensible + latent)
		2.558 Tons (based on 77% sensible capacity)

Notes


Calculations are based on 7th edition of ACCA Manual J.
All computed results are estimates as building use and weather may vary.
Be sure to select a unit that meets both sensible and latent loads.

Building Load Pie Charts

Total
Building
Loss
33,774
BTUH



Total
Building
Gain
28,623
BTUH



System #1 Summary Loads

Component Description	Area Quan	Sen. Loss	Lat. Gain	Sen. Gain	Total Gain
3C Window Double Pane Clear Glass Metal Frame	231	7,537	0	7,863	7,863
9G French Door Double Clear Glass Wood Frame	21	493	0	491	491
10D Door Wood Solid Core	42	870	0	476	476
12C Wall R-11 + 1/2" Gypsum(R-0.5)	1,130	4,577	0	2,502	2,502
16G Ceiling R-30 Insulation	1,612	2,394	0	2,394	2,394
22A Slab on Grade No Edge Insulation	176	6,416	0	0	0
Subtotals for structure:	3,212	22,287	0	13,726	13,726
Active People:	3	0	690	900	1,590
Inactive People:	0	0	0	0	0
Appliances:	0	0	1,200	1,200	2,400
Lighting:	0	0		3,615	
Ductwork:	0	1,608	0	2,149	2,149
Infiltration: Winter CFM: 199.6, Summer CFM: 88.7	294	9,879	3,094	2,049	5,143
Ventilation: Winter CFM: 0.0, Summer CFM: 0.0	0	0	0	0	0
Sensible Gain Total:				23,639	
Temperature Swing Multiplier:				X1.00	
System Load Totals:		33,774	4,984	23,639	28,623

Check Figures

Supply CFM:	1,074	CFM per square foot:	0.665
Square feet of room area:	1,615	Square feet per ton:	631.281

System Loads

Total heating required with outside air:	33,774 Btuh	33.774 MBH
Total sensible gain:	23,639 Btuh	83 %
Total latent gain:	4,984 Btuh	17 %
Total cooling required with outside air:	28,623 Btuh	2.385 Tons (based on sensible + latent)
		2.558 Tons (based on 77% sensible capacity)

Notes

Calculations are based on 7th edition of ACCA Manual J.
 All computed results are estimates as building use and weather may vary.
 Be sure to select a unit that meets both sensible and latent loads.

Room Load Summary Reports

System #1 Room Load Summary

No	Room Name	Area SF	Htg Sens Btuh	Htg Nom CFM	Run Duct Size	Run Duct Vel	Clg Sens Btuh	Clg Lat Btuh	Clg Nom CFM	Zone Adj Fact	Clg Adj CFM	Air Sys CFM
—Zone 1—												
1	Living Room	294	5,532	72	1-10	489	4,346	861	198	1.35	267	198
2	Dining Room	161	4,320	56	1-6	572	2,470	536	112	1.00	112	112
3	Kitchen	136	1,595	21	1-7	466	2,741	1,525	125	1.00	125	125
4	Bedroom#3	179	5,161	67	1-9	462	3,325	473	151	1.35	204	151
5	Bath	70	717	9	1-4	441	846	32	38	1.00	38	38
6	Bedroom#2	166	4,089	53	1-6	481	2,077	316	94	1.00	94	94
7	Utility Room	167	4,125	54	1-6	548	2,368	316	108	1.00	108	108
8	Master Bedroom	206	3,215	42	1-6	514	2,222	546	101	1.00	101	101
9	Master Closet	54	501	7	6-0	0	420	0	19	1.00	19	19
10	Master Bath	109	2,664	35	1-5	583	1,749	158	80	1.00	80	80
11	Foyer	73	1,855	24	1-4	560	1,075	221	49	1.00	49	49
System 1 Totals		1615	33,774	439			23,639	4,984	1,074		1,197	1,074

Main Trunk Size: 16x12 in.

System #1 Cooling System Summary

	Cooling Tons	Sensible/Latent Split	Sensible Btuh	Latent Btuh	Total Btuh
Net Required:	2.385	83%/17%	23,639	4,984	28,623
Recommended:	2.558	77%/23%	23,639	7,061	30,699

Alpine Engineered Products, Inc.

1950 Marley Drive Haines City, FL 33844
Florida Engineering Certificate of Authorization Number: 567
Florida Certificate of Product Approval # FL1999
Page 1 of 1 Document ID:1SQF487-Z0312153242

Truss Fabricator: Anderson Truss Company
Job Identification: 5-399-MACK ROBINSON-LITTLE
Truss Count: 35
Model Code: Florida Building Code 2001
Truss Criteria: ANSI/TPI-1995(STD)/FBC
Engineering Software: Alpine Software,Version 7.04.
Structural Engineer of Record:
Address:
Minimum Design Loads: Roof - 40.0 PSF @ 1.25 Duration
Floor - N/A
Wind - 110 MPH ASCE 7-98 -Closed

Notes:

1. Determination as to the suitability of these truss components for the structure is the responsibility of the building designer/engineer of record, as defined in ANSI/TPI 1-1995 Section 2.2
2. The drawing date shown on this index sheet must match the date shown on the individual truss component drawing.
3. As shown on attached drawings; the drawing number is preceded by: HCUSR487

Details: BRCLBSUB-A11015EC-GBLLETIN

Seal Date: 09/12/2005

-Truss Design Engineer-
Arthur R. Fisher
Florida License Number: 59687
1950 Marley Drive
Haines City, FL 33844

#	Ref	Description	Drawing#	Date
1	88060--A1		05255092	09/12/05
2	88061--A2		05255093	09/12/05
3	88062--A3		05255094	09/12/05
4	88063--A4		05255095	09/12/05
5	88064--A5		05255096	09/12/05
6	88065--A6		05255097	09/12/05
7	88066--AA1		05255098	09/12/05
8	88067--AA2		05255077	09/12/05
9	88068--AA3		05255078	09/12/05
10	88069--AA4		05255079	09/12/05
11	88070--AA5		05255080	09/12/05
12	88071--AA6		05255081	09/12/05
13	88072--AA7		05255082	09/12/05
14	88073--B1		05255099	09/12/05
15	88074--B2		05255083	09/12/05
16	88075--B3		05255084	09/12/05
17	88076--C1-GE		05255100	09/12/05
18	88077--C2		05255085	09/12/05
19	88078--C3		05255086	09/12/05
20	88079--C4		05255087	09/12/05
21	88080--C5		05255088	09/12/05
22	88081--C6		05255089	09/12/05
23	88082--D1		05255101	09/12/05
24	88083--HJA		05255102	09/12/05
25	88084--HJ7		05255103	09/12/05
26	88085--EJ7		05255104	09/12/05
27	88086--J7		05255105	09/12/05
28	88087--J5		05255106	09/12/05
29	88088--J3		05255090	09/12/05
30	88089--J1		05255107	09/12/05
31	88090--MA		05255091	09/12/05
32	88091--AP1		05255108	09/12/05
33	88092--AP2		05255109	09/12/05
34	88093--AP3		05255110	09/12/05
35	88094--AP4		05255111	09/12/05



JOB NO: 5-399

Shim all supports to solid bearing.



TC LL	20.0 PSF	REF	R487 - -	88060
TC DL	10.0 PSF	DATE	09/12/05	
BC DL	10.0 PSF	DRW	HCUSR487	05255092
BC LL	0.0 PSF	HC-ENG	DF/AF	
TOT.LD.	40.0 PSF	SEQN-	31894	
DUR.FAC.	1.25	FROM	JP	
SPACING	24.0"	JREF-	1S0F487_Z03	

Haines City, FL 33844
FL Certificate of Authorization # 567

(5-399-MACK ROBINSON-LITTLE - A2)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.


(A) Continuous lateral bracing equally spaced on member.

Shim all supports to solid bearing.

** Negative reaction(s) of -318# MAX. (See below) from a non-wind load case requires uplift connection.

110 mph wind, 11.60 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

Scale = .1875"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DAMAGE TO BUILDING OR PERSONS OR PROPERTY DURING THE INSTALLATION OF THIS TRUSS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY ASEP) AND TPI ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (H/H/S/S) ASTM A653 GRADE 40/60 (N, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

Alpine Engineered Products, Inc.
1950 Marney Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"


REF	R487--	88061
DATE	09/12/05	
DRW	HCUSR487	05255093
HC-ENG	DF/AF	
SEQN-	31905	
FROM	JP	
JREF-	1SQF487_Z03	

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Left end vertical not exposed to wind pressure.
Deflection meets L/360 live and L/240 total load.

110 mph wind, 11.51 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.
Shim all supports to solid bearing.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

QTY:1

Scale = .1875"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF BCS (NATIONAL DESIGN SPEC. BY AIAA) AND TPI. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN AND FABRICATION OF THE TRUSS. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL OR THIS DESIGN INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BUILDING SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE
Alpine Engineered Products, Inc.
Haines City, FL 33844
1950 Marley Drive
FL Certificate of Authorization # 567




TC LL	20.0 PSF	REF	R487 -- 88063
TC DL	10.0 PSF	DATE	09/12/05
BC DL	10.0 PSF	DRW	HCUSR487 05255095
BC LL	0.0 PSF	HC-ENG	DF/AF
TOT.LD.	40.0 PSF	SEQN	31932
DUR.FAC.	1.25	FROM	JP
SPACING	24.0"	JREF	1SQF487_Z03

110 mph wind, 12.01 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 dsf.

(A) Continuous lateral bracing equally spaced on member.

Shim all supports to solid bearing.



Design Crit: TPI-1995(STD)/FBC

QTY:4 FL / - / 4 / - / - / R / -

Scale = 1875" / Ft.

TC LL	20.0 PSF	REF	R487 -	88064
TC DL	10.0 PSF	DATE	09/12/05	
BC DL	10.0 PSF	DRW	HCUSR487	05255096
BC LL	0.0 PSF	HC-ENG	DF/AF	
TOT.LD.	40.0 PSF	SEQN-	31944	
DUR.FAC.	1.25	FROM	JP	
SPACING	24.0"	JREF-	1S0F487_Z03	

Haines City, FL 33844
FL Certificate of Authorization # 567

Top	chord	2x4	SP	#2	Dense
Bot	chord	2x4	SP	#2	Dense
	webs	2x4	SP	#3	


1110 mph wind, 12.01 ft mean hgt., ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Left end vertical not exposed to wind pressure.

(A) Continuous lateral bracing equally spaced on member.

Deflection meets L/360 live and L/240 total load.

Shim all supports to solid bearing.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

QTY:4 FL/-/4/-/-/R/-

Scale = .1875"/Ft.

ALPINE

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** TURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AIA/P) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2010/16GA (W/H/5/8) ASTM A653 GRADE 40/60 (M, K/H/5) ONLY. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TP11-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



TC LL	20.0	PSF	REF R487 --	88065
TC DL	10.0	PSF	DATE	09/12/05
BC DL	10.0	PSF	DRW HCUSR487	05255097
BC LL	0.0	PSF	HC-ENG DF/AF	
TOT.LD.	40.0	PSF	SEQN-	31951
DUR.FAC.	1.25		FROM	JP
SPACING	24.0"		JREF-	1SQF487_Z03

Sep 12 '05

Right end vertical not exposed to wind pressure.



Sep 12 '05

(A) 1x4 SP #3 or better "T" brace. 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC.

PLT TYP. Wave TPI

7.04.0805

Scale = .25"/Ft.

WARNING TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLATION AND BRACING. REFER TO RCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSSING PLATE INSTITUTE, 583 O'ROURKE DR., SUITE 200, MADISON, WI 53719, AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE IN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.


* ** IMPORTANT ** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. TRUSS IN CONFORMANCE WITH TP1 - OR FABRICATING, HANDLING, SHIPPING, INSTALLING OR ERECTING TRUSSES WITH APPLICABLE PROVISIONS OF NDS NATIONAL DESIGN SPEC. BY APPLICABLE DESIGN CODES AND APPLICABLE CODES. THIS TRUSS IS DESIGNED TO BE USED AS A TRUSS TO SUPPORT THE TRUSSES TO BE INSTALLED ON EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A OF TP1-2002-2002. EXAMINING INDICATES A PROFESSIONAL ENGINEERING RESPONSIBILITY SOLICITATION. BUILDING DESIGNER PER ANNEX (TP1) 1 SEC. 2 OF THIS COMPANION FORM BY BUILDING



Haines City, FL 33844
FL Certificate of Authorization # 567

Sep 12 '05

JREF- 1SQF487_Z03



Right end vertical not exposed to wind pressure.




Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

(A) 1x4 SP #3 or better "T" brace, 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC.

110 mph wind, 11.60 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.
Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

QTY:1

FL/- /4/- /- /R/-

Scale = .25"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF MDS (NATIONAL DESIGN SPEC. BY ACPA) AND TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL OR THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



Sep 12 '05

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"


REF	R487-- 88070
DATE	09/12/05
DRW	HCUSR487 05255080
HC-ENG	DF/AF
SEQN	31777
FROM	JP
JREF	1SQF487_Z03

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

(A) 1x4 SP #3 or better "T" brace. 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC.

110 mph wind, 12.10 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.
Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

QTY: 1

Scale = .25"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE INSTALLER SHALL BE RESPONSIBLE FOR THE DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPECIFICATION FOR WOOD TRUSSES. THE CONNECTOR PLATES ARE MADE OF 20/18/16GA (N-H/S/R) ASTM A653 GRADE 40/60 (N, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A2 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

ALPINE

Alpine Engineered Products, Inc.
1950 Kinney Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

ARTHUR R. FISHER
No. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Sep 12 '05

TC LL	20.0 PSF	REF	R487 -- 88071
TC DL	10.0 PSF	DATE	09/12/05
BC DL	10.0 PSF	DRW	HCUSR487 05255081
BC LL	0.0 PSF	HC-ENG	DF/AF
TOT.LD.	40.0 PSF	SEQN-	31788
DUR.FAC.	1.25	FROM	JP
SPACING	24.0"	JREF-	1SQF487_Z03


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

(A) 1x4 SP #3 or better "T" brace. 80% length of web member. Attach with 8d Box or Gun (0.113"x2.5",min.)nails @ 6" OC.
Deflection meets L/360 live and L/240 total load.

110 mph wind, 12.60 ft mean hgt., ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.

(B) 2x4 SP #3 or better "T" brace. 80% length of web member. Attach with 16d Box or Gun (0.135"x3.5",min.)nails @ 6" OC.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805


QTY:2

FL/-/4/-/-/R/-

Scale = .25"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 983 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND WCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT****FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF AISI, NATIONAL DESIGN SPEC. BY AIA/ASCE AND TPI. ALPINE ENGINEERED PRODUCTS, INC. SHALL BE RESPONSIBLE FOR THE DESIGN OF THIS TRUSS. ALL TRUSS DRAWINGS SHALL BE FOR THE EXCLUSIVE USE OF THE TRUSS MANUFACTURER. NO OTHER USE IS PERMITTED. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567



Sep 12 '05

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"

REF	R487 -- 88072
DATE	09/12/05
DRW	HCUSR487 05255082
HC-ENG	DF/AF
SEQN-	31797
FROM	JP
JREF-	1SQF487_Z03

110 mph wind, 15.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.




(5-399-MACK ROBINSON-LITTLE - B2)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

110 mph wind, 10.10 ft mean hgt, ASCE 7-98, CLOSED bldg. not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.



PLT TYP. Wave TPI

ALPINE

Alpine Engineered Products, Inc.
1950 Maple Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

Design Crit: TPI-1995(STD)/FBC

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI TRUSS PLATE INSTITUTE, 583 DUNDAS DR., SUITE 200, MADISON, WI 53719) AND MICA (MILITARY INSTITUTE FOR CONSTRUCTION, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, ALL DIMENSIONS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AFPA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (M/H/S/K) ASTM A653 GRADE 40/60 (W, K/H/S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

QTY: 1

FL / - / 4 / - / - / R / -

Scale = .1875" / Ft.

TC LL	20.0 PSF	REF	R487 - -	88074
TC DL	10.0 PSF	DATE	09/12/05	
BC DL	10.0 PSF	DRW	HCUSR487	05255083
BC LL	0.0 PSF	HC-ENG	DF/AF	*
TOT.LD.	40.0 PSF	SEQN	31869	
DUR.FAC.	1.25	FROM	JP	
SPACING	24.0"	JREF	1SQF487_Z03	


ARTHUR R. FISHER
LICENSE
No. 59687
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Sep 12 '05

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

110 mph wind, 10.60 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

QTY:1

Scale = .1875"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 503 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND NITCA (NORTH TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS OR TO FOLLOW THE DESIGN REQUIREMENTS, INCLUDING THE INSTALLATION OF TRUSSES, SHALL BE THE RESPONSIBILITY OF THE INSTALLER. PROVIDE THE FOLLOWING INFORMATION TO THE INSTALLER: 1. THE TRUSS SHALL BE MADE OF 20/18/16GA (H-H/S/E) ASH A653 GRADE 40/60 (H, K/H/S) GALV. STEEL. APPLY CONNECTOR PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

Arthur R. Fisher
Professional Engineer
Sep 12 '05

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"


REF	R487 -- 88075
DATE	09/12/05
DRW	HCUSR487 05255084
HC-ENG	DF/AF
SEQN	31877
FROM	JP
JREF	1SQF487_Z03

Sep 12, 05

	Top	Bot	Dense
chord	2x4	2x4	#2
chord	2x4	2x4	#2
webs	2x4	2x4	#3

110 mph wind, 10.66 ft mean hgt., ASCE 7-98, CLOSED bldg. Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI

Design Crit: TPI-1995 (STD)/FBC

7.04.0805

QTY:7 FL/-/4/-/-/R/-

Scale = .3125"/Ft.



Alpine Engineering Products, Inc.
1950 Marley Drive
Haines City, FL 33844

Professional Engineer
ARTHUR R. FISHER
LICENSE NO. 59887
STATE OF FLORIDA

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCES 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE), 983 D-090810 DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. TRUSSES IN CONFORMANCE WITH TPI: OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA/AS) AND AIA/AS STEEL. CONNECTOR PLATES ARE MADE OF 2018/10GA (14/10/57A) STRENGTH GRADE 50 DESIGN. DESIGNER'S SEAL ON THIS PLATES TO EACH FACE OF TRUSS. TOP AND BOTTOM CHORDS SHALL BE PER ANEX A3 OF TPI-1-2002 SEC. 2. INSTALLATION SHALL BE FOLLOWED BY THE TPI-1-2002 SEC. 2. A SEAL ON THIS BUILDING SHOWN. ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY, SOLELY FOR THE TRUSS COMPONENT DESIGNER SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Right end vertical not exposed to wind pressure.



Right end vertical not exposed to wind pressure.



Right end vertical not exposed to wind pressure.




(5-399-MACK ROBINSON-LITTLE - C6)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3


110 mph wind, 12.43 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

(A) Continuous lateral bracing equally spaced on member.
Deflection meets L/360 live and L/240 total load.

Right end vertical not exposed to wind pressure.



PLT TYP. Wave TPI



Design Crit: TPI-1995(STD)/FBC

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (PRESS PLATES INSTALLED PER INSTRUCTIONS ON BACK OF PLATES), AND TPI-1995(STD)/FBC (DESIGN CRITERIA) FOR ADDITIONAL INFORMATION. UNLESS OTHERWISE INDICATED, ALL DIMENSIONS SHALL BE IN FEET AND INCHES. UNLESS OTHERWISE INDICATED, ALL DIMENSIONS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (W, P/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 100A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SELECT FOR THE RESPONSIBILITY OF THE DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

7.04.0805

QTY:1

FL/-/4/-/-/R/-

Scale =.25"/Ft.


TC LL	20.0 PSF	REF	R487 -- 88081
TC DL	10.0 PSF	DATE	09/12/05
BC DL	10.0 PSF	DRW	HCUSR487 05255089
BC LL	0.0 PSF	HC-ENG	DF/AF *
TOT.LD.	40.0 PSF	SEQN	31853
DUR.FAC.	1.25	FROM	JP
SPACING	24.0"	JREF	1SQF487_Z03



Sep 12 '05

FL Certificate of Authorization # 567

Left side jacks have 7-3-8 setback with 0-0-0 cant and 2-0-0 overhang. End jacks have 7-3-8 setback with 0-0-0 cant and 2-0-0 overhang. Right side jacks have 7-3-8 setback with 0-0-0 cant and 2-0-0 overhang.



Sep 12 '05

TC LL	20.0	PSF	REF	R487 --	88082
TC DL	10.0	PSF	DATE	09/12/05	
BC DL	10.0	PSF	DRW	HCUSR487	05255101
BC LL	0.0	PSF	HC-ENG	DF /AF	
TOT.LD.	40.0	PSF	SEQN-	10070	
DUR.FAC.	1.25		FROM	JP	
SPACING	SEE ABOVE		JREF-	15QF487_Z03	


Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Hipjack supports 7'-0" setback jacks with no webs.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (3) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.

110 mph wind, 15.00 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Deflection meets L/360 live and L/240 total load.



PLT TYP. Wave TPI



Design Crit: TPI-1995(STD)/FBC.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ORFIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC. BY AIA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 2018/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (M, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BUILDING SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

7.04.0805

QTY: 5 FL/-/4/-/-/R/-

Scale = .375"/Ft.

	TC LL	20.0 PSF	REF	R487--	88084
	TC DL	10.0 PSF	DATE	09/12/05	
	BC DL	10.0 PSF	DRW	HCUSR487	05255103
	BC LL	0.0 PSF	HC-ENG	DF/AF	
	TOT.LD.	40.0 PSF	SEQN-	31700	
	DUR.FAC.	1.25	FROM	JP	
	SPACING	SEE ABOVE	JREF-	1SQF487_Z03	


Sep 12 '05

Top chord 2x4 Sp #2 Dense
Bot chord 2x4 Sp #2 Dense

Deflection meets L/360 live and L/240 total load.

110 mph wind, 9.60 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Provide (2) 16d common nails(0.162"x3.5"); toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"); toe nailed at Bot chord.



7-0-0 Over 3 Supports
R=445 U=180 W=3.5"

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

QTY:25 FL/-/4/-/-/R/-

Scale = .375"/Ft.

ALPINE

Alpine Engineered Products, Inc.
1050 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCS1 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 593 D'ONDRIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE BL, MADISON, WI 53719). FOR SAFETY PRACTICES PRIOR TO FABRICATING TRUSSES, THE FABRICATOR SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AIA/AIA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W/H/S/K) ASTM A653 GRADE 40/60 (H, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS BRACING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGNER SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Sep 12 '05


TC LL	20.0 PSF	REF	R487 -- 88085
TC DL	10.0 PSF	DATE	09/12/05
BC DL	10.0 PSF	DRW	HCUSR487 05255104
BC LL	0.0 PSF	HC-ENG	DF/AF
TOT.LD.	40.0 PSF	SEQN-	10074
DUR.FAC.	1.25	FROM	JP
SPACING	24.0"	JREF-	1SQF487_Z03

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Deflection meets L/360 live and L/240 total load.

110 mph wind, 9.60 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.



7'-0" Over 3 Supports
 $R=445$ $U=180$ $W=3.5"$

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805


QTY:2

FL/-/4/-/R/-

Scale = .375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MICA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THIS (NATIONAL DESIGN SPEC. BY TAPPS) AND A STEEL APPLICABLE TO EACH FACE OF TRUSS AND UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

FL Certificate of Authorization # 567



Sep 12 '05

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"


REF	R487-- 88086
DATE	09/12/05
DRW	HCUSR487 05255105
HC-ENG	DF/AF
SEQN-	31706
FROM	JP
JREF-	1SQF487_Z03

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Deflection meets L/360 live and L/240 total load.

110 mph wind, 9.10 ft mean hgt, ASCE 7-98, CLOSED bldg, not located within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.



←-2-0-0→

←-5-0-0 Over 3 Supports →
R-376 U=180 W=3.5"

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

QTY:12 FL/-/4/-/-/R/-

Scale = .375"/Ft.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BEST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS TO THE REQUIREMENTS OF THE DESIGN SHALL BE THE RESPONSIBILITY OF THE INSTALLER. THE TRUSS SHALL BE CONSIDERED TO BE A BUILDING COMPONENT AND SHALL BE SUBJECT TO THE REQUIREMENTS OF THE BUILDING CODES. THE TRUSS SHALL BE CONSIDERED TO BE A BUILDING COMPONENT AND SHALL BE SUBJECT TO THE REQUIREMENTS OF THE BUILDING CODES.

ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DESIGN INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Sep 12 '05

TC LL	20.0 PSF
TC DL	10.0 PSF
BC DL	10.0 PSF
BC LL	0.0 PSF
TOT.LD.	40.0 PSF
DUR.FAC.	1.25
SPACING	24.0"


REF	R487 --	88087
DATE	09/12/05	
DRW	HCUSR487	05255106
HC-ENG	DF/AF	
SEQN	10079	
FROM	JP	
JREF	1SQF487_Z03	

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense

Deflection meets L/360 live and L/240 total load.

110 mph wind, 8.60 ft mean hgt, ASCE 7-98, CLOSED bldg, Located
anywhere in roof, CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0
psf.

Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide (2) 16d common nails(0.162"x3.5"), toe nailed at Bot chord.



3-0-0 Over 3 Supports
R-322 U=180 W=3.5"

PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

QTY:12 FL/-/4/-/-/R/-

Scale =.375"/Ft.

ALPINE

Alpine Engineered Products, Inc.
1350 Veterans Drive
Haines City, FL 33844
FL Certificate of Authorization # 567

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 5810 O'ROURD DR., SUITE 200, MADISON, WI 53719) AND MTCA (WOOD TRUSS CONSTRUCTION ASSOCIATION, 1000 W. 10TH AVE., SUITE 100, MADISON, WI 53719) FOR SAFETY PRACTICES. TRUSSES ARE NOT TO BE USED FOR ANY OTHER PURPOSES UNLESS OTHERWISE INDICATED. THE CONTRACTOR SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC, BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (M, H/S/K) ASTM A653 GRADE 40/60 (M, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DESIGN SHOWS THE ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT BUILDING DESIGNER. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Sep 12 '05

SPACING 24.0"

FROM JP

JREF- 1SQF487_Z03

DUR.FAC. 1.25

SEQN- 10084

HC-ENG DF/AF

DRW HCUR487 05255090

DATE 09/12/05

REF R487 -- 88088

Top chord	2x4	SP	#2	Dense
Bot. chord	2x4	SP	#2	Dense


** Negative reaction(s) of -190# MAX. (See below) from a non-wind load case requires uplift connection.

Deflection meets L/360 live and L/240 total load.

110 mph wind, 8.10 ft mean hgt, ASCE 7-98, CLOSED bldg, Located anywhere on roof CAT II, EXP B, wind TC DL=5.0 psf, wind BC DL=5.0 psf.

Provide { 2 } 16d common nails(0.162"x3.5"), toe nailed at Top chord.
Provide { 2 } 16d common nails(0.162"x3.5"), toe nailed at Bot chord.

** R=-.191 U=180


$$R = -19 \quad U = 180$$

$\hookleftarrow 2-0-0 \rightarrow$
 $1-0-0$ over 3 Supports

R=418 U=180 W=3.5"

Scale = .375"/Ft.

QTY: 12 EL 1 - 141 - 1 - 1R / -

7 04 0805

Design Crit: TPI-1995 (STD) / FBC

PIT TYP. Wave TPI

TC	11	20.0	PSF
----	----	------	-----

RFF R487-- 88089

DATE 09/12/05


DATE 05/21/00

DRW HCUR487 0

HC-ENG DF/AF

SEQN-

FROM JP



Sep 12 '05

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO DESIGNS 1-03 (BUILDING COMPLETION INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 DUMFRIES DR., SUITE 100, ST. LOUIS, MO 63119) AND AISC (AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC., 500 MADISON AVENUE, NEW YORK, NY 10017). THE FOLLOWING ARE SOME OF THE MOST COMMONLY MADE MISTAKES THAT CAN BE PREVENTED BY PROPER DESIGN AND FABRICATION. THESE MISTAKES CAN BE PREVENTED BY THOROUGHLY REVIEWING THE TRUSS DESIGN PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, ALL DIMENSIONS SHALL HAVE PROPERLY ATTACHED DIMENSION LINES. ALL DIMENSIONS SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERTY ATTACHED TO IDENTIFY IT.

[illegible]


Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.


110 mph wind, 9.92 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.

Right end vertical not exposed to wind pressure.



8'-2-0-0
4'-9-1
3'-4-11
0'-1-12
8'-3-8 Over 2 Supports
R=492 U=180 W=3.5"
R=299 U=180 W=3.5"

PLT TYP. Wave TPI



Design Crit: TPI-1995(STD)/FBC

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCSE 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTION), 1000 D'ONOFRIO DR., SUITE 200, MADISON, WI 53719, AND MTCA (WOOD TRUSS COUNCIL OF AMERICA), 1000 WOOD TRUSS DRIVE, MADISON, WI 53719, FOR SAFETY PRACTICES. ALL TRUSSES SHALL BE PROPERLY ATTACHED TO THE BUILDING STRUCTURE. UNLESS OTHERWISE INDICATED, ALL TRUSSES SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY A/E/P/A) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/166A (H-H/S/K) ASTM A653 GRADE 40/60 (H, K/H-S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-Z. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI-2002 SEC.3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY. SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.

Scale = .375"/Ft.

QTY: 2

7.04.0805

FL/-/4/-/-/R/-

TC LL

20.0 PSF

REF R487 -- 88090

DATE 09/12/05

TC DL

10.0 PSF

BC DL

10.0 PSF

DRW HCUSR487 05255091

HC-ENG DF/AF *

SEQN - 31714

BC LL

0.0 PSF

TOT.LD.

40.0 PSF

DUR.FAC.

1.25

FROM JP

SPACING

24.0"

JREF - 1SQF487_Z03

Sep 12 '05

Professional Engineer

ARTHEA FISHER

License No. 59687

Professional Engineer

FL Certificate of Authorization # 567

Alpine Engineering Products, Inc.

1950 Haines Drive

Haines City, FL 33844

FL Certificate of Authorization # 567


(5-399-MACK ROBINSON-LITTLE - AP1)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

Refer to DWG PIGBACK1103 or PIGBACK1103 for piggyback details.
PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC,
UNLESS OTHERWISE SPECIFIED.

110 mph wind, 8.50 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0805

Scale = .375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BCST 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI AMERICA, 6300 ENTERPRISE LN, DUNFORD DR., SUITE 200, MADISON, WI 53719, AND MTCA (MOUNTAIN TOP CHORD) FOR SAFETY PRACTICES PRIOR TO THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** UNLESS A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ANY FAILURE TO BUILD THE TRUSS TO THE DESIGN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES. DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF NDS (NATIONAL DESIGN SPEC., BY AF&PA) AND TPI. ALPINE CONNECTOR PLATES ARE MADE OF 20/18/16GA (W, H/5/8) ASTM A653 GRADE 40/60 (H, K/H, S) GALV. STEEL. APPLY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 1004, 1005, 1006, 1007, 1008, 1009, 1010, 1011, 1012, 1013, 1014, 1015, 1016, 1017, 1018, 1019, 1020, 1021, 1022, 1023, 1024, 1025, 1026, 1027, 1028, 1029, 1030, 1031, 1032, 1033, 1034, 1035, 1036, 1037, 1038, 1039, 1040, 1041, 1042, 1043, 1044, 1045, 1046, 1047, 1048, 1049, 1050, 1051, 1052, 1053, 1054, 1055, 1056, 1057, 1058, 1059, 1060, 1061, 1062, 1063, 1064, 1065, 1066, 1067, 1068, 1069, 1070, 1071, 1072, 1073, 1074, 1075, 1076, 1077, 1078, 1079, 1080, 1081, 1082, 1083, 1084, 1085, 1086, 1087, 1088, 1089, 1090, 1091, 1092, 1093, 1094, 1095, 1096, 1097, 1098, 1099, 1100, 1101, 1102, 1103, 1104, 1105, 1106, 1107, 1108, 1109, 1110, 1111, 1112, 1113, 1114, 1115, 1116, 1117, 1118, 1119, 1120, 1121, 1122, 1123, 1124, 1125, 1126, 1127, 1128, 1129, 1130, 1131, 1132, 1133, 1134, 1135, 1136, 1137, 1138, 1139, 1140, 1141, 1142, 1143, 1144, 1145, 1146, 1147, 1148, 1149, 1150, 1151, 1152, 1153, 1154, 1155, 1156, 1157, 1158, 1159, 1160, 1161, 1162, 1163, 1164, 1165, 1166, 1167, 1168, 1169, 1170, 1171, 1172, 1173, 1174, 1175, 1176, 1177, 1178, 1179, 1180, 1181, 1182, 1183, 1184, 1185, 1186, 1187, 1188, 1189, 1190, 1191, 1192, 1193, 1194, 1195, 1196, 1197, 1198, 1199, 1200, 1201, 1202, 1203, 1204, 1205, 1206, 1207, 1208, 1209, 1210, 1211, 1212, 1213, 1214, 1215, 1216, 1217, 1218, 1219, 1220, 1221, 1222, 1223, 1224, 1225, 1226, 1227, 1228, 1229, 1230, 1231, 1232, 1233, 1234, 1235, 1236, 1237, 1238, 1239, 1240, 1241, 1242, 1243, 1244, 1245, 1246, 1247, 1248, 1249, 1250, 1251, 1252, 1253, 1254, 1255, 1256, 1257, 1258, 1259, 1260, 1261, 1262, 1263, 1264, 1265, 1266, 1267, 1268, 1269, 1270, 1271, 1272, 1273, 1274, 1275, 1276, 1277, 1278, 1279, 1280, 1281, 1282, 1283, 1284, 1285, 1286, 1287, 1288, 1289, 1290, 1291, 1292, 1293, 1294, 1295, 1296, 1297, 1298, 1299, 1300, 1301, 1302, 1303, 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1312, 1313, 1314, 1315, 1316, 1317, 1318, 1319, 1320, 1321, 1322, 1323, 1324, 1325, 1326, 1327, 1328, 1329, 1330, 1331, 1332, 1333, 1334, 1335, 1336, 1337, 1338, 1339, 1340, 1341, 1342, 1343, 1344, 1345, 1346, 1347, 1348, 1349, 1350, 1351, 1352, 1353, 1354, 1355, 1356, 1357, 1358, 1359, 1360, 1361, 1362, 1363, 1364, 1365, 1366, 1367, 1368, 1369, 1370, 1371, 1372, 1373, 1374, 1375, 1376, 1377, 1378, 1379, 1380, 1381, 1382, 1383, 1384, 1385, 1386, 1387, 1388, 1389, 1390, 1391, 1392, 1393, 1394, 1395, 1396, 1397, 1398, 1399, 1400, 1401, 1402, 1403, 1404, 1405, 1406, 1407, 1408, 1409, 1410, 1411, 1412, 1413, 1414, 1415, 1416, 1417, 1418, 1419, 1420, 1421, 1422, 1423, 1424, 1425, 1426, 1427, 1428, 1429, 1430, 1431, 1432, 1433, 1434, 1435, 1436, 1437, 1438, 1439, 1440, 1441, 1442, 1443, 1444, 1445, 1446, 1447, 1448, 1449, 1450, 1451, 1452, 1453, 1454, 1455, 1456, 1457, 1458, 1459, 1460, 1461, 1462, 1463, 1464, 1465, 1466, 1467, 1468, 1469, 1470, 1471, 1472, 1473, 1474, 1475, 1476, 1477, 1478, 1479, 1480, 1481, 1482, 1483, 1484, 1485, 1486, 1487, 1488, 1489, 1490, 1491, 1492, 1493, 1494, 1495, 1496, 1497, 1498, 1499, 1500, 1501, 1502, 1503, 1504, 1505, 1506, 1507, 1508, 1509, 1510, 1511, 1512, 1513, 1514, 1515, 1516, 1517, 1518, 1519, 1520, 1521, 1522, 1523, 1524, 1525, 1526, 1527, 1528, 1529, 1530, 1531, 1532, 1533, 1534, 1535, 1536, 1537, 1538, 1539, 1540, 1541, 1542, 1543, 1544, 1545, 1546, 1547, 1548, 1549, 1550, 1551, 1552, 1553, 1554, 1555, 1556, 1557, 1558, 1559, 1560, 1561, 1562, 1563, 1564, 1565, 1566, 1567, 1568, 1569, 1570, 1571, 1572, 1573, 1574, 1575, 1576, 1577, 1578, 1579, 1580, 1581, 1582, 1583, 1584, 1585, 1586, 1587, 1588, 1589, 1590, 1591, 1592, 1593, 1594, 1595, 1596, 1597, 1598, 1599, 1600, 1601, 1602, 1603, 1604, 1605, 1606, 1607, 1608, 1609, 1610, 1611, 1612, 1613, 1614, 1615, 1616, 1617, 1618, 1619, 1620, 1621, 1622, 1623, 1624, 1625, 1626, 1627, 1628, 1629, 1630, 1631, 1632, 1633, 1634, 1635, 1636, 1637, 1638, 1639, 1640, 1641, 1642, 1643, 1644, 1645, 1646, 1647, 1648, 1649, 1650, 1651, 1652, 1653, 1654, 1655, 1656, 1657, 1658, 1659, 1660, 1661, 1662, 1663, 1664, 1665, 1666, 1667, 1668, 1669, 1670, 1671, 1672, 1673, 1674, 1675, 1676, 1677, 1678, 1679, 1680, 1681, 1682, 1683, 1684, 1685, 1686, 1687, 1688, 1689, 1690, 1691, 1692, 1693, 1694, 1695, 1696, 1697, 1698, 1699, 1700, 1701, 1702, 1703, 1704, 1705, 1706, 1707, 1708, 1709, 1710, 1711, 1712, 1713, 1714, 1715, 1716, 1717, 1718, 1719, 1720, 1721, 1722, 1723, 1724, 1725, 1726, 1727, 1728, 1729, 1730, 1731, 1732, 1733, 1734, 1735, 1736, 1737, 1738, 1739, 1740, 1741, 1742, 1743, 1744, 1745, 1746, 1747, 1748, 1749, 1750, 1751, 1752, 1753, 1754, 1755, 1756, 1757, 1758, 1759, 1760, 1761, 1762, 1763, 1764, 1765, 1766, 1767, 1768, 1769, 1770, 1771, 1772, 1773, 1774, 1775, 1776, 1777, 1778, 1779, 1780, 1781, 1782, 1783, 1784, 1785, 1786, 1787, 1788, 1789, 1790, 1791, 1792, 1793, 1794, 1795, 1796, 1797, 1798, 1799, 1800, 1801, 1802, 1803, 1804, 1805, 1806, 1807, 1808, 1809, 1810, 1811, 1812, 1813, 1814, 1815, 1816, 1817, 1818, 1819, 1820, 1821, 1822, 1823, 1824, 1825, 1826, 1827, 1828, 1829, 1830, 1831, 1832, 1833, 1834, 1835, 1836, 1837, 1838, 1839, 1840, 1841, 1842, 1843, 1844, 1845, 1846, 1847, 1848, 1849, 1850, 1851, 1852, 1853, 1854, 1855, 1856, 1857, 1858, 1859, 1860, 1861, 1862, 1863, 1864, 1865, 1866, 1867, 1868, 1869, 1870, 1871, 1872, 1873, 1874, 1875, 1876, 1877, 1878, 1879, 1880, 1881, 1882, 1883, 1884, 1885, 1886, 1887, 1888, 1889, 1890, 1891, 1892, 1893, 1894, 1895, 1896, 1897, 1898, 1899, 1900, 1901, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1909, 1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1918, 1919, 1920, 1921, 1922, 1923, 1924, 1925, 1926, 1927, 1928, 1929, 1930, 1931, 1932, 1933, 1934, 1935, 1936, 1937, 1938, 1939, 1940, 1941, 1942, 1943, 1944, 1945, 1946, 1947, 1948, 1949, 1950, 1951, 1952, 1953, 1954, 1955, 1956, 1957, 1958, 1959, 1960, 1961, 1962, 1963, 1964, 1965, 1966, 1967, 1968, 1969, 1970, 1971, 1972, 1973, 1974, 1975, 1976, 1977, 1978, 1979, 1980, 1981, 1982, 1983, 1984, 1985, 1986, 1987, 1988, 1989, 1990, 1991, 1992, 1993, 1994, 1995, 1996, 1997, 1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 2680, 2681, 2682, 2683, 2684, 2685, 2686, 2687, 2688, 2689, 2690, 2691, 2692, 2693, 2694, 2695, 2696, 2697, 2698, 2699, 2700, 2701, 2702, 2703, 2704, 2705, 2706, 2707, 2708, 2709, 2710, 2711, 2712, 2713, 2714, 2715, 2716, 2717, 2718, 2719, 2720, 2721, 2722, 2723, 2724, 2725, 2726, 2727, 2728, 2729, 2730, 2731, 2732, 2733, 2734, 2735, 2736, 2737, 2738, 2739, 2740, 2741, 2742, 2743, 2744, 2745, 2746, 2747, 2748, 2749, 2750, 2751, 2752, 2753, 2754, 2755, 2756, 2757, 2758, 2759, 2760, 2761, 2762, 2763, 2764, 2765, 2766, 2767, 2768, 2769, 2770, 2771, 2772, 2773, 2774, 2775, 2776, 2777, 2778, 2779, 2780, 2781, 2782, 2783, 2784, 2785, 2786, 2787, 2788, 2789, 2790, 2791, 2792, 2793, 2794, 2795, 2796, 2797, 2798, 2799, 2800, 2801, 2802, 2803, 2804, 2805, 2806, 2807, 2808, 2809, 2810, 2811, 2812, 2813, 2814, 2815, 2816, 2817, 2818, 2819, 2820, 2821, 2822, 2823, 2824, 2825, 2826, 2827, 2828, 2829, 2830, 2831, 2832, 2833, 2834, 2835, 2836, 2837, 2838, 2839, 2840, 2841, 2842, 2843, 2844, 2845, 2846, 2847, 2848, 2849, 2850


(5-399-MACK ROBINSON-LITTLE - AP2)

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

Refer to DWG PIGBACK1103 or PIGBACK1103 for piggyback details.
PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC,
UNLESS OTHERWISE SPECIFIED.

110 mph wind, 9.00 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.



PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.0800


QTY: 1

FL/-4/-/-R/-

Scale = .375"/Ft.

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 593 O'CONNOR DR., SUITE 200, MADISON, WI 53719) AND WTC (WOOD TRUSS COUNCIL OF AMERICA, 6500 ENTERPRISE BLVD., MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE SPECIFIED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI'S PROVISIONS OR ANY FAILURE TO FOLLOW THE DESIGN SPEC. BY THE INSTALLER, THE DESIGNER OR THE USER, SHALL BE THE RESPONSIBILITY OF THE USER. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY FAILURE TO FOLLOW THE DESIGN SPEC. BY THE INSTALLER, THE DESIGNER OR THE USER, SHALL BE THE RESPONSIBILITY OF THE USER. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY FAILURE TO FOLLOW THE DESIGN SPEC. BY THE INSTALLER, THE DESIGNER OR THE USER, SHALL BE THE RESPONSIBILITY OF THE USER.



Alpine Engineered Products, Inc.
1950 Marley Drive
Haines City, FL 33844



Sep 12 '05


JREF- 150F487_Z03

Top chord 2x4 SP #2 Dense
Bot chord 2x4 SP #2 Dense
Webs 2x4 SP #3

Deflection meets L/360 live and L/240 total load.

Refer to DWG PIGBACK1103 or PIGBACK1103 for piggyback details.
PORTION OF TRUSS UNDER PIGGYBACK IS TO BE BRACED @ 24" OC,
UNLESS OTHERWISE SPECIFIED.

110 mph wind, 9.21 ft mean hgt, ASCE 7-98, CLOSED bldg, not located
within 4.50 ft from roof edge, CAT II, EXP B, wind TC DL=5.0 psf, wind
BC DL=5.0 psf.




PLT TYP. Wave TPI

Design Crit: TPI-1995(STD)/FBC

7.04.080

Scale = .375"/Ft.

QTY:5	FL/-/4/-/-/R/-	TC LL	20.0 PSF	REF	R487--	88093
		TC DL	10.0 PSF	DATE	09/12/05	
		BC DL	10.0 PSF	DRW	HCUSR487	05255110
		BC LL	0.0 PSF	HC-ENG	DF/AF	
		TOT.LD.	40.0 PSF	SEQN-	31969	
		DUR.FAC.	1.25	FROM	JP	
		SPACING	24.0"	JREF-	1S0F487_Z03	



****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATION, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC51 1-03 (BUILDING COMPONENT SAFETY INFORMATION), PUBLISHED BY TPI (TRUSS PLATE INSTITUTE, 583 O'DONOHUE DR., SUITE 200, MADISON, WI 53719) AND WTA (WOOD TRUSS COUNCIL OF AMERICA, 6300 ENTERPRISE LN, MADISON, WI 53719) FOR SAFETY PRACTICES PRIOR TO PERFORMING THESE FUNCTIONS. UNLESS OTHERWISE INDICATED, TOP CHORD SHALL HAVE PROPERLY ATTACHED STRUCTURAL PANELS AND BOTTOM CHORD SHALL HAVE A PROPERLY ATTACHED RIGID CEILING.

****IMPORTANT**** FURNISH A COPY OF THIS DESIGN TO THE INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI OR FABRICATING, HANDLING, SHIPPING, INSTALLING & BRACING OF TRUSSES, DESIGN CONFORMS WITH APPLICABLE PROVISIONS OF THE NATIONAL DESIGN SPEC. BY AISC/AIA AND TPI. ALPINE CONNECTOR PLATES ARE MADE TO SPECIFICATION OF THE NATIONAL DESIGN SPEC. BY AISC/AIA AND TPI. APPLY PLATES TO THE TRUSS IN ACCORDANCE WITH THE NATIONAL DESIGN SPEC. BY AISC/AIA AND TPI. A SEAL ON THIS DESIGN INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER PER ANSI/TPI 1 SEC. 2.



Sep 1 '05

CLB WEB BRACE SUBSTITUTION

THIS DETAIL IS TO BE USED WHEN CONTINUOUS LATERAL BRACING (CLB) IS SPECIFIED ON AN ALPINE TRUSS DESIGN BUT AN ALTERNATIVE WEB BRACING METHOD IS DESIRED.

NOTES:

THIS DETAIL IS ONLY APPLICABLE FOR CHANGING THE SPECIFIED CLB SHOWN ON SINGLE PLY SEALED DESIGNS TO T-BRACING OR SCAB BRACING.
ALTERNATIVE BRACING SPECIFIED IN CHART BELOW MAY BE CONSERVATIVE. FOR MINIMUM ALTERNATIVE BRACING, RE-RUN DESIGN WITH APPROPRIATE BRACING.


WEB MEMBER SIZE	SPECIFIED CLB BRACING	T OR L-BRACE	ALTERNATIVE BRACING SCAB BRACE
2X3 OR 2X4	1 ROW	2X4	1-2X4
	2 ROWS	2X6	2-2X4
2X6	1 ROW	2X4	1-2X6
	2 ROWS	2X6	2-2X4(*)
2X8	1 ROW	2X6	1-2X8
	2 ROWS	2X6	2-2X6(*)

T-BRACE, L-BRACE AND SCAB BRACE TO BE SAME SPECIES AND GRADE OR BETTER THAN WEB MEMBER UNLESS SPECIFIED OTHERWISE ON ENGINEER'S SEALED DESIGN.

(*) CENTER SCAB ON WIDE FACE OF WEB. APPLY (1) SCAB TO EACH FACE OF WEB.



T-BRACING
OR
L-BRACING:

APPLY TO EITHER SIDE OF WEB
NARROW FACE
ATTACH WITH 16d NAILS AT 6" O.C.
BRACE IS A MINIMUM 80% OF WEB
MEMBER LENGTH



SCAB BRACING:

APPLY SCAB(S) TO WIDE FACE OF WEB.
NO MORE THAN (1) SCAB PER FACE.
ATTACH WITH 10d OR 128"x3" GUN
NAILS AT 6" O.C. BRACE IS A MINIMUM
80% OF WEB MEMBER LENGTH



ALPINE ENGINEERED PRODUCTS, INC.
POMPANO BEACH, FLORIDA

****WARNING**** TRUSSES REQUIRE EXTREME CARE IN FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING. REFER TO BC311-03 BUILDING CODES AND SAFETY PRACTICES FOR TRUSSES, PUBLISHED BY THE TRUSS ASSOCIATION OF AMERICA, 6200 ENTERPRISE LN, MADISON, WI 53719, AND VITA (VIDE) TRUSS COUNCIL, 1000 N. 10TH ST, SUITE 100, MADISON, WI 53705. DESIGN CONCEPTS AND PRACTICES ARE MADE OF 2018/16GA (W/H/S/M) ASTM A653 GRADE 50/50 (F44/H43) GALV STEEL. SAFELY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.

****IMPORTANT**** FURNISH COPY OF THIS DESIGN TO INSTALLATION CONTRACTOR. ALPINE ENGINEERED PRODUCTS, INC., SHALL NOT BE RESPONSIBLE FOR ANY DEVIATION FROM THIS DESIGN. ANY FAILURE TO BUILD THE TRUSS IN CONFORMANCE WITH TPI1 OR FABRICATING, HANDLING, SHIPPING, INSTALLING AND BRACING OF TRUSSES. DESIGN CONCEPTS AND PRACTICES ARE MADE OF 2018/16GA (W/H/S/M) ASTM A653 GRADE 50/50 (F44/H43) GALV STEEL. SAFELY PLATES TO EACH FACE OF TRUSS AND, UNLESS OTHERWISE LOCATED ON THIS DESIGN, POSITION PER DRAWINGS 160A-2. ANY INSPECTION OF PLATES FOLLOWED BY (1) SHALL BE PER ANNEX A3 OF TPI 1-2002 SEC. 3. A SEAL ON THIS DRAWING INDICATES ACCEPTANCE OF PROFESSIONAL ENGINEERING RESPONSIBILITY SOLELY FOR THE TRUSS COMPONENT DESIGN SHOWN. THE SUITABILITY AND USE OF THIS COMPONENT FOR ANY BUILDING IS THE RESPONSIBILITY OF THE BUILDING DESIGNER, PER ANSI/TPI 1 SEC. 2.



TC LL	PSF	REF	CLB SUBST.
TC DL	PSF	DATE	11/26/03
BC DL	PSF	DRWG	BRCCLBSUB1103
BC LL	PSF	-ENG	MLH/KAR
TOT. LD.	PSF		
DUR. FAC.			
SPACING			

THIS DRAWING REPLACES DRAWING 579.640

ASCE 7-98: 110 MPH WIND SPEED, 15' MEAN HEIGHT, ENCLOSED, I = 1.00, EXPOSURE C

2X4 GABLE VERTICAL SPACING SPECIES GRADE		BRACE		(1) 1X4 "L" BRACE *		(2) 2X4 "L" BRACE *		(1) 2X6 "L" BRACE **		(2) 2X6 "L" BRACE **	
		NO BRACES		GROUP A		GROUP B		GROUP A		GROUP B	
MAX GABLE VERTICAL LENGTH	24" O.C.	SPF	#1 / #2	3' 10"	6' 8"	6' 10"	7' 11"	8' 1"	9' 5"	9' 8"	12' 5"
		HF	#3	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 4"
		STANDARD	STUD	3' 9"	6' 0"	6' 0"	7' 11"	7' 11"	9' 5"	9' 5"	12' 3"
		STANDARD	STUD	3' 9"	5' 2"	5' 2"	6' 9"	6' 9"	9' 1"	9' 1"	10' 7"
	24" O.C.	SP	#1	4' 3"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"
		HF	#2	4' 2"	6' 8"	7' 2"	7' 11"	8' 6"	9' 5"	10' 2"	12' 5"
		STANDARD	#3	4' 0"	6' 2"	6' 2"	7' 11"	8' 0"	9' 5"	9' 11"	12' 5"
		STANDARD	STUD	4' 0"	6' 1"	6' 1"	7' 11"	8' 0"	9' 5"	9' 11"	12' 5"
	16" O.C.	SPF	#1 / #2	3' 10"	5' 3"	5' 3"	6' 11"	6' 11"	9' 4"	10' 10"	14' 0"
		HF	#3	4' 4"	7' 4"	7' 4"	9' 1"	9' 1"	10' 10"	10' 10"	14' 0"
		STANDARD	STUD	4' 4"	7' 4"	7' 4"	9' 1"	9' 1"	10' 10"	10' 10"	14' 0"
		STANDARD	#1	4' 10"	7' 8"	8' 3"	9' 1"	9' 9"	10' 10"	11' 8"	14' 0"
	12" O.C.	SPF	#2	4' 9"	7' 8"	8' 3"	9' 1"	9' 9"	10' 10"	11' 8"	14' 0"
		HF	#3	4' 6"	7' 7"	7' 7"	9' 1"	9' 6"	10' 10"	11' 4"	14' 0"
		STANDARD	STUD	4' 5"	6' 5"	6' 5"	8' 6"	8' 6"	10' 10"	11' 1"	14' 0"
		STANDARD	#1 / #2	4' 11"	8' 5"	8' 5"	10' 0"	10' 3"	11' 11"	12' 3"	14' 0"
	12" O.C.	SPF	#3	4' 9"	8' 5"	8' 5"	10' 0"	10' 0"	11' 11"	11' 11"	14' 0"
		HF	STANDARD	4' 9"	7' 3"	7' 3"	9' 7"	9' 7"	11' 11"	11' 11"	14' 0"
		STANDARD	#1	5' 4"	8' 5"	9' 1"	10' 0"	10' 9"	11' 11"	12' 10"	14' 0"
		STANDARD	#2	5' 3"	8' 5"	9' 1"	10' 0"	10' 9"	11' 11"	12' 10"	14' 0"
	12" O.C.	SP	#3	5' 0"	8' 5"	8' 5"	10' 0"	10' 6"	11' 11"	12' 6"	14' 0"
		DFL	STUD	5' 0"	8' 5"	8' 7"	10' 0"	10' 6"	11' 11"	12' 6"	14' 0"
		STANDARD	STUD	4' 11"	7' 5"	7' 5"	9' 10"	9' 10"	11' 11"	12' 3"	14' 0"

BRACING GROUP SPECIES AND GRADES:

GROUP A:		GROUP B:	
SPRUCE-PINE-FIR	HEM-FIR	SPRUCE-PINE-FIR	HEM-FIR
#1 / #2	STUD	#2	STUD
#3	STANDARD	#3	STANDARD


GROUP B:		GROUP C:	
DOUGLAS FIR-LARCH	DOUGLAS FIR-LARCH	DOUGLAS FIR-LARCH	DOUGLAS FIR-LARCH
#3	STUD	#1	STUD
STANDARD	STANDARD	#2	STANDARD

GABLE TRUSS DETAIL NOTES:

- LIVE LOAD DEFLECTION CRITERIA IS L/240.
- PROVIDE UPLIFT CONNECTIONS FOR 80 PLF OVER CONTINUOUS BEARING (5 PSF TC DEAD LOAD).
- GABLE END SUPPORTS LOAD FROM 4' 0" OUTLOOKERS WITH 2' 0" OVERHANG, OR 12" PLYWOOD OVERHANG.
- ATTACH EACH "L" BRACE WITH 10d NAILS.
- * FOR (1) "L" BRACE: SPACE NAILS AT 2" O.C. IN 18" END ZONES AND 4" O.C. BETWEEN ZONES.
- ** FOR (2) "L" BRACES: SPACE NAILS AT 3" O.C. IN 18" END ZONES AND 6" O.C. BETWEEN ZONES.
- "L" BRACING MUST BE A MINIMUM OF 80% OF WEB MEMBER LENGTH.

GABLE VERTICAL PLATE SIZES	
VERTICAL LENGTH	NO SPLICE
LESS THAN 4' 0"	1X4 OR 2X3
GREATER THAN 4' 0", BUT LESS THAN 11' 6"	2X4
GREATER THAN 11' 6"	2.5X4

+ REFER TO COMMON TRUSS DESIGN FOR PEAK, SPLICE, AND HEEL PLATES.



REFER TO CHART ABOVE FOR MAX GABLE VERTICAL LENGTH.

DIAGONAL BRACE OPTION: VERTICAL LENGTH MAY BE DOUBLED WHEN DIAGONAL BRACE IS USED. CONNECT DIAGONAL BRACE FOR 600# AT EACH END. MAX WEB TOTAL LENGTH IS 14'.

VERTICAL LENGTH SHOWN IN TABLE ABOVE.


CONNECT DIAGONAL AT MIDPOINT OF VERTICAL WEB.

ALPINE ENGINEERED PRODUCTS, INC.
POMPAHO BEACH, FLORIDA


ALPINE

MAX. TOT. LD. 60 PSF

MAX. SPACING 24.0"



REF	ASCE7-98-GABI1015
DATE	11/26/03
DRWG	A11015EC1103
-ENG	



Mark Disosway, P.E.

POB 868, Lake City, FL 32056, Ph (386) 754-5419, Fax (386) 269-4871

Nov 2, 2005


Columbia County, Florida Building Department

Re: Mack Robinson, Roger Little Residence, NW 1/4 of NW 1/5 - Section 7 TWP-5-South, Range-17-East Columbia County, Florida

Dear Building Official:

Please accept this letter as addendum to the plans for the above referenced house to change all references to FBC 2001 to FBC 2004.

- The plan was drawn prior to the effective date for FBC 2004, 01 October 2005.
- Since the wind load requirements of FBC 2004 remain basically unchanged from FBC 2001 there are no structural changes required to this plan.



02 NOV 05

Mark Disosway, PE
Florida Registered Professional Engineer

Cc Mack Robinson

TABLE 1

DOOR	STILT SPACING (BASED ON RECOMMENDED SECTION CONFIGURATION)														TOP
HEIGHT	A	B	C	D	E	F	G	H	I	J	K	L	M	N	T
6'6"	5'12"	18'14"	25'12"	36'14"	43'12"	54'14"									67'12"
7'0"	5'12"	18'14"	25'12"	33'14"	46'12"										73'12"
7'6"	5'12"	15'14"	22'12"	33'14"	40'12"	51'14"	58'12"	69'14"							81'12"
8'0"	5'12"	18'14"	25'12"	36'14"	43'12"	54'14"	61'12"	72'14"							86'12"
8'6"	5'12"	18'14"	25'12"	38'14"	48'12"	60'14"	67'12"	78'14"							91'12"
9'0"	5'12"	15'14"	22'12"	33'14"	40'12"	51'14"	58'12"	69'14"	76'12"	87'14"					99'12"
9'6"	5'12"	18'14"	25'12"	39'14"	49'12"	61'14"	68'12"	79'14"	86'12"	97'14"					103'12"
10'0"	5'12"	18'14"	25'12"	39'14"	46'12"	60'14"	67'12"	78'14"	85'12"	96'14"					109'12"
10'6"	5'12"	18'14"	25'12"	39'14"	46'12"	60'14"	67'12"	78'14"	85'12"	96'14"					115'12"
11'0"	5'12"	18'14"	25'12"	39'14"	43'12"	54'14"	61'12"	72'14"	83'14"	94'14"					121'12"
11'6"	5'12"	18'14"	25'12"	39'14"	46'12"	60'14"	67'12"	78'14"	85'12"	96'14"					127'12"
12'0"	5'12"	18'14"	25'12"	39'14"	46'12"	60'14"	67'12"	81'14"	88'12"	102'14"					133'12"
12'6"	5'12"	18'14"	25'12"	36'14"	43'12"	54'14"	61'12"	72'14"	79'12"	90'14"	97'12"				139'12"
13'0"	5'12"	18'14"	25'12"	33'14"	46'12"	60'14"	67'12"	78'14"	85'12"	96'14"	103'12"				145'12"
13'6"	5'12"	18'14"	25'12"	33'14"	46'12"	60'14"	67'12"	81'14"	88'12"	102'14"	109'12"				151'12"
14'0"	5'12"	18'14"	25'12"	39'14"	46'12"	60'14"	67'12"	81'14"	88'12"	102'14"	109'12"	123'14"			157'12"

TABLE 2

DOOR HEIGHT	SECTION HEIGHTS							
	B1m	#2	#3	#4	#5	#6	#7	#8
14'0"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"
13'6"	2'1"	2'1"	2'1"	2'1"	2'1"	18"	18"	2'1"
13'0"	2'1"	2'1"	2'1"	18"	18"	18"	18"	2'1"
12'6"	2'1"	18"	18"	18"	18"	18"	18"	2'1"
12'0"	2'1"	2'1"	2'1"	2'1"	18"	18"	18"	2'1"
11'6"	2'1"	2'1"	2'1"	18"	18"	18"	18"	2'1"
11'0"	2'1"	18"	18"	18"	18"	18"	18"	2'1"
10'6"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"
10'0"	2'1"	2'1"	2'1"	18"	18"	18"	18"	2'1"
9'6"	2'1"	18"	18"	18"	18"	18"	18"	2'1"
9'0"	18"	18"	18"	18"	18"	18"	18"	2'1"
8'6"	2'1"	2'1"	2'1"	18"	18"	18"	18"	2'1"
8'0"	2'1"	18"	18"	18"	18"	18"	18"	2'1"
7'6"	18"	18"	18"	18"	18"	18"	18"	2'1"
7'0"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"	2'1"
6'6"	2'1"	18"	18"	18"	18"	18"	18"	2'1"

TABLE 3

DOOR HEIGHT	TRACK ATTACHMENT								SPLICE
	A	B	C	D	E	F	G	S	
6'6"	10'	38"	58"					70"	
7'	10'	38"	58"					76"	
7'6"	4"	28"	52"	76"				82"	
8'	10'	34"	58"	82"				88"	
8'6"	4"	28"	52"	76"				94"	
9'	10'	34"	58"	82"				100"	
9'6"	4"	28"	52"	76"	100"			106"	
10'	10'	34"	58"	82"	106"			112"	
10'6"	4"	28"	52"	76"	100"			118"	
11'	4"	34"	58"	82"	106"			124"	
11'6"	4"	28"	52"	76"	100"	124"		130"	
12'	10'	34"	58"	82"	106"	130"		136"	
12'6"	4"	28"	52"	76"	100"	124"		142"	
13'	10'	34"	58"	82"	106"	130"		148"	
13'6"	4"	28"	52"	76"	100"	124"	148"	154"	
14'	10'	34"	58"	82"	106"	130"	154"	160"	

TABLE 4

		Center Stile Locations (Measured from Left Edge)				
Section	Panel Type	1st	2st	3rd	4th	5th
Width (ft)		(in)	(in)	(in)	(in)	(in)
10'0"	Short	48,406	71,594			
10'6"	Long	30,000	60,000	90,000		
12'0"	Short	48,812	72,000	96,364		
12'6"	Long	49,625	72,000	94,375		
12'12"	Short	49,636	73,000	96,364		
12'2"	Long	50,084	73,000	95,916		
12'4"	Short	50,636	74,000	97,364		
12'4"	Long	51,084	74,000	96,916		
12'6"	Short	50,670	75,000	99,330		
12'6"	Long	51,170	75,000	98,830		
12'8"	Short	51,670	76,000	100,330		
12'8"	Long	52,100	76,000	99,900		
12'10"	Short	52,260	77,000	101,750		
12'10"	Long	53,100	77,000	100,900		
13'0"	Short	53,000	78,000	103,000		
13'0"	Long	54,100	78,000	101,900		
13'2"	Short	54,000	79,000	104,000		
13'2"	Long	55,100	79,000	102,900		
13'4"	Short	54,400	80,000	105,600		
13'4"	Long	54,900	80,000	105,100		
13'6"	Short	55,400	81,000	106,600		
13'6"	Long	55,900	81,000	106,100		
13'8"	Short	56,400	82,000	107,600		
13'8"	Long	56,825	82,000	107,375		
13'10"	Short	57,163	82,938	109,719		
13'10"	Long	57,770	83,000	108,830		
14'0"	Short	57,763	83,938	110,133		
14'0"	Long	58,625	84,000	109,375		
14'2"	Short	58,846	84,938	111,213		
14'2"	Long	59,170	85,000	110,830		
14'4"	Short	59,163	85,938	112,773		
14'4"	Long	60,170	86,000	111,830		
14'6"	Short	59,983	86,938	113,833		
14'6"	Long	61,170	87,000	112,830		
14'8"	Short	60,563	87,938	115,313		
14'8"	Long	64,812	88,406	88,000	109,594	131,188
14'10"	Short	61,263	88,938	116,613		
14'10"	Long	45,600	46,700	89,000	110,700	132,400
15'0"	Short	61,938	87,938	89,938	110,938	137,938
15'0"	Long	46,600	46,600	90,000	113,400	
15'12"	Short	62,663	87,600	90,938	105,076	119,213
15'2"	Long	47,600	46,900	91,000	112,700	134,400
15'4"	Short	53,600	59,200	104,800	130,400	
15'4"	Long	47,260	46,625	92,000	114,375	136,750
15'6"	Short	46,824	46,812	93,000	116,168	139,376
15'6"	Long	47,600	47,000	93,000	115,700	138,400
15'8"	Short	47,624	47,012	94,800	117,768	140,376
15'8"	Long	48,600	47,100	94,000	116,700	139,400
15'10"	Short	48,624	47,1812	95,000	118,168	141,376
15'10"	Long	49,167	47,2084	96,000	119,833	
16'0"	Short	49,624	47,2812	96,000	119,188	142,376
16'0"	Long	50,600	47,300	96,000	118,700	141,400

Notice of Treatment

11755

Applicator: Florida Pest Control & Chemical Co. (www.flapest.com)

Address: 13454 Ave

City: L.C. Phone: 7521703

Site Location: Subdivision _____

Lot # _____ Block# _____ Permit # 23811

Address: 401 SW Little Rd

Product used

Active Ingredient

% Concentration

☐ Premise Imidacloprid 0.1%

☐ Termidor Fipronil 0.12%

☒ Bora-Care Disodium Octaborate Tetrahydrate 23.0%

Type treatment:

☐ Soil

☒ Wood

Area Treated

Square feet

Linear feet

Gallons Applied

Dwelling

2596

661

4

As per Florida Building Code 104.2.6 – If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line _____

12/29/05
Date

1100
Time

GUNNY F254
Print Technician's Name

Remarks: _____



Applicator - White

Permit File - Canary

Permit Holder - Pink

10/05

©




NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

COLUMBIA
COUNTY,
FLORIDA
(UNINCORPORATED AREAS)

PANEL 175 OF 290

PANEL LOCATION



COMMUNITY-PANEL NUMBER

120070 0175 B


EFFECTIVE DATE:

JANUARY 6, 1988



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT Version 1.0. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. Further information




NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

COLUMBIA
COUNTY,
FLORIDA
(UNINCORPORATED AREAS)

PANEL 225 OF 290

PANEL LOCATION



COMMUNITY-PANEL NUMBER

120070 0225 B

EFFECTIVE DATE:

JANUARY 6, 1988



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT Version 1.0. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. Further information about National Flood Insurance Program flood hazard maps is available at www.fema.gov/mit/tsd.

Print Date: 10/31/2005 (printed at scale and type A)