


NOTES:

- Products and installations depicted satisfy the requirements of the Florida Building Code, Building 7th Edition (2020) for design wind pressures and overall sizes noted.
- Wood bucks, wood framing, steel stud framing, concrete and concrete masonry are by others and shall be designed by the architect or engineer of record to resist the loads imparted to them.
- Wood buck strips and wood frames are assumed S-P-F (G=0.42) or denser. Buck width shall be greater than the frame width. Tapered or partial width buck strips are not allowed.
- Concrete masonry installations are assumed at least ASTM C90 normal weight hollow masonry units with a 1-1/4" wall thickness or normal weight concrete with a minimum compressive strength of $f'_c = 3,000$ psi.
- Metal stud frames are assumed to be a minimum 18 gauge 33 KSI steel.
- Wood screws shall be corrosion resistant and meet the requirements of ANSI/ASME B18.6.1
- Tapcon masonry anchors shall have a minimum embedment of 1-1/2" or full penetration of concrete masonry unit shell. They shall also have a minimum of 2" edge distance. Install concrete masonry anchors per manufacturer's installation instructions.
- TEKS screws shall be corrosion resistant and shall be ASTM A510 Grade 1018 or equivalent.
- Maximum permitted shim thickness is 1/4". Shims shall be non-compressible and load bearing type. Every through-frame fastener shall have a shim.
- Short term load duration factors have not been used for evaluation of aluminum and steel components. Load duration factor $C_D = 1.6$ utilized for connections to wood.
- Products are impact resistant and do not require approved protection devices if used in wind-borne debris regions.
- Approved for use in High Velocity Hurricane Zone (HVHZ).

CONTENTS:

Sheet 1	Notes and Elevations
Sheets 2-5	Frame Installations
Sheet 6	Glazing Details
Sheet 7	Sections and Bill of Materials
Sheet 8	Components


47000 SINGLE HUNG WINDOW (IMPACT)
 MAXIMUM SIZE: 52-1/8" WIDE X 49-5/8" TALL
 MAXIMUM GLAZING SIZE: 46-7/8" WIDE X 19-7/8" TALL
 DESIGN PRESSURE: +35/-65 PSF
 LARGE MISSILE IMPACT RESISTANT



ANCHOR
 (SEE SHEETS 2 TO 5)

Design Pressure Rating	Impact Rating
+35/-65 psf	Large Missile

NOTE: Structural Performance +60/-65 psf
 Impact/Cycle Performance +60/-65 psf
 Water Test Performance +5.25 psf



Joseph A. Reed, PE
 FL PE 58920
 FL REG 33474
 5 Leigh Dr.
 York, PA 17406
 717-846-1200

2021.01.08 09:27:49 -05'00'




47000 Single Hung - Impact Notes and Elevations

TAFCO Corporation
 1953 North 17th Avenue
 Melrose Park, IL 60160

Drawing No.: 23824-1-1001
 Project No.: 23824-1
 Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 1 of 8



Joseph A. Reed, PE
FL PE 58920
FL REG 33474
5 Leigh Dr.
York, PA 17406
717-846-1200

Joseph A. Reed
2021.01.08 09:27:49 -05'00'



**47000 Single Hung - Impact
Through Frame Installations
Wood**

TAFCO Corporation
1953 North 17th Avenue
Melrose Park, IL 60160


Drawing No.: 23824-1-1001
Project No.: 23824-1
Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 2 of 8



JAMB



Joseph A. Reed, PE
FL PE 58920
FL REG 33474
5 Leigh Dr.
York, PA 17406
717-846-1200

Joseph A. Reed
2021.01.08 09:27:49 -05'00'




47000 Single Hung - Impact
Through Frame Installations
Steel Stud

TAFCO Corporation
1953 North 17th Avenue
Melrose Park, IL 60160

Drawing No.: 23824-1-1001
Project No.: 23824-1
Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 3 of 8



Joseph A. Reed, PE
 FL PE 58920
 FL REG 33474
 5 Leigh Dr.
 York, PA 17406
 717-846-1200

Joseph A. Reed

2021.01.08 09:27:49 -05'00'



47000 Single Hung - Impact
 Through Frame Installations
 Concrete or CMU

TAFCO Corporation
 1953 North 17th Avenue
 Melrose Park, IL 60160

Drawing No.: 23824-1-1001
 Project No.: 23824-1
 Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 4 of 8



Joseph A. Reed, PE
FL PE 58920
FL REG 33474
5 Leigh Dr.
York, PA 17406
717-846-1200

Joseph A. Reed
2021.01.08 09:27:49 -05'00'

47000 Single Hung - Impact
Through Frame Installations
Concrete or CMU with Buck Strip

TAFCO Corporation
1953 North 17th Avenue
Melrose Park, IL 60160



Drawing No.: 23824-1-1001
Project No.: 23824-1
Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 5 of 8

GLAZING DETAIL

G1 — LAMINATED GLASS



Joseph A. Reed, PE
 FL PE 58920
 FL REG 33474
 5 Leigh Dr.
 York, PA 17406
 717-846-1200

Joseph A. Reed
 2021.01.08 09:27:49 -05'00'


**47000 Single Hung - Impact
 Glazing Details**

TAFCO Corporation
 1953 North 17th Avenue
 Melrose Park, IL 60160


Drawing No.: 23824-1-1001
 Project No.: 23824-1
 Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS


Sheet 6 of 8



VERTICAL SECTION




HORIZONTAL SECTION AT TOP SASH



HORIZONTAL SECTION AT BOTTOM SASH

HARDWARE		
ITEM	NUMBER	LOCATION
SWEEP LOCK	2	TOP RAIL OF BOTTOM SASH
PINCH LOCK	2	BOTTOM RAIL OF BOTTOM SASH
BLOCK AND TACKLE BALANCE	2	ONE EACH JAMB
WEATHERSTRIPPING		
ITEM	NUMBER	LOCATION
2-FIN PILE	2 ROWS	HEAD FRAME
2 FIN PILE	1 ROW	TOP SASH BOTTOM RAIL
2-FIN PILE	1 ROW	BOTTOM SASH TOP RAIL
2-FIN PILE	1 ROW	SILL UPSTAND
VINYL BULB	1 ROW	SILL
2-FIN PILE	2 ROWS	TOP SASH STILES
2-FIN PILE	2 ROWS	BOTTOM SASH STILES

ITEM NO.	NAME	MATERIAL	DESCRIP.
1	Head	6063-T5	EXTRUSION
2	Jamb	6063-T5	EXTRUSION
3	Sill	6063-T5	EXTRUSION
4	Bottom Sash Bottom Rail	6063-T5	EXTRUSION
5	Fixed Sash Top Rail	6063-T5	EXTRUSION
7	Fixed Sash Support	6063-T5	EXTRUSION
8	Pinch Lock	6063-T5	EXTRUSION
9	Glazing Bead	6063-T5	EXTRUSION
10	Sash Stile	6063-T5	EXTRUSION
11	Fixed Sash Bottom Rail	6063-T5	EXTRUSION
12	Bottom Sash Top Rail	6063-T5	EXTRUSION
13	Track Filler	PA6	INJECTION MOLD
14	Reinforcement Retainer	PA6	INJECTION MOLD
15	Wedge Gasket	EPDM RUBBER	EXTRUSION
16	Wedge Gasket	EPDM RUBBER	EXTRUSION
17	1/2" x 5/8" Reinforcement	STEEL	FLAT BAR STOCK



Joseph A. Reed, PE
FL PE 58920
FL REG 33474
5 Leigh Dr.
York, PA 17406
717-846-1200
2021.01.08 09:27:49 -05'00'


47000 Single Hung - Impact
Sections and Bill of Material

TAFCO Corporation
1953 North 17th Avenue
Melrose Park, IL 60160


Drawing No.: 23824-1-1001
Project No.: 23824-1
Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS


Sheet 7 of 8




HEAD
6063-T5




SILL
6063-T5




JAMB
6063-T5




BOTTOM SASH BOTTOM RAIL
6063-T5




BOTTOM SASH TOP RAIL
6063-T5




TOP SASH BOTTOM RAIL
6063-T5



TOP SASH TOP RAIL
6063-T5



SASH STILE
6063-T5




BLAZING BEAD
6063-T5




Joseph A. Reed, PE
FL PE 58920
FL REG 33474
5 Leigh Dr.
York, PA 17406
717-846-1200

Joseph A. Reed


2021.01.08 09:27:49 -05'00'



SASH SUPPORT
6063-T5



PINCH LOCK
6063-T5



REINFORCEMENT
STEEL


47000 Single Hung - Impact Components

TAFCO Corporation
1953 North 17th Avenue
Melrose Park, IL 60160

Drawing No.: 23824-1-1001
Project No.: 23824-1
Drawn By: JAR Rev: 1 Date: 01/08/21

Scale: NTS

Sheet 8 of 8



MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

401 S. Main Street
Suite 200
Mt. Airy, NC 27030
Phone: (336) 415-3540
Fax: (336) 719-2020

1009 East Avenue
North Augusta, SC 29841
Phone: (803) 279-7799
Fax: (803) 279-3848
www.MandaA-inc.com

15 April 2021

**State of Florida- Metal Building Component Product Approval
Engineering Evaluation Report
M&A Project No. 20300S**

Prepared By:

Wayne S. Moore, P.E.
FL PE No. 57170
M&A COA No. 8966

Manufacturer:

Steel Buildings and Structures, Inc.
820 Reeves Drive
Mount Airy, NC 27030

Product:

AG Metal Wall Panel

Product Description:

Low and high wind rated wall panels.

FL Product Code Approval No.: **FL22562**

Code Compliance Statement:

Moore and Associates Engineering and Consulting, Inc. (M&A) has reviewed the plans, calculations and testing information that applies to Florida Product Approval #FL22562 under the 2020 Florida Building Code, 7th Edition and finds them in compliance.

Certificate of Independence:

Wayne S. Moore, P.E. and M&A does not have, nor does it intend to acquire or will it acquire, a financial interest the company manufacturing or distributing the product or products being tested. Wayne S. Moore, P.E. is not employed by nor is M&A owned, operated or controlled by the company manufacturing or distributing the product or products being tested. Wayne S. Moore, P.E. and other M&A staff who are licensed Professional Engineers registered in the State of Florida who perform technical evaluations do not have, nor will they acquire, a financial interest in the company manufacturing or distributing the product or products for which test reports are being issued. Wayne S. Moore, P.E. and other M&A staff who are licensed Professional Engineers registered in the State of Florida who perform technical evaluations do not have, nor will acquire, a financial interest in any other entity involved in the approval process of the product or products.



**National Society of
Professional Engineers®**

Supporting Documents:

Calculations: Structural calculations dated 11 January 2021 performed by John Smith, E.I.T. and checked by Wayne S. Moore, P.E.

Drawings: Drawings SK-1 through SK-6 signed/sealed by Wayne S. Moore, P.E.

Testing: ATLNC #0321.01-17 test report dated 04/05/2017 and signed/sealed by David Johnson, P.E.

Limitations and Conditions of Use:

1. Structural calculations were performed in accordance with the 2020 FBC, 7th Edition and compared to test results performed under previous FBC given that testing of panel was performed to maximum deflection and ultimate failure and that manufacturer utilizes same panel, supports and attachment fasteners.
2. Maximum allowable design pressure shall be as indicated on plans for each configuration.
3. This product is for use outside of the High Velocity Hurricane Zone (HVHZ).
4. This product shall be minimum 29 gauge thick galvalume coated steel with minimum yield stress of 80 ksi.
5. Panel material shall comply with 2020 FBC, 7th Edition Sections 1405.2, 1405.11 and 1405.17.
6. All supporting structural members shall be capable of supporting superimposed loads applied to this product.
7. Fasteners must consist of minimum 12-14 x $\frac{3}{4}$ " self-drilling fasteners (SDFs) with control seal washers.
8. Analysis/design was performed assuming a maximum mean roof height of 20'-0" and a roof slope of 3:12 (14 degrees) or less.
9. Product shall be installed into substrates shown on installation drawings and shall not exceed spacing limitations.
10. Site conditions that deviate from calculation, drawing and/or testing limitation noted shall require further analysis by a licensed Professional Engineer registered in the State of Florida.

Quality Assurance:

The manufacturer has demonstrated compliance of proper quality assurance/quality control (QA/QC) in accordance with the Florida Administrative Code Rule 61G20-3.005. Manufacturer's QA/QC plan and practices have been audited by an approved quality assurance entity (Subsection 3).

Signature/Seal:





AG Metal Wall Calc Set

Design Loads:

$$space_1 := 5 \cdot ft \text{ o.c.}$$

$$space_2 := 4 \cdot ft \text{ o.c.}$$

**Risk Cat. I
Exposure B**

Low Wind Spacing

High Wind Spacing

$$width := 180 \cdot in$$

$$Ht_{roof} := \frac{width}{2} \cdot 0.25 = 1.875 \text{ ft}$$

$$Ht := 120 \text{ in}$$

$$mean_{r,ht} := 20 \text{ ft} = 20 \text{ ft}$$

Note: Test Protocol ASTM E330 requires a
50% safety factor over design load pressures.

$$FS := 1.5$$

Low Wind 140mph (Vasd=108mph) Components and Cladding Doors and Window Pressures:

$$\lambda := 0.89 \quad mean_{r,ht} = 20 \text{ ft} \quad \text{(Based on 2018 IBC (ASCE 7-16), Pg. 362)}$$

Adjustment Factor

Wall (Wind Area = 20 square ft):

Note: Values found from interpolation using
Vasd wind speeds since structure is Risk I.

$$P_{w_{net30pos108}} := 20.04 \text{ psf} \cdot \lambda = 17.836 \text{ psf}$$

(Based on 2018 IBC (ASCE 7-16), Pg. 352-353)

$$P_{w_{net30neg108}} := -26.24 \text{ psf} \cdot \lambda = -23.354 \text{ psf}$$

Note: Used Zone 5 (more conservative)

Note: Highlighted values indicate input.



Client: SBSI Job No. 203005 Sheet No. 2
Job Name: Keystone FPC Update Rev. 0 Computed By: JS
Subject: Design (Exp. B) Date: 1/12/21 Checked By: [Signature]

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

High Wind 170mph (Vasd=132mph) Components and Cladding Doors and Window Pressures:

$\lambda := 0.89$ $mean_{r,ft} = 20\ ft$ (Based on 2018 IBC (ASCE 7-16), Pg. 362)

Adjustment Factor

Note: Values found from interpolation using
Vasd wind speeds since structure is Risk I.

Wall (Wind Area = 20 square ft):

$Pw_{net30post132} := 29.94\ psf \cdot \lambda = 26.647\ psf$ (Based on 2018 IBC (ASCE 7-16), Pg. 353)

$Pw_{net30neg132} := -39.2\ psf \cdot \lambda = -34.888\ psf$

Note: Used Zone 5 to be
conservative.

Note: Highlighted values indicate input.

CHAPTER 30

WIND LOADS: COMPONENTS AND CLADDING

30.1 SCOPE

30.1.1 Building Types. This chapter applies to the determination of wind pressures on components and cladding (C&C) on buildings.

1. Part 1 is applicable to an enclosed or partially enclosed

- Low-rise building (see definition in Section 26.2); or
- Building with $h \leq 60$ ft (18.3 m).

The building has a flat roof, gable roof, multispans gable roof, hip roof, monoslope roof, stepped roof, or sawtooth roof, and the wind pressures are calculated from a wind pressure equation.

2. Part 2 is a simplified approach and is applicable to an enclosed

- Low-rise building (see definition in Section 26.2); or
- Building with $h \leq 60$ ft (18.3 m).

The building has a flat roof, gable roof, or hip roof, and the wind pressures are determined directly from a table.

3. Part 3 is applicable to an enclosed or partially enclosed

- Building with $h > 60$ ft (18.3 m).

The building has a flat roof, pitched roof, gable roof, hip roof, mansard roof, arched roof, or domed roof, and the wind pressures are calculated from a wind pressure equation.

4. Part 4 is a simplified approach and is applicable to an enclosed

- Building with $60 \text{ ft} < h \leq 160 \text{ ft}$ (18.3 m $< h \leq 48.8$ m).

The building has a flat roof, gable roof, hip roof, monoslope roof, or mansard roof, and the wind pressures are determined directly from a table.

5. Part 5 is applicable to an open building of all heights that has a pitched free roof, monoslope free roof, or troughed free roof.

6. Part 6 is applicable to building appendances such as roof overhangs, parapets, and rooftop equipment.

7. Part 7 is applicable to non-building structures – circular bins, silos and tanks; and rooftop solar panels.

- Circular Bins, Silos and Tanks: $h \leq 120$ ft (38.6 m).
- Rooftop Solar Panels: Buildings of all heights with flat roofs or Gable or Hip Roofs with roof slopes less than or equal to 7 degrees

30.1.2 Conditions. A building that has design wind loads determined in accordance with this chapter shall comply with all of the following conditions:

1. The building is a regular-shaped building as defined in Section 26.2; and
2. The building does not have response characteristics that make it subject to across-wind loading, vortex shedding, or instability caused by galloping or flutter; nor does it have a site

location for which channeling effects or buffeting in the wake of upwind obstructions warrant special consideration.

30.1.3 Limitations. The provisions of this chapter take into consideration the load magnification effect caused by gusts in resonance with along-wind vibrations of flexible buildings. The loads on buildings that do not meet the requirements of Section 30.1.2 or that have unusual shapes or response characteristics shall be determined using recognized literature documenting such wind load effects or shall use the wind tunnel procedure specified in Chapter 31.

30.1.4 Shielding. There shall be no reductions in velocity pressure caused by apparent shielding afforded by buildings and other structures or terrain features.

30.1.5 Air-Permeable Cladding. Design wind loads determined from Chapter 30 shall be used for air-permeable claddings, including modular vegetative roof assemblies, unless approved test data or recognized literature demonstrates lower loads for the type of air-permeable cladding being considered.

30.2 GENERAL REQUIREMENTS

30.2.1 Wind Load Parameters Specified in Chapter 26. The following wind load parameters are specified in Chapter 26:

- Basic wind speed, V (Section 26.5).
- Wind directionality factor, K_d (Section 26.6).
- Exposure category (Section 26.7).
- Topographic factor, K_z (Section 26.8).
- Ground elevation factor, K_e (Section 26.9)
- Velocity pressure exposure coefficient, K_z , or K_h (Section 26.10.1); Velocity pressure, q_z (Section 26.10.2)
- Gust-effect factor (Section 26.11).
- Enclosure classification (Section 26.12).
- Internal pressure coefficient, (GC_p) (Section 26.13).

30.2.2 Minimum Design Wind Pressures. The design wind pressure for C&C of buildings shall not be less than a net pressure of 16 lb/ft² (0.77 kN/m²) acting in either direction normal to the surface.

30.2.3 Tributary Areas Greater than 700 ft² (65 m²). C&C elements with tributary areas greater than 700 ft² (65 m²) shall be permitted to be designed using the provisions for main wind force resisting systems (MWFRS).

30.2.4 External Pressure Coefficients. Combined gust-effect factor and external pressure coefficients for C&C, (GC_p) , are given in the figures associated with this chapter. The pressure coefficient values and gust-effect factor shall not be separated.

Net Design Wind Pressure, P_{net} , in lb/ft^2 , for Exposure B at $h = 30 \text{ ft}$, $V = 95\text{--}130 \text{ mph}$

Zone	Effective Wind Area (ft²)	Basic Wind Speed (mph)												
		95	100	105	110	115	120	130						
Walls														
4	10	16.2	-17.6	18.0	-19.5	19.8	-21.5	21.8	-23.6	23.8	-25.8	25.9	-28.1	30.4
4	20	15.5	-16.9	17.2	-18.7	18.9	-20.6	20.8	-22.6	22.7	-24.7	24.7	-26.9	29.0
4	50	14.5	-15.9	16.1	-17.6	17.8	-19.4	19.5	-21.3	21.3	-23.3	23.2	-25.4	27.2
4	100	13.8	-15.2	15.3	-16.8	16.9	-18.5	18.5	-20.4	20.2	-22.2	22.0	-24.2	25.9
5	10	16.2	-21.7	18.0	-24.1	19.8	-26.6	21.8	-29.1	23.8	-31.9	25.9	-34.7	30.4
5	20	15.5	-20.3	17.2	-22.5	18.9	-24.8	20.8	-27.2	22.7	-29.7	24.7	-32.4	29.0
5	50	14.5	-18.3	16.1	-20.3	17.8	-22.4	19.5	-24.6	21.3	-26.9	23.2	-29.3	27.2
5	100	13.8	-16.9	15.3	-18.7	16.9	-20.6	18.5	-22.6	20.2	-24.7	22.0	-26.9	25.9
1	10	6.6	-25.9	7.3	-28.7	8.1	-31.6	8.9	-34.7	9.7	-37.9	10.5	-41.3	12.4
1	20	6.2	-24.2	6.9	-26.8	7.6	-29.5	8.3	-32.4	9.1	-35.4	9.9	-38.5	11.6
1	50	5.6	-21.9	6.3	-24.3	6.9	-26.8	7.6	-29.4	8.3	-32.1	9.0	-34.9	10.6
1	100	5.2	-20.2	5.8	-22.4	6.4	-24.7	7.0	-27.1	7.7	-29.6	8.3	-32.2	9.8
1'	10	6.6	-14.9	7.3	-16.5	8.1	-18.2	8.9	-19.9	9.7	-21.8	10.5	-23.7	12.4
1'	20	6.2	-14.9	6.9	-16.5	7.6	-18.2	8.3	-19.9	9.1	-21.8	9.9	-23.7	11.6
1'	50	5.6	-14.9	6.3	-16.5	6.9	-18.2	7.6	-19.9	8.3	-21.8	9.0	-23.7	10.6
1'	100	5.2	-14.9	5.8	-16.5	6.4	-18.2	7.0	-19.9	7.7	-21.8	8.3	-23.7	9.8
2	10	6.6	-34.1	7.3	-37.8	8.1	-41.7	8.9	-45.7	9.7	-50.0	10.5	-54.4	12.4
2	20	6.2	-31.9	6.9	-35.4	7.6	-39.0	8.3	-42.8	9.1	-46.8	9.9	-50.9	11.6
2	50	5.6	-29.0	6.3	-32.2	6.9	-35.5	7.6	-38.9	8.3	-42.5	9.0	-46.3	10.6
2	100	5.2	-26.8	5.8	-29.7	6.4	-32.8	7.0	-36.0	7.7	-39.3	8.3	-42.8	9.8
3	10	6.6	-46.5	7.3	-51.5	8.1	-56.8	8.9	-62.3	9.7	-68.1	10.5	-74.2	12.4
3	20	6.2	-42.1	6.9	-46.7	7.6	-51.4	8.3	-56.5	9.1	-61.7	9.9	-67.2	11.6
3	50	5.6	-36.3	6.3	-40.2	6.9	-44.4	7.6	-48.7	8.3	-53.2	9.0	-57.9	10.6
3	100	5.2	-31.9	5.8	-35.4	6.4	-39.0	7.0	-42.8	7.7	-46.8	8.3	-50.9	9.8
Flat/Hip/Gable Roof 0 to 7 Degrees														
1	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	18.4
1	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	16.6
1	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	14.2
1	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	12.4
2e	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	18.4
2e	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	16.6
2e	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	14.2
2e	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	12.4
2n	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
2n	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
2n	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
2n	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
2r	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
2r	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
2r	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
2r	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
3e	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
3e	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
3e	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
3e	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
3r	10	9.8	-52.0	10.9	-57.6	12.0	-63.5	13.2	-69.7	14.4	-76.2	15.7	-83.0	18.4
3r	20	8.9	-44.6	9.8	-49.4	10.8	-54.4	11.9	-59.7	13.0	-65.3	14.1	-71.1	16.6
3r	50	7.6	-34.7	8.4	-38.4	9.3	-42.4	10.2	-46.5	11.1	-50.8	12.1	-55.4	14.2
3r	100	6.6	-27.2	7.3	-30.2	8.1	-33.3	8.9	-36.5	9.7	-39.9	10.5	-43.5	12.4
Gable Roof > 7 to 20 Degrees														
1	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	18.4
1	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	16.6
1	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	14.2
1	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	12.4
2e	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	18.4
2e	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	16.6
2e	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	14.2
2e	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	12.4
2n	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
2n	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
2n	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
2n	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
2r	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
2r	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
2r	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
2r	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
3e	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	18.4
3e	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	16.6
3e	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	14.2
3e	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	12.4
3r	10	9.8	-52.0	10.9	-57.6	12.0	-63.5	13.2	-69.7	14.4	-76.2	15.7	-83.0	18.4
3r	20	8.9	-44.6	9.8	-49.4	10.8	-54.4	11.9	-59.7	13.0	-65.3	14.1	-71.1	16.6
3r	50	7.6	-34.7	8.4	-38.4	9.3	-42.4	10.2	-46.5	11.1	-50.8	12.1	-55.4	14.2
3r	100	6.6	-27.2	7.3	-30.2	8.1	-33.3	8.9	-36.5	9.7	-39.9	10.5	-43.5	12.4

Notes: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively. For effective wind areas between those given above, the load may be interpolated; otherwise, use the load associated with the lower effective area. Gray shading indicates that the final value, including all permitted reductions, used in the design shall not be less than that required by Section 30.2.2. Metric conversions: $1.0 \text{ ft} = 0.3048 \text{ m}$, $1.0 \text{ ft}^2 = 0.0929 \text{ m}^2$, $1.0 \text{ lb}/\text{ft}^2 = 0.0479 \text{ kN}/\text{m}^2$.

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 [$h \leq 60 \text{ ft}$ ($h \leq 18.3 \text{ m}$): Design Wind Pressures for Enclosed Buildings—Walls and Roofs]

continues

Net Design Wind Pressure, $P_{net(z)}$, in lb/ft^2 , for Exposure B at $h = 30 \text{ ft}$, $V = 140\text{--}200 \text{ mph}$

Basic Wind Speed (mph)																
Zone	Effective Wind Area (ft ²)	140	150	160	170	180	190	200								
Walls	4	10	35.3	-38.2	40.5	-38.2	46.1	-50.0	52.0	-56.4	58.3	-63.2	64.9	-70.4	72.0	-78.1
	4	20	33.7	-36.7	38.7	-36.7	44.0	-47.9	49.6	-54.1	55.7	-60.6	62.0	-67.5	68.7	-74.8
	4	50	31.6	-34.6	36.2	-34.6	41.2	-45.1	46.6	-51.0	52.2	-57.1	58.1	-63.7	64.4	-70.5
	4	100	30.0	-33.0	34.4	-33.0	39.2	-43.1	44.2	-48.6	49.6	-54.5	55.2	-60.7	61.2	-67.3
	5	10	35.3	-47.2	40.5	-47.2	46.1	-61.7	52.0	-69.6	58.3	-78.0	64.9	-87.0	72.0	-96.3
	5	20	33.7	-44.0	38.7	-44.0	44.0	-57.5	49.6	-64.9	55.7	-72.8	62.0	-81.1	68.7	-89.9
	5	50	31.6	-39.8	36.2	-39.8	41.2	-52.0	46.6	-58.7	52.2	-65.8	58.1	-73.4	64.4	-81.3
	5	100	30.0	-36.7	34.4	-36.7	39.2	-47.9	44.2	-54.1	49.6	-60.6	55.2	-67.5	61.2	-74.8
	1	10	14.3	-56.2	16.5	-56.2	18.7	-73.4	21.1	-82.8	23.7	-92.9	26.4	-103.5	29.3	-114.6
	1	20	13.4	-52.5	15.4	-52.5	17.6	-68.5	19.8	-77.4	22.2	-86.7	24.8	-96.6	27.4	-107.1
Flat/Hip/Gable Roof 0 to 7 Degrees	1	50	12.3	-47.6	14.1	-47.6	16.0	-62.1	18.1	-70.1	20.3	-78.6	22.6	-87.6	25.0	-97.1
	1	100	11.4	-43.9	13.0	-43.9	14.8	-57.3	16.7	-64.7	18.8	-72.5	20.9	-80.8	23.2	-89.5
	1'	10	14.3	-32.3	16.5	-32.3	18.7	-42.1	21.1	-47.6	23.7	-53.3	26.4	-59.4	29.3	-65.9
	1'	20	13.4	-32.3	15.4	-32.3	17.6	-42.1	19.8	-47.6	22.2	-53.3	24.8	-59.4	27.4	-65.9
	1'	50	12.3	-32.3	14.1	-32.3	16.0	-42.1	18.1	-47.6	20.3	-53.3	22.6	-59.4	25.0	-65.9
	1'	100	11.4	-32.3	13.0	-32.3	14.8	-42.1	16.7	-47.6	18.8	-53.3	20.9	-59.4	23.2	-65.9
	2	10	14.3	-74.1	16.5	-74.1	18.7	-96.8	21.1	-109.3	23.7	-122.5	26.4	-136.5	29.3	-151.2
	2	20	13.4	-69.3	15.4	-69.3	17.6	-90.6	19.8	-102.2	22.2	-114.6	24.8	-127.7	27.4	-141.5
	2	50	12.3	-63.0	14.1	-63.0	16.0	-82.3	18.1	-92.9	20.3	-104.2	22.6	-116.1	25.0	-128.7
	2	100	11.4	-58.3	13.0	-58.3	14.8	-76.1	16.7	-85.9	18.8	-96.3	20.9	-107.3	23.2	-118.9
Gable Roof > 7 to 20 Degrees	3	10	14.3	-101.0	16.5	-101.0	18.7	-131.9	21.1	-148.9	23.7	-166.9	26.4	-186.0	29.3	-206.1
	3	20	13.4	-91.5	15.4	-91.5	17.6	-119.5	19.8	-134.9	22.2	-151.2	24.8	-168.5	27.4	-186.7
	3	50	12.3	-89.9	14.1	-89.9	16.0	-103.0	18.1	-116.3	20.3	-130.4	22.6	-145.3	25.0	-161.0
	3	100	11.4	-78.9	13.0	-78.9	14.8	-90.6	16.7	-102.2	18.8	-114.6	20.9	-127.7	23.2	-141.5
	1	10	21.4	-65.1	24.5	-65.1	27.9	-85.1	31.5	-96.0	35.3	-107.7	39.4	-120.0	43.6	-132.9
	1	20	19.3	-65.1	22.1	-65.1	25.2	-85.1	28.4	-96.0	31.8	-107.7	35.5	-120.0	39.3	-132.9
	1	50	16.5	-39.6	18.9	-39.6	21.5	-51.8	24.3	-58.4	27.2	-65.5	30.3	-73.0	33.6	-80.9
	1	100	14.3	-20.3	16.5	-20.3	18.7	-26.5	21.1	-30.0	23.7	-33.6	26.4	-37.4	29.3	-41.5
	2e	10	21.4	-65.1	24.5	-65.1	27.9	-85.1	31.5	-96.0	35.3	-107.7	39.4	-120.0	43.6	-132.9
	2e	20	19.3	-65.1	22.1	-65.1	25.2	-85.1	28.4	-96.0	31.8	-107.7	35.5	-120.0	39.3	-132.9
Gable Roof > 20 to 30 Degrees	2e	50	16.5	-39.6	18.9	-39.6	21.5	-51.8	24.3	-58.4	27.2	-65.5	30.3	-73.0	33.6	-80.9
	2e	100	14.3	-20.3	16.5	-20.3	18.7	-26.5	21.1	-30.0	23.7	-33.6	26.4	-37.4	29.3	-41.5
	2n	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
	2n	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
	2n	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
	2n	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
	2r	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
	2r	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
	2r	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
	2r	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
Gable Roof > 30 to 40 Degrees	3e	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
	3e	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
	3e	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
	3e	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
	3r	10	21.4	-112.9	24.5	-112.9	27.9	-147.5	31.5	-166.5	35.3	-186.7	39.4	-208.0	43.6	-230.5
	3r	20	19.3	-96.8	22.1	-96.8	25.2	-126.4	28.4	-142.7	31.8	-159.9	35.5	-178.2	39.3	-197.5
	3r	50	16.5	-75.4	18.9	-75.4	21.5	-98.4	24.3	-111.1	27.2	-124.6	30.3	-138.8	33.6	-153.8
	3r	100	14.3	-59.2	16.5	-59.2	18.7	-77.3	21.1	-87.2	23.7	-97.8	26.4	-109.0	29.3	-120.7

Notes: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively. For effective wind areas between those given above, the load may be interpolated; otherwise, use the load associated with the lower effective area. Gray shading indicates that the final value, including all permitted reductions, used in the design shall not be less than that required by Section 30.2.2. Metric conversions: $1.0 \text{ ft} = 0.3048 \text{ m}$, $1.0 \text{ ft}^2 = 0.0929 \text{ m}^2$, $1.0 \text{ lb}/\text{ft}^2 = 0.0479 \text{ kN}/\text{m}^2$.

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 ($h \leq 60 \text{ ft}$ ($h \leq 18.3 \text{ m}$)): Design Wind Pressures for Enclosed Buildings—Walls and Roofs

continues

Net Design Wind Pressure for Roof Overhang, p_{net30} , in lb/ft², for Exposure B at $h = 30$ ft, $V = 95$ –200 mph

Zone	Effective Wind Area (ft ²)	Wind Speed (mph)															
		95	100	105	110	115	120	130	140	150	160	170	180	190	200	210	220
1	10	-31.6	-35.1	-38.7	-42.4	-46.4	-50.5	-59.3	-68.7	-78.9	-89.8	-101.3	-113.6	-126.6	-140.0	-153.8	-168.0
1	20	-29.1	-32.2	-35.5	-39.0	-42.6	-46.4	-54.5	-63.2	-72.5	-82.5	-93.2	-104.5	-116.4	-128.7	-141.4	-154.5
1	50	-25.7	-28.5	-31.4	-34.5	-37.7	-41.1	-48.2	-55.9	-64.1	-73.0	-82.4	-92.4	-102.9	-113.8	-125.0	-136.5
1	100	-23.2	-25.7	-28.3	-31.1	-34.0	-37.0	-43.4	-50.4	-57.8	-65.8	-74.2	-83.2	-92.7	-102.7	-113.0	-123.5
2e	10	-38.1	-42.3	-46.6	-51.1	-55.9	-60.9	-71.4	-82.8	-95.1	-108.2	-122.1	-136.9	-152.6	-169.0	-185.8	-203.0
2e	20	-31.6	-35.0	-38.6	-42.3	-46.3	-50.4	-59.1	-68.6	-78.7	-89.6	-101.1	-113.4	-126.3	-140.0	-154.2	-168.9
2e	50	-22.9	-25.4	-28.0	-30.7	-33.6	-36.6	-42.9	-49.8	-57.1	-65.0	-73.4	-82.3	-91.7	-101.6	-111.8	-122.3
2e	100	-22.0	-24.4	-26.9	-29.5	-32.3	-35.1	-41.2	-47.8	-54.9	-62.4	-70.5	-79.0	-88.1	-97.6	-107.4	-117.5
2r	10	-46.1	-51.1	-56.3	-61.8	-67.5	-73.5	-86.3	-100.1	-114.9	-130.7	-147.6	-165.5	-184.4	-204.3	-224.3	-244.5
2r	20	-39.7	-44.0	-48.5	-53.2	-58.1	-63.3	-74.3	-86.2	-98.9	-112.5	-127.0	-142.4	-158.7	-175.8	-193.4	-211.4
2r	50	-31.2	-34.6	-38.1	-41.8	-45.7	-49.8	-58.4	-67.7	-77.7	-88.5	-99.9	-112.0	-124.7	-138.2	-152.2	-166.5
2r	100	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-120.9	-132.3
3	10	-45.2	-50.1	-55.3	-60.6	-66.3	-72.2	-84.7	-98.2	-112.8	-128.3	-144.8	-162.4	-180.9	-200.5	-220.3	-240.3
3	20	-36.4	-40.3	-44.5	-48.8	-53.4	-58.1	-68.2	-79.1	-90.8	-103.3	-116.6	-130.7	-145.7	-161.4	-177.5	-193.9
3	50	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-120.9	-132.3
3	100	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-120.9	-132.3

Note: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively.
Metric conversions: 1.0 ft = 0.3048 m; 1.0 ft² = 0.0929 m²; 1.0 lb/ft² = 0.0479 kN/m².

Adjustment Factor for Building Height and Exposure, λ

Mean Roof Height (ft)	Exposure		
	B	C	D
15	0.82	1.21	1.47
20	0.89	1.29	1.55
30	1.00	1.40	1.66
35	1.05	1.45	1.70
40	1.09	1.49	1.74
45	1.12	1.53	1.78
50	1.16	1.56	1.81
55	1.19	1.59	1.84
60	1.22	1.62	1.87

Note: Metric conversions: 1.0 ft = 0.3048 m; 1.0 ft² = 0.0929 m²; 1.0 lb/ft² = 0.0479 kN/m².

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 [$h \leq 60$ ft ($h \leq 18.3$ m)]; Design Wind Pressures for Enclosed Buildings—Walls and Roofs

Table 30.5-1 Steps to Determine C&C Wind Loads for Enclosed or Partially Enclosed Building with $h > 60$ ft ($h > 18.3$ m)

- Step 1: Determine risk category; see Table 1.5-1.
- Step 2: Determine the basic wind speed, V , for applicable risk category; see Figs. 26.5-1 and 26.5-2.
- Step 3: Determine wind load parameters:
 - Wind directionality factor, K_d ; see Section 26.6 and Table 26.6-1.
 - Exposure category B, C, or D; see Section 26.7.
 - Topographic factor, K_g ; see Section 26.8 and Fig. 26.8-1.
 - Ground elevation factor, K_z ; see Section 26.9 and Table 26.9-1
 - Enclosure classification; see Section 26.12.
- Step 4: Determine pressure coefficient, (GC_{pi}); see Section 26.13 and Table 26.13-1.
- Step 5: Determine velocity pressure exposure coefficient, K_z or K_h ; see Table 26.10-1.
- Step 6: Determine external pressure coefficient, (GC_{pe}):
 - Walls and flat roofs ($\theta < 10^\circ$), see Fig. 30.5-1
 - Gable and hip roofs, see Fig. 30.3-2 per Note 6 of Fig. 30.5-1
 - Arched roofs, see Fig. 27.3-3, Note 4
 - Domed roofs, see Fig. 30.3-7
- Step 7: Calculate wind pressure, p , Eq. (30.5-1).



American Test Lab, Inc
1122 Calvert Road Brevard, NC 28712
828-884-3700
atl@compurum.net atlnc.com

ATLNC # 0321.01-17

Report Date: 04/05/17

Miami Dade Certification # 16-0526.01
FL Organizational # TST 1555
IAS Certification # TL-423

Test Dates: 03/21/17 – 03/23/17

Test Requested By: Steel Building And Structures Inc.

820 Reeves Drive
Mount Airy, NC 27030
Phone 877-272-8276, Fax 336-551-3449

Test Standard: ASTM E 1592-05


Test Conditions: 65 - 75 degrees F

Description of products tested:

Specimens A, F 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawings SK-1, SK-3, SK-4, SK-5, SK-6. Panels attached to 2-1/2" x 2-1/2" x 14 ga. rafters/ post with 12-14" x 3/4" self drilling screws at 6" oc.

Specimen B, D 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawing SK-1, SK-3, SK-4, SK-5, SK-6 over 2-5/16" wide Hat Channel attached to 2-1/2" x 2-1/2" x 14 ga. rafter/post. Hat Channel was attached to each rafter with (2) 12-14 x 3/4" self drilling screws, panels to Hat Channels with 12-14 x 3/4" self drilling screws at 6" OC.

Specimen C, E 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawing SK-1, SK-3, SK-4, SK-5, SK-6 over 2-1/2" x 14 ga sq galvanized steel girth attached to 2-1/2" x 2-1/2" x 14 ga. rafter/post. Girth was attached to each rafter with 2" x 2" x 14 ga angle with (4) 12-14 x 3/4" self drilling screws, panels attached to girth with 12-14 x 3/4" self drilling screws at 6" OC.



Configuration:

Specimen A, (3) 4' purlin spans, 3 panels wide mounted horizontally.

Specimen B, (3) 4' purlin spans, 4' Hat Channel spans 3 panels wide mounted horizontally.

Specimen C, (3) 4' purlin spans, 4' girth spans with 2-1/2" tubes, 3 panels wide mounted horizontally.

Specimen D, 5' purlin spans, 4' Hat Channel spans 3 panels wide mounted horizontally.

Specimen E, (3) 5' purlin spans, 5' girth spans with 2-1/2" tubes, 3 panels wide mounted horizontally.

Specimen F, (3) 5' purlin spans, 3 panels wide mounted horizontally.

Rafter/Post/Girth Construction- 2-1/2" x 2-1/2" x 14 ga tube

Rafter Spacing- Specimen A B, C, 3 spans 48" OC with 12" overhang.
Specimen D, E, F, 3 spans 60" OC, with 12" overhang.

Hat Channel Spacing: Specimen B, 3 spans 48" OC with 12" overhang, rafter spacing 48" OC.
Specimen D, 3 spans 48" OC with 12" overhang, rafter spacing 60" OC.

2-1/2" Tube Girth Spacing: Specimen C, 3 spans 48" OC with 12" overhang, rafter spacing 48" OC.
Specimen D, 3 spans 60" OC with 12" overhang, rafter spacing 60" OC.

Rafter/Post Attachment- Each rafter/post was attached the chamber.

Test Specimens

Indicator Locations

Specimens A, F

	E		
	B	C	D
	A		

Specimens B, C,

	E		
	B	C	D
	A		

Specimens D, E

	E		
	B	C	D
	A		

Specimen A

Deflections in inches


Pressure Increments psf	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
Negative							
20	60	.75"	.02"	.83"	.03"	.93"	.03"
30	60	1.04"	.05"	1.12"	.07"	1.26"	.08"
40	60	1.45"	.15"	1.52"	.17"	1.73"	.20"
50	60	1.84"	.30"	1.92"	.33"	2.22"	.39"
60	60	2.35"	.55"	2.47"	.64"	2.90"	.76"
70	60	2.86"	.84"	2.97"	.99"	3.53"	1.22"
80	60						
90	60						
100	60						
110	60						
120	60						

Deflections in inches

Pressure Increments psf	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
Negative							
20	60	.80"	.02"	.81"	.02"	.93"	.03"
30	60	1.09"	.06"	1.06"	.06"	1.26"	.08"
40	60	1.50"	.17"	1.47"	.16"	1.73"	.20"
50	60	1.90"	.32"	1.86"	.30"	2.22"	.39"
60	60	2.46"	.63"	2.40"	.58"	2.90"	.76"
70	60	2.97"	.97"	2.87"	.89"	3.53"	1.22"
80	60						
90	60						
100	60						
110	60						
120	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 70 psf to prevent damage. **Failure occurred at approximately 124 psf.**

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen B

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
20	60	.58"	.01"	.60"	0.0	.75"	.01"
30	60	1.34"	.07"	1.45"	.08"	.169"	.08"
40	60	2.07"	.21"	2.29"	.21"	2.57"	.22"
50	60	2.97"	.44"	3.03"	.46"	3.58"	.49"
60	60	3.89"	.75"	4.36"	.80"	4.62"	.86"
70	60						
80	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
20	60	.61"	0.0	.56"	0.0	.75"	.01"
30	60	1.60"	.08"	1.30"	.06"	.169"	.08"
40	60	2.37"	.24"	2.06"	.18"	2.57"	.22"
50	60	3.36"	.48"	2.92"	.39"	3.58"	.49"
60	60	4.38"	.83"	3.83"	.69"	4.62"	.86"
70	60						
80	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 70 psf to prevent damage. **Failure** occurred at approximately 82 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Hat channel screws disengaged from rafter/post.

Specimen C

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	.70"	.04"	.82"	.05"	.96"	.06"
20	60	1.53"	.08"	1.72"	.10"	1.99"	.12"
30	60	2.41"	.22"	2.68"	.24"	3.15"	.32"
40	60	3.18"	.44"	3.57"	.49"	4.26"	.66"
50	60	3.97"	.75"	4.41"	.84"	5.30	1.16"
60	60						
70	60						
80	60						
90	60						
100	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	.93"	.05"	.71"	.03"	.96"	.06"
20	60	1.90"	.11"	1.49"	.07"	1.99"	.12"
30	60	2.94"	.28"	2.36"	.20"	3.15"	.32"
40	60	3.89"	.56"	3.10"	.44"	4.26"	.66"
50	60	4.79"	.96"	3.92	.78"	5.30	1.16"
60	60						
70	60						
80	60						
90	60						
100	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 50 psf to prevent damage. **Failure occurred at approximately 105 psf.**

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen D

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.54"	.02"	.69"	.02"	.78"	.02"
14	60	1.70"	.29"	2.18"	.36"	2.26"	.28"
21	60	2.20"	.47"	2.81"	.57"	2.90"	.45"
28	60	2.83"	.63"	3.61"	.78"	3.72"	.67"
35	60	3.32"	.88"	4.27"	1.13"	4.43"	.99"
42	60	4.11"	1.22"	5.14"	1.56"	5.28"	1.40"
49	60						
56	60						
63	60						
70	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.76"	.02"	.75"	.02"	.78"	.02"
14	60	2.08"	.22"	2.35"	.37"	2.26"	.28"
21	60	2.65"	.37"	3.01"	.58"	2.90"	.45"
28	60	3.37"	.56"	3.89"	.81"	3.72"	.67"
35	60	3.88"	.81"	4.62"	1.20"	4.43"	.99"
42	60	4.56"	1.10"	5.63"	1.71"	5.28"	1.40"
49	60						
56	60						
63	60						
70	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 42 psf to prevent damage. **Failure** occurred at approximately 73 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen E

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	1.13"	.10"	1.22"	.07"	1.38"	.07"
20	60	2.49"	.30"	2.72"	.30"	3.12"	.31"
30	60	3.56"	.51"	3.90"	.53"	4.56"	.60"
40	60	4.45"	.80"	4.71"	.87"	5.37"	.98"
50	60						
60	60						
70	60						
80	60						
90	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	1.40"	.08"	1.09"	.07"	1.38"	.07"
20	60	3.08"	.30"	2.42"	.25"	3.12"	.31"
30	60	4.46"	.59"	3.44"	.42"	4.56"	.60"
40	60	5.43"	.99"	4.33"	.71"	5.37"	.98"
50	60						
60	60						
70	60						
80	60						
90	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 40 psf to prevent damage. Failure occurred at approximately 95 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen FDeflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.23"	.0"	.27"	.01"	.36"	.02"
14	60	.49"	.0"	.56"	.02"	.71"	.02"
21	60	.74"	.03"	.84"	.04"	1.05"	.06"
28	60	1.06"	.09"	1.12"	.10"	1.39"	.13"
25	60	1.41"	.20"	1.52"	.21"	1.90"	.27"
42	60	1.77"	.37"	1.52"	.40"	2.40"	.50"
49	60	2.27"	.63"	2.40"	.70"	2.93"	.86"
56	60	2.81"	1.00"	2.99"	1.11"	3.66"	1.38"
63	60	3.43"	1.48"	3.79"	1.61"	4.70"	2.06"
70	60						
77							
84							

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.28"	.01"	.24"	.0"	.36"	.02"
14	60	.60"	.02"	.52"	.01"	.71"	.02"
21	60	.90"	.05"	.80"	.04"	1.05"	.06"
28	60	1.19"	.11"	1.09"	.09"	1.39"	.13"
25	60	1.59"	.23"	1.44"	.19"	1.90"	.27"
42	60	2.01"	.41"	1.81"	.35"	2.40"	.50"
49	60	2.49"	.70"	2.26"	.60"	2.93"	.86"
56	60	3.08"	1.12"	2.78"	.98"	3.66"	1.38"
63	60	3.87"	1.64"	3.39"	1.45"	4.70"	2.06"
70	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 63 psf to prevent damage. **Failure occurred at approximately 95 psf.**

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Note: 2 mil or 4 mil polyethylene film was used for the ASTM 1592 test, it is the opinion of the undersigned that it had no influence on the results of the test.

Technician: Keith Owen

Observers:-


Keith Owen, Ashley Poplin, / ATL
Sam Poplin, Keith Owen Jr., Ronald Anders / ATL,
David W. Johnson, P.E

Keith Owen, Lab Director
American Test Lab, Inc.

Keith Owen
4/5/17

All Tests Witnessed and Certified by:


David Johnson P. E.
1122 Calvert Rd.
Brevard, NC 28712
Florida P.E. # 61915



Certificate of Independence: The witnessing engineer has no equity interest in American Test Lab of North Carolina, Steel Building and Structures or their parts vendors. Witnessing engineer is in complete compliance of Florida Statue 9B-72, Section 72.110

Disclaimer:

ATL and its staff have no equity interest in any product tested or installed. This test report was prepared by American Test Lab, North (ATL) for the exclusive use of the above named client; it does not constitute certification of this product. The results are for that particular specimen tested and does not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. ATL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed. This report may not be reproduced except in full, and only under expressed permission from American Test Lab or Steel Building and Structures. Reproduced reports in hard copy must be labeled "Copy".



**TS2.5x2.5-14 GAGE
RAFTER/POST/PURLIN/GIRT MEMBERS**

NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17

Keith Owen
ATL INSPECTOR

PROPERTIES

AREA = 0.727 IN.²
Sx = 0.570 IN.³
Sy = 0.570 IN.³
Ix = 0.713 IN.⁴
Iy = 0.713 IN.⁴
rx = 0.990 IN.
ry = 0.990 IN.

APPLICATION:

ALL 30'-0", 40'-0", 50'-0" AND
60'-0" WIDE STRUCTURES


CALCULATED COIL WIDTH: 3.81" @ $\pm$ = 0.052"
CUSTOMER SPECIFIED WIDTH: 4.00" @ $\pm$ = 0.052"
METAL THICKNESS: 0.052"
MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+) OR (-) 1/16 IN
DEPTH --- (+) OR (-) 1/16 IN
RADIUS --- (+) OR (-) 1/32 IN
ANGLES --- (+) OR (-) 2 DEGREES
CAMBER --- (+) OR (-) 1/8 IN IN 10 FT
SKI --- (+) OR (-) 1/8 IN IN 10 FT
DIVE --- (+) OR (-) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS



STEEL BUILDINGS AND STRUCTURES, INC. TS2.5x2.5 RAFTER/POST/PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED		SCALE:	N/A	JOB NO.	16192S							
		AS NOTED										
REV. D	DATE:	3-14-17	DRAWN BY:	JRS	CHECKED BY:	PHH						
SK-1												
MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1005 East Avenue Keith Augusta, South Carolina 29841 (803) 278-7799 / FAX (803) 278-3040 www.mandac-inc.com		NO.	0	DATE	3/16/17	ISSUED FOR:	PRODUCT TESTING/APPROVAL	UN\$ PDH	BY	CK.	APVD.	WSH
REVISION												



HAT CHANNEL PROFILE PURLIN/GIRT MEMBERS

NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17

Keith Owen
ATL INSPECTOR



CALCULATED COIL WIDTH: 3.81' @ $t = 0.052'$
CUSTOMER SPECIFIED WIDTH: 4.00' @ $t = 0.052'$
METAL THICKNESS: 0.052"
MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL:
*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH ----- (+ OR -) 1/16 IN
RADII ----- (+ OR -) 1/32 IN
ANGLES ----- (+ OR -) 2 DEGREES
CAMBER ----- (+ OR -) 1/8 IN IN 10 FT
SKI ----- (+ OR -) 1/8 IN IN 10 FT
DIVE ----- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

STEEL BUILDINGS AND STRUCTURES, INC. HAT CHANNEL PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED		SCALE: AS NOTED		H&A JOB NO. 161925	CHECKED BY: JRS
		REV. 0	DATE: 3-14-17		
MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1009 East Avenue North Augusta, South Carolina 29841 (803) 270-7759 / FAX (803) 270-3848 www.Moore-inc.com		REVISION 3/16/17 ISSUED FOR PRODUCT TESTING/APPROVAL	BY: CK	APVD: VSH	



This document is the property of Moore and Associates Engineering and Consulting. It is to be used for the project and no other use of this document is authorized without the written consent of Moore and Associates Engineering and Consulting. It is to be kept in a secure location and not subject to legal action.

INBOARD SIDE 36.00' COVERAGE OUTBOARD SIDE

AG PANEL PROFILE ROOF - LOW WIND SPEED


NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17


Keith Owen
ATL INSPECTOR

GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- LOW ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 106 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 5.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY 1.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14" (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE ROOF PRESSURE: 16.0 PSF
NEGATIVE ROOF PRESSURE: -28.2 PSF



29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION	--- (+ OR -)	1/16 IN
DEPTH	----- (+ OR -)	1/32 IN
RADII	----- (+ OR -)	1/32 IN
ANGLES	----- (+ OR -)	2 DEGREES
CAMBER	----- (+ OR -)	1/8 IN IN 10 FT
SKI	----- (+ OR -)	1/8 IN IN 10 FT
DIVE	----- (+ OR -)	1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS		

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7789 / FAX (803) 279-3846
www.moore-inc.com

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/REVIEW			

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

This document is the property of Moore and Associates Engineering and Consulting, Inc. It is to be used for the project and location specified only. It is not to be reproduced, copied, or otherwise used for any other project without the written consent of Moore and Associates Engineering and Consulting, Inc.

STEEL BUILDINGS AND
STRUCTURES, INC.

ASC STANDARD G88 AG PANEL
ROOF
LOW WIND SPEED


SCALE: AS NOTED	N/A JOB NO. 16192S	CHECKED BY: PNH
--------------------	--------------------	-----------------

SHEET NO.
SK-3

REV. 0	DATE: 3-14-17
--------	------------------

INBOARD SIDE

OUTBOARD SIDE




AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17


Keith Owen
ATL INSPECTOR

AG PANEL PROFILE ROOF - HIGH WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

1. ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
2. DIMENSIONS ARE BASED ON 0.020" MATERIAL.
3. ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE ROOF PRESSURE: 21.2 PSF
SUCTION ROOF PRESSURE: -39.4 PSF

GENERAL NOTES

1. DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
2. DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
3. HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH) MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
4. WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
5. RISK CATEGORY 1.
6. WIND EXPOSURE CATEGORY B.
7. AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
8. FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14" (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.



29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1009 East Avenue North Augusta, South Carolina 29081 (803) 279-7700 / FAX (803) 279-3840 www.mohda-inc.com				NO.	DATE	REVISION	BY	CHK.	APVD.
				0	3/16/17	ISSUED FOR PRODUCT TESTING/ APPROVAL	JRS	PDH	MSH
STEEL BUILDINGS AND STRUCTURES, INC. ASC STANDARD GRB AG PANEL HIGH WIND SPEED				HSA JOB NO. 16192S		CHECKED BY: PDH			
SHEET NO. SK-4				REV. 0		DATE: 3-14-17			

INBOARD SIDE

OUTBOARD SIDE

36.00' COVERAGE

9.000

3.125

(TYP.)

2.750

(TYP.)

3.125

(TYP.)

18.000

0.020

AG PANEL PROFILE WALL - LOW WIND SPEED


NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17


Keith Owen
ATL INSPECTOR

GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- LOW ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 5.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY 1.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GIRTS (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3




OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE: 18.5 PSF
NEGATIVE WALL PRESSURE: -24.1 PSF



29 GAGE
CALCULATED COIL WIDTH: 43-13/16' ± t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 90 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADI: --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

1009 East Avenue
North Augusta, South Carolina 29841
(803) 278-7769 / FAX (803) 278-3846
www.Moore-Eng.com

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

This document is the property of Moore and Associates, Inc. Any unauthorized reproduction, copying, or other use without the written consent of Moore and Associates, Inc. is subject to legal action.

STEEL BUILDINGS AND
STRUCTURES, INC.

ASC STANDARD GRB AG PANEL
WALL
LOW WIND SPEED

SHEET NO.
SK-5

SCALE:	M/A	DATE:
AS NOTED	JOB NO. 16192S	3-14-17
DRAWN BY: JRS	CHECKED BY: PMH	
REV. 0		

DATE	REVISION	BY	CHK	APVD.
3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PMH	VSH
0				

INBOARD SIDE


OUTBOARD SIDE

36.00' COVERAGE


9.000

9.000


18.000

3.125 : 2.750 : 3.125
(TYP.) : (TYP.) : (TYP.)AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17*Keith Owen*
ATL INSPECTOR**AG PANEL PROFILE**
WALL - HIGH WIND SPEED
NOT TO SCALE


UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER-LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

1. ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
2. DIMENSIONS ARE BASED ON 0.020" MATERIAL.
3. ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE: 27.3 PSF
SUCTION WALL PRESSURE: -35.5 PSF

GENERAL NOTES

1. DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
2. DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
3. HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
4. WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
5. RISK CATEGORY I.
6. WIND EXPOSURE CATEGORY B.
7. AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GIRTS (INTERIOR OR END) = 6 INCHES.
8. FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER; SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14" (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1009 East Avenue North Augusta, South Carolina 29841 (803) 279-7789 / FAX (803) 279-3848 www.Moore-Inc.com	NO.	DATE	REVISION	BY	CHK	APVD.
	0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	ARS	PMH	VSH
STEEL BUILDINGS AND STRUCTURES, INC. ASC STANDARD GR8 AG PANEL WALL HIGH WIND SPEED	This document is the property of Moore and Associates Engineering and Consulting. It is to be used for the project and purpose stated only. Any unauthorized reproduction, copying, or alteration of this document is strictly prohibited and may be subject to legal action.					
	SCALE: AS NOTED	HA JOB NO. 16192S	CHECKED BY: PMH			
	DRAWN BY: JRS					
	REV. 0					
SHEET NO.	REV. 0	DATE:				
SK-6		3-14-17				



TS2.5x2.5-14 GAGE RAFTER/POST/PURLIN/GIRT MEMBERS

NOT TO SCALE

PROPERTIES

AREA = 0.727 IN.²
 $S_x = 0.570 \text{ IN.}^3$
 $S_y = 0.570 \text{ IN.}^3$
 $I_x = 0.713 \text{ IN.}^4$
 $I_y = 0.713 \text{ IN.}^4$
 $r_x = 0.990 \text{ IN.}$
 $r_y = 0.990 \text{ IN.}$

APPLICATION:

ALL 30'-0", 40'-0", 50'-0" AND
 60'-0" WIDE STRUCTURES

CALCULATED COIL WIDTH: 3.81" @ $t = 0.052"$
 CUSTOMER SPECIFIED WIDTH: 4.00" @ $t = 0.052"$
 METAL THICKNESS: 0.052"
 MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL


*ACCUMULATION --- (+ OR -) 1/16 IN
 DEPTH --- (+ OR -) 1/16 IN
 RADII --- (+ OR -) 1/32 IN
 ANGLES --- (+ OR -) 2 DEGREES
 CAMBER --- (+ OR -) 1/8 IN IN 10 FT
 SKI --- (+ OR -) 1/8 IN IN 10 FT
 DIVE --- (+ OR -) 1/8 IN IN 10 FT
 *NET VARIATION FOR COMBINED DIMENSIONS



MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC.				STEEL BUILDINGS AND STRUCTURES, INC.			
1009 East Avenue North Augusta, South Carolina 29841 (803) 279-7799 / FAX (803) 279-3848 www.MooreA-Inc.com				TS2.5x2.5 RAFTER/POST/PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED			
REV.	DATE	REVISION	BY	SCALE	AS NOTED	DRAWN BY	CHECKED BY
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	MAA JOB NO. 16192S			
1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JS				
				SHEET NO. SK-1			
				REV. 0 DATE: 3-14-17			
				APVD. WSH WSH			



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document is prohibited. Infringement may be subject to legal action.



HAT CHANNEL PROFILE PURLIN/GIRT MEMBERS

NOT TO SCALE




CALCULATED CUII WIDTH: 3.81" @ $t = 0.052"$
 CUSTOMER SPECIFIED WIDTH: 4.00" @ $t = 0.052"$
 METAL THICKNESS: 0.052"
 MATERIAL GRADE: 50 80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION - (+ OR -) 1/16 IN
 DEPTH - (+ OR -) 1/16 IN
 RADII - (+ OR -) 1/32 IN
 ANGLES - (+ OR -) 2 DEGREES
 CAMBER - (+ OR -) 1/8 IN IN 10 FT
 SKI - (+ OR -) 1/8 IN IN 10 FT
 DIVE - (+ OR -) 1/8 IN IN 10 FT
 *NET VARIATION FOR COMBINED DIMENSIONS

SHEET NO. SK-2		STEEL BUILDINGS AND STRUCTURES, INC. HAT CHANNEL PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED		 MOORE AND ASSOCIATES ENGINEERING AND CONSULTING		MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1009 East Avenue North Augusta, South Carolina 29841 (803) 279-7799 / FAX (803) 279-3848 www.MooreA-Inc.com						
REV. 0	SCALE: AS NOTED	M&A JOB NO. 16192S	This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document without the written consent of Moore and Associates, Inc. is strictly prohibited and may be subject to legal action.				NDL	DATE	REVISION	BY	CHK.	APVD.
DATE: 3-14-17	DRAWN BY: JRS	CHECKED BY: PDH					0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PDH	WSH
							1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JS	JB	WSH


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE ROOF - LOW WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- LOW ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/PURST AND END PURST SPACING = 5.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF #12-14x3/4\"/>

29 GAGE
CALCULATED CML WIDTH: 43 13/16\"/>

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADIUS --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

POSITIVE ROOF PRESSURE: **16.0 PSF**
NEGATIVE ROOF PRESSURE: **-39.9 PSF**



**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3848
www.monda-inc.com



This document is the property of Moore and Associates, Inc. The user is authorized to reproduce, copy, or otherwise use of this document for their own internal use only. Any other use without the written consent of Moore and Associates, Inc. is prohibited and may be subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
ROOF
LOW WIND SPEED

SHEET NO.
SK-3

REV. 0

SCALE:
AS NOTED

DRAWN BY: JRS

CHECKED BY: PDH

DATE:
3-14-17

BY: CK

APVD.

REVISION

3/16/17 ISSUED FOR PRODUCT TESTING/ APPROVAL JRS PDH

1/12/21 REVISED FOR 2020 FBC, 7TH EDITION JS JB

WSH


WSH

TOOLING STANDARD ASC SET WITH
44\"/>

NOTE:

- ALL INSIDE BEND RADII ARE 0.062\"/>


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE ROOF - HIGH WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

GENERAL NOTES

- DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 15 PSF
B) LIVE LOAD = 12 PSF
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING (ON-CENTERS ALONG RAFTERS OR PURLINS, INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET III TOP OF SHEET.

POSITIVE ROOF PRESSURE:
SUCTION ROOF PRESSURE:

16.0 PSF
-59.7 PSF

29 GAGE
CALCULATED CUII WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1008 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3648
www.MooreA-inc.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document without the written consent of Moore and Associates, Inc. is prohibited. Infringement thereupon may be subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
ROOF
HIGH WIND SPEED

SHEET NO.
SK-4

REV. 0
DATE: 3-14-17

DRAWN BY: JRS
CHECKED BY: PDH

SCALE: AS NOTED

M&A JOB NO. 1619ES


BY: CK, APVD: VSM

REVISION

ISSUED FOR PRODUCT TESTING/APPROVAL JRS PDH

REVISED FOR 2020 FBC, 7TH EDITION JS JB VSM


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE WALL - LOW WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

1. ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
2. DIMENSIONS ARE BASED ON 0.020" MATERIAL.
3. ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE: **17.8 PSF**
NEGATIVE WALL PRESSURE: **-23.4 PSF**

GENERAL NOTES

1. DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
2. DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 15 PSF
B) LIVE LOAD = 12 PSF
3. LOW ULTIMATE WIND SPEED 105 TO 140 MPH (MINIMAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/POST AND LND POST SPACING = 50 FEET.
4. WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
5. RISK CATEGORY I.
6. WIND EXPOSURE CATEGORY B.
7. AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GUTS (INTERIOR OR END) = 6 INCHES.
8. FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SPAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

29 GAGI.
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLLRANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS



**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3648
www.MooreA-inc.com



This document is the property of Moore and Associates, Inc. The user is authorized to reproduce, copy, or otherwise use of this document for their own internal use only. Any other use without the written consent of Moore and Associates, Inc. is subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
WALL
LOW WIND SPEED

SHEET NO.
SK-5

SCALE/
AS NOTED

DRAWN BY: JRS

CHECKED BY: PDH

REV. 0

DATE:
3-14-17

NO. DATE

REVISION

BY: CK

APVD:

3/16/17

ISSUED FOR PRODUCT TESTING/APPROVAL

JRS

PDH

VSM


VSM

REVISED FOR 2020 FBC, 7TH EDITION

1/12/21

1

INBOARD SIDE



OUTBOARD SIDE


AG PANEL PROFILE WALL - HIGH WIND SPEED

NOT TO SCALE




GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD - 15 PSF
B) LIVE LOAD - 12 PSF
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 105 TO 132 MPH); MAXIMUM RAFTER/POST AND LND POST SPACING - 4.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON CENTERS ALONG PUSTS AND GIRLS (INTERIOR JLR END) - 6 INCHES.
- FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MAIN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.0P6" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET IN TOP OF SHEET.

POSITIVE WALL PRESSURE:
SUCTION WALL PRESSURE:

26.6 PSF
-34.9 PSF

29 GAGE,
CALCULATED COIL WIDTH: 43 13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH ----- (+ OR -) 1/32 IN
RADII ----- (+ OR -) 1/32 IN
ANGLES ----- (+ OR -) 2 DEGREES
CAMBER ----- (+ OR -) 1/8 IN IN 10 FT
SKI ----- (+ OR -) 1/8 IN IN 10 FT
DIVE ----- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3948
www.MooreA-Inc.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document is strictly prohibited and any use without the written consent of Moore and Associates, Inc. may be subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
WALL
HIGH WIND SPEED

SHEET NO.
SK-6

SCALE: AS NOTED	M&A JOB NO. 16192S	REVISION	BY CK.	APVD.
DRAWN BY: JRS	CHECKED BY: PDH	DATE: 3-14-17	REV. 0	WSH
			JS JB	WSH



MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

401 S. Main Street
Suite 200
Mt. Airy, NC 27030
Phone: (336) 415-3540
Fax: (336) 719-2020

1009 East Avenue
North Augusta, SC 29841
Phone: (803) 279-7799
Fax: (803) 279-3848
www.MandaA-inc.com

15 April 2021

**State of Florida- Metal Building Component Product Approval
Engineering Evaluation Report
M&A Project No. 20300S**

Prepared By: Wayne S. Moore, P.E.
FL PE No. 57170

M&A COA No. 8966

Manufacturer: Steel Buildings and Structures, Inc.
820 Reeves Drive
Mount Airy, NC 27030

Product: **AG Metal Roof Panel**

Product Description: Low and high wind rated wall panels.

FL Product Code Approval No.: **FL22561**

Code Compliance Statement:

Moore and Associates Engineering and Consulting, Inc. (M&A) has reviewed the plans, calculations and testing information that applies to Florida Product Approval #FL22561 under the 2020 Florida Building Code, 7th Edition and finds them in compliance.

Certificate of Independence:

Wayne S. Moore, P.E. and M&A does not have, nor does it intend to acquire or will it acquire, a financial interest in the company manufacturing or distributing the product or products being tested. Wayne S. Moore, P.E. is not employed by nor is M&A owned, operated or controlled by the company manufacturing or distributing the product or products being tested. Wayne S. Moore, P.E. and other M&A staff who are licensed Professional Engineers registered in the State of Florida who perform technical evaluations do not have, nor will they acquire, a financial interest in the company manufacturing or distributing the product or products for which test reports are being issued. Wayne S. Moore, P.E. and other M&A staff who are licensed Professional Engineers registered in the State of Florida who perform technical evaluations do not have, nor will acquire, a financial interest in any other entity involved in the approval process of the product or products.



**National Society of
Professional Engineers®**

Supporting Documents:

Calculations: Structural calculations dated 11 January 2021 performed by John Smith, E.I.T. and checked by Wayne S. Moore, P.E.
Drawings: Drawings SK-1 through SK-6 signed/sealed by Wayne S. Moore, P.E.
Testing: ATLNC #0321.01-17 test report dated 04/05/2017 and signed/sealed by David Johnson, P.E.


Limitations and Conditions of Use:


1. Structural calculations were performed in accordance with the 2020 FBC, 7th Edition and compared to test results performed under previous FBC given that testing of panel was performed to maximum deflection and ultimate failure and that manufacturer utilizes same panel, supports and attachment fasteners.
2. Maximum allowable design pressure shall be as indicated on plans for each configuration.
3. This product is for use outside of the High Velocity Hurricane Zone (HVHZ).
4. This product shall be minimum 29 gauge thick galvalume coated steel with minimum yield stress of 80 ksi.
5. Panel material shall comply with 2020 FBC, 7th Edition Sections 1405.2, 1405.11 and 1405.17.
6. All supporting structural members shall be capable of supporting superimposed loads applied to this product.
7. Fasteners must consist of minimum 12-14 x $\frac{3}{4}$ " self-drilling fasteners (SDFs) with control seal washers.
8. Analysis/design was performed assuming a maximum mean roof height of 20'-0" and a roof slope of 3:12 (14 degrees) or less.
9. Product shall be installed into substrates shown on installation drawings and shall not exceed spacing limitations.
10. Site conditions that deviate from calculation, drawing and/or testing limitation noted shall require further analysis by a licensed Professional Engineer registered in the State of Florida.

Quality Assurance:

The manufacturer has demonstrated compliance of proper quality assurance/quality control (QA/QC) in accordance with the Florida Administrative Code Rule 61G20-3.005. Manufacturer's QA/QC plan and practices have been audited by an approved quality assurance entity (Subsection 3).

Signature/Seal:





MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

1009 East Ave
North Augusta, SC 29841
(803) 279-7799
Fax (803) 279-3848
www.MandaA-Inc.com

401 S. Main Street
Mount Airy, NC 27030
(336) 415-3540
Fax (336) 719-2020
www.MandaA-Inc.com

Structural Analysis/Design Calculations Project Data Sheet

Client:	SBSI
Client Project/ PO Number:	
Project Name:	SBSI - Keystone FPC (FL22561.1)
Project Location:	
Subject:	Design
Date:	1/12/2021
M&A Project Number:	203005

	Engineer	Checked By	Approved By
Name:	John Smith		
Date:	1/12/2021		

Project:	The purpose of the above calculations is to find design wind pressures for a 15'x10' section of AG Metal Roof for Risk Category I and Exposure B for 105-140mph (Low) and 141-170mph (High) winds.
References:	2018 International Building Code (IBC) 2020 Florida Building Code (FBC) ASCE 7-16 Mathcad 6.0



AG Metal Roof Calc Set

Design Loads:

$$space_1 := 5 \cdot ft \text{ o.c.}$$

$$space_2 := 4 \cdot ft \text{ o.c.}$$

Risk Cat. I
Exposure B

Low Wind Spacing

High Wind Spacing

$$width := 180 \cdot in$$

$$Ht_{roof} := \frac{width}{2} \cdot 0.25 = 1.875 \text{ ft}$$

$$Ht := 120 \text{ in}$$

$$mean_{rht} := 20 \text{ ft} = 20 \text{ ft}$$

$$FS := 1.5$$

Note: Test Protocol ASTM E330 requires a 50% safety factor over design load pressures.

Low Wind 140mph (Vasd=108mph) Components and Cladding Doors and Window Pressures:

$$\lambda := 0.89$$

$$mean_{rht} = 20 \text{ ft}$$

(Based on 2018 IBC (ASCE 7-16), Pg. 362)

Adjustment Factor

Roof (Wind Area = 50 square ft):

$$Ppd_{net30pos108} := 9.84 \text{ psf} \cdot \lambda = 8.758 \text{ psf}$$

Note: Used Zone 3r (most conservative)

$$Ppd_{net30pos108} := \max(16 \text{ psf}, Ppd_{net30pos108}) = 16 \text{ psf}$$

$$Ppd_{net30neg108} := -44.86 \text{ psf} \cdot \lambda = -39.925 \text{ psf}$$

Note: Minimum Design pressure in either direction is 16psf per ASCE 7-16 Section 30.2.2 (pg. 333)

Roof (Wind Area = 50 square ft):

Note: Using Zone 3e (2nd most conservative)

$$Ppd_{net30pos108} := 9.84 \text{ psf} \cdot \lambda = 8.758 \text{ psf}$$

$$Ppd_{net30pos108} := \max(16 \text{ psf}, Ppd_{net30pos108}) = 16 \text{ psf}$$

$$Ppd_{net30neg108} := -38.76 \text{ psf} \cdot \lambda = -34.496 \text{ psf}$$

Note: Highlighted values indicate input.



Client: SBSI Job No. 203005 Sheet No. 2
Job Name: Keystone FPC Update Rev. 0 Computed By: JS
MOORE AND ASSOCIATES Subject: Design (Exp. B) Date: 1/12/21 Checked By: [Signature]
ENGINEERING AND CONSULTING

High Wind 170mph (Vasd=132mph) Components and Cladding Doors and Window Pressures:

$\lambda := 0.89$ $mean_{r,ht} = 20 \text{ ft}$ (Based on 2018 IBC (ASCE 7-16), Pg. 362)
Adjustment Factor

Note: Values found from interpolation using
Vasd wind speeds since structure is Risk I.

Roof (Wind Area = 50 square ft):

$$P_{pd_{net30pos132}} := 14.66 \text{ psf} \cdot \lambda = 13.047 \text{ psf}$$

Note: Used Zone 3r (most conservative)

$$P_{pd_{net30pos108}} := \max(16 \text{ psf}, P_{pd_{net30pos132}}) = 16 \text{ psf}$$

Note: Minimum Design pressure in either direction is 16psf per ASCE 7-16 Section 30.2.2 (pg. 333)

$$P_{pd_{net30neg132}} := -67.08 \text{ psf} \cdot \lambda = -59.701 \text{ psf}$$

Roof (Wind Area = 50 square ft):

$$P_{pd_{net30pos132}} := 14.66 \text{ psf} \cdot \lambda = 13.047 \text{ psf}$$

Note: Used Zone 3e (2nd most conservative)

$$P_{pd_{net30pos108}} := \max(16 \text{ psf}, P_{pd_{net30pos132}}) = 16 \text{ psf}$$

$$P_{pd_{net30neg132}} := -57.98 \text{ psf} \cdot \lambda = -51.602 \text{ psf}$$

Note: Highlighted values indicate input.

CHAPTER 30

WIND LOADS: COMPONENTS AND CLADDING

30.1 SCOPE

30.1.1 Building Types. This chapter applies to the determination of wind pressures on components and cladding (C&C) on buildings.

1. Part 1 is applicable to an enclosed or partially enclosed

- Low-rise building (see definition in Section 26.2); or
- Building with $h \leq 60$ ft (18.3 m).

The building has a flat roof, gable roof, multispans gable roof, hip roof, monoslope roof, stepped roof, or sawtooth roof, and the wind pressures are calculated from a wind pressure equation.

2. Part 2 is a simplified approach and is applicable to an enclosed

- Low-rise building (see definition in Section 26.2); or
- Building with $h \leq 60$ ft (18.3 m).

The building has a flat roof, gable roof, or hip roof, and the wind pressures are determined directly from a table.

3. Part 3 is applicable to an enclosed or partially enclosed

- Building with $h > 60$ ft (18.3 m).

The building has a flat roof, pitched roof, gable roof, hip roof, mansard roof, arched roof, or domed roof, and the wind pressures are calculated from a wind pressure equation.

4. Part 4 is a simplified approach and is applicable to an enclosed

- Building with 60 ft $< h \leq 160$ ft (18.3 m $< h \leq 48.8$ m).

The building has a flat roof, gable roof, hip roof, monoslope roof, or mansard roof, and the wind pressures are determined directly from a table.

5. Part 5 is applicable to an open building of all heights that has a pitched free roof, monoslope free roof, or troughed free roof.

6. Part 6 is applicable to building appurtenances such as roof overhangs, parapets, and rooftop equipment.

7. Part 7 is applicable to non-building structures – circular bins, silos and tanks; and rooftop solar panels.

- Circular Bins, Silos and Tanks: $h \leq 120$ ft (38.6 m).
- Rooftop Solar Panels: Buildings of all heights with flat roofs or Gable or Hip Roofs with roof slopes less than or equal to 7 degrees

30.1.2 Conditions. A building that has design wind loads determined in accordance with this chapter shall comply with all of the following conditions:

1. The building is a regular-shaped building as defined in Section 26.2; and
2. The building does not have response characteristics that make it subject to across-wind loading, vortex shedding, or instability caused by galloping or flutter; nor does it have a site

location for which channeling effects or buffeting in the wake of upwind obstructions warrant special consideration.

30.1.3 Limitations. The provisions of this chapter take into consideration the load magnification effect caused by gusts in resonance with along-wind vibrations of flexible buildings. The loads on buildings that do not meet the requirements of Section 30.1.2 or that have unusual shapes or response characteristics shall be determined using recognized literature documenting such wind load effects or shall use the wind tunnel procedure specified in Chapter 31.

30.1.4 Shielding. There shall be no reductions in velocity pressure caused by apparent shielding afforded by buildings and other structures or terrain features.

30.1.5 Air-Permeable Cladding. Design wind loads determined from Chapter 30 shall be used for air-permeable claddings, including modular vegetative roof assemblies, unless approved test data or recognized literature demonstrates lower loads for the type of air-permeable cladding being considered.

30.2 GENERAL REQUIREMENTS

30.2.1 Wind Load Parameters Specified in Chapter 26. The following wind load parameters are specified in Chapter 26:

- Basic wind speed, V (Section 26.5).
- Wind directionality factor, K_d (Section 26.6).
- Exposure category (Section 26.7).
- Topographic factor, K_z (Section 26.8).
- Ground elevation factor, K_e (Section 26.9)
- Velocity pressure exposure coefficient, K_z or K_h (Section 26.10.1); Velocity pressure, q_z (Section 26.10.2)
- Gust-effect factor (Section 26.11).
- Enclosure classification (Section 26.12).
- Internal pressure coefficient, (GC_{pi}) (Section 26.13).

30.2.2 Minimum Design Wind Pressures. The design wind pressure for C&C of buildings shall not be less than a net pressure of 16 lb/ft² (0.77 kN/m²) acting in either direction normal to the surface.

30.2.3 Tributary Areas Greater than 700 ft² (65 m²). C&C elements with tributary areas greater than 700 ft² (65 m²) shall be permitted to be designed using the provisions for main wind force resisting systems (MWFERS).

30.2.4 External Pressure Coefficients. Combined gust-effect factor and external pressure coefficients for C&C, (GC_p) , are given in the figures associated with this chapter. The pressure coefficient values and gust-effect factor shall not be separated.

Net Design Wind Pressure, P_{net300} , in lb/ft^2 , for Exposure B at $h = 30 \text{ ft}$, $V_e = 95\text{--}130 \text{ mph}$

Zone	Effective Wind Area (ft ²)	Basic Wind Speed (mph)												
		95	100	105	110	115	120	125	130	135	140			
Walls														
4	10	16.2	-17.6	18.0	-19.5	19.8	-21.5	21.8	-23.6	23.8	-25.8	25.9	-28.1	30.4
4	20	15.5	-16.9	17.2	-18.7	18.9	-20.6	20.8	-22.6	22.7	-24.7	24.7	-26.9	29.0
4	50	14.5	-15.9	16.1	-17.6	17.8	-19.4	19.5	-21.3	21.3	-23.3	23.2	-25.4	27.2
4	100	13.8	-15.2	15.3	-16.8	16.9	-18.5	18.5	-20.4	20.2	-22.2	22.0	-24.2	25.9
5	10	16.2	-21.7	18.0	-24.1	19.8	-26.6	21.8	-29.1	23.8	-31.9	25.9	-34.7	30.4
5	20	15.5	-20.3	17.2	-22.5	18.9	-24.8	20.8	-27.2	22.7	-29.7	24.7	-32.4	29.0
5	50	14.5	-18.3	16.1	-20.3	17.8	-22.4	19.5	-24.6	21.3	-26.9	23.2	-29.3	27.2
5	100	13.8	-16.9	15.3	-18.7	16.9	-20.6	18.5	-22.6	20.2	-24.7	22.0	-26.9	25.9
1	10	6.6	-25.9	7.3	-28.7	8.1	-31.6	8.9	-34.7	9.7	-37.9	10.5	-41.3	38.4
1	20	6.2	-24.2	6.9	-26.8	7.6	-29.5	8.3	-32.4	9.1	-35.4	9.9	-38.5	36.1
1	50	5.6	-21.9	6.3	-24.3	6.9	-26.8	7.6	-29.4	8.3	-32.1	9.0	-34.9	34.0
1	100	5.2	-20.2	5.8	-22.4	6.4	-24.7	7.0	-27.1	7.7	-29.6	8.3	-32.2	32.1
1'	10	6.6	-14.9	7.3	-16.5	8.1	-18.2	8.9	-19.9	9.7	-21.8	10.5	-23.7	21.4
1'	20	6.2	-14.9	6.9	-16.5	7.6	-18.2	8.3	-19.9	9.1	-21.8	9.9	-23.7	20.1
1'	50	5.6	-14.9	6.3	-16.5	6.9	-18.2	7.6	-19.9	8.3	-21.8	9.0	-23.7	18.8
1'	100	5.2	-14.9	5.8	-16.5	6.4	-18.2	7.0	-19.9	7.7	-21.8	8.3	-23.7	17.5
2	10	6.6	-34.1	7.3	-37.8	8.1	-41.7	8.9	-45.7	9.7	-50.0	10.5	-54.4	51.4
2	20	6.2	-31.9	6.9	-35.4	7.6	-39.0	8.3	-42.8	9.1	-46.8	9.9	-50.9	48.1
2	50	5.6	-29.0	6.3	-32.2	6.9	-35.5	7.6	-38.9	8.3	-42.5	9.0	-46.3	44.8
2	100	5.2	-26.8	5.8	-29.7	6.4	-32.8	7.0	-36.0	7.7	-39.3	8.3	-42.8	41.5
3	10	6.6	-46.5	7.3	-51.5	8.1	-56.8	8.9	-62.3	9.7	-68.1	10.5	-74.2	70.9
3	20	6.2	-42.1	6.9	-46.7	7.6	-51.4	8.3	-56.5	9.1	-61.7	9.9	-67.2	64.0
3	50	5.6	-36.3	6.3	-40.2	6.9	-44.4	7.6	-48.7	8.3	-53.2	9.0	-57.9	54.6
3	100	5.2	-31.9	5.8	-35.4	6.4	-39.0	7.0	-42.8	7.7	-46.8	8.3	-50.9	48.1
1	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	44.8
1	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	41.5
1	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	38.4
1	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	17.5
2e	10	9.8	-30.0	10.9	-33.2	12.0	-36.6	13.2	-40.2	14.4	-44.0	15.7	-47.9	44.8
2e	20	8.9	-30.0	9.8	-33.2	10.8	-36.6	11.9	-40.2	13.0	-44.0	14.1	-47.9	41.5
2e	50	7.6	-18.2	8.4	-20.2	9.3	-22.3	10.2	-24.5	11.1	-26.7	12.1	-29.1	38.4
2e	100	6.6	-9.4	7.3	-10.4	8.1	-11.4	8.9	-12.5	9.7	-13.7	10.5	-14.9	17.5
2n	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	66.4
2n	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	57.1
2n	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	48.1
2n	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	45.1
2r	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	66.4
2r	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	57.1
2r	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	48.1
2r	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	45.1
3e	10	9.8	-43.8	10.9	-48.5	12.0	-53.4	13.2	-58.7	14.4	-64.1	15.7	-69.8	66.4
3e	20	8.9	-37.8	9.8	-41.9	10.8	-46.2	11.9	-50.7	13.0	-55.4	14.1	-60.4	57.1
3e	50	7.6	-30.0	8.4	-33.2	9.3	-36.6	10.2	-40.2	11.1	-44.0	12.1	-47.9	48.1
3e	100	6.6	-24.1	7.3	-26.7	8.1	-29.4	8.9	-32.3	9.7	-35.3	10.5	-38.4	45.1
3r	10	9.8	-52.0	10.9	-57.6	12.0	-63.5	13.2	-69.7	14.4	-76.2	15.7	-83.0	79.4
3r	20	8.9	-44.6	9.8	-49.4	10.8	-54.4	11.9	-59.7	13.0	-65.3	14.1	-71.1	66.4
3r	50	7.6	-34.7	8.4	-38.4	9.3	-42.4	10.2	-46.5	11.1	-50.8	12.1	-55.4	51.4
3r	100	6.6	-27.2	7.3	-30.2	8.1	-33.3	8.9	-36.5	9.7	-39.9	10.5	-43.5	44.8

Notes: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively. For effective wind areas between those given above, the load may be interpolated; otherwise, use the load associated with the lower effective area. Gray shading indicates that the final value, including all permitted reductions, used in the design shall not be less than that required by Section 30.2.2. Metric conversions: $1.0 \text{ ft} = 0.3048 \text{ m}$, $1.0 \text{ ft}^2 = 0.0929 \text{ m}^2$, $1.0 \text{ lb}/\text{ft}^2 = 0.0479 \text{ kN}/\text{m}^2$.

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 [$h \leq 60 \text{ ft}$ ($h \leq 18.3 \text{ m}$): Design Wind Pressures for Enclosed Buildings—Walls and Roofs]

continues

Net Design Wind Pressure, P_{net30} , in lb/ft², for Exposure B at $h = 30$ ft, $V = 140$ –200 mph

Zone		Effective Wind Area (ft²)	Basic Wind Speed (mph)												
			140	150	160	170	180	190	200						
Walls															
4	10	35.3	-38.2	40.5	-38.2	46.1	-50.0	52.0	-56.4	58.3	-63.2	64.9	-70.4	72.0	-78.1
4	20	33.7	-36.7	38.7	-36.7	44.0	-47.9	49.6	-54.1	55.7	-60.6	62.0	-67.5	68.7	-74.8
4	50	31.6	-34.6	36.2	-34.6	41.2	-45.1	46.6	-51.0	52.2	-57.1	58.1	-63.7	64.4	-70.5
4	100	30.0	-33.0	34.4	-33.0	39.2	-43.1	44.2	-48.6	49.6	-54.5	55.2	-60.7	61.2	-67.3
5	10	35.3	-47.2	40.5	-47.2	46.1	-61.7	52.0	-69.6	58.3	-78.0	64.9	-87.0	72.0	-96.3
5	20	33.7	-44.0	38.7	-44.0	44.0	-57.5	49.6	-64.9	55.7	-72.8	62.0	-81.1	68.7	-89.9
5	50	31.6	-39.8	36.2	-39.8	41.2	-52.0	46.6	-58.7	52.2	-65.8	58.1	-73.4	64.4	-81.3
5	100	30.0	-36.7	34.4	-36.7	39.2	-47.9	44.2	-54.1	49.6	-60.6	55.2	-67.5	61.2	-74.8
1	10	14.3	-56.2	16.5	-56.2	18.7	-73.4	21.1	-82.8	23.7	-92.9	26.4	-103.5	29.3	-114.6
1	20	13.4	-52.5	15.4	-52.5	17.6	-68.5	19.8	-77.4	22.2	-86.7	24.8	-96.6	27.4	-107.1
1	50	12.3	-47.6	14.1	-47.6	16.0	-62.1	18.1	-70.1	20.3	-78.6	22.6	-87.6	25.0	-97.1
1	100	11.4	-43.9	13.0	-43.9	14.8	-57.3	16.7	-64.7	18.8	-72.5	20.9	-80.8	23.2	-89.5
1'	10	14.3	-32.3	16.5	-32.3	18.7	-42.1	21.1	-47.6	23.7	-53.3	26.4	-59.4	29.3	-65.9
1'	20	13.4	-32.3	15.4	-32.3	17.6	-42.1	19.8	-47.6	22.2	-53.3	24.8	-59.4	27.4	-65.9
1'	50	12.3	-32.3	14.1	-32.3	16.0	-42.1	18.1	-47.6	20.3	-53.3	22.6	-59.4	25.0	-65.9
1'	100	11.4	-32.3	13.0	-32.3	14.8	-42.1	16.7	-47.6	18.8	-53.3	20.9	-59.4	23.2	-65.9
2	10	14.3	-74.1	16.5	-74.1	18.7	-96.8	21.1	-109.3	23.7	-122.5	26.4	-136.5	29.3	-151.2
2	20	13.4	-69.3	15.4	-69.3	17.6	-90.6	19.8	-102.2	22.2	-114.6	24.8	-127.7	27.4	-141.5
2	50	12.3	-63.0	14.1	-63.0	16.0	-82.3	18.1	-92.9	20.3	-104.2	22.6	-116.1	25.0	-128.7
2	100	11.4	-58.3	13.0	-58.3	14.8	-76.1	16.7	-85.9	18.8	-96.3	20.9	-107.3	23.2	-118.9
3	10	14.3	-101.0	16.5	-101.0	18.7	-131.9	21.1	-148.9	23.7	-166.9	26.4	-186.0	29.3	-206.1
3	20	13.4	-91.5	15.4	-91.5	17.6	-119.5	19.8	-134.9	22.2	-151.2	24.8	-168.5	27.4	-186.7
3	50	12.3	-78.9	14.1	-78.9	16.0	-103.0	18.1	-116.3	20.3	-130.4	22.6	-145.3	25.0	-161.0
3	100	11.4	-69.3	13.0	-69.3	14.8	-90.6	16.7	-102.2	18.8	-114.6	20.9	-127.7	23.2	-141.5
Flat/Hip/Gable Roof 0 to 7 Degrees															
1	10	21.4	-65.1	24.5	-65.1	27.9	-85.1	31.5	-96.0	35.3	-107.7	39.4	-120.0	43.6	-132.9
1	20	19.3	-65.1	22.1	-65.1	25.2	-85.1	28.4	-96.0	31.8	-107.7	35.5	-120.0	39.3	-132.9
1	50	16.5	-39.6	18.9	-39.6	21.5	-51.8	24.3	-58.4	27.2	-65.5	30.3	-73.0	33.6	-80.9
1	100	14.3	-20.3	16.5	-20.3	18.7	-26.5	21.1	-30.0	23.7	-33.6	26.4	-37.4	29.3	-41.5
2e	10	21.4	-65.1	24.5	-65.1	27.9	-85.1	31.5	-96.0	35.3	-107.7	39.4	-120.0	43.6	-132.9
2e	20	19.3	-65.1	22.1	-65.1	25.2	-85.1	28.4	-96.0	31.8	-107.7	35.5	-120.0	39.3	-132.9
2e	50	16.5	-39.6	18.9	-39.6	21.5	-51.8	24.3	-58.4	27.2	-65.5	30.3	-73.0	33.6	-80.9
2e	100	14.3	-20.3	16.5	-20.3	18.7	-26.5	21.1	-30.0	23.7	-33.6	26.4	-37.4	29.3	-41.5
2n	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
2n	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
2n	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
2n	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
2r	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
2r	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
2r	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
2r	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
3e	10	21.4	-95.0	24.5	-95.0	27.9	-124.1	31.5	-140.1	35.3	-157.1	39.4	-175.0	43.6	-193.9
3e	20	19.3	-82.1	22.1	-82.1	25.2	-107.3	28.4	-121.1	31.8	-135.8	35.5	-151.3	39.3	-167.7
3e	50	16.5	-65.1	18.9	-65.1	21.5	-85.1	24.3	-96.0	27.2	-107.7	30.3	-120.0	33.6	-132.9
3e	100	14.3	-52.3	16.5	-52.3	18.7	-68.3	21.1	-77.1	23.7	-86.4	26.4	-96.3	29.3	-106.7
3r	10	21.4	-112.9	24.5	-112.9	27.9	-147.5	31.5	-166.5	35.3	-186.7	39.4	-208.0	43.6	-230.5
3r	20	19.3	-96.8	22.1	-96.8	25.2	-126.4	28.4	-142.7	31.8	-159.9	35.5	-178.2	39.3	-197.5
3r	50	16.5	-75.4	18.9	-75.4	21.5	-98.4	24.3	-111.1	27.2	-124.6	30.3	-138.8	33.6	-153.8
3r	100	14.3	-59.2	16.5	-59.2	18.7	-77.3	21.1	-87.2	23.7	-97.8	26.4	-109.0	29.3	-120.7
Gable Roof > 7 to 20 Degrees															

Notes: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively. For effective wind areas between those given above, the load may be interpolated; otherwise, use the load associated with the lower effective area. Gray shading indicates that the final value, including all permitted reductions, used in the design shall not be less than that required by Section 30.2.2.

Metric conversions: 1.0 ft = 0.3048 m; 1.0 ft² = 0.0929 m²; 1.0 lb/ft² = 0.0479 kN/m².

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 ($h \leq 60$ ft ($h \leq 18.3$ m)): Design Wind Pressures for Enclosed Buildings—Walls and Roofs

continues

Net Design Wind Pressure for Roof Overhang, p_{neto} , in lb/ft², for Exposure B at $h = 30$ ft, $V = 95$ –200 mph

Zone	Effective Wind Area (ft ²)	Wind Speed (mph)															
		95	100	105	110	115	120	130	140	150	160	170	180	190	200	210	220
1	10	-31.6	-35.1	-38.7	-42.4	-46.4	-50.5	-59.3	-68.7	-78.9	-89.8	-101.3	-113.6	-126.6	-140.0	-153.8	-168.0
1	20	-29.1	-32.2	-35.5	-39.0	-42.6	-46.4	-54.5	-63.2	-72.5	-82.5	-93.2	-104.5	-116.4	-129.2	-142.9	-157.5
1	50	-25.7	-28.5	-31.4	-34.5	-37.7	-41.1	-48.2	-55.9	-64.1	-73.0	-82.4	-92.4	-102.9	-114.0	-125.6	-137.8
1	100	-23.2	-25.7	-28.3	-31.1	-34.0	-37.0	-43.4	-50.4	-57.8	-65.8	-74.2	-83.2	-92.7	-102.8	-113.4	-124.5
2e	10	-38.1	-42.3	-46.6	-51.1	-55.9	-60.9	-71.4	-82.8	-95.1	-108.2	-122.1	-136.9	-152.6	-169.0	-186.1	-203.8
2e	20	-31.6	-35.0	-38.6	-42.3	-46.3	-50.4	-59.1	-68.6	-78.7	-89.6	-101.1	-113.4	-126.3	-140.0	-154.4	-169.4
2e	50	-22.9	-25.4	-28.0	-30.7	-33.6	-36.6	-42.9	-49.8	-57.1	-65.0	-73.4	-82.3	-91.7	-101.6	-112.0	-122.9
2e	100	-22.0	-24.4	-26.9	-29.5	-32.3	-35.1	-41.2	-47.8	-54.9	-62.4	-70.5	-79.0	-88.1	-97.6	-107.5	-117.8
2r	10	-46.1	-51.1	-56.3	-61.8	-67.5	-73.5	-86.3	-100.1	-114.9	-130.7	-147.6	-165.5	-184.4	-204.3	-225.1	-246.8
2r	20	-39.7	-44.0	-48.5	-53.2	-58.1	-63.3	-74.3	-86.2	-98.9	-112.5	-127.0	-142.4	-158.7	-175.8	-193.7	-212.5
2r	50	-31.2	-34.6	-38.1	-41.8	-45.7	-49.8	-58.4	-67.7	-77.7	-88.5	-99.9	-112.0	-124.7	-138.2	-152.4	-167.4
2r	100	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-121.0	-132.6
3	10	-45.2	-50.1	-55.3	-60.6	-66.3	-72.2	-84.7	-98.2	-112.8	-128.3	-144.8	-162.4	-180.9	-200.5	-221.1	-242.7
3	20	-36.4	-40.3	-44.5	-48.8	-53.4	-58.1	-68.2	-79.1	-90.8	-103.3	-116.6	-130.7	-145.7	-161.4	-177.7	-194.7
3	50	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-121.0	-132.6
3	100	-24.8	-27.4	-30.3	-33.2	-36.3	-39.5	-46.4	-53.8	-61.7	-70.2	-79.3	-88.9	-99.1	-109.8	-121.0	-132.6

Note: Plus and minus signs signify pressures acting toward and away from the surfaces, respectively.
Metric conversions: 1.0 ft = 0.3048 m; 1.0 ft² = 0.0929 m²; 1.0 lb/ft² = 0.0479 kN/m².

Adjustment Factor for Building Height and Exposure, λ


Mean Roof Height (ft)	Exposure		
	B	C	D
15	0.82	1.21	1.47
20	0.89	1.29	1.55
30	1.00	1.40	1.66
35	1.05	1.45	1.70
40	1.09	1.49	1.74
45	1.12	1.53	1.78
50	1.16	1.56	1.81
55	1.19	1.59	1.84
60	1.22	1.62	1.87

Note: Metric conversions: 1.0 ft = 0.3048 m; 1.0 ft² = 0.0929 m²; 1.0 lb/ft² = 0.0479 kN/m².

FIGURE 30.4-1 (Continued). Components and Cladding, Part 2 [$h \leq 60$ ft ($h \leq 18.3$ m)]: Design Wind Pressures for Enclosed Buildings—Walls and Roofs

Table 30.5-1 Steps to Determine C&C Wind Loads for Enclosed or Partially Enclosed Building with $h > 60$ ft ($h > 18.3$ m)

- Step 1:** Determine risk category; see Table 1.5-1.
- Step 2:** Determine the basic wind speed, V , for applicable risk category; see Figs. 26.5-1 and 26.5-2.
- Step 3:** Determine wind load parameters:
 - Wind directionality factor, K_d ; see Section 26.6 and Table 26.6-1.
 - Exposure category B, C, or D; see Section 26.7.
 - Topographic factor, K_g ; see Section 26.8 and Fig. 26.8-1.
 - Ground elevation factor, K_z ; see Section 26.9 and Table 26.9-1
 - Enclosure classification; see Section 26.12.
- Step 4:** Determine pressure coefficient, (GC_{pi}); see Section 26.13 and Table 26.13-1.
- Step 5:** Determine velocity pressure, q , Eq. (26.10-1).
- Step 6:** Determine external pressure coefficient, (GC_{pe}):
 - Walls and flat roofs ($\theta < 10^\circ$), see Fig. 30.5-1
 - Gable and hip roofs, see Fig. 30.3-2 per Note 6 of Fig. 30.5-1
 - Arched roofs, see Fig. 27.3-3, Note 4
 - Domed roofs, see Fig. 30.3-7
- Step 7:** Calculate wind pressure, p , Eq. (30.5-1).



American Test Lab, Inc

1122 Calvert Road Brevard, NC 28712
828-884-3700

atl@comportum.net

atlnc.com

ATLNC # 0321.01-17

Report Date: 04/05/17

Test Dates: 03/21/17 – 03/23/17

Miami Dade Certification # 16-0526.01

FL Organizational # TST 1555

IAS Certification # TL-423

Test Requested By:

Steel Building And Structures Inc.
820 Reeves Drive
Mount Airy, NC 27030
Phone 877-272-8276, Fax 336-551-3449

Test Standard:

ASTM E 1592-05


Test Conditions: 65 - 75 degrees F

Description of products tested:

Specimens A, F 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawings SK-1, SK-3, SK-4, SK-5, SK-6. Panels attached to 2-1/2" x 2-1/2" x 14 ga. rafters/ post with 12-14" x 3/4" self drilling screws at 6" oc.

Specimen B, D 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawing SK-1, SK-3, SK-4, SK-5, SK-6 over 2-5/16" wide Hat Channel attached to 2-1/2" x 2-1/2" x 14 ga. rafter/post. Hat Channel was attached to each rafter with (2) 12-14 x 3/4" self drilling screws, panels to Hat Channels with 12-14 x 3/4" self drilling screws at 6" OC.

Specimen C, E 29 gauge Galvalume AG Metal Roof and Wall Panels as shown in Steel Building and Structures drawing SK-1, SK-3, SK-4, SK-5, SK-6 over 2-1/2" x 14 ga sq galvanized steel girth attached to 2-1/2" x 2-1/2" x 14 ga. rafter/post. Girth was attached to each rafter with 2" x 2" x 14 ga angle with (4) 12-14 x 3/4" self drilling screws, panels attached to girth with 12-14 x 3/4" self drilling screws at 6" OC.



Configuration:

Specimen A, (3) 4' purlin spans, 3 panels wide mounted horizontally.

Specimen B, (3) 4' purlin spans, 4' Hat Channel spans 3 panels wide mounted horizontally.

Specimen C, (3) 4' purlin spans, 4' girth spans with 2-1/2" tubes, 3 panels wide mounted horizontally.

Specimen D, 5' purlin spans, 4' Hat Channel spans 3 panels wide mounted horizontally.

Specimen E, (3) 5' purlin spans, 5' girth spans with 2-1/2" tubes, 3 panels wide mounted horizontally.

Specimen F, (3) 5' purlin spans, 3 panels wide mounted horizontally.

Rafter/Post/Girth Construction- 2-1/2" x 2-1/2" x 14 ga tube

Rafter Spacing- Specimen A B, C, 3 spans 48" OC with 12" overhang.
Specimen D, E, F, 3 spans 60" OC, with 12" overhang.

Hat Channel Spacing: Specimen B, 3 spans 48" OC with 12" overhang, rafter spacing 48" OC.
Specimen D, 3 spans 48" OC with 12" overhang, rafter spacing 60" OC.

2-1/2" Tube Girth Spacing: Specimen C, 3 spans 48" OC with 12" overhang, rafter spacing 48" OC.
Specimen D, 3 spans 60" OC with 12" overhang, rafter spacing 60" OC.

Rafter/Post Attachment- Each rafter/post was attached the chamber.

Test Specimens

Indicator Locations

Specimens A, F

	E		
	B	C	D
	A		

Specimens B, C,

	E		
	B	C	D
	A		

Specimens D, E

	E		
	B	C	D
	A		

Specimen A

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
20	60	.75"	.02"	.83"	.03"	.93"	.03"
30	60	1.04"	.05"	1.12"	.07"	1.26"	.08"
40	60	1.45"	.15"	1.52"	.17"	1.73"	.20"
50	60	1.84"	.30"	1.92"	.33"	2.22"	.39"
60	60	2.35"	.55"	2.47"	.64"	2.90"	.76"
70	60	2.86"	.84"	2.97"	.99"	3.53"	1.22"
80	60						
90	60						
100	60						
110	60						
120	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
20	60	.80"	.02"	.81"	.02"	.93"	.03"
30	60	1.09"	.06"	1.06"	.06"	1.26"	.08"
40	60	1.50"	.17"	1.47"	.16"	1.73"	.20"
50	60	1.90"	.32"	1.86"	.30"	2.22"	.39"
60	60	2.46"	.63"	2.40"	.58"	2.90"	.76"
70	60	2.97"	.97"	2.87"	.89"	3.53"	1.22"
80	60						
90	60						
100	60						
110	60						
120	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 70 psf to prevent damage. Failure occurred at approximately 124 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen B

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
20	60	.58"	.01"	.60"	0.0	.75"	.01"
30	60	1.34"	.07"	1.45"	.08"	.169"	.08"
40	60	2.07"	.21"	2.29"	.21"	2.57"	.22"
50	60	2.97"	.44"	3.03"	.46"	3.58"	.49"
60	60	3.89"	.75"	4.36"	.80"	4.62"	.86"
70	60						
80	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
20	60	.61"	0.0	.56"	0.0	.75"	.01"
30	60	1.60"	.08"	1.30"	.06"	.169"	.08"
40	60	2.37"	.24"	2.06"	.18"	2.57"	.22"
50	60	3.36"	.48"	2.92"	.39"	3.58"	.49"
60	60	4.38"	.83"	3.83"	.69"	4.62"	.86"
70	60						
80	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 70 psf to prevent damage. Failure occurred at approximately 82 psf.

Negative Side Graph



Observations- Deflections Increased as pressure increased. Hat channel screws disengaged from rafter/post.

Specimen C

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	.70"	.04"	.82"	.05"	.96"	.06"
20	60	1.53"	.08"	1.72"	.10"	1.99"	.12"
30	60	2.41"	.22"	2.68"	.24"	3.15"	.32"
40	60	3.18"	.44"	3.57"	.49"	4.26"	.66"
50	60	3.97"	.75"	4.41"	.84"	5.30"	1.16"
60	60						
70	60						
80	60						
90	60						
100	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	.93"	.05"	.71"	.03"	.96"	.06"
20	60	1.90"	.11"	1.49"	.07"	1.99"	.12"
30	60	2.94"	.28"	2.36"	.20"	3.15"	.32"
40	60	3.89"	.56"	3.10"	.44"	4.26"	.66"
50	60	4.79"	.96"	3.92"	.78"	5.30"	1.16"
60	60						
70	60						
80	60						
90	60						
100	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 50 psf to prevent damage. Failure occurred at approximately 105 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen D


Deflections in inches

Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.54"	.02"	.69"	.02"	.78"	.02"
14	60	1.70"	.29"	2.18"	.36"	2.26"	.28"
21	60	2.20"	.47"	2.81"	.57"	2.90"	.45"
28	60	2.83"	.63"	3.61"	.78"	3.72"	.67"
35	60	3.32"	.88"	4.27"	1.13"	4.43"	.99"
42	60	4.11"	1.22"	5.14"	1.56"	5.28"	1.40"
49	60						
56	60						
63	60						
70	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.76"	.02"	.75"	.02"	.78"	.02"
14	60	2.08"	.22"	2.35"	.37"	2.26"	.28"
21	60	2.65"	.37"	3.01"	.58"	2.90"	.45"
28	60	3.37"	.56"	3.89"	.81"	3.72"	.67"
35	60	3.88"	.81"	4.62"	1.20"	4.43"	.99"
42	60	4.56"	1.10"	5.63"	1.71"	5.28"	1.40"
49	60						
56	60						
63	60						
70	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 42 psf to prevent damage. Failure occurred at approximately 73 psf.

Negative Side Graph

Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen E

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	1.13"	.10"	1.22"	.07"	1.38"	.07"
20	60	2.49"	.30"	2.72"	.30"	3.12"	.31"
30	60	3.56"	.51"	3.90"	.53"	4.56"	.60"
40	60	4.45"	.80"	4.71"	.87"	5.37"	.98"
50	60						
60	60						
70	60						
80	60						
90	60						

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
10	60	1.40"	.08"	1.09"	.07"	1.38"	.07"
20	60	3.08"	.30"	2.42"	.25"	3.12"	.31"
30	60	4.46"	.59"	3.44"	.42"	4.56"	.60"
40	60	5.43"	.99"	4.33"	.71"	5.37"	.98"
50	60						
60	60						
70	60						
80	60						
90	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 40 psf to prevent damage. Failure occurred at approximately 95 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Specimen F

Deflections in inches


Pressure Increments psf Negative	Time (sec)	Purlin Rib (A)	Perm. Set	Mid-Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.23"	.0"	.27"	.01"	.36"	.02"
14	60	.49"	.0"	.56"	.02"	.71"	.02"
21	60	.74"	.03"	.84"	.04"	1.05"	.06"
28	60	1.06"	.09"	1.12"	.10"	1.39"	.13"
25	60	1.41"	.20"	1.52"	.21"	1.90"	.27"
42	60	1.77"	.37"	1.52"	.40"	2.40"	.50"
49	60	2.27"	.63"	2.40"	.70"	2.93"	.86"
56	60	2.81"	1.00"	2.99"	1.11"	3.66"	1.38"
63	60	3.43"	1.48"	3.79"	1.61"	4.70"	2.06"
70	60						
77							
84							

Deflections in inches

Pressure Increments psf Negative	Time (sec)	Mid Span Rib (D)	Perm Set	Purlin Rib (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
0	60	0"	0"	0"	0"	0"	0"
7	60	.28"	.01"	.24"	.0"	.36"	.02"
14	60	.60"	.02"	.52"	.01"	.71"	.02"
21	60	.90"	.05"	.80"	.04"	1.05"	.06"
28	60	1.19"	.11"	1.09"	.09"	1.39"	.13"
25	60	1.59"	.23"	1.44"	.19"	1.90"	.27"
42	60	2.01"	.41"	1.81"	.35"	2.40"	.50"
49	60	2.49"	.70"	2.26"	.60"	2.93"	.86"
56	60	3.08"	1.12"	2.78"	.98"	3.66"	1.38"
63	60	3.87"	1.64"	3.39"	1.45"	4.70"	2.06"
70	60						

Note: C indicator reading is used as Total Panel Deflection and Permanent Set. Indicators removed after 63 psf to prevent damage. Failure occurred at approximately 95 psf.

Negative Side Graph



Observations- Deflections increased as pressure increased. Screws pulled through panel.

Note: 2 mil or 4 mil polyethylene film was used for the ASTM 1592 test, it is the opinion of the undersigned that it had no influence on the results of the test.

Technician: Keith Owen

Observers-


Keith Owen, Ashley Poplin, / ATL
Sam Poplin, Keith Owen Jr., Ronald Anders / ATL
David W. Johnson, P.E

Keith Owen, Lab Director
American Test Lab, Inc.

Keith Owen
4/5/17

All Tests Witnessed and Certified by:


David Johnson P. E.
1122 Calvert Rd.
Brevard, NC 28712
Florida P.E. # 61915



Certificate of Independence: The witnessing engineer has no equity interest in American Test Lab of North Carolina, Steel Building and Structures or their parts vendors. Witnessing engineer is in complete compliance of Florida Statue 9B-72, Section 72.110

Disclaimer:

ATL and its staff have no equity interest in any product tested or installed. This test report was prepared by American Test Lab, North (ATL) for the exclusive use of the above named client; it does not constitute certification of this product. The results are for that particular specimen tested and does not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. ATL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed. This report may not be reproduced except in full, and only under expressed permission from American Test Lab or Steel Building and Structures. Reproduced reports in hard copy must be labeled "Copy".



AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17

Keith Owen
ATL INSPECTOR

TS2.5x2.5-14 GAGE
RAFTER/POST/PURLIN/GIRT MEMBERS

NOT TO SCALE

PROPERTIES

AREA = 0.727 IN.²
S_x = 0.570 IN.³
S_y = 0.570 IN.³
I_x = 0.713 IN.⁴
I_y = 0.713 IN.⁴
r_x = 0.990 IN.
r_y = 0.990 IN.

APPLICATION:


ALL 30'-0", 40'-0", 50'-0" AND
60'-0" WIDE STRUCTURES

CALCULATED COIL WIDTH: 3.81" @ t = 0.052"
CUSTOMER SPECIFIED WIDTH: 4.00" @ t = 0.052"
METAL THICKNESS: 0.052"
MATERIAL GRADE: 50-80 KSI



TOLERANCE STANDARDS FOR THICKEST METAL:
*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/16 IN
RADI --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

STEEL BUILDINGS AND STRUCTURES, INC. TS2.5x2.5 RAFTER/POST/PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED		SCALE: AS NOTED		MIA JOB NO. 16192S		CHECKED BY: JRS	
		REV. 0		DATE: 3-14-17		DRAWN BY: JRS	
MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1008 East Avenue North Augusta, South Carolina 29841 (803) 279-7799 / FAX (803) 279-3848 www.moore-inc.com		REVISION 0 3/16/17 ISSUED FOR PRODUCT TESTING/APPROVAL JRS/PDH		BY: DC		APVD: VSH	



HAT CHANNEL PROFILE PURLIN/GIRT MEMBERS

NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17

Keith Cowen
ATL INSPECTOR



CALCULATED COIL WIDTH: 3.81' @ t = 0.052"
CUSTOMER SPECIFIED WIDTH: 4.00' @ t = 0.052"
METAL THICKNESS: 0.052"
MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/16 IN
RADIUS --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

STEEL BUILDINGS AND STRUCTURES, INC. HAT CHANNEL PURLIN/GIRT MEMBERS HIGH WIND SPEED AND LOW WIND SPEED		MOORE AND ASSOCIATES, INC. 1009 East Avenue North Augusta, South Carolina 29841 (803) 279-7799 / FAX (803) 279-3848 www.moore-inc.com	
		NO. 0 DATE 3/16/17 ISSUED FOR PRODUCT TESTING/APPROVAL	BY CK. APVD. WSH
SHEET NO. SK-2	SCALE: AS NOTED	HMA JOB NO. 161925	CHECKED BY: JRS
REV. 0	DATE: 3-14-17	REVISION 	



This document is the property of Moore and Associates, Inc. Copying or reproduction of this document is strictly prohibited and any infringement thereupon may be subject to legal action.

INBOARD SIDE 36.00' COVERAGE OUTBOARD SIDE

9.000 9.000 18.000

3.125 2.750 3.125
(TYP.) (TYP.) (TYP.)

AG PANEL PROFILE ROOF - LOW WIND SPEED


NOT TO SCALE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17


Keith Owen
ATL INSPECTOR

GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 15 PSF
B) LIVE LOAD = 12 PSF
- LOW ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 50 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTR. SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14" (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET

POSITIVE ROOF PRESSURE: 16.0 PSF
NEGATIVE ROOF PRESSURE: -28.2 PSF



29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADI: --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

1009 East Avenue
North Augusta, South Carolina 29941
(803) 279-7799 / FAX (803) 279-3848
www.moore-inc.com

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PH	VSH

STEEL BUILDINGS AND
STRUCTURES, INC.

ASC STANDARD GRB AG PANEL
ROOF
LOW WIND SPEED


SCALE:	AS NOTED	REA	JOB NO.	161925	CHECKED BY:	PH

SHEET NO.
SK-3

REV. 0
DATE:
3-14-17

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING
This document is the property of
Moore and Associates, Inc. The
unauthorized reproduction, copying,
or alteration of this document
is strictly prohibited and any
infringement thereon may be
subject to legal action.


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE ROOF - HIGH WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17

Keith Clavin
ATL INSPECTOR

GENERAL NOTES

- DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADIi --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET

POSITIVE ROOF PRESSURE: 21.2 PSF
SUCTION ROOF PRESSURE: -39.4 PSF



MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

1099 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3848
www.moore-inc.com

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING

This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or alteration of this document in any form without the written consent of Moore and Associates, Inc. is strictly prohibited and may be subject to legal action.

STEEL BUILDINGS AND
STRUCTURES, INC.


ASC STANDARD GR8 AG PANEL
ROOF
HIGH WIND SPEED

SCALE: AS NOTED
HSA JOB NDL 16192S
DRAWN BY: JRS
CHECKED BY: PDH

SHEET NO.
SK-4

REV. 0
DATE: 3-14-17

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPVAL JRS PDH			VSH



MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC. 1009 East Avenue North Augusta, South Carolina 29041 (803) 279-7789 / FAX (803) 279-3848 www.Moore-Eng.com			
NO.	DATE	REVISION	BY
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS
			APVD.
			VSH

STEEL BUILDINGS AND STRUCTURES, INC. ASC STANDARD GRB AG PANEL WALL LOW WIND SPEED		NLA JOB NO. 16192S SCALE: AS NOTED DRAWN BY: JRS CHECKED BY: PDH
SHEET NO. SK-5		REV. 0 DATE: 3-14-17

INBOARD SIDE

9.000

36.00' COVERAGE

3.125
(TYP.)2.750
(TYP.)3.125
(TYP.)

18.000





OUTBOARD SIDE

AMERICAN TEST LAB NORTH
DATE 04/05/17
REPORT NO. ATLNC0321.01-17*Keith Owen*
ATL INSPECTOR**AG PANEL PROFILE
WALL - HIGH WIND SPEED**

NOT TO SCALE

GENERAL NOTES

- DESIGN WAS DONE IN ACCORDANCE WITH THE 2014 FLORIDA BUILDING CODE, 5TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY 1.
- WIND EXPOSURE CATEGORY B
- AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GIRTS (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF 1/4"-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

**UNDERLAP SIDE****TYPICAL MINOR X-8****TYPICAL RIB X-3****OVERLAP SIDE**

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE: 27.3 PSF
SUCTION WALL PRESSURE: -35.5 PSF



29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
NET VARIATION FOR COMBINED DIMENSIONS

**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 278-7789 / FAX (803) 278-3818
www.Moore-Eng.com

**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING**

This document is the property of Moore and Associates, Inc. The user is authorized to reproduce, copy, or use the information contained herein for their own use only. Infringement thereon may be subject to legal action.


**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
WALL
HIGH WIND SPEED

SHEET NO.
SK-6

SCALE: AS NOTED	MLA JOB NO. 161925	CHECKED BY: PJH
REV. 0	DRAWN BY: JRS	DATE: 3-14-17

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PJH	WSH



TS2.5x2.5-14 GAGE **RAFTER/POST/PURLIN/GIRT MEMBERS**

NOT TO SCALE

PROPERTIES

AREA = 0.727 IN²
 S_x = 0.570 IN³
 S_y = 0.570 IN³
 I_x = 0.713 IN⁴
 I_y = 0.713 IN⁴
 r_x = 0.990 IN.
 r_y = 0.990 IN.

APPLICATION:

ALL 30'-0", 40'-0", 50'-0" AND
 60'-0" WIDE STRUCTURES

CALCULATED COIL WIDTH: 3.81" @ t = 0.052"
 CUSTOMER SPECIFIED WIDTH: 4.00" @ t = 0.052"
 METAL THICKNESS: 0.052"
 MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
 DEPTH --- (+ OR -) 1/16 IN
 RADII --- (+ OR -) 1/32 IN
 ANGLES --- (+ OR -) 2 DEGREES
 CAMBER --- (+ OR -) 1/8 IN IN 10 FT
 SKI --- (+ OR -) 1/8 IN IN 10 FT
 DIVE --- (+ OR -) 1/8 IN IN 10 FT
 *NET VARIATION FOR COMBINED DIMENSIONS



STEEL BUILDINGS AND STRUCTURES, INC.

TS2.5x2.5
 RAFTER/POST/PURLIN/GIRT MEMBERS
 HIGH WIND SPEED AND LOW WIND
 SPEED

SCALE:
 AS NOTED

DRAWN BY: JRS

CHECKED BY: PDH

SHEET NO.
SK-1

REV. 0

DATE:
 9-14-17

MOORE AND ASSOCIATES ENGINEERING AND CONSULTING, INC.


1009 East Avenue
 North Augusta, South Carolina 29841
 (803) 279-7799 / FAX (803) 279-3948
 www.MoAndA-INC.com

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PDH	WSM
1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JS	JB	WSM



MOORE AND ASSOCIATES
 ENGINEERING AND CONSULTING

This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or distribution of this document is strictly prohibited and infringement thereupon may be subject to legal action.



HAT CHANNEL PROFILE PURLIN/GIRT MEMBERS

NOT TO SCALE



CALCULATED COIL WIDTH: 3.81" @ $t = 0.052"$
 CUSTOMER SPECIFIED WIDTH: 4.00" @ $t = 0.052"$
 METAL THICKNESS: 0.052"
 MATERIAL GRADE: 50-80 KSI

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
 DEPTH --- (+ OR -) 1/16 IN
 RADII --- (+ OR -) 1/32 IN
 ANGLES --- (+ OR -) 2 DEGREES
 CAMBER --- (+ OR -) 1/8 IN IN 10 FT
 SKI --- (+ OR -) 1/8 IN IN 10 FT
 DIVE --- (+ OR -) 1/8 IN IN 10 FT
 *NET VARIATION FOR COMBINED DIMENSIONS

**STEEL BUILDINGS AND
STRUCTURES, INC.**
 HAT CHANNEL
 PURLIN/GIRT MEMBERS
 HIGH WIND SPEED AND LOW WIND
 SPEED

SHEET NO.
SK-2

REV. 0
DATE:
3-14-17

SCALE:
AS NOTED

DRAWN BY: JRS

CHECKED BY: PDH

M&A JOB NO. 16192S


**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**
 1008 East Avenue
 North Augusta, South Carolina 29841
 (803) 279-7799 / FAX (803) 279-3848
www.MoAndA-Inc.com

NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PDH	WSH
1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JRS	JB	WSH



This document is the property of
 Moore and Associates, Inc. The
 unauthorized reproduction, copying,
 or distribution of this document
 is strictly prohibited. Infringement
 thereupon may be
 subject to legal action.


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE ROOF - LOW WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

1. ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
2. DIMENSIONS ARE BASED ON 0.020" MATERIAL.
3. ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE ROOF PRESSURE:
NEGATIVE ROOF PRESSURE:

16.0 PSF
-39.9 PSF

GENERAL NOTES

1. DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
2. DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
3. LOW ULTIMATE WIND SPEED 105 TO 140 MPH (MINIMAL WIND SPEED 83 TO 108 MPH). MAXIMUM RAFTER/POST AND LND PIST SPACING = 5.0 FEET.
4. WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
5. RISK CATEGORY I.
6. WIND EXPOSURE CATEGORY B.
7. AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
8. FASTENERS CONSIST OF #12 14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH). SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

2) GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:
*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIAL --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS



**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1008 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3948
www.manda-inc.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document without the written consent of Moore and Associates, Inc. may be subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**


ASC STANDARD GR8 AG PANEL
ROOF
LOW WIND SPEED

SHEET NO.
SK-3

SCALE: AS NOTED	M&A JOB NO. 16192S	DATE: 9-14-17
DRAWN BY: JRS	CHECKED BY: PDH	
REV. 0		

NO.	DATE	REVISION	BY CK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	WSM
1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JS	WSM


INBOARD SIDE



OUTBOARD SIDE


AG PANEL PROFILE ROOF - HIGH WIND SPEED

NOT TO SCALE




GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD - 1.5 PSF
B) LIVE LOAD - 12 PSF
- HIGH ULTIMATE WIND SPEED: 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/POST AND END POST SPACING - 4.0 FEET
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (2" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADIUS ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE ROOF PRESSURE:
SUCTION ROOF PRESSURE:

16.0 PSF
-59.7 PSF

29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADIUS --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIP --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

**MOORE AND ASSOCIATES,
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3848
www.MooreA-Inc.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or distribution of this document is strictly prohibited. This document is subject to legal action.


**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
ROOF
HIGH WIND SPEED

SHEET NO.
SK-4

SCALE: AS NOTED	M&A JOB NO. 16192S	CHECKED BY: PJH
REV. 0	DRAWN BY: JRS	DATE: 3-14-17
		APVD: BY CK.
		VSM
		JS JB
		REVISED FOR 2020 FBC, 7TH EDITION


INBOARD SIDE




OUTBOARD SIDE

AG PANEL PROFILE WALL - LOW WIND SPEED


NOT TO SCALE




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

1. ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
2. DIMENSIONS ARE BASED ON 0.020" MATERIAL.
3. ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE: **17.8 PSF**
NEGATIVE WALL PRESSURE: **-23.4 PSF**

GENERAL NOTES

1. DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
2. DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
3. L100 ULTIMATE WIND SPEED 105 TO 140 MPH (NOMINAL WIND SPEED 81 TO 108 MPH); MAXIMUM RAFTER/POST AND END POST SPACING = 50 FEET.
4. WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
5. RISK CATEGORY I.
6. WIND EXPOSURE CATEGORY B.
7. AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GIRTS (INTERIOR OR END) = 6 INCHES.
8. FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES UP TO 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.

29 GAGE
CALCULATED COIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL:

*ACCUMULATION: (+ OR -) 1/16 IN
DEPTH: (+ OR -) 1/32 IN
RADII: (+ OR -) 1/32 IN
ANGLES: (+ OR -) 2 DEGREES
CAMBER: (+ OR -) 1/8 IN IN 10 FT
SKI: (+ OR -) 1/8 IN IN 10 FT
DIVE: (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS



**MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.**

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3848
www.Moore-Eng.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or distribution of this document is strictly prohibited and may be subject to legal action.

**STEEL BUILDINGS AND
STRUCTURES, INC.**

ASC STANDARD GR8 AG PANEL
WALL
LOW WIND SPEED

SHEET NO.
SK-5

SCALE:
AS NOTED

DRAWN BY: JRS

DATE:
3-14-17

M&A JOB NO. 16198S

CHECKED BY: PDH

BY: CK, APVD.

REVISION

NO. DATE


0 3/16/17 ISSUED FOR PRODUCT TESTING/APPROVAL JRS/PDH

1 1/12/21 REVISED FOR 2020 FBC, 7TH EDITION JS JB

WSH

WSH

INBOARD SIDE



OUTBOARD SIDE


AG PANEL PROFILE WALL - HIGH WIND SPEED

NOT TO SCALE




GENERAL NOTES


- DESIGN WAS DONE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION.
- DESIGN LOADS ARE AS FOLLOWS:
A) DEAD LOAD = 1.5 PSF
B) LIVE LOAD = 12 PSF
- HIGH ULTIMATE WIND SPEED 141 TO 170 MPH (NOMINAL WIND SPEED 109 TO 132 MPH); MAXIMUM RAFTER/PDSI AND END POST SPACING = 4.0 FEET.
- WIND PRESSURES ARE BASED ON ALLOWABLE STRENGTH DESIGN (ASD).
- RISK CATEGORY I.
- WIND EXPOSURE CATEGORY B.
- AVERAGE FASTENER SPACING ON-CENTERS ALONG POSTS AND GIRTS (INTERIOR OR END) = 6 INCHES.
- FASTENERS CONSIST OF #12-14x3/4" SELF-DRILLING SCREWS WITH CONTROL SEAL WASHER. SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) SPACING REQUIREMENTS FOR OTHER ROOF HEIGHTS AND/OR SLOPES MAY VARY.




UNDERLAP SIDE



TYPICAL MINOR X-8



TYPICAL RIB X-3



OVERLAP SIDE

TOOLING: STANDARD ASC SET WITH
44" TOOL SPACE (22" CENTER LINE)
3" BORE AND 6.026" PITCH DIAMETER

NOTE:

- ALL INSIDE BEND RADII ARE 0.062" EXCEPT WHERE NOTED.
- DIMENSIONS ARE BASED ON 0.020" MATERIAL.
- ALL HEIGHT DIMENSIONS ARE TOP OF SHEET TO TOP OF SHEET.

POSITIVE WALL PRESSURE:
SUCTION WALL PRESSURE:

26.6 PSF
-34.9 PSF

PSY GAGE
CALCULATED CHIL WIDTH: 43-13/16" @ t = 0.020"
DESIGN THICKNESS: 0.0135"
GRADE OF MATERIAL: 80 KSI MIN

TOLERANCE STANDARDS FOR THICKEST METAL

*ACCUMULATION --- (+ OR -) 1/16 IN
DEPTH --- (+ OR -) 1/32 IN
RADII --- (+ OR -) 1/32 IN
ANGLES --- (+ OR -) 2 DEGREES
CAMBER --- (+ OR -) 1/8 IN IN 10 FT
SKI --- (+ OR -) 1/8 IN IN 10 FT
DIVE --- (+ OR -) 1/8 IN IN 10 FT
*NET VARIATION FOR COMBINED DIMENSIONS

MOORE AND ASSOCIATES
ENGINEERING AND CONSULTING, INC.

1009 East Avenue
North Augusta, South Carolina 29841
(803) 279-7799 / FAX (803) 279-3848
www.manda-inc.com



This document is the property of Moore and Associates, Inc. The unauthorized reproduction, copying, or otherwise use of this document without the written permission of Moore and Associates, Inc. is prohibited and may be subject to legal action.


STEEL BUILDINGS AND
STRUCTURES, INC.

ASC STANDARD GR8 AG PANEL
WALL
HIGH WIND SPEED


SHEET NO.
SK-6

REV.	SCALE	AS NOTED	DATE	DRAWN BY: JRS	CHECKED BY: PDH	DATE
0			3-14-17			


NO.	DATE	REVISION	BY	CHK.	APVD.
0	3/16/17	ISSUED FOR PRODUCT TESTING/APPROVAL	JRS	PDH	WSH
1	1/12/21	REVISED FOR 2020 FBC, 7TH EDITION	JRS	JB	WSH




Handwritten signature and date:
2/16/12




SIDE VIEW



INSIDE ELEVATION




CURTAIN PANEL
ASTM A653 GR 80 ZINC COATED STEEL
PRE-PAINTED WITH FULL COAT OF PRIMER AND
BAKED SILICONIZED POLYESTER FINISH COAT
26 GA CURTAIN DETAIL




BOTTOM BAR ASSEMBLY

REVISIONS			
REV	DESCRIPTION	DATE	APPROVAL
—	DRAWING RELEASE	11-14-02	DM
A	NOTE REVISIONS	4-16-04	DM
B	NOTE REVISIONS	6-17-09	CS



CONCRETE/FILLED BLOCK JACKS
USING 5/16" X 2-1/4" TAPCON XL

ALL COMPONENTS SHALL BE
ASTM A653 STEEL V/MIN
FY=33 KSI GALVANIZED
PER ASTM A653 G-90




STEEL JACKS

USING #12-14 X 1" TEKS PANCAKE HEAD

16 GA (.063) GUIDE MOUNTING DETAIL

OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
THRU 7'-4"	15-1/2"	17-1/2"
OVER 7'-4" THRU 8'-8"	16"	18"
OVER 8'-8" THRU 10'-0"	17"	18-1/4"

HEADROOM REQUIRED



WINDLOCK
GALV. STEEL,
ASTM A653
WITH MIN.
FY=33KSI

THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY JANUS CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OF ENGINEERING WITHOUT THE EXPRESS PERMISSION OF JANUS WHICH MAY RECALL DOCUMENTS AT ANY TIME.

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE:

DECIMAL	FRACTIONS	ANGLES	HOLE DIAMETERS
.XX ±.03	± 1/16	± 0° 30'	UNDER .251 +.004 -.003
.XXX ±.005			.251 to .500 +.006 -.003
			OVER .500 +.008 -.003

PART NUMBER:	
MATERIAL:	
APPLIED FINISH:	
UNIT OF MEASURE:	
APPROVALS	DATE
DRAWN: BECKY NELSON	11-14-02
CHECKED: DON MILLS	11-14-02
APPROVED: DON MILLS	11-14-02


JANUS INTERNATIONAL CORPORATION

134 JANUS INTERNATIONAL BLVD TEMPLE, GA 30179
770-562-2850/Fax 770-562-2264




© 2012 Janus International Corporation All Rights Reserved

CERTIFIED WIND LOAD RATED
26 GA SERIES 750 DOOR ASSEMBLY
MAX. SIZE 8'-8" X 12'-0"

SIZE	DRAWING NUMBER	REV
B	T1002	B
SCALE: NONE	SHEET: 1 OF 2	




REVISIONS			
REV	DESCRIPTION	DATE	APPROVAL
—	DRAWING RELEASE	11-14-02	DM
A	NOTE REVISIONS	4-16-04	DM
B	NOTE REVISIONS	6-17-09	CS



STEEL JACKS
LH GUIDE MOUNT SHOWN

CONCRETE/FILLED BLOCK JACKS
RH GUIDE MOUNT SHOWN


SUPERIMPOSED LOAD DIAGRAM



REAR VIEW

EXISTING CONCRETE

TWO 1/4" POWER WEDGE-BOLTS W/ 1-1/2" MIN. EMBEDMENT IN CONCRETE OR TWO 1/4" STEEL SCREWS W/FULL PENETRATION INTO MIN. 1/8" STEEL. IF EXISTING IS MASONRY, FILL CELL W/2500 PSI GROUT.



SIDE VIEW

ASTM A653 WITH $F_y = 37$ KSI GALV. STEEL IN ACCORDANCE WITH ASTM A653 G90

DOOR MOUNTING BRACKET DETAIL

GENERAL NOTES

- THIS ROLL-UP DOOR SYSTEM IS DESIGNED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE.
- THIS ROLL-UP DOOR HAS BEEN TESTED IN ACCORDANCE WITH ASTM E-330 AND COMPLIES WITH ANSI/DASMA 108.
- DESIGN LOAD $= +24.4$ PSF
 -27.0
- WIND LOADS FOR BUILDING OPENINGS SHALL BE DETERMINED BY A PROFESSIONAL ENGINEER USING APPROPRIATE WIND SPEED AND DESIGN CRITERIA. THIS DOOR MAY BE USED WHERE THE DESIGN LOAD MEETS OR EXCEEDS THE DESIGN LOAD FOR THE BUILDING OPENING.
- SUPERIMPOSED LOADS ON THE JACKS FROM THIS DOOR ARE DESIGNED AS V_x AND V_y HEREIN. CONTRACTORS SHALL HAVE BUILDING ENGINEER VERIFY ADEQUACY OF BUILDING STRUCTURE TO RESIST SUPERIMPOSED LOADS V_x , V_y AND BRACKET LOADS SHOWN.
- ALL WELDING SHALL BE PERFORMED BY QUALIFIED WELDERS IN ACCORDANCE WITH A.W.S. SPECIFICATIONS, LATEST EDITION. ALL WELDING ELECTRODES SHALL CONFORM TO A.W.S. A51 GRADE E-70.
- DOORS SHALL BE PROVIDED WITH LOCK MECHANISMS AT THE OPTION OF THE OWNER.
- ALL BOLTS AND WASHERS SHALL BE GALVANIZED OR STAINLESS STEEL WITH A MINIMUM TENSILE STRENGTH OF 60 KSI.

- DESIGN BASED ON CERTIFIED TESTING LABORATORIES, INC., TEST REPORT NO. CTLA - 983W-2
- ANCHOR NOTES:
A. EMBEDMENT LENGTH DOES NOT INCLUDE STUCCO FINISH.
B. FOR HOLLOW MASONRY, FILL ALL CELLS @ ANCHOR WITH 2500 PSI GROUT.
C. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- DOOR OPERATION TYPE TO BE PUSH-UP.

- GUIDE TO JAMB ATTACHMENT FASTENERS BEGIN 4" FROM FLOOR AND END 3-1/2" BELOW TOP OF WALL OPENING.
- TEST DOOR WALL OPENING SIZE: 8'-8" x 8'-0".

THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY JANUS CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OF ENGINEERING WITHOUT THE EXPRESS PERMISSION OF JANUS WHICH MAY RECALL DOCUMENTS AT ANY TIME.

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE:

DECIMAL	FRACTIONS	ANGLES	HOLE DIAMETERS
.XX $\pm .03$	$\pm 1/16$	$\pm 0^\circ 30'$	UNDER .251 $+0.04$ -0.03
.XXX $\pm .005$			.251 to .500 $+0.06$ -0.03 OVER .500 $+0.08$ -0.03

PART NUMBER:	
MATERIAL:	
APPLIED FINISH:	
UNIT OF MEASURE:	
APPROVALS:	DATE
DRAWN: BECKY NELSON	11-14-02
CHECKED: DON MILLS	11-14-02
APPROVED: DON MILLS	11-14-02

JANUS INTERNATIONAL CORPORATION	
134 JANUS INTERNATIONAL BLVD TEMPLE, GA 30179	
770-562-2850/Fax 770-562-2264	
© 2012 Janus International Corporation All Rights Reserved	
CERTIFIED WIND LOAD RATED	
26 GA SERIES 750 DOOR ASSEMBLY	
MAX. SIZE 8'-8" X 12'-0"	
SIZE: B	DRAWING NUMBER: T1002
SCALE: NONE	SHEET: 2 OF: 2

June 22, 2009
Rev. 02/15/12**EVALUATION REPORT No.:****ER-09-0007-R****Reference No.:** 29018_32003**Product:** Exterior Doors - Rolling Overhead Doors
Series 750, Series 3100, Series 850-S**Manufacturer:** Janus International Corporation
134 Janus International Blvd.
Temple, GA 30179-4435**Statement of Compliance:**


The Rolling Doors, Series 750 and Series 3100 described in this report were evaluated to be in compliance with the 2010 Florida Building Code. Series 850-S was evaluated to be in compliance with the 2010 Florida Building Code "High Velocity Hurricane Zones" Sections in Chapters 16 and 17, and may be considered impact resistant. The doors are, for the purpose intended, at least equivalent to that required by the Code when manufactured and installed as described below.

Description of the Product:

All doors consist of a corrugated steel sheet curtain suspended from a drum roller. The curtain on all models is suspended from a drum roller. Coiling around the drum raises the curtain. The sides of the curtain are constrained from lateral movement along their vertical edges by steel guides that are attached to the door jambs. This constraint provides resistance to lateral wind forces. Various guide configurations are used for the different door styles included in this report. The lateral wind forces are transferred from the curtain to the guides and then through the attachment elements to the door jamb. The door jambs are part of the main wind frame resisting system and usually are constructed of steel, concrete, or concrete masonry units.

Series 750 (Mini Door)

Door curtains have a thickness of 26 gage (min. 0.017 in.) and are made of ASTM A653 structural steel, grade 80, pre-painted, galvanized steel with a full coat of primer and baked siliconized polyester finish coat. The corrugated sheets are interlocked mechanically to form the curtain. Lap splices are at approximately 20 inches on center vertically in the installed door. The corrugation height is approximately 5/8 inches and the corrugation pitch is 3.25 in. Style variations include door width, windlocks, and wind load rating. Maximum door height is limited to 12'-0". Various door widths are described in detail on drawings T1000 (3'-0" wide), T1001 (6'-0" wide), T1002 (8'-8" wide) and T1003 (10'-0" wide). Tests were conducted on each of the four width doors shown on these drawings. A comparative analysis was used to determine the design pressures on doors between 3'-0" and 6'-0" wide. Doors greater than 6'-0" wide having opening widths between those shown on drawings T1001, T1002, and T1003 may be used for the same design wind pressure as



the next larger width door provided all other requirements on the larger width door drawing remain unchanged. Doors shown on drawings T1000 and T1001 do not have windlocks. Doors shown on drawings T1002 and T1003 have windlocks. The guide geometry and attachment method is fully described on the drawings.

Series 3100 (Commercial Door)

Door curtains have a thickness of 26 gage (min. 0.017 in.) and are made of ASTM A653 structural steel, grade 80, pre-painted, galvanized steel with a full coat of primer and baked silicized polyester finish coat. The corrugated sheets are interlocked mechanically to form the curtain. Lap splices are at approximately 20 inches on center vertically in the installed door. The corrugation height is approximately 5/8 inches and the corrugation pitch is 3.25 in. Style variations include door width, and wind load rating. Maximum door height is limited to 20'-0". Two door widths are described in detail on drawings T1004 (12'-0" wide), and T1005 (16'-0" wide). Two complete tests were conducted on each of these two width doors. One test used the Option 1 Guide and the other used the Option 2 Guide for attachment to the steel jamb. Doors having opening widths less than 12'-0" may be used for the same design wind pressure as the 12'-0" wide door provided all other requirements on that drawing remain unchanged. Doors having opening widths less than 16'-0" may be used for the same design wind pressure as the 16'-0" wide door provided all other requirements on that drawing remain unchanged. All doors shown on drawings T1004 and T1005 have windlocks.

Series 850-S (Florida State Mini Door) Impact Resistant

Door curtains may have a thickness of either 24 gage (min. 0.022 in.) or 26 gage (min. 0.017 in.). The curtain steel is ASTM A653 structural steel, grade 80, pre-painted, galvanized steel with a full coat of primer and baked silicized polyester finish coat. The corrugated sheets are interlocked mechanically to form the curtain. Lap splices are at approximately 20 inches on center vertically in the installed door. The corrugation height is approximately 5/8 inches and the corrugation pitch is 3.25 inches. Maximum door height is limited to 12'-0". Only the 8'-8" wide door is qualified as impact resistant and it is described in detail on drawing T1006-S. Doors having opening widths less than 8'-8" may be used for the same design wind pressure as the 8'-8" wide door provided all other requirements on that drawing remain unchanged. The door shown on drawing T1006-S has windlocks. Tests in accordance with Florida Building Code Test Protocols TAS 201, TAS 202, and TAS 203 were conducted on this door.

All Series

Maximum door widths and heights are shown in Table 1. The pressures shown in Table 1 are the maximum allowable design wind load values. These design pressures may be used for any door width doors of the same Series provided all other requirements of the wider door remain unchanged.

Drawings

The Door Series covered by this report are described in detail on the following Janus International Corporation drawings:

Drawing T1000: 3'-0" wide max. x 12'-0" high max., shts 1 and 2 of 2, revised 06/17/09 ©2012
Drawing T1001: 6'-0" wide max. x 12'-0" high max., shts 1 and 2 of 2, revised 06/17/09 ©2012
Drawing T1002: 8'-8" wide max. x 12'-0" high max., shts 1 and 2 of 2, revised 06/17/09 ©2012
Drawing T1003: 10'-0" wide max. x 12'-0" high max., shts 1 and 2 of 2, revised 06/17/09 ©2012
Drawing T1004: 12'-0" wide max. x 20'-0" high max., shts 1 and 2 of 2, revised 01/20/12 ©2012
Drawing T1005: 16'-0" wide max. x 20'-0" high max., shts 1 and 2 of 2, revised 01/20/12 ©2012
Drawing T1006-S: 8'-8" wide max. x 12'-0" high max., shts 1 and 2 of 2, revised 06/17/09 ©2012



Technical Documentation:

All testing was done at Certified Testing Laboratories, Orlando, Florida. Tests for Series 750 and Series 3100 were conducted following the procedures of ASTM E330, Structural Performance of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference. The following test reports, signed and sealed by R. Patel, P.E. cover the Series 750 and Series 3100 doors contained in this report:

- Test Report No.: CTLA-983W, date: November 7, 2002, (Series 750, T1000), 3'-0" wide x 8'-0" high, +35 / -45 psf design pressure
- Test Report No.: CTLA-983W-1, date: November 7, 2002, (Series 750, T1001), 6'-0" wide x 8'-0" high, +19.9 / -24.4 psf design pressure
- Test Report No.: CTLA-983W-2, date: December 2, 2002, (Series 750, T1002), 8'-8" wide x 8'-0" high, +24.4 / -27.0 psf design pressure
- Test Report No.: CTLA-983W-3, date: November 7, 2002, (Series 750, T1003), 10'-0" wide x 8'-0" high, +19.4 / -22.7 psf design pressure
- Test Report No.: CTLA-1024W, date: February 20, 2003, (Series 3100, T1004) 12'-0" wide x 8'-0" high, +36.0 / -41.0 psf design pressure
- Test Report No.: CTLA-1194W, date: December 2, 2003, (Series 3100, T1004) 12'-0" wide x 8'-0" high, +36.0 / -41.0 psf design pressure, (Option 1 guide for steel)
- Test Report No.: CTLA-1432W, date: November 3, 2005, (Series 3100, T1005) 16'-0" wide x 8'-0" high, +35.0 / -38.0 psf design pressure
- Test Report No.: CTLA-1432W-1, date: November 3, 2005, (Series 3100, T1005) 16'-0" wide x 8'-0" high, +35.0 / -38.0 psf design pressure, (Option 1 guide for steel)

Calculations prepared by Joseph H. Dixon, Jr. P.E.:

- Series 750, no windlocks, Summary of Design Wind Pressures based on comparative analysis for doors 3'-4" to 5'-6" wide, 1 page, revised 4/10/04.
- Series 3100, dwg. T1004, attachment of guide, Option 3, to 14 gage minimum steel jamb thickness, 6 pages dated 6/18/09, plus drawing JI-3100G1-2SP and drawing JI-3100G1-2SN, both dated 4/07/04.
- Series 750 and 3100 verification of compliance with ANSI/DASMA 108

Impact Resistant Doors

Tests for Series 850-S were conducted following the procedures of the Florida Building Code Test Protocols TAS 201, TAS 202, and TAS 203. The following test reports, signed and sealed by R. Patel, P.E. cover the Series 850-S doors contained in this report:

- Test Report No.: CTLA-1115W, date: August 20, 2003, (Series 850-S, T1006) 8'-8" wide x 8'-0" high, +46 / -54 psf design pressure



TABLE 1
Allowable Transverse Design Wind Loads (psf)

Series	Max. Door Width	Max. Door Height	Drawing Number	Design Load Positive	Design Load Negative
750	3'-0"	12'-0"	T1000	35.0	45.0
750	3'-4"	12'-0"	T1001	35.6	43.7
750	3'-6"	12'-0"	T1001	33.9	41.6
750	3'-8"	12'-0"	T1001	32.4	39.8
750	4'-0"	12'-0"	T1001	29.7	36.5
750	5'-0"	12'-0"	T1001	23.8	29.2
750	5'-6"	12'-0"	T1001	21.7	26.6
750	6'-0"	12'-0"	T1001	19.9	24.4
750	8'-8"	12'-0"	T1002	24.4	27.0
750	10'-0"	12'-0"	T1003	19.4	22.7
3100	12'-0"	20'-0"	T1004	36.0	41.0
3100	16'-0"	20'-0"	T1005	35.0	38.0
850-S	8'-8"	12'-0"	T1006-S	46.0	54.0

Design values used for the tests are shown in the boxed shaded values.
Maximum test load was 150% of design load.

Unshaded design wind loads were determined by comparative analyses using test results.

Installation Requirements:

Installation requirements are described in the Janus International Corporation Installation Instructions as follows:

- Series 750: 4 pages, Mini Door Installation Instructions Series 750
- Series 3100: 8 pages, Commercial Door Installation Instructions Series 3100
- Series 850: 4 pages, Mini Door Installation Instructions Series 850



Handwritten signature and date:
2/16/12

Limitations and Conditions of use:

The use of any door is limited to buildings for which the design wind loads for wall components and cladding, determined in accordance with Section 1609 of the 2010 Florida Building Code, do not exceed the rated design wind loads of the door as shown in Table 1.

Series 850-S is qualified as impact resistant. This door has been tested and met the additional requirements of Sections 1625 and 1626 of the 2010 Florida Building Code.

The maximum width and height limitations for each Series are shown in Table 1.

Doors are to be assembled as shown on the appropriate drawing referenced above, and the doors are to be installed in accordance with the installation instructions referenced above.

Door manufacturing is limited to those plants that have met the 2010 Florida Building Code Product Approval quality assurance requirements.

The doors covered by this report are not for use in the Florida High-Velocity Hurricane Zone.

Certification of Independence:

I, Joseph H. Dixon, Jr., certify that I am self-employed and operate as an independent contractor providing professional engineering services. I have no financial interest in nor will I acquire any financial interest in any company manufacturing or distributing products for which evaluation or validation reports have been issued by me.

Likewise, I have no financial interest in nor will I acquire any financial interest in any other entity involved in the approval process of those products for which I have issued reports.

Joseph H. Dixon, Jr. P.E.



9/15/12
2/16/12




JANUS INTERNATIONAL CORPORATION

134 EAST LUKE ROAD
TEMPLE, GA 30179-4435

13374 WEST PEORIA AVENUE
SURPRISE, AZ 85379-9724

PHONE 770-562-2850 FAX 770-562-2264

www.janusintl.com



DOOR INSTALLATION INSTRUCTIONS SERIES 750/1000/1100

CAUTION

Use proper lifting equipment and correct lifting procedures to avoid damage or injury.

WARNING!

A rolling door is a large heavy object that moves with the help of springs under extreme tension. Moving objects and springs under tension can cause serious injuries or death. For your safety and the safety of others, follow these instructions.

POTENTIAL HAZARD

EFFECT

PREVENTION



CAN CAUSE SERIOUS INJURY OR DEATH

DO NOT stand or walk under moving door. Keep door in full view and free of obstructions while operating.




CAN CAUSE SERIOUS INJURY OR DEATH


Installation, repairs and adjustments must be made by a trained rolling service door systems technician using proper tools and instructions. DOOR MUST BE FULLY OPENED WHEN MAKING ADJUSTMENTS.

TABLE 1: Wall Fasteners - for jamb attachment of Brackets and Guides

ITEM	JAMB	FASTENERS	DRILL SIZE
Brackets	Steel	1/4-14 x 1" TEKs Screw	None
	Concrete or Filled Block	1/4" x 1-3/4" Powers Wedge-Bolt	Powers 01314
Guides without windlocks	Steel	1/4-14 x 1" TEKs Screw	None
	Concrete or Filled Block	1/4" x 1-3/4" Powers Wedge-Bolt	Powers 01314
Guides with windlocks	Steel	#12-14 x 1" PSD Panclache Head TEKs Screw	None
	Concrete or Filled Block	5/16" x 2-1/4" Topcon XL (TORX T-40 drive)	1/4" Masonry



OPTIONAL BOTTOM BAR MOUNTED SLIDE LOCKS
FIGURE 1





IMPORTANT NOTE: Do not cut tape and plastic wrap that holds the door in a roll until you are directed to do so in step 6B. Janus International Corporation cannot guarantee or accept responsibility for doors that are not installed as directed. Please read and understand all instructions before beginning the installation process.

SERIES 750/1000/1100 CLEARANCE CHARTS FIGURE 2

SIDE ROOM REQUIRED*

WITHOUT WINDOW LOCKS		WITH WINDOW LOCKS	
CLIDE	OUTSIDE OF EACH BRACKET LEG	EACH END OF RAIL	
2-1/4"	3-3/8"	3-1/4"	
2-7/8"	4-1/8"	4"	

*Dimensions are taken from edge of opening



**SERIES 750
HEADROOM REQUIRED**

OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
OVER 7'-4"	15-1/2"	7"
OVER 7'-4" TO 8'-8"	16"	17-1/2"
OVER 8'-8" TO 10'-0"	17"	18-1/4"

**SERIES 1000/1100
HEADROOM REQUIRED**

OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
OVER 7'-4" TO 8'-0"	18"	17-1/2"
OVER 8'-0" TO 10'-0"	18-1/2"	17-3/4"
OVER 10'-0" TO 11'-4"	18-3/4"	18"
OVER 11'-4" TO 12'-0"	19"	18-1/2"




FIGURE 3

SERIES 750 GUIDE CROSS SECTION




FIGURE 6




FIGURE 4




FIGURE 5




FIGURE 7




FIGURE 8

JOSEPH M. DISNEY, JR.
REGISTERED PROFESSIONAL ENGINEER
No. 11467
State of Florida

STEP 1: WALL OPENING

SERIES 750/1000/1100

- A. Check wall opening width and height and verify these measurements against size of door to be installed.
- B. Verify that jambs are plumb.
- C. Check floor and header for level.
- D. Check for adequate side clearance at jambs and clearance above and at sides of header. Consult figure 2 for minimum requirements.
- E. Verify that the guide mounting surface on the jamb is flush.
- F. Make sure all parts required for installation are with the door.

STEP 2: POSITION DOOR AND PARTS

- A. Make sure floor is clean in order to prevent damage to curtain.
- B. On inside of building, place left guide on floor perpendicular to opening with guide bottom close to the left jamb and the top toward inside of building. Do the same with the right guide to the right jamb. See figure 3.
- C. Place door on floor at top of and between guides. Rotate door as necessary to locate bottom bar against floor. See figures 3 and 4.
- D. Distribute hardware parts to appropriate areas.

NOTE: Brackets, tensioner, spring(s) and curtain mounted tabs are pre-assembled to the door at the factory. Do not remove.

STEP 3: GUIDES TO BRACKETS INSTALLATION

- A. At tensioner end of door, lift flange on tensioner pawl until end of the pawl clears the tensioner ratchet wheel. Rotate bracket in order to position short leg end upward. Release flange on pawl and allow end to engage with the nearest tooth on the ratchet wheel. See figure 4.
- B. Bring top end of guide in alignment with bracket and insert hooks on bracket into slots in guide.
- C. Slide bracket and guide together until locking tab in guide fully engages notch in bracket.
- D. If locking tab does not fully engage with bracket notch, use a hammer and punch to bend tab into bracket notch.
- E. Repeat steps 3B through 3D for other bracket and guide. This bracket will require being held in position.

NOTE: For non-windlock doors with opening heights over 8'-6", clamp bottom of brackets to guides with locking plates in order to ensure rigidity of top of guide while lifting. Remove plates after securing brackets to jambs.

⚠ WARNING!


Locking tab in guide must fully engage with notch in bracket. Failure to do so may allow the door to fall during installation, which can cause serious injury or death and/or damage to door.

STEP 4: GUIDES AND BRACKETS TO JAMB

- A. Brackets and guides will be attached to jambs using fasteners shown in table 1.
- B. The guides should be mounted centered about the opening and spaced curtain width + 9/16" apart for non-windlock doors and curtain width + 2-1/2" for windlock doors. This spacing is measured from back of guide to back of guide. See figure 6. Both guides must be plumb.
- C. The appropriate fastener must be installed at each hole location in brackets and guides. See table 1.

⚠ WARNING!

Door can fall if both brackets are not securely fastened to the jamb. All fasteners attaching brackets to jambs must fit securely into a structural member or surface. If door falls, serious injury or death and/or damage to door can result.



SERIES 750/1000/1100

STEP 5: LIFTING DOOR ASSEMBLY

- A. Move door and guide assemblies toward wall opening with bottom of guides resting next to jambs.
- B. Lift door assembly evenly, pivoting around bottom of guides. See figure 5.
- C. Attach brackets and guides to jambs, according to step 4.

▲ WARNING!

Two installers are required to lift door assembly into position against jambs. The guides are not designed to support the curtain weight during a one man installation. Attempting to make installation with only one installer can result in serious injury and/or damage to door. Do not leave door unattended until it is securely attached to jambs.

NOTE: Welding of guides to the jambs is not recommended.

STEP 6: SETTING SPRING INITIAL TENSION

▲ WARNING!

Extreme spring tension can cause serious injury or death. Installation, repairs and adjustments must be made by a trained rolling service door systems technician using proper tools and instructions. Door must be fully opened when making adjustments.

- A. Rotate door 1-1/2 revolutions in the direction that would send the bottom bar down through the guides.
- B. While firmly holding the door at the bottom bar, cut the tape and plastic wrap that holds the door in a coil. Direct the bottom bar down into the guides, stopping just past the head stop area.

STEP 7: HEAD STOPS

- A. For doors without windlocks, slide head stop from inside of each guide. Secure with 1/4-20 x 3/4" thread cutting type F hex screw. See figure 7.
- B. For doors with windlocks, place head stop over outside of each guide. Secure with 1/4-20 x 1/2" carriage bolt and 1/4-20 serrated flange nut. Install carriage bolt from inside of guide. See figure 7.

STEP 8: MINI STOP CLIPS, HANDLE(S) AND PULL ROPE

- A. Install mini stop clip at each end on inside of bottom bar using existing single 1/4-20 x 1/2" carriage bolt.
 - B. Install handle(s) on outside of bottom bar using 1/4-20 x 1/2" carriage bolts.
 - C. Install rope in one of the holes at the center of the horizontal leg of the bottom bar angle.
- OPTIONAL: BOTTOM BAR MOUNTED SLIDE LOCKS - SEE FIGURE 1 FOR INSTALLATION.**

STEP 9: CHECK DOOR OPERATION

- A. Lower and raise the door to test the door balance.
- B. If door is easy to close, but hard to open, increase spring tension.
- C. If door is hard to close, but easy to open, decrease spring tension.

STEP 10: ADJUST SPRING TENSION


▲ WARNING!

DOOR MUST BE FULLY OPENED WHEN MAKING ADJUSTMENTS.

- A. Place 3/8" diameter winding bar in tensioner ratchet wheel. See figure 8.
- B. Rotate winding bar in the down direction to increase spring tension. Each engagement of a tooth equals 1/8 turn.
- C. To decrease spring tension, pull down slightly on winding bar until pawl disengages tooth. Lift flange on pawl and move winding bar up until past the pawl/tooth engagement. Allow pawl to rest on ratchet wheel and continue moving winding bar up until the pawl is fully engaged with the tooth.
- D. Remove winding bar and operate door.
- E. Repeat steps 10A through 10D as necessary.



NOTE: Latch stile slot in the guide may require oilcasing after door installation due to variances in manufacturing and/or the conditions.






2/16/12

REVISIONS			
REV	DESCRIPTION	DATE	APPROVAL
—	DRAWING RELEASE	11-14-02	DM
A	NOTE REVISIONS	4-16-04	DM
B	NOTE REVISIONS	6-17-09	CS




CURTAIN PANEL
ASTM A653 GR 80 ZINC COATED STEEL
PRE-PAINTED WITH FULL COAT OF PRIMER AND
BAKED SILICONIZED POLYESTER FINISH COAT
26 GA CURTAIN DETAIL




CONCRETE/FILLED BLOCK JAMBS
USING 5/16" X 2-1/4" TAPCON XL

ALL COMPONENTS SHALL BE
ASTM A653 STEEL W/MIN
FY=33 KSI GALVANIZED
PER ASTM A653 G-90




STEEL JAMBS
USING #12-14 X 1' TEKS PANCAKE HEAD
16 GA (.063) GUIDE MOUNTING DETAIL



BOTTOM BAR ASSEMBLY

OPENING HEIGHT	VERTICAL HEADROOM	HORIZONTAL HEADROOM
THRU 7'-4"	15-1/2"	17-1/2"
OVER 7'-4" THRU 8'-8"	16"	18"
OVER 8'-8" THRU 10'-0"	17"	18-1/4"

HEADROOM REQUIRED




WINDLOCK
GALV. STEEL,
ASTM A653
WITH MIN.
FY=33KSI

THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY JANUS CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OF ENGINEERING WITHOUT THE EXPRESS PERMISSION OF JANUS WHICH MAY RECALL DOCUMENTS AT ANY TIME.

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE:




DECIMAL	FRACTIONS	ANGLES	HOLE DIAMETERS
.XX ±.03	± 1/16	± 0° 30'	UNDER .251 +.004 -.003
.XXX ±.005			.251 to .500 +.006 -.003
			OVER .500 +.008 -.003

PART NUMBER		JANUS INTERNATIONAL CORPORATION 134 JANUS INTERNATIONAL BLVD TEMPLE, GA 30179 770-562-2850/Fax 770-562-2264 © 2012 Janus International Corporation All Rights Reserved	
MATERIAL			
APPLIED FINISH		CERTIFIED WIND LOAD RATED 26 GA SERIES 750 DOOR ASSEMBLY MAX. SIZE 10'-0" X 12'-0"	
UNIT OF MEASURE			
APPROVALS		DATE	
DRAWN: BECKY NELSON		11-14-02	
CHECKED: DON MILLS		11-14-02	
APPROVED: DON MILLS		11-14-02	
SIZE: B	DRAWING NUMBER: T1003	SCALE: NONE	SHEET: 1 OF 2



Handwritten signature and date:
2/16/12


REVISIONS			
REV	DESCRIPTION	DATE	APPROVAL
—	DRAWING RELEASE	11-14-02	DM
A	NOTE REVISIONS	4-16-04	DM
B	NOTE REVISIONS	6-17-09	CS




STEEL JAMBS
LH GUIDE MOUNT SHOWN

CONCRETE/FILLED BLOCK JAMBS
RH GUIDE MOUNT SHOWN

SUPERIMPOSED LOAD DIAGRAM



REAR VIEW



SIDE VIEW

DOOR MOUNTING BRACKET DETAIL

GENERAL NOTES

- THIS ROLL-UP DOOR SYSTEM IS DESIGNED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE.
- THIS ROLL-UP DOOR HAS BEEN TESTED IN ACCORDANCE WITH ASTM E-330 AND COMPLIES WITH ANSI/DASMA 108.

DESIGN LOAD = +19.4 PSF
-22.7

- WIND LOADS FOR BUILDING OPENINGS SHALL BE DETERMINED BY A PROFESSIONAL ENGINEER USING APPROPRIATE WIND SPEED AND DESIGN CRITERIA. THIS DOOR MAY BE USED WHERE THE DESIGN LOAD MEETS OR EXCEEDS THE DESIGN LOAD FOR THE BUILDING OPENING.
- SUPERIMPOSED LOADS ON THE JAMBS FROM THIS DOOR ARE DESIGNED AS Vx AND Vy HEREIN. CONTRACTORS SHALL HAVE BUILDING ENGINEER VERIFY ADEQUACY OF BUILDING STRUCTURE TO RESIST SUPERIMPOSED LOADS Vx, Vy AND BRACKET LOADS SHOWN.
- ALL WELDING SHALL BE PERFORMED BY QUALIFIED WELDERS IN ACCORDANCE WITH A.W.S. SPECIFICATIONS, LATEST EDITION. ALL WELDING ELECTRODES SHALL CONFORM TO A.W.S. A5.1 GRADE E-70.
- DOORS SHALL BE PROVIDED WITH LOCK MECHANISMS AT THE OPTION OF THE OWNER.
- ALL BOLTS AND WASHERS SHALL BE GALVANIZED OR STAINLESS STEEL WITH A MINIMUM TENSILE STRENGTH OF 60 KSI.

- DESIGN BASED ON CERTIFIED TESTING LABORATORIES, INC., TEST REPORT NO. CTLA - 983W-3
- ANCHOR NOTES:
A. EMBEDMENT LENGTH DOES NOT INCLUDE STUCCO FINISH.
B. FOR HOLLOW MASONRY, FILL ALL CELLS @ ANCHOR WITH 2500 PSI GROUT.
C. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- DOOR OPERATION TYPE TO BE PUSH-UP.

- GUIDE TO JAMB ATTACHMENT FASTENERS BEGIN 4" FROM FLOOR AND END 3-1/2" BELOW TOP OF WALL OPENING.
- TEST DOOR WALL OPENING SIZE: 10'-0" x 8'-0".

THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY JANUS CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OF ENGINEERING WITHOUT THE EXPRESS PERMISSION OF JANUS WHICH MAY RECALL DOCUMENTS AT ANY TIME.

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE:

DECIMAL	FRACTIONS	ANGLES	HOLE DIAMETERS
.XX ±.03	± 1/16	± 0° 30'	UNDER .251 +.004 -.003
.XXX ±.005			.251 to .500 +.006 -.003
			OVER .500 +.008 -.003

PART NUMBER	
MATERIAL	
APPLIED FINISH	
UNIT OF MEASURE	
APPROVALS	DATE
DRAWN: BECKY NELSON	11-14-02
CHECKED: DON MILLS	11-14-02
APPROVED: DON MILLS	11-14-02

JANUS INTERNATIONAL CORPORATION
134 JANUS INTERNATIONAL BLVD TEMPLE, GA 30179
770-562-2850/Fax 770-562-2264
© 2012 Janus International Corporation All Rights Reserved

CERTIFIED WIND LOAD RATED 26 GA SERIES 750 DOOR ASSEMBLY MAX. SIZE 10'-0" X 12'-0"	
SIZE: B	DRAWING NUMBER: T1003
SCALE: NONE	SHEET: 2 OF 2