





- RE-SHINGLE ENTIRE ROOF WITH ARCHITECTURAL ASPHALT SHINGLES
- CONSTRUCT LIBRARY ADDITION ON A MONOLITHIC SLAB ON REAR ELEVATION
- RELOCATE EXISTING REAR WINDOWS TO LEFT ELEVATION OF THE ADDITION



Architectural Asphalt Shingles

Roof Underlayment

7/16" OSB Decking

Pre-Engineered Trusses 24" O.C.

R-30 Insulation (or Fiberglass Batts)

1/2" Anti Sag or 5/8" Gypsum Wall Bd.

2X6 Surfsab

Aluminum Vented Soffit

2' - 0" Overhang

House Wrap

R-19 Fiberglass Insulation

1/2" Gypsum Bd. w/ Drywall Finish

Horizontal Fiber Cement Lap Siding

2X6 Studs SYP 16" O.C.

2X6 P.T. Bottom Plate

Finish Flooring

Anchor Bolt as per Wind Load Design

4" 3000 PSI Fiber-Lab Reinforced Conc. Slab (Optional 4" x 6" Mesh)

6 Mil Polyethylene Vapor Barrier

Clean Treated Compacted Sand Fill

20" Deep x 12" Wide Monolithic Footing 2 #8 Rebar Cont.

Plate Height 9' - 118"

B A101

[illegible]

SITE PLAN
FLOORPLAN
WALL SECTION
& FOUNDATION

A101	
Scale	As indicated