

### COLUMBIA COUNTY BUILDING DEPARTMENT RESIDENTIAL CHECK LIST

MINIMUM PLAN REQUIREMENTS: FLORIDA BUILDING CODE RESIDENTIAL 2017 EFFECTIVE 1 JANUARY 2018

AND THE NATIONAL ELECTRICAL 2014 EFFECTIVE 1 JANUARY 2018

### ALL REQUIREMENTS ARE SUBJECT TO CHANGE

ALL BUILDING PLANS MUST INDICATE COMPLIANCE WITH THE CURRENT FLORIDA BUILDING CODES RESIDENTIAL AND THE NATIONAL ELECTRICAL CODE. ALL PLANS OR DRAWINGS SHALL PROVIDE CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS, FBC 1609.3.1 THRU 1609.3.3.

FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEEDS ARE PER FLORIDA BUILDING CODE FIGURE 1609-A
THROUGH 1609-C ULTIMATE DESIGN WIND SPEEDS FOR RISK CATEGORY AND BUILDINGS AND OTHER STRUCTURES
Revised 7/1/18

Designers name and signature shall be on all documents and a licensed architect or engineer, signature and official embossed seal

Total (Sq. Ft.) under roof 3332

3328

Website: http://www.columbiacountyfla.com/BuildingandZoning.asp

**GENERAL REQUIREMENTS:** 

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

All drawings must be clear, concise, drawn to scale, details that are not used shall be marked void

shall be affixed to the plans and documents as per the FLORIDA BUILDING CODES RESIDENTIAL 107.1.

<del>22%</del>

2250

Two (2) complete sets of plans containing the following:

Condition space (Sq. Ft.)

Site Plan information including:

Items to Include-

Each Box shall be

Circled as

Applicable
Select From Drop down

No

NA

Yes

4	Dimensions of lot or parcel of land	-/		1		
5	Dimensions of all building set backs	_/				
6	Location of all other structures (include square footage of structures) on parcel, existing or proposed	./				
	well and septic tank and all utility easements.					
7	Provide a full legal description of property.	1/				
w	nd-load Engineering Summary, calculations and any details are required.					
	GENERAL REQUIREMENTS:	Item	s to Inclu	ide-		
	APPLICANT PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Each	Box sha	ll be		
		Circled as Applicable				
8	Plans or specifications must show compliance with FBCR Chapter 3	Yes	No	NA		
		Select Fro	m Drop	dow		
9	Basic wind speed (3-second gust), miles per hour	-/				
10	(Wind exposure – if more than one wind exposure					
	is used, the wind exposure and applicable wind direction shall be indicated)	1				
11	Wind importance factor and nature of occupancy	1/				
12	The applicable internal pressure coefficient, Components and Cladding	_/_/				
	The design wind pressure in terms of psf (kN/m²), to be used for the design of exterior component,					
13	cladding materials not specifally designed by the registered design professional.	-/				
El	evations Drawing including:	/				
14	All side views of the structure	-/				
15	Roof pitch	- / /				
16	Overhang dimensions and detail with attic ventilation	- /				
17	Location, size and height above roof of chimneys					
18	Location and size of skylights with Florida Product Approval	- 0				
19	Number of stories	- 4				
20	Building height from the established grade to the roofs highest peak	-				

Fl oor Pl an Including:

	110011100111000	
21	Dimensioned area plan showing rooms, attached garage, breeze ways, covered porches,	-/
	deck, balconies	
22	Raised floor surfaces located more than 30 inches above the floor or grade	- /
23	All exterior and interior shear walls indicated	-/
24	Shear wall opening shown (Windows, Doors and Garage doors)	-
25	Show compliance with Section FBCR 310 Emergency escape and rescue opening shown in each	
	bedroom (net clear opening shown) and Show compliance with Section FBC 1405.13.2 where the opening of an operable window is located more than 72 inches above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches above the finished floor of the room in which the window is located. Glazing between the floor and 24	-/
	inches shall be fixed or have openings through which a 4-inch-diameter sphere cannot pass.	
26	Safety glazing of glass where needed	- /
27	Fireplaces types (gas appliance) (vented or non-vented) or wood burning with Hearth (see chapter 10 and chapter 24 of FBCR)	-/
28	Show stairs with dimensions (width, tread and riser and total run) details of guardrails, Handrails	- /
29	Identify accessibility of bathroom (see FBCR SECTION 320)	1-/

All materials placed within opening or onto/into exterior walls, soffits or roofs shall have Florida product approval number and mfg. installation information submitted with the plans (see Florida product approval form)

**GENERAL REQUIREMENTS:** 

FBCR 606: Masonry Walls and Stem walls (load bearing & shear Walls)

38 Show all materials making up walls, wall height, and Block size, mortar type

39 Show all Lintel sizes, type, spans and tie-beam sizes and spacing of reinforcement

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

APPLICANT - PLEASE CHECK ALL ATT LICABLE BOXES BEFORE SUBMITTAL	Circled as Applicable
FBCR 403: Foundation Plans	Select From Drop down
Location of all load-bearing walls footings indicated as standard, monolithic, dimensions, size and type of reinforcing.	-/
1 All posts and/or column footing including size and reinforcing	/
2 Any special support required by soil analysis such as piling.	- /
3 Assumed load-bearing valve of soil Pound Per Square Foot	
Location of horizontal and vertical steel, for foundation or walls (include # size and type) For s with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an grounding electrode sys Per the National Electrical Code article 250.52.3	
FBCR 506: CONCRETE SLAB ON GRADE	
5 Show Varor retarder (6mil. Polyethylene with 'pints la ph 6 inches and sealed)	- (
6 Show control j oints, synthetic fiber reinforcement or welded fire fabric reinforcement and Spp	rts -
BCR 318: PROTECTION AGAINST TERMITES	
Indicate on the foundation plan if soil treatment is used for subterranean termite prevention or Submit other approved termite protection methods. Protection shall be provided by registered termiticides	- /

Metal frame shear wall and roof systems shall be designed, signed and sealed by Florida Prof. Engineer or Architect

Items to Include-

Each Box shall be

Fle	oor Framing System: First and/or second story	
	Floor truss package shall including layout and details, signed and sealed by Florida Registered	-
40	Professional Engineer	-
49	Show conventional floor joist type, size, span, spacing and attachment to load bearing walls,	-   /
41	stem walls and/or priers	
42	Girder type, size and spacing to load bearing walls, stem wall and/or priers  Attachment of joist to girder	
43	Wind load requirements where applicable	- u//
45	Show required under-floor crawl space	
46	Show required amount of ventilation opening for under-floor spaces	- / W/ //
47	Show required amount of ventilation opening for under-noor spaces  Show required covering of ventilation opening	
47	Show the required access opening to access to under-floor spaces	
40	Show the sub-floor structural panel sheathing type, thickness and fastener schedule on the edges &	
49	intermediate of the areas structural panel sheathing	- /
50	Show Draftstopping, Fire caulking and Fire blocking	-/
51	Show fireproofing requirements for garages attached to living spaces, per FBCR section 302.6	-/
52	Provide live and dead load rating of floor framing systems (psf).	1
J4	11011do 1110 dita dotta 1000 1001 1001 1001 1001 1001 1001 1	1 1 1 -
FB	CR CHAPTER 6 WOOD WALL FRAMING CONSTRUCTION	
		Items to Include-
	GENERAL REQUIREMENTS:	Each Box shall be
	APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL	Circled as
		Applicable
	S	elect from Drop dow
53	Stud type, grade, size, wall height and oc spacing for all load bearing or shear walls	- /
54	Fastener schedule for structural members per table FBC-R602.3.2 are to be shown	-/
	Show wood structural panel's sheathing attachment to studs, joist, trusses, rafters and structural	
55	members, showing fastener schedule attachment on the edges & intermediate of the areas structural	- /
	panel sheathing	
	Show all required connectors with a max uplift rating and required number of connectors and	
56	oc spacing for continuous connection of structural walls to foundation and roof trusses or	- /
	rafter systems	/
	Show sizes, type, span lengths and required number of support jack studs, king studs for	- /
57	shear wall opening and girder or header per FBC-R602.7.	
58	Indicate where pressure treated wood will be placed	-/
l	Show all wall structural panel sheathing, grade, thickness and show fastener schedule for structural	- /
59	panel sheathing edges & intermediate areas	-/-
60	A detail showing gable truss bracing, wall balloon framing details or/ and wall hinge bracing detail	- /
	OCD DOOR GUOTEMO.	
	BCR :ROOF SYSTEMS:	
61	Truss design drawing shall meet section FBC-R 802.10. I Wood trusses	
62	Include a layout and truss details, signed and sealed by Florida Professional Engineer	7/
63	Show types of connector's assemblies' and resistance uplift rating for all trusses and rafters	
64	Show gable ends with rake beams showing reinforcement or gable truss and wall bracing details	
65	Provide dead load rating of trusses	l <del>-</del> / l
F	BCR 802:Conventional Roof Framing Layout	
66	Rafter and ridge beams sizes, span, species and spacing	- /
67	Connectors to wall assemblies' include assemblies' resistance to uplift rating	_ (
68	Valley framing and support details	- //
69	Provide dead load rating of rafter system	- //
F	BCR 803 ROOF SHEATHING	
70	Include all materials which will make up the roof decking, identification of structural panel	[.()
	sheathing, grade, thickness	
71	Show fastener Size and schedule for structural panel sheathing on the edges & intermediate areas	-

R	OOF ASSEMBLIES FRC Chapter 9			
72	Include all materials which will make up the roof assembles covering	I-		
73	Submit Florida Product Approval numbers for each component of the roof assembles covering	-		

## FBCR Chapter 11 Energy Efficiency Code for Residential Building

Residential construction shall comply with this code by using the following compliance methods in the FBCR Chapter 11 Residential buildings compliance methods. Two of the required forms are to be submitted, N1100.1.1.1 As an alternative to the computerized Compliance Method A, the Alternate Residential Point System Method hand calculation, Alternate Form 600A, may be used. All requirements specific to this calculation are located in Sub appendix C to Appendix G. Buildings complying by this alternative shall meet all mandatory requirements of this chapter. Computerized versions of the Alternate Residential Point System Method shall not be acceptable for code compliance.

	GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL		Items to Include- Each Box shall be Circled as Applicable				
		elect from	Drop	Down			
74	Show the insulation R value for the following areas of the structure	- //					
75	Attic space	- //					
76	Exterior wall cavity	-					
77	Crawl space	-					
TU N	VAC information						
-		T_ /					
78	Submit two copies of a Manual J sizing equipment or equivalent computation study  Exhaust fans shown in bathrooms Mechanical exhaust capacity of 50 cfm intermittent or	-					
79		- /					
00	20 cfm continuous required						
80	Show clothes dryer route and total run of exhaust duct	- /					
Pi	umbing Fixture layout shown						
	All fixtures waste water lines shall be shown on the foundationplan	- /					
	Show the location of water heater	- //					
Pr	ivate Potable Water						
	Pump motor horse power	- (					
	Reservoir pressure tank gallon capacity	- //					
	Rating of cycle stop valve if used	- / /					
	ectrical layout shown including						
86		- /					
87	Show all 120-volt, single phase, 15- and 20-ampere branch circuits outlets required to be protected	1/					
-	by Ground-Fault Circuit Interrupter (GFCI) Article 210.8 A	J- //					
88	Show the location of smoke detectors & Carbon monoxide detectors	- /					
89	Show service panel, sub-panel, location(s) and total ampere ratings	-					
90	On the electrical plans identify the electrical service overcurrent protection device for the main electrical service. This device shall be installed on the exterior of structures to serve as a	- /					
	For structures with foundation which establish new electrical utility companies service connection a Concrete Encased Electrode will be required within the foundation to serve as an Grounding electrode system. Per the National Electrical Code article 250.52.3	/					
91	Appliances and HVAC equipment and disconnects						
92	Show all 120-volt, single phase, 15- and 20-ampere branch circuits supplying outlets installed in dwelling unit family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreation rooms, closets, hallways, or similar rooms or areas shall be protected by a listed Combination arc-fault circuit interrupter. Protection device.	- /					

### **Notice Of Commencement:**

A notice of commencement form RECORDED in the Columbia County Clerk Office is required to be filed with the Building Department BEFORE ANY INSPECTIONS can be performed.

# GENERAL REQUIREMENTS: APPLICANT – PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL Applicable Items to Include Each Box shall be Circled as Applicable

<ul> <li>Building Permit Application A current Building Permit Application is to be completed, by following the Checklist all supporting documents must be submitted.         There is a \$15.00 application fee. The completed application with attached documents and application fee can be mailed.     </li> <li>Parcel Number The parcel number (Tax ID number) from the Property Appraisers Office (386) 758-1083 is required. A copy of property deed is also required. www.columbiacountyfla.com</li> <li>Environmental Health Permit or Sewer Tap Approval A copy of a approved Columbia County Environmental Health (386) 758-1058</li> <li>City of Lake City A City Water and/or Sewer letter. Call 386-752-2031</li> <li>Toilet facilities shall be provided for all construction sites</li> <li>Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the</li> </ul>	- /	
(386) 758-1083 is required. A copy of property deed is also required. www.columbiacountyfla.com.  Environmental Health Permit or Sewer Tap Approval A copy of a approved Columbia County Environmental Health (386) 758-1058  City of Lake City A City Water and/or Sewer letter. Call 386-752-2031  Toilet facilities shall be provided for all construction sites  Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the	-/	
Columbia County Environmental Health (386) 758-1058  96 City of Lake City A City Water and/or Sewer letter. Call 386-752-2031  97 Toilet facilities shall be provided for all construction sites  98 Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the	- (	
97 Toilet facilities shall be provided for all construction sites  98 Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the		
97 Toilet facilities shall be provided for all construction sites  98 Town of Fort White (386) 497-2321 If the parcel in the application for building permit is within the Corporate city limits of Fort White, an approval land use development letter issued by the		/
within the Corporate city limits of Fort White, an approval land use development letter issued by the		
Town of Fort is required to be submitted with the application for a building permit.	-	/
Flood Information: All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting a application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.5.2 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.5.3 of the Columbia County Land Development Regulations (Municode.com)	- /	
100 CERTIFIED FINISHED FLOOR ELEVATIONS will be required on any project where the approved FIRM Flood Maps show the property is in a AE, Floodway, and AH flood zones. Additionally One Foot Rise letters are required for AE and AH zones. In the Floodway Flood zones a Zero Rise letter is required.	- /	
101 A Flood development permit is also required for AE, Floodway & AH. Development permit cost is \$50.00	-	 -
Driveway Connection: If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. County Public Works Dept. determines the size and length of every culvert before instillation and completes a final inspection before permanent power is granted. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00) Separate Check when issued. If the project is to be located on an F.D.O.T. maintained road, then an F.D.O.T. access permit is required.	_/	
911 Address: An application for a 911 address must be applied for and received through the Columbia County Emergency Management Office of 911 Addressing Department (386) 758-1125.	- /	

Ordinance Sec. 90-75. - Construction debris. (e) It shall be unlawful for any person to dispose of or discard solid waste, including construction or demolition debris at any place within the county other than on an authorized disposal site or at the county's solid waste facilities. The temporary storage, not to exceed seven days of solid waste (excluding construction and demolition debris) on the premises where generated or vegetative trash pending disposition as authorized by law or ordinance, shall not be deemed a violation of this section. The temporary storage of construction and demolition debris on the premises where generated or vegetative trash pending disposition as authorized by law or ordinance shall not be deemed in violation of this section; provided, however, such construction and demolition debris must be disposed of in accordance with this article prior to the county's issuance of a certificate of occupancy for the premises. The burning of lumber from a construction or demolition project or vegetative trash when done so with legal and proper permits from the authorized agencies and in accordance with such agencies' rules and regulations, shall not be deemed a violation of this section. No person shall bury, throw, place, or deposit, or cause to be buried, thrown, placed, or deposited, any solid waste, special waste, or debris of any kind into or on any of the public streets, road right-of-way, highways, bridges, alleys, lanes, thoroughfares, waters, canals, or vacant lots or lands within the county. No person shall bury any vegetative trash on any of the public streets, road right-of-way, highways, bridges, lanes, thoroughfares, waters, canals, or lots less than ten acres in size within the county.

As required by Florida Statute 553.842 and Florida Administrative Code 98-72, please provide the information and approval numbers on the building components listed below if they will be utilized on the construction project for which you are applying for a building permit. We recommend you contact your local product supplier should you not know the product approval number for any of the applicable listed products. Statewide approved products are listed online @ www.floridabuilding.org

Category/Subcategory	Manufacturer	Product Description	Approval Number(s)
1. EXTERIOR DOORS			
A. SWINGING	THERMO - TRU	EXTERIOR HINGED DOORS	FL 5891 - R3
B. SLIDING	PGT	SLIDING GLASS DOORS	FL 251 - R15
C. SECTIONAL/ROLL UP		GARAGE DOORS	FL 5678 - R2
D. OTHER			
2. WINDOWS			
A. SINGLE/DOUBLE HUNG	PGT	WINDOW	FL 239 - R19
B. HORIZONTAL SLIDER	PGT	WINDOW	FL 242 - R16
C. CASEMENT			
D. FIXED	PGT	WINDOW	FL 243 - R14
E. MULLION			
F. SKYLIGHTS			
G. OTHER			
3. PANEL WALL			
A. SIDING	HARDIE	PANEL WALL SIDING	FL 13192 - R5
B. SOFFITS	KAYCON	ALUMINUM SOFFIT / FACIA	FL 12198 - R1
C. STOREFRONTS	STO	STUCCO FINISH	FL 15026 - R1
D. GLASS BLOCK			
E. OTHER			
4. ROOFING PRODUCTS			
A. ASPHALT SHINGLES	GAF	ARCH SHINGLES 30YR	FL 10124 - R20
B. NON-STRUCTURAL METAL	GAF	TAR PAPER	FL 4911 - R3
C. ROOFING TILES	OMG	ROOFING NAILS	FL 699 - R3
D. SINGLE PLY ROOF			
E. OTHER			
5. STRUCTURAL COMPONENTS			
A. WOOD CONNECTORS	USPC	ANCHORS	FL 5631 - R1
B. WOOD ANCHORS	USPC	ANCHORS	FL 5631 - R1
C. TRUSS PLATES			
D. INSULATION FORMS			
E. LINTELS			
F. OTHERS			
6. NEW EXTERIOR			
ENVELOPE PRODUCTS			

The products listed below did not demonstrate product approval at plan review. I understand that at the time of inspection of these products, the following information must be available to the inspector on the jobsite; 1) copy of the product approval, 2) performance characteristics which the product was tested and certified to comply with (3) copy of the applicable manufacturers installation requirements.

Further, I understand these products may have to be removed if approval cannot be demonstrated during inspection.

	5/31/18	
Contractor OR Agent Signature	Date	NOTES:
		7

## RESIDENTIAL ENERGY CONSERVATION CODE DOCUMENTATION CHECKLIST

## Florida Department of Business and Professional Regulation Simulated Performance Alternative (Performance) Method

Applications for compliance with the 2017 Florida Building Code, Energy Conservation via the residential Simulated Performance Method shall include:

Ш	This checklist
	A Form R405 report that documents that the Proposed Design complies with Section R405.3 of the Florida Energy Code. This form shall include a summary page indicating home address, e-ratio and the pass or fail status along with summary areas and types of components, whether the home was simulated as a worst-case orientation, name and version of the compliance software tool, name of individual completing the compliance report (one page) and an input summary checklist that can be used for field verification (usually four pages/may be greater).
	Energy Performance Level (EPL) Display Card (one page)
	HVAC system sizing and selection based on ACCA Manual S or per exceptions provided in Section R403.7
	Mandatory Requirements (five pages)
Req	uired prior to CO for the Performance Method:
	Air Barrier and Insulation Inspection Component Criteria checklist (Table R402.4.1.1 - one page)
	A completed Envelope Leakage Test Report (usually one page)
	If Form R405 duct leakage type indicates anything other than "default leakage", then a completed Form R405 Duct Leakage Test Report (usually one page)

1314 COUNTE

# FLORIDA ENERGY EFFICIENCY CODE FOR BUILDING CONSTRUCTION

Florida Department of Business and Professional Regulation - Residential Performance Method

Project Name: 190950 Rivers Res Street: City, State, Zip: Lake City, FL, Owner: Design Location: FL, Gainesville	Builder Name: Bryan Zecher Construction Permit Office: Permit Number: Jurisdiction: County: Columbia (Florida Climate Zone 2)
1. New construction or existing 2. Single family or multiple family 3. Number of units, if multiple family 4. Number of Bedrooms 5. Is this a worst case? 6. Conditioned floor area above grade (ft²) 7. Windows(367.0 sqft.) Description a. U-Factor: Dbi, U=0.30 SHGC: SHGC=0.20 b. U-Factor: N/A SHGC: c. U-Factor: N/A SHGC: d. U-Factor: N/A SHGC: d. U-Factor: N/A SHGC: Area Weighted Average Overhang Depth: Area Weighted Average SHGC: a. Slab-On-Grade Edge Insulation BNA SHGC R= ft²	9. Wall Types (2110.5 sqft.) a. Frame - Wood, Exterior b. Frame - Wood, Adjacent c. N/A d. N/A 10. Ceiling Types (2396.0 sqft.) a. Under Attic (Vented) b. Knee Wall (Vented) c. N/A 11. Ducts a. Sup: Attic, Ret: Attic, AH: Main  12. Cooling systems a. Central Unit  13. Heating systems a. Electric Heat Pump  14. Hot water systems a. Electric b. Conservation features None 15. Credits  15. Credits  16. 231.00 ft² R=13.0 231.00 ft² R=16.2 R=16.2 R=16.2 R=38.0 2256.00 ft² R=38.0 140.00 ft² R=38.0 140.00 ft² R=16² R=1
Glass/Floor Area: 0.163 Total Proposed Modified Total Baseline	PASS
I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.  PREPARED BY: Evan Beamsley DATE: 2019-08-20  I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.  OWNER/AGENT:	Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

- Compliance requires certification by the air handler unit manufacturer that the air handler enclosure qualifies as certified factory-sealed in accordance with R403.3.2.1.
- Compliance requires an Air Barrier and Insulation Inspection Checklist in accordance with R402.4.1.1 and this project requires an envelope leakage test report with envelope leakage no greater than 7.00 ACH50 (R402.4.1.2).

DATE: .

DATE:

				PROJ	ECT									
Title: Building Type: Owner Name: # of Units: Builder Name: Permit Office: Jurisdiction: Family Type: New/Existing: Comment:	190950 Rivers Res User 1 Bryan Zecher Const Single-family New (From Plans)	truction	Bedrooms Conditione Total Stori Worst Cas Rotate And Cross Ven Whole Hot	ed Area: es: ee: gle: stilation:	3 2256 1 Yes 225			Lot # Block PlatB Stree Coun	d/Subdivi Book: Bot:	sion: C p: L	Street A Columb ake Ci			
			····	CLIM	ATE									
√ Des	sign Location	TMY Site			Design Ter 7.5 % 2	mp 2.5 %		sign Tem Summ		leating ree Day		esign [ isture	Daily To Rang	
FL,	, Gainesville FL	_GAINESVILLE	_REGI		32	92	70	75	1	305.5		51	Medi	un
				BLOC	KS									
Number	Name	Агеа	Volume											
1	Block1	2256	20755	.2										
				SPAC	ES							······		
Number	Name	Area	Volume	Kitchen	Occupar	nts	Bedroon	ns Ir	nfil ID	Finishe	d	Cooled	Н	ea
1	Main	2256	20755.2	Yes	8		3	1		Yes		Yes	Y	es
				FLOC	RS									
\/ #	Floor Type	Space	Peri	meter	R-Value		Area				Tile	Wood	Carp	et
1 Sla	ab-On-Grade Edge Insu		ain 237	'ft	0		2256 ft²				0.3	0.3	0.4	
				ROC	)F				· · · · · · · · · · · · · · · · · · ·			<u> </u>		
√ #	Туре	Materials	Roof Area	Gab Area		loof olor	Rad Barr	Solar Absor.	SA Tested	Emitt	En Test			Pit (de
1	Hip Cor	mposition shing	les 2613 ft²	0 ft²	· D	ark	N	0.92	No	0.9	N	lo	0	30
				ATT	IC									
√ #	Туре	Ventili	ation	Vent Rat	tio (1 in)		Area	RBS	IR	cc				
1	Full attic	Vent		30			256 ft²	N		N				
······································				CEILI	NG									
<b>√</b> #	Ceiling Type		Space	R-Valu	ie i	lns Typ	e A	Area	Fran	ning Fra	с Т	russ Ty	oe	
1	Under Attic (Vented)	)	Main	38		Blown	2	256 ft²		0		Wood		
2	Knee Wall (Vented)		Main	38	1	Blown	1	40 ft²		0.11		Wood		

INPUT SUMMARY CHECKLIST REPORT

FORIVIR	FORM R405-2017 INPUT SUMMARY CHECKLIST REPORT WALLS														
√ <b>#</b>	Omt	Adjace To		Туре	Space	Cavity R-Value	Wid Ft	ith in	HeEt	eight In	Area_	Sheathing R-Value	Framing Fraction	Solar Absor.	Below Grade%
1	N=>SW	Exterior		me - Wood	Main	13	13	8	9		123.0 ft²		0.23	0.75	0
2	E=>NW	Exterior	Fra	me - Wood	Main	13	10	1	9		90.8 ft²		0.23	0.75	0
3	NE=>W	Exterior	Fra	me - Wood	Main	13	3	10	9		34.5 ft²		0.23	0.75	0
4	N=>SW	Exterior	Frai	ne - Wood	Main	13	12	11	9		116.3 ft²		0.23	0.75	0
5	E=>NW	Exterior	Fra	ne - Wood	Main	13	9	4	9		84.0 ft <sup>2</sup>		0.23	0.75	0
6	N=>SW	Exterior	Frai	me - Wood	Main	13	13	8	9		123.0 ft²		0.23	0.75	0
— <sup>7</sup>	W=>SE	Exterior	Frai	ne - Wood	Main	13	2		9		18.0 ft²		0.23	0.75	0
8	N=>SW	Exterior	Frai	me - Wood	Main	13	13	8	9		123.0 ft²		0.23	0.75	0
<sup>9</sup>	E=>NW	Exterior	Frai	ne - Wood	Main	13	35	8	9		321.0 ft²		0.23	0.75	0
10	S=>NE	Exterior	Frai	ne - Wood	Main	13	16	6	9		148.5 ft²		0.23	0.75	0
11	W=>SE		Frai	ne - Wood	Main	13	4	8	9	0	42.0 ft <sup>2</sup>		0.23	0.75	0
12	S=>NE		Frai	ne - Wood	Main	13	18	2	9		163.5 ft²		0.23	0.75	0
13	S=>NE	_	Frai	ne - Wood	Main	13	6		9		54.0 ft²		0.23	0.75	0
14	E=>NW	•		ne - Wood	Main	13	3	8	9		33.0 ft²		0.23	0.75	0
15	S=>NE	-		ne - Wood	Main	13	16	0	9		144.0 ft²		0.23	0.75	0
16	W=>SE	Exterior	Frai	ne - Wood	Main	13	54	8	9		492.0 ft²		0.23	0.75	0
	DOORS														
$\vee$	#	Omt	•	Door Type	Space			Storms	3	U-Valu	Je Fi	Width In	Height Ft	ln	Area
	1	NE=>\	V	Insulated	Main			None		.4	1		8		8 ft²
	2	E≂>N\	٧	Insulated	Main			None		.4	2		8		16 ft²
	3	N=>SV	٧	Insulated	Main			None		.4	3		8	:	24 ft²
]	4	S=>NE	Ξ	Insulated	Main			None		.4	2		8		16 ft²
	5	S=>N	=	Insulated	Main			None		.4	3		6	8 :	20 ft²
							ows				- 10			<u>-</u>	
/		Wall	·····	Onentation	shown is the	entered one	entation	(=>) C	ange	ed to VV		thang			
$\checkmark$	# Or		Frame	Panes	NFRC	U-Factor	SHGC	lm	р	Area		Separation	Int Sha	de S	Screening
	1 N=>	SW 1	Metal	Low-E Double	Yes	0.3	0.2	N	3	86.0 ft²	1 ft 6 in	1 ft 0 in	None		None
	2 NE=	>W 3	Metal	Low-E Double	Yes	0.3	0.2	N	1	6.0 ft²	16 ft 4 in	0 ft 6 in	None	)	None
	3 N=>	SW 4	Metal	Low-E Double	Yes	0.3	0.2	N	3	6.0 ft²	14 ft 6 in	0 ft 6 in	None	<b>)</b>	None
	4 E=>	NW 5	Metal	Low-E Double	Yes	0.3	0.2	N	4	8.0 ft²	15 ft 10 in	0 ft 6 in	None	•	None
	5 N=>	SW 6	Metal	Low-E Double	Yes	0.3	0.2	N	7	'2.0 ft²	15 ft 2 in	0 ft 6 in	None	•	None
	6 N=>	SW 8	Metal	Low-E Double	Yes	0.3	0.2	N	3	86.0 ft²	1 ft 6 in	1 ft 0 in	None	:	None
	7 E=>	NW 9	Metal	Low-E Double	Yes	0.3	0.2	N	1	5.0 ft <sup>2</sup>	1 ft 6 in	1 ft 0 in	None	•	None
	8 E=>	NW 9	Metal	Low-E Double	Yes	0.3	0.2	N	(	6.0 ft²	1 ft 6 in	1 ft 0 in	None	•	None
	9 S=>	NE 10	Metal	Low-E Double	Yes	0.3	0.2	N	•	4.0 ft²	1 ft 6 in	1 ft 0 in	None	;	None
	10 S=>	NE 10	Metal	Low-E Double	Yes	0.3	0.2	N	1	5.0 ft <sup>2</sup>	1 ft 6 in	1 ft 0 in	None	•	None
	11 S=>	NE 12	Metal	Low-E Double	Yes	0.3	0.2	N	3	32.0 ft²	7 ft 11 in	0 ft 0 in	None	!	None
	12 S=>	NE 12	Metal	Low-E Double	Yes	0.3	0.2	N	1	5.0 ft <sup>2</sup>	7 ft 11 in	0 ft 6 in	None	:	None
	13 W=>	SE 16	Metal	Low-E Double	Yes	0.3	0.2	N	3	0.0 ft <sup>2</sup>	1 ft 6 in	1 ft 0 in	None	1	None
	14 W=>	SE 16	Metal	Low-E Double	Yes	0.3	0.2	N		6.0 ft²	1 ft 6 in	1 ft 0 in	None	· 	None
	·														

FORM R405-2017

INPUT SUMMARY CHECKLIST REPORT

ORN	И R405-20	17	INPU	T SUMM	ARY CH	IECKLIST	REP	ORT					
					G	ARAGE							
V	#	Floor Area	Ce	eiling Area	Expose	d Wall Perimete	er /	Avg. Wall	Height	Expose	d Wall insula	ation	
	1	544.06 ft <sup>2</sup>	5	44.06 ft²		71.5 ft		9 ft			1	_	
					INFIL	TRATION							
#	Scope	Method		SLA	CFM 50	ELA	EqLA		ACH	ACH	50		
1 '	Wholehouse	Proposed ACI	H(50)	.000409	2421.4	132.93	250		1628	7			
					HEATII	NG SYSTEM	N						
V	#	System Type		Subtype		Effic	iency	Car	acity		Bloo	ck [	Ducts
	1	Electric Heat Pum	p/	None		HSP	PF:8.8	41 k	Btu/hr		1	9	sys#1
				·	COOLI	NG SYSTEM	Л						
	#	System Type		Subtype		Efficie	ency	Capacity	Air F	low SI	HR Bloc	ck [	Ducts
	1	Central Unit/		None		SEEF	₹: 16 4	1 kBtu/hr	1230	cfm 0.	75 1	s	sys#1
		· · · · · · · · · · · · · · · · · · ·			HOT WA	TER SYSTE	EM						<u> </u>
V	#	System Type	SubType	Location	EF	Сар	U	se	SetPnt		Conserva	tion	
	1	Electric	None	Garage	0.95	50 gal	60	gal	120 deg		None		
				SOL	AR HOT	WATER SY	STEM						
V	FSEC Cert #		ne	-	System M	lodel#	Collec	ctor Mode		llector Area	Storage Volume	FEF	;
	None	None								ft²			
		•			D	UCTS							
1/	/	Supply		Ret		Lookogo Tr	200	Air Handler	CFM 25 TOT	CFM25 OUT	QN RL		VAC #
V	#	Location R-V		Location	Area	Leakage Ty					WIN KL		
	1	Attic 6	451.2 ft	Attic	112.8 ft	Default Leak	age	Main	(Default)	(Default)		1	1

FORM R405-2017

INPUT SUMMARY CHECKLIST REPORT

ONIVI N403-201	<u>'                                    </u>	1111	01 001	HIVI/IX I	CHLCKI	-101 1/1	-1 01(1					
				TE	MPERATU	JRES						
Programable The	rmostat: Y			Ceiling F	ans:				•			
Cooling [ ] Ja Heating [X] Ja Venting [ ] Ja	n [] Feb n [X] Feb n [] Feb	[ ] Mar [X] Mar [X] Mar	Apr Apr X Apr	[ ] May [ ] May [ ] May	Jun	[X] Jul   Jul   Jul	[X] Aug   Aug   Aug	[X] Se [ ] Se [ ] Se	p p p	Oct Oct X Oct	Nov X Nov X Nov	[ ] Dec [X] Dec [ ] Dec
Thermostat Schedu	Thermostat Schedule: HERS 2006 Reference Hours											
Schedule Type		1	2	3	4 5	6	7	8	9	10	11	12
Cooling (WD)	AM PM	78 80	78 80	78 78	78 78 78 78	78 78	78 78	78 78	80 78	80 78	80 78	80 78
Cooling (WEH)	AM PM	78 78	78 78	78 7 78 7	78 78 78 78	78 78	78 78	78 78	78 78	78 78	78 78	78 78
Heating (WD)	AM PM	66 68	66 68	66 6 68 6	66 66 68 68	68 68	68 68	68 68	68 68	68 68	68 66	68 66
Heating (WEH)	AM PM	66 68	66 68	66 6 68 6	66 66 8 68	68 68	68 68	68 68	68 68	68 68	68 66	68 66
					MASS							
Mass Type			Area		Thickness	S	Furniture Fra	ction		Space		
Default(8 lb	s/sq.ft.		0 ft²		0 ft		0.3			Main		

# **ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD**

### **ESTIMATED ENERGY PERFORMANCE INDEX\* = 96**

The lower the Energy Performance Index, the more efficient the home.

1. New home or, addition	1. New (From Plans)	12. Ducts, location & insulation level
		a) Supply ducts R 6.0
Single-family or multiple-family	2. <u>Single-fami</u> ly	b) Return ducts R 6.0
3. No. of units (if multiple-family)	31_	c) AHU location Main
3. No. of driks (if malaple-latting)	J	
4. Number of bedrooms	43	13. Cooling system: Capacity 41.0
		a) Split system SEER
5. Is this a worst case? (yes/no)	5. <u>Yes</u>	b) Single package SEER
6 Conditioned floor area (or ft)	6. 2256	c) Ground/water source SEER/COP d) Room unit/PTAC EER
6. Conditioned floor area (sq. ft.)	6. <u>2256</u>	d) Room unit/PTAC EER
7. Windows, type and area		
a) U-factor:(weighted average)	7a. 0.300	
b) Solar Heat Gain Coefficient (SHGC)	7b. 0.200	14. Heating system: Capacity 41.0
c) Area	7c. 367.0	a) Split system heat pump HSPF
•		b) Single package heat pump HSPF
8. Skylights		c) Electric resistance COP
a) U-factor:(weighted average)	8aNA_	d) Gas furnace, natural gas AFUE
b) Solar Heat Gain Coefficient (SHGC)	8b. <u>NA</u>	e) Gas furnace, LPG AFUE
		f) Other 8.80
9. Floor type, insulation level:		
a) Slab-on-grade (R-value)	9a. <u>0.0</u>	
b) Wood, raised (R-value)	9b	15. Water heating system
c) Concrete, raised (R-value)	9c	a) Electric resistance EF 0.95
		b) Gas fired, natural gas EF
10. Wall type and insulation:		c) Gas fired, LPG EF
A. Exterior:	4044 400	d) Solar system with tank EF
Wood frame (Insulation R-value)	10A1. 13.0	e) Dedicated heat pump with tank EF
2. Masonry (Insulation R-value)	10A2	f) Heat recovery unit HeatRec%
B. Adjacent:	40D4 40 0	g) Other
Wood frame (Insulation R-value)     Message (Insulation R-value)	10B1. <u>13.0</u> 10B2	
2. Masonry (Insulation R-value)	10BZ	16. HVAC credits claimed (Performance Method)
11. Ceiling type and insulation level		a) Ceiling fans
a) Under attic	11a. 38.0	b) Cross ventilation No
b) Single assembly	11b	c) Whole house fan No
c) Knee walls/skylight walls	11c. 38.0	d) Multizone cooling credit
d) Radiant barrier installed	11d. <u>No</u>	e) Multizone heating credit
,		f) Programmable thermostat Yes
		, 0
*Label required by Section R303.1.3 of the Flo	orida Building Code, Ener	rgy Conservation, if not DEFAULT.
•	_	
I certify that this home has complied with the	Florida Building Code, En	ergy Conservation, through the above energy
saving features which will be installed (or exce	eeded) in this home befor	e final inspection. Otherwise, a new EPL
display card will be completed based on insta	lled code compliant featu	res.
		ſſ
		Date: 8/20/19
Builder Signature:		Date:
X		
Address of New Home: 350 NW	Taylor Mage D	City/FL Zin: Lake City_FL

# Florida Building Code, Energy Conservation, 6th Edition (2017) Mandatory Requirements for Residential Performance, Prescriptive and ERI Methods

ΑI	DDRESS:			Permit Number:	
BEAL	VDATOR	Lake City , FL ,	80		
WAI	NDATOR	Y REQUIREMENT	See individual code sec	tions for full details.	
$\checkmark$			SECTION R401	GENERAL	
	card be con 553.9085, F residential t dwelling un	npleted and certified by the b Florida Statutes) requires the puildings. The EPL display ca it. The building official shall vo	uilder to be accurate and correct be EPL display card to be included as	efore final approval of the building f an addendum to each sales contra he energy performance level and e pleted and signed by the builder ac	
		leakage (Mandatory). s R402.4.1 through R402.4.5		be constructed to limit air leakage	in accordance with the requirements o
		Exception: Dwelling unit comply with Section C402	s of R-2 Occupancies and multiple 5.	attached single family dwellings sh	all be permitted to
			Time building thermal envelope sha imilar materials shall allow for diffe		and R402.4.1.2.
	the m	anufacturer's instructions and		1.1, as applicable to the method of	shall be installed in accordance with construction. Where required by the
	chang accor individ an ap	ges per hour in Climate Zones dance with ANSI/RESNET/IC duals as defined in Section 5 proved third party. A written r	g or dwelling unit shall be tested ar a 1 and 2, and three air changes pe C 380 and reported at a pressure 53.993(5) or (7), Florida Statutes, o eport of the results of the test shall at any time after creation of all per	er hour in Climate Zones 3 through of 0.2 inch w.g. (50 pascals). Testir r individuals licensed as set forth in be signed by the party conducting	8. Testing shall be conducted in ig shall be conducted by either in Section 489.105(3)(f), (g) or (i) or the test and provided to the code
			uired for additions, alterations, reno ction is less than 85 percent of the		thermal envelope of existing
	1. Ext other 2. Da infiltra 3. Inte 4. Ext 5. He	infiltration control measures, mpers including exhaust, inta tion control measures. erior doors, if installed at the tenor doors for continuous veating and cooling systems, if	place and stove doors shall be clost ke, makeup air, backdraft and flue ime of the test, shall be open. Intilation systems and heat recovery installed at the time of the test, shall stalled at the time of the test, shall	dampers shall be closed, but not so ventilators shall be closed and se if be turned off.	ealed beyond intended
	tight-fitting o	doors on factory-built fireplace	ng fireplaces shall have tight-fitting es listed and labeled in accordance on masonry fireplaces, the doors sl	with UL 127, the doors shall be tes	sted and listed for the
	square foot	(1.5 L/s/m2), and swinging de	ows, skylights and sliding glass doo oors no more than 0.5 cfm per squa n accredited, independent laborato	are foot (2.6 L/s/m2), when tested a	ccording to NFRC 400 or
	Exce	ption: Site-built windows	s, skylights and doors.		

### **MANDATORY REQUIREMENTS** - (Continued) R402.4.4 Rooms containing fuel-burning appliances. In Climate Zones 3 through 8, where open combustion air ducts provide combustion air to open combustion fuel burning appliances, the appliances and combustion air opening shall be located outside the building thermal envelope or enclosed in a room, isolated from inside the thermal envelope. Such rooms shall be sealed and insulated in accordance with the envelope requirements of Table R402.1.2, where the walls, floors and ceilings shall meet not less than the basement wall R-value requirement. The door into the room shall be fully gasketed and any water lines and ducts in the room insulated in accordance with Section R403. The combustion air duct shall be insulated where it passes through conditioned space to a minimum of R-8. **Exceptions:** Direct vent appliances with both intake and exhaust pipes installed continuous to the outside. 1. Fireplaces and stoves complying with Section R402.4.2 and Section R1006 of the Florida Building Code, Residential. 2. Recessed luminaires installed in the building thermal envelope shall be sealed to limit air leakage between conditioned and unconditioned spaces. All recessed luminaires shall be IC-rated and labeled as having an air leakage rate not more than 2.0 cfm (0.944 L/s) when tested in accordance with ASTM E283 at a 1.57 psf (75 Pa) pressure differential. All recessed luminaires shall be sealed with a gasket or caulk between the housing and the interior wall or ceiling covering. SECTION R403 SYSTEMS R403.1 Controls. R403.1.1 Thermostat provision (Mandatory). At least one thermostat shall be provided for each separate heating and cooling system. R403.1.3 Heat pump supplementary heat (Mandatory). Heat pumps having supplementary electric-resistance heat shall have controls that, except during defrost, prevent supplemental heat operation when the heat pump compressor can meet the heating load. All ducts, air handlers, filter boxes and building cavities that form the primary air containment passageways R403.3.2 Sealing (Mandatory) for air distribution systems shall be considered ducts or plenum chambers, shall be constructed and sealed in accordance with Section C403.2.9.2 of the Commercial Provisions of this code and shall be shown to meet duct tightness criteria below. Duct tightness shall be verified by testing in accordance with ANSI/RESNET/ICC 380 by either individuals as defined in Section 553.993(5) or (7), Florida Statutes, or individuals licensed as set forth in Section 489.105(3)(f), (g) or (i), Florida Statutes, to be "substantially leak free" in accordance with Section R403.3.3. R403.3.2.1 Sealed air handler. Air handlers shall have a manufacturer's designation for an air leakage of no more than 2 percent of the design airflow rate when tested in accordance with ASHRAE 193. R403.3.3 Duct testing (Mandatory). Ducts shall be pressure tested to determine air leakage by one of the following methods: Rough-in test: Total leakage shall be measured with a pressure differential of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system, including the manufacture of 0.1 inch w.g. (25 Pa) across the system of 0.1 inch w.g. (25 Pa) across the system of 0.1 inch w.g. (25 Pa) across the 0.1 inch w.g. (25 Pa) air handler enclosure if installed at the time of the test. All registers shall be taped or otherwise sealed during the test. Postconstruction test: Total leakage shall be measured with a pressure differential of 0.1 inch w.g. (25 Pa) across the entire system, including the manufacturer's air handler enclosure. Registers shall be taped or otherwise sealed during the **Exceptions:** 1. A duct air leakage test shall not be required where the ducts and air handlers are located entirely within the building thermal envelope. 2. Duct testing is not mandatory for buildings complying by Section 405 of this code. A written report of the results of the test shall be signed by the party conducting the test and provided to the code official. R403.3.5 Building cavities (Mandatory). Building framing cavities shall not be used as ducts or plenums. R403.4 Mechanical system piping insulation (Mandatory). Mechanical system piping capable of carrying fluids above 105°F (41°C) or below 55°F (13°C) shall be insulated to a minimum of R-3. R403.4.1 Protection of piping insulation. Piping insulation exposed to weather shall be protected from damage, including that caused by sunlight, moisture, equipment maintenance and wind, and shall provide shielding from solar radiation that can cause degradation of the material. Adhesive tape shall not be permitted. R403.5.1 Heated water circulation and temperature maintenance systems (Mandatory) Heated water circulation systems shall be in accordance with Section R403.5.1.1. Heat trace temperature maintenance systems shall be in accordance with Section R403.5.1.2.

occupancy. The controls shall automatically turn off the pump when the water in the circulation loop is at the desired temperature and when there is no demand for hot water.

R403.5.1.2 Heat trace systems. Electric heat trace systems shall comply with IEEE 515.1 or UL 515. Controls for such systems shall

R403.5.1.1 Circulation systems. Heated water circulation systems shall be provided with a circulation pump. The system return pipe shall be a dedicated return pipe or a cold water supply pipe. Gravity and thermosiphon circulation systems shall be prohibited. Controls for circulating hot water system pumps shall start the pump based on the identification of a demand for hot water within the

automatically adjust the energy input to the heat trace systems shall automatically adjust the energy input to the heat tracing to maintain the desired water temperature in the piping in accordance with the times when heated water is used in the occupancy.

Automatic controls, temperature sensors and pumps shall be accessible. Manual controls shall be readily accessible.

### MANDATORY REQUIREMENTS - (Continued) R403.5.5 Heat traps (Mandatory). Storage water heaters not equipped with integral heat traps and having vertical pipe risers shall have heat traps installed on both the inlets and outlets. External heat traps shall consist of either a commercially available heat trap or a downward and upward bend of at least 3 ½ inches (89 mm) in the hot water distribution line and cold water line located as close as possible to the storage tank. R403.5.6 Water heater efficiencies (Mandatory). R403.5.6.1.1 Automatic controls. Service water-heating systems shall be equipped with automatic temperature controls capable of adjustment from the lowest to the highest acceptable temperature settings for the intended use. The minimum temperature setting range shall be from 100°F to 140°F (38°C to 60°C). R403.5.6.1.2 Shut down. A separate switch or a clearly marked circuit breaker shall be provided to permit the power supplied to electric service systems to be turned off. A separate valve shall be provided to permit the energy supplied to the main burner(s) of combustion types of service water-heating systems to be turned off. R403.5.6.2 Water-heating equipment. Water-heating equipment installed in residential units shall meet the minimum efficiencies of Table C404.2 in Chapter 4 of the Florida Building Code, Energy Conservation, Commercial Provisions, for the type of equipment installed. Equipment used to provide heating functions as part of a combination system shall satisfy all stated requirements for the appropriate water-heating category. Solar water heaters shall meet the criteria of Section R403.5.6.2.1. Solar systems for domestic hot water production are rated by the annual solar energy R403.5.6.2.1 Solar water-heating systems. factor of the system. The solar energy factor of a system shall be determined from the Florida Solar Energy Center Directory of Certified Solar Systems. Solar collectors shall be tested in accordance with ISO Standard 9806, Test Methods for Solar Collectors, and SRCC Standard TM-1, Solar Domestic Hot Water System and Component Test Protocol. Collectors in installed solar water-heating systems should meet the following criteria: 1. Be installed with a tilt angle between 10 degrees and 40 degrees of the horizontal; and 2. Be installed at an orientation within 45 degrees of true south. The building shall be provided with ventilation that meets the requirements of the R403.6 Mechanical ventilation (Mandatory). Florida Building Code, Residential, or Florida Building Code, Mechanical, as applicable, or with other approved means of ventilation including: Natural, Infiltration or Mechanical means. Outdoor air intakes and exhausts shall have automatic or gravity dampers that close when the ventilation system is not operating. R403.6.1 Whole-house mechanical ventilation system fan efficacy. When installed to function as a whole-house mechanical ventilation system, fans shall meet the efficacy requirements of Table R403.6.1. Exception: Where whole-house mechanical ventilation fans are integral to tested and listed HVAC equipment, they shall be powered by an electronically commutated motor. R403.6.2 Ventilation air. Residential buildings designed to be operated at a positive indoor pressure or for mechanical ventilation shall meet the following criteria: The design air change per hour minimums for residential buildings in ASHRAE 62.2, Ventilation for Acceptable Indoor Air Quality, shall be the maximum rates allowed for residential applications.

- No ventilation or air-conditioning system make-up air shall be provided to conditioned space from attics, crawlspaces, attached enclosed garages or outdoor spaces adjacent to swimming pools or spas.
- 3. If ventilation air is drawn from enclosed space(s), then the walls of the space(s) from which air is drawn shall be insulated to a minimum of R-11 and the ceiling shall be insulated to a minimum of R-19, space permitting, or R-10 otherwise.

### R403.7 Heating and cooling equipment (Mandatory).

R403.7.1 Equipment sizing. Heating and cooling equipment shall be sized in accordance with ACCA Manual S based on the equipment loads calculated in accordance with ACCA Manual J or other approved heating and cooling calculation methodologies, based on building loads for the directional orientation of the building. The manufacturer and model number of the outdoor and indoor units (if split system) shall be submitted along with the sensible and total cooling capacities at the design conditions described in Section R302.1. This Code does not allow designer safety factors, provisions for future expansion or other factors that affect equipment sizing. System sizing calculations shall not include loads created by local intermittent mechanical ventilation such as standard kitchen and bathroom exhaust systems. New or replacement heating and cooling equipment shall have an efficiency rating equal to or greater than the minimum required by federal law for the geographic location where the equipment is installed.

# TABLE R403.6.1 WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM FAN EFFICACY

FAN LOCATION	AIRFLOW RATE MINIMUM (CFM)	MINIMUM EFFICACY <sup>a</sup> (CFM/WATT)	AIRFLOW RATE MAXIMUM (CFM)
Range hoods	Any	2.8 cfm/watt	Any
In-line fan	Any	2.8 cfm/watt	Any
Bathroom, utility room	10	1.4 cfm/watt	<90
Bathroom, utility room	90	2.8 cfm/watt	Any

For SI: 1 cfm = 28.3 L/min.

a. When tested in accordance with HVI Standard 916

### MANDATORY REQUIREMENTS -(Continued) R403.7.1.1 Cooling equipment capacity. Cooling only equipment shall be selected so that its total capacity is not less than the calculated total load but not more than 1.15 times greater than the total load calculated according to the procedure selected in Section 403.7, or the closest available size provided by the manufacturer's product lines. The corresponding latent capacity of the equipment shall not be less than the calculated latent load. The published value for AHRI total capacity is a nominal, rating-test value and shall not be used for equipment sizing. Manufacturer's expanded performance data shall be used to select cooling-only equipment. This selection shall be based on the outdoor design dry-bulb temperature for the load calculation (or entering water temperature for water-source equipment), the blower CFM provided by the expanded performance data, the design value for entering wet-bulb temperature and the design value for entering dry-bulb temperature. Design values for entering wet-bulb and dry-bulb temperatures shall be for the indoor dry bulb and relative humidity used for the load calculation and shall be adjusted for return side gains if the return duct(s) is installed in an unconditioned space. Attached single- and multiple-family residential equipment sizing may be selected so that its cooling capacity is less than the 1. calculated total sensible load but not less than 80 percent of that load. 2. When signed and sealed by a Florida-registered engineer, in attached single- and multiple-family units, the capacity of equipment may be sized in accordance with good design practice. R403.7.1.2 Heating equipment capacity. R403.7.1.2.1 Heat pumps. Heat pump sizing shall be based on the cooling requirements as calculated according to Section R403.7.1.1, and the heat pump total cooling capacity shall not be more than 1.15 times greater than the design cooling load even if the design heating load is 1.15 times greater than the design cooling load. R403.7.1.2.2 Electric resistance furnaces. Electric resistance furnaces shall be sized within 4 kW of the design requirements calculated according to the procedure selected in Section R403.7.1. R403.7.1.2.3 Fossil fuel heating equipment. The capacity of fossil fuel heating equipment with natural draft atmospheric burners shall not be less than the design load calculated in accordance with Section R403.7.1. R403.7.1.3 Extra capacity required for special occasions. Residences requiring excess cooling or heating equipment capacity on an intermittent basis, such as anticipated additional loads caused by major entertainment events, shall have equipment sized or controlled to prevent continuous space cooling or heating within that space by one or more of the following options: 1. A separate cooling or heating system is utilized to provide cooling or heating to the major entertainment areas. 2. A variable capacity system sized for optimum performance during base load periods is utilized. R403.8 Systems serving multiple dwelling units (Mandatory). Systems serving multiple dwelling units shall comply with Sections C403 and C404 of the IECC-Commercial Provisions in lieu of Section R403. R403.9 Snow melt and ice system controls (Mandatory) Snow- and ice-melting systems, supplied through energy service to the building, shall include automatic controls capable of shutting off the system when the pavement temperature is above 50°F (10°C), and no precipitation is falling and an automatic or manual control that will allow shutoff when the outdoor temperature is above 40°F (4.8°C). R403.10 Pools and permanent spa energy consumption (Mandatory). The energy consumption of pools and permanent spas shall be in accordance with Sections R403.10.1 through R403.10.5. The electric power to heaters shall be controlled by a readily accessible on-off switch that is an R403.10.1 Heaters. integral part of the heater mounted on the exterior of the heater, or external to and within 3 feet (914 mm) of the heater. Operation of such switch shall not change the setting of the heater thermostat. Such switches shall be in addition to a circuit breaker for the power to the heater. Gas-fired heaters shall not be equipped with continuously burning ignition pilots. R403.10.2 Time switches. Time switches or other control methods that can automatically turn off and on according to a preset schedule shall be installed for heaters and pump motors. Heaters and pump motors that have built-in time switches shall be in compliance with this section. **Exceptions:** 1. Where public health standards require 24-hour pump operation. 2. Pumps that operate solar- and waste-heat-recovery pool heating systems. 3. Where pumps are powered exclusively from on-site renewable generation. R403.10.3 Covers. Outdoor heated swimming pools and outdoor permanent spas shall be equipped with a vapor-retardant cover on or at the water surface or a liquid cover or other means proven to reduce heat loss. Where more than 70 percent of the energy for heating, computed over an operation season, is from site-recovered energy, such as from a heat pump or solar energy source, covers or other vapor-retardant means shall not be required. R403.10.4 Gas- and oil-fired pool and spa heaters. All gas- and oil-fired pool and spa heaters shall have a minimum thermal efficiency of 82 percent for heaters manufactured on or after April 16, 2013, when tested in accordance with ANSI Z 21.56. Pool heaters fired by natural or LP gas shall not have continuously burning pilot lights.

	<b>R403.10.5</b> Heat pump pool heaters. Heat pump pool heaters shall have a minimum COP of 4.0 when tested in accordance with AHRI 1160, Table 2, Standard Rating Conditions-Low Air Temperature. A test report from an independent laboratory is required to verify procedure compliance. Geothermal swimming pool heat pumps are not required to meet this standard.
	R403.11 Portable spas (Mandatory) e energy consumption of electric-powered portable spas shall be controlled by the requirements of APSP-14.
	SECTION R404
EL	ECTRICAL POWER AND LIGHTING SYSTEMS
	R404.1 Lighting equipment (Mandatory). Not less than 75 percent of the lamps in permanently installed lighting fixtures shall be high-efficacy lamps or not less than 75 percent of the permanently installed lighting fixtures shall contain only high-efficacy lamps.  Exception: Low-voltage lighting.

R404.1.1 Lighting equipment (Mandatory)Fuel gas lighting systems shall not have continuously burning pilot lights.

### 2017 - AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA

# TABLE 402.4.1.1 AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA

Project Name:

190950 Rivers Res

Builder Name: Bryan Zecher Construction

Street: City, State, Zip:

Lake City , FL ,

Permit Office: Permit Number:

Owner:

Jurisdiction:

Design Location:	FL, Gainesville		
COMPONENT	AIR BARRIER CRITERIA	INSULATION INSTALLATION CRITERIA	
General requirements	A continuous air barrier shall be installed in the building envelope. The exterior thermal envelope contains a continuous air barrier. Breaks or joints in the air barrier shall be sealed.	Air-permeable insulation shall not be used as a sealing material.	
Ceiling/attic	The air barrier in any dropped ceiling/soffit shall be aligned with the insulation and any gaps in the air barrier shall be sealed.  Access openings, drop down stairs or knee wall doors to unconditioned attic spaces shall be sealed.	The insulation in any dropped ceiling/soffit shall be aligned with the air barrier.	
Walls	The junction of the foundation and sill plate shall be sealed. The junction of the top plate and the top of exterior walls shall be sealed. Knee walls shall be sealed.	Cavities within corners and headers of frame walls shall be insulated by completely filling the cavity with a material having a thermal resistance of R-3 per inch minimum.  Exterior thermal envelope insulation for framed walls shall be installed in substantial contact and continuous alignment with the air barrier.	
Windows, skylights and doors	The space between window/door jambs and framing, and skylights and framing shall be sealed.	33331803	
Rim joists	Rim joists shall include the air barrier.	Rim joists shall be insulated.	
Floors (including above-garage and cantilevered floors)	The air barrier shall be installed at any exposed edge of insulation.	Floor framing cavity insulation shall be installed to maintain permanent contact with the underside of subfloor decking, or floor framing cavity insulation shall be permitted to be in contact with the top side of sheathing, or continuous insulation installed on the underside of floor framing and extends from the bottom to the top of all perimeter floor framing members.	
Crawl space walls	Exposed earth in unvented crawl spaces shall be covered with a Class I vapor retarder with overlapping joints taped.	Where provided instead of floor insulation, insulation shall be permanently attached to the crawlspace	
Shafts, penetrations	Duct shafts, utility penetrations, and flue shafts opening to exterior or unconditioned space shall be sealed.		
Narrow cavities		Batts in narrow cavities shall be cut to fit, or narrow cavities shall be filled by insulation that on installation readily conforms to the available cavity spaces.	
Garage separation	Air sealing shall be provided between the garage and conditioned space	es.	
Recessed lighting	Recessed light fixtures installed in the building thermal envelope shall be sealed to the drywall.	Recessed light fixtures installed in the building thermal envelope shall be air tight and IC rated.	
Plumbing and wiring		Batt insulation shall be cut neatly to fit around wiring and plumbing in exterior walls, or insulation that on installation readily conforms to available space shall extend behind piping and wiring.	
Shower/tub on exterior wall	The air barrier installed at exterior walls adjacent to showers and tubs shall separate them from the showers and tubs.	Exterior walls adjacent to showers and tubs shall be insulated.	
Electrical/phone box or exterior walls	The air barrier shall be installed behind electrical or communication boxes or air-sealed boxes shall be installed.		
HVAC register boots	HVAC register boots that penetrate building thermal envelope shall be sealed to the sub-floor or drywall.		
Concealed sprinklers	When required to be sealed, concealed fire sprinklers shall only be sealed in a manner that is recommended by the manufacturer.  Caulking or other adhesive sealants shall not be used to fill voids between fire sprinkler cover plates and walls or ceilings.		

a. In addition, inspection of log walls shall be in accordance with the provisions of ICC-400.

**ECK** 

# **Envelope Leakage Test Report (Blower Door Test)**

Residential Prescriptive, Performance or ERI Method Compliance 2017 Florida Building Code, Energy Conservation, 6th Edition

Builder: Bryan Zecher Construction Community: Lot: NA  Address:  City: Lake City	Jurisdiction:	Permit #:
Address:  City: Lake City	Job Information	
Air Leakage Test Results  Passing results must meet either the Performance, Prescriptive, or ERI Method  PRESCRIPTIVE METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.  PERFORMANCE or ERI METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.  PERFORMANCE or ERI METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R405-2017 (ERI); 7.000  ACH(50) specified on Form R405-2017 Energy Calc (Performance) or R405-2017 (ERI); 7.000  PASS  ACH(50) pascalt and the selected ACH(50) PASS  When ACH(50) is less than 3, Mechanical Ventilation installation Field measured and calculated must be verified by building department.  R402.4.1.2 Testing, Testing shall be conducted by either individuals as defined in Section 553 a93(5) or (7), Florida Statues or individuals iconsed as set forth in Section 489.105(3)), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to thecode official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.  During testing:  L'Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers inducting exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Feterior doors for continuous verifilation systems and heat recovery ventilations systems and heat recovery ventilations systems if installed at the time of the test, shall be turne	Builder: Bryan Zecher Construction Community:	Lot: NA
Air Leakage Test Results  Passing results must meet either the Performance, Prescriptive, or ERI Method  PRESCRIPTIVE METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.  PERFORMANCE or ERI METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R406-2017 (ERI), section labeled as infiltration, sub-section ACH50. ACH(50) specified on Form R405-2017-Energy Cela (Performance) or R406-2017 (ERI):  7.000  X 60 + 20755 Building Volume  ACH(50) PASS  When ACH(50) is less than 3, Mechanical Ventilation installation must be verified by building department.  R402.4.1.2 Testing. Testing shall be conducted in accordance with ANSI/RESNETI/CC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascal resting shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5) or (7), Florida Statues or individuals icensed as set forth in Section 553.993(5)	Address:	
PRESCRIPTIVE METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding 7 air changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.  PERFORMANCE or ERI METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R406-2017 (ERI); section labeled as infiltration, sub-section ACH(50) specified on Form R405-2017-Energy Cata (Performance) or R406-2017 (ERI); 7.000  X 60 + 20755  Building Volume  ACH(50)  PASS  ACH(50)  Building Volume  ACH(50)  ACH(50) is less than 3, Mechanical Ventilation installation  Method for calculating building volume:  Retrieved from architectural plans  Code software calculated  Field measured and calculated  When ACH(50) is less than 3, Mechanical Ventilation installation  Field measured and calculated  R402.4.1.2 Testing, Testing shall be conducted in accordance with ANSI/RESNETI/CC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascalt Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statuse or individuals licensed as set forth in Section 483 1053(0), (0), or (0) or an approved third party. A written report of the results of the test shall be signed by any conducting the test and provided to thecode official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.  During testing:  1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Interior doors, if installed at the time of the test, shall be timed of the seat, shall be timed off.  5. Heating and cooling systems and heat recovery ventilators shall be	City: Lake City	State: FL Zip:
changes per hour at a pressure of 0.2 inch w.g. (50 Pascals) in Climate Zones 1 and 2.    PERFORMANCE or ERI METHOD-The building or dwelling unit shall be tested and verified as having an air leakage rate of not exceeding the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R406-2017 (ERI); acciton labeled as Infiltration, sub-section ACH50. ACH(50) specified on Form R405-2017-Energy Calc (Performance) or R406-2017 (ERI); 7.000    X 60 + 20755	Air Leakage Test Results Passing results must m	neet either the Performance, Prescriptive, or ERI Method
the selected ACH(50) value, as shown on Form R405-2017 (Performance) or R406-2017 (ERI), section labeled as infiltration, sub-section ACH(50) specified on Form R405-2017-Energy Cale (Performance) or R406-2017 (ERI): 7.000    X 60 + 20755		
PASS  Code software calculated  When ACH(50) is less than 3, Mechanical Ventilation installation  must be verified by building department.  R402.4.1.2 Testing, Testing shall be conducted in accordance with ANSI/RESNET/ICC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascals Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statues or individuals licensed as set forth in Section 489.105(3)(f), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to thecode official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.  During testing:  1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Interior doors, if installed at the time of the test, shall be open.  4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.  5. Heating and cooling systems, if installed at the time of the test, shall be turned off.  6. Supply and return registers, if installed at the time of the test, shall be fully open.  Testing Company  Company Name:  Phone:  I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester:  Date of Test:  Printed Name of Tester:	the selected ACH(50) value, as shown on Form R405-2017 (Performa	ance) or R406-2017 (ERI), section labeled as infiltration, sub-section ACH50.
When ACH(50) is less than 3, Mechanical Ventilation installation	CFM(50) Building Volume ACH(50	
R402.4.1.2 Testing. Testing shall be conducted in accordance with ANSI/RESNET/ICC 380 and reported at a pressure of 0.2 inch w.g. (50 Pascalt Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statues.or individuals licensed as set forth in Section 489.105(3)(f), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to thecode official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.  During testing:  1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Interior doors, if installed at the time of the test, shall be open.  4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.  5. Heating and cooling systems, if installed at the time of the test, shall be turned off.  6. Supply and return registers, if installed at the time of the test, shall be fully open.  Testing Company  Company Name:  I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester:  Date of Test:  Date of Test:  Printed Name of Tester:	PASS	Code software calculated
Testing shall be conducted by either individuals as defined in Section 553.993(5) or (7), Florida Statues.or individuals licensed as set forth in Sectio 489.105(3)(f), (g), or (i) or an approved third party. A written report of the results of the test shall be signed by the party conducting the test and provided to thecode official. Testing shall be performed at any time after creation of all penetrations of the building thermal envelope.  During testing:  1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Interior doors, if installed at the time of the test, shall be open.  4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.  5. Heating and cooling systems, if installed at the time of the test, shall be turned off.  6. Supply and return registers, if installed at the time of the test, shall be fully open.  Testing Company  Company Name:  I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester:  Date of Test:  Printed Name of Tester:		on installation Field measured and calculated
1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed, beyond the intended weatherstripping or other infiltration control measures.  2. Dampers including exhaust, intake, makeup air, back draft and flue dampers shall be closed, but not sealed beyond intended infiltration control measures.  3. Interior doors, if installed at the time of the test, shall be open.  4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed.  5. Heating and cooling systems, if installed at the time of the test, shall be turned off.  6. Supply and return registers, if installed at the time of the test, shall be fully open.  Testing Company  Company Name:  I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester:  Date of Test:  Printed Name of Tester:	Testing shall be conducted by either individuals as defined in Section 489.105(3)(f), (g), or (i) or an approved third party. A written report of t	553.993(5) or (7), Florida Statues.or individuals licensed as set forth in Section he results of the test shall be signed by the party conducting the test and
3. Interior doors, if installed at the time of the test, shall be open. 4. Exterior doors for continuous ventilation systems and heat recovery ventilators shall be closed and sealed. 5. Heating and cooling systems, if installed at the time of the test, shall be turned off. 6. Supply and return registers, if installed at the time of the test, shall be fully open.  Testing Company  Company Name: Phone: I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester: Date of Test: Printed Name of Tester: Date of Tester:	Exterior windows and doors, fireplace and stove doors shall be clos control measures.	
Company Name: Phone: I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester: Date of Test: Printed Name of Tester:	<ul><li>3. Interior doors, if installed at the time of the test, shall be open.</li><li>4. Exterior doors for continuous ventilation systems and heat recovery</li><li>5. Heating and cooling systems, if installed at the time of the test, shall</li></ul>	ll be turned off.
I hereby verify that the above Air Leakage results are in accordance with the 2017 6th Edition Florida Building Code Energy Conservation requirements according to the compliance method selected above.  Signature of Tester: Date of Test:  Printed Name of Tester:		
Energy Conservation requirements according to the compliance method selected above.  Signature of Tester: Date of Test:  Printed Name of Tester:	Company Name:	Phone:
Printed Name of Tester:		
	Signature of Tester:	Date of Test:
License/Certification #: Issuing Authority:	Printed Name of Tester:	
	License/Certification #:	Issuing Authority:

# **Residential System Sizing Calculation**

Summary Project Title: 190950 Rivers Res

Lake City, FL


2019-08-20

Location for weather data: Gaine	sville, FL -	Defaults: L	atitude(29.7) Altitude(152 ft.) Tem	p Range(M)	)			
Humidity data: Interior RH (50%	) Outdoor	wet bulb (7	77F) Humidity difference(51gr.)					
Winter design temperature(TMY3 99%) 30 F   Summer design temperature(TMY3 99%) 94 F								
Winter setpoint	70	F	Summer setpoint	75	F			
Winter temperature difference	40	F	Summer temperature difference	19	F			
Total heating load calculation	34567	Btuh	Total cooling load calculation	32995	Btuh			
Submitted heating capacity	% of calc	Btuh	Submitted cooling capacity	% of calc	Btuh			
Total (Electric Heat Pump)	118.6	41000	Sensible (SHR = 0.75)	111.0	30750			
Heat Pump + Auxiliary(0.0kW)	118.6	41000	Latent	193.6	10250			
			Total (Electric Heat Pump)	124.3	41000			

### WINTER CALCULATIONS

Winter Heating Load (for 2256 soft)


THIRD TIOURING LOUGH (10)	EEGG GGIG			
Load component			Load	
Window total	367	sqft	4404	Btuh
Wall total	1660	sqft	5892	Btuh
Door total	84	sqft	1344	Btuh
Ceiling total	2396	sqft	2432	Btuh
Floor total	2256	sqft	11186	Btuh
Infiltration	90	cfm	3946	Btuh
Duct loss			5363	Btuh
Subtotal			34567	Btuh
Ventilation	0	cfm	0	Btuh
TOTAL HEAT LOSS			34567	Btuh



## SUMMER CALCULATIONS

Summer Cooling Load (for 2256 sqft)

Load component			Load	
Window total	367	sqft	7037	Btuh
Wall total	1660	sqft	3634	Btuh
Door total	84	sqft	1008	Btuh
Ceiling total	2396	sqft	3284	Btuh
Floor total			0	Btuh
Infiltration	68	cfm	1406	Btuh
Internal gain			4240	Btuh
Duct gain			7090	Btuh
Sens. Ventilation	0	cfm	0	Btuh
Blower Load			0	Btuh
Total sensible gain			27699	Btuh
Latent gain(ducts)			1363	Btuh
Latent gain(infiltration)			2333	Btuh
Latent gain(ventilation)	0	Btuh		
Latent gain(internal/occup	1600	Btuh		
Total latent gain			5296	Btuh
TOTAL HEAT GAIN			32995	Btuh





EnergyGauge® System Sizing PREPARED BY: Evan Beamsley DATE: 2019-08-20

# **System Sizing Calculations - Winter**

# Residential Load - Whole House Component Details

Project Title:
190950 Rivers Res
Lake City, FL Building Type: User

2019-08-20

Reference City: Gainesville, FL (Defaults) Winter Temperature Difference: 40.0 F (TMY3 99%) This calculation is for Worst Case. The house has been rotated 225 degrees.

### **Component Loads for Whole House**

Window	Panes/Type	Frame U	Orientation /	Area(sqft) X	HTM=	Load
1	2, NFRC 0.20	Metal 0.30	SW	36.0	12.0	432 Btuh
2	2, NFRC 0.20	Metal 0.30	W	16.0	12.0	192 Btuh
3	2, NFRC 0.20	Metal 0.30	SW	36.0	12.0	432 Btuh
4	2, NFRC 0.20	Metal 0.30	NW	48.0	12.0	576 Btuh
5	2, NFRC 0.20	Metal 0.30	SW	72.0	12.0	864 Btuh
6	2, NFRC 0.20	Metal 0.30	SW	36.0	12.0	432 Btuh
7	2, NFRC 0.20	Metal 0.30	NW	15.0	12.0	180 Btuh
8	2, NFRC 0.20	Metal 0.30	NW	6.0	12.0	72 Btuh
9	2, NFRC 0.20	Metal 0.30	NE	4.0	12.0	48 Btuh
10	2, NFRC 0.20	Metal 0.30	NE	15.0	12.0	180 Btuh
11	2, NFRC 0.20	Metal 0.30	NE	32.0	12.0	384 Btuh
12	2, NFRC 0.20	Metal 0.30	NE	15.0	12.0	180 Btuh
13	2, NFRC 0.20	Metal 0.30	SE	30.0	12.0	360 Btuh
14	2, NFRC 0.20	Metal 0.30	SE	6.0	12.0	72 Btuh
	Window Total			367.0(sqft)		4404 Btuh
Walls	Туре	Ornt. Ueff.	R-Value	Area X	HTM=	Load
			(Cav/Sh)			
1	Frame - Wood	- Ext (0.089)	13.0/0.0	87	3.55	309 Btuh
2	Frame - Wood	- Ext (0.089)	13.0/0.0	91	3.55	322 Btuh
3	Frame - Wood	- Ext (0.089)	13.0/0.0	11	3.55	37 Btuh
4	Frame - Wood	- Ext (0.089)	13.0/0.0	80	3.55	285 Btuh
5	Frame - Wood	- Ext (0.089)	13.0/0.0	20	3.55	71 Btuh
6	Frame - Wood	- Ext (0.089)	13.0/0.0	27	3.55	96 Btuh
7	Frame - Wood	- Ext (0.089)	13.0/0.0	18	3.55	64 Btuh
8	Frame - Wood	- Ext (0.089)	13.0/0.0	87	3.55	309 Btuh
9	Frame - Wood	- Ext (0.089)	13.0/0.0	300	3.55	1065 Btuh
10	Frame - Wood	- Ext (0.089)	13.0/0.0	130	3.55	460 Btuh
11	Frame - Wood	- Ext (0.089)	13.0/0.0	42	3.55	149 Btuh
12	Frame - Wood	- Ext (0.089)	13.0/0.0	101	3.55	357 Btuh
13	Frame - Wood	- Adj (0.089)	13.0/0.0	34	3.55	121 Btuh
14	Frame - Wood	- Adj (0.089)	13.0/0.0	33	3.55	117 Btuh
15	Frame - Wood	- Adj (0.089)	13.0/0.0	144	3.55	511 Btuh
16	Frame - Wood	- Ext (0.089)	13.0/0.0	456	3.55	1619 Btuh
	Wall Total			1660(sqft)		5892 Btuh
Doors	Туре	Storm Ueff.		Area X	HTM=	Load
1	Insulated - Exter	,		8	16.0	128 Btuh
2	Insulated - Exter			16	16.0	256 Btuh
3	Insulated - Exter			24	16.0	384 Btuh
4	Insulated - Exter			16	16.0	256 Btuh
5	Insulated - Gara	ge, n (0.400)		20	16.0	320 Btuh
	Door Total			84(sqft)		1344Btuh

# **Manual J Winter Calculations**

# Residential Load - Component Details (continued)

Lake City, FL

Project Title: 190950 Rivers Res Building Type: User

2019-08-20

Ceilings	Type/Color/Surface	Ueff.	R-Value	Area X	HTM=	Load
1	Vented Attic/D/Shing	(0.025)	38.0/0.0	2256	1.0	2290 Btuh
2	Knee Wall/D/Shing	(0.025)	38.0/0.0	140	1.0	142 Btuh
	Ceiling Total			2396(sqft)		2432Btuh
Floors	Туре	Ueff.	R-Value	Size X	HTM=	Load
1	Slab On Grade	(1.180)	0.0	237.0 ft(per	im.) 47.2	11186 Btuh
	Floor Total			2256 sqft	•	11186 Btuh
				Envelope Subto	otal:	25259 Btuh
Infiltration	Type V	Vholehouse AC	CH Volume	(cuft) Wall Rat	io CFM=	
	Natural	0.2	26 2075	5 1.00	90.1	3946 Btuh
Duct load	Average sealed, R6.0	), Supply(Att),	Return(Att	) (DLM	of 0.184)	5363 Btuh
All Zones			Sensible	e Subtotal All Z	ones	34567 Btuh

### WHOLE HOUSE TOTALS

Subtotal Sensible Heat Loss Totals for Heating Ventilation Sensible Heat Loss Total Heat Loss 34567 E
---

### **EQUIPMENT**

1. Electric Heat Pump	#	41000 Btuh
-----------------------	---	------------

Key: Window types - NFRC (Requires U-Factor and Shading coefficient(SHGC) of glass as numerical values) or - Glass as 'Clear' or 'Tint' (Uses U-Factor and SHGC defaults)

U - (Window U-Factor)

HTM - (ManualJ Heat Transfer Multiplier)



# System Sizing Calculations - Summer

# Residential Load - Whole House Component Details Project Title:

190950 Rivers Res

Lake City, FL

2019-08-20

Reference City: Gainesville, FL Temperature Difference: 19.0F(TMY3 99%) Humidity difference: 51gr. This calculation is for Worst Case. The house has been rotated 225 degrees.

### **Component Loads for Whole House**

		Туре	<b>*</b>			Over	hang	Wind	low Area	a(sqft)	Н	TM	Load	
Window	Panes	SHGC U		IS	Omt	Len	Hgt	Gross	Shaded	Unshaded	Shaded	Unshaded		
1		0.20, 0.30	No	No	SW	1.5ft.	1.0ft.	36.0	8.8	27.2	10	20	632	Btuh
2		0.20, 0.30	No	No	W	16.3f		16.0	16.0	0.0	10	25	159	Btuh
3		0.20, 0.30	No	No	SW	14.5f	0.5ft.	36.0	36.0	0.0	10	20	357	Btuh
4	2 NFRC	0.20, 0.30	No	No	NW	15.8f	0.5ft.	48.0	0.0	48.0	10	19	919	Btuh
5	2 NFRC	0.20, 0.30	No	No	SW	15.2f	0.5ft.	72.0	72.0	0.0	10	20	713	Btuh
6	2 NFRC	0.20, 0.30	No	No	SW	1.5ft.	1.0ft.	36.0	8.8	27.2	10	20	632	Btuh
7	2 NFRC	0.20, 0.30	No	Νo	NW	1.5ft.	1.0ft.	15.0	0.0	15.0	10	19	287	Btuh
8	2 NFRC	0.20, 0.30	No	Νo	NW	1.5ft.	1.0ft.	6.0	0.0	6.0	10	19	115	Btuh
9	2 NFRC	0.20, 0.30	No	No	NE	1.5ft.	1.0ft.	4.0	0.0	4.0	10	19	77	Btuh
10	2 NFRC	0.20, 0.30	No	No	NE	1.5ft.	1.0ft.	15.0	0.0	15.0	10	19	287	Btuh
11	2 NFRC	0.20, 0.30	No	No	NE	7.9ft.	0.0ft.	32.0	0.0	32.0	10	19	612	Btuh
12	2 NFRC	0.20, 0.30	No	No	NE	7.9ft.	0.5ft.	15.0	0.0	15.0	10	19	287	Btuh
13	2 NFRC	0.20, 0.30	No	No	SE	1.5ft.	1.0ft.	30.0	8.8	21.2	10	20	512	Btuh
14	2 NFRC	0.20, 0.30	No	Νo	SE	1.5ft.	1.0ft.	6.0	2.9	3.1	10	20	90	Btuh
	Excursio												1358	Btuh
	Windov	v Total						367 (s	sqft)				7037	Btuh
Walls	Type				U	-Value	R-V	/alue	Area	(sqft)		HTM	Load	
							Cav/S	heath						
1	Frame -	Wood - Ext			(	0.09	13.0		87	'.0		2.3	197	Btuh
2	Frame -	Wood - Ext			(	0.09	13.0	/0.0	90	8.0		2.3	205	Btuh
3	Frame -	Wood - Ext			(	0.09	13.0	/0.0	10	).5		2.3	24	Btuh
4	Frame - 1	Wood - Ext			(	0.09	13.0	/0.0	80	).3		2.3	182	Btuh
5	Frame -	Wood - Ext				0.09	13.0		20			2.3	45	Btuh
6		Wood - Ext				0.09	13.0		27			2.3	61	Btuh
7		Wood - Ext				0.09	13.0		18			2.3	41	Btuh
8		Wood - Ext				0.09	13.0		87			2.3	197	
9		Wood - Ext				0.09	13.0		300			2.3	679	Btuh
10		Wood - Ext				0.09	13.0		129			2.3	293	Btuh
11		Wood - Ext				0.09	13.0		42			2.3	95	Btuh
12		Wood - Ext				0.09	13.0		100			2.3	227	Btuh
13		Wood - Adj				0.09	13.0		34			1.7	57	Btuh
14		Wood - Adj				0.09	13.0		33			1.7	56	Btuh
15		Wood - Adj				0.09	13.0		144			1.7	243 1032	Btuh
16		Wood - Ext			,	0.09	13.0	10.0		456.0 2.3				
	Wall To	otai		-						0 (sqft)		LITEA	3634	biun
Doors	Туре								Area			HTM	Load	
1		- Exterior							8.			12.0	96	Btuh
2		i - Exterior							16			12.0	192	Btuh
3		- Exterior							24			12.0	288	Btuh
4		- Exterior							16			12.0		Btuh
5		l - Garage							20			12.0		Btuh
0.111	Door To			-		\ /e.l.		D 1/-1		4 (sqft)		LITEA	1008	DIUN
Ceilings		olor/Surfa				-Value		R-Value				HTM	Load	
1		Attic/DarkSh	-			0.025		38.0/0.0	225			1.37	3092	
2		all/DarkShin	gle			0.025	3	38.0/0.0	140			1.37		Btuh
	Ceiling	Total							239	6 (sqft)			3284	Btuh

# **Manual J Summer Calculations**

# Residential Load - Component Details (continued) Project Title: Climate:FL\_GAINESVILLE\_REGIONAL\_A 190950 Rivers Res

Lake City, FL

2019-08-20

Floors	Туре	R-V	alue	Size		НТМ	Load	
1 8	Slab On Grade Floor Total		0.0	2256 256.0	(ft-perimeter) (sqft)	0.0	_	Btuh Btuh
				Enve	elope Subto	otal:	14963	Btuh
Infiltration	Type Natural	Average ACH 0.20		(cuft) V 0755	Wall Ratio	CFM= 67.6	Load 1406	Btuh
Internal gain		Occupants 8	Btu X	h/occu 230	ıpant +	Appliance 2400	Load 4240	Btuh
				Sen	sible Envel	ope Load:	20608	Btuh
Duct load	Average sealed, Supply	(R6.0-Attic), Return(R6.0-Atti	c)		(DGM of 0	0.344)	7090	Btuh
				Sensi	ble Load A	All Zones	27699	Btuh

# **Manual J Summer Calculations**

# Residential Load - Component Details (continued)

Project Title: 190950 Rivers Res Climate:FL\_GAINESVILLE\_REGIONAL\_A

Lake City, FL

2019-08-20

WHOLE HOUSE TOTALS		14-12-30	
	Sensible Envelope Load All Zones	20608	Btuh
	Sensible Duct Load	7090	Btuh
	Total Sensible Zone Loads	27699	Btuh
	Sensible ventilation	0	Btuh
	Blower	0	Btuh
Whole House	Total sensible gain	27699	Btuh
<b>Totals for Cooling</b>	Latent infiltration gain (for 51 gr. humidity difference)	2333	Btuh
	Latent ventilation gain	0	Btuh
	Latent duct gain	1363	Btuh
	Latent occupant gain (8.0 people @ 200 Btuh per person)	1600	Btuh
	Latent other gain	0	Btuh
	Latent total gain	5296	Btuh
	TOTAL GAIN	32995	Btuh

EQUIPMENT		
1. Central Unit	#	41000 Btuh

\*Key: Window types (Panes - Number and type of panes of glass)
(SHGC - Shading coefficient of glass as SHGC numerical value)

(U - Window U-Factor)

(InSh - Interior shading device: none(No), Blinds(B), Draperies(D) or Roller Shades(R))
- For Blinds: Assume medium color, half closed

For Draperies: Assume medium weave, half closed

For Roller shades: Assume translucent, half closed (IS - Insect screen: none(N), Full(F) or Half(½))

(Ornt - compass orientation)

