

2421 NW 49 Ave., Gainesville, FL 32605

dayayan85arch@gmail.com

June 4, 2020

Mr. Jerry Lerner
Lerner Enterprises
292 Hermitage Glen
High Springs, Florida

RE: Construction Clarification for Apartment Buildout in Hanger for Andy Bender located at 706 Southwest Rasberry Court in Columbia County, Florida.

Dear Mr. Jerry Lerner,


Ceiling framing shall be 2 x 8 No. 2 Southern Pine at 16" O.C..

Ceiling framing shall be 2 x 6 No. 2 Southern Pine at 24" O.C..

No span over 12'-0".

If you have any questions, please do not hesitate to call. Thank you for the opportunity to provide you with this service.

Thank You,



Digitally signed by Donald A
Yanskey
DN: c=US, o=Unaffiliated,
ou=A01427D0000016A6E97AAF7
000020DA, cn=Donald A Yanskey
Date: 2020.06.04 14:33:32 -04'00'



Donald Alan Yanskey, Architect FL AR 0011010

File: Jerry Lerner - Bender - Const - 02.doc