



been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies. Date: 2024.05.01 19:37:22 -04'00'

Digitally signed by MICHAEL THOMPSON Reason: This item has

Screen Room Sun Room Fill In Pool Screen/Cage (Non-Removable Screen – Designed to withstand actual Wind Expansion View (Non Standard) Car Port Patio Cover Pergola Swimming Pool (Non Standard) Summer Kitchen (Non Standard) Other	Date: 2024.05.01 1 -04'00' d Speed
Screen Room Sun Room Fill In Pool Screen/Cage (Non-Removable Screen – Designed to withstand actual Wind Speed Expansion View (Non Standard) Car Port Patio Cover Pergola Swimming Pool (Non Standard) Summer Kitchen (Non Standard) Other Standard Non Standard Revision Commercial \$75.00 Rush Fee Project Address: 358 5. W. Marynik Or. Sity: High Springs, Fl. 33643 Date: 4-30.34 Contractor/Company Name: Jason Jewis Custon Screen Enclosures, Inc. dity: Krystone Heights p Code: 33656 honol/Fax: 386-623-4262 mail: Screen it Right @ gmail.com choose One: Mail Pick Up Fe-File Fed Ex/UPS* # of Copies Single PDF Each Page Separate For FedEx option go to www.aluminumscreendesign.com to pay by credit card)	
*Project Address: 358 S.W. Marynik Dr.	
*City: High Springs, Fl. 32643 Date: 4-30.2	Patio Cover Pool (Non Standard) Id Non Standard Revision Commercial \$75.00 Rush Fee Id Non Standard Revision Commercial \$75.00 Rush Fee
*City: Keystone Heights *Zip Code: 32656 *Phone/Fax: 386-623-4262 *Email: Screen it Right @ g mail. com *Choose One: Mail Pick Up E-File Fed Ex/UPS*# of Cop Single PDF Each Page Separate	
* Payment: Check Credit Card* *(For Credit Card option go to www.aluminumscreendesign.com to pay by credit card) Engineering prepared by:	#)

TASD

Engineer: Michael Thompson, MSc, P.E. (P.E. # 47509)
4401 Vineland Road- Suite A6 Orlando, FL 32811
Office:888-607-0747 or 407-734-1470 Cell: 407-721-2292
Project Manager Paul Thomas 386-479-9504 Fax: 888-923-8181

Email: aluminumscreendesign@yahoo.com

Website: www.aluminumscreendesign.com ca#30930





been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies. Date: 2024.05.01 19:37:38 -04'00'

Digitally signed by MICHAEL THOMPSON Reason: This item has

* Ultimate Wind Speed (mph): 130 Exposed Category: C Risk Category: 1
Screen Room Fill In Sun Room (Window Type Vinyl or Glass) Roof Type: Insulated " Pan Roof " Roof Connecting to: Gutter Fascia Block Wall Conventional Wall 4th Wall Riser Front Wall: Uprights X Top Plate X Bottom Plate X Chair Rail X Side Wall: Uprights X Top Plate X Bottom Plate X Chair Rail X Roof Ridge Beam (gable style): Beams X Kick Plate
Pool Screen/Cage: Roof Type: Dome Gable Mansard/Hip Flat/Slope Roof Connecting to: Gutter Fascia Block Wall Conventional Wall Riser Roof: Beams 2 x 8 Front Wall: Uprights 2 x 6 Purlin 2 x 2 Chair Rail 2 x 3 Side Wall: Uprights 2 x 4 Chair Rail 2 x 3
Expansion View: BeamsX PostX Kick Plate
Car Port Patio Cover or Pergola (pergola material Aluminum Wood) Roof Type: Insulated Pan Roof Mone (Pergola Only) Roof Connecting to: Gutter Fascia Block Wall Conventional Wall 4th Wall Beams X Post X Pergola Purlins X Roof Ridge Beam (gable style): Beams X
Swimming Pool Gunite Fiberglass Overall Deck SQ FT
Summer Kitchen Concrete: □ Existing □ New 4" w/6" Thickened Edge □ Pier X X Ribbon Footer X With # Rebar □ Pavers with Footer 1 X 1 Y With # Rebar
Other:

Note: In the event that there is a conflict with the design plans and general notes and design standard, the contractor shall utilize the more stringent dimensions and member sizes prior to ordering materials, fabrication and/or construction between the plans and the general notes and design standard.

Engineer: Michael Thompson, MSc, P.E. (PE#47509) 4401 Vineland Road Suite A6, Orlando, FL 32811 (CA#30930)-Ph 407-734-1470/Fax 407-734-1790



General Notes & Design Standards

(Non-Removable Pool Screen)

The following are general design standards. More stringent design standards may be noted on the plans. In the event of a conflict in plans and/or design standard dimensions and/or member sizes, the contractor must utilize the more stringent dimensions and/or member sizes prior to ordering materials, fabrication and/or construction.

Design Codes:

Florida Building Code 2023 (8th Edition) Aluminum Design Manual 2020 ASCE 7-22

Design Loads:

Pursuant to FBC Chapters 16 & 20

Ultimate Wind: -130 MPH (FBC Table 2002.4)

Risk Category:-See attach site specific plan sheet (FBC Table 1604.5) Exposure Category: -See attach site specific plan sheet (FBC 1609.4.3)



Digitally signed by MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Date: 2024 05 01 19-39-33 -04'00'

Additional Load requirements:

Structural members supporting screened enclosures are designed for wind in both of two orthogonal directions using the pressures given in Table 2002.4. Each primary member is also designed for a 300 pound load applied vertically downward along any 1 foot of any member, not occurring simultaneously with wind load. In addition to wind pressures, purlins is also be designed for a 200 pound load applied vertically downward along any 1 foot of any member, not occurring simultaneously with wind load.

Design Basis:

Allowable Stress Design (ASD) = Allowable Strength Design (ASD) divide by safety factor

General Requirements:

Reproductions of contract drawings by contractor in lieu of preparation of shop drawings signifies acceptance of information shown as correct and obligates himself to any expense, real or implied, arising from their use.

A change to the structural drawings due to the acceptance of alternates and/or substitutes is the responsibility of the contractor and must be submitted to the engineer for approval.

The general contractor and each subcontractor shall review the approve construction plans in its entirety and verify all existing conditions prior to the start of any work. All inconsistencies shall be reported to the designer and/or structural engineer, if needed. Should contractor construct the premises in a fashion not consistent with the plans prepared by the designer and/or structural engineer, or in any fashion, change the plans and drawing without the review and approval from the designer and/or structural engineer. Then designer and/or structural engineer shall bear no responsibility or liability for the construction of premises and accuracy of the drawings.

Foundation and Earthwork:

Applicable only when unsuitable soils are encountered.

When unsuitable soils are encountered as specified bearing strata, notify owner's representative/engineer. Soil bearing capacity – 2,000 psf Minimum

Provide neat excavation for footing and place concrete immediately after excavation and inspection.

Pump water from footing excavation if greater than one inch. Compact all fill to 95% ASTM D698 density.

Unit soil weight = 105 pcf Internal angle of friction = 30 degrees

Coeff. Of friction between footing and soil = 0.5



Structural Aluminum:

Conform to latest edition of Florida Building Code and Aluminum Design Manual standard practice for aluminum design.

All aluminum shall be 6005-T5 (E= 10,000 ksi; Fy = 35 ksi) with a minimum wall thickness of 0.046"

Splicing prohibited without prior approval as to location and type.

Burning of holes in aluminum members is prohibited. Any member with burned holes must be replaced.

Aluminum Protection:

Shall be pursuant FBC 2003.8.4. Aluminum surfaces in contact with dissimilar materials, lime-mortar, concrete, or other masonry materials, shall be protected with powder coated or ESP paint or alkali-resistant coatings, such as heavy-bodied bituminous paint or water-white methacrylate lacquer.

Screws:

Aluminum self-tapping screws shall conform to ASME B18.6.4 specification.

Self –tapping screws shall meet the requirements of ADM J.5

Maximum fastener spacing shall not exceed (3+20t) where "t" is the member thickness in inches.

For roofing and siding connection, use minimum #12 screws for end and side laps spaced at 12" max for side lap and end lap fasteners shall be no more than 2" from the end of overlapping sheets.

For bottom plate and column base, secure with 1/4" tapcons a minimum embedment of 1 1/8" and 2 1/4" respectively into concrete footer.

Bolts:

Bolts and other fasteners shall be aluminum, stainless steel, hot-dip or electro-galvanized steel. Double cadmium plated steel bolts may also be used. Bolt holes diameter shall not exceed 1/16" larger than the bolt diameter and shall be spaced at a minimum of 2.5 times the bolt diameter with minimum edge distance of 1.5 times the bolt diameter. Bolts shall meet the requirements of ADM J.3

Chair Rails, Purlins & Wind Brace:

Chair rails, purlins and wind brace shall conform with the below maximum span length. If the event contractor's specific site plan conflict with the below recommended length, the contractor shall utilize the more stringent dimensions and member sizes prior to ordering materials, fabrication and/or construction. Screen mesh cover areas shall be continuously secure to each top rail, bottom rail, chair rail, upright, beam and purlin.

Wind Speed = 130 MPH

```
2 x 2 Chair Rail = 7'-0" 2 x 2 Purlins = 7'-0" 2 x 2 Wind Brace = 4'-3" 2 x 3 (0.125) Wind Brace = 9'-0" 2 x 3 Chair Rail = 8'-0" 2 x 3 Purlins = 8'-0" 2 x 3 Wind Brace = 8'-0" 2 x 4 Wind Brace = 9'-0"
```

Concrete:

Conform to ACI 318, latest edition and ACI 301 Compressive Ultimate Strength (Minimum at 28 days) shall be 3000 psi Exposed chamfer edges shall be 3/4"

Reinforcing Steel:

Conform to ACI 318 and 315, Latest edition All reinforcement steel shall be ASTM A615 Grade 60. Smooth dowels & ties shall be ASTM A185 Welded Wire Fabric shall be ASTM A185 or A82 (Flat sheet). Deformed bar anchors shall be ASTM A496, Grade 70 Cover: Footing 3"

<u> Washer:</u>

Washers shall be used under bolt heads and under nuts.



Digitally signed by MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Date: 2024.05.01 19:40:00 -04'00'



Hole Alignment:

Poor matching holes must be rejected. Contractor shall prevent holes from drifting and distort the metal. All chips and foreign matter between contacting surfaces shall be removed before assembly.

Cables:

Contractor shall provide a minimum 1/8" diameter stainless steel cable tie down at side and rear walls of pool screen enclosure. Contractor shall secure cable to top of column located at each corner and where there is a difference in column height locations. In addition, cables shall be spaced to provide wall support not exceeding 227.5 ft² with bottom each end of cables secure to concrete slab with a minimum 3"ASTM A-36 steel clip with 2-1 ½" x ¼" tapcons or equal.

Beams & Uprights:

In the event of a conflict with the values in this table and the site specific plan, the contractor must utilize the more stringent dimensions and/or member sizes between the site specific plan and the below applicable span limitations prior to ordering materials, fabrication and/or construction.

prior to or	dering materials, ractical	Toll ullu, of collect action	•					
130 MPH								
PRIMARY ROOF MEMBERS-POOL CAGE ENCLOSURES								
SIZE	Roof Span *Maximum Beam Spacing = 6'-0"	Roof Span *Maximum Beam Spacing = 6'-8"	Roof Span *Maximum Beam Spacing = 7'-2"					
2 X 4	17'-9"	16'-9"	15'-6"					
2 X 5	23'-3"	22'-0"	19'-0"					
2 X 6	26'-0"	25'-0"	22'-9"					
2 X 7	28'-0"	27'-0"	26'-6"					
2 X 8	34'-0"	33'-0"	32'-6"					
2 X 9	36'-0"	35'-0"	34'-6"					
2 X 10	40'-0"	39'-0"	38'-6"					

Upright -Pool Cage Enclosures						
Upright	130 MPH					
SIZE	Height					
2 X 4	11'-6"					
2 X 5	13'-6"					
2 X 6	15'-0"					
2 X 7	16'-9"					
2 X 8	17'-9"					
2 X 9	18'-9"					
2 X 10	22'-0"					



Digitally signed by MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies. Date: 2024.05.01 19:40:47

Knee Bracing:

Contractor shall provide knee bracing on 45 degree angle pursuant the attach detail sheet that specified size and length requirements. Knee bracing on upright above super gutter intersection shall be connected to upright no more than 6" above the super gutter. Knee brace size shall be a minimum of 2 x 2 for beam span of 15' max; 2 x 3 for 30' max; 2 x 4 for beam span greater than 30'.

Purlin:

Contractor is required to install purlins spaced to align with column spacing; however, spacing between purlins shall not exceed 7'-2".

Header Beam:


Contractor is required to install a minimum 2 x 7 header beam supported with 3 x 3 column space at 10 feet (max) with a 2' x 2' x 1'-6" concrete footer with 3#5 each way when screen enclosed is required to be attached super gutter at the interface of the insulated roof panel. Contractor is required to install insulated roof covering pursuant to the Florida product approval specification (35 psf).


Intermediate Girts:

Contractor is required to install intermediate chair rails/girts spaced at mid-span between the chair rails and top rail or 6'-0" max on center when column height exceeds 11 feet. Contractor is also required to install one additional intermediate chair rail/girt to be located 3 feet below the top rail when column height exceeds 14 feet.

Edge Distance:

Contractor is required to install uprights to provide a 2" minimum clearance from edge of slab and/or footer.






2X2 ANGLE IS ATTACHED TO BEAM

WITH (2) #10 1" & INTO BLOCK WITH

2-1/4" X 1/4" TAPCON



ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PHONE: 407-734-1470 FAX: 407-734-1790

Reason: This item has been digitally signed & sealed by Michael A. Thompson on the

date adjacent to the seal. Printed copies of


this document are not considered signed

and sealed and the signature must be verified on any electronic copies. Date: 2024.05.01 19:41:59 -04'00'

DESIGN STATEMENT

METAL IS .046 THICKNESS OR GREATER, ALLOY IS 6005-T5
ALL TAPCONS SHALL PROVIDE MINIMUM OF 1 1/8" CONCRETE EMBEDMENT DEPTH

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE TO MEET THE REQUIREMENTS OF THE 2023 (8TH EDITION)
FLORIDA BUILDING CODE FOR OPEN AND SEMI-OPEN STRUCTURES AND SHALL WITH STAND ULTIMATE WIND SPEEDS OF 130 MPH
(FOR 3 SECOND GUSTS) NOMINAL SPEED 101.4 MPH UP TO A 15FT ROOF HEIGHT, FACTOR OF 1.0, AND EXPOSURE C, RISK CATEGORY 1.
CONTRACTOR SHALL FIELD VERIFY ALL PLANS DIMENSIONS PRIOR TO MATERIAL PURCHASE, FABRICATION AND CONSTRUCTION
CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SHOULD SITE CONDITIONS DIFFER FROM CONSTRUCTION PLANS




ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PHONE: 407-734-1470

FAX: 407-734-1790

DESIGN STATEMENT
METAL IS .046 THICKNESS OR GREATER, ALLOY IS 6005-T5 ALL TAPCONS SHALL PROVIDE MINIMUM OF 1 1/8" CONCRETE EMBEDMENT DEPTH

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE TO MEET THE REQUIREMENTS OF THE 2023 (8TH EDITION) FLORIDA BUILDING CODE FOR OPEN AND SEMI-OPEN STRUCTURES AND SHALL WITH STAND ULTIMATE WIND SPEEDS OF 130 MPH (FOR 3 SECOND GUSTS) NOMINAL SPEED 101.4 MPH UP TO A 15FT ROOF HEIGHT, FACTOR OF 1.0, AND EXPOSURE C, RISK CATEGORY 1. CONTRACTOR SHALL FIELD VERIFY ALL PLANS DIMENSIONS PRIOR TO MATERIAL PURCHASE, FABRICATION AND CONSTRUCTION CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SHOULD SITE CONDITIONS DIFFER FROM CONSTRUCTION PLANS



ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PHONE: 407-734-1470 FAX: 407-734-1790

DESIGN STATEMENT

METAL IS .046 THICKNESS OR GREATER, ALLOY IS 6005-T5
ALL TAPCONS SHALL PROVIDE MINIMUM OF 1 1/8" CONCRETE EMBEDMENT DEPTH

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE TO MEET THE REQUIREMENTS OF THE 2023 (8TH EDITION)
FLORIDA BUILDING CODE FOR OPEN AND SEMI-OPEN STRUCTURES AND SHALL WITH STAND ULTIMATE WIND SPEEDS OF 130 MPH
(FOR 3 SECOND GUSTS) NOMINAL SPEED 101.4 MPH UP TO A 15FT ROOF HEIGHT, FACTOR OF 1.0, AND EXPOSURE C, RISK CATEGORY 1.
CONTRACTOR SHALL FIELD VERIFY ALL PLANS DIMENSIONS PRIOR TO MATERIAL PURCHASE, FABRICATION AND CONSTRUCTION
CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SHOULD SITE CONDITIONS DIFFER FROM CONSTRUCTION PLANS

ALUMINUM SCREEN DESIGN BLIND CLIP & CAPRI CLIP DETAILS CHAIR RAIL & KICK PLATE DETAIL MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date diacent to the seal. rinted copies of this onsidered signed and SIDE WALL DETAIL CHAIR RAILS & GIRTS ARE sealed and the signature must be verified on any ATTACHED W/ INTERNAL CLIPS electronic copies Date: 2024.05.01 19:44:01 W/(4) #10 1", CAPRI CLIPPED, 1X2 W/ RECIEVING CHANNEL & (6) #10 1" W/(8) #10 1", OR BLIND SCREWED W/ (3) #10 2" 1X2 TOP PLATE IS ATTACHED TO 2X2 WALL BEAM WITH #10 2" 6" FROM ENDS 24" O.C. KICK PLATE IS ATTACHED TO STRUCTURE WITH #10 1" 6" FROM ENDS 18" O.C. (OPTIONAL) SIDE WALL IS ATTACHED TO FRONT LL WITH #10 2" 6" FROM ENDS 24" O.C 1X2 IS ATTACHED TO H 2/1/4" X 1/4" TAPCONS OF FROM ENDS 24" O.C. SELF MATING UPRIGHT DETAILS UPRIGHT SHALL BE STITCHED SIDE WALL UPRIGHT #10 1" 12" O.C.: #12 1" 18" O.C.: #14 1" 24" O.C. 6" FROM ENDS RECIEVING CHANNEL CLIP DETAILS 1X2 INTERNALLY SCREWED THRU 2X2X1/8" ANGLE TO UPRIGHT W/ (2) #10 X SEE GENERAL NOTES 1-1/2" FASTEN 1X2 TO & DESIGN STANDARD CONCRETE W/3" X 1/4" FOR ADDITIONAL (5" X 1/4" TAPCONS IF THRU PAVERS) INFORMATION (TYP.) (#10 2" IF TO WOOD DECK) SCREW CONCRETE ANCHOR 6" FROM UPRIGHT 24" O.C. (2) #10 1" PER SIDE 1X2 BOTTOM PLATE IS ATTACHED 1X2 BOTTOM PLATE IS ATTACHED TO TO CONCRETE WITH 2-1/4" X 1/4" TAPCONS UPRIGHTS WITH CAPRI CLIP WITH (4) (5" X 1/4" IF THRU PAVERS TO FOOTER) #10 1" OR BLIND SCREWED WITH (2) (#10 2" IF TO WOOD DECK) 6" FROM ENDS 24" O.C. #10 2" PER SIDE MIN 4" SLAB 2500 PSI CONCRETE W/ FIBERMESH

ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PHONE: 407-734-1470 FAX: 407-734-1790

DESIGN STATEMENT

METAL IS .046 THICKNESS OR GREATER, ALLOY IS 6005-T5
ALL TAPCONS SHALL PROVIDE MINIMUM OF 1 1/8" CONCRETE EMBEDMENT DEPTH

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE TO MEET THE REQUIREMENTS OF THE 2023 (8TH EDITION) FLORIDA BUILDING CODE FOR OPEN AND SEMI-OPEN STRUCTURES AND SHALL WITH STAND ULTIMATE WIND SPEEDS OF 130 MPH (FOR 3 SECOND GUSTS) NOMINAL SPEED 101.4 MPH UP TO A 15FT ROOF HEIGHT, FACTOR OF 1.0, AND EXPOSURE C, RISK CATEGORY 1. CONTRACTOR SHALL FIELD VERIFY ALL PLANS DIMENSIONS PRIOR TO MATERIAL PURCHASE, FABRICATION AND CONSTRUCTION CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SHOULD SITE CONDITIONS DIFFER FROM CONSTRUCTION PLANS


ALUMINUM SCREEN DESIGN



Digitally signed by MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Date: 2024.05.01 19:44:26 -04'00'

RISER WALL DETAIL



ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PHONE: 407-734-1470

FAX: 407-734-1790

DESIGN STATEMENT

METAL IS .046 THICKNESS OR GREATER, ALLOY IS 6005-T5
ALL TAPCONS SHALL PROVIDE MINIMUM OF 1 1/8" CONCRETE EMBEDMENT DEPTH


THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE TO MEET THE REQUIREMENTS OF THE 2023 (8TH EDITION) FLORIDA BUILDING CODE FOR OPEN AND SEMI-OPEN STRUCTURES AND SHALL WITH STAND ULTIMATE WIND SPEEDS OF 130 MPH (FOR 3 SECOND GUSTS) NOMINAL SPEED 101.4 MPH UP TO A 15FT ROOF HEIGHT, FACTOR OF 1.0, AND EXPOSURE C, RISK CATEGORY 1. CONTRACTOR SHALL FIELD VERIFY ALL PLANS DIMENSIONS PRIOR TO MATERIAL PURCHASE, FABRICATION AND CONSTRUCTION CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SHOULD SITE CONDITIONS DIFFER FROM CONSTRUCTION PLANS

ALUMINUM SCREEN DESIGN



Digitally signed by MICHAEL THOMPSON Reason: This item has been digitally signed & sealed by Michael A. Thompson on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Date: 2024.05.01 19:44:56 -04'00'



ALUMINUMSCREENDESIGN.COM ALUMINUMSCREENDESIGN @YAHOO.COM

PAVERS W/ 12" X 12" FOOTER & (2) #5 THRU OUT

PHONE: 407-734-1470

FAX: 407-734-1790

CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING:
FIBER MESH, VAPOR & TERMITE PROTECTION (IF REQUIRED)
CONCRETE SHALL BE A MINIMUM OF 3000 PSI
FOR COVERED STRUCTURES, CONTRACTOR SHALL
SECURE COLUMN BASE DIRECTLY TO THICKENED EDGE