



Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 4648479 - ROBBINS

MiTek, Inc.
16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200

Site Information:

Customer Info: JEREMY ROBBINS Project Name: Robbins Res. Model: Custom
Lot/Block: N/A Subdivision: N/A
Address: 4295 SW Birley Ave., N/A
City: Lake City, State: FL

Name Address and License # of Structural Engineer of Record, if there is one, for the building.

Name: License #:
Address:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2023/TPI2014 Design Program: MiTek 20/20 8.8
Wind Code: ASCE 7-22 Wind Speed: 130 mph
Roof Load: 40.0 psf Floor Load: 55.0 psf


This package includes 4 individual, Truss Design Drawings and 0 Additional Drawings.
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this index sheet conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.

No.	Seal#	Truss Name	Date
1	T37401862	F01	5/22/25
2	T37401863	KW1	5/22/25
3	T37401864	T01	5/22/25
4	T37401865	T01G	5/22/25

This item has been digitally signed and sealed by Velez, Joaquin, PE on the date adjacent to the seal.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision based on the parameters
provided by Builders FirstSource-Lake City, FL.

Truss Design Engineer's Name: Velez, Joaquin
My license renewal date for the state of Florida is February 28, 2027.



Joaquin Velez PE No.68182
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd. Chesterfield, MO 63017
Date:



IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

May 22,2025

Job 4648479	Truss F01	Truss Type Floor	Qty 70	Ply 1	ROBBINS	T37401862
----------------	--------------	---------------------	-----------	----------	---------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.830 s Apr 24 2025 MiTek Industries, Inc. Wed May 21 14:52:49 2025 Page 1
ID:YaAmJs5Uy1XzU8UefC4k4szGLk0-j30fFInCgsIQBQEnV3t9k_Onv8CuybSbUiF8lhZEF?i



1-6-0	4-0-0	9-5-4	11-11-4	14-5-4	15-11-4
1-6-0	2-6-0	5-5-4	2-6-0	2-6-0	1-6-0

Plate Offsets (X,Y)-- [5:0-1-8,Edge], [8:0-1-8,Edge], [14:0-1-8,Edge]

LOADING (psf)	SPACING- 1-4-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.38	Vert(LL) -0.12 12-13 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.73	Vert(CT) -0.16 12-13 >999 240		
BCLL 0.0	Rep Stress Incr YES	WB 0.35	Horz(CT) 0.03 9 n/a n/a		
BCDL 5.0	Code FBC2023/TPI2014	Matrix-S		Weight: 83 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 17=0-7-2, 9=0-3-9
Max Grav 17=571(LC 1), 9=571(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-569/0, 8-9=-568/0, 1-2=-573/0, 2-3=-1367/0, 3-4=-1845/0, 4-5=-1845/0, 5-6=-1776/0, 6-7=-1377/0, 7-8=-570/0
BOT CHORD 15-16=0/1073, 14-15=0/1655, 13-14=0/1845, 12-13=0/1845, 11-12=0/1669, 10-11=0/1070
WEBS 8-10=0/735, 1-16=0/739, 7-10=-695/0, 2-16=-695/0, 7-11=0/427, 2-15=0/408, 6-11=-407/0, 3-15=-402/0, 3-14=0/388

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x4 MT20 unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

This item has been digitally signed and sealed by Velez, Joaquin, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd.
Chesterfield, MO 63017
Date:

May 22,2025

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)</p>	<p>16023 Swingley Ridge Rd. Chesterfield, MO 63017 314.434.1200 / MiTek-US.com</p>
--	--

Job 4648479	Truss KW1	Truss Type GABLE	Qty 4	Ply 1	ROBBINS	T37401863
----------------	--------------	---------------------	----------	----------	---------	-----------


Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.830 s Apr 24 2025 MiTek Industries, Inc. Wed May 21 14:52:50 2025 Page 1
ID:YaAmJs5Uy1XzU8UefC4k4szGLk0-BFa1S5OERAQHpapz3nPOGCx0VYjPh7qjM?iq7zEF?h

0-1/8

0-1/8

Scale = 1:26.3



1-6-12	2-10-12	4-2-12	5-6-12	6-10-12	7-11-8	9-0-4	10-4-4	11-8-4	13-0-4	14-4-4	15-11-0
1-6-12	1-4-0	1-4-0	1-4-0	1-4-0	1-0-12	1-0-12	1-4-0	1-4-0	1-4-0	1-4-0	1-6-12

Plate Offsets (X, Y)-- [13:0-1-8,Edge], [15:0-1-8,Edge], [25:0-1-8,Edge]											
LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL 40.0	Plate Grip DOL	1.00	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	244/190	
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999			
BCLL 0.0	Rep Stress Incr	YES	WB 0.02	Horz(CT)	-0.00	15	n/a	n/a			
BCDL 5.0	Code	FBC2023/TPI2014	Matrix-S								Weight: 76 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 25-26,14-15.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 15-11-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 25, 15, 20, 16, 17, 18, 19, 24, 23, 22, 21

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

This item has been digitally signed and sealed by Velez, Joaquin, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek Inc. DBA MiTek USA FL Cert 6634
16023 Swingley Ridge Rd.
Chesterfield, MO 63017
Date:

May 22,2025


<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)</p>	 <p>16023 Swingley Ridge Rd. Chesterfield, MO 63017 314.434.1200 / MiTek-US.com</p>
--	--

Job 4648479	Truss T01	Truss Type MONOPITCH	Qty 23	Ply 1	ROBBINS	T37401864
----------------	--------------	-------------------------	-----------	----------	---------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.830 s Apr 24 2025 MiTek Industries, Inc. Wed May 21 14:52:50 2025 Page 1

ID:YaAmJs5Uy1XzU8UefC4k4szGLk0-BFa1SSOERAQHpapz3nPOGCxv7YeAhxXlJM?iq7zEF?h



Scale = 1:55.7




Plate Offsets (X,Y)--	[3:0-3-0,0-3-0], [6:0-2-12,0-3-0], [11:0-3-0,0-3-0], [14:0-3-0,0-3-0]
-----------------------	---

LOADING (psf)	SPACING-	CSi.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.54	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.25	BC 0.34	Vert(LL) 0.06 14-15 >999 240		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.81	Vert(CT) -0.11 11-12 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.02 17 n/a n/a		
	Code FBC2023/TPI2014			Weight: 160 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-4-7 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 5-6-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x6 SP No.2	

REACTIONS. (size) 16=0-5-8, 13=0-3-8, 17=0-5-8
 Max Horz 16=239(LC 12)
 Max Uplift 16=195(LC 8), 13=715(LC 12), 17=257(LC 8)
 Max Grav 16=533(LC 1), 13=1525(LC 1), 17=527(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-16=-493/305, 2-3=-1018/405, 3-4=-574/183, 4-5=-588/1105, 5-6=-562/184, 6-7=-1051/424, 8-10=-137/354
 BOT CHORD 15-16=-305/202, 14-15=-659/1008, 13-14=-378/534, 12-13=-1090/431, 11-12=-301/550, 10-11=-496/1028
 WEBS 2-15=-356/916, 3-14=-452/275, 4-14=-55/313, 4-13=-1603/802, 5-13=-853/460, 5-12=-722/1616, 6-12=-453/280, 6-11=-192/481, 7-10=-847/404, 8-17=-547/316

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -0-4-0 to 2-10-6, Zone1 2-10-6 to 32-4-0 zone; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 16, 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 195 lb uplift at joint 16, 715 lb uplift at joint 13 and 257 lb uplift at joint 17.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 13.

This item has been digitally signed and sealed by Velez, Joaquin, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
 MiTek Inc. DBA MiTek USA FL Cert 6634
 16023 Swingley Ridge Rd.
 Chesterfield, MO 63017
 Date:

May 22, 2025


<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)</p>	<p>16023 Swingley Ridge Rd. Chesterfield, MO 63017 314.434.1200 / MiTek-US.com</p>
--	--

Job 4648479	Truss T01G	Truss Type GABLE	Qty 2	Ply 1	ROBBINS	T37401865
----------------	---------------	---------------------	----------	----------	---------	-----------

Builders FirstSource (Lake City,FL), Lake City, FL - 32055,

8.830 s Apr 24 2025 MiTek Industries, Inc. Wed May 21 14:52:51 2025 Page 1

ID:YaAmJs5Uy1XzU8UefC4k4szGLk0-fR8PgROsCUY8RkO9cUwdpPU8ey1JQZLuy0kFMZzEF?g



Scale = 1:55.9




Plate Offsets (X, Y)--	[3:0-3-0,0-3-0], [6:0-2-12,0-3-0], [12:0-3-0,0-3-0], [19:0-3-0,0-3-0], [28:0-1-9,0-1-0], [40:0-1-8,0-1-0]
------------------------	---

LOADING (psf)	SPACING-	CS.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.25	BC 0.09	Vert(LL) -0.01 17-18 >999 240		
BCLL 0.0 *	Lumber DOL 1.25	WB 0.07	Vert(CT) -0.01 17-18 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) -0.01 10 n/a n/a		
	Code FBC2023/TPI2014			Weight: 181 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3 *Except*	9-11-12 oc bracing: 23-24,22-23
2-24,8-10: 2x6 SP No.2	6-0-0 oc bracing: 21-22,14-15.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 31-6-8.
 (lb) - Max Horz 24=245(LC 9)
 Max Uplift All uplift 100 lb or less at joint(s) 24, 21 except 22=235(LC 12), 19=222(LC 12), 17=195(LC 12), 15=213(LC 12), 12=234(LC 12), 10=112(LC 12)
 Max Grav All reactions 250 lb or less at joint(s) 24, 24, 10, 10, 23, 20, 18, 16, 14, 13, 11 except 22=415(LC 1), 19=343(LC 1), 17=364(LC 1), 15=373(LC 1), 12=370(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 BOT CHORD 23-24=-353/237, 22-23=-354/238
 WEBS 3-22=-324/220, 4-19=-314/214, 5-17=-292/200, 6-15=-320/220, 7-12=-349/237

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-22; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=20ft; Cat. II; Exp C; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Zone3 -0-4-0 to 2-10-6, Zone1 2-10-6 to 32-4-0 zone; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 17, 15, 12, 10, 18, 16, 14, 13, 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 24, 21 except (jt=lb) 22=235, 19=222, 17=195, 15=213, 12=234, 10=112.

This item has been digitally signed and sealed by Velez, Joaquin, PE on the date indicated here. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.


Joaquin Velez PE No.68182
 MiTek Inc. DBA MiTek USA FL Cert 6634
 16023 Swingley Ridge Rd.
 Chesterfield, MO 63017
 Date:

May 22,2025


<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)</p>	 <p>16023 Swingley Ridge Rd. Chesterfield, MO 63017 314.434.1200 / MiTek-US.com</p>
--	--

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITtek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on Lumber values established by others.

© 2023 MITtek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek®

MITtek Engineering Reference Sheet: Mill-7473 rev. 1/2/2023