



New exit door with sidewalk from door to street - without handrails

New ADA concrete entrance with steps & handrails.

WALL LEGEND

- EXISTING EXTERIOR AND INTERIOR STUD FRAMED WALL TO REMAIN
- NEW INTERIOR 5-5/8" 20 GA. MTL. STUD FRAMG. (UNLESS NOTED OTHERWISE AT RESTROOM CHASE WALLS) AT 16" O.C. W/ FULL BATT INSUL. AND ONE LAYER OF 5/8" TYPE X GYP. BD. ON EA. SIDE (MOISTURE RESISTANT GYP. BD. ON ANY RESTROOM WALLS) - NEW STUD WALL HT. TO BE 12'-0" UNLESS NOTED OTHERWISE
- EXISTING INTERIOR 8" CMU WALL TO REMAIN

DOOR LEGEND

- EXISTING DOOR TO REMAIN
- NEW DOOR, FRAME AND DOOR HARDWARE AS SCHEDULED

RENOVATION NOTES

- NEW EXTERIOR ALUM.-FRAMED STOREFRONT FRAMG., DOOR, DOOR HARDWARE AND GLAZG. SYS.
- NEW INTERIOR ALUM.-FRAMED STOREFRONT DOOR, DOOR HARDWARE AND GLAZG. SYS.
- NEW INTERIOR ALUM.-FRAMED VIEW WINDOW AND GLAZG.
- NEW PLUMBG. FIXTURES AND ACCESSORIES - COORD. W/ PLUMBG.
- NEW REPLACEMENT PLUMBG. FIXTURES (WATER CLOSETS, LAVATORIES AND URINALS) - PROVIDED BY OWNER AND INSTALLED BY CONTRACTOR
- NEW ARCHITECTURAL CASEWORK W/ SINKS WHERE INDICATED - COORD. W/ PLUMBG.
- OWNER FURNISHED AND CONTRACTOR INSTALLED REFRIGERATOR - COORD. W/ PLUMBG. AND ELEC. FOR ROUGH-IN REQUIREMENTS
- NEW MANUAL ROLLER SHADES
- NEW EXTERIOR CONC. ENTRY RAMP, SIDEWALK AND RAILING
- NEW EXTERIOR CONC. SLAB ON GRADE SIDEWALK
- COORD. MEPPF DOCUMENTS FOR ADDITIONAL SCOPE OF WORK - TYP. NOTE THROUGHOUT
- COORD. W/ FINISH SCHEDULE ON SHEET A-4 - TYP. NOTE THROUGHOUT

#	Date	Note