

SCOPE OF WORK

PERMIT #: _____

JOB SITE ADDRESS: 215 SW HOME DEPOT DR LAKE CITY, FL 32025

BUILDING (INTERIOR)

1. New maintenance room slab with a slope that directs water towards a newly installed interior catch basin
- 2.
- 3.

BUILDING (EXTERIOR)

A fence-enclosed materials yard will be designed and constructed adjacent to the existing building. The yard will have an area of 800 sqft and will be built on an unreinforced concrete slab-on-grade construction.

A chain-linked fence system with gates will be implemented. The system will be installed on an isolated structural foundation system.

MECHANICAL

Adding (2) exhaust fans, downblast type on roof. EF-T1 will be intermittent. It will serve the tool washdown hood and can be toggled on or off via a wall switch. EF-T2 will be continuous for ventilation requirements, and will have a high

Adding (4) wall grilles, (2) high and (2) low for transfer air ventilation requirements.

Adding a fuel storage cabinet with (2) insulated vents, (1) high and (1) low that penetrate exterior wall for ventilation of the fuel gases and fumes.

ELECTRICAL

1. New electric for exterior charging stations for large format rental equipment.

New Lighting and electrical receptacles for new addition areas.

New electric panels for addition are tied into existing electric service. No new electric service associated with scope of work.

PLUMBING

Adding a catch basin with sediment bucket in the washdown area for tools equipment to be cleaned. An exterior interceptor will be downstream to catch any oils.

New 1" domestic CW line into existing 1" CW line nearby with backflow preventer serving expansion.

Adding a compressed air system with air compressor, hose reel, quick – connects for pneumatic tools.

GAS

1. N/A
2. N/A

ROOF

1. Two new exhaust fans onto the existing roof framing system and additional reinforcing at the proposed opening locations.