GENERAL NOTES

1. DESIGN IS FOR MAXIMUM 30'-0" WIDE X 20'-0" EAVE HEIGHT FULLY ENCLOSED STRUCTURES.

2. APPLICABLE CODES, REGULATIONS, & STANDARDS: 2023 FLORIDA BUILDING CODE (8TH EDITION)

- B. 2024 INTERNATIONAL BUILDING CODE
- C. ASCE 7-22: MINIMUM DESIGN LOADS ON BUILDINGS AND OTHER STRUCTURES
- D. AISC STEEL CONSTRUCTION MANUAL (15TH EDITION)
 E. ACI 318-19: BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
- F. TMS 402-16: BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES
- G AWS D1 1: STRUCTURAL WELDING
- 2. RISK CATEGORY: I
- 3. EXPOSURE CATEGORY: C

LOW ULTIMATE WIND SPEED 105 TO 150 MPH (NOMINAL WIND SPEED 81 TO 116 MPH): MAXIMUM RAFTER/POST AND END POST SPACING = 5.0 FEET.

HIGH ULTIMATE WIND SPEED 151 TO 180 MPH (NOMINAL WIND SPEED 117 TO 139 MPH): MAXIMUM RAFTER/POST AND END POST SPACING = 4.0 FEET.

- 4. DEAD LOAD = 10 PSF
- 5. LIVE LOAD = 10 PSF
- 6 SPECIFICATIONS APPLICABLE TO 29 GALIGE METAL PANELS FASTENED DIRECTLY TO 2 1/2" x 2 1/2" 14 GAUGE TUBE STEEL (TS) FRAMING MEMBERS FOR VERTICAL PANELS, 29 GAUGE METAL PANELS SHALL BE FASTENED TO 18 GAUGE HAT CHANNELS (UNLESS OTHERWISE NOTED).
- 7. OPTIONAL BASE RAIL ANCHORAGE MAY BE USED FOR LOW AND MUST BE USED FOR HIGH WIND
- 8. FASTENERS CONSIST OF #12-14 x 3/4" SELF DRILLING FASTENER (SDF), USE CONTROL SEAL WASHER WITH EXTERIOR FASTENERS SPECIFICATIONS APPLICABLE ONLY FOR MEAN ROOF HEIGHT OF 20 FEET OR LESS, AND ROOF SLOPES OF 14° (3:12 PITCH) OR LESS SPACING REQUIREMENTS FOR OTHER ROOF
- 9. AVERAGE FASTENER SPACING ON-CENTERS ALONG RAFTERS OR PURLINS, AND POSTS, INTERIOR = 9" OR END = 6", (MAX.).
- 10. WIND FORCES GOVERN OVER SEISMIC FORCES. SEISMIC PARAMETERS ANALYZED ARE:

SOIL SITE CLASS = D RISK CATEGORY I/II/III R = 3.25

Sds = 0.087 g V = CsW


Sdi = 0.084 g

- 11. GROUND ANCHORS SHALL BE INSTALLED THROUGH BASE RAIL WITHIN 6" OF EACH RAFTER COLUMN ALONG SIDES.
- 12 GROLIND ANCHOR (SOIL NAILS) CONSIST OF #5 REBAR W/ WELDED NUT X 30" LONG IN SUITABLE SOIL CONDITIONS MAY BE USED FOR LOW (\$ 108 MPH NOMINAL) WIND SPEEDS ONLY. OPTIONAL ANCHORAGE MAY BE USED IN SUITABLE SOILS AND MUST BE USE IN UNSUITABLE SOILS AS NOTED.
- 13. MIN. LAP REQUIREMENT FOR REBAR IN FOOTER IS 25".
- 14. SOIL TO BE COMPACTED TO 95% OF ITS MAXIMUM DRY DENSITY, AT OPTIMUM MOISTURE CONTENT, IN ACCORDANCE WITH ASTM D1557-93
- 15. PRIOR TO PLACING CONCRETE, TREAT THE ENTIRE SUBSURFACE AREA FOR TERMITES IN COMPLIANCE
- 16. A LANDING OF MIN. 36" WIDTH IN THE DIRECTION OF TRAVEL SHALL BE PROVIDED AT THE EXTERIOR DOORS. SLOPE OF LANDING NOT TO EXCEED 1/4"-1'. LANDING LEVEL NOT TO BE LOWER THAN 1-1/2" (FOR EGRESS DOORS) & 7-3/4" (FOR OTHER EXTERIOR DOORS) BELOW THE TOP OF THRESHOLD

DRAWING INDEX

PAGE NO.	DESCRIPTION
1	NOTES AND SPECIFICATIONS
2	BOX EAVE FRAME RAFTER ENCLOSED BUILDING
3	BOW EAVE FRAME RAFTER ENCLOSED BUILDING/WIND PRESSURES
4	BASE RAIL AND FOUNDATION ANCHORAGE
5	BOX/BOW EAVE VERTICAL ROOF/SIDING OPTION
6	BOX/BOW EAVE RAFTER LEAN-TO OPTIONS
7	BOX EAVE RAFTER END WALL, SIDE WALL AND OPENING FRAMING
8	VENT AND CMU STEM WALL DETAIL
9	OPTIONAL CONCRETE STRIP FOOTING

ENCLOSED METAL BUILDING DESIGN MAXIMUM 30'-0" WIDE X 20'-0" EAVE HEIGHT **BOX/BOW EAVE FRAME**



Plans


Reviewed for Code


Compliance

are of Florid



BOX EAVE FRAME RAFTER ENCLOSED BUILDING





TYPICAL SIDE ELEVATION - HORIZONTAL ROOF

BOW FRAME RAFTER ENCLOSEDBUILDING

PRODUCT CATEGORY SUB CATEGORY		MANUFACTURER	APPROVAL No. & DATE	
STRUCTURAL COMPONENTS	ROOF DECK	CAPITAL METAL SUPPLY, INC. 29 GA. CAPITAL RIB ROOF PANEL	FL20147.2-R3 12/13/2023	
STRUCTURAL COMPONENTS	STRUCTURAL WALL	CAPITAL METAL SUPPLY, INC. 29 GA. CAPITAL RIB WALL PANEL	FL20148.2-R3 12/13/2023	
EXTERIOR DOORS	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC. SERIES 3652	FL14425.1-R6 12/15/21	
EXTERIOR DOORS	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC. SERIES 750	FL21450.10-R11 10/17/23	
EXTERIOR DOORS	ROLL-UP	JANUS INTERNATIONAL GROUP, LLC. SERIES 3100	FL12765.4-R6 10/12/20	
EXTERIOR DOORS	SWINGING	ELIXIR DOOR AND METAL COMPANY SERIES 407	FL17996.5-R3 12/26/23	
WINDOWS	SINGLE HUNG	KINRO, INC 9750 SH	FL993.5-R19 11/01/23	
WINDOWS	VERTICAL SLIDING	KINRO, INC 18000-R VS	FL993.8-R19 11/01/23	

DIGITAL CERTIFICATION NOTES: 1. THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SHALL REMAIN IN DIGITAL FORMAT, SHALL BE VERIFIED BY ELECTRONIC MEANS & PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED. 2. THIS DOCUMENT HAS BEEN CREATED BY FLORIDA ENGINEERING LLC FOR TUBULAR BUILDING SYSTEMS ONLY IT SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT THE WRITTEN CONSENT OF FLORIDA ENGINEERING LLC AND TUBULAR BUILDING SYSTEMS. 3. ALTERATIONS, ADDITIONS OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE FLORIDA ENGINEERING LLC'S CERTIFICATION. 4. THESE PLANS ARE GENERIC AND DO NOT PROVIDE INFORMATION FOR A SITE-SPECIFIC PROJECT WHERE THE SITE CONDITIONS DEVIATE FROM WHAT HAS BEEN CALLED OUT ON THESE PLANS. 5. CONTRACTOR MUST NOT DEVIATE FROM THE CONDITIONS DETAILED ON THESE PLANS 6. CONSTRUCTION SAFETY AT THE SITE IS THE CONTRACTOR'S RESPONSIBILITY

This item has been digitally signed and seaded by Kindrand E. Walker, P. E. on the data adjacent to the seal. Printed copies of this document are not considered signed and sealed and he signature must be verified on any electronic copies.

Digitally signed by Richard E Walker 2024 01 16 10:25:52-05'00

CA CERT. #30782

2322771-30-

ġ

PROJECT

1 TAMIAMI TRAIL, UNIT 101 T CHARLOTTE, FLORIDA 33952 (941) 391-5980 FLEng.com Orders@FLEng.com LLC ENGINEERING

FLORIDA **PORT** 161







TUBULAR BUILDING SYSTEMS 631 SE INDUSTRIAL CIRCLE, LAKE CITY, FL 32025


30' WIDE X 20' HIGH ENCLOSED STRUCTURE PROJECT DESCRIPTION

_			
DESIGN DATE:	12/14/20	023	
REVISION 1:	DATE	PAGE :	
REVISION 2:	DATE	1	
SCALE:	NTS	ı	






BASE RAIL ANCHORAGE OPTIONS FOR LOW AND HIGH WIND SPEED




WIND SPEED




CONCRETE MONOLITHIC SLAB BASE RAIL ANCHORAGE


SCALE: NTS



3A2



ASPHALT BASE ANCHORAGE (HP 9 BARRED DRIVE ANCHOR) 3C



TYPICAL ANCHOR DETAIL WHEN BASE RAIL IS NEAR EDGE OF CONCRETE 3D SCALE: NTS

Digitally signed by Richard E Walker This item has been digit and sealed by Richard P.E. on the date adjace Printed copies of this drot considered signed and the signature must any electronic copies. Date: 2024.01.16 10:25:56-05'00'

FLORIDA ENGINEERING LLC 101 33952 TAMIAMI TRAIL, UNIT T CHARLOTTE, FLORIDA 3: (941) 391-5980 FLEng.com Orders@FLEng.com

CA CERT. #30782

2322771-30-E

PROJECT NO.

161 PORT



TUBULAR BUILDING SYSTEMS 631 SE INDUSTRIAL CIRCLE, LAKE CITY, FL 32025 JECT DESCRIPTION

30' WIDE X 20' HIGH ENCLOSED STRUCTURE DESIGN DATE: 12/14/2023

REVISION 1: DATE PAGE DATE REVISION 2: SCALE: NTS

GENERAL NOTES

CONCRETE

- 1. CONCRETE SHALL HAVE A MINIMUM SPECIFIED COMPRESSIVE STRENGTH OF 3000 PSI AT
- 2. PRIOR TO PLACING CONCRETE, TREAT THE ENTIRE SUBSURFACE AREA FOR TERMITES IN COMPLIANCE WITH THE FBC.

 3. MINIMUM SOIL BEARING CAPACITY OF COMPACTED GRADE= 2000 PSF

COVERAGE OF THE REINFORCED STEEL:

FOR FOUNDATIONS, MINIMUM CONCRETE COVER OVER REINFORCING BARS SHALL BE PER ACI-318: 3 INCHES WHERE THE CONCRETE IS POURED AGAINST AND TEMPORARY IN CONTACT WITH THE EARTH OR UNPROTECTED FROM THE EARTH OR WEATHER, OTHERWISE

REINFORCING STEEL:


THE TURNDOWN REINFORCING STEEL SHALL BE ASTM AG15 GRADE 60. THE SLAB REINFORCEMENT SHALL BE WELDED WIRE FABRIC MEETING ASTM A185 OR FIBERGLASS


REINFORCEMENT MAY BE BENT IN THE FIELD OR SHOP AS LONG AS:

- 1. IT IS BENT COLD;
- REINFORCEMENT PARTIALLY EMBEDDED IN CONCRETE SHALL NOT BE FIELD BENT;
 THE DIAMETER OF THE BEND, MEASURED ON THE INSIDE OF THE BAR, IS NOT LESS THAN SIX-BAR DIAMETERS
- 4. MINIMUM REQUIRED LAP LENGTH SHALL NOT BE LESS THAN 57-BAR DIAMETERS.

HELIX ANCHOR NOTES

- 1 FOR VERY DENSE AND/OR CEMENTED SANDS COARSE GRAVEL AND COBBLES, CALICHE, PRELOADED SILTS AND CLAYS USE MINIMUM (2) 4" HELICES WITH MINIMUM 30 INCH EMBEDMENT
- 2. FOR CORAL USE MINIMUM (2) 4" HELICES WITH MINIMUM 30 INCH EMBEDMENT
- 3. FOR MEDIUM DENSE COARSE SANDS, SANDY GRAVELS, VERY STIFF SILTS AND CLAYS USE MINIMUM (2) 4" HELICES WITH MINIMUM 30 INCH EMBEDMENT
- 4. FOR LOOSE TO MEDIUM DENSE COARSE SANDS, FIRM TO STIFF CLAYS AND SILTS ALLUVIAL FILL USE MINIMUM (2) 6" HELICES WITH MINIMUM 50 INCH EMBEDMENT
- 5. FOR VERY LOSE TO MEDIUM DENSE SANDS, FIRM TO STIFFER CLAYS AND SILTS, ALLUVIAL FILL USE MINIMUM (2) 8" HELICES WITH MINIMUM 60 INCH EMBEDMENT.





This item has been digitally signed and seated by Richard E. Walker, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies. Digitally Digitally signed by signed

4161 TAMIAMI TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com FLORIDA ENGINEERING LLC

CA CERT. #30782

2322771-30-E

PROJECT NO.






TUBULAR BUILDING SYSTEMS 631 SE INDUSTRIAL CIRCLE, LAKE CITY, FL 32025 DESCRIPTION CONTRACTOR:

PROJECT DESCRIPTION:	30' WIDE X 20' HIGH	ENCLOSED STRUCTURE
12/1	14/20	23
DATE		РΔ

٢	ľ	ш.	
DESIGN DATE:		12/14/20	23
REVISION 1:	DA	TE	PAGE :
REVISION 2:	DA	TE	6
SCALE:	N.	rs	U



CA CERT. #30782

2322771-30-E

PROJECT NO.

This item has been digitally signed and seated by Richard E. Walker. P. E. on the date adjacent to the seal. Printed topies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

4161 TAMIAMI TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com FLORIDA ENGINEERING LLC






TUBULAR BUILDING SYSTEMS 631 SE INDUSTRIAL CIRCLE, LAKE CITY, FL 32025

30' WIDE X 20' HIGH ENCLOSED STRUCTURE JECT DESCRIPTION

DESIGN DATE: 12/14/2023


DATE REVISION 1: PAGE REVISION 2: DATE 8 SCALE: NTS




TYPICAL FLOOD VENT DETAIL

NOTES:

- 1. MINIMUM VENT SPACE REQUIRED = 1 SQ. IN. OF OPEN VENT AREA PER SQ. FT. OF BUILDING AREA.
- 2. PROVIDE A MINIMUM OF TWO OPENINGS ON DIFFERENT SIDES OF EACH ENCLOSED BUILDING.
- 3. APPLY A 1.3 FACTOR WHEN CALCULATING TOTAL OPEN AREA WHEN USING 1/2"-18GA S OR F EXPANDED METAL.
- 4. TOTAL OPEN AREA OF VENT = L X H (MIN. 12").
- 5. FLOOD VENT DETAIL COMPLIES WITH FEMA/NFIP.
- 6. PREFABRICATED FLOOD VENTS MEETING THE REQUIREMENTS OF FEMA/NFIP MAY BE USED.



STAND-ALONE CONCRETE MASONRY UNIT (CMU) FOUNDATION STEM WALL DETAIL



SECTION X-X


TS RAFTER COLUMN

CONCRETE STRIP
FOOTING

COMPACT
SUBGRADE

(4) #4 REBAR CONT. T & B

MIN. COVER = 3"



OPTIONAL CONCRETE STRIP FOOTING

This fem has been digitally signed and seafled by Richard E. Walker.
P.E. on the date adjacent to the seal.
Printed copies of this document are not considered signed and sealed and the signature must be verified on and the signature must be verified on any electronic copies.

Marker.
M

CA CERT. #30782

2322771-30-E

PROJECT NO.

FLORIDA ENGINEERING LLC
4161 TAMIAMI TRAIL, UNIT 101
PORT CHARLOTTE, FLORIDA 33952
(941) 391-5980
FLEng.com
Orders@FLEng.com



TUBULAR BUILDING SYSTEMS
631 SE INDUSTRIAL CIRCLE,
LAKE CITY, FL 32025

30' WIDE X 20' HIGH
ENCLOSED STRUCTURE

DESIGN DATE: 12/14/2023

REVISION 1: DATE PAGE REVISION 2: DATE SCALE: NTS