

Scope of Work Lake City Office Renovation

- Demo of non-load bearing walls
- Existing air duct supplies to be dropped down to 9' ceilings
- Acoustical ceilings to be installed
- Box lights to be installed
- Non-load bearing walls to be installed



General notes:

1. Remove and clean all diffusers and supply register's prior to install in the new ceiling tiles.
2. Remove existing chandeliers and lighting fixtures, safe off and terminate wiring not used. Re-use existing wiring for new fixt's all electrical work to be performed by a licensed electrical contractor.
3. Modify existing ductwork as required to make a complete system.
4. Modify existing plumbing lines and fixtures to relocate bathroom fixtures.