

TYPICAL WALL SECTION
SCALE: 1/4" = 1'-0"



FRONT ELEVATION
SCALE: 1/4" = 1'-0"



REAR ELEVATION
SCALE: 1/4" = 1'-0"

REVISIONS SCHEDULE	
MAY 21st, 2019	ORIGINAL DRAWINGS
JUNE 8th, 2019	PERMIT SET

LOT 49, EMERALD COVE
238 SW FIELDSTONE CT, LAKE CITY, 32024
1819 DANIEL STREET LAKE CITY, FL 32009
IC CONSTRUCTION, LLC.



RIDGEPOINT DESIGN
1819 DANIEL STREET, LAKE CITY, FLORIDA 32009
E: RIDGEPOINTDESIGN@GMAIL.COM

SHEET NUMBER
A.1
OF 4 SHEETS



RIGHT ELEVATION
SCALE: 1/4" = 1'-0"




LEFT ELEVATION
SCALE: 1/4" = 1'-0"

REVISIONS SCHEDULE	
MAY 21st, 2019	ORIGINAL DRAWINGS
JUNE 0th, 2019	PERMIT SET

LOT 49, EMERALD COVE
299 SW FIELDSTONE CT, LAKE CITY, 32024
IC CONSTRUCTION, LLC
899 BUNAL STREET, LAKE CITY, FL 32065

RIDGEPOINT DESIGN
315 W. WHITE OAK STREET, LAKE CITY, FLORIDA 32065
P: 386-288-1888
E: RIDGEPOINTDESIGN@GMAIL.COM

SHEET NUMBER
A.2
OF 4 SHEETS



DIMENSIONED FLOOR PLAN
SCALE: 1/8" = 1'-0"

Garage fire separations shall comply with the following:

1. The private garage shall be separated from the dwelling unit and its attic area by means of a minimum 1/2-inch (12.7 mm) gypsum board applied to the garage side. Garages beneath habitable rooms shall be separated from all habitable rooms above by not less than 5/8-inch Type X gypsum board or equivalent. Door openings between a private garage and the dwelling unit shall be equipped with either solid wood doors, or solid or honeycomb core steel doors not less than 1 3/8 inches (34.9 mm) thick, or doors in compliance with Section 715.3.3. Openings from a private garage directly into a room used for sleeping purposes shall not be permitted.
2. Ducts in a private garage and ducts penetrating the walls or ceilings separating the dwelling unit from the garage shall be constructed of a minimum 0.019-inch (0.48 mm) sheet steel and shall have no openings into the garage.
3. A separation is not required between a Group R-3 and U carport provided the carport is entirely open on two or more sides and there are not enclosed areas above.
4. When installing an attic access and/or pull-down stair unit in the garage, devise shall have a minimum 20 min. fire rating.

AREA SUMMARY	
LIVING	1,854 S.F.
GARAGE	500 S.F.
FRONT PORCH	93 S.F.
REAR PORCH	365 S.F.
TOTAL LIVING	2,812 S.F.

REVISIONS SCHEDULE	
MAY 21st, 2018	ORIGINAL DRAWINGS
JUNE 06th, 2019	PERMIT SET

LOT 49, EMERALD COVE
209 SW FELDSTONE CT, LAKE CITY, 33224
I.C. CONSTRUCTION, LLC.
818 W. DUAL STREET, LAKE CITY, FL 33209


RIDGEPOINT DESIGN
1400 W. DUAL STREET, LAKE CITY, FL 33209
P: 386-288-1188
E: RIDGEPOINTDESIGN@GMAIL.COM

SHEET NUMBER
A.3
OF 4 SHEETS

ELECTRICAL LEGEND		
ELECTRICAL	COUNT	SYMBOL
CEILING FAN	4	
CAN LIGHT 6inch	27	
CHANDELIER	1	
FLUORESCENT LIGHT 1x4	3	
PENDANT LIGHT	3	
EXTERIOR SCENCE	5	
MOTION SECURITY LIGHT	4	
ELECTRIC METER	1	
ELECTRIC PANEL	1	
CABLE TV OUTLET	5	
EXHAUST FAN	2	
OUTLET	29	
OUTLET 220v	4	
OUTLET GFI	12	
OUTLET WP	5	
SMOKE DETECTOR	5	
STANDARD LIGHT	7	
SWITCH	29	
SWITCH 3 WAY	16	
VANITY BAR LIGHT - SMALL	3	

ELECTRICAL PLAN NOTES:

INSTALLATION SHALL BE PER 2017 NATL. ELECTRIC CODE.
 WIRE ALL APPLIANCES, HVAC UNITS AND OTHER EQUIPMENT PER MANUF. SPECIFICATIONS
 CONSULT WITH THE OWNER FOR THE NUMBER OF SEPARATE TELEPHONE LINES TO BE INSTALLED
 ALL SMOKE DETECTORS SHALL BE 120V W/ BATTERY BACKUP OF THE PHOTOELECTRIC TYPE, AND SHALL BE INTERLOCKED TOGETHER. INSTALL INSIDE AND NEAR ALL BEDROOMS
 TELEPHONE, TELEVISION AND OTHER LOW VOLTAGE DEVICES OR OUTLETS SHALL BE AS PER THE OWNERS DIRECTIONS, & IN ACCORDANCE W/ APPLICABLE SECTIONS OF RECLATEST EDITION.
 ALL RECEPTICALS, NOT OTHERWISE NOTED, SHALL BE ARC FAULT INTERRUPTER TYPE, EXCEPT DEDICATED OUTLETS
 ALL RECEPTICALS IN WET AREAS SHALL BE GROUND FAULT INTERRUPTER TYPE (GFI)
 ALL EXTERIOR RECEPTICALS SHALL BE WEATHERPROOF GROUND FAULT INTERRUPTER TYPE (WP/GFI)
 NOTE:
 ELECTRICAL CONTR SHALL PREPARE "AS-BUILT" SHOP DRAWS INDICATING ALL ELECTRICAL WORK, INCLUDING ANY CHANGES TO THE ELEC. PLAN. ADDNS TO THE ELEC. PLAN, RISER DIAGRAM, AS-BUILT PANEL SCHEDULE W/ ALL CKTS IDENTIFIED W/ CKT NO., DESCRIPTION & BREAK, SERVICE ENT. & ALL UNDERGROUND WIRE LOCATIONS/ROUTING / DEPTH. RISER DIA. SHALL INCLUDE WIRE SIZES/TYPES & EQUIPMENT TYPE W/ RATINGS & LOADS.
 CONTRACTOR SHALL PROVIDE 1 COPY OF AS-BUILT DWGS TO OWNER & 1 COPY TO THE PERMIT ISSUING AUTHORITY



ELECTRICAL FLOOR PLAN
 SCALE: 1/8" = 1'-0"

REVISIONS SCHEDULE	
MAY 21st, 2019	ORIGINAL DRAWINGS
JUNE 6th, 2019	PERMIT SET



LOT 49, EMERALD COVE
 239 SW FIELDSTONE CT. LAKE CITY, 32024
 I.C. CONSTRUCTION, LLC
 218 W. WALNUT STREET, LAKE CITY, FL 32025

RIDGEPOINT DESIGN
 BRUNSWICK COUNTY, FLORIDA 32009
 P: 386-288-1188
 E: RIDGEPOINTDESIGN@GMAIL.COM

SHEET NUMBER
A.4
 OF 4 SHEETS

CONCRETE / MASONRY / METALS GENERAL NOTES:

- DESIGN SOIL BEARING PRESSURE: 1500 PSF.
- EXPANSIVE SOILS: WHERE DIRECTED BY THE SOILS ENGINEER, SOIL AUGMENTATION PER THE SOILS ENGINEER'S SPECIFICATIONS SHALL BE IMPLEMENTED PRIOR TO PLACING ANY FOUNDATIONS - TESTS AS SPECIFIED SHALL BE PERFORMED TO DETERMINE THE SUITABILITY OF THE SUB-GRADE TO SUPPORT THE DESIGN LOADS.
- CLEAN SAND FILL OVER STRIPPED AND COMPACTED EXISTING SO. SHALL BE PLACED IN 12" LIFTS, BOTH SUB-SOIL AND FILL. COMPACTION SHALL BE NOT LESS THAN 95% AS MEASURED BY A MODIFIED PROCTOR TEST AT THE RATE OF ONE TEST FOR EACH 100 SF OF BUILDING FOOT AREA OR FRACTION THEREOF, FOR EACH 12" LIFT.
- REINFORCING STEEL SHALL BE GRADE 60 AND MEET THE REQUIREMENTS OF ASTM A618. ALL BENDS SHALL BE MADE COLD.
- WELDED WIRE FISH SLAB REINFORCING SHALL MEET THE REQUIREMENTS OF ASTM A618 - MIN. YIELD STRESS = 65 KSI.
- CONCRETE SHALL BE STANDARD MIX #2 + 3000 PSI FOR ALL FTGS. SLABS, COLUMNS AND BEAMS OR SHALL BE STANDARD PUMP MIX #2 + 3000 PSI. STRENGTH SHALL BE ATTAINED WITHIN 28 DAYS OF PLACEMENT. FINISH, PLACING AND FINISHING SHALL BE AS PER ACI STANDARDS.
- CONCRETE BLOCK SHALL BE AS PER MANUFACTURER'S PRODUCT GUIDE FOR ASTM C-90 REQUIREMENTS WITH MEDIUM SURFACE FINISH - F_h = 1500 PSI.
- MORTAR SHALL BE TYPE "M" OR "N" FOR ALL MASONRY UNITS.
- STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 STANDARDS FOR STRENGTH. BOLTS SHALL BE ASTM A307 / GRADE 1 OR A325, AS PER PLAN REQUIREMENTS.
- WELDS SHALL BE AS PER "AMERICAN WELDING SOCIETY" STANDARDS FOR STRUCTURAL STEEL APPLICATIONS.
- 2x4 P/T WOOD SILL, CONT. ALL AROUND, W/ 5/8" A.B. W/ 3" SQ. X 1/4" PLATE BARRIERS WITHIN 2-1/2" FROM EACH CORNER, EA. WAY, + WITHIN 8-2" FROM ALL WALL OPENINGS / DOORS / 1/2" A.B. W/ 2" SQ. BARRIERS ALONG EACH RUN + 48" O.C. MAX. + ALL ANCHOR BOLTS SHALL HAVE A MINIMUM OF 6" EMBEDMENT INTO THE CONCRETE.




* NOTE: ALL INTERIOR BEARING WALLS TO USE THIS FOOTING *

NOTE: THE DESIGN WIND SPEED FOR THIS PROJECT IS 130 MPH PER RES 1609 AND LOCAL JURISDICTION REQUIREMENTS.

NOTE: ACCED FILL SHALL BE APPLIED IN 6" LIFTS - EA. LIFT SHALL BE COMPACTED TO 95% DRY COMPACTION PER THE "MODIFIED PROCTOR" METHOD.

NOTE: PLUMBING CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL PLUMBING WORK INCLUDING ALL PLUMBING LINE LOCATIONS AND RISER DIAGRAM - CONTRACTOR SHALL PROVIDE 1 COPY OF AS-BUILT DRAW TO OWNER AND 1 COPY TO THE PERMIT ISSUING AUTHORITY.

NOTE: H.V.A.C. CONTRACTOR SHALL PREPARE "AS-BUILT" SHOP DRAWINGS INDICATING ALL H.V.A.C. WORK, INCLUDING ALL DUCTWORK, LOG, SIZE, LINE, EQUIPMENT SIZE + BALANCING REPORT - CONTRACTOR SHALL PROVIDE 1 COPY OF AS-BUILT DRAW TO OWNER + 1 COPY TO THE PERMIT ISSUING AUTHORITY.




REVISIONS
JUNE 06, 2019

LOT 49, EMERALD COVE
239 SW FLESTONE CT, LAKE CITY, 32024
IC CONSTRUCTION, LLC
815 W Duval Street, Lake City, FL 32050

IC
NICHOLAS
GESLER
ARCHITECT
1000 W. Duval Street, Suite 100
LAKE CITY, FL 32050
PHONE: 386-381-8001

SHEET NUMBER
S.1
OF 4 SHEETS





MULTIPLE GANG LAM. DETAIL
NOT TO SCALE



PLYWOOD FLITCH BEAM DETAIL
NOT TO SCALE

B/U Beam DETAILS
SCALE: NONE

B

NOTE:
THE DESIGN AND SPEED FOR THIS PROJECT IS 30 MPH PER 2015 IRC AND LOCAL JURISDICTION REQUIREMENTS

NOTE:
SHRINK ROOF W/ 1/2" GYM PLYWOOD PLACES AT LONG DIMENSION PERPENDICULAR TO THE ROOF TRUSSES. SECURE TO RAFTERS W/ 60 RING SHANK NAILS - AS PER DETAIL 'A' ON SHEET 'A'

NOTE:
ALL UPLIFT CONNECTORS SHALL BE FIELD ADJUSTED TO MATCH OR EXCEED THE DEVELOPED LOADS PER ENGINEERED TRUSS SHOP DRAWINGS


NOTE:
ALL PENETRATIONS OF THE TOP PLATE OF ALL LOAD BEARING WALLS SHALL BE SEALED WITH FIRE RETARDANT CAULKING INCLUDING LIVING, PLUMBING OR OTHER SUCH PENETRATIONS. WALLS OVER 8'-0" TALL SHALL HAVE CONTINUOUS BLOCKING TO UPLIFT CAVITY HEIGHT TO 8'-0". PENETRATIONS THROUGH SUCH BLOCKING SHALL BE TREATED IN THE SAME MANNER AS TOP PLATES, NOTED ABOVE.

WOOD STRUCTURAL NOTES

- TEMPORARY BRACING OF THE STRUCTURE DURING ERECTION, REQUIRED FOR SAFE AND STABLE CONSTRUCTION, SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AS ENAGED. TEMPORARY BRACING BRACING OF ROOF TRUSSES SHALL BE AS PER THE STANDARD OUTSIDE LOAD OF THE TRUSS PLATE MANUFACTURER.
- ALL TRUSSES SHALL BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER. ALL TRUSSES SHALL BE BUILT AND SEALED BY SAFE TRUSS DESIGN SHALL INCLUDE PLACEMENT PLANS, TRUSS DETAILS, TRUSS TO TRUSS CONNECTIONS & THE STANDARD SPECIFICATIONS & RECOMMENDATIONS OF INSTALLATION OF THE TRUSS PLATE MANUFACTURER.
- WOOD STUDS IN EXTERIOR WALLS & INTERIOR BEARING WALLS SHALL BE NOT LESS THAN 2x4 MEMBER OR BETTER.
- CONNECTORS FOR WOOD FRAMING SHALL BE GALVANIZED METAL OR BLACK METAL AND MANUFACTURED OR AS CALLED FOR IN THE PLANS AND BE OF A DESIGN SUITABLE FOR THE LOADS AND USE INTENDED. REFER TO THE JOINT REINFORCEMENT SCHEDULE FOR PRINCIPLE CONNECTIONS.

GENERAL TRUSS NOTES:

- TRUSSES SHALL BE DESIGNED BY A LICENSED ENGINEER AND IN ACCORDANCE WITH THE REQUIREMENTS OF THE NATIONAL FOREST PRODUCTS ASSOCIATION (NFPA) FOR TRUSSES BUILT UNDER AND ITS CONNECTIONS. LATEST E.A. ALONG WITH THE TRUSS PLATE MANUFACTURER'S SUGGESTED GUIDELINES FOR TEMPORARY AND PERMANENT BRACING AND HANDLING OF TRUSSES. TRUSS SHOP DRAWINGS SHALL INCLUDE TRUSS DESIGN, PLACEMENT PLANS, DETS. & TRUSS TO TRUSS CONNECTIONS.
- TRUSS SHOP DRAWINGS SHALL BE REVIEWED & SEALED BY THE DESIGNING ENGINEER.
- INCLUDING DEVELOPMENT OF TRUSS SHOP DRAWINGS, ADJUSTMENTS TO THE ANCHOR REQUIREMENTS THAT ARE REQUIRED DEPENDS ON THE ENGINEERED GRAVITY AND UPLIFT REQUIREMENTS OF TRUSSES OR ORDERS. THE CONTRACTOR SHALL HAVE AVAILABLE A COMPLETE SET OF TRUSS SHOP DRAWINGS TO THE ARCHITECT FOR THE PURPOSES OF REVIEW OF LOADS IMPOSED ON THE BALANCE OF THE STRUCTURE. ANY SUCH REQUIRED CHANGE SHALL BE INCORPORATED INTO THE CONSTRUCTION OF THE STRUCTURE.



ROOF PLAN NOTES

- R-1 ALL ROOF PITCH 1:12 MIN.
- R-2 ALL OPENINGS W/ SILLERS OTHER THAN NOTED
- R-3 PROVIDE ATTIC VENTILATION IN ACC. CONFORMANCE WITH ROOF VENT DETAIL
- R-4 MOVE ALL VENTS AND OTHER ROOF PENETRATIONS TO CLEAR

TRUSS SHOP DRAWINGS ARE SUGGESTED STRAPS AS INDICATED IN THE CONSTRUCTION DOCUMENTS AND THAT THE TRUSS ENGINEERED SHOP DRAWINGS SHALL TAKE PRECEDENCE OVER THAT INDICATED IN THE CONSTRUCTION DOCUMENTS. TRUSS SHOP DRAWINGS MAY BE MATCHED TO ESTABLISHED PRODUCT UPLIFT RATINGS FOR COMPATIBILITY WITH THE TRUSS ENGINEERED SHOP DRAWINGS. THE CONTRACTOR SHALL COORDINATE THE TRUSS TO TRUSS ANCHOR REQUIREMENTS WITH THE TRUSS ENGINEERING SHOP DRAWINGS. SOME OF THE TRUSS TO TRUSS CONNECTIONS WILL REQUIRE ANCHOR STRAPS IN ADDITION TO TYPICAL WALLS. ANCHOR STRAPS SHALL BE REQUIRED FOR ALL JOINTS WITH AN UPLIFT OR GRAVITY LOAD OF 300 LBS OR GREATER. TRUSSES BEARING ON INTERIOR PARTITIONS WHERE UPLIFT LOADS ARE PRESENT SHALL REQUIRE ANCHORS OF EQUAL OR GREATER LOAD CAPACITY THAN THAT INDICATED BY THE TRUSS SHOP DRAWINGS. THE UPLIFT ANCHOR SYSTEM SHALL BE CONTINUOUS TO THE FOUNDATION.

ANCHOR ALL TRUSSES W/ "SIMPSON" H24C STRAPS # EA. POINT OF BEARING

CONSTRUCT EXTERIOR WALLS W/ 3 TOP PLATES & 1 SILL PLATE. 2x8 STUDS # 16" O.C. ANCHOR TOP PLATE TO SILL W/ "SIMPSON" ORB BRACING. APPLIED W/ 60 RING SHANK NAILS # 4" O.C. ALONG EDGES & 8" O.C. ALONG INTERMEDIATE SUPPORTS.

STANDARD HEADER SCHEDULE

- 0'-0" UP TO 6'-0" OPENINGS
DOUBLE 2x8 NO. 2 SOUTHERN PINE WITH 1/2" ORB SOLID CONTINUOUS SPACERS GLED AND NAILED WITH 10d x 0.9d" x 3" NAILS IN 2 ROWS # 12" O.C. STAGGERED EACH SIDE WITH 1 - SIMPSON INSTAB-TOP AND 1 - SIMPSON STRAP BOTTOM EACH SIDE OF OPENING WITH 1 - HEADER STUD AND 1 FULL HEIGHT STUD EACH SIDE OF OPENING
- 6'-0" UP TO 9'-0" OPENINGS
DOUBLE 2x8 NO. 2 SOUTHERN PINE WITH 1/2" ORB SOLID CONTINUOUS SPACERS GLED AND NAILED WITH 10d x 0.9d" x 3" NAILS IN 2 ROWS # 12" O.C. STAGGERED EACH SIDE WITH 1 - SIMPSON INSTAB-TOP AND 1 - SIMPSON STRAP BOTTOM EACH SIDE OF OPENING WITH 1 - HEADER STUD AND 1 FULL HEIGHT STUD EACH SIDE OF OPENING
- 9'-0" UP TO 12'-0" OPENINGS
DOUBLE 2x8 NO. 2 SOUTHERN PINE WITH 1/2" ORB SOLID CONTINUOUS SPACERS GLED AND NAILED WITH 10d x 0.9d" x 3" NAILS IN 2 ROWS # 12" O.C. STAGGERED EACH SIDE WITH 1 - SIMPSON INSTAB-TOP AND 1 - SIMPSON STRAP BOTTOM EACH SIDE OF OPENING WITH 1 - HEADER STUD AND 1 FULL HEIGHT STUD EACH SIDE OF OPENING
- 12'-0" GARAGE DOOR OPENINGS
2 FULL 12" x 12" 2x8 PROHOLAPLY LVL HEADER GLED AND NAILED WITH 10d x 0.9d" x 3" NAILS IN 2 ROWS # 12" O.C. STAGGERED EACH SIDE WITH 1 - SIMPSON INSTAB-TOP AND 1 - SIMPSON STRAP BOTTOM EACH SIDE OF OPENING WITH 1 - HEADER STUD AND 1 FULL HEIGHT STUD EACH SIDE OF OPENING


REVISIONS
JUNE 08, 2019

LOT 49, EMERALD COVE
239 SW FELLOSTONE CT., LAKE CITY, 32024
IC CONSTRUCTION, LLC.
516 W Duell Street, Lake City, FL 32055

N3
NICHOLAS
GESLER
ARCHITECT
INC. AIA 154000000
1000 N. W. 10th Street, Lake City, FL 32055
Tel: 407.350.0000

SHEET NUMBER
OF 4 SHEETS






GABLE END GYPSUM DIAPHRAGM HOLDDOWN CONNECTOR

SCALE: NONE

A.1




END WALL BRACING FOR CEILING DIAPHRAGM

NTS (ALTERNATIVE TO BALLOON FRAMING)
NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

A

ROOF SHEATHING FASTENINGS			
NAILING ZONE	SHEATHING TYPE	FASTENER	SPACING
1	1/2" G.S.B. OR 3/8" G.S.B.	16 RING SHANKED NAILS	6" IN R.A. EDGE 12" IN R.A. FIELD
2	1/2" G.S.B. OR 3/8" G.S.B.	16 RING SHANKED NAILS	6" IN R.A. EDGE 12" IN R.A. FIELD
3	1/2" G.S.B. OR 3/8" G.S.B.	16 RING SHANKED NAILS	6" IN R.A. EDGE 12" IN R.A. FIELD




Roof Sheathing Nailing Zones (HIP ROOF) (GABLE ROOF)

Roof Nail Pattern DET.

SCALE: NONE


B



Girder Truss Column DET.

SCALE: 1/2" = 1'-0"

C




TYP. PERMANENT TRUSS BRACING DIA.

NTS
NOTE: ALL WOOD TO BE NUMBER 2 GRADE SOUTHERN YELLOW PINE

Truss Bracing DETAILS

SCALE: AS NOTED


D



Garage End Wall DETAILS

SCALE: 1/2" = 1'-0"

G



Wall Framing/Header DETAILS

SCALE: NONE

F

Shear Wall DETAILS

SCALE: NONE

- SHEARWALL NOTES:**
- ALL SHEARWALLS SHALL BE TYPE 3 SHEARWALLS
 - THE WALL SHALL BE ENTIRELY SHEATHED WITH 7/8" SHEATHING BOARD INCLUDING AREAS ABOVE AND BELOW OPENINGS
 - ALL SHEATHING SHALL BE ATTACHED TO FRAMING ALONG ALL FOUR EDGES WITH JOINTS FOR ADJACENT PANELS OCCURRING OVER COPPIN FRAMING MEMBERS OR ALONG BLOCKING
 - NAIL SPACING SHALL BE 6" O.C. EDGES AND 12" O.C. IN THE FIELD
 - TYPE 3 SHEARWALLS ARE DESIGNED FOR THE OPENING IT CONTAINS. FRAMING HEIGHT OF OPENING SHALL BE 80% FREE THE WALL HEIGHT. THE FRAMING DISTANCE BETWEEN OPENINGS SHALL BE THE WALL HEIGHT FOR 8/17 WALLS (3-2)
- | OPENING SIZE | WALL PLATE | MIN. TIE NAILS EACH END |
|----------------|--------------------|-------------------------|
| UP TO 8'-0" | (1) 2x4 OR (1) 2x6 | 1 |
| 7'-6" TO 8'-0" | (1) 2x4 OR (1) 2x6 | 2 |
| 8'-0" TO 8'-6" | (1) 2x4 OR (1) 2x6 | 3 |

E

REVISIONS
JUNE 08, 2019

LOT 49, EMERALD COVE
233 SW FILLSTONE CT., LAKE CITY, 30024
IC CONSTRUCTION, LLC
618 W. Duval Street, Lake City, FL 32005

IC CONSTRUCTION, LLC
ARCHITECT
100 S. Duval Street, Lake City, FL 32005

SHEET NUMBER
S.4
OF 15 SHEETS



FLORIDA BUILDING CODE	
Compliance Summary	
TYPE OF CONSTRUCTION	
Roof:	Gable Construction, Wood Trusses + 3/4" O.C. Rafters, 3/4" Solid Shear + 3/4" O.C.
Floor:	4" Thk. Concrete Slab w/ Reinforcing Concrete Additional Reinforcement (Continued From Item 1)
ROOF DECKING	
Material:	1/2" CD Plywood or 1/4" O.S.B.
Sheet Size:	48" x 96" Sheets Perpendicular to Roof Tracing
Fasteners:	8d Common Nails per schedule on sheet A.1.
SHIMS/GIRDS	
Material:	1/2" CD Plywood or 1/4" O.S.B.
Sheet Size:	48" x 96" Sheets Placed Vertical
Fasteners:	8d Common Nails + 4" O.C. Edges + 8" O.C. Interior
Support:	Double Top Plate (B.T.P.) w/ 2x4 Nails + 12" O.C.
Wall Studs:	3x4 Studs + 8" O.C.
HURRICANE UPLIFT CONNECTORS	
Truss Anchors:	SIMPSON HD34 or SDUC6000 + 8x Truss Stud (High U.O.L.)
Uplift Tension:	Uplift Shearlag Nailing is Adequate - 8d # 4" O.C. Top + 8d Anchor Bolts - 1/2" x 30" Bolt + 48" O.C. - In Bolt 12" w/ from corner
Corner Horizontal Devices:	1/2" x 2x4 + 8d each corner
Porch Column Base Connector:	Simpson ASD66 + 8d each column
Porch Column to Beam Connector:	Simpson SPC66/PC66 + 8d each column
FOOTINGS AND FOUNDATIONS	
Footings:	30"x60" x 12" CONC. CONCRETE FOOTING w/ 2 # REBAR.

- STRUCTURAL DESIGN CRITERIA:**
- THE DESIGN COMPLIES WITH THE REQUIREMENTS OF THE 2017 FLORIDA BUILDING CODE SECTION 601.05. ALL CODES AND SPECIFICATIONS SHALL BE LATEST EDITION AT THE TIME OF PERMIT.
 - WIND LOAD CRITERIA: WIND CATEGORY: I, EXPOSURE: B7
BASED ON ANEMOMETER 30 FT FREQ WIND-SPEED VELOCITY, V_W = 130 MPH
V_W = 101 MPH
 - ROOF DESIGN LOAD:
SUPERIMPOSED DEAD LOADS: 10 PSF
SUPERIMPOSED LIVE LOADS: 20 PSF
 - FLOOR DESIGN LOADS:
SUPERIMPOSED DEAD LOADS: 10 PSF
SUPERIMPOSED LIVE LOADS: 40 PSF
RESIDENTIAL: 40 PSF
BALCONIES: 80 PSF
 - WIND NET UPLIFT: AS INDICATED ON PLANS

- TERMITE PROTECTION NOTES:**
- SOL CHEMICAL BARRIER METHOD:**
- A PERMANENT SIGN WHICH IDENTIFIES THE TERMITE TREATMENT PROVIDER AND NEED FOR REINJECTION AND TREATMENT CONTRACT RENEWAL SHALL BE PROVIDED. THE SIGN SHALL BE POSTED NEAR THE WATER HEATER OR ELECTRIC PANEL. FBC 104.2.6
 - CONDENSATE AND ROOF DOWNSPOUTS SHALL DISCHARGE AT LEAST 1'-0" AWAY FROM BUILDING SIDE WALLS. FBC 104.4.4
 - IRRIGATION/SPRINKLER SYSTEMS INCLUDING ALL RISERS AND SPRAY HEADS SHALL NOT BE INSTALLED WITHIN 1'-0" FROM BUILDING SIDE WALLS. FBC 104.4.4
 - TO PROVIDE FOR INSPECTION FOR TERMITE INFESTATION, BETWEEN WALL COVERINGS AND FINAL EARTH GRADE SHALL NOT BE LESS THAN 3/8" THICK ADHESIVE DIRECTLY TO THE FOUNDATION WALL. FBC 103.6.6
 - INITIAL TREATMENT SHALL BE DONE AFTER ALL EXCAVATION AND BACKFILL IS COMPLETE. FBC 104.1.1
 - SOIL DISTURBED AFTER THE INITIAL TREATMENT SHALL BE RETREATED INCLUDING SPACES BORED OR FORMED. FBC 104.1.2
 - BORED AREAS IN CONCRETE FLOOR FOR SUBSEQUENT INSTALLATION OF TRAPS, ETC. SHALL BE MADE WITH PERMANENT METAL OR PLASTIC FORMS. PERMANENT FORMS MUST BE OF A SIZE AND DEPTH THAT WILL ELIMINATE THE CONTAMINANCE OF SOIL AFTER THE INITIAL TREATMENT. FBC 104.1.3
 - A VAPOR BARRIER MUST BE INSTALLED TO PROTECT AGAINST RAINFALL DILUTION. IF RAINFALL OCCURS BEFORE VAPOR BARRIER PLACEMENT, RETREATMENT IS REQUIRED. FBC 104.1.4
 - CONCRETE OVERPOUR AND FORMS ALONG THE FOUNDATION PERIMETER MUST BE REMOVED BEFORE EXTERIOR SOIL TREATMENT. FBC 104.1.5
 - SOIL TREATMENT MUST BE APPLIED UNDER ALL EXTERIOR CONCRETE OR GRADE WITHIN 1'-0" OF THE STRUCTURE INDIVIDUALLY. FBC 104.1.6
 - AN EXTERIOR VERTICAL CHEMICAL BARRIER MUST BE INSTALLED. AFTER CONSTRUCTION IS COMPLETE INCLUDING LANDSCAPING AND REDUCATION ANY SOIL DISTURBED AFTER THE VERTICAL BARRIER IS APPLIED SHALL BE RETREATED. FBC 104.1.7
 - ALL BUILDERS ARE REQUIRED TO HAVE PERI-CONSTRUCTION TREATMENT. FBC 104.1.7
 - A CERTIFICATE OF COMPLIANCE MUST BE ISSUED TO THE BUILDING DEPARTMENT BY A LICENSED PEST CONTROL COMPANY BEFORE A CERTIFICATE OF OCCUPANCY WILL BE ISSUED. THE CERTIFICATE OF COMPLIANCE SHALL STATE THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. THE TREATMENT IS IN ACCORDANCE WITH THE RULES AND LAWS OF THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. FBC 104.1.7
 - AFTER ALL WORK IS COMPLETED, LOOSE WOOD AND FILL MUST BE REMOVED FROM BELOW AND WITHIN 1'-0" OF THE BUILDING. THIS INCLUDES ALL GRADE STAKES, TRAP BOXES, FORMS, SHOWN OR OTHER CELLULOSE CONTAINING MATERIAL. FBC 104.1.7
 - NO WOOD, VEGETATION, STUMPS, CARDBOARD, TRASH, ETC. SHALL BE BURIED WITHIN 8'-0" OF ANY BUILDING OR PROPOSED BUILDING. FBC 104.1.7

FRAMING ANCHOR SCHEDULE

APPLICATION	MANUF./MODEL	CAP.
TRUSS TO WALL	SIMPSON HD34 or SDUC6000 anchor	600A
CORNER TRUSS TO POST/HEADER	SIMPSON LOT W/ 3/8" x 6d NAILS	185A
HEADER TO KING STUD(S)	SIMPSON 672	137A
PLATE TO STUD	NO CONNECTION REQ. WHEN USING UNDERLAYER BOARD	720A
STUD TO RAIL	NO CONNECTION REQ. WHEN USING UNDERLAYER BOARD	720A
POURCH BEAM TO POST	SIMPSON PC66/PC66	35A/240A
POURCH POST TO FND.	SIMPSON ASD66	
TRUSS JOINTS	SIMPSON AS34	

NOTE: ALL ANCHORS SHALL BE SECURED W/ NAILS AS PRESCRIBED BY THE MANUFACTURER FOR MAXIMUM JOINT STRENGTH, UNLESS NOTED OTHERWISE.

NOTE: REFER TO THE INCLUDED STRUCTURAL DETAILS FOR ADDITIONAL ANCHORS/ JOINT REINFORCEMENT AND FASTENERS.

NOTE: ALL UNLISTED JOINTS IN THE LOAD PATH SHALL BE REINFORCED WITH SIMPSON AS4 FRAMING ANCHORS, TYPICAL T.O.

NOTE: "SERICO" PRODUCT APPROVAL:
FLA/HI/DADE COUNTY REPORT #88-0818


NOTE: "SERICO" PRODUCT APPROVALS:
FLA/HI/DADE COUNTY REPORT #81-021.05, #86-106.3, #88-0623.04
#80CCI-NER-443, NER-393

BUILDING COMPONENTS & CLADDING LOADS
MEAN BUILDING HEIGHT = 30'-0", EXPOSURE "B"
ROOF ANGLE T° TO T°

WIND SPEED (MPH)	WIND PRESSURE (PSF)		WIND SUCTION (PSF)	
	WINDWARD WALL	WINDWARD ROOF	LEEWARD WALL	LEEWARD ROOF
10	14.7/18.4	18.7/23.1	19.7/24.9	25.7/32.3
15	24.7/31.4	31.7/39.9	32.7/41.9	41.7/52.4
20	34.7/43.4	44.7/56.4	45.7/58.4	57.7/72.4
25	44.7/56.4	57.7/72.4	58.7/74.4	74.7/93.4
30	54.7/69.4	69.7/88.4	70.7/89.4	89.7/112.4
35	64.7/82.4	81.7/103.4	82.7/104.4	103.7/130.4
40	74.7/95.4	93.7/118.4	94.7/119.4	118.7/149.4
45	84.7/108.4	105.7/133.4	106.7/134.4	133.7/168.4
50	94.7/121.4	117.7/148.4	118.7/149.4	148.7/187.4
55	104.7/134.4	129.7/163.4	130.7/164.4	163.7/206.4
60	114.7/147.4	141.7/178.4	142.7/179.4	178.7/225.4
65	124.7/160.4	153.7/193.4	154.7/194.4	193.7/244.4
70	134.7/173.4	165.7/208.4	166.7/209.4	208.7/264.4
75	144.7/186.4	177.7/223.4	178.7/224.4	223.7/281.4
80	154.7/199.4	189.7/238.4	190.7/239.4	238.7/299.4
85	164.7/212.4	201.7/253.4	202.7/254.4	253.7/319.4
90	174.7/225.4	213.7/268.4	214.7/269.4	268.7/337.4
95	184.7/238.4	225.7/283.4	226.7/284.4	283.7/356.4
100	194.7/251.4	237.7/298.4	238.7/299.4	298.7/375.4


WIND & EXPOSURE ADJUSTMENT COEFFICIENTS FOR BUILDING COMPONENTS & CLADDING

BUILDING HEIGHT	EXPOSURE "B"	EXPOSURE "C"	EXPOSURE "D"
0	1.00	1.15	1.40
5	1.00	1.15	1.40
10	1.00	1.30	1.60
15	1.00	1.40	1.80




- FIREBLOCKING NOTES:**
- FIREBLOCKING SHALL BE INSTALLED IN WOOD FRAME CONSTRUCTION IN THE FOLLOWING LOCATIONS:
- IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS INCLUDING PURSED SPACES AT CEILING AND FLOOR LEVELS.
 - AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, CROWN MOULDING, CEILING, ETC.
 - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CHIMNEYS AND FIREPLACES AT CEILING AND FLOOR LEVELS WITH "PYROPLASTIC MULTIFLEX SEALANT"
 - AT ALL INTERCONNECTIONS BETWEEN CONCEALED VERTICAL STUD WALL OR PARTITION SPACES AND CONCEALED SPACES CREATED BY AN ASSEMBLY OF FLOOR JOISTS, FIREBLOCKING SHALL BE PROVIDED FOR THE FULL DEPTH OF THE JOISTS AT THE ENDS AND OVER THE SUPPORTS.


Fire Stopping DETAILS
SCALE: NONE



Vent DETAIL
SCALE: 1" = 1'-0"



Joint DETAIL
SCALE: 1" = 1'-0"



Ridge DETAIL
SCALE: 1" = 1'-0"

General Roofing NOTES:

- DECK REQUIREMENTS:**
ASPHALT SHINGLES SHALL BE FASTENED TO SOLIDLY SHEATHED DECKS.
- SLOPE:**
ASPHALT SHINGLES SHALL BE USED ONLY ON ROOF SLOPES OF 3:12 OR GREATER. FOR ROOF SLOPES FROM 3:12 TO 4:12, UNDERLAYMENT IS REQUIRED.
- UNDERLAYMENT:**
UNLESS OTHERWISE NOTED, UNDERLAYMENT SHALL CONFORM W/ ASTM D 366, TYPE I OR ASTM D 4846, TYPE I.
- SELF-ADHERING POLYMER MODIFIED BITUMEN SHEET:**
SELF-ADHERING POLYMER MODIFIED BITUMEN SHALL CONFORM W/ ASTM D 1930.
- ASPHALT SHINGLES:**
ASPHALT SHINGLES SHALL HAVE SELF SEAL STRIPS OR BE INTERLOCKING, AND COMPLY WITH ASTM D 396 OR ASTM D 3463.
- FASTENERS:**
FASTENERS FOR ASPHALT SHINGLES SHALL BE GALVANIZED, STAINLESS STEEL, ALUMINUM OR CORROS RESISTANT NAILS, MINIMUM 5 GAUGE SHANK WITH A MINIMUM 3/8 INCH DIAMETER HEAD, OF A LENGTH TO PENETRATE THROUGH THE ROOFING MATERIAL AND A MINIMUM 3/4" INTO THE ROOF SHEATHING. WHERE THE SHEATHING IS LESS THAN 3/4" THICK, THE NAILS SHALL PENETRATE THROUGH THE SHEATHING.
- ATTACHMENT:**
ASPHALT SHINGLES SHALL BE SECURED TO THE ROOF WITH NOT LESS THAN FOUR FASTENERS PER SHINGLE OR TWO FASTENERS PER INDIVIDUAL SHINGLE, UNLESS ROOFS LOCATED IN BASIC WIND SPEEDS OF 10 MPH OR GREATER. SPECIAL METHODS OF FASTENING ARE REQUIRED, UNLESS OTHERWISE NOTED. ATTACHMENT OF ASPHALT SHINGLES SHALL CONFORM WITH ASTM D 396 OR ASTM D 3463.
- UNDERLAYMENT APPLICATION:**
FOR ROOF SLOPES FROM 3:12 TO 4:12, UNDERLAYMENT SHALL BE A MINIMUM OF TWO LAYERS APPLIED AS FOLLOWS:
1. STARTING AT THE EAVE, A 1/2 INCH UNDERLAYMENT SHALL BE APPLIED PARALLEL WITH THE EAVE AND FASTENED SUFFICIENTLY TO STAY IN PLACE.
2. STARTING AT THE EAVE, 3/8 INCH WIDE STRIPS OF UNDERLAYMENT FELT SHALL BE APPLIED OVERLAPPING SUCCESSIVE SHEETS 1/2 INCHES AND FASTENED SUFFICIENTLY TO STAY IN PLACE.
- FOR ROOF SLOPES 4:12 AND GREATER, UNDERLAYMENT SHALL BE A MINIMUM OF ONE LAYER OF UNDERLAYMENT FELT APPLIED AS FOLLOWS:**
STARTING AT THE EAVE, UNDERLAYMENT FELT SHALL BE APPLIED SINGLE FABRIC PARALLEL TO THE EAVE, LAPPED 2 INCHES, AND FASTENED SUFFICIENTLY TO STAY IN PLACE.
- BASE AND CAP FLASHINGS:**
BASE AND CAP FLASHINGS SHALL BE INSTALLED IN ACCORDANCE W/ SHINGLE INSTALLATION INSTRUCTIONS. BASE FLASHING SHALL BE OF EITHER CORROSION RESISTANT METAL OR FINISH NOMINAL THICKNESS 0.015 INCH OR MINERAL SURFACE ROLL ROOFING WITH A MINIMUM OF 7 LBS PER 100 SQUARE FEET. CAP FLASHING SHALL BE CORROSION RESISTANT METAL OF FINISH NOMINAL THICKNESS OF 0.015 INCH.
- VALLEYS:**
VALLEY LINING SHALL BE INSTALLED IN ACCORDANCE W/ MANUFACTURER'S INSTALLATION INSTRUCTIONS BEFORE APPLYING ASPHALT SHINGLES. VALLEY LINING OF THE FOLLOWING TYPES SHALL BE PERMITTED:
1. FOR OPEN VALLEYS LINED WITH METAL, THE VALLEY LINING SHALL BE AT LEAST 1/2" WIDE AND OF ANY OF THE CORROSION RESISTANT METALS IN FBC TABLE 601.5.5.1.
2. FOR OPEN VALLEYS, VALLEY LINING OF TWO PLYS OF MINERAL SURFACE ROLL ROOFING SHALL BE PERMITTED. THE BOTTOM LAYER SHALL BE 1/2 INCHES AND THE TOP LAYER A MINIMUM OF 3/8 INCHES WIDE.
3. FOR CLOSED VALLEYS VALLEY LINING SHALL BE ONE OF THE FOLLOWING:
1. BOTH TYPES 1 AND 2 ABOVE COMBINED.
2. ONE PLY OF SMOOTH ROLL ROOFING AT LEAST 3/8 INCHES WIDE AND COMPLYING WITH ASTM D 346.
3. SPECIALTY UNDERLAYMENT AT LEAST 3/8 INCHES WIDE AND COMPLYING WITH ASTM D 1930.

NOTE 1.1.1
ROOF SHINGLES SHALL BE AS MANUFACTURED BY "HARKO ROOFING PRODUCTS" OF THE FOLLOWING MODELS:

- GLASS-REAL AIR
- ELITE GLASS-REAL AIR
- HERITAGE 30 AIR
- HERITAGE 40 AIR
- HERITAGE 50 AIR

THESE SHINGLES MEET THE REQUIREMENTS OF ASTM D-3161 TYPE I MODIFIED TO 130 MPH WINDS + FBC TAB 100, USING 4 NAILS/SHINGLE.

REVISIONS
JUNE 08, 2019

LOT 49, EMERALD COVE
239 SW FLORESTONE CT, LAKE CITY, 32024
IC CONSTRUCTION, LLC
818 W Duval Street, Lake City, FL 32025

NICHOLAS PAUL GEISLER ARCHITECT
1700 Hill Street, Lake City, FL 32025
Phone: 407-321-1000
Fax: 407-321-1001

SHEET NUMBER
S.3
OF 4 SHEETS



02438-149