



Affine Engineering and Surveying, Inc.

---

Date:4/6/2021

Mr. Tommy Bulock

Evanston Contracting, Inc

386.344.8888


Re: **Elevation Letter-7387 SW Tustenuggee Avenue, Lake City, Fl.**

SUBJECT:

FINISH FLOOR HEIGHT VERIFICATION

To whom it may concern,

During a field survey conducted 4/27/2021 the subject property (~~Parcel 20-58-17-02270-124~~), the finish floor of the existing structure was measured. According to an elevation letter prepared by Carol Chadwick PE - Job#FL21052 signed 2-27-2021, the elevation of the road at the intersection of the extension of the north property line and the centerline of Tustenuggee Avenue is at elevation 106.0' +/- . Based on that elevation and after measuring the elevation of the Finish Floor, it was found that the Finish Floor is at elevation 98.45 feet.

 4.27.21

Victor O. Marrero, PE, PSM

Florida PSM 6586

