


	<div>TERMITE SPECIFICATIONS:</div> <div>R318.1 TERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES, INCLUDING SOIL APPLIED PESTICIDES, BAITING SYSTEMS, AND OTHER METHODS APPLICABLE TO WOOD, OR OTHER APPROVED METHODS OF TERMITE PROTECTION LABELED FOR USE AS A PREVENTATIVE TREATMENT TO NEW CONSTRUCTION (SEE SECTION 202 - REGISTERED TERMITICIDE). UPON COMPLETION OF THE APPLICATION OF THE TERMITE PROTECTIVE TREATMENT, A CERTIFICATE OF COMPLIANCE SHALL BE ISSUED TO THE BUILDING DEPARTMENT BY THE LICENSED PEST CONTROL COMPANY THAT CONTAINS THE FOLLOWING STATEMENT: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT IS IN ACCORDANCE WITH RULES AND LAWS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES." <b>NOTES:</b> 1. METHOD OF TREATMENT SHALL BE APPROVED BY THE GOVERNING JURISDICTION "LIQUID BORATE OR BORA-COR". PRODUCT METHODS MUST BE DETERMINED AT PERMIT STAGE AND PRODUCT APPROVAL DATA MUST BE ON FILE WITH THE BUILDING DEPARTMENT. 2. PRESSURE TREATED LUMBER THAT HAS BEEN KNOB OR DRILLED THAT EXPOSES UNTREATED PORTIONS OF WOOD ARE REQUIRED TO BE FILLED TREATED TO PREVENT INSECT INFestation 3. OPTIONAL BORATE APPLIED TO ALL FRAME MEMBERS WITHIN 24" A.F.F.</div> <div>EXTERIOR COVERING</div> <div>R703.7 EXTERIOR PLASTER. INSTALLATION OF THESE MATERIALS SHALL BE IN COMPLIANCE WITH ASTM C926 AND ASTM C1063, OR ASTM C1787 AND THE PROVISIONS OF THIS CODE.  R703.7.1 LATH. LATH AND LATH ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIALS. EXPANDED METAL OR WOMEN WIRE LATH SHALL BE ATTACHED WITH 1/32" LONG, 11 GAGE NAILS HAVING A 7/16" HEAD, OR 1 1/2" LONG, 16 GAGE STAPLES, SPACED IN ACCORDANCE WITH ASTM C1063 OR C1787, OR AS OTHERWISE APPROVED. REFER TO SHEET 5 OR S.1 FOR THE ENGINEERED METHOD FOR LATH ATTACHMENT.  <b>LATHING ACCESSORIES:</b> ATTACHMENTS SHALL BE OF CORROSION-RESISTANT MATERIALS. WOOD APPLICATION; 16 GA X 1 1/2" LONG (3/4" x .1") CROWN) STAPLES @ 6" O.C., VERT/HORIZ INTO THE FRAMING MEMBERS. MASONRY APPLICATION; CONCRETE STUD NAIL, 3/8" (10 mm) HEAD DIA. MIN. #8 @ 6" O.C. VERT/HORIZ, OR COMPATIBLE ADHESIVES. EXTERIOR GUNGRADE. CONSTRUCTION ADHESIVE WITH 1" DIAPS @ 6" O.C. or IN A SEMI-CONTINUOUS BEAD BETWEEN THE SOLID PLASTER BASE AND THE SOLID PORTION OF THE JOINT. VERIFY THE TYPE OF ADHESIVE USED. INSTALL CONTROL JOINT LATHING ACCESSORIES IN CONFORMANCE WITH C1063. LATH SHALL NOT BE CONTINUOUS THROUGH CONTROL JOINTS, BUT SHALL BE STOPPED AND TIED AT EACH SIDE. All ACCESSORIES SHALL BE IN ACCORDANCE WITH THE LATEST ASTM C1063 &amp; ASTM C1861.  R703.7.2 PLASTER. PLASTERING WITH CEMENT PLASTER SHALL BE NOT LESS THAN THREE COATS WHERE APPLIED OVER ANY TYPE OF CODE-APPROVED LATH AND SHALL BE NOT LESS THAN TWO COATS WHERE DIRECTLY APPLIED OVER MASONRY, CONCRETE, CLAY BRICK, STONE, OR TILE. IF THE PLASTER SURFACE IS COMPLETELY COVERED BY VENER OR OTHER FACING MATERIAL OR IS COMPLETELY CONCEALED, PLASTER APPLICATION NEED BE ONLY TWO COATS, PROVIDED TOTAL THICKNESS IS AS SET IN TABLE R702.1(1). CEMENT PLASTER SHALL BE IN ACCORDANCE WITH ASTM C926 AND MATERIAL SHALL BE IN ACCORDANCE WITH ONE OF THE TYPES LISTED IN R703.7.2.  R703.7.3 WATER-RESISTIVE BARRIERS. WATER-RESISTIVE BARRIERS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOUR-RETARDABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE-D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.  R703.2 WATER-RESISTIVE BARRIER. NOT FEWER THAN ONE LAYER OF WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS WITH FLASHINGS AS INDICATED IN SECTION R703.4. IN SUCH A MANNER AS TO PROVIDE A CONTINUOUS WATER-RESISTIVE BARRIER BEHIND THE EXTERIOR WALL VENEER. THE WATER-RESISTIVE BARRIER MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1. WATER-RESISTIVE BARRIER MATERIALS SHALL COMPLY WITH ONE OF THE FOLLOWING: 1. NO. 15 FELT COMPLYING WITH ASTM D226. TYPE 1. 2. ASTM E2568, TYPE 1 OR 2. 3. ASTM E331, IN ACCORDANCE WITH SECTION R703.11. 4. OTHER APPROVED MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. NO. 15 ASPHALT FELT AND WATER-RESISTIVE BARRIERS COMPLYING WITH ASTM E2568 shall be applied horizontally, with the UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51MM), AND WHERE JOINTS OCCUR, SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 mm).  R703.4 FLASHING. APPROVED METAL FLASHING, VINYL FLASHING, SELF-ADHERED MEMBRANES AND MECHANICALLY ATTACHED FLEXIBLE FLASHING SHALL BE APPLIED SHINGLE-FASHION OR IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. METAL FLASHING SHALL BE CORROSION RESISTANT. FLUID-APPLIED MEMBRANES USED AS FLASHING SHALL BE APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. ALL FLASHING SHALL BE APPLIED IN A MANNER TO PREVENT THE ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED MEMBRANES USED AS FLASHING SHALL COMPLY WITH ANMA 71.1. ALL EXTERIOR PENETRATION PRODUCTS SHALL BE SEALED AT THE JUNCTURE WITH A SEALANT COMPLYING WITH ANMA 800 OR ASTMA C920 CLASS 25 GRADE NS OR GREATER FOR PROPER JOINT EXPANSION AND CONTRACTION, ASTM C1281, ANMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE TYPE OF SEALANT. FLUID-APPLIED MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH ANMA 714. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS. • EXTERIOR WINDOW/DOOR OPENINGS. • INTERSECTION OF CHIMNEYS OR OTHER Masonry CONSTRUCTION WITH FRAME WALLS. • UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS. • CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM. • WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION. • AT WALL AND ROOF INTERSECTION. • AT BUILT-IN GUTTERS.  R703.2 ADHERED MASONRY VENEER INSTALLATION. ADHERED MASONRY VENEER (OR STONE VENEER) - INSTALLATION SHALL COMPLY WITH THE REQUIREMENTS OF SECTION R703.7.3 AND THE REQUIREMENTS IN SECTIONS 12.1 AND 12.3 OF TMS 402/ACI 530/ASCE 5. ADHERED MASONRY VENEER SHALL BE INSTALLED IN ACCORDANCE WITH SECTION R703.7.1, ARTICLE 3.3C OF TMS 602/ACI 530.1/ASCE 6 OR THE MANUFACTURER'S INSTRUCTIONS.  EXTERIOR CEILING LATH ATTACHMENT PER THE ASTM C 1063 7.10.2.2 DIAMOND-MESH EXPANDED METAL LATH, FLAT-RIB EXPANDED METAL LATH, AND WIRE LATH SHALL BE ATTACHED TO HORIZONTAL WOOD FRAMING MEMBERS WITH 1 1/2"-H. (38.1-MM) ROOFING NAILS DRIVEN FLUSH WITH THE PLASTER BASE AND ATTACHED TO VERTICAL WOOD FRAMING MEMBERS WITH 6D COMMON NAILS, OR 1-IN. (25-MM) ROOFING NAILS DRIVEN TO A PENETRATION OF NOT LESS THAN 3/4-IN. (.19.1 MM), OR 1-IN. (25-MM) WIRE STAPLES DRIVEN FLUSH WITH THE PLASTER BASE. STAPLES SHALL HAVE CROWNS NOT LESS THAN 3/4-IN. (.19.05 MM) AND SHALL ENGAGE NOT LESS THAN THREE STRANDS OF LATH AND PENETRATE THE WOOD FRAMING MEMBERS NOT LESS THAN 3/4-IN. (.19.05 MM). WHEN METAL LATH IS APPLIED OVER SHEATHING, USE FASTENERS THAT WILL PENETRATE THE STRUCTURAL MEMBERS NOT LESS THAN 3/4-IN. (.19 MM).  7.10.2.3 EXPANDED 3/8-IN. (.95 MM) RIB LATH SHALL BE ATTACHED TO HORIZONTAL AND VERTICAL WOOD FRAMING MEMBERS WITH NAILS OR STAPLES TO PROVIDE NOT LESS THAN 13/4-IN. (44.5-MM) PENETRATION INTO HORIZONTAL WOOD FRAMING MEMBERS, AND 3/4-IN. (.19.1-MM) PENETRATION INTO VERTICAL WOOD FRAMING MEMBERS.  7.10.2.4. COMMON NAILS SHALL BE BENT OVER TO ENGAGE NOT LESS THAN THREE STRANDS OF LATH OR BE BENT OVER A RIB WHEN RIB LATH IS INSTALLED.  7.10.2.5. SCREWS USED TO ATTACH METAL PLASTER BASE TO HORIZONTAL AND VERTICAL WOOD FRAMING MEMBERS SHALL PENETRATE NOT LESS THAN 5/8-IN. (15.9 MM) INTO THE MEMBER WHEN THE LATH IS INSTALLED AND SHALL ENGAGE NOT LESS THAN THREE STRANDS OF LATH. WHEN INSTALLING RIB LATH, THE SCREW SHALL PASS THROUGH, BUT NOT DEFORM, THE RIB.  COASTAL FLASHINGS: ALL FLASHING MATERIAL FOR COASTAL LOCATIONS (EX: WITHIN 3,000 FEET OF THE OCEAN) SHALL BE CORROSION RESISTANT MATERIAL (EX ZINC AND/OR STAINLESS STEEL) AND SHALL BE SELECTED FOR COMPATIBILITY WITH ADJACENT WOOD PRESERVATIVES PER THE MANUFACTURER'S RECOMMENDATIONS.</div> <div>MASTER REVISIONS</div> <table><thead><tr><th>DATE</th><th>DESCRIPTION</th></tr></thead><tbody><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr></tbody></table> <div>STRUCTURAL NOTES:</div> <div>CAST IN PLACE CONCRETE</div> <div>1. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2500 PSI (SLABS) 3000 PSI (COLUMNS AND BEAMS); A SLUMP OF 5" PLUS OR MINUS 1"; AND HAVE 2 TO 5% AIR ENTRAINMENT, AND A MAXIMUM WATER/CEMENT RATIO OF 0.63. 2. HOOPS SHALL BE PROVIDED AT DISCONTINUOUS ENDS OF ALL TOP BARS OF BEAMS. 3. HORIZONTAL FOOTING BARS SHALL BE BENT 25° AROUND CORNERS OR CORNER BARS WITH A 25° LAP PROVIDED EACH WAY. 4. CONCRETE COVER MIN. 3" WHEN EXPOSED TO EARTH OR 1 1/2" TO FORM U.N.O. 5. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A1064/A1064M. WWF SHALL BE LAPPED AT LEAST 6" AND CONTAIN AT LEAST ONE CROSS WIRE WITHIN THE 6", OR POLYPROPYLENE FIBERS FOR SLABS ON GRADE TO BE MIN. 75 LBS OF FIBER PER CUBIC YARD. 6. ALL REINFORCING STEEL / STIRRUPS AND TIES SHALL BE NEW DOMESTIC DEFORMED BARS FREE FROM RUST SCALE &amp; OIL &amp; SHALL MEET ASTM 615, ASTM A706, OR ASTMA 566 GRADE 40 U.N.O. REINFORCING FOR FOOTING SHALL BE SUPPORTED ON PRE-CAST CONCRETE PADSS. STEEL WIRE OR PLASTIC SUPPORTS. TOP REINFORCING SHALL BE POSITIVELY SUPPORTED BY TEMPORARY STIRRUPS. DOWELS FOR COLUMNS &amp; FILLED CELLS SHALL BE SECURED IN PLACE BY USING ADDITIONAL CROSS-REINFORCING TIE TO FOOTING REINFORCING. SPLICES IN REINFORCING WHERE PERMITTED SHALL BE AS PER DETAIL MS05. SEE PLAN SET. 7. HIGH STRENGTH SIMPSON SET EPOXY/TIE ANCHORING ADHESIVE WAS USED IN THE DESIGN OF THIS PRODUCT.. IF CONTRACTORS WISH TO USE A DIFFERENT EPOXY, THEY MUST FIRST CONTACT THE ENGINEER OF RECORD FOR WRITTEN APPROVAL. 8. WHERE PROJECT IS TO BE LOCATED IN KNOWN RADON GAS PREVALENT AREAS, APPENDIX "F" OF THE FLORIDA BUILDING CODE 8TH EDITION (2023) IS TO BE IMPLEMENTED. F303.4.1 CONCRETE STRENGTH IN THESE AREAS ARE TO BE A MINIMUM OF 3000 P.S.I. THEREFORE, ANY AND ALL NOTES ON THESE PLANS THAT INDICATE 2500 P.S.I. SHALL BE REPLACED WITH 3000 P.S.I. FOR THE CONCRETE STRENGTH.</div> <div>MASONRY WALL CONST.</div> <div>1. HOLLOW LOAD BEARING UNITS SHALL BE NORMAL WEIGHT, GRADE N, TYPE 2, CONFORMING TO ASTM C90-2016A, WITH A MINIMUM NET COMPRESSIVE STRENGTH OF 2000 PSI (f m = 2000 PSI) 2. MORTAR SHALL BE TYPE "S", CONFORMING TO ASTM C270-14A. 3. COURSE GROUITS SHALL CONFORM TO ASTM C476-19 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 3000 PSI SLUMP 8" TO 11". CONTINUOUS MASONRY INSPECTIONS ARE REQUIRED DURING CONSTRUCTION. 4. GRADE 40 U.N.O. VERTICAL REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS WITH THE CELLS FILLED WITH COARSE GROUT. 5. REINFORCING STEEL SHALL BE LAPPED PER DETAIL MS05 ON LINEAL PLAN PAGE, UNLESS OTHERWISE NOTED ON THE DRAWINGS. 6. GROUT SIOPS SHALL BE PROVIDED BELOW BOND BEAM. PLASTIC SCREEN, METAL LATH STRIP OR CAVITY CAPS MAY BE USED TO PREVENT THE FLOW OF GROUT INTO CELLS BELOW. THE USE OF FELT PAPER AS A STOP IS PROHIBITED. 7. TEMPORARY BRACING AND SHORING OF WALL TO PROVIDE STABILITY DURING CONSTRUCTION</div>	DATE	DESCRIPTION										
DATE	DESCRIPTION												



BEARING WALL INTERIOR WALL SCHEDULE					
MARK	STUD SPACING	CONNECTION & FASTENERS		LUMBER SPECIES	UPLIFT CAP.(KIP)
		TOP	BOTTOM		
BW1	16"	(2) 16G TOENAILS	(2) 16G TOENAILS	SPF	0
BW2	16"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SPF	402
BW3	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	571
BW4	16"	(2) 16G TOENAILS	(2) 16G TOENAILS	SYP	0
BW5	16"	SP2 W/ (6)-10d NAILS	SP1 W/ (6)-10d NAILS	SYP	439
BW6	16"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	665
BW7	12"	(2) 16G TOENAILS	(2) 16G TOENAILS	SPF	0
BW8	12"	SP2 W/ (6)-10d NAILS	SP1 W/ (6) 10d NAILS	SPF	535
BW9	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SPF	760
BW10	12"	(2) 16G TOENAILS	(2) 16G TOENAILS	SYP	0
BW11	12"	SP2 W/ (6)-10d NAILS	SP1 W/ (6) 10d NAILS	SYP	565
BW12	12"	SP4 W/ (6) 10d X 1 1/2" NAILS	SP4 W/ (6) 10d X 1 1/2" NAILS	SYP	885

NOTE: 2 x 4 WALLS ARE ASSUMED J.N.O. ON FLOOR PLANS

\* ALL LUMBER TO BE GRADE #2  
 \*\* CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED



## BEARING INTERIOR WALL DETAIL

### GENERAL NOTES

1. SEE FLOOR PLAN FOR WALL TYPE. ASSUME 24" STUDS USE UNO.
2. ALL STRUCTURAL LUMBER BE BEARING PLAN UNO.
3. CONNECTIONS TO BE INSTALLED AS EACH STUD AS INDICATED.
4. IF BEARING WALL IS TO BE CONNECTED TO ANOTHER BEARING WALL, THE CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
5. IF "B-W" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO IGNORED. SEE W/PROG 3-2 FOR INDICATED DETAIL FOR PROPER CONNECTIONS. OR SEE DETAIL FOR FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY.)
6. IF "SW" IS INDICATED THE WALL IS TO BE EXTERIOR. GROUND ANCHORS MIN. 7/16" ØD PLYWOOD W/ 8" NAILS AT 4" O.C. IN FIELD AND EDGE TO (1) SIDE OF WALL.
7. ALL 2" EXTERIOR SHEATHING AT EXTERIOR SHEATHING ATTACHMENT SCHEDULE.
8. ALL 1/2" EXTERIOR SHEATHING AT INTERIOR SHEATHING ATTACHMENT SCHEDULE. IF THE BEARING WALL IS INDICATED WITH THE B-W1, B-W2, B-W3, THESE WALLS ARE TO BE EXTERIOR. IF THE WALL IS NOT INDICATED WITH B-W1, B-W2, B-W3, USE FDS NAIL TO THE PLATE AND THE 2" PLATE CAN BE ATTACHED WITH HARD CASED NAILS. (OUR NAILS ARE 16" LONG) SEE DETAIL FOR ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.

COLUMN SCHEDULE				
MARK	COLUMN SIZE	BASIC CORR. & FASTENER	UPLIFTS(Lb)	
C1	(3) 2 x 4 2" SPF	(4) 16d TOENAILS	0	
C2	(3) 2 x 4 2" SPF	DT12Z W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145	
C3	(3) 2 x 4 SYP #1 GR.	(4) 16d TOENAILS	0	
C4	(4) 2 x 4 SPF #2	DT12Z W/ 1/2" WEDGE ANCHOR & (8) 1/4" X 1 1/2" SDS SCREWS	2145	
C5	4 x 4 P.T.#2 SYP POST	ABU4 4 W/ 5/8" AT** & (12) 16d NAILS	G = 6665 U = 2300	
C6	6 x 8 P.T.#2 SYP POST	ABU6 6 W/ 5/8" AT** & (12) 16d NAILS	G = 12000 U = 2300	
C7	8 x 8 P.T.#2 SYP POST	ABU8 8 W/ (2) 5/8" AT** & (18) 16d NAILS	G = 24355 U = 2320	
C8	3.5 x 3.5 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ (14) 1/4" X 2 1/2" SDS WS 5/8" EXCPY ANCHOR OR ATP-1**	5645	
C9	3.5 x 5.25 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ (14) 1/4" X 2 1/2" SDS WS 5/8" EXCPY ANCHOR OR ATP-1**	5645	
C10	3.5 x 7 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ (20) 1/4" X 2 1/2" SDS WS 7/8" EXCPY ANCHOR OR ATP-1**	6970	
C11	5.25 x 5.25 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ (20) 1/4" X 2 1/2" SDS WS 7/8" EXCPY ANCHOR OR ATP-1**	7870	
C12	7 x 7 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ (20) 1/4" X 2 1/2" SDS WS 7/8" EXCPY ANCHOR OR ATP-1**	7870	
C13	5.25" x 7 PL 1.8E R-2400 PSI (WOLMANIZED F.E.T.)	HDCU-S5S2 5 W/ 1" 7/8" AT AND (20) 1/4" X 1/2" SDS WOOD SCREWS	7870	

## GENERAL COLUMN NOTES

1. SEE FLOOR PLAN FOR WALL WIDTH. STUD PUNCH TO MATCH WALL WIDTH UNO.
2. ALL STRUCTURAL LUMENES TO BE SYP #1 OR SYP #2 UNO ON PLAN.
3. NAIL BOLT UP STUDS PER DETAIL W37.
4. NINETY-FOUR (94) INCHES LONG.
5. EMBEDEDMENT FOR 1/2" AIR.
6. EMBEDEDMENT FOR 5/8" AIR.
7. 8" EMBEDEDMENT FOR 7/8" AIR.
8. IF (C) COLUMN IS INDICATED ON SECOND FLOOR, THE BASE CONNECTION IS HOT REQUIRED. (SEE INDICATED CALL OUT ON PLAN FOR ATTACHMENT).
9. SEE WOOD CONNECTIONS SECTION 44.00 COVER STUDS FOR CORROSION INFORMATION.
7. SAME NOMINAL SIZE PARALLEL COLUMNS (L&E) MAY BE SUBSTITUTED FOR ANY P.T.Y. SYP POST NOTED IN THE PLANS

COMMON NAIL vs. PNEUMATIC GUN APPLICATION:				
COMMON NAIL	DIA. / LENGTH	PNEUMATIC GUN NAIL DIA.-LENGTH	COMMON vs. GUN NAIL SPACING	APPLICATION
8d	0.131" X 2 1/2"	0.131" X 2 1/2"	SEE PLAN	SWEEPING ROOF & WALLS
10s OR 12d	0.148" X 3"	0.131" X 3"	SEE PLAN	BLOCKING & TOE NAILS & TOP PLATES
12d	0.148" X 3 1/4"	0.131" X 3 1/4"	8" O.C. (COMMON) 6" O.C. (GUN NAIL)	STUD WALL CORNERS
12d	0.148" X 3"	0.131" X 3"	8" O.C. (COMMON) 6" O.C. (GUN NAIL)	STUD PACE COLUMNS
16d	0.162" X 3 1/4"	0.131" X 3 1/4"	12" (COMMON) 3" (GUN NAIL)	SEE PLAN

## HEADER SCHEDULE

(IF USED, SEE DET, "HWR" ON SHEET S-2 FOR ENERGY STAR INSULATION ON HEADERS)

MARK	HEADER SIZE	REMARKS
H1	(2) - 2X6 S2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H2	(2) - 2X8 S2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H3	(2) - 2X10 S2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H4	(2) - 2X12 S2 SYP W/ 1/2" FLITCH PLATE	SEE GENERAL HEADER NOTE #5 THIS SHEET
H5	(2) - 134" X 11 1/4" LVL 2.0E (R=2600 PSI)	ATTACH TOGETHER W/ (2) ROWS 14" X 3 1/2" S2S W/ KINGS @ 16" O.C. TYP. EACH SIDE
H6	(2) - 134" X 9 1/4" LVL 2.0E (R=2600 PSI)	ATTACH TOGETHER W/ (2) ROWS 14" X 3 1/2" S2S W/ KINGS @ 16" O.C. TYP. EACH SIDE


**HEADER SUPPORT NO. OF JACKS &  
STUDS REQ. AT OPENINGS**

OPENING SIZE	2x4 WALL		2x6 OR 2x8 WALL	
	JACKS EA. END	KINGS EA. END	JACKS EA. END	KINGS EA. END
1'-0" - 3'-11"	(1)	(2)	(1)	(2)
4'-0" - 9'-11"	(2)	(3)	(2)	(3)
10'-0" - 16'-0"	(3)	(4)	(3)	(4)

### GENERAL HEADER NOTES

- VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED
- IF HEADER IS ON THE 1<sup>ST</sup> FLOOR SEE PLAN FOR BEARING WALL & TYPE AND FOLLOW INSTRUCTIONS FOR BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS AND ON PLAN
- IF HEADER IS ON THE 2<sup>ND</sup> FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR CONNECTIONS.
- ALL HEADER JACK AND KING STUDS SHALL BE NOTED TO EACH PER DETAIL W373
- FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12g COMMON NAILS AT 32" O.C. ALONG ENDS OR (3) ROWS IF 2X10 LARGER
- FASTEN ALL HEADERS TO KING STUDS WITH (3) 12d NAILS PER SIDE IF IF HEADER IS NOT SPECIFIED CONTACT E.O.R.


BEAM SCHEDULE		
MARK	BEAM SIZE	CONNECTIONS
EM1	(2) - 2 x 8 @ 2' S/P W/ 7' 18" GSS FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 120 NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
EM2	(2) - 2 x 10 @ 2' S/P W/ 7' 18" GSS FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 120 NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
EM3	(2) - 2 x 12 @ 2' S/P W/ 7' 18" GSS FLUTCH PLATE, NAIL BEAM TOGETHER USING (2) ROWS OF 120 NAILS @ 12" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
EM4	(2) - 1 3/4" x 11 1/4" LVL 2.05 FIB-2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SSS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
EM5	(2) - 1 3/4" x 11 7/8" LVL 2.05 FIB-2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SSS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
EM6	(2) - 1 3/4" x 18" LVL 2.05 FIB-2600 PSI, NAIL BEAM TOGETHER USING (2) ROWS 1/4" x 3 1/2" SSS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE	CONNECTION PROVIDE (2) SMIPSON LST424 OR (2) SMIPSON H5250 TO WOOD POST OR (2) SMIPSON HET416 TO CMU CL. U.N.O. ON ROOF PLATE.
<h2 style="text-align: center;">GENERAL BEAM NOTES</h2>		
<ol style="list-style-type: none"> <li>1. VERIFY WITH PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN. 4" BEARING EACH END).</li> <li>2. SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS.</li> <li>3. BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.</li> </ol>		



Y	N	MASTER BATH OPT.
		3'-4" X 4'-0" TEMP. FIXED GLS. WINDOW CNTR. ON TUB
		4030 (1) PC. FIBERGLAS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. DISC LT.

## OPT. FLOOR PLAN

SCALE: 1/4" = 1'-0"




## FLOOR PLAN

SCALE: 1/4" = 1'-0"

**NOTE:**

 INDICATES OPENINGS WIND PRESSURES. SEE WIND LOADING CRITERIA ON COVER SHEET FOR INFORMATION.

### WALL LEGEND






## GENERAL NOTES




- R302.2.1a (table 302.6) If water based ceiling texture material is used, provide 7/8" gypsum board for 16" O.C. Framing, or 5/8" gypsum board for 24" O.C. Framing. If mineral wool insulation and board may be used 1/2" O.C. 5/8" gypsum board, 5/8" Type "X" gypsum board must be installed on garage ceiling beneath habitable room(s).
- R302.2.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the garage from the living space shall be protected by a minimum No. 26 gages (0.45 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, or other approved material and shall not have openings into the garage.
- R302.5.1 Door from garage into house must be a minimum 1 3/4" thick solid wood door, or 1 3/4" thick honeycomb-core steel door, or 20 Minutes fire rated door, or 1 3/4" thick solid wood door.
- R302.7 Enclosed space under stairs that is accessed by a door or access panel shall have walls, under-stair surface and any soffits protected on the enclosed side with 1/2" gypsum board.
5. Outdoor swimming pool shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.
6. Bathroom exhaust fans must vent to the exterior of the building. Exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the roof if solid soffit is installed 5" O/C on each side of the venting.
7. R302.6 The garage shall be separated from the residence and its attic as required by Table R302.6. From the residence and attics by not less than 12-inch (12.7mm) gypsum board applied to the garage side. The finished basement shall be 1/2" (12.7mm) above all habitable rooms above by not less than 5/8" (15.9mm) Type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2" (12.7mm) gypsum board or equivalent.
- R312.2.1 Window sills. In dwelling units, where the bottom of the clear opening of an operable window opening is less than 44 inches (1118 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below the exterior of the building, the operable window shall comply with one of the following:
1. Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening when the opening is in its largest open position.
  2. Operable windows that are provided with window fall prevention devices that comply with ASTM F2050.
  3. Operable windows that are provided with window open control devices that comply with Section R312.2.2.
- R308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.
8. E.C. R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and sealed to be as level and equivalent to the insulation on the surrounding surfaces.
11. M1502 4.5 Duct Length  
The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502 4.5.1 through M1502 4.5.3  
Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer does not give instructions to not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings and not less than 1 foot (305 mm) from exhaust duct terminations shall be equipped with a backdraft damper. Screens shall not be installed at the duct termination.
12. Porch Ceilings: (See plan for the following options)  
Option 1. Gypsum:  
The gypsum board ceiling shall be attached w/ Type "W" 1/2" x 4" gypsum board 8" O.C. in field and edges.  
Option 2. Plaster Base:  
7/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screws shall 2" O.C. field and 4" edges.
13. Energy Code Compliance Plan Performance Based Pass Code cycle is FBC 2023 8th Edition:  
\* ALL INTERIOR AND EXTERIOR WALL FRAMING, INCLUDING ALL EXTERIOR WALLS, FLOORING STRIPS ON CMU WALLS, TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS	
1st FLOOR	2166 S.F.
TOTAL LIVING (AC)	2166 S.F.
GARAGE	418 S.F.
COVERED ENTRY (BASE)	155 S.F.
COVERED PATIO/LANAI	204 S.F.
TOTAL AREA UNDER ROOF	2943 S.F.










<b>FM01</b>	SINGLE STORY FTG	1/2" = 1'-0"	<b>FM02</b>	SECTION @ GARAGE	1/2" = 1'-0"	<b>FM25</b>	PORCH COLUMN W/ BRICK	1/2" = 1'-0"
-------------	------------------	--------------	-------------	------------------	--------------	-------------	-----------------------	--------------





<b>FM03</b>	THICKENED EDGE	1/2" = 1'-0"	<b>FM08</b>	2-STORY FTG.	1/2" = 1'-0"	<b>FM01A</b>	SINGLE STORY FTG	1/2" = 1'-0"
-------------	----------------	--------------	-------------	--------------	--------------	--------------	------------------	--------------





<b>FM09</b>	SECTION @ GAR. DOOR	1/2" = 1'-0"	<b>FM10</b>	INTERIOR BRG WALL	1/2" = 1'-0"	<b>FM02A</b>	SECTION @ GARAGE	1/2" = 1'-0"
-------------	---------------------	--------------	-------------	-------------------	--------------	--------------	------------------	--------------



<b>FM11</b>	STEP DOWN BRG.	1/2" = 1'-0"	<b>FM12</b>	STEP DOWN NON BRG.	1/2" = 1'-0"	RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.
-------------	----------------	--------------	-------------	--------------------	--------------	---



<b>FM14</b>	SECTION @ RECESS SHOWER	1/2" = 1'-0"	<b>FM18</b>	TYP. STEP FTG. DETAIL	1/2" = 1'-0"	LESS THAN 12 INCHES FROM THE FINISHED GRADE OR GROUND SURFACE WHERE APPLICABLE. THE DEPTH OF FOOTINGS SHALL ALSO CONFORM TO SECTION R403.1.4.1.
-------------	-------------------------	--------------	-------------	-----------------------	--------------	---




FM19	TYP. CORNER BAR DETAIL	1-1/2" = 1'-0"	FM23	TYP. FND PENETRATION	1/2" = 1'-0"	FOUND. SCHEDULE				
						MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. (lbs)

STEMWALL SCHEDULE							
STEMWALL HEIGHT (h)	FOOTING DIMENSION				NUMBER/SIZE OF BARS	LAT.	MAXIMUM F.C. SPACING (O.C.) IN STEM WALL
	d 1 STORY	d 2 STORY	b 1 STORY	b 2 STORY			
0'-0"-2'-0"	8"	10"	16"	20"	W/ (2) #5 BARS	<674#	6'-8"
>2'-0"-3'-4"	10"	10"	20"	24"	W/ (3) #5 BARS	674#	5'-4"
>3'-4"-4'-0"	12"	12"	32"	32"	W/ (4) #5 BARS	845#	4'-0"
>4'-0"-5'-4"	16"	16"	48"	48"	W/ (5) #5 BARS CONT. & #5 @ 18" O.C. TRANS.	1,162#	2'-8"


NOTES:

1. VERTICAL REINF. IN SOLID GROUTED CELLS AT ALL CORNERS, JAMBS, WALL INTERSECTIONS, BELOW GIRDER TRUSS LOCATIONS, AND AT THE MAXIMUM SPACING STATED IN SCHEDULE
2. W.W.M. IS REQUIRED TO MAKE ADEQUATE CONNECTION BETWEEN SLAB AND WALL WHEN STEM WALL EXCEEDS 4'-0" FIBERMESH CAN NOT BE USED AND #4 TURN BARS ARE REQUIRED @ EACH FILLED CELL LOCATION. EACH BAR TO TURN INTO VERTICAL BAR AND EXTEND OUT A MIN. 4'-0" INTO SLAB/ STEM
3. IF STEM IS REQ'D TO BE HIGHER CONTACT ENGINEER OF RECORD PRIOR TO CONSTRUCTION FOR MORE INFORMATION!
4. G.C. TO PROVIDE ADEQUATE BRACING OF STEM WALL WHEN UNEVEN BACK FILLING IS TAKING PLACE.
5. #5 HORIZONTAL CORNER BARS WITH 4'-0" LEGS IN KNOCKOUT BLOCK @ 16" O.C. VERTICAL. GROUTED SOLID WHEN STEM WALL IS GREATER THAN 4'-0" TALL (TYPICAL ALL CORNERS)
6. IF STEM WALL IS WITH IN 4'-0" OF POOL OR WATER FEATURE FOUNDATIONS TO BE A MINIMUM 12" BELOW BOTTOM OF POOL OR WATER FEATURE
7. ALL STEM WALLS GREATER THAN (4) COURSES SHALL BE FULLY GROUTED.
8. R.403.1.4 MINIMUM DEPTH: ALL EXTERIOR FOOTINGS (BOTTOM) SHALL BE PLACED AT LEAST 12" BELOW THE UNDISTURBED GROUND SURFACE.
- SEE CHART ABOVE  
STEM WALL F.G.  
SPACING
- (1) #5 CONT. TIED TO EACH VERT. REINF. BAR.
- #4 TURN BAR AT STEM WALLS GREATER THAN 4'
- IF USED: W.W.M. TO BE TIED TO #5 CONT. REBAR
- COMPACTED CLEAN FILL
- SEE SCHEDULE FOR REINF.
- EXTERIOR SHORING BY CONTRACTOR AS REQ'D WHEN STEM WALL IS OVER 4'-0"
- FINISH GRADE
- MIN. 8" COVER REQ'D
- 3" COVER TYP.
- h"  
d  
b



FOOTING SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. [lbs]
F1.0	1'-0" X CONT.	1'-0"	2 #5 E.W. BOT.	2000
F2.0	2'-0" X 2'-0"	1'-0"	3 #5 E.W. BOT.	7200
F2.5	2'-6" X 2'-6"	1'-0"	3 #5 E.W. BOT.	11000
F3.0	3'-0" X 3'-0"	1'-0"	4 #5 E.W. BOT.	15600
F3.5	3'-6" X 3'-6"	1'-0"	4 #5 E.W. BOT.	21500
F4.0	4'-0" X 4'-0"	1'-0"	5 #5 E.W. BOT.	28000
F4.5	4'-6" X 4'-6"	1'-4"	5 #5 E.W. BOT.	34500
F5.0	5'-0" X 5'-0"	1'-4"	6 #5 E.W. BOT.	42500
F6.0	6'-0" X 6'-0"	1'-4"	7 #5 E.W. BOT.	61500

LEGEND	
	- INDICATES SINGLE-STORY FOOTING
	- INDICATES TWO-STORY FOOTING
	- INDICATES PAD FOOTING



# FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

ELEVATION "A" & "B"



## LOAD CALCULATIONS

### COOLING GREATER THAN HEATING

#### GENERAL LIGHTING & RECEPTACLES

3 WATTS PER SQUARE FOOT OF LIVING

$$\text{S.F. LIVING} = \frac{2,166 \times 3}{6498}$$

#### APPLIANCE CIRCUITS

RANGE	8500
OVEN	NONE
MICRO / HOOD	1000
WATER HEATER	4500
WHIRL POOL	1250
WASHER	1500
DRYER	5000
DISHWASHER	1500
DISPOSAL	600
SMALL APPLIANCE CIRCUITS (3)	4500
BATH FANS (100 WATTS / EACH)	300


$$\begin{aligned} \text{GEN LIGHT'G \& RECEPT. + APP. CIR.} &= 35,048 \\ \text{SUBTRACT 100 \% OF FIRST 10,000} &= 10,000 \\ \mathbf{A} &= 25,048 \end{aligned}$$

#### HVAC CIRCUITS


A/C (AIR HANDLER & COMP.)	10,000
A/C (AUXILIARY HEAT STRIP)	10,000
<b>B</b>	20,000

#### CIRCUIT CALCULATIONS


FIRST 10,000 AMPS @ 100%	= 10,000
+ 40% OF "A" = (.40 x 25,048)	= 10,019
+ 100% OF "B" = (20,000)	= 20,000
TOTAL WATTAGE	= 40,019
WATTS DIVIDED BY 240 = AMPS	
CALCULATED SERVICE AMPS	= 167




**FM24** PROTECTION BARRIER N.T.S.



**FM24.1** ALTERNATIVE PROTECTION BARRIER N.T.S.



**2169 PLUMBING RISER**



## ELECTRICAL PLAN


SCALE: 1/4" = 1'-0"  
ELEVATION "A" & "B"

## ELECTRICAL NOTES:

- UNLESS OTHERWISE NOTED.
1. ELECTRICAL OUTLET HEIGHTS AS MEASURED FROM FINISHED FLOOR TO CENTER LINE OF THE BOX TO BE: 16" AFF (GENERAL), IN A FLOOD ZONE, ALL ELECTRICAL EQUIPMENT TO BE AT OR ABOVE DFE.  
KITCHEN: 44" AFF  
BATHROOM: 39" AFF  
LAUNDRY ROOM: 36" AFF  
EXTERIOR WATERPROOF: 12" AFF  
GARAGE: GENERAL PURPOSE 42" AFF  
RANGE: 2" AFF
  2. ALL TRIM PLATES AND DEVICES TO BE GANGED, WHERE POSSIBLE.
  3. ELECTRICAL SWITCHES TO BE AT 42" CENTERLINE ABOVE FINISHED FLOOR.
  4. ELECTRICAL PLAN IS INTENDED FOR BID PURPOSES ONLY. ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC), LATEST EDITION, BY A LICENSED ELECTRICAL CONTRACTOR WHO SHALL BE RESPONSIBLE FOR THE INSTALLATION & SIZING OF ALL ELECTRICAL WIRING & ACCESSORIES.
  5. SMOKE ALARMS SHALL COMPLY WITH NFPA 72 AND SECTION R314 AND SHALL BE LISTED IN ACCORDANCE WITH UL 217, COMBINATION SMOKE AND CARBON MONOXIDE ALARMS SHALL BE LISTED IN ACCORDANCE WITH UL 217 AND UL 2034.
  6. PROVIDE AFCI'S (ARC-FAULT CIRCUIT INTERRUPTERS) COMBINATION TYPE INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUITS IN ALL DWELLING UNITS PER NFPA 70 (CURRENT EDITION) AND THE NEC AND AS DEFINED IN ILL 1699.
  7. PROVIDE TAMPER RESISTANT RECEPTACLES AS REQUIRED BY THE NFPA 70 (CURRENT EDITION).
  8. CARBON MONOXIDE PROTECTION: CARBON MONOXIDE ALARMS OR DETECTORS SHALL BE INSTALLED IN ALL DWELLING UNITS IN ACCORDANCE WITH IFC R315 AND NFPA 70. SUCH DEVICES SHALL BE LISTED BY THE APPROPRIATE STANDARD, EITHER ANSI/UL 2034, STANDARD FOR SINGLE AND MULTIPLE STATION CO ALARMS OR UL 2075, GAS AND VAPOR DETECTOR SENSOR, ACCORDING TO THE INSTALLATION.
  9. RESID. I-2 COMBINATION ALARMS: COMBINATION SMOKE/CARBON MONOXIDE ALARMS SHALL BE LISTED AND LABELED BY A NATIONALLY RECOGNIZED TESTING LABORATORY.
  10. KEEP ALL SMOKE DETECTORS MINIMUM OF 36" FROM BATHROOM DOORS.
  11. IN NEW CONSTRUCTION, SMOKE DETECTORS SHALL BE HARDWIRED INTO AN A/C ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTERY BACKUP.
  12. BATHROOM EXHAUST FANS MUST VENT TO THE EXTERIOR OF THE BUILDING, VENTILATION TO ATTIC SPACE AND SOFFITS IS NOT ACCEPTABLE.
  13. CHAPTER 45 PRIVATE SWIMMING POOLS — OUTDOOR SWIMMING POOLS SHALL BE PROVIDED WITH A BARRIER COMPLYING WITH R4501.17.1.1 THROUGH R4501.17.1.14.
  14. ADD GFCI PROTECTION TO RECEPTACLES IN LAUNDRY ROOMS AND UTILITY ROOMS OF DWELLINGS WHERE INSTALLED WITHIN 6' OF THE OUTSIDE EDGE OF A SINK. THIS WOULD INCLUDE THE RECEPTACLE INSTALLED FOR A WASHING MACHINE. RECEPTACLE OUTLETS SHALL NOT BE REQUIRED ON A WALL DIRECTLY BEHIND A RANGE OR SINK TO FULFILL THE REQUIREMENT OF AN OUTLET EVERY 24". THE WIDTH OF THE SINK OR RANGE IS NOT TO BE INCLUDED IN THE SPACING OF THE OUTLETS UNLESS THE DISTANCE FROM THE SINK OR RANGE IS GREATER THAN 12" FOR STRAIGHT COUNTER TOPS AND 18" FOR SINKS AND RANGES INSTALLED IN CORNER COUNTERS.
  15. WHERE MORE THAN ONE SMOKE ALARM IS REQUIRED TO BE INSTALLED WITHIN AN INDIVIDUAL DWELLING UNIT IN ACCORDANCE WITH SECTION R314.3, THE ALARM DEVICES SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTUATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE INDIVIDUAL DWELLING UNIT. PHYSICAL INTERCONNECTION OF SMOKE ALARMS SHALL NOT BE REQUIRED WHERE LISTED WIRELESS ALARMS ARE INSTALLED AND ALL ALARMS SOUND UPON ACTIVATION OF ONE ALARM.
  16. FOR ONE AND TWO-FAMILY DWELLING UNITS, ALL SERVICE CONDUCTORS SHALL TERMINATE IN DISCONNECTING MEANS HAVING A SHORT-CIRCUIT CURRENT RATING EQUAL TO OR GREATER THAN THE AVAILABLE FAULT CURRENT, INSTALLED IN A READILY ACCESSIBLE OUTDOOR LOCATION. EACH DISCONNECT SHALL BE ONE OF THE FOLLOWING:  
(1) SERVICE DISCONNECTS MARKED AS FOLLOWS:  
EMERGENCY DISCONNECT.  
(2) METER DISCONNECTS (INSTALLED PER 230.82(3) AND MARKED AS FOLLOWS:  
EMERGENCY DISCONNECT.  
METER DISCONNECT.  
NOT SERVICE EQUIPMENT  
(3) OTHER LISTED DISCONNECT SWITCHES OR CIRCUIT BREAKERS ON THE SUPPLY SIDE OF EACH SERVICE DISCONNECT THAT ARE SUITABLE FOR USE AS SERVICE EQUIPMENT AND MARKED AS FOLLOWS:  
EMERGENCY DISCONNECT.  
NOT SERVICE EQUIPMENT
  17. ALL PERMANENTLY INSTALLED LUMINAIRES, EXCLUDING THOSE IN KITCHEN APPLIANCES, SHALL HAVE AN EFFICACY OF AT LEAST 45 LUMENS/PERWATT OR SHALL UTILIZE LAMPS WITH AN EFFICACY OF NOT LESS THAN 65 LUMENS/PERWATT.

## ELECTRICAL LEGEND

\$ SINGLE POLE SWITCH	SMOKE DETECTOR
\$2 DOUBLE POLE SWITCH	CARBON MONOXIDE/ SMOKE DETECTOR COMBO UNIT
\$3 THREE-WAY SWITCH	FLOOD LIGHT
\$4 FOUR-WAY SWITCH	FLUORESCENT LIGHTING
\$DM DIMMER SWITCH	CEILING MOUNTED FIXTURE
CEILING MOUNTED FIXTURE	TRACK LIGHTING
SCOUNCE (WALL MOUNTED) FIXTURE	CEILING FAN
110 VOLT DUPLEX OUTLET	DOOR BELL CHIMES
110 VOLT SPLIT SWITCHED OUTLET	DOOR BELL
GROUND FAULT INTERRUPT	DISPOSAL
WP WATER PROOF W/ GROUND FAULT	DISCONNECT SWITCH
220 VOLT OUTLET	PREWIRE SPEAKER
SPECIAL SERVICES OUTLET	JUNCTION BOX
T.V. CABLE OUTLET	THERMOSTAT
TELEPHONE CABLE OUTLET	LOW VOLTAGE LIGHTING
RECESSED LIGHTING	INTERCOM SYSTEM
WP RECESSED LIGHTING	GARAGE DOOR PUSH BUTTON
BATH FAN	
BATH FAN W/ LIGHT	
L.E.D. DISC LIGHT	




## ELECTRICAL RISER

NOTE:  
ELECTRICAL MATERIAL AND INSTALLATIONS SHALL COMPLY WITH APPLICABLE PROVISIONS AS STATED ON STRUCTURAL NOTES SHEET LOCAL CODES AND THE LOCAL POWER CO.

COUNTY  
SEAL

Thursday, September 5, 2024



100 WEST GARDEN STREET  
PENSACOLA FL 32502

DIVISION LOCATION:  
GAINESVILLE

Job Information:

INVENTORY  
LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY

Model Name / Number:

2169


Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
24-10573


Sheet: 4 Of:

ELECTRICAL






LEFT ELEVATION "A"  
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION "A"  
SCALE: 1/4" = 1'-0"



REAR ELEVATION  
SCALE: 1/4" = 1'-0"



SECTION @ ENTRY  
SCALE: 1/4" = 1'-0"



FRONT ELEVATION "A"  
SCALE: 1/4" = 1'-0"

VENTILATION CALCULATION	
Formula = SF / 300 / 2 * 144 = net sq inches of venting needed equally for intake and exhaust	
Soffit product provides	4.12 net sq in / sf
Ridge vent provides	18.00 net sq in / lf
Off ridge vent provides	138.00 net sq in / sf
Overhang distance	2.00 ft
S.F. of Area to be vented (SF)	2943 s.f.
Total needed for exhaust for upper 1/3	706 net sq inches
Total needed for intake (soffit area, lower)	706 net sq inches
Number of Off Ridge Vents for upper 1/3 needed	5
L.F. of Ridge Vent needed (can be used in combo with ORV)	39
Lineal Feet of Soffit needed to meet required	86
Lineal S.F. provided by plan	220

COUNTY  
SEAL

Thursday, September 5, 2024

www.fdseng.com

**FDS**

ENGINEERING ASSOCIATES

288 Seaboard Lane, Suite 200  
Pensacola, Florida 32504  
(904) 840-2335  
Certificate of Accreditation No. 9481

Keese Associates  
ARCHITECTURE | DESIGN | PLANNING  
22507 86th Ave, Maitland, FL 32751, Suite 200  
(407) 880-2335  
keeseassociates.com

AA26003115

AB

in f b e

To the best of the Engineer's knowledge, information, and belief, this document complies with the current Florida Building Code, Engineering Law and Rules, and all applicable codes and regulations. The Engineer's signature is required on all drawings and specifications. The Engineer's seal is required on all drawings and specifications. The Engineer's stamp is required on all drawings and specifications. The Engineer's stamp is required on all drawings and specifications.

☐ CARL A. BROWN, P.E. FL # 55126  
☐ SCOTT A. LEWOWSKI, P.E. FL # 78750  
☐ THIEN BAO DUONG, P.E. FL # 94452

**DAMS HOMES**

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

**100 WEST GARDEN STREET  
PENSACOLA FL 32502**

**DIVISION LOCATION:**  
GAINESVILLE

**INVENTORY**

LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY

Model Name / Number:  
**2169**

Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
**24-10573**


Sheet: **5** OF

**ELEVATIONS-A**












**TB15** EXTERIOR NON-BEARING WALL DETAIL N.T.S.




**WC04** GARAGE HEADER ANCHOR 3/4" = 1'-0"




**WC05** SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.




**WF64** EXTERIOR NON BRG. WALL DETAIL N.T.S.




**WF43** EXTERIOR ANGLED WALL DETAIL N.T.S.




**WC03** WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"




**CD11** COMMON BEAM ATTACHMENT N.T.S.




**CD25** BEAM TO WALL CONNECTION N.T.S.




**WF66** TYPICAL BEARING WALL N.T.S.




**WC09** WALL STEP @ CORNER N.T.S.




**WC06** EXTERIOR FRAME CORNER 3/4" = 1'-0"



**RD01** VALLEY FLASHING DETAIL N.T.S.



**CD26** GIRDER BASE CONNECTION 1/2" = 1'-0"



**WF68** CORNER CONNECTION N.T.S.

COUNTY SEAL

www.FDSeng.com

**FDS**

ENGINEERS & ARCHITECTS

255 Seaboard Lane, Suite 200  
Maitland, Florida 32751  
Tel: 407.980.2325  
Fax: 407.980.2325  
License No. 9361

www.keesee.com

**keesee** associates

ARCHITECTURE | DESIGN | PLANNING

2407 Ysabel Street, Suite 200  
Maitland, FL 32751  
Tel: 407.980.2325  
Fax: 407.980.2325  
www.keesee.com

AA26003115

FL # 66126  
FL # 78750  
FL # 94452

Carl A. Brown, P.E.  
Scott A. Lemkowski, P.E.  
Thien Bao Duong, P.E.

**DAMS HOMES**

FLORIDA CONTRACTORS LICENSE NO. CRC13301416

100 WEST GARDEN STREET  
PENSACOLA FL 32502

DIVISION LOCATION:  
GAINESVILLE

Job Information:

Model Name / Number:  
**2169**

Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
**24-10573**

Sheet: **S-2** of:


TYPICAL FRAMING DETAILS

INVENTORY


LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY

Thursday, September 5, 2024






**WF39** TRANSOM DETAIL AT ENTRY 1/2" = 1'-0"



**WF09** WALL HEADER DETAIL N.T.S.



**WF67** WALL FRAMING 3/4" = 1'-0"

To the best of the Engineer's knowledge, information, and belief, the preparation of these drawings complies with the minimum requirements of the Florida Building Code, and the design and construction of the project complies with the current Florida Building Code. Engineer's seal and stamp are only valid if the engineer's registration is current and in good standing with the State of Florida.

**FDS**  
ENGINEERING ASSOCIATES  
255 Seaboard Lane, Suite 200  
Maitland, Florida 32751  
Tel: 407.966.2204  
Fax: 407.966.2204  
Certificate of Authorization No. 9361

☐ CARL A. BROWN, P.E.  
☐ SCOTT A. LEWIS, P.E.  
☐ THIEN BAO DUONG, P.E.

www.fdseng.com

**keese**  
associates  
ARCHITECTURE | DESIGN | PLANNING  
25407 YSBO 2355  
g@keese.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

**DIVISION LOCATION:**  
GAINESVILLE

**Job Information:**

**INVENTORY**

LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY

Model Name / Number:  
**2169**












Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
**24-10573**

Sheet: **S-2.1** Of:

TYPICAL FRAMING  
DETAILS





COUNTY  
SEAL

**keese**  
associates  
ARCHITECTURE | DESIGN | PLANNING  
2250 W. 11th Avenue, Suite 200  
Gainesville, FL 32609  
352.380.2355  
goveesee.com

**FDS**  
ENGINEERING ASSOCIATES  
2250 W. 11th Avenue, Suite 200  
Gainesville, FL 32609  
352.380.2355  
Certificate of Authorization No. 9481

FL # 86126  
FL # 78750  
FL # 94452

Carla A. Brown, P.E.  
Scott A. Lewkowksi, P.E.  
Then Bao Duong, P.E.

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330148  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

**DIVISION LOCATION:**  
GAINESVILLE

**INVENTORY**  
LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY

Model Name / Number:  
**2169**

Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
**24-10573**

Sheet: **S-3** Of:


TYPICAL WALL DETAILS

Thursday, September 5, 2024












**GE05** GABLE END BRACING - FRAME WALL N.T.S.




**GE22** GABLE END BRACING w/ VOL CEILING 1/2"=1'-0"




**GE23** GABLE END BRACING w/o VOLUME CEILING 1/2"=1'-0"




**GE24** GABLE @ VAULT N.T.S.




**WF72** LEDGER N.T.S.




**WF73** KNEEWALL @ DORMER N.T.S.





**GE21** SECTION @ DUTCH GABLE 3/4"=1'-0"



**LD02** SHEAR TRANSFER EXTERIOR WALL N.T.S.



**GE23.1** GABLE END OVERHANG 1/2"=1'-0"



**SR01** SECTION AT SHED ROOF 3/4"=1'-0"

COUNTY  
SEAL

Thursday, September 5, 2024

To the best of the Engineer's knowledge, information, and belief, the design complies with all applicable codes, regulations, and standards, and the Engineer is not providing any warranty or guarantee of performance or results. The Engineer's responsibility is limited to the design and construction of the project as shown on the drawings and as approved by the local building department.

**FDS ENGINEERING ASSOCIATES**  
255 South Lake Ave., Suite 200  
Tampa, Florida 33606  
Tel: 813.255.1234  
Fax: 813.255.1235  
www.fdseng.com

**keesee associates**  
ARCHITECTURE | DESIGN | PLANNING  
22407 SBO 2355  
Gainesville, FL 32651  
Tel: 352.751.3275  
www.keesee.com

**DAMS HOMES**  
FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

**DIVISION LOCATION:**  
GAINESVILLE

**Job Information:**

**Model Name / Number:**  
2169

**Plan Issue Date:**  
Thursday, September 5, 2024


**KA PROJECT NUMBER:**  
24-10573

**Sheet:**  
S-4.1

**Of:**  
08

**ROOF FRAMING AND BRACING DETAILS**






- HEAD FLASHING TIE-IN INSTRUCTIONS:
1. Cut, fold up & temporarily secure weather resistive barrier above header to allow for flashing installation
  2. Self-adhered flashing plus head flashing under weather resistive barrier
  3. Fold weather resistive barrier back over head flashing and seal with tape

SELF-ADHERED FLASHING  
FLASHING INSTALLATION AFTER WEATHER RESISTIVE BARRIER


Scale: NTS

WP01




SELF-ADHERED FLASHING  
HALF ROUND WINDOW

WP04



SELF-ADHERED FLASHING  
W0.8362x;DECK JOIST


WP07



- NOTES:
1. INSTALL WINDOW PER MANUFACTURER'S RECOMMENDATION AND USE APPROPRIATE SEALANT FOR WINDOW AND WOOD BUCK
  2. WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.


RECESSED WINDOW

WP10




SELF-ADHERED FLASHING  
EXTERIOR DOOR WITH DECK - SECTION A

WP02




SELF-ADHERED FLASHING  
EXTERIOR DOOR WITH DECK

WP05



SELF-ADHERED FLASHING  
OUTSIDE CORNER


WP08



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
  2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.


WALL-TO-WALL OUTSIDE CORNER

WP11




TIE-IN WITH VINYL SIDING  
AT WINDOW SILL

WP03



SELF-ADHERED FLASHING  
INSIDE CORNER

WP06



- NOTES:
1. EXTEND SELF-ADHERED FLASHING BEYOND JOINT BETWEEN SIDING AND CORNER POST/BOARDS.
  2. INSTALL SELF-ADHERED FLASHING ON OUTSIDE CORNER FOR THE HEIGHT OF THE WALL.

WALL-TO-WALL INSIDE CORNER

WP12

THESE DETAILS ARE GENERIC AND MEANT TO SHOW  
GENERAL FLASHING AND WATERPROOFING METHODS  
TO BE USED.

## SELF-ADHERED FLASHING PRODUCTS DETAILS

TWO LAYERS OF FELT OR ONE LAYER OF HOUSE WRAP AND  
ONE LAYER OF FELT ARE REQUIRED BEHIND STUCCO. FBC R703.2

### DETAIL INSTRUCTIONS

REFER TO THE NUMBER MARKED AS (#) IN EACH DETAIL THAT  
CORRESPONDS TO THE NUMBERED ITEMS IN THE LIST OF  
INSTRUCTIONS BELOW:

1. INSTALL SELF-ADHERED FLASHING IN ORDER AS SHOWN BY NUMBERS.
2. INSTALL FLASHING AND WEATHER RESISTIVE BARRIER TO FORM WATER-SHEDDING LAPS.
3. SELF-ADHERED FLASHING CAN BE SUBSTITUTED FOR BUILDING PAPER.
4. SPLIT THE RELEASE PAPER USING THE RIPCORD (SPLIT RELEASE ON DEMAND, EMBEDDED IN THE ADHESIVE LAYER) - FOR EASE OF INSTALLATION AND TO MINIMIZE SCORING CUTS.
5. REMOVE ALL RELEASE PAPER PER STANDARD INSTALLATION INSTRUCTIONS AND ADHERE TO SUBSTRATE USING A SQUARE PIECE OF FLASHING MATERIAL (6" X 6" MINIMUM).
6. FOLD AS SHOWN BY ARROWS.
7. ANGLE OF CORNER MAY VARY, ADJUST FOLDING OF THE FLASHING ACCORDINGLY TO FIT TIGHT TO CORNER.
8. MECHANICALLY FASTEN AS NECESSARY.

## FLASHING REQUIREMENTS

R703.1 GENERAL. EXTERIOR WALLS SHALL PROVIDE THE BUILDING WITH A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE. THE EXTERIOR WALL ENVELOPE SHALL INCLUDE FLASHING AS DESCRIBED IN SECTION R703.4. A WATER-RESISTIVE BARRIER IS DESCRIBED AS A MATERIAL, BEHIND AN EXTERIOR WALL COVERING THAT IS INTENDED TO RESIST LIQUID WATER THAT HAS PENETRATED BEHIND THE EXTERIOR COVERING FROM FURTHER INTRUDING INTO THE EXTERIOR WALL ASSEMBLY. AN EXTERIOR WALL COVERING IS DESCRIBED AS A MATERIAL OR ASSEMBLY OF MATERIALS APPLIED ON THE EXTERIOR SIDE OF EXTERIOR WALLS FOR THE PURPOSE OF PROVIDING A WEATHER-RESISTIVE BARRIER, INSULATION, OR FOR AESTHETICS, INCLUDING BUT NOT LIMITED TO, VENEERS, SIDING, EXTERIOR INSULATION AND FINISH SYSTEMS, ARCHITECTURAL TRIM AND EMBELLISHMENTS SUCH AS CORNICES, SOFFITS, AND FASCIAS.

R703.2 WATER-RESISTIVE BARRIER. ONE LAYER OF NO. 15 ASPHALT FELT, FREE FROM HOLES AND BREAKS, COMPLYING WITH ASTM D2286 FOR TYPE I FELT OR OTHER APPROVED WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS. SUCH FELT OR MATERIAL SHALL BE APPLIED HORIZONTALLY, WITH THE UPPER LAYER LAPPED OVER THE LOWER LAYER NOT LESS THAN 2 INCHES (51 MM) WHERE JOINTS OCCUR. FELT SHALL BE LAPPED NOT LESS THAN 6 INCHES (152 MM). THE FELT OR OTHER APPROVED MATERIAL SHALL BE CONTINUOUS TO THE TOP OF WALLS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES IN A MANNER TO MEET THE REQUIREMENTS OF THE EXTERIOR WALL ENVELOPE AS DESCRIBED IN SECTION R703.1.

R703.7.3 WATER-RESISTIVE BARRIERS SHALL BE INSTALLED AS REQUIRED IN SECTION R703.2 AND, WHERE APPLIED OVER WOOD-BASED SHEATHING, SHALL INCLUDE A WATER-RESISTIVE VAPOR-PERMEABLE BARRIER WITH A PERFORMANCE AT LEAST EQUIVALENT TO TWO LAYERS OF GRADE D PAPER. THE INDIVIDUAL LAYERS SHALL BE INSTALLED INDEPENDENTLY SUCH THAT EACH LAYER PROVIDES A SEPARATE CONTINUOUS PLANE AND ANY FLASHING (INSTALLED IN ACCORDANCE WITH SECTION R703.4) INTENDED TO DRAIN TO THE WATER-RESISTIVE BARRIER IS DIRECTED BETWEEN THE LAYERS.

EXCEPTION: WHERE THE WATER-RESISTIVE BARRIER THAT IS APPLIED OVER WOOD-BASED SHEATHING HAS A WATER RESISTANCE EQUAL TO OR GREATER THAN THAT OF 60-MINUTE GRADE D PAPER AND IS SEPARATED FROM THE STUCCO BY AN INTERVENING, SUBSTANTIALLY NONWATER-ABSORBING LAYER OR DESIGNED DRAINAGE SPACE.

R703.4 FLASHING. APPROVED CORROSION-RESISTANT FLASHING SHALL BE APPLIED SHINGLE-FASHION IN A MANNER TO PREVENT ENTRY OF WATER INTO THE WALL CAVITY OR PENETRATION OF WATER TO THE BUILDING STRUCTURAL FRAMING COMPONENTS. SELF-ADHERED MEMBRANES USED AS FLASHING SHALL COMPLY WITH AAMA 711. ALL EXTERIOR PENETRATION PRODUCTS SHALL BE SEALED AT THE JUNCTURE WITH THE BUILDING WALL WITH A SEALANT COMPLYING WITH AAMA 800 OR ASTA C300 CLASS 25 GRADE NS OR GREATER FOR PROPER JOINT EXPANSION AND CONTRACTION. ASTM C1281, AAMA 812, OR OTHER APPROVED STANDARD AS APPROPRIATE FOR THE TYPE OF SEALANT. FLUID-APPLIED MEMBRANES USED AS FLASHING IN EXTERIOR WALLS SHALL COMPLY WITH AAMA 714. THE FLASHING SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH. APPROVED CORROSION-RESISTANT FLASHINGS SHALL BE INSTALLED AT THE FOLLOWING LOCATIONS:

1. EXTERIOR WINDOW AND DOOR OPENINGS. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL EXTEND TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER-RESISTIVE BARRIER COMPLYING WITH SECTION 703.2 FOR SUBSEQUENT DRAINAGE. MECHANICALLY ATTACHED FLEXIBLE FLASHINGS SHALL COMPLY WITH AAMA 712. FLASHING AT EXTERIOR WINDOW AND DOOR OPENINGS SHALL BE INSTALLED IN ACCORDANCE WITH ONE OR MORE OF THE FOLLOWING:
  - 1.1 THE FENESTRATION MANUFACTURER'S INSTALLATION AND FLASHING INSTRUCTIONS, OR FOR APPLICATIONS NOT ADDRESSED IN THE FENESTRATION MANUFACTURER'S INSTRUCTIONS, IN ACCORDANCE WITH THE FLASHING MANUFACTURER'S INSTRUCTIONS, WHERE FLASHING INSTRUCTIONS OR DETAILS ARE NOT PROVIDED. PAN FLASHING SHALL BE INSTALLED AT THE SILL OF EXTERIOR WINDOW AND DOOR OPENINGS. PAN FLASHING SHALL BE SEALED OR SLOPED IN SUCH A MANNER AS TO DIRECT WATER TO THE SURFACE OF THE EXTERIOR WALL FINISH OR TO THE WATER RESISTIVE BARRIER FOR SUBSEQUENT DRAINAGE. OPENINGS USING PAN FLASHING SHALL INCORPORATE FLASHING OR PROTECTION AT THE HEAD AND SIDES.
  - 1.2. IN ACCORDANCE WITH THE FLASHING DESIGN OR METHOD OF A REGISTERED DESIGN PROFESSIONAL.
  - 1.3. IN ACCORDANCE WITH OTHER APPROVED METHODS.
  - 1.4. IN ACCORDANCE WITH FMA/AAMA 100, FMA/AAMA 200, FMA/WDMA 250, FMA/AAMA/WDMA 300 OR FMA/AAMA/WDMA 400.
2. AT THE INTERSECTION OF CHIMNEYS OR OTHER MASONRY CONSTRUCTION WITH FRAME OR STUCCO WALLS, WITH PROJECTING LIPS ON BOTH SIDES UNDER STUCCO CORNICES.
3. UNDER AND AT THE ENDS OF MASONRY, WOOD OR METAL COPINGS AND SILLS.
4. CONTINUOUSLY ABOVE ALL PROJECTING WOOD TRIM.
5. WHERE EXTERIOR PORCHES, DECKS OR STAIRS ATTACH TO A WALL OR FLOOR ASSEMBLY OF WOOD-FRAME CONSTRUCTION.
6. AT WALL AND ROOF INTERSECTIONS.
7. AT BUILT-IN GUTTERS.

FIGURE 1: FLASHING INSTALLATION

ASPHALT SEALANT:  
EXTEND MIN. OF 6"  
OUTSIDE OF FLASHING






FIGURE 2: WALL FINISH

TEXTURED, PAINTED  
EXTERIOR WALL FINISH



FLASHING INSTALLATION  
WHERE ROOF MEETS VERTICAL WALL

FIGURE 3: CORNER DETAIL



FLASHING DETAIL AT CRICKET  
/ KNEEWALL INTERSECTION

www.FDSeng.com

**FDS**  
ENGINEERING ASSOCIATES

255 South Main Street, Suite 200  
Tallahassee, Florida 32301  
Phone: 904.225.4000  
Fax: 904.225.4001  
Email: info@fdseng.com

Professional Engineer  
No. 1251  
Professional Engineer  
No. 1251

Carl A. Brown, P.E.  
Scott A. Lebowitz, P.E.  
Then Bao Duong, P.E.

Florida Professional Engineer  
No. 1251

Florida Professional Engineer  
No. 1251

Florida Professional Engineer  
No. 1251

**keesee**  
associates  
ARCHITECTURE | DESIGN | PLANNING

22401 SEBASTIAN AVE., SUITE 200  
GAINESVILLE, FL 32609  
954.886.3333  
www.keesee.com

FLORIDA CONTRACTORS LICENSE NO. CRC1330146  
100 WEST GARDEN STREET  
PENSACOLA FL 32502

DIVISION LOCATION:  
GAINESVILLE

Job Information:

Model Name / Number:  
**2169**

Plan Issue Date:  
Thursday, September 5, 2024

KA PROJECT NUMBER:  
**24-10573**

Sheet: **WP** Of: **WP**

WATER PROOF  
DETAILS

LOT: 89  
BLK:  
SEC:  
SUB: PRESERVE AT LAUREL LAKE  
297 SW SILVER PALM DRIVE  
LAKE CITY