

DATE 01/12/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000022692

APPLICANT CHRIS COX PHONE 867-0633
ADDRESS P.O. BOX 815 LAKE CITY FL 32056
OWNER CORNERSTONE DEVELOPMENT GROUP/ZECHER PHONE 752-8653
ADDRESS 165 SE VICTORIA GLEN LAKE CITY FL 32055
CONTRACTOR BRYAN ZECHER PHONE 752-8653
LOCATION OF PROPERTY BAYA AVE, TR ON OLD COUNTRY CLUB ROAD, 3 MILES ON LEFT, TL
ON VIUCTORIA GLEN, 1ST LOT ON LEFT
TYPE DEVELOPMENT SFD,UTILITY ESTIMATED COST OF CONSTRUCTION 75000.00
HEATED FLOOR AREA 1500.00 TOTAL AREA 1974.00 HEIGHT .00 STORIES 1
FOUNDATION CONC WALLS FRAMED ROOF PITCH 6/12 FLOOR SLAB
LAND USE & ZONING RSF-2 MAX. HEIGHT 19
Minimum Set Back Requirments: STREET-FRONT 25.00 REAR 15.00 SIDE 10.00
NO. EX.D.U. 0 FLOOD ZONE X PP DEVELOPMENT PERMIT NO.

PARCEL ID 15-4S-17-08359-016 SUBDIVISION COUNTRY SIDES ESTATES
LOT 1 BLOCK PHASE UNIT TOTAL ACRES .50

000000501 CBC054575
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
CULVERT PERMIT 04-0731-N BK RJ Y
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ONE FOOT ABOVE THE ROAD, NOC ON FILE

Check # or Cash 1097

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$ 375.00 CERTIFICATION FEE \$ 9.87 SURCHARGE FEE \$ 9.87
MISC. FEES \$.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$ WASTE FEE \$
FLOOD ZONE DEVELOPMENT FEE \$ CULVERT FEE \$ 25.00 TOTAL FEE 469.74

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

Columbia County Building Permit Application

For Office Use Only Application # 0408-18 Date Received 8/5/04 By G Permit # 501/22692
 Application Approved by - Zoning Official BLK Date 12.01.05 Plans Examiner _____ Date _____
 Flood Zone Xar Development Permit N/A Zoning R3F-2 Land Use Plan Map Category RES. Low Den.
 Comments plat make sure of IO Number

need 911

Applicants Name Bryan Zecher Const Phone 752-8653
 Address PO Box 815 LC, FL 32056
 Owners Name Cornerstone Development Group Phone 752-8653
 911 Address 165 SE VICTORIA GLEN LAKE CITY, FLA.
 Contractors Name Bryan Zecher Construction Phone 752-8653
 Address PO Box 815 Lake City, FL 32056
 Fee Simple Owner Name & Address _____
 Bonding Co. Name & Address _____
 Architect/Engineer Name & Address Teena Ruffo / Mark Disonway
 Mortgage Lenders Name & Address _____
 Property ID Number 15-45-17-0839-016 Estimated Cost of Construction \$100,000
 Subdivision Name Country Side Estates Country Sides Lot 1 Block _____ Unit _____ Phase _____
 Driving Directions Buys Ave to Old Country Club Rd, T/R - go about 3 miles to subdivision on left
 Type of Construction new home Number of Existing Dwellings on Property 0
 Total Acreage 1/2 Lot Size 1/2 Do you need a - Culvert Permit or Culvert Waiver or Have an Existing Drive
 Actual Distance of Structure from Property Lines - Front 25 Side 35 Side 35 Rear 45
 Total Building Height 19' Number of Stories 1 Heated Floor Area 1500 Roof Pitch 6/12

Application is hereby made to obtain a permit to do work and installations as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work be performed to meet the standards of all laws regulating construction in this jurisdiction.

OWNERS AFFIDAVIT: I hereby certify that all the foregoing information is accurate and all work will be done in compliance with all applicable laws and regulating construction and zoning.

WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT.

Owner Builder or Agent (Including Contractor)

STATE OF FLORIDA
COUNTY OF COLUMBIA


Sworn to (or affirmed) and subscribed before me

this 5th day of AUG 2004.

Personally known ✓ or Produced Identification _____

Contractor Signature _____
 Contractors License Number CBC054575
 Competency Card Number _____

NOTAR



Notary Signature _____


COLUMBIA COUNTY 9-1-1 ADDRESSING

263 NW Lake City Ave. * P. O. Box 2949 * Lake City, FL 32056-2949
PHONE: (386) 752-8787 * FAX (386) 758-1365 * Email: ron_croft@columbiacountyfla.com

Addresses for Country Side Estates Subdivision:

Lot #:	Address Assigned:
1	165 SE Victoria Glen
2	195 SE Victoria Glen
3	223 SE Victoria Glen
4	251 SE Victoria Glen
5	281 SE Victoria Glen
6	311 SE Victoria Glen
7	329 SE Victoria Glen
8	328 SE Victoria Glen
9	306 SE Victoria Glen
10	274 SE Victoria Glen
11	244 SE Victoria Glen
12	214 SE Victoria Glen
13	182 SE Victoria Glen
14	152 SE Victoria Glen
15	122 SE Victoria Glen


Lot #:	Address Assigned:
16	123 SE Gregory Glen
17	153 SE Gregory Glen
18	183 SE Gregory Glen
19	215 SE Gregory Glen
20	245 SE Gregory Glen
21	275 SE Gregory Glen
22	309 SE Gregory Glen
23	329 SE Gregory Glen
24	330 SE Gregory Glen
25	308 SE Gregory Glen
26	276 SE Gregory Glen
27	246 SE Gregory Glen
28	216 SE Gregory Glen
29	184 SE Gregory Glen
30	154 SE Gregory Glen
31	3239 SE Country Club Rd



Application for Onsite Sewage Disposal System
Construction Permit. Part II Site Plan
Permit Application Number: 04-0731N

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH UNIT

ZECHER/CR 03-2182



1 inch = 50 feet

Site Plan Submitted By Paul Lloyd Date 6/29/04
Plan Approved Not Approved Date 6/29/04

By Paul Lloyd Columbia CPHU 7-7-04

Notes: M 1/1

COLUMBIA COUNTY BUILDING DEPARTMENT

RESIDENTIAL MINIMUM PLAN REQUIREMENTS AND CHECKLIST FOR FLORIDA BUILDING CODE 2001 ONE (1) AND TWO (2) FAMILY DWELLINGS ALL REQUIREMENTS ARE SUBJECT TO CHANGE EFFECTIVE MARCH 1, 2002

ALL BUILDING PLANS MUST INDICATE THE FOLLOWING ITEMS AND INDICATE COMPLIANCE WITH CHAPTER 1606 OF THE FLORIDA BUILDING CODE 2001 BY PROVIDING CALCULATIONS AND DETAILS THAT HAVE THE SEAL AND SIGNATURE OF A CERTIFIED ARCHITECT OR ENGINEER REGISTERED IN THE STATE OF FLORIDA, OR ALTERNATE METHODOLOGIES, APPROVED BY THE STATE OF FLORIDA BUILDING COMMISSION FOR ONE-AND-TWO FAMILY DWELLINGS. FOR DESIGN PURPOSES THE FOLLOWING BASIC WIND SPEED AS PER FIGURE 1606 SHALL BE USED.

WIND SPEED LINE SHALL BE DEFINED AS FOLLOWS: THE CENTERLINE OF INTERSTATE 75.

1. ALL BUILDINGS CONSTRUCTED EAST OF SAID LINE SHALL BE ----- 100 MPH
2. ALL BUILDINGS CONSTRUCTED WEST OF SAID LINE SHALL BE ----- 110 MPH
3. NO AREA IN COLUMBIA COUNTY IS IN A WIND BORNE DEBRIS REGION

APPLICANT - PLEASE CHECK ALL APPLICABLE BOXES BEFORE SUBMITTAL

GENERAL REQUIREMENTS: Two (2) complete sets of plans containing the following:

Applicant	Plans Examiner	
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	All drawings must be clear, concise and drawn to scale ("Optional " details that are not used shall be marked void or crossed off). Square footage of different areas shall be shown on plans.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Designers name and signature on document (FBC 104.2.1). If licensed architect or engineer, official seal shall be affixed.
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site Plan including:
	BK	a) Dimensions of lot
		b) Dimensions of building set backs
		c) Location of all other buildings on lot, well and septic tank if applicable, and all utility easements.
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	d) Provide a full legal description of property.
		Wind-load Engineering Summary, calculations and any details required
		a) Plans or specifications must state compliance with FBC Section 1606
		b) The following information must be shown as per section 1606.1.7 FBC
		a. Basic wind speed (MPH)
		b. Wind importance factor (I) and building category
		c. Wind exposure - if more than one wind exposure is used, the wind exposure and applicable wind direction shall be indicated
		d. The applicable internal pressure coefficient
		e. Components and Cladding. The design wind pressure in terms of psf (kN/m ²), to be used for the design of exterior component and cladding materials not speciffally designed by the registered design professional
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Elevations including:
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	a) All sides
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	b) Roof pitch
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	c) Overhang dimensions and detail with attic ventilation
<input checked="" type="checkbox"/>	<input type="checkbox"/>	d) Location, size and height above roof of chimneys
<input checked="" type="checkbox"/>	<input type="checkbox"/>	e) Location and size of skylights
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	f) Building height
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	g) Number of stories

N/A
N/A

☒
☒
☒

N/A

N/A

☒

☒

☒

☒

☒

N/A

N/A

☒
☒
☒

N/A

N/A

☒

☒

☒

☒

☐ ?

☐

N/A

N/A

Floor Plan including:

- a) Rooms labeled and dimensioned
- b) Shear walls
- c) Windows and doors (including garage doors) showing size, mfg., approval listing and attachment specs. (FBC 1707) and safety glazing where needed (egress windows in bedrooms to be shown)
- d) Fireplaces (gas appliance) (vented or non-vented) or wood burning with hearth
- e) Stairs with dimensions (width, tread and riser) and details of guardrails and handrails
- f) Must show and identify accessibility requirements (accessible bathroom)

Foundation Plan including:

- a) Location of all load-bearing wall with required footings indicated as standard Or monolithic and dimensions and reinforcing
- b) All posts and/or column footing including size and reinforcing
- c) Any special support required by soil analysis such as piling
- d) Location of any vertical steel

Roof System:

- a) Truss package including:
 - 1. Truss layout and truss details signed and sealed by FI. Pro. Eng.
 - 2. Roof assembly (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
- b) Conventional Framing Layout including:
 - 1. Rafter size, species and spacing
 - 2. Attachment to wall and uplift
 - 3. Ridge beam sized and valley framing and support details
 - 4. Roof assembly (FBC 104.2.1 Roofing systems, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)

Wall Sections including:

- a) Masonry wall
 - 1. All materials making up wall
 - 2. Block size and mortar type with size and spacing of reinforcement
 - 3. Lintel, tie-beam sizes and reinforcement
 - 4. Gable ends with rake beams showing reinforcement or gable truss and wall bracing details
 - 5. All required connectors with uplift rating and required number and size of fasteners for continuous tie from roof to foundation
 - 6. Roof assembly shown here or on roof system detail (FBC 104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with resistance rating)
 - 7. Fire resistant construction (if required)
 - 8. Fireproofing requirements
 - 9. Shoe type of termite treatment (termiteicide or alternative method)
 - 10. Slab on grade
 - a. Vapor retarder (6mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or Welded fire fabric reinforcement and supports
 - 11. Indicate where pressure treated wood will be placed
 - 12. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

b) Wood frame wall

1. All materials making up wall
2. Size and species of studs
3. Sheathing size, type and nailing schedule
4. Headers sized
5. Gable end showing balloon framing detail or gable truss and wall hinge bracing detail
6. All required fasteners for continuous tie from roof to foundation (truss anchors, straps, anchor bolts and washers)
7. Roof assembly shown here or on roof system detail (FBC104.2.1 Roofing system, materials, manufacturer, fastening requirements and product evaluation with wind resistance rating)
8. Fire resistant construction (if applicable)
9. Fireproofing requirements
10. Show type of termite treatment (termicide or alternative method)
11. Slab on grade
 - a. Vapor retarder (6Mil. Polyethylene with joints lapped 6 inches and sealed)
 - b. Must show control joints, synthetic fiber reinforcement or welded wire fabric reinforcement and supports
12. Indicate where pressure treated wood will be placed
13. Provide insulation R value for the following:
 - a. Attic space
 - b. Exterior wall cavity
 - c. Crawl space (if applicable)

c) Metal frame wall and roof (designed, signed and sealed by Florida Prof. Engineer or Architect)

Floor Framing System:

- a) Floor truss package including layout and details, signed and sealed by Florida Registered Professional Engineer
- b) Floor joist size and spacing
- c) Girder size and spacing
- d) Attachment of joist to girder
- e) Wind load requirements where applicable

Plumbing Fixture layout

Electrical layout including:

- a) Switches, outlets/receptacles, lighting and all required GFCI outlets identified
- b) Ceiling fans
- c) Smoke detectors
- d) Service panel and sub-panel size and location(s)
- e) Meter location with type of service entrance (overhead or underground)
- f) Appliances and HVAC equipment
- g) Arc Fault Circuits (AFCI) in bedrooms

HVAC information

- a) Manual J sizing equipment or equivalent computation
- b) Exhaust fans in bathroom

Energy Calculations (dimensions shall match plans)

Gas System Type (LP or Natural) Location and BTU demand of equipment

Disclosure Statement for Owner Builders

Notice Of Commencement

Private Potable Water

- a) Size of pump motor
- b) Size of pressure tank
- c) Cycle stop valve if used

private system

THE FOLLOWING ITEMS MUST BE SUBMITTED WITH BUILDING PLANS

1. **Building Permit Application:** A current Building Permit Application form is to be completed and submitted for all residential projects.
2. **Parcel Number:** The parcel number (Tax ID number) from the Property Appraiser (386) 758-1084 is required. A copy of property deed is also requested.
3. **Environmental Health Permit or Sewer Tap Approval:** A copy of the Environmental Health permit, existing septic approval or sewer tap approval is required before a building permit can be issued. (386) 758-1058 (Toilet facilities shall be provided for construction workers)
4. **City Approval:** If the project is to be located within the city limits of the Town of Fort White, prior approval is required. The Town of Fort White approval letter is required to be submitted by the owner or contractor to this office when applying for a Building Permit.
5. **Flood Information:** All projects within the Floodway of the Suwannee or Santa Fe Rivers shall require permitting through the Suwannee River Water Management District, before submitting application to this office. Any project located within a flood zone where the base flood elevation (100 year flood) has been established shall meet the requirements of Section 8.8 of the Columbia County Land Development Regulations. Any project located within a flood zone where the base flood elevation has not been established (Zone A) shall meet the requirements of Section 8.7 of the Columbia County Land Development Regulations. **CERTIFIED FINISHED FLOOR ELEVATIONS WILL BE REQUIRED ON ANY PROJECT WHERE THE BASE FLOOD ELEVATION (100 YEAR FLOOD) HAS BEEN ESTABLISHED.**
A development permit will also be required. Development permit cost is \$10.00
6. **Driveway Connection:** If the property does not have an existing access to a public road, then an application for a culvert permit (\$25.00) must be made. If the applicant feels that a culvert is not needed, they may apply for a culvert waiver (\$50.00). All culvert waivers are sent to the Columbia County Public Works Department for approval or denial.
7. **911 Address:** If the project is located in an area where the 911 address has been issued, then the proper paperwork from the 911 Addressing Department must be submitted. (386) 758-8787

ALL REQUIRED INFORMATION IS TO BE SUBMITTED FOR REVIEW. YOU WILL BE NOTIFIED WHEN YOUR APPLICATION AND PLANS ARE APPROVED AND READY TO PERMIT. PLEASE DO NOT EXPECT OR REQUEST THAT PERMIT APPLICATIONS BE REVIEWED OR APPROVED WHILE YOU ARE HERE – TIME WILL NOT ALLOW THIS – PLEASE DO NOT ASK

**NOTICE OF COMMENCEMENT FORM
COLUMBIA COUNTY, FLORIDA**

THE UNDERSIGNED hereby gives notice that improvement will be made to certain real property, and in accordance with Chapter 713, Florida Statutes, the following information is provided in this Notice of Commencement.

Tax Parcel ID Number 15-45-17-08359-016

1. Description of property: (legal description of the property and street address or 911 address)

Candy Side Estates, lot 1

2. General description of improvement: New Home

3. Owner Name & Address Cornerstone Development Group
PO Box 815 Lake City, FL 32056 Interest in Property Simple

4. Name & Address of Fee Simple Owner (if other than owner): —

5. Contractor Name Bryan Zecher Construction, Inc Phone Number 72-0683
Address PO Box 815 Lake City, FL 32056

6. Surety Holders Name —
Address — Inst:2004018021 Date:08/05/2004 Time:12:24
Amount of Bond 75K DC,P.Dewitt Cason,Columbia County B:1022 P:2291

7. Lender Name —
Address —

8. Persons within the State of Florida designated by the Owner upon whom notices or other documents may be served as provided by section 718.13 (1)(a) 7; Florida Statutes:

Name — Phone Number —
Address —

9. In addition to himself/herself the owner designates — of —
— to receive a copy of the Lienor's Notice as provided in Section 713.13 (1) -
(a) 7. Phone Number of the designee —

10. Expiration date of the Notice of Commencement (the expiration date is 1 (one) year from the date of recording, (Unless a different date is specified) —

NOTICE AS PER CHAPTER 713, Florida Statutes:

The owner must sign the notice of commencement and no one else may be permitted to sign in his/her stead.

Signature of Owner [Signature]

OFFICIAL NOTARY SEAL
SUSANA GARBER
NOTARY PUBLIC STATE OF FLORIDA
COMMISSION NO. DD043861
MY COMMISSION EXP. AUG 7, 2005

Sworn to (or affirmed) and subscribed before
day of August 4, 2004





NOTARY STAMP/SEAL


[Signature]
Signature of Notary

15-4S-17-08359-016

COMM SE COR OF NW1/4, RUN N ALONG E LINE OF NW1/4, 343.13 FT TO POB, RUN W 1295.71 FT, N ALONG R/W OF CR-133, 672.85 FT										CORNERSTONE DEVELOPMENT GROUP LLC 180 NW AMENITY COURT LAKE CITY										15-4S-17-08359-016 FL 32025										Columbia County 2004 R CARD 001 of 001 PRINTED 6/23/2004 8:41 APPR 7/01/1996 AT BY JEFF																																																											
USE 000800 MOBILE HME										AE? Y										1512 HTD AREA										106.000 INDEX										15417.00 NBHD										PROP USE 005000 IMPROVED AG																																							
MOD 2 MOBILE HME BATH										2.00										1544 EFF AREA										25.440 E-RATE										100.000 INDX										STR 15- 4S- 17																																							
EXW 26 ALL SIDING FIXT																				39279 RCN																				1984 AYB										MKT AREA 01																																							
% N/A BDRM										2										51.00 %GOOD										20,032 B BLDG VAL										1984 EYB										(PUD1																																							
RSTR 03 GABLE/HIP RMS																																								AC 20.000										11,000 LAND																																							
RCVR 03 COMP SHNGL UNTS																				FIELD CK:																				NTCD AG										3,135 AG																																							
% N/A C-W%																				LOC: ---																				APPR CD										95,000 MKAG																																							
INT 04 PLYWOOD HGHT																																								CNDO										131,782 JUST																																							
% N/A PMTR																				+-----56-----+																				SUBD										39,917 CLAS																																							
FLR 14 CARPET STYS										1.0										IBAS1993										I																				BLK																																							
10% 08 SHT VINYL ECON																				I										I																				LOT										0 SOHD																													
HTTP 04 AIR DUCTED FUNC																				I										I																				MAP#										0 ASSD																													
A/C 03 CENTRAL SPCD																				I										I																				HX										0 EXPT																													
QUAL 03 AVERAGE DEPR 09																				2										2																				TXDT 002										0 COTXB																													
FNDN N/A UD-1										N/A										7										7																																																											
SIZE N/A UD-2										N/A										I										I																																																											
CEIL N/A UD-3										N/A										I										I																																																											
ARCH N/A UD-4										N/A										I										I																																																											
FRME 01 NONE UD-5										N/A										+-----20-----+-----16-----+36-----+																																																																					
KTCH N/A UD-6										N/A																				8UOP1993 8																																																											
WNDO N/A UD-7										N/A																				I I																																																											
CLAS N/A UD-8										N/A																				+-----16-----+																																																											
OCC N/A UD-9										N/A																																																																															
COND N/A %										N/A																																																																															
SUB A-AREA % E-AREA SUB VALUE																																																																																									
BAS93 1512 100 1512																				19617																																																																					
UOP93 128 25 32																				415																																																																					
TOTAL 1640 1544 20032																																																																																									
EXTRA FEATURES																				FIELD CK:																																																																					
AE BN CODE DESC LEN WID HGHT QTY QL YR ADJ																				UNITS UT										PRICE										ADJ UT PR										SPCD %										%GOOD										XFOB										VALUE									
Y 0210 GARAGE U																				1 0000 1.00										1.000 UT										5000.000										5000.000										100.00																				5,000									
Y 0070 CARPORT UF																				1 0000 1.00										1.000 UT										750.000										750.000										100.00																				750									
LAND DESC ZONE ROAD {UD1 {UD3 FRONT DEPTH																				FIELD CK:																																																																					
AE CODE TOPO UTIL {UD2 {UD4 BACK DT																				ADJUSTMENTS										UNITS UT										PRICE										ADJ UT PR										LAND										VALUE																			
Y 000102 SFR/MH A-1 0003																				1.00 1.00 1.00 1.00										1.000 AC										9000.000										9000.00																				9,000																			
N 005200 CROPLAND 2 A-1 0003																				1.00 1.00 1.00 1.00										19.000 AC										165.000										165.00																				3,135AG																			
N 009910 MKT.VAL.AG A-1 0003																				1.00 1.00 1.00 1.00										19.000 AC																																																											
Y 009945 WELL/SEPT A-1 0003																				1.00 1.00 1.00 1.00										1.000 UT										5000.000										5000.00																				95,000MK																			
																																								2000.000										2000.00																				2,000																			
L003 - NOT REC																																																																																									
2004																																																																																									

COUNTRY SIDE
ESTATES
LOT 1
SITE PLAN
COLUMBIA, CO.

-  = HOME
-  = POWER
-  = SEPTIC
-  = WATER



SE VICTORIA GLEN

FLORIDA ENERGY EFFICIENCY CODE
FOR BUILDING CONSTRUCTION

Florida Department of Community Affairs
Residential Whole Building Performance Method A

Project Name:	406297TheSamuelModel	Builder:	Bryan Zecher Construction
Address:		Permitting Office:	
City, State:	Lake City, FL	Permit Number:	22692
Owner:	The Samuel Model	Jurisdiction Number:	221000
Climate Zone:	North		

1. New construction or existing	New	12. Cooling systems	
2. Single family or multi-family	Single family	a. Central Unit	Cap: 34.0 kBtu/hr
3. Number of units, if multi-family	1		SEER: 11.50
4. Number of Bedrooms	3	b. N/A	
5. Is this a worst case?	Yes	c. N/A	
6. Conditioned floor area (ft²)	1500 ft²		
7. Glass area & type	Single Pane Double Pane	13. Heating systems	
a. Clear glass, default U-factor	0.0 ft² 215.0 ft²	a. Electric Heat Pump	Cap: 34.0 kBtu/hr
b. Default tint, default U-factor	0.0 ft² 0.0 ft²		HSPF: 7.40
c. Labeled U-factor or SHGC	0.0 ft² 0.0 ft²	b. N/A	
8. Floor types		c. N/A	
a. Slab-On-Grade Edge Insulation	R=0.0, 196.0(p) ft		
b. N/A		14. Hot water systems	
c. N/A		a. Electric Resistance	Cap: 40.0 gallons
9. Wall types			EF: 0.93
a. Frame, Wood, Adjacent	R=13.0, 172.0 ft²	b. N/A	
b. Frame, Wood, Exterior	R=13.0, 1121.0 ft²	c. Conservation credits	
c. N/A		(HR-Heat recovery, Solar	
d. N/A		DHP-Dedicated heat pump)	
e. N/A		15. HVAC credits	
10. Ceiling types		(CF-Ceiling fan, CV-Cross ventilation,	
a. Under Attic	R=30.0, 1754.0 ft²	HF-Whole house fan,	
b. N/A		PT-Programmable Thermostat,	
c. N/A		MZ-C-Multizone cooling,	
11. Ducts		MZ-H-Multizone heating)	
a. Sup: Unc. Ret: Unc. AH: Garage	Sup. R=6.0, 150.0 ft		
b. N/A			

Glass/Floor Area: 0.14

Total as-built points: 24080
Total base points: 24152

PASS

I hereby certify that the plans and specifications covered by this calculation are in compliance with the Florida Energy Code.

PREPARED BY: Evan Beamsley

DATE: 6/29/04

I hereby certify that this building, as designed, is in compliance with the Florida Energy Code.


OWNER/AGENT:

DATE: 6/4/04

Review of the plans and specifications covered by this calculation indicates compliance with the Florida Energy Code. Before construction is completed this building will be inspected for compliance with Section 553.908 Florida Statutes.

BUILDING OFFICIAL:

DATE:



SUMMER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
Summer Base Points: 18386.9				Summer As-Built Points: 17600.2							
Total Summer Points	X	System Multiplier	= Cooling Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Cooling Points	
18386.9		0.4266	7843.9	17600.2		1.000	(1.090 x 1.147 x 1.00)	0.297	1.000	6530.5	
				17600.2		1.00	1.250	0.297	1.000	6530.5	

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
GLASS TYPES .18 X Conditioned X BWPM = Points Floor Area				Type/SC	Overhang Ornt Len Hgt			Area X WPM X WOF = Points			
.18	1500.0	12.74	3439.8	Double, Clear	SE	1.5	5.5	45.0	14.71	1.11	737.3
				Double, Clear	S	14.0	7.0	10.0	13.30	3.51	466.1
				Double, Clear	SE	11.5	5.3	45.0	14.71	2.52	1668.0
				Double, Clear	E	8.0	7.0	10.0	18.79	1.32	249.0
				Double, Clear	SW	1.5	1.5	3.0	16.74	1.60	80.3
				Double, Clear	NW	9.0	7.5	6.0	24.30	1.03	149.8
				Double, Clear	NW	1.5	5.5	30.0	24.30	1.00	731.9
				Double, Clear	NW	1.5	8.0	30.0	24.30	1.00	729.4
				Double, Clear	NE	1.5	3.5	6.0	23.57	1.02	144.2
				Double, Clear	NE	1.5	5.5	30.0	23.57	1.01	712.7
				As-Built Total:							215.0
WALL TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Adjacent	172.0	3.60	619.2	Frame, Wood, Adjacent	13.0		172.0	3.30	567.6		
Exterior	1121.0	3.70	4147.7	Frame, Wood, Exterior	13.0		1121.0	3.40	3811.4		
Base Total: 1293.0 4766.9				As-Built Total:		1293.0		4379.0			
DOOR TYPES Area X BWPM = Points				Type	Area X WPM = Points						
Adjacent	20.0	11.50	230.0	Exterior Insulated	20.0 8.40 168.0						
Exterior	40.0	12.30	492.0	Exterior Insulated	20.0 8.40 168.0						
				Adjacent Insulated	20.0 8.00 160.0						
Base Total: 60.0 722.0				As-Built Total:		60.0		496.0			
CEILING TYPES Area X BWPM = Points				Type	R-Value		Area X WPM X WCM = Points				
Under Attic	1500.0	2.05	3075.0	Under Attic	30.0		1754.0	2.05 X 1.00		3595.7	
Base Total: 1500.0 3075.0				As-Built Total:		1754.0		3595.7			
FLOOR TYPES Area X BWPM = Points				Type	R-Value		Area X WPM = Points				
Slab	196.0(p)	8.9	1744.4	Slab-On-Grade Edge Insulation	0.0		196.0(p)	18.80		3684.8	
Raised	0.0	0.00	0.0								
Base Total: 1744.4				As-Built Total:		196.0		3684.8			
INFILTRATION Area X BWPM = Points				Area X WPM = Points							
1500.0 -0.59 -885.0				1500.0 -0.59 -885.0							

WINTER CALCULATIONS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT							
Winter Base Points:		12863.1		Winter As-Built Points:				16939.2			
Total Winter Points	X	System Multiplier	= Heating Points	Total Component	X	Cap Ratio	X Duct Multiplier (DM x DSM x AHU)	X System Multiplier	X Credit Multiplier	= Heating Points	
12863.1		0.6274	8070.3	16939.2		1.000	(1.069 x 1.169 x 1.00)	0.461	1.000	9754.5	
				16939.2		1.00	1.250	0.461	1.000	9754.5	

WATER HEATING & CODE COMPLIANCE STATUS

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

BASE				AS-BUILT					
WATER HEATING				Tank	EF	Number of	X	Tank	X Multiplier X Credit = Total
Number of	X	Multiplier	=	Volume		Bedrooms		Ratio	Multiplier
Bedrooms									
3		2746.00	8238.0	40.0	0.93	3		1.00	2598.37 1.00 7795.1
				As-Built Total:					7795.1

CODE COMPLIANCE STATUS									
BASE					AS-BUILT				
Cooling	+	Heating	+	Hot Water	=	Cooling	+	Heating	=
Points		Points		Points	Points	Points		Points	Points
7844		8070		8238	24152	6530		9755	24080

PASS



Code Compliance Checklist

Residential Whole Building Performance Method A - Details

ADDRESS: , Lake City, FL,

PERMIT #:

6A-21 INFILTRATION REDUCTION COMPLIANCE CHECKLIST

COMPONENTS	SECTION	REQUIREMENTS FOR EACH PRACTICE	CHECK
Exterior Windows & Doors	606.1.ABC.1.1	Maximum:.3 cfm/sq.ft. window area; .5 cfm/sq.ft. door area.	
Exterior & Adjacent Walls	606.1.ABC.1.2.1	Caulk, gasket, weatherstrip or seal between: windows/doors & frames, surrounding wall; foundation & wall sole or sill plate; joints between exterior wall panels at corners; utility penetrations; between wall panels & top/bottom plates; between walls and floor. EXCEPTION: Frame walls where a continuous infiltration barrier is installed that extends from, and is sealed to, the foundation to the top plate.	
Floors	606.1.ABC.1.2.2	Penetrations/openings >1/8" sealed unless backed by truss or joint members. EXCEPTION: Frame floors where a continuous infiltration barrier is installed that is sealed to the perimeter, penetrations and seams.	
Ceilings	606.1.ABC.1.2.3	Between walls & ceilings; penetrations of ceiling plane of top floor; around shafts, chases, soffits, chimneys, cabinets sealed to continuous air barrier; gaps in gyp board & top plate; attic access. EXCEPTION: Frame ceilings where a continuous infiltration barrier is installed that is sealed at the perimeter, at penetrations and seams.	
Recessed Lighting Fixtures	606.1.ABC.1.2.4	Type IC rated with no penetrations, sealed; or Type IC or non-IC rated, installed inside a sealed box with 1/2" clearance & 3" from insulation; or Type IC rated with < 2.0 cfm from conditioned space, tested.	
Multi-story Houses	606.1.ABC.1.2.5	Air barrier on perimeter of floor cavity between floors.	
Additional Infiltration reqts	606.1.ABC.1.3	Exhaust fans vented to outdoors, dampers; combustion space heaters comply with NFPA, have combustion air.	

6A-22 OTHER PRESCRIPTIVE MEASURES (must be met or exceeded by all residences.)

COMPONENTS	SECTION	REQUIREMENTS	CHECK
Water Heaters	612.1	Comply with efficiency requirements in Table 6-12. Switch or clearly marked circuit breaker (electric) or cutoff (gas) must be provided. External or built-in heat trap required.	
Swimming Pools & Spas	612.1	Spas & heated pools must have covers (except solar heated). Non-commercial pools must have a pump timer. Gas spa & pool heaters must have a minimum thermal efficiency of 78%.	
Shower heads	612.1	Water flow must be restricted to no more than 2.5 gallons per minute at 80 PSIG.	
Air Distribution Systems	610.1	All ducts, fittings, mechanical equipment and plenum chambers shall be mechanically attached, sealed, insulated, and installed in accordance with the criteria of Section 610. Ducts in unconditioned attics: R-6 min. insulation.	
HVAC Controls	607.1	Separate readily accessible manual or automatic thermostat for each system.	
Insulation	604.1, 602.1	Ceilings-Min. R-19. Common walls-Frame R-11 or CBS R-3 both sides. Common ceiling & floors R-11.	

ENERGY PERFORMANCE LEVEL (EPL) DISPLAY CARD

ESTIMATED ENERGY PERFORMANCE SCORE* = 82.8

The higher the score, the more efficient the home.

The Samuel Model, , Lake City, FL,

1. New construction or existing	New	___	12. Cooling systems	
2. Single family or multi-family	Single family	___	a. Central Unit	Cap: 34.0 kBtu/hr
3. Number of units, if multi-family	1	___		SEER: 11.50
4. Number of Bedrooms	3	___	b. N/A	___
5. Is this a worst case?	Yes	___	c. N/A	___
6. Conditioned floor area (ft²)	1500 ft²	___		___
7. Glass area & type	Single Pane	Double Pane	13. Heating systems	
a. Clear glass, default U-factor	0.0 ft²	215.0 ft²	a. Electric Heat Pump	Cap: 34.0 kBtu/hr
b. Default tint, default U-factor	0.0 ft²	0.0 ft²		HSPF: 7.40
c. Labeled U-factor or SHGC	0.0 ft²	0.0 ft²	b. N/A	___
8. Floor types			c. N/A	___
a. Slab-On-Grade Edge Insulation	R=0.0, 196.0(p) ft	___		___
b. N/A	___	___	14. Hot water systems	
c. N/A	___	___	a. Electric Resistance	Cap: 40.0 gallons
9. Wall types				EF: 0.93
a. Frame, Wood, Adjacent	R=13.0, 172.0 ft²	___	b. N/A	___
b. Frame, Wood, Exterior	R=13.0, 1121.0 ft²	___	c. Conservation credits	___
c. N/A	___	___	(HR-Heat recovery, Solar	___
d. N/A	___	___	DHP-Dedicated heat pump)	___
e. N/A	___	___	15. HVAC credits	___
10. Ceiling types			(CF-Ceiling fan, CV-Cross ventilation,	___
a. Under Attic	R=30.0, 1754.0 ft²	___	HF-Whole house fan,	___
b. N/A	___	___	PT-Programmable Thermostat,	___
c. N/A	___	___	MZ-C-Multizone cooling,	___
11. Ducts			MZ-H-Multizone heating)	___
a. Sup: Unc. Ret: Unc. AH: Garage	Sup. R=6.0, 150.0 ft	___		___
b. N/A	___	___		___

I certify that this home has complied with the Florida Energy Efficiency Code For Building Construction through the above energy saving features which will be installed (or exceeded) in this home before final inspection. Otherwise, a new EPL Display Card will be completed based on installed Code compliant features.

Builder Signature: [Signature] Date: 8/4/04

Address of New Home: Condy Side Est City/FL Zip: LC, FL



**NOTE: The home's estimated energy performance score is only available through the FLA/RES computer program. This is not a Building Energy Rating. If your score is 80 or greater (or 86 for a US EPA/DOE EnergyStar™ designation), your home may qualify for energy efficiency mortgage (EEM) incentives if you obtain a Florida Energy Gauge Rating. Contact the Energy Gauge Hotline at 321/638-1492 or see the Energy Gauge web site at www.fsec.ucf.edu for information and a list of certified Raters. For information about Florida's Energy Efficiency Code For Building Construction, contact the Department of Community Affairs at 850/487-1824.*

EnergyGauge® (Version: FLR2PB v3.4)

Residential System Sizing Calculation

Summary

The Samuel Model
Lake City, FL

Project Title:
406297TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North


6/29/2004

Location for weather data: Gainesville - Defaults: Latitude(29) Temp Range(M)			
Humidity data: Interior RH (50%) Outdoor wet bulb (77F) Humidity difference(51gr.)			
Winter design temperature	31 F	Summer design temperature	93 F
Winter setpoint	70 F	Summer setpoint	75 F
Winter temperature difference	39 F	Summer temperature difference	18 F
Total heating load calculation	29218 Btuh	Total cooling load calculation	27764 Btuh
Submitted heating capacity	% of calc Btuh	Submitted cooling capacity	% of calc Btuh
Total (Electric Heat Pump)	116.4 34000	Sensible (SHR = 0.75)	125.6 25500
Heat Pump + Auxiliary(0.0kW)	116.4 34000	Latent	113.9 8500
		Total (Electric Heat Pump)	122.5 34000

WINTER CALCULATIONS

Winter Heating Load (for 1500 sqft)


Load component		Load	
Window total	215 sqft	6085	Btuh
Wall total	1293 sqft	3750	Btuh
Door total	60 sqft	921	Btuh
Ceiling total	1754 sqft	2280	Btuh
Floor total	196 ft	6194	Btuh
Infiltration	200 cfm	8597	Btuh
Subtotal		27827	Btuh
Duct loss		1391	Btuh
TOTAL HEAT LOSS		29218	Btuh



SUMMER CALCULATIONS

Summer Cooling Load (for 1500 sqft)

Load component		Load	
Window total	215 sqft	6757	Btuh
Wall total	1293 sqft	2129	Btuh
Door total	60 sqft	608	Btuh
Ceiling total	1754 sqft	2491	Btuh
Floor total		0	Btuh
Infiltration	175 cfm	3472	Btuh
Internal gain		3000	Btuh
Subtotal(sensible)		18457	Btuh
Duct gain		1846	Btuh
Total sensible gain		20303	Btuh
Latent gain(infiltration)		6081	Btuh
Latent gain(internal)		1380	Btuh
Total latent gain		7461	Btuh
TOTAL HEAT GAIN		27764	Btuh



EnergyGauge® System Sizing based on ACCA Manual J.

PREPARED BY:

DATE: 6/29/04

EnergyGauge® FLR2PB v3.4

System Sizing Calculations - Winter

Residential Load - Component Details

The Samuel Model

Project Title:
406297TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

Lake City, FL

Reference City: Gainesville (Defaults) Winter Temperature Difference: 39.0 F

6/29/2004

Window	Panes/SHGC/Frame/U	Orientation	Area X	HTM=	Load
1	2, Clear, Metal, DEF	N	45.0	28.3	1274 Btuh
2	2, Clear, Metal, DEF	NE	10.0	28.3	283 Btuh
3	2, Clear, Metal, DEF	N	45.0	28.3	1274 Btuh
4	2, Clear, Metal, DEF	NW	10.0	28.3	283 Btuh
5	2, Clear, Metal, DEF	E	3.0	28.3	85 Btuh
6	2, Clear, Metal, DEF	S	6.0	28.3	170 Btuh
7	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
8	2, Clear, Metal, DEF	S	30.0	28.3	849 Btuh
9	2, Clear, Metal, DEF	W	6.0	28.3	170 Btuh
10	2, Clear, Metal, DEF	W	30.0	28.3	849 Btuh
Window Total			215		6085 Btuh
Walls	Type	R-Value	Area X	HTM=	Load
1	Frame - Adjacent	13.0	172	1.6	275 Btuh
2	Frame - Exterior	13.0	1121	3.1	3475 Btuh
Wall Total			1293		3750 Btuh
Doors	Type		Area X	HTM=	Load
1	Insulated - Exter		20	18.3	367 Btuh
2	Insulated - Exter		20	18.3	367 Btuh
3	Insulated - Adjac		20	9.4	188 Btuh
Door Total			60		921Btuh
Ceilings	Type	R-Value	Area X	HTM=	Load
1	Under Attic	30.0	1754	1.3	2280 Btuh
Ceiling Total			1754		2280Btuh
Floors	Type	R-Value	Size X	HTM=	Load
1	Slab-On-Grade Edge Insul	0	196.0 ft(p)	31.6	6194 Btuh
Floor Total			196		6194 Btuh
Infiltration	Type	ACH X	Building Volume	CFM=	Load
	Natural	0.80	15000(sqft)	200	8597 Btuh
	Mechanical			0	0 Btuh
Infiltration Total				200	8597 Btuh

Totals for Heating	Subtotal	27827 Btuh
	Duct Loss(using duct multiplier of 0.05)	1391 Btuh
	Total Btuh Loss	29218 Btuh

Manual J Winter Calculations

Residential Load - Component Details (continued)

The Samuel Model
Lake City, FL

Project Title:
406297TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

6/29/2004

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(Frame types - metal, wood or insulated metal)
(U - Window U-Factor or 'DEF' for default)
(HTM - ManualJ Heat Transfer Multiplier)
Key: Floor size (perimeter(p) for slab-on-grade or area for all other floor types)

System Sizing Calculations - Summer

Residential Load - Component Details

The Samuel Model

Project Title:
406297TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

Lake City, FL

Reference City: Gainesville (Defaults)

Summer Temperature Difference: 18.0 F

6/29/2004

Window	Type	Len	Hgt	Window Area(sqft)			HTM		Load	
	Panes/SHGC/U/InSh/ExSh Ornt			Gross	Shaded	Unshaded	Shaded	Unshaded		
1	2, Clear, DEF, N, N	N	1.5	5.5	45.0	0.0	45.0	22	22	990 Btuh
2	2, Clear, DEF, N, N	NE	14	7	10.0	0.0	10.0	22	50	500 Btuh
3	2, Clear, DEF, N, N	N	11.5	5.25	45.0	0.0	45.0	22	22	990 Btuh
4	2, Clear, DEF, N, N	NW	8	7	10.0	0.0	10.0	22	50	500 Btuh
5	2, Clear, DEF, N, N	E	1.5	1.5	3.0	2.5	0.5	22	72	92 Btuh
6	2, Clear, DEF, N, N	S	9	7.5	6.0	6.0	0.0	22	37	132 Btuh
7	2, Clear, DEF, N, N	S	1.5	5.5	30.0	30.0	0.0	22	37	660 Btuh
8	2, Clear, DEF, N, N	S	1.5	8	30.0	30.0	0.0	22	37	660 Btuh
9	2, Clear, DEF, N, N	W	1.5	3.5	6.0	0.5	5.5	22	72	408 Btuh
10	2, Clear, DEF, N, N	W	1.5	5.5	30.0	6.7	23.3	22	72	1825 Btuh
	Window Total				215					6757 Btuh
Walls	Type		R-Value		Area		HTM		Load	
1	Frame - Adjacent		13.0		172.0		1.0		179 Btuh	
2	Frame - Exterior		13.0		1121.0		1.7		1951 Btuh	
	Wall Total				1293.0				2129 Btuh	
Doors	Type				Area		HTM		Load	
1	Insulated - Exter				20.0		10.1		203 Btuh	
2	Insulated - Exter				20.0		10.1		203 Btuh	
3	Insulated - Adjac				20.0		10.1		203 Btuh	
	Door Total				60.0				608 Btuh	
Ceilings	Type/Color		R-Value		Area		HTM		Load	
1	Under Attic/Dark		30.0		1754.0		1.4		2491 Btuh	
	Ceiling Total				1754.0				2491 Btuh	
Floors	Type		R-Value		Size		HTM		Load	
1	Slab-On-Grade Edge Insulation		0.0		196.0 ft(p)		0.0		0 Btuh	
	Floor Total				196.0				0 Btuh	
Infiltration	Type		ACH		Volume		CFM=		Load	
	Natural		0.70		15000		175.4		3472 Btuh	
	Mechanical						0		0 Btuh	
	Infiltration Total						175		3472 Btuh	
Internal gain			Occupants		Btuh/occupant		Appliance		Load	
			6		X 300 +		1200		3000 Btuh	

Manual J Summer Calculations

Residential Load - Component Details (continued)

The Samuel Model
Lake City, FL

Project Title:
406297TheSamuelModel

Class 3 Rating
Registration No. 0
Climate: North

6/29/2004

Totals for Cooling	Subtotal	18457 Btuh
	Duct gain(using duct multiplier of 0.10)	1846 Btuh
	Total sensible gain	20303 Btuh
	Latent infiltration gain (for 51 gr. humidity difference)	6081 Btuh
	Latent occupant gain (6 people @ 230 Btuh per person)	1380 Btuh
	Latent other gain	0 Btuh
	TOTAL GAIN	27764 Btuh

Key: Window types (SHGC - Shading coefficient of glass as SHGC numerical value or as clear or tint)
(U - Window U-Factor or 'DEF' for default)
(InSh - Interior shading device: none(N), Blinds/Daperies(B) or Roller Shades(R))
(ExSh - Exterior shading device: none(N) or numerical value)
(Ornt - compass orientation)

**Columbia County Building Department
Culvert Permit**

**Culvert Permit No.
000000501**

DATE 01/12/2005 PARCEL ID # 15-4S-17-08359-016
APPLICANT CHRIS COX PHONE 8670633
ADDRESS P.O. BOX 815 LAKE CITY FL 32056
OWNER CORNERSTONE DEV. GROUP/ZECHER PHONE 752-8653
ADDRESS 165 SE VICTORIA GLEN LAKE CITY FL 32055
CONTRACTOR BRYAN ZECHER PHONE 752-8693
LOCATION OF PROPERTY BAYA AVE, TR ON OLD COUNTRY CLUB ROAD, 3 MILES ON LEFT. TL ON
VICTORIA GLEN, 1ST LOT ON LEFT

SUBDIVISION/LOT/BLOCK/PHASE/UNIT COUNTRY SIDES 1

SIGNATURE



INSTALLATION REQUIREMENTS

☒ X

Culvert size will be 18 inches in diameter with a total length of 32 feet, leaving 24 feet of driving surface. Both ends will be mitered 4 foot with a 4 : 1 slope and poured with a 4 inch thick reinforced concrete slab.

INSTALLATION NOTE: Turnouts will be required as follows:

- a) a majority of the current and existing driveway turnouts are paved, or;
- b) the driveway to be served will be paved or formed with concrete.

Turnouts shall be concrete or paved a minimum of 12 feet wide or the width of the concrete or paved driveway, whichever is greater. The width shall conform to the current and existing paved or concreted turnouts.

☐

Culvert installation shall conform to the approved site plan standards.

☐

Department of Transportation Permit installation approved standards.

☐

Other _____

ALL PROPER SAFETY REQUIREMENTS SHOULD BE FOLLOWED
DURING THE INSTALLATION OF THE CULVERT.

135 NE Hernando Ave., Suite B-21
Lake City, FL 32055
Phone: 386-758-1008 Fax: 386-758-2160

Amount Paid 25.00



GLENVIEW AVENUE ON

OCCUPANCY

COLUMBIA COUNTY, FLORIDA

Department of Building and Zoning Inspection

This Certificate of Occupancy is issued to the below named permit holder for the building and premises at the below named location, and certifies that the work has been completed in accordance with the Columbia County Building Code.

Parcel Number 15-4S-17-08359-016

Building permit No. 000022692

Use Classification SFD, UTILITY

Fire: 65.12

Permit Holder BRYAN ZECHER

Waste: 134.75

Owner of Building CORNERSTONE DEVELOPMENT GROUP/ZECHER 199.87

Location: 165 SE VICTORIA GLEN(COUNTRY SIDES EST., LOT 1)

Date: 11/09/2005

Harry Dieke

Building Inspector



POST IN A CONSPICUOUS PLACE
(Business Places Only)



UNIVERSAL

ENGINEERING SCIENCES

Consultant In: Geotechnical Engineering,
Environmental Sciences, Construction Materials Testing
4475 SW 35th Terrace, Gainesville, Florida 32608 (352) 372-3392

Project No.: 27915-001-01
Report No.: 3546
Date: June 30, 2005

REPORT ON IN-PLACE DENSITY TESTS

22692

Client: Cornerstone Development
P.O. Box 1867
Lake City, FL 32056

Project: Country Side Estates, Lot No. 1, Permit Not Posted, Lake City, Columbia County, FL

Area Tested: Fill Beneath Proposed Building Pad

Course: Final Grade

Depth of Test: 0-1'

Type of Test: ASTM D-2922

Date Tested: 06-30-05

Remarks: The tests below meet the minimum 95 percent relative soil compaction requirement of Laboratory Modified Proctor maximum dry density. (ASTM D-1557)

TEST LOCATION		LABORATORY RESULTS		FIELD TEST RESULTS		
Description of Test Location		Maximum Density (pcf)	Optimum Moisture (%)	Dry Density (pcf)	Field Moisture (%)	Soil Compaction (%)
1.	Approximate Center of Pad	112.0	11.0	109.3	6.4	97.6
2.	Approximately 10' Southeast of Northwest Corner of Pad	112.0	11.0	107.5	6.3	96.0
3.	Approximately 10' Northwest of Southeast Corner of Pad	112.0	11.0	108.0	7.0	96.4

Technician: DM/jk

Andrew T. Schmid, P.E.
FL Professional Engineer No. 56022

Notice of Treatment

11543

Applicator: Florida Pest Control & Chemical Co. (www.flapest.com)

Address: BAYA AVE

City: LAKE CITY Phone: _____

Site Location: Subdivision COUNTRY SIDE EST.

Lot # 1 Block# _____ Permit # not on site 22692

Address 165 SE VICTORIA GLEN

<u>Product used</u>	<u>Active Ingredient</u>	<u>% Concentration</u>
<input type="checkbox"/> Dursban TC	Chlorpyrifos	0.5%
<input type="checkbox"/> Termidor	Fipronil	0.06%
<input checked="" type="checkbox"/> Bora-Care	Disodium Octaborate Tetrahydrate	23.0%

Type treatment:

☐ Soil

☒ Wood

<u>Area Treated</u>	<u>Square feet</u>	<u>Linear feet</u>	<u>Gallons Applied</u>
<u>Durkling</u>	<u>1832</u>	<u>584</u>	<u>4</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

As per Florida Building Code 104.2.6 – If soil chemical barrier method for termite prevention is used, final exterior treatment shall be completed prior to final building approval.

If this notice is for the final exterior treatment, initial this line _____.

9-2-05
Date

1530
Time

F254 GUNNY
Print Technician's Name

Remarks: _____

Applicator - White

Permit File - Canary

Permit Holder - Pink

6/04

