

DATE 11/28/2005

Columbia County Building Permit

PERMIT

This Permit Expires One Year From the Date of Issue

000023894

APPLICANT MIKE TAYLOR PHONE 454-7489
ADDRESS 1181 SW BARNEY ST HIGH SPRINGS FL 32643
OWNER MIKE & DARLA TAYLOR PHONE 454-7489
ADDRESS 1181 SW BARNEY ST HIGH SPRINGS FL 32648
CONTRACTOR RONNIE NORRIS PHONE 752-3871
LOCATION OF PROPERTY 441 SOUTH, TR ON BARNEY ST, 1 1/4 MILES ON RIGHT,
2 MAILBOXES, SILVER & BLACK, MOTOR HOME IN FRONT
TYPE DEVELOPMENT MH, UTILITY ESTIMATED COST OF CONSTRUCTION .00
HEATED FLOOR AREA TOTAL AREA HEIGHT .00 STORIES
FOUNDATION WALLS ROOF PITCH FLOOR
LAND USE & ZONING A-3 MAX. HEIGHT
Minimum Set Back Requirements: STREET-FRONT 30.00 REAR 25.00 SIDE 25.00
NO. EX.D.U. 1 FLOOD ZONE X DEVELOPMENT PERMIT NO.

PARCEL ID 05-7S-17-09918-105 SUBDIVISION SUNNYDALE FARMS
LOT 5 BLOCK PHASE UNIT TOTAL ACRES

IH0000049
Culvert Permit No. Culvert Waiver Contractor's License Number Applicant/Owner/Contractor
EXISTING 05-1157-E BK JH N
Driveway Connection Septic Tank Number LU & Zoning checked by Approved for Issuance New Resident

COMMENTS: ONE FOOT ABOVE THE ROAD

Check # or Cash 548

FOR BUILDING & ZONING DEPARTMENT ONLY

(footer/Slab)

Temporary Power date/app. by Foundation date/app. by Monolithic date/app. by
Under slab rough-in plumbing date/app. by Slab date/app. by Sheathing/Nailing date/app. by
Framing date/app. by Rough-in plumbing above slab and below wood floor date/app. by
Electrical rough-in date/app. by Heat & Air Duct date/app. by Peri. beam (Lintel) date/app. by
Permanent power date/app. by C.O. Final date/app. by Culvert date/app. by
M/H tie downs, blocking, electricity and plumbing date/app. by Pool date/app. by
Reconnection date/app. by Pump pole date/app. by Utility Pole date/app. by
M/H Pole date/app. by Travel Trailer date/app. by Re-roof date/app. by

BUILDING PERMIT FEE \$.00 CERTIFICATION FEE \$.00 SURCHARGE FEE \$.00
MISC. FEES \$ 200.00 ZONING CERT. FEE \$ 50.00 FIRE FEE \$.00 WASTE FEE \$
FLOOD DEVELOPMENT FEE \$ FLOOD ZONE FEE \$ 25.00 CULVERT FEE \$ TOTAL FEE 275.00

INSPECTORS OFFICE CLERKS OFFICE

NOTICE: IN ADDITION TO THE REQUIREMENTS OF THIS PERMIT, THERE MAY BE ADDITIONAL RESTRICTIONS APPLICABLE TO THIS PROPERTY THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY. AND THERE MAY BE ADDITIONAL PERMITS REQUIRED FROM OTHER GOVERNMENTAL ENTITIES SUCH AS WATER MANAGEMENT DISTRICTS, STATE AGENCIES, OR FEDERAL AGENCIES.

"WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOUR PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR LENDER OR AN ATTORNEY BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT."

This Permit Must Be Prominently Posted on Premises During Construction

PLEASE NOTIFY THE COLUMBIA COUNTY BUILDING DEPARTMENT AT LEAST 24 HOURS IN ADVANCE OF EACH INSPECTION, IN ORDER THAT IT MAY BE MADE WITHOUT DELAY OR INCONVENIENCE, PHONE 758-1008. THIS PERMIT IS NOT VALID UNLESS THE WORK AUTHORIZED BY IT IS COMMENCED WITHIN 6 MONTHS AFTER ISSUANCE.

The Issuance of this Permit Does Not Waive Compliance by Permittee with Deed Restrictions.

C# 548 left message 11/15/05

PERMIT APPLICATION / MANUFACTURED HOME INSTALLATION APPLICATION

For Office Use Only (Revised 6-23-05) Zoning Official BLK 14.11.05 Building Official OK JTH 11-9-05

AP# 0511-32 Date Received 11/8/05 By G Permit # 23894

Flood Zone _____ Development Permit N/A Zoning A-3 Land Use Plan Map Category A3

Comments ~~NEED State Site Plan showing Distances to Property Lines and to MH~~
#04-09 NEED STUPM attached
STUPM WAS applied for for mother-in-law & approved

FEMA Map# _____ Elevation _____ Finished Floor _____ River _____ In Floodway _____

☒ Site Plan with Setbacks Shown ☐ EH Signed Site Plan ☒ EH Release ☐ Well letter ☐ Existing well

☒ Copy of Recorded Deed or Affidavit from land owner ☒ Letter of Authorization from installer



- Sunnydale Farms, lot 5
- Property ID # 05-75-17-09918-105 Must have a copy of the property deed
 - New Mobile Home X Used Mobile Home _____ Year 2005
 - Applicant Darla J. Taylor Phone # 386-454-7489
 - Address 1181 SW Barney St, High Springs, FL 32648
 - Name of Property Owner Darla J. Taylor Phone# 386-454-7489
 - 911 Address 1181 SW Barney St, High Springs, FL 32648
 - Circle the correct power company - FL Power & Light - Clay Electric
 (Circle One) - Suwannee Valley Electric - Progress Energy
 - Name of Owner of Mobile Home Mike & Darla Taylor Phone # 386-454-7489
 - Address 1181 SW Barney St, High Springs, FL 32648
 - Relationship to Property Owner Owner
 - Current Number of Dwellings on Property 2
 - Lot Size 4.01 Total Acreage 4.01 acre
 - Do you : Have an Existing Drive or need a Culvert Permit or a Culvert Waiver (Circle one)
 - Is this Mobile Home Replacing an Existing Mobile Home yes (Pd)
 - Driving Directions to the Property 441 South to Barney St., Right
1 1/4 miles on right, 2 mailboxes, silver & black, with
motor home.
 - Name of Licensed Dealer/Installer Loanne Norris Phone # 752 3871
 - Installers Address 1004 SW Charlotte Dr
 - License Number TH0000049 Installation Decal # 253647

@ CAM112M01S CamaUSA Appraisal SystemColumbia County
11/08/2005 17:47 Legal Description Maintenance21998 Land 003
Year T Property * PRIOR YEAR * SelAG 000
2005 R 05-7S-17-09918-10533539 Bldg 001 *
1181 BARNEY ST SWXfea 000 *
HX TAYLOR DARLA J GUZMAN55537 TOTALB*

1	LOT 5 SUNNYDALE FARMS S/D.	ORB 745-664.	2
3			4
5			6
7			8
9			10
11			12
13			14
15			16
17			18
19			20
21			22
23			24
25			26
27			28

Mnt 12/30/1997 TERR

F1=Task F3=Exit F4=Prompt F10=GoTo PgUp/PgDn F24=More




NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

COLUMBIA
COUNTY,
FLORIDA
(UNINCORPORATED AREAS)

PANEL 260 OF 290

PANEL LOCATION




COMMUNITY-PANEL NUMBER
120070 0260 B

EFFECTIVE DATE:
JANUARY 6, 1988




Federal Emergency Management Agency


This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT Version 1.0. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. Further information about National Flood Insurance Program flood hazard maps is available at www.fema.gov/nifm.



SITE PLAN EXAMPLE / WORKSHEET



Use this example to draw your own site plan. Show all existing buildings and any other homes on this property and show the distances between them, Also show where the roads or roads are around the property. This site plan can also be used for the 911 Addressing department if you include the distance from the driveway to the nearest property line.



LETTER OF AUTHORIZATION TO PULL PERMITS


I, Ronnie Norris, DO HEREBY GRANT
Michael Taylor, AUTHORIZATION TO PULL THE NECESSARY
PERMITS REQUIRED FOR THE DELIVERY AND SET OF A MANUFACTURED
HOME IN Columbia COUNTY, FLORIDA.

Ronnie Norris
Signature

THIS FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS
8th DAY OF November, 2005, BY _____
Ronnie Norris, WHO IS PERSONALLY KNOWN TO ME.

STATE OF FLORIDA
COUNTY OF Columbia

Rebecca L. Gallina
NOTARY PUBLIC



MOBILE HOME INSTALLER AFFIDAVIT

As per Florida Statutes Section 320.8249 Mobile Home Installers License:

Any person who engages in mobile home installation shall obtain a mobile home Installer's license from the Bureau of Mobile Home and Recreational Vehicle Construction of the Department of Highway Safety and Motor Vehicles pursuant to this section. Said license shall be renewed annually, and each licensee shall pay a fee of \$150.00.

I, Ronnie Nork, license number IH 0000049
Please Print

Do hereby state that the installation of the manufactured home for:
Michael Taylor at 1181 SW Barney St., High Springs
Applicant 911 Address


will be done under my supervision.

[Signature]
Signature

Sworn to and subscribed before me this 8th day of November,
2005.

Notary Public: Rebecca L. Gallina
Signature

My Commission Expires:



AFFIDAVIT

I Certify that the following described mobile home being placed on the referenced parcel is not a Wind Zone 1 mobile home.

Customer Name: Micheel + Darla Taylor

Property ID: Sec: _____ Twp: _____ Rge: _____ Tax Parcel No: _____

Lot: _____ Block: _____ Subdivision: _____

Moible Home Year/Make: 2006 skyline Size: 32' x 60'

[Signature]

Signature of Mobile Home Installer

Sworn to and subscribed before me this 8th day of November, 2005

By Ronnie Norris



Notary's name printed/typed

Rebecca L. Gallina

Notary Public, State of Florida

Commission No. DD 253343

Personally Known: ✓

Id Produced (type) _____

PERMIT NUMBER

Installer David E. Noffs License # _____



Address of home being installed _____

Manufacturer _____ Length x width _____

NOTE: if home is a single wide fill out one half of the blocking plan
if home is a triple or quad wide sketch in remainder of home

I understand Lateral Arm Systems cannot be used on any home (new or used) where the sidewall ties exceed 5 ft 4 in.

Installer's initials DN



New Home ☒ Used Home ☐
Home installed to the Manufacturer's Installation Manual ☒

Home is installed in accordance with Rule 15-C

Single wide ☐ Wind Zone II ☒ Wind Zone III ☐

Double wide ☒ Installation Decal # 253647

Triple/Quad ☐ Serial # 20-62-0154-U A/B

PIER SPACING TABLE FOR USED HOMES

Load bearing capacity	Footer size (sq in)	16" x 16" (256)	18 1/2" x 18 1/2" (342)	20" x 20" (400)	22" x 22" (484)*	24" X 24" (576)*	26" x 26" (676)
1000 psf	3'	3'	4'	5'	6'	7'	8'
1500 psf	4' 6"	4' 6"	6'	7'	8'	8'	8'
2000 psf	6'	6'	8'	8'	8'	8'	8'
2500 psf	7' 6"	7' 6"	8'	8'	8'	8'	8'
3000 psf	8'	8'	8'	8'	8'	8'	8'
3500 psf	8'	8'	8'	8'	8'	8'	8'

* interpolated from Rule 15C-1 pier spacing table.

PIER PAD SIZES

Pad Size	Sq In
16 x 16	256
16 x 18	288
18.5 x 18.5	342
16 x 22.5	360
17 x 22	374
13 1/4 x 26 1/4	348
20 x 20	400
17 3/16 x 25 3/16	441
17 1/2 x 25 1/2	446
24 x 24	576
26 x 26	676

I-beam pier pad size 17x22

Perimeter pier pad size 16x16

Other pier pad sizes (required by the mfg.) 17x22

Draw the approximate locations of marriage wall openings 4 foot or greater. Use this symbol to show the piers.

List all marriage wall openings greater than 4 foot and their pier pad sizes below.

Opening	Pier pad size
<u>8</u>	<u>20x20</u>
<u>6</u>	<u>17x22</u>
<u>1</u>	<u>16x16</u>

ANCHORS

4 ft 5 ft

FRAME TIES

within 2' of end of home spaced at 5' 4" oc

OTHER TIES

Number 22
Sidewall 2
Longitudinal 2
Marriage wall 4
Shearwall

TIEDOWN COMPONENTS

Longitudinal Stabilizing Device (LSD)

Manufacturer

Longitudinal Stabilizing Device w/ Lateral Arms

Manufacturer

PERMIT NUMBER

POCKET PENETROMETER TEST

The pocket penetrometer tests are rounded down to 2850 psf or check here to declare 1000 lb. soil without testing.

x 150 x 100 x 150

POCKET PENETROMETER TESTING METHOD

1. Test the perimeter of the home at 6 locations.
2. Take the reading at the depth of the footer.
3. Using 500 lb. increments, take the lowest reading and round down to that increment.

x 150 x 200 x 150

TORQUE PROBE TEST

The results of the torque probe test is 285 inch pounds or check here if you are declaring 5' anchors without testing. A test showing 275 inch pounds or less will require 4 foot anchors.

Note: A state approved lateral arm system is being used and 4 ft. anchors are allowed at the sidewall locations. I understand 5 ft anchors are required at all centerline tie points where the torque test reading is 275 or less and where the mobile home manufacturer may requires anchors with 4000 lb. holding capacity.

Installer's initials

ALL TESTS MUST BE PERFORMED BY A LICENSED INSTALLER

Installer Name

Date Tested

11-1-05

Electrical

Connect electrical conductors between multi-wide units, but not to the main power source. This includes the bonding wire between multi-wide units. Pg.

Plumbing

Connect all sewer drains to an existing sewer tap or septic tank. Pg.

Connect all potable water supply piping to an existing water meter, water tap, or other independent water supply systems. Pg.

Site Preparation

Debris and organic material removed Swale Pad Other

Fastening multi wide units

Floor: Type Fastener: Length: Spacing: 24 in
Walls: Type Fastener: Length: Spacing: 24 in
Roof: Type Fastener: Length: Spacing: 24 in
For used homes a min. 30 gauge, 8" wide, galvanized metal strip will be centered over the peak of the roof and fastened with galv. roofing nails at 2" on center on both sides of the centerline.

Gasket (weatherproofing requirement)

I understand a properly installed gasket is a requirement of all new and used homes and that condensation, mold, mildew and buckled marriage walls are a result of a poorly installed or no gasket being installed. I understand a strip of tape will not serve as a gasket.

Installer's initials

Type gasket Pg.

Installed:
Between Floors Yes
Between Walls Yes
Bottom of ridgebeam Yes

Weatherproofing

The bottomboard will be repaired and/or taped. Yes Pg.
Siding on units is installed to manufacturer's specifications. Yes
Fireplace chimney installed so as not to allow intrusion of rain water. Yes

Miscellaneous

Skirting to be installed. Yes No
Dryer vent installed outside of skirting. Yes N/A
Range downflow vent installed outside of skirting. Yes
Drain lines supported at 4 foot intervals. Yes
Electrical crossovers protected. Yes
Other :


Installer verifies all information given with this permit worksheet is accurate and true based on the manufacturer's installation instructions and or Rule 15C-1 & 2

Installer Signature

Date 11-8-05

TIE-DOWN DETAILS FOR 5/12 ROOF PITCH DOUBLE WIDES AT WIND ZONE II & III

TABLE 6A





WIND ZONE II (100 mph)				
Unit Width	H (max.)	H (min.)	Angle (max.)	Angle (min.)
24'	48"	12"	23.2 degrees	6.12 degrees
26'	48"	12"	20.3 degrees	6.12 degrees
28'	48"	12"	20.3 degrees	5.28 degrees
32'	48"	12"	18.96 degrees	4.91 degrees

WIND ZONE III (110 mph)				
Unit Width	H (max.)	H (min.)	Angle (max.)	Angle (min.)
24'	48"	12"	25.2 degrees	6.12 degrees
26'	48"	12"	20.3 degrees	6.12 degrees
28'	48"	12"	20.3 degrees	5.28 degrees
32'	48"	12"	18.96 degrees	4.91 degrees

NOTES:

- 1) Straps and anchors to be rated for 3150 lbs. of working stress (min.).
- 2) Use H1 and A1 for standard strap location. Use H2 and A2 for optional strap location.
- 3) See page 25 for strap material specification, connection to I-Beam and other setup information.
- 4) The A-B chance strap seal device depicted by Fig. 5-12 may be used as directed for attaching the required doublewide centerline straps to ground anchors.

STANDARD TIE-DOWN DETAILS



DOUBLE-WIDE

WIDE RESULTS FOR 12" HALF OF 22" WIDE DOUBLE WIDES

WIDTH	WIND ZONE II		WIND ZONE III	
	MIN. & MAX. ELEVATION	MIN. & MAX. DIAGONAL STRAP ANGLE	MIN. & MAX. ELEVATION	MIN. & MAX. DIAGONAL STRAP ANGLE
12'	14" TO 25"	25 TO 40	14" TO 26"	25 TO 41
14'	12" TO 27"	20.5 TO 40	12" TO 28"	20.5 TO 41
12' SHED ROOF	25.2" TO 34.6"	41 TO 50	25.2" TO 34.6"	41 TO 50
14' SHED ROOF	23.4" TO 38.4"	36 TO 50	23.4" TO 38.4"	36 TO 50
16'	16" TO 36"	20.5 TO 40	15.5" TO 38"	19.5 TO 41
18'	20" TO 44"	20.5 TO 40	19" TO 47"	19.5 TO 41
20' OR 22' *	12" TO 15"	34 TO 40	12" TO 16"	34 TO 42
24'	12" TO 22"	24.5 TO 40	12" TO 23.5	24.5 TO 42
28'	12" TO 23.5"	23 TO 40	12" TO 25.5"	23 TO 42
32'	12" TO 33"	16.6 TO 39.3	12" TO 36"	16.6 TO 41.8
16' SHED ROOF	21" TO 27.5"	25.9 TO 32.4	21" TO 27.5"	25.9 TO 32.4

STRAP MATERIAL SPECIFICATION, CONNECTION TO FRAME BEAM & OTHER SET UP INFORMATION, REFER TO SKYLINE INSTALLATION MANUAL.

ANCHORING SYSTEMS, THE INSTRUCTIONS SHALL INDICATE: A) THE MINIMUM ANCHOR CAPACITY REQUIRED, B) ANCHORS SHOULD BE RATED BY PROFESSIONAL ENGINEER, ARCHITECT, OR A NATIONALLY RECOGNIZED TESTING LABORATORY AS TO THEIR RESISTANCE, C) ON THE MAXIMUM ANGLE OF DIAGONAL TIE AND/OR VERTICAL TIE LOADING AND ANGLE OF ANCHOR INSTALLATION, AND TYPE OF SOIL, D) THE ANCHOR IS TO BE INSTALLED; C) GROUND ANCHORS SHOULD BE EMBEDDED BELOW THE FROST LINE AND BE AT LEAST 2 FEET ABOVE THE WATER TABLE; D) GROUND ANCHORS SHOULD BE INSTALLED TO THEIR FULL DEPTH, AND STABILIZER PLATES SHOULD BE INSTALLED TO PROVIDE ADDED RESISTANCE TO OVERTURNING OR SLIDING FORCES, E) ANCHORING EQUIPMENT SHOULD BE CERTIFIED BY A PROFESSIONAL ENGINEER OR ARCHITECT TO RESIST THESE SPECIFIED FORCES IN ACCORDANCE WITH TESTING PROCEDURES IN ASTM F1554-03 STANDARD SPECIFICATION FOR STRAPPING, FLAT STEEL AND SEALS.

STRAPS RATED @ 3150# OF WORKING STRESS TOTAL FOR BOTH STRAPS, MAY BE USED IF STRAP & ANCHOR SPACING IS REDUCED TO 5'-4" @ WIND ZONE II AND 4'-6" @ WIND ZONE III. STRAPS AND ANCHORS MAY BE INSTALLED 4'-0" O.C. ON SHED ROOF SINGLEWIDES WITH STRAPS RATED @ 3150#.

SKYLINE STRAP SEAL DEVICE DEPICTED BY FIG. 5-12 MAY BE USED AS DIRECTED FOR ATTACHING THE REQUIRED DOUBLEWIDE SKYLINE STRAPS TO GROUND ANCHORS.


STANDARD TIE-DOWN DETAILS ARE NOT APPLICABLE TO 5/12 ROOF PITCH DOUBLEWIDES @ WIND ZONE II & III

SKYLINE CORP.

MANUFACTURED HOME TIE-DOWN INSTRUCTIONS (Continued)

TIONAL OVER-THE-ROOF STRAP PROCEDURE

over-the-roof straps are provided (optional on all homes) / may be connected to ground anchors as specified in the wing procedure in order to achieve additional stability in eme winds. Note that the frame tie-down procedure on e 25 is still mandatory.





Materials not furnished with the home which will be necessary to properly connect the over-the-roof straps are:

1. Ground anchors capable of withstanding at least 4,750 pound pull when installed in the soil at the site.
2. Strap end connection devices (See Fig. 5-10).

THE HOME MUST BE IN ITS FINAL LEVEL POSITION WITH FRAME TIES INSTALLED BEFORE CONNECTING THE OVER-THE-ROOF STRAPS.


The procedure for over-the-roof strap installation is as follows:

1. Position and install the ground anchors so that the strap will be vertical after attachment to the anchor. The anchor may be installed slightly beneath the home to avoid interference with skirting (See Fig. 5-11).
2. Insert the minuteman connector yoke through the eye of the anchor and insert slotted bolt through the yoke.
3. Place end of strap through slotted bolt and remove slat by turning bolt. DO NOT TENSION UNTIL BOTH ENDS OF STRAP ARE CONNECTED.
4. Tension and lock minuteman connector in position; consult instructions furnished with connectors.
5. Check strap tension (See step 4 under frame tie-down procedure).
6. For double-wide homes see Fig. 5-12 for the splice connection at the centerline.



Insert end of the strap through the slot on the splice device, allowing the strap to extend through the device. Make a 180 degree bend in the strap and slide a strap seal over the thickness of strap, positioning the strap seal as close to the splice device as possible. Compress the strap seal on the strap with a vise grip pliers or hammer, or crimp strap seal with an A-B vice crimping tool. (Make all bends in the strap as sharp as possible by crimping with vise grip or larger pliers). End strap back over the seal and insert back through the slot on splice device. Flatten bend with vise grip pliers or hammer. Repeat steps 1 through 4 with the mating strap. Draw the completed assembly down to the ridge beam by tensioning the strap in ground anchor.

DOUBLEWIDE OPTIONAL OVER-THE-ROOF STRAPS



MANUFACTURED HOME TIE-DOWN INSTRUCTIONS

support system must also resist lifting, sliding, and racking forces resulting from side winds. A method used to install ground anchors and tie-down straps in addition to piers. Tie-downs as described are the minimum necessary for the home to withstand its design loads without failure. On multi-section homes, sections must be leveled together and level before tie-down straps are installed.

WARNING

BEFORE GROUND ANCHOR INSTALLATION, DETERMINE THAT THE ANCHOR LOCATIONS AROUND THE HOME WILL NOT BE CLOSE TO ANY UNDERGROUND ELECTRICAL CABLES, WATER LINES OR SEWER PIPES. FAILURE TO DETERMINE THE LOCATION OF UNDERGROUND ELECTRICAL CABLES MAY RESULT IN PERSONAL INJURY OR DEATH.

IN THE FRAME TIE-DOWN SYSTEM, IT IS IMPORTANT TO USE MATERIALS OF PROPER DESIGN AND OF HIGHEST QUALITY. THE MATERIAL SPECIFICATIONS LISTED HEREIN SHOULD BE CONSIDERED AS MINIMUM REQUIREMENTS.

Materials not furnished with the home which will be necessary to complete the tie-down system must meet the requirements set forth below. Such materials would include:

1. Steel strap with a breaking strength of at least 5,000 pounds e.g. galvanized aircraft cable at least 1/4" diameter or Type 1, Finish B, Grade 1 steel strapping 1-1/4" wide and 0.03" thick, conforming with ASTM D3953-91.

2. Anchored connection devices such as turnbuckles, shackles, strap buckles, and cable clamps should be rated at working load minimum.

3. Ground anchors — capable of withstanding at least a 5,000 pound pull. Anchors must be installed as specified by the anchor manufacturer. Stabilizers or concrete collars may be used by anchor manufacturer.

THE HOME MUST BE IN ITS FINAL LEVEL POSITION BEFORE TYING IT DOWN.

The procedure for tying down the manufactured home is as follows:

1. Position and install the ground anchors under exterior corners so that the final strap angle and height (H) will be within the limits shown in tables 5 thru 6C.


2. Connect the straps to the frame and ground anchors (See Fig. 5-9 and 5-10). Straps wrapped around the I-Beam as

shown in Fig. 5-9 require protection from premature failure due to sharp corners. Fig. 5-9A illustrates one method to protect against sharp corner damage. Other methods (such as beam clamps — Tie-Down Engineering part no. 59003 or equivalent) approved by the local building authority having jurisdiction may be used.

3. Tighten the straps using the tensioning device provided with the ground anchors. Use caution to avoid overtensioning the straps which might pull the home off the piers. It is recommended that all straps be tightened only enough to remove slack. Then, after all straps are installed and the slack removed, tension the straps.

4. The strap tension should be rechecked at frequent intervals until all pier settlement has stopped.

CAUTION: DURING THE RELEVELING PROCESS, DO NOT JACK THE HOME AGAINST TIGHT STRAPS.



DOUBLE-WIDE INTERCONNECTION (Continued)

NOTE: IT IS IMPORTANT TO HAVE ROOF/CEILING SECTIONS FLUSH AT MATING LINE PRIOR TO FASTENING OF RIDGE BEAM HALVES. IF THEY ARE NOT FLUSH, THEN THE LOW SIDE SHOULD BE RAISED BY JACKING WITH A WOOD POST OR STEEL PIPE WITH A WOOD OR METAL PAD AT THE CEILING. PLACE THE BASE OF THE JACK ACROSS THE FLOOR MATING LINE SO THAT IT RESTS ON BOTH HALVES. JACK AGAINST CEILING ONLY IN AREAS WHERE THERE IS NO MARRIAGE WALL.




FIG. 5-8




FIG. 5-8A

ATTACHMENT OF GYPSUM PANELS AT DOUBLE-WIDE CENTERLINE

Some multiple-wide units will have a gypsum panel left off at the centerline for field attachment. Fasten the factory supplied gypsum wallboard panel(s) at the center of the endwalls after the units have been attached. Fasten the panel(s) to framing as described in figure 5-8B below.




FIG. 5-8B

DOUBLE-WIDE INTERCONNECTION

Procedure for connecting the homes is as follows.

move the temporary closure materials (polyethylene atten strips) and position the halves as close together as le in the final desired location. Do not remove tempo- beam supports until step 7 has been completed.

ve the first section of home into its desired position. and level it in the same manner as described for a section home. Skyline Corp. recommends, if possible, avy half be blocked and leveled first as it is easier to lift ll the light half and fit into place.

tall sill sealer insulating material (provided) around the i (to the ridge beam at the ceiling panel line), endwalls or mating line. Fasten sill sealer with staples or nails. ure 5-8A.

le the two halves together with rolling and jacking nent. Care must be taken during rolling and jacking ions to avoid overstressing structural members. With lves together at the floor, align the floors at the ends of me. It is better to have a minor misalignment under the where it cannot be seen and will not cause a problem, small misalignment that will be observed in the interior home.

h the home aligned at the floor and supported by its tion, join the floors using 3/8" x 3" (4-1/2" lags with perimeter joist) lag screws 2 to 3 feet on center. The ine gap at the floor should be a maximum of 3/16". e procedures outlined on page 19 to level the home eck supports and footings with tables 2 and 3.

obtain access into the ceiling cavity to bolt or alter- lag screw the ridge beam sections together, fold back leryment paper and remove the 16" wide sheathing s) at the peak. Note that the shingles may not have istalled on one or both halves, at the 16" wide area at

the peak. If one side is shingled, it is intended that the beam be lag screwed together. If neither side is shingled, the beam may be lag screwed or bolted together. Bolts to be 3/8" x 4 1/2" at 48" o.c. with 3 additional bolts at 3" o.c. over interior beam supports. Lag screws to be 3/8" x 5" at 24" o.c. with 6 additional lag screws at 3" o.c. over interior beam supports (If marriage walls and ridge beam halves have been plated with 3/8" sheathing, then the bolts/lags must be increased in length by 3/4" to 5-3/4".) Predrill 1/4" pilot holes for the lag screws at 1-1/2" down from the top of the beam and with a maximum offset from the horizontal of 45 degrees. A gap between beam halves up to 1" is allowable. Gaps larger than 1/2" must be filled with plywood or lumber shims. For 1/2" max gaps, increase fastener length 1/2". For 1" max. gaps increase fastener length 1-1/4". See Fig. 5-7.

7. Prior to interconnecting the ridge beam halves, examine the ridge beam ends. Should there be a slight misalignment it can be eliminated by placing a jack under the low side of main beam on one half and use the jack to raise the beam. The alignment can be held by properly bolting or lag screwing the beam halves together. See Fig. 5-8.

8. Place additional pier supports at the centerline at the interior column locations marked on the floor with indicator strips or paint (see Figure 5-3 and 5-4 and Table 3). Skyline Corp. provides pier location diagrams for all multiwide models. These diagrams show the required locations of piers and are very useful in determining pier placement prior to taking receipt of home. Additional piers are required each side of exterior doors and sidewall openings greater than 4' in width. See Table 3A for these pier load requirements.

9. Toe-nail endwall centerline studs together using 16d nail 10" o.c.

10. If home has double mating walls, then fasten the mating wall columns together with #8 x 4" screws 16" o.c. See Figure 5-7A.




FIG. 5-7

APPROVED
PFS Corporation
Madison WI
01/31/05
HUD Manufactured
Home
Construction &
Safety Standard




FIG. 5-7A



STATE OF FLORIDA
DEPARTMENT OF HEALTH


APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Permit Application Number

05-1157E
05-1157E

PART II - SITE PLAN

Scale: Each block represents 5 feet and 1 inch = 50 feet.



Notes:

Site Plan submitted by: Michael O. Taylor Signature

Plan Approved ✓ Not Approved _____ Date 11-14-05

By Mr. Taylor Columbin County Health Department

ALL CHANGES MUST BE APPROVED BY THE COUNTY HEALTH DEPARTMENT