

CHRISTELLE PUTNEY
NEW GRID-INTERACTIVE PHOTOVOLTAIC SYSTEM
DC SYSTEM SIZE (9.86 KW)



ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REVISIONS	DATE				
	DESCRIPTION				
REV	ENGG.				

PERMIT DEVELOPER

DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME

SITE MAP &
VICINITY MAP

SHEET NUMBER

A-01

SYSTEM DETAILS

DESCRIPTION	NEW GRID-INTERACTIVE PHOTOVOLTAIC SYSTEM WITH NO BATTERY STORAGE
DC RATING OF SYSTEM	SYSTEM SIZE :9.86 KW DC STC
AC RATING OF SYSTEM	6.96 KW
AC OUTPUT CURRENT	29 A
NO. OF MODULES	(29) HANWHA Q.PEAK DUO BLK-G6+ (340W) MODULES
NO. OF INVERTERS	(29) ENPHASE IQ7 -60-2-US MICROINVERTERS
POINT OF INTERCONNECTION	LINE SIDE TAP IN THE MSP
ARRAY STRINGING	(1) BRANCH OF 15 MODULES (1) BRANCH OF 14 MODULES

SITE DETAILS


ASHRAE EXTREME LOW	-5°C
ASHRAE 2% HIGH	34°C
GROUND SNOW LOAD	0 PSF
WIND SPEED	120MPH (ASCE 7-16)
RISK CATEGORY	II
WIND EXPOSURE CATEGORY	B

GOVERNING CODES

FLORIDA RESIDENTIAL CODE, 7TH EDITION 2020 (FRC)
FLORIDA BUILDING CODE, 7TH EDITION 2020 (FBC)
FLORIDA FIRE PREVENTION CODE, 7TH EDITION 2020 (FFPC)
NATIONAL ELECTRIC CODE, NEC 2017 CODE BOOK, NFPA 70

SHEET INDEX

SHEET NO.	SHEET NAME
A - 01	SITE MAP & VICINITY MAP
A - 02	ROOF PLAN & MODULES
S - 01	ARRAY LAYOUT
S - 02	STRUCTURAL ATTACHMENT DETAIL
E - 01	ELECTRICAL LINE DIAGRAM
E - 02	WIRING CALCULATIONS
E - 03	SYSTEM LABELING
DS - 01	MODULE DATASHEET
DS - 02	INVERTER DATASHEET
DS - 03	COMBINER BOX DATASHEET
DS - 04	ATTACHMENT DATASHEET
DS - 05	RACKING DATASHEET




SITE MAP (N.T.S)




VICINITY MAP



WIND FLOW MAP





MODULE TYPE, DIMENSIONS & WEIGHT

NUMBER OF MODULES = 29 MODULES
MODULE TYPE = HANWHA Q.PEAK DUO BLK-G6+ (340W) MODULES
MODULE WEIGHT = 43.87 LBS / 19.9 KG.
MODULE DIMENSIONS = 68.5" X 40.6" = 19.31 SF

NUMBER OF INVERTER = 29 MICROINVERTERS
INVERTER TYPE = ENPHASE IQ7 -60-2-US MICROINVERTERS

DC SYSTEM SIZE: 9.86 KW
AC SYSTEM SIZE: 6.96 KW

GENERAL INSTALLATION PLAN NOTES:

(1) PANEL DESIGNATIONS SHOWN ON THESE DRAWINGS ARE GIVEN FOR CLARIFICATION OF THE CIRCUITING ONLY AND MAY NOT CORRESPOND TO THE DESIGNATIONS FOUND IN THE FIELD

2) ROOF ATTACHMENTS TO TRUSSES SHALL BE INSTALLED AS SHOWN IN SHEET S-01 AND AS FOLLOWS FOR EACH WIND ZONE:

WIND ZONE 1: MAX SPAN 4'-0" O.C.
WIND ZONE 2: MAX SPAN 4'-0" O.C.
WIND ZONE 3: MAX SPAN 2'-0" O.C.

3) EXISTING RESIDENTIAL BUILDING ROOF WITH MEAN ROOF HEIGHT 15 FT AND 2"X4" WOOD ROOF TRUSSES SPACED 24" O.C.

CONTRACTOR TO FIELD VERIFY AND SHALL REPORT TO THE ENGINEER IF ANY DISCREPANCIES EXIST BETWEEN PLANS AND IN FIELD CONDITIONS.

I CERTIFY THAT THE INSTALLATION OF THE MODULES IS IN COMPLIANCE WITH FBC: RESIDENTIAL CHAPTER 3.BUILDING STRUCTURE WILL SAFELY ACCOMMODATE LATERAL AND UPLIFT WIND LOADS, AND EQUIPMENT DEAD LOADS.


NOTES:

1. LOCATION OF JUNCTION BOX(ES), AC DISCONNECTS(S), AC COMBINER PANEL(S), AND OTHER ELECTRICAL EQUIPMENT(S) RELEVANT TO PV INSTALLATION SUBJECT TO CHANGE BASED ON SITE CONDITIONS.
2. SETBACKS AT RIDGES CAN BE REDUCED TO 18 INCHES IN COMPLIANCE WITH FBC R 324.6.2:
TOTAL PLAN VIEW AREA = 2460 SQFT
TOTAL PV AREA = 29(68.5 IN)(40.6 IN)/(144 IN^2)
= 560.08 SQFT
(560.08 SQFT/ 2460 SQFT)100 = 22.77 %
TOTAL PV AREA POPULATES 22.77 % OF TOTAL PLAN VIEW AREA AND IS WITHIN THE 33% REQUIREMENT.

LEGENDS

UM	- UTILITY METER
MSP	- MAIN SERVICE PANEL
M	- METER MAIN COMBO
JB	- JUNCTION BOX
ACD	- AC DISCONNECT
PM	- PRODUCTION METER
CP	- COMBINER PANEL
	- FIRE SETBACK
	- ROOF ACCESS POINT
	- MICROINVERTER
	- VENT, ATTIC FAN (ROOF OBSTRUCTION)
	- CONDUIT

NOTE : INSTALLERS MAY MOVE PANELS IF NEEDED TO BE WITHIN THE MEANS OF THE SETBACKS.



This item has been electronically signed and sealed by Vincent Mwumvaneza using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Vincent Mwumvaneza
Digitally signed by Vincent Mwumvaneza
Date: 2022.03.04 12:02:28 -05'00'



Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY, FL 32025, USA

REVISIONS	DATE				
	DESCRIPTION				
REV	ENGG.				

PERMIT DEVELOPER

DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME

ROOF PLAN & MODULES

SHEET NUMBER

A-02

ROOF DESCRIPTION:

(ROOF #1)

MODULES - 11
ROOF TILT - 22°
ROOF AZIMUTH - 182°
TRUSSES SIZE - 2"X4" @ 24" O.C.

(ROOF #2)

MODULES - 18
ROOF TILT - 22°
ROOF AZIMUTH - 272°
TRUSSES SIZE - 2"X4" @ 24" O.C.

TRUSS LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MAY DIFFER AND
CONTRACTOR MAY NEED TO ADJUST MOUNT
LOCATIONS. IN NO CASE SHALL THE MOUNT
SPACING EXCEED "MAX. MOUNT SPACING"

WIND LOAD INFORMATION:
THIS SYSTEM HAS BEEN DESIGN TO MEET
THE REQUIREMENTS OF THE 7TH EDITION OF
THE FLORIDA BUILDING CODE AND USED
THE FOLLOWING DESIGN PARAMETERS:
ULTIMATE WIND SPEED: 120 MPH
EXPOSURE CATEGORY: B
RISK CATEGORY: II
MEAN ROOF HEIGHT: 15 FEET
ROOF SLOPE: 20-27°




ADD : 612 FLORIDA AVENUE, PALM
HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA




This item has been electronically signed
and sealed by Vincent Mwumvaneza
using a Digital Signature and Date.
Printed copies of this document are not
considered signed and sealed and the
signature must be verified on any
electronic copies.

Vincent Mwumvaneza
Digitally signed by Vincent Mwumvaneza
Date: 2022.03.04 12:02:12 -05'00'

LEGENDS

- FIRE SETBACK
- VENT, ATTIC FAN (ROOF OBSTRUCTION)
- PV ROOF ATTACHMENT
- RAIL
- RAFTERS / TRUSSES
- METAL SEAM
- WIND ZONE 1
 - WIND ZONE 1
 - WIND ZONE 1'
- WIND ZONE 2
 - WIND ZONE (2)
 - WIND ZONE (2r)
 - WIND ZONE (2e)
 - WIND ZONE (2n)
- WIND ZONE 3
 - WIND ZONE (3)
 - WIND ZONE (3r)
 - WIND ZONE (3e)



REV	ENG.	DESCRIPTION	DATE			

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
ARRAY LAYOUT

SHEET NUMBER
S-01

PHOTOVOLTAIC MODULE GENERAL NOTES:


FOR PITCHED ROOF

- 1. APPLICABLE CODE: 2020 FLORIDA BUILDING CODE 7th ED. & ASCE 7-16
MINIMUM DESIGN LOADS FOR BUILDING AND OTHER STRUCTURES
- 2. BOLT DIAMETER AND EMBEDMENT LENGTHS ARE DESIGNED PER NDS(2012) REQUIREMENTS. ALL BOLT CAPACITIES ARE BASED ON A WOOD ROOF TRUSS AS EMBEDMENT MATERIAL.
- 3. ALL WIND DESIGN CRITERIA AND PARAMETERS ARE FOR HIP AND GABLE RESIDENTIAL ROOFS, CONSIDERING FROM A 7° TO A MAXIMUM 27° (2/12 TO A MAXIMUM 6/12 PITCH) ROOF IN SCHEDULE. ALL RESIDENTIAL ROOFS SHALL NOT EXCEED 30'-0" MEAN ROOF HEIGHT.
- 4. ROOF SEALANTS SHALL CONFORM TO ASTM C920 AND ASTM 6511.
- 5. THIS SHEET REFLECTS STRUCTURAL CONNECTIONS ONLY. REFER TO MANUFACTURER'S MANUAL FOR ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND SOLAR SPECS.
- 6. ALL ALUMINIUM COMPONENTS SHALL BE ANODIZED ALUMINIUM 6105-T5 UNLESS OTHERWISE NOTED.
- 7. LAG BOLTS SHALL BE ASTM A276 STAINLESS STEEL UNLESS OTHERWISE NOTED.
- 8. ALL RAILING AND MODULES SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS.
- 9. I CERTIFY THAT THE INSTALLATION OF THE MODULES IS IN COMPLIANCE WITH FBC:BUILDING CHAPTER 16 AND FBC:RESIDENTIAL CHAPTER 3. BUILDING STRUCTURE WILL SAFELY ACCOMMODATE CALCULATED WIND LATERAL AND UPLIFT FORCES AND EQUIPMENT DEAD LOADS.



This item has been electronically signed and sealed by Vincent Mwumvaneza using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Vincent Mwumvaneza
Digitally signed by Vincent Mwumvaneza
Date: 2022.03.04 12:01:57 -05'00'



STRUCTURAL ATTACHMENT DETAILS

ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REV	ENG.	DESCRIPTION	DATE				

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
STRUCTURAL ATTACHMENT DETAILS

SHEET NUMBER
S-03

MODULE SPECIFICATION	
MODEL NO.	HANWHA Q PEAK DUO BLK-G6+
PEAK POWER	340W
RATED VOLTAGE (Vmpp)	33.94V
RATED CURRENT (Impp)	10.02A
OPEN CIRCUIT VOLTAGE (Voc)	40.66V
SHORT CIRCUIT CURRENT (Isc)	10.52A


- NOTE:
- ALL ELECTRICAL EQUIPMENTS SHALL COMPLY WITH NEC CODE AND MAY CHANGE AS PER THE SITE CONDITION, NEC OR AHJ REQUIREMENTS.
 - LEGEND: (E) = EXISTING, (N) = NEW; APPLICABLE TO CONDUCTORS, CONDUITS, ELECECTRICAL ENCLOSURES, ETC.

INVERTER SPECIFICATIONS	
MANUFACTURER	ENPHASE
MODEL NO.	IQ7-60-2-US
MAX DC INPUT VOLTAGE	48 V
MAX OUTPUT POWER	240 VA
NOMINAL AC OUTPUT VOLTAGE	240 V
NOMINAL AC OUTPUT CURRENT	1 A

- NOTE:
- SUBJECT PV SYSTEMS HAS BEEN DESIGNED TO MEET THE REQUIREMENTS OF THE NEC 2017, NFPA 70 AND THOSE SET FORTH BY THE FLORIDA SOLAR ENERGY CENTER CERTIFICATION, INCLUDING MAXIMUM NUMBER OF MODULE STRINGS, MAXIMUM NUMBER OF MODULES PER STRING, MAXIMUM OUTPUT, MODULE MANUFACTURER AND MODEL NUMBER, INVERTER MANUFACTURER AND MODEL NUMBER, AS APPLICABLE.
 - PROVIDE TAP BOX IN COMPLIANCE WITH 312.8 IF PANEL GUTTER SPACE IS INADEQUATE.


SOLAR ARRAY (9.86 KW-DC STC)

(29) HANWHA Q.PEAK DUO BLK-G6+ (340W) MODULES
(1) BRANCH OF 15 MODULES
(1) BRANCH OF 14 MODULES



Domingo A
Villaruel:A01410
D00000177F3BC
588C0001626D

Digitally signed by
Domingo A
Villaruel:A01410D00000
177F3BC588C0001626D
Date: 2022.03.04
06:34:28 -08'00'



This item has been electronically signed and sealed by Domingo Villaruel using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronics copies.



Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REVISIONS	DATE	DESCRIPTION	REV	ENG.				

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
SINGLE LINE DIAGRAM

SHEET NUMBER
E-01

ELECTRICAL CALCULATIONS:

1. CURRENT CARRYING CONDUCTOR

(A) BEFORE IQ COMBINER PANEL
AMBIENT TEMPERATURE = 34°C
CONDUIT INSTALLED AT MINIMUM DISTANCE OF 7/8 INCHES ABOVE ROOFNEC 310.15(B)(3)(c)
TEMPERATURE DERATE FACTOR - 0.96 ...NEC 310.15(B)(2)(a)
GROUPING FACTOR - 0.8...NEC 310.15(B)(3)(a)

CONDUCTOR AMPACITY
= (INV O/P CURRENT) x 1.25 / A.T.F / G.F ...NEC 690.8(B)
= [(15 x 1) x 1.25] / 0.96 / 0.8
= 24.41 A
SELECTED CONDUCTOR - #10 THWN-2 ...NEC 310.15(B)(16)

(B) AFTER IQ COMBINER PANEL
TEMPERATURE DERATE FACTOR - 0.96
GROUPING FACTOR - 1

CONDUCTOR AMPACITY
=(TOTAL INV O/P CURRENT) x 1.25 / 0.96 / 1 ...NEC 690.8(B)
=[(29x 1) x 1.25] /0.96 / 1
=37.76 A
SELECTED CONDUCTOR - #6 THWN-2 ...NEC 310.15(B)(16)

2. PV OVER CURRENT PROTECTION ..NEC 690.9(B)
=TOTAL INVERTER O/P CURRENT x 1.25
=(29 x 1) x 1.25 = 36.25 A
SELECTED OCPD = 40A

SELECTED EQUIPMENT GROUND CONDUCTOR (EGC) = #10 THWN-2 ... NEC 250.122(A)

MAX VOLTAGE DROP CALCULATION						
CABLE SIZE	CABLE DESCRIPTION	ONE WAY DISTANCE IN FEET (D)	BRANCH CURRENT (I)	RESISTANCE OF CONDUCTOR(R)	VOLTAGE (V)	% VOLTAGE DROP=(0.2*D*I*R)/V
#10 THWN-2	JUNCTION BOX TO COMBINER PANEL	20	29	1.24	240	0.599

ELECTRICAL NOTES

- ALL EQUIPMENT TO BE LISTED BY UL OR OTHER NRTL AND LABELED FOR ITS APPLICATION.
- ALL CONDUCTORS SHALL BE COPPER, RATED FOR 600 V AND 90 DEGREE C WET ENVIRONMENT.THE TERMINALS ARE RATED FOR 75 DEGREE C.
- CONDUCTOR TERMINATION AND SPLICING AS PER NEC 110.14 4.
- WIRING, CONDUIT AND RACEWAYS MOUNTED ON ROOFTOPS SHALL BE ROUTED DIRECTLY TO AND LOCATED AS CLOSE AS POSSIBLE TO THE NEAREST RIDGE, HIP, OR VALLEY.
- WORKING CLEARANCES AROUND ALL NEW AND EXISTING ELECTRICAL EQUIPMENT SHALL COMPLY WITH NEC 110.26.
- DRAWINGS INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS. CONTRACTOR SHALL FURNISH ALL NECESSARY OUTLETS, SUPPORTS, FITTINGS AND ACCESSORIES TO FULFILL APPLICABLE CODES AND STANDARDS.
- WHERE SIZES OF JUNCTION BOXES, RACEWAYS AND CONDUITS ARE NOT SPECIFIED, THE CONTRACTOR SHALL SIZE THEM ACCORDINGLY.
- ALL WIRE TERMINATIONS SHALL BE APPROPRIATELY LABELED AND READILY VISIBLE.
- MODULE GROUNDING CLIPS TO BE INSTALLED BETWEEN MODULE FRAME AND MODULE SUPPORT RAIL, PER THE GROUNDING CLIP MANUFACTURER'S INSTRUCTION.
- MODULE SUPPORT RAIL TO BE BONDED TO CONTINUOUS COPPER G.E.C. VIA WEEB LUG OR ILSCO GBL-4DBT LAY-IN LUG.
- THE POLARITY OF THE GROUNDED CONDUCTORS IS NEGATIVE .
- UTILITY HAS 24-HR UNRESTRICTED ACCESS TO ALL PHOTOVOLTAIC SYSTEM COMPONENTS LOCATED AT THE SERVICE ENTRANCE.
- MODULES CONFORM TO AND ARE LISTED UNDER UL 1703.
- RACKING CONFORMS TO AND IS LISTED UNDER UL 2703.
- CONDUCTORS EXPOSED TO SUNLIGHT SHALL BE LISTED AS SUNLIGHT RESISTANT PER NEC ARTICLE 300.6 (C) (1) AND ARTICLE 310.10 (D).
- CONDUCTORS EXPOSED TO WET LOCATIONS SHALL BE SUITABLE FOR USE IN WET LOCATIONS PER NEC ARTICLE 310.10 (C).



ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal


CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REV	ENG.	DESCRIPTION	DATE				

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME	
WIRING CALCULATIONS	
SHEET NUMBER	
E-02	



Domingo A Villaruel:A01410D00
000177F3BC588C000
1626D

Digitally signed by Domingo A Villaruel:A01410D00000177F3B
CS88C0001626D
Date: 2022.03.04 06:34:41 -08'00'

This item has been electronically signed and sealed by Domingo Villaruel using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronics copies.

⚠

WARNING

ELECTRIC SHOCK HAZARD

DO NOT TOUCH TERMINALS

TERMINALS ON BOTH LINE AND

LOAD SIDES MAY BE ENERGIZED

IN THE OPEN POSITION

LABEL LOCATION:
AC DISCONNECT, POINT OF INTERCONNECTION,
COMBINER PANEL
(PER CODE: NEC 690.13(B))

WARNING PHOTOVOLTAIC

POWER SOURCE

LABEL LOCATION:
CONDUIT RUNWAY
(PER CODE: NEC690.31(G)(3)(4))

⚠

WARNING DUAL POWER SOURCE

SECOND SOURCE IS PHOTOVOLTAIC SYSTEM

LABEL LOCATION:
MAIN SERVICE DISCONNECT
(NEC 705.12(B)(3-4) & NEC 690.59)

ADHESIVE FASTENED SIGNS:

- ANSI Z535.4-2011 PRODUCT SAFETY SIGNS AND LABELS, PROVIDES GUIDELINES FOR SUITABLE FONT SIZES, WORDS, COLORS, SYMBOLS, AND LOCATION REQUIREMENTS FOR LABELS. NEC 110.21(B)(1)
- THE LABEL SHALL BE OF SUFFICIENT DURABILITY TO WITHSTAND THE ENVIRONMENT INVOLVED. NEC 110.21(B)(3)
- ADHESIVE FASTENED SIGNS MAY BE ACCEPTABLE IF PROPERLY ADHERED. VINYL SIGNS SHALL BE WEATHER RESISTANT. IFC 605.11.1.3

PHOTOVOLTAIC SYSTEM AC DISCONNECT

RATED AC OPERATING CURRENT 29 AMPS

AC NOMINAL OPERATING VOLTAGE 240 VOLTS

LABEL LOCATION:
AC DISCONNECT, INVERTER
(PER CODE: NEC 690.54)

WARNING

INVERTER OUTPUT CONNECTION DO NOT

RELOCATE THIS OVERCURRENT DEVICE

LABEL LOCATION:
POINT OF INTERCONNECTION, MAIN SERVICE DISCONNECT
(PER CODE: NEC 705.12 (B)(2)(c))
[Not required if panelboard is rated not less than sum of ampere ratings of all overcurrent devices supplying it]

DATA PER PANEL

NOMINAL OPERATING AC VOLTAGE -	240	V
NOMINAL OPERATING AC FREQUENCY-	60	Hz
MAXIMUM AC POWER-	240	VA
MAXIMUM AC CURRENT-	1	A
MAXIMUM OVERCURRENT DEVICE RATING FOR AC MODULE PROTECTION PER CIRCUIT-	20	A

LABEL LOCATION:
COMBINER PANEL, AC DISCONNECT
(PER CODE: NEC 690.52)

PHOTOVOLTAIC SYSTEM

EQUIPPED WITH RAPID

SHUTDOWN

LABEL LOCATION:
AC DISCONNECT, DC DISCONNECT, POINT OF
INTERCONNECTION
(PER CODE: NEC 690.56(C)(3))

⚠

WARNING

INVERTER OUTPUT CONNECTION

DO NOT RELOCATE THIS

OVERCURRENT DEVICE

EMERGENCY CONTACT

727-945-6060

⚠

WARNING

DEDICATED SOLAR PANELS DO

NOT CONNECT ANY OTHER LOADS

SOLAR PV SYSTEM EQUIPPED

WITH RAPID SHUTDOWN

TURN RAPID SHUTDOWN

SWITCH TO THE

"OFF" POSITION TO

SHUTDOWN PV SYSTEM

AND REDUCE

SHOCK HAZARD

IN ARRAY


SOLAR ELECTRIC

PV PANELS

IFC 605.11.3.1(1) & 690.56(C)(1)(a) Label for PV Systems that Shut down the array and the conductors leaving the array

Domingo A
Villaruel:A01410
D00000177F3BC
588C0001626D

Digitally signed by
Domingo A
Villaruel:A01410D000001
77F3BC588C0001626D
Date: 2022.03.04 06:34:51
-08'00'



This item has been electronically signed and sealed by Domingo Villaruel using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronics copies.

Unicity

Solar Energy

ADD : 612 FLORIDA AVENUE, PALM

HARBOR, FL 34683, USA

CONTACT : 727 945 6060

LICENSE #EC13010036

#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REVIEWS	DESCRIPTION	DATE	REV	ENG.				

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
SYSTEM LABELING

SHEET NUMBER
E-03



Q.ANTUM DUO BLK-G6+

330-345

ENDURING HIGH PERFORMANCE




- Q.ANTUM TECHNOLOGY: LOW LEVELIZED COST OF ELECTRICITY**
Higher yield per surface area, lower BOS costs, higher power classes, and an efficiency rate of up to 19.5%.
- INNOVATIVE ALL-WEATHER TECHNOLOGY**
Optimal yields, whatever the weather with excellent low-light and temperature behavior.
- ENDURING HIGH PERFORMANCE**
Long-term yield security with Anti LID and Anti PID Technology-, Hot-Spot Protect and Traceable Quality Tra.Q™.
- EXTREME WEATHER RATING**
High-tech aluminum alloy frame, certified for high snow (5400 Pa) and wind loads (4000 Pa).
- A RELIABLE INVESTMENT**
Inclusive 25-year product warranty and 25-year linear performance warranty².
- STATE OF THE ART MODULE TECHNOLOGY**
Q.ANTUM DUO combines cutting edge cell separation and innovative wiring with Q.ANTUM Technology.

THE IDEAL SOLUTION FOR:

Rooftop arrays on residential buildings

Engineered in Germany




Domingo A Villaruel: A01410D0
0000177F3BC588C
0001626D

Digitally signed by Domingo A Villaruel: A01410D00000177F3BC588C0001626D
Date: 2022.03.04 06:35:05 -08'00'



MECHANICAL SPECIFICATION

Format	68.5 x 40.6 x 1.26 in (including frame) (1740 x 1030 x 32 mm)
Weight	43.9 lbs (19.9 kg)
Front Cover	0.13 in (3.2 mm) thermally pre-stressed glass with anti-reflection technology
Back Cover	Composite film
Frame	Black anodized aluminum
Cell	6 x 20 monocrystalline Q.ANTUM solar half cells
Junction Box	2.09-3.95 x 1.26-2.36 x 0.59-0.71 in (53-101 x 32-60 x 15-18 mm), Protection class IP67, with bypass diodes
Cable	4 mm ² Solar cable, (+) ≥ 45.3 in (1150 mm), (-) ≥ 45.3 in (1150 mm)
Connector	Süßblü MC4, Hanwha Q CELLS HQC4, Amphenol UTX, Renhe Os-6, Tongling TL-Cebe01S, JMTHY JM801; IP68 or Friends PV2c; IP67




ELECTRICAL CHARACTERISTICS

POWER CLASS	330	335	340	345
MINIMUM PERFORMANCE AT STANDARD TEST CONDITIONS, STC ¹ (POWER TOLERANCE +5 W / -0 W)				
Power at MPP ¹	P _{MPP} [W]	330	340	345
Short Circuit Current ¹	I _{sc} [A]	10.41	10.47	10.58
Open Circuit Voltage ¹	V _{oc} [V]	40.15	40.41	40.92
Current at MPP	I _{MPP} [A]	9.91	9.97	10.07
Voltage at MPP	V _{MPP} [V]	33.29	33.62	33.94
Efficiency ¹	η [%]	≥ 18.4	≥ 18.7	≥ 19.0
MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT ²				
Power at MPP	P _{MPP} [W]	247.0	250.7	254.5
Short Circuit Current	I _{sc} [A]	8.39	8.43	8.48
Open Circuit Voltage	V _{oc} [V]	37.86	38.10	38.34
Current at MPP	I _{MPP} [A]	7.80	7.84	7.89
Voltage at MPP	V _{MPP} [V]	31.66	31.97	32.27

¹ Measurement tolerances P_{MPP} ± 3%; I_{sc} ± 3%; V_{oc} ± 5% at STC: 1000 W/m², 25 ± 2 °C, AM 1.5 according to IEC 60904-3 + 7800 W/m², NMOT, spectrum AM 1.5


Q CELLS PERFORMANCE WARRANTY



At least 96% of nominal power during first year. Thereafter max. 0.54% degradation per year. At least 93.1% of nominal power up to 10 years. At least 85% of nominal power up to 25 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Q CELLS sales organization of your respective country.

PERFORMANCE AT LOW IRRADIANCE



Typical module performance under low irradiance conditions in comparison to STC conditions (25 °C, 1000 W/m²)

TEMPERATURE COEFFICIENTS

Temperature Coefficient of I _{sc}	α	[%/K]	+0.04	Temperature Coefficient of V _{oc}	β	[%/K]	-0.27
Temperature Coefficient of P _{MPP}	γ	[%/K]	-0.36	Normal Module Operating Temperature	NMOT	[°F]	109 ± 5.4 (43 ± 3 °C)


PROPERTIES FOR SYSTEM DESIGN

Maximum System Voltage V _{sys}	[V]	1000 (IEC) / 1000 (UL)	Safety Class	II
Maximum Series Fuse Rating	[A DC]	20	Fire Rating based on ANSI / UL 1703	C (IEC) / TYPE 2 (UL)
Max. Design Load, Push / Pull ¹	[lbs / ft ²]	75 (3600 Pa) / 55 (2667 Pa)	Permitted Module Temperature on Continuous Duty	-40 °F up to +185 °F (-40 °C up to +85 °C)
Max. Test Load, Push / Pull ¹	[lbs / ft ²]	113 (5400 Pa) / 84 (4000 Pa)		

¹ See Installation Manual

QUALIFICATIONS AND CERTIFICATES

UL1703, VDE Quality Tested, CE-compliant, IEC 61215:2016, IEC 61730:2016, Application Class II, U.S. Patent Nos. 9,593,215 (solar cells)



Note: Installation instructions must be followed. See the installation and operating manual or contact our technical service department for further information on approved installation and use of this product.

Hanwha Q CELLS America Inc.

400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 742 59 96 | EMAIL inquiry@us.q-cells.com | WEB www.q-cells.us

PACKAGING INFORMATION

Number of Modules per Pallet	32
Number of Pallets per 53' Trailer	28
Number of Pallets per 40' HC-Container	24
Pallet Dimensions (L x W x H)	71.5 x 45.3 x 48.0 in (1815 x 1150 x 1220 mm)
Pallet Weight	1505 lbs (683 kg)

Spec. remains subject to technical changes @ Q CELLS Q-PEAK DUO BLK-G6+ 330-345_2022-06_Rev01_MX



ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REV	ENG.	DESCRIPTION	DATE				

PERMIT DEVELOPER

DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME

MODULE DATASHEET

SHEET NUMBER

DS-01

Data Sheet
Enphase Microinverters
Region: AMERICAS


Enphase IQ 7 and IQ 7+ Microinverters



To learn more about Enphase offerings, visit enphase.com

Domingo A
Villaruel:A01410D0
0000177F3BC588C
0001626D

Digitally signed by Domingo A
Villaruel:A01410D00000177F
3BC588C0001626D
Date: 2022.03.04 06:35:14
-08'00'



This item has been electronically signed and sealed by Domingo Villaruel using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronics copies.

The high-powered smart grid-ready **Enphase IQ 7 Micro™** and **Enphase IQ 7+ Micro™** dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enphase IQ System, the IQ 7 and IQ 7+ Microinverters integrate with the Enphase IQ Envoy™, Enphase IQ Battery™, and the Enphase Enlighten™ monitoring and analysis software.

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power-on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.

Easy to Install

- Lightweight and simple
- Faster installation with improved, lighter two-wire cabling
- Built-in rapid shutdown compliant (NEC 2014 & 2017)

Productive and Reliable

- Optimized for high powered 60-cell and 72-cell* modules
- More than a million hours of testing
- Class II double-insulated enclosure
- UL listed

Smart Grid Ready

- Complies with advanced grid support, voltage and frequency ride-through requirements
- Remotely updates to respond to changing grid requirements
- Configurable for varying grid profiles
- Meets CA Rule 21 (UL 1741-SA)

* The IQ 7+ Micro is required to support 72-cell modules.



Enphase IQ 7 and IQ 7+ Microinverters

INPUT DATA (DC)	IQ7-60-2-US		IQ7PLUS-72-2-US	
Commonly used module pairings¹	235 W - 350 W +		235 W - 440 W +	
Module compatibility	60-cell PV modules only		60-cell and 72-cell PV modules	
Maximum input DC voltage	48 V		60 V	
Peak power tracking voltage	27 V - 37 V		27 V - 45 V	
Operating range	16 V - 48 V		16 V - 60 V	
Min/Max start voltage	22 V / 48 V		22 V / 60 V	
Max DC short circuit current (module Isc)	15 A		15 A	
Overvoltage class DC port	II		II	
DC port backfeed current	0 A		0 A	
PV array configuration	1 x 1 ungrounded array; No additional DC side protection required; AC side protection requires max 20A per branch circuit			
OUTPUT DATA (AC)	IQ 7 Microinverter		IQ 7+ Microinverter	
Peak output power	250 VA		295 VA	
Maximum continuous output power	240 VA		290 VA	
Nominal (L-L) voltage/range²	240 V / 211-264 V	208 V / 183-229 V	240 V / 211-264 V	208 V / 183-229 V
Maximum continuous output current	1.0 A (240 V)	1.15 A (208 V)	1.21 A (240 V)	1.39 A (208 V)
Nominal frequency	60 Hz		60 Hz	
Extended frequency range	47 - 68 Hz		47 - 68 Hz	
AC short circuit fault current over 3 cycles	5.8 Arms		5.8 Arms	
Maximum units per 20 A (L-L) branch circuit³	16 (240 VAC)	13 (208 VAC)	13 (240 VAC)	11 (208 VAC)
Overvoltage class AC port	III		III	
AC port backfeed current	18 mA		18 mA	
Power factor setting	1.0		1.0	
Power factor (adjustable)	0.85 leading ... 0.85 lagging		0.85 leading ... 0.85 lagging	
EFFICIENCY	@240 V	@208 V	@240 V	@208 V
Peak efficiency	97.6 %	97.6 %	97.5 %	97.3 %
CEC weighted efficiency	97.0 %	97.0 %	97.0 %	97.0 %
MECHANICAL DATA				
Ambient temperature range	-40°C to +65°C			
Relative humidity range	4% to 100% (condensing)			
Connector type	MC4 (or Amphenol H4 UTX with additional Q-DCC-5 adapter)			
Dimensions (HxWxD)	212 mm x 175 mm x 30.2 mm (without bracket)			
Weight	1.08 kg (2.38 lbs)			
Cooling	Natural convection - No fans			
Approved for wet locations	Yes			
Pollution degree	PD3			
Enclosure	Class II double-insulated, corrosion resistant polymeric enclosure			
Environmental category / UV exposure rating	NEMA Type 6 / outdoor			
FEATURES				
Communication	Power Line Communication (PLC)			
Monitoring	Enlighten Manager and MyEnlighten monitoring options. Both options require installation of an Enphase IQ Envoy.			
Disconnecting means	The AC and DC connectors have been evaluated and approved by UL for use as the load-break disconnect required by NEC 690.			
Compliance	CA Rule 21 (UL 1741-SA) UL 62109-1, UL1741/IEEE1547, FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA-C22.2 NO. 107.1-01 This product is UL Listed as PV Rapid Shut Down Equipment and conforms with NEC-2014 and NEC-2017 section 690.12 and C22.1-2015 Rule 64-218 Rapid Shutdown of PV Systems, for AC and DC conductors, when installed according manufacturer's instructions.			

1. No enforced DC/AC ratio. See the compatibility calculator at <https://enphase.com/en-us/support/module-compatibility>.
2. Nominal voltage range can be extended beyond nominal if required by the utility.
3. Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

To learn more about Enphase offerings, visit enphase.com

© 2020 Enphase Energy. All rights reserved. Enphase, the Enphase logo, Enphase IQ 7, Enphase IQ 7+, Enphase IQ Battery, Enphase Enlighten, Enphase IQ Envoy, and other trademarks or service names are the trademarks of Enphase Energy, Inc. Data subject to change. 2020-01-05.



ADD : 612 FLORIDA AVENUE, PALM
HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY,
FL 32025, USA

REVISIONS	DATE				
	DESCRIPTION				
REV	ENG.				

PERMIT DEVELOPER

DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME

INVERTER
DATASHEET

SHEET NUMBER

DS-02

FLASH LOC



FLASHLOC is the ultimate attachment for composition shingle and rolled comp roofs. The all-in-one mount installs fast — no kneeling on hot roofs to install flashing, no prying or cutting shingles, no pulling nails. Simply drive the lag bolt and inject sealant into the base. **FLASHLOC's** patented TRIPLE SEAL technology preserves the roof and protects the penetration with a permanent pressure seal. Kitted with lag bolts, sealant, and hardware for maximum convenience. Don't just divert water, **LOC it out!**




This item has been electronically signed and sealed by Vincent Mwumvaneza using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Vincent Mwumvaneza
Digitally signed by Vincent Mwumvaneza
Date: 2022.03.04 12:01:35 -05'00'



PROTECT THE ROOF
Install a high-strength waterproof attachment without lifting, prying or damaging shingles.



LOC OUT WATER
With an outer shield **1** contour-conforming gasket **2** and pressurized sealant chamber **3** the Triple-Loc Seal delivers a 100% waterproof connection.



HIGH-SPEED INSTALL
Simply drive lag bolt and inject sealant into the port **4** to create a permanent pressure seal.

FLASH LOC

INSTALLATION GUIDE



PRE-INSTALL
Snap chalk lines for attachment rows. On shingle roofs, snap lines 1-3/4" below upslope edge of shingle course. Locate rafters and mark attachment locations.

At each location, drill a 7/32" pilot hole. Clean roof surface of dirt, debris, snow, and ice, then fill pilot hole with sealant.

NOTE: Space mounts per racking system install specifications. When down pressure is ≥ 34 psf, span may not exceed 2 ft.



STEP 1: SECURE
Place **FLASHLOC** over pilot hole with lag on down-slope side. Align indicator marks on sides of mount with chalk line. Pass included lag bolt and sealing washer through **FLASHLOC** into pilot hole. Drive lag bolt until mount is held firmly in place.

NOTE: The EPDM in the sealing washer will expand beyond the edge of the metal washer when proper torque is applied.



STEP 2: SEAL
Insert tip of UNIRAC provided sealant into port. Inject until sealant exits both vents.

Continue array installation, attaching rails to mounts with provided T-bolts.

NOTE: When **FLASHLOC** is installed over gap between shingle or tabs or vertical joints, fill gap/joint with sealant between mount and upslope edge of shingle course.

Use only provided sealant.

Unicity Solar Energy
ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY, FL 32025, USA

REVISIONS	REV	ENG.	DESCRIPTION	DATE					

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
ATTACHMENT DATASHEET
SHEET NUMBER
DS-04

FASTER INSTALLATION. 25-YEAR WARRANTY.

FOR QUESTIONS OR CUSTOMER SERVICE VISIT UNIRAC.COM OR CALL (505) 248-2702

FASTER INSTALLATION. 25-YEAR WARRANTY.

FOR QUESTIONS OR CUSTOMER SERVICE VISIT UNIRAC.COM OR CALL (505) 248-2702



This form has been electronically signed and sealed by Vincent Mwumvaneza using a Digital Signature and Date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Vincent Mwumvaneza
Digitally signed by Vincent Mwumvaneza
Date: 2022.03.04 12:01:20 -05'00'

SOLARMOUNT



SOLARMOUNT defined the standard in solar racking. Features are designed to get installers off the roof faster. Our grounding & bonding process eliminates copper wire and grounding straps to reduce costs. Systems can be configured with standard or light rail to meet your design requirements at the lowest cost possible. The superior aesthetics package provides a streamlined clean edge for enhanced curb appeal, with no special brackets required for installation.



Now Featuring:
THE NEW FACE OF SOLAR RACKING
Superior Aesthetics Package



LOSE ALL OF THE COPPER & LUGS
System grounding through Enphase microinverters and trunk cables



SMALL IS THE NEXT NEW BIG THING
Light Rail is fully Compatible with all SM Components



ENHANCED DESIGN & LAYOUT TOOLS
Featuring Google Map Capabilities within U-Builder

FAST INSTALLATION. SUPERIOR AESTHETICS

OPTIMIZED COMPONENTS • VERSATILITY • DESIGN TOOLS • QUALITY PROVIDER

SOLARMOUNT



OPTIMIZED COMPONENTS

INTEGRATED BONDING & PRE-ASSEMBLED PARTS

Components are pre-assembled and optimized to reduce installation steps and save labor time. Our new grounding & bonding process eliminates copper wire and grounding straps or bonding jumpers to reduce costs. Utilize the microinverter mount with a wire management clip for an easier installation.

VERSATILITY


ONE PRODUCT - MANY APPLICATIONS

Quickly set modules flush to the roof or at a desired tilt angle. Change module orientation to portrait or landscape while securing a large variety of framed modules on flat, low slope or steep pitched roofs. Available in mill, clear and dark anodized finishes to outperform your projects financial and aesthetic aspirations.


AUTOMATED DESIGN TOOL

DESIGN PLATFORM AT YOUR SERVICE


Creating a bill of materials is just a few clicks away with U-Builder, a powerful online tool that streamlines the process of designing a code compliant solar mounting system. Save time by creating a user profile, and recall preferences and projects automatically when you log in. You will enjoy the ability to share projects with customers: there's no need to print results and send to a distributor, just click and share.




INTEGRATED BONDING MIDCLAMP



INTEGRATED BONDING SPLICE BAR



INTEGRATED BONDING L-FOOT w/ T-BOLT



INTEGRATED BONDING MICROINVERTER MOUNT w/ WIRE MANAGEMENT



UNIRAC CUSTOMER SERVICE MEANS THE HIGHEST LEVEL OF PRODUCT SUPPORT



UNMATCHED EXPERIENCE



CERTIFIED QUALITY



ENGINEERING EXCELLENCE



BANKABLE WARRANTY



DESIGN TOOLS



PERMIT DOCUMENTATION

TECHNICAL SUPPORT

Unirac's technical support team is dedicated to answering questions & addressing issues in real time. An online library of documents including engineering reports, stamped letters and technical data sheets greatly simplifies your permitting and project planning process.

CERTIFIED QUALITY PROVIDER

Unirac is the only PV mounting vendor with ISO certifications for 9001:2015, 14001:2015 and OHSAS 18001:2007, which means we deliver the highest standards for fit, form, and function. These certifications demonstrate our excellence and commitment to first class business practices.

BANKABLE WARRANTY

Don't leave your project to chance. Unirac has the financial strength to back our products and reduce your risk. Have peace of mind knowing you are receiving products of exceptional quality. SOLARMOUNT is covered by a twenty five (25) year limited product warranty and a five (5) year limited finish warranty.

PROTECT YOUR REPUTATION WITH QUALITY RACKING SOLUTIONS BACKED BY ENGINEERING EXCELLENCE AND A SUPERIOR SUPPLY CHAIN

PLB2017FEB28 - (PRINTED)

Unicity Solar Energy
ADD : 612 FLORIDA AVENUE, PALM HARBOR, FL 34683, USA
CONTACT : 727 945 6060
LICENSE #EC13010036
#CBC1263094

Signature with Seal

CHRISTELLE PUTNEY

1340 SW INDIAN GLEN, LAKE CITY, FL 32025, USA

REVISIONS	REV	ENG.	DESCRIPTION	DATE					

PERMIT DEVELOPER	
DATE	03/04/2022
DESIGNER	ODK
REVIEWER	

SHEET NAME
RACKING DATASHEET

SHEET NUMBER
DS-05